
© 2010 RAFAEL VIÑOLY ARCHITECTS

TERMINATION SYMBOL KEY



TERMINATION ID
(SEE SCHEDULE OF TERMINATIONS)

LOCATION CONTAINS POWER CIRCUIT(S)
P = AUDITORIUM ISOLATED AUDIO/VIDEO TECHNICAL POWER
N = CLEAN, AUDIO/VIDEO POWER FROM DEDICATED CIRCUITS
B = NON-TECHNICAL BUILDING POWER

MOUNTING TYPE
(SEE DEVICE MOUNTING KEY)

DEVICE MOUNTING KEY

1 - MOUNT FLUSH IN CEILING
2 - MOUNT AT 12" A.F.F.
3 - MOUNT AT 18" A.F.F.
4 - MOUNT AT 48" A.F.F.
5 - MOUNT AT 12" BELOW CEILING
6 - MOUNT PER DETAIL DRAWING OR NOTE
7 - CLAMP TO STRUCTURE
8 - FREE STANDING
9 - FLUSH MOUNT IN FLOOR
0 - REFER TO ARCHITECTURAL DETAILS

AUDIO & VIDEO SYSTEM POWER NOT INCLUDED IN AUDIO & VIDEO SYSTEM CONTRACT
-SEE ELECTRICAL DOCUMENTS FOR COMPLETE POWER INFORMATION-

SCHEDULE OF TERMINATIONS - SCHOOL OF BUSINESS

TERM(1)	TERMINATION FUNCTION	MOUNTING HEIGHT	BACKBOX	WIRE GROUP(2)	WIRE QTY(3)	WIRE TYPE(4)	ROUTE TO(5)
SYSTEM INTERFACE:							
AA	MOVEABLE INSTRUCTOR LECTERN - FLOOR, ON-GRADE OR RAISE FLOOR CONDITION	REFER TO MOUNTING KEY	LEGRAND EFB10S	A D D --	1 5 3 2	9451 2412 2412 ($) AVTP	ZC, YA OR ZE ZC, YA OR ZE BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AB	FIXED INSTRUCTOR LECTERN - FLOOR	REFER TO MOUNTING KEY	LEGRAND EFB10S	D --	4 2	2412 ($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AC	FIXED INSTRUCTOR LECTERN - FLOOR	REFER TO MOUNTING KEY	FSR 600P	D --	7 2	2412 ($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AD	FUTURE COMPUTER/AUDIO VIDEO INPUT CONNECTION PANEL - WALL	REFER TO MOUNTING KEY	6" X 4" X 4"	B D D D --	4 6 2 2 1	9451 1694A 2412 2412 ($) AVTP	ZC, AB OR AC ZC, AB OR AC ZC, AB OR AC BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AE	MOVEABLE INSTRUCTOR LECTERN - FLOOR, ON-STRUCTURE CONDITION	REFER TO MOUNTING KEY	LEGRAND EFB10S OR LEGRAND 8AT	A D D --	1 5 3 2	9451 2412 2412 ($) AVTP	ZC ZC BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AF	PROJECTOR	ABOVE CEILING	4" X 4" X 4"	D D --	1 1 1	2412 2412 ($) NTP	AB, AC, ZA, ZC OR ZE ZC OR BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AG	42" LCD PANEL	5' - 6"	CHIEF PAC522	D --	2 1	2412 ($) NTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AH	65" LCD PANEL W/O SPEAKERS	REFER TO MOUNTING KEY, TYP. WALL MOUNT HT 6' - 0"	CHIEF PAC522	D D --	1 2 1	2412 2412 ($) AVTP	AB, AC, ZA OR ZC ZC OR BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AI	NOT USED						
AJ	PTZ CAMERA (FOR LECTURE CAPTURE IN CLASSROOMS AND AUDITORIUM, CAMERA WILL ALSO PROVIDE VIDEO FEED OF MUSIC PERFORMANCES AS REQUIRED)	REFER TO MOUNTING KEY	6" X 4" X 4"	D D --	1 1 1	1694A 2412 AVTP	ZA OR ZC ZA OR ZC ISOLATED BUILDING POWER
AK	INTERACTIVE WHITE BOARD	7' - 0"	4" X 4" X 4"	B D D D D --	2 1 1 1 1 1	9451 HDMI RGBHV 2412 2412 ($) AVTP	GA OR GD GA OR GD GA OR GD GA OR GD BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AL	ROOM SCHEDULE PANEL	REFER TO ARCH. DRAWINGS	1-GANG OR MANUFACTURER BACKBOX	D	1	2412 ($)	POE BUILDING NETWORK (BY OTHERS)
AM	INTERACTIVE INFORMATION KIOSK	REFER TO MOUNTING KEY	STEEL CITY 68D	D --	1 1	2412 ($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AN	ELECTRIC SCREEN	REFER TO MOUNTING KEY	4" X 4" X 4"	D --	1 1	9831 NTP	AB, AC, ZA, ZB, ZC, YA OR ZE BUILDING POWER
AO	FUTURE PROJECTOR (INFRASTRUCTURE ONLY PROVIDED WITH AV INSTALLATION)	ABOVE CEILING	4" X 4" X 4"	D D --	1 1 1	2412 2412 ($) AVTP	AB, AC, ZA, ZC OR ZE ZC OR BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AP	FUTURE SCREEN (INFRASTRUCTURE ONLY PROVIDED WITH AV INSTALLATION)	REFER TO MOUNTING KEY	4" X 4" X 4"	D --	2 1	5300UG NTP	AB, AC, ZA, ZB OR ZC BUILDING POWER
AQ	FUTURE INTERACTIVE WHITEBOARD (INFRASTRUCTURE ONLY PROVIDED WITH AV INSTALLATION)	7' - 0"	4" X 4" X 4"	D D D --	10 2 4 1	1694A HDMI 2412 AVTP	AE AE AE ISOLATED BUILDING POWER
AR	LIVE ROOM MIC (FOR ADA AND CAPTURE SYSTEMS)	ABOVE CEILING	1-GANG	A	1	9451	AB, AC, ZA OR ZC
AS	VIDEO CONFERENCING SYSTEM (NOT OWNER PROVIDED)	7' - 0"	4" X 4" X 4"	D --	1 1	2412 ($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AT	THIN-BEZEL FLAT PANEL VIDEO WALL DISPLAY	5' - 6"	6" X 6" X 4"	D D --	4 4 3	2412 2412 ($) AVTP	ZC ZC OR BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
AU	NOT USED						
AV	NOT USED						
AW	PROJECTOR WITH MOTORIZED LIFT	ABOVE CEILING	4" X 4" X 4"	D D -- --	2 1 1 1	2412 2412 ($) NTP AVTP	ZC BUILDING NETWORK (BY OTHERS) BUILDING POWER ISOLATED BUILDING POWER
AX	WIRELESS MICROPHONE ANTENNA	REFER TO MOUNTING KEY	4" X 4" X 4"	D	1	9914	AX OR ZF
AY	CEILING MOUNTED DOCUMENT CAMERA	REFER TO MOUNTING KEY	4" X 4" X 4"	D	2 1	2412 AVTP	AB, AC, ZA OR ZC ISOLATED BUILDING POWER
AZ	ROOM PARTITION SENSOR	REFER TO MOUNTING KEY	4" X 4" X 4"	D	1	1810A	ZE
LOUDSPEAKER:							
BA	FLUSH MOUNTED CEILING SPEAKER	REFER TO MOUNTING KEY	N/A	C	1	8471	AB, AC, ZC, ZE OR ZF
BB	NOT USED						
BC	FUTURE SURFACE MOUNTED SPEAKER (INFRASTRUCTURE ONLY)	TBD	1-GANG	C	1	8471	BC OR ZA
BD	NOT USED						
SYSTEM CONTROL:							
CA	NOT USED						
CB	ADA IR EMITTER	TBD	1-GANG	D D	1 1	8240 2412	AB, AC, ZC, YA, CB OR ZE AB, AC, ZC, YA, CB OR ZE
CC	CONTROL SYSTEM TOUCH PANEL	REFER TO MOUNTING KEY	1-GANG OR MANUFACTURER BACKBOX	D	1	2412	ZA OR ZC
CD	MEETING / COLLABORATION ROOM SYSTEM CONTROLLER	REFER TO MOUNTING KEY	1-GANG OR MANUFACTURER BACKBOX	D D D	1 1 1	2412($) 9831 5300UG	BUILDING NETWORK (BY OTHERS) GV/GW/GX/GY/GZ AND/OR AK GV/GW/GX/GY/GZ AND/OR AK
CE	WIRELESS TOUCH PANEL AND WALL MOUNT DOCKING STATION	REFER TO MOUNTING KEY	MANUFACTURER BACKBOX	D	1	2412	ZC
CF	CONTROL SYSTEM WIRELESS ACCESS POINT	REFER TO MOUNTING KEY	1-GANG	D	1	2412	ZC

SCHEDULE OF TERMINATIONS - SCHOOL OF BUSINESS (CONTINUED)

TERM(1)	TERMINATION FUNCTION	MOUNTING HEIGHT	BACKBOX	WIRE GROUP(2)	WIRE QTY(3)	WIRE TYPE(4)	ROUTE TO(5)
SYSTEM INTERFACE:							
GH	CONFERENCE ROOM FLOORBOX	IN FLOOR	LEGRAND EFB10S	A D D --	1 2 2 1	9451 2412 2412 ($) AVTP	ZC ZC BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
GV	65" LCD PANEL W SPEAKERS - TWO INPUTS WITH VIDEO CONFERENCE	6' - 0"	CHIEF PAC522	A B D D D --	1 6 3 2 2 1	9451 9451 RGBHV HDMI 2412 ($) AVTP	GD OR GG GD OR GG GD OR GG GD OR GG BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
GW	65" LCD PANEL W SPEAKERS - ONE INPUT WITH VIDEO CONFERENCE	6' - 0"	CHIEF PAC522	A B D D D --	1 4 2 1 2 1	9451 9451 RGBHV HDMI 2412 ($) AVTP	GE GE GE GE BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
GX	65" LCD PANEL W SPEAKERS - ONE INPUT WITH VIDEO CONFERENCE	6' - 0"	CHIEF PAC522	A B D D D --	1 4 1 2 2 1	9451 9451 RGBHV HDMI 2412 ($) AVTP	GI GI GI GI BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
GY	65" LCD PANEL W SPEAKERS - ONE INPUT	6' - 0"	CHIEF PAC522	B D D D --	2 1 1 2 1	9451 RGBHV HDMI 2412 ($) AVTP	GA OR GB GA OR GB GA OR GB OR BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
GZ	65" LCD PANEL W SPEAKERS - TWO INPUTS	6' - 0"	CHIEF PAC522	B D D D --	4 2 2 2 1	9451 RGBHV HDMI 2412 ($) AVTP	GC GC GC OR BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
HA	TABLETOP COMPUTER A/V (COORDINATE WITH FURNITURE AND SYSTEM DESIGN)	MOUNT IN TABLE. COORD. WITH OWNER	TBD	B D D D --	2 1 1 2 1	9451 HDMI RGBHV 2412 AVTP	GA, GB, GC OR GG GA, GB, GC OR GG GA, GB, GC OR GG GA, GB, GC OR GG ISOLATED BUILDING POWER
HB	TABLETOP COMPUTER A/V - SMARTBOARD (COORDINATE WITH FURNITURE AND SYSTEM DESIGN)	MOUNT IN TABLE. COORD. WITH OWNER	TBD	B D D D D --	2 1 1 2 1 1	9451 HDMI RGBHV 2412 2412 AVTP	GA OR GI GA OR GI GA OR GI GA OR GI GA OR GI ISOLATED BUILDING POWER
HC	TABLETOP COMPUTER A/V - VIDEO CONFERENCE (COORDINATE WITH FURNITURE AND SYSTEM DESIGN)	MOUNT IN TABLE. COORD. WITH OWNER	TBD	A B D D D --	1 4 1 2 2 1	9451 9451 HDMI RGBHV 2412 AVTP	GD, GE OR GG GD, GE OR GG GD, GE OR GG GD, GE OR GG GD, GE OR GG ISOLATED BUILDING POWER
HD	TABLETOP COMPUTER A/V - SMARTBOARD/SECONDARY INPUT (COORDINATE WITH FURNITURE AND SYSTEM DESIGN)	MOUNT IN TABLE. COORD. WITH OWNER	TBD	B D D D D --	4 2 2 2 1 1	9451 HDMI RGBHV 2412 2412 AVTP	GD GD GD GD GD ISOLATED BUILDING POWER
HE	TABLETOP MULTIMEDIA INTERFACE	MOUNT IN TABLE. COORD. WITH OWNER	TBD	D D --	1 1 1	2412 2412 AVTP	GH GH ISOLATED BUILDING POWER
HF	VIDEO CONFERENCE CAMERA	REFER TO MOUNTING KEY	TBD	B D --	2 1 1	9451 HDMI AVTP	GA OR ZC GA OR ZC ISOLATED BUILDING POWER
HG	LOCAL AUDIO INPUT	REFER TO MOUNTING KEY	2 GANG	A B	2 2	9451 9451	ZF ZF
HH	TABLETOP COMPUTER A/V - SMARTBOARD/SECONDARY INPUT (COORDINATE WITH FURNITURE AND SYSTEM DESIGN)	MOUNT IN TABLE. COORD. WITH OWNER	TBD	B D D D D --	4 2 2 4 1 2	9451 HDMI RGBHV 2412 2412 AVTP	GA GA GA GA GA ISOLATED BUILDING POWER
HI	TABLETOP COMPUTER A/V - VIDEO CONFERENCE (COORDINATE WITH FURNITURE AND SYSTEM DESIGN)	MOUNT IN TABLE. COORD. WITH OWNER	TBD	A B D D D --	1 4 2 1 2 2	9451 9451 HDMI RGBHV 2412 AVTP	GI GI GI GI GI ISOLATED BUILDING POWER
HJ	TABLETOP COMPUTER A/V - VIDEO INPUT (COORDINATE WITH FURNITURE AND SYSTEM DESIGN)	MOUNT IN TABLE. COORD. WITH OWNER	TBD	A B D D D --	1 4 2 1 2 2	9451 9451 HDMI RGBHV 2412 AVTP	ZC ZC ZC ZC ZC ISOLATED BUILDING POWER
SYSTEM HUB:							
GA	CONFERENCE ROOM FLOORBOX	REFER TO MOUNTING KEY	LEGRAND EFB10S	D --	4 1	2412($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
GB	CONFERENCE ROOM FLOORBOX	REFER TO MOUNTING KEY	LEGRAND EFB10S	D --	2 1	2412($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
GC	CONFERENCE ROOM FLOORBOX	REFER TO MOUNTING KEY	LEGRAND EFB10S	D --	4 1	2412($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
GD	CONFERENCE ROOM FLOORBOX	REFER TO MOUNTING KEY	LEGRAND EFB10S	D --	4 1	2412($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
GE	CONFERENCE ROOM FLOORBOX	REFER TO MOUNTING KEY	LEGRAND EFB10S	D --	2 1	2412($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
GG	CONFERENCE ROOM FLOORBOX	REFER TO MOUNTING KEY	LEGRAND EFB10S	D --	4 1	2412($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
ZA	AUDITORIUM RACK		STUB CONDUIT WITHIN 6' OF RACK LOCATION	D E --	8 4 4	2412($) M9A026 (#) AVTP	BUILDING NETWORK (BY OTHERS) CAMPUS MANHOLE SYSTEM (BY OTHERS) ISOLATED BUILDING POWER
ZB	WALL MOUNTED RACK		STUB CONDUIT TO RACK LOCATION	D E --	4 4 4	2412($) M9A026 (#) AVTP	BUILDING NETWORK (BY OTHERS) CAMPUS MANHOLE SYSTEM (BY OTHERS) ISOLATED BUILDING POWER
ZC	EQUIPMENT ENCLOSURE		STUB CONDUIT TO RACK LOCATION	D --	6 2	2412($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
ZD	BUILDINGWIDE SYSTEMS RACK		STUB CONDUIT WITHIN 6' OF RACK LOCATION	B D D E --	12 8 4 4 2	9451 2412 2412($) M9A026 (#) AVTP	YA YA BUILDING NETWORK (BY OTHERS) CAMPUS MANHOLE SYSTEM (BY OTHERS) ISOLATED BUILDING POWER
ZE	COMBINABLE CLASSROOM RACK		STUB CONDUIT WITHIN 6' OF RACK LOCATION	D --	20 4	2412($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER
ZF	REMOTE RECESSED WALL MOUNTED RACK		STUB CONDUIT TO RACK LOCATION	D --	4 2	2412($) AVTP	BUILDING NETWORK (BY OTHERS) ISOLATED BUILDING POWER

SCHEDULE OF TERMINATION NOTES:

1. REFER TO LOCATION DRAWINGS.
2. REFER TO CONDUIT SPECIFICATIONS FOR WIRE GROUP SEPARATION REQUIREMENTS.
3. QUANTITY IS TO EACH TERMINATION ID AS INDICATED IN LOCATION DRAWINGS. THIS QUANTITY DOES NOT INCLUDE REQUIRED SPARE RUNS.
4. WIRE TYPE LISTED AS A BELDEN PART NUMBER OR THHN STRANDED TYPE WIRE UNLESS OTHERWISE INDICATED.
5. WIRING HOME RUNS FROM EACH TERMINATION LOCATION TO "ROUTE TO" TERMINATION WITH NO SPLICES.

*: ROUTING INDICATED IN PARENTHESIS MAY BE ROUTED AS A CIRCUIT BUS WIRING SYSTEM. WIRING MAY BE ROUTED TO ANY OTHER TERMINATION ON THE SAME BUS. ALL TERMINATIONS ON THE BUS ARE EFFECTIVELY WIRED IN PARALLEL.

NOTE: I-COM * ARE SEPARATE CIRCUIT BUSES AND MAY NOT BE INTERCONNECTED.

$: IT CAT 6 WIRE IS NOT PART OF AUDIO VIDEO CONTRACT. IT/DATA CONNECTORS ARE LOCATED ON PANELS ADJACENT TO THE AV AND AC POWER RECEPTACLE LOCATIONS. THESE LOCATIONS ARE SHOWN IN THE AV PACKAGE AS A COURTESY AND ARE PROVIDED BY IT CONTRACTOR.

AVTP: AUDIO VISUAL TECHNICAL POWER. SEE WRITTEN SPECIFICATION FOR DETAILS.

NTP: BUILDING POWER. SEE ELECTRICAL SPECIFICATION FOR FULL DETAILS

ELECTRICAL AND BACKBOX INOTES:

AVTP = AUDIO AND VIDEO TECHNICAL POWER. SEE ELECTRICAL SPECIFICATION FOR FULL DETAILS.

NTP = BUILDING POWER. SEE ELECTRICAL SPECIFICATION FOR FULL DETAILS

$ IT CAT 6 WIRE IS NOT INCLUDED IN SCOPE OF WORK FOR BP3 ELECTRICAL CONTRACTOR OR AUDIO/VIDEO SYSTEMS INSTALLER. IT/DATA CONNECTIONS ARE SHOWN IN AV PACKAGE AS A COURTESY, FIELD COORDINATION REQUIRED, REFER TO ELECTRICAL AND TELECOMMUNICATIONS DOCUMENTATION.

% DEVICES INSTALLED TO BE INFRASTRUCTURE ONLY FOR BOTH BP3 AND AUDIO-VIDEO SYSTEM INSTALLATION. THIS WILL INCLUDE A BACKBOX AND CONDUIT AS INDICATED IN THE SCHEDULE OF TERMINATIONS WITH A BLANK FACEPLATE BY BP3 ELECTRICAL CONTRACTOR. AUDIO-VIDEO SYSTEMS INSTALLER IS NOT RESPONSIBLE FOR THE DEVICE.

& DEVICES TO BE COORDINATED WITH FURNITURE (BY OTHERS) AND INSTALLED BY AV SYSTEMS INSTALLER.

CONDUIT PATHWAY REQUIRED TO PROVIDE ACCESS TO CAMPUS MANHOLE SYSTEM WHICH CONNECTS TO USC'S SCHOOLS OF MUSIC AND PUBLIC HEALTH.

BP3 ELECTRICAL CONTRACTOR TO PROVIDE AND INSTALL ALL BACKBOXES AND CONDUIT TO SUPPORT THE AUDIO-VIDEO SYSTEMS. AUDIO-VIDEO SYSTEMS INSTALLATION BY AV INSTALLER.

FINAL LOCATIONS OF BOXES TO BE INDICATED IN ARCHITECTURAL DRAWINGS AND FIELD VERIFIED BY USC/DMSB PERSONNEL. REFER TO A1800 SERIES ARCHITECTURAL DRAWINGS AS DEFAULT. DMSB / USC TO REVIEW AND APPROVE LOCATIONS, IF NECESSARY.

INFRASTRUCTURE ONLY CONSISTS OF CONDUIT, PULLBOX/BACKBOXES AND COVERS. ALL CONDUIT WILL HAVE TWO (2) PULL STRINGS INSTALLED
WIRE COUNTS FOR INFRASTRUCTURE ONLY ARE ANTICIPATED QUANTITY FOR CONDUIT SIZING PURPOSES ONLY

BP3 GENERAL CONTRACTOR TO PROVIDE WALL BACKING AT ALL WALL-MOUNTED DISPLAYS AND EQUIPMENT RACK LOCATIONS PER SHEET A7003.

AV SYSTEM POWER NOT INCLUDED IN AV CONTRACT - SEE ELECTRICAL DOCUMENTS.

USC BUSINESS PARTNERSHIP FOUNDATION
ON BEHALF OF
USC CAMPUS PLANNING & CONSTRUCTION

PROJECT NAME:
UNIVERSITY OF SOUTH CAROLINA
DARLA MOORE SCHOOL OF BUSINESS CONSTRUCTION

OSE PROJECT NUMBER:
H27-6069-AC-3

743 GREENE STREET
COLUMBIA, SC 29298
TEL: 803 777 4022 FAX: 803 777 0484

ARCHITECT:
RAFAEL VIÑOLY ARCHITECTS PC
50 VANDAM STREET
NEW YORK, NY 10013
TEL: 212 924 5060 FAX: 212 924 5858

STRUCTURAL ENGINEER, MEP ENGINEER, CIVIL ENGINEER, FIRE PROTECTION ENGINEER:
STEVENS & WILKINSON, SC
1501 MAIN STREET, FLOOR G
COLUMBIA, SC 29201-5801
TEL: 803 765 0320 FAX: 803 254 6209

TELECOMMUNICATIONS, AUDIOVISUAL & ACOUSTICS:
JAFFE HOLDEN ACOUSTICS, INC.
114A WASHINGTON STREET
NORWALK, CT 06854-3007
TEL: 203 838 4167 FAX: 203 838 4168

LANDSCAPE ARCHITECT:
GRIMBALL-COTTERILL ASSOCIATES
600 BELTLINE BOULEVARD
COLUMBIA, SC 29205
TEL: 803 738 9525 FAX:

SURVEYOR:
BP BARBER & ASSOCIATES, INC.
101 RESEARCH DRIVE
COLUMBIA, SC 29202-1116
TEL: 803 429 4028 FAX:

BUILDING CODE:
HUGHES ASSOCIATES
3610 COMMERCE DRIVE, SUITE 817
BALTIMORE, MD 21227-1652
TEL: 410 737 8677 FAX: 410 737 8688

LIGHTING DESIGNER
ONE LUX STUDIO, LLC
39 WEST 13TH STREET
NEW YORK, NY 10011
TEL: 212 201 5792 FAX: 212 615 3700

FOOD & WASTE MANAGEMENT:
WILLIAM CARUSO & ASSOCIATES, INC.
8955 EAST TUFTS AVE, SUITE 1320
DENVER, CO 80237
TEL: 303.649.1600 FAX: 303.649.1660

SIGNAGE & WAYFINDING:
RAFAEL VIÑOLY ARCHITECTS PC
50 VANDAM STREET
NEW YORK, NY 10013
TEL: 212 924 5060 FAX: 212 924 5858

SPECIFICATIONS:
ROBERT SCHWARTZ & ASSOCIATES
589 8TH. AVE., 17TH. FLOOR
NEW YORK, NY 10018
TEL: 212 691 3248 FAX: 212 633 1613


AV BID PACKAGE A
AUDIO/VIDEO SYSTEMS
JANUARY 18, 2012

PHASE :

100% CONSTRUCTION DOCUMENTS

SEAL & SIGNATURE

ISSUE NO.	ISSUE DATE	ISSUE NO.	ISSUE DATE	ISSUE NO.	ISSUE DATE
4	2013.01.18				
3	2012.12.05				
2	2012.10.26				
1	2012.09.10				
0	2012.07.23				



KEY PLAN & NORTH SIGN

IF THIS DRAWING IS NOT 30" X 42" IT IS A REDUCED PRINT, REFER TO GRAPHIC SCALE

0

NTS

AUDIO / VIDEO SYSTEMS
SCHEDULE OF TERMINATIONS
CLASSROOMS
SCHOOL OF BUSINESS

SHEET TITLE :

AV0003

SHEET NUMBER :