
MCBRYDE FIRE LANE SITE IMPROVEMENTS

FOR

UNIVERSITY OF SOUTH CAROLINA COLUMBIA, SOUTH CAROLINA



LOCATION MAP

SCALE: 1" = 2,000 FT



INDEX OF DRAWINGS	
Sheet Number	Sheet Title
1	COVER SHEET
2	GENERAL NOTES
3	EXISTING CONDITIONS AND DEMOLITION PLAN
4	SITE LAYOUT PLAN
5	GRADING AND EROSION CONTROL PLAN
6	DETAILS SHEET

DICKSON community infrastructure consultants

OWNER/DEVELOPER:

UNIVERSITY OF SOUTH CAROLINA

CONTACT: EMILY JONES,
PROJECT MANAGER/LANDSCAPE ARCHITECT
UNIVERSITY OF SOUTH CAROLINA FACILITIES
DESIGN AND CONSTRUCTION
1300 PICKENS STREET
COLUMBIA, SC 29208
803-777-7592 (PHONE)
EFJONES@FMC.SC.EDU

ENGINEER:


WK DICKSON

CONTACT: MATT JENNINGS, P.E.,
SENIOR PROJECT ENGINEER
1320 MAIN STREET, SUITE 400
COLUMBIA, SC 29201
803-786-4261 (PHONE)
MJENNINGS@WKDICKSON.COM (EMAIL)
WWW.WKDICKSON.COM

NOTICE TO CONTRACTOR

1. PRIOR TO CONSTRUCTION, DIGGING, OR EXCAVATION THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES (PUBLIC OR PRIVATE) THAT MAY EXIST AND CROSS THROUGH THE AREA(S) OF CONSTRUCTION, WHETHER INDICATED ON THE PLANS OR NOT. CALL "811" A MINIMUM OF 72 HOURS PRIOR TO DIGGING OR EXCAVATING. REPAIRS TO ANY UTILITY DAMAGED RESULTING FROM CONSTRUCTION ACTIVITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.





PROJECT NAME:

MCBRYDE FIRE LANE
SITE IMPROVEMENTS
FOR
UNIVERSITY OF SOUTH CAROLINA
COLUMBIA, SOUTH CAROLINA
DRAWING TITLE:

PROJ. MGR.: BET
DESIGN BY: MDJ
DRAWN BY: BAD
PROJ. DATE: NOV. 2019

1 OF 6

WKD PROJ. NO.: 20190363.00.CA WATER LINE

WATER VALVE

WATER METER

WELL

FIRE HYDRANT

TOP OF BANK

BOTTOM OF BANK

PROPERTY LINE

ROADWAY CENTERLINE

LIMITS OF DISTURBANCE

GRASS PAVER SYSTEM REMOVAL

CONCRETE PAVEMENT

CONCRETE SIDEWALK

BRICK PAVERS

MULCH / LANDSCAPE BEDS

COMPOST FILTER SOCK CHECK DAM

COMPOST FILTER SOCK

SEDIMENT TUBE INLET PROTECTION

SURFACE DRAINAGE FLOW DIRECTION

SILT FENCE

DOUBLE ROW SILT FENCE

DIVERSION BERM

· · • • · ·

0-0-

 $-\omega$

SCDHEC EROSION AND SEDIMENT CONTROL NOTES:

- 1. IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
- 2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW:
- A. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE
- B. WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.
- 4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- 5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
- 7. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 ET SEQ. AND SCR100000.
- 8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
- 9. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.
- 10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 11. A COPY OF THE SWPPP, INSPECTIONS RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 12. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- 13. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL
- 14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE:
- 15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG, ETC.).
- 16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
- A. WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL;
- WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS;
- C. FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; AND
- D. SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
- 17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 18. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
- 19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.

SEQUENCE OF CONSTRUCTION

- 1. RECEIVE NPDES COVERAGE FROM SCDHEC AND/OR LOCAL MS4.
- 2. CONDUCT PRE-CONSTRUCTION MEETING.
- 3. NOTIFY SCDHEC EQC REGIONAL EQC OFFICE 48 HOURS PRIOR TO BEGINNING LAND DISTURBANCE ACTIVITIES. MAY ALSO REQUIRE LOCAL REGULATORY NOTIFICATION.
- 4. INSTALLATION OF CONSTRUCTION ENTRANCE.
- 5. INSTALLATION OF PRELIMINARY EROSION CONTROLS.
- 6. BEGIN PERFORMING WEEKLY SCDHEC SWPPP INSPECTIONS UNTIL SITE IS PERMANENTLY STABILIZED.
- 7. INSTALL ALL TEMPORARY EROSION CONTROLS.
- 8. BEGIN DEMOLITION ACTIVITIES AND CLEAR AND GRUB REMAINING AREAS OF THE SITE AS INDICATED ON THE PLANS.
- 9. STRIP AND STOCKPILE TOPSOIL AS NOTED IN THE PLANS AND SPECIFICATIONS.
- COMPLETE THE SITE IMPROVEMENTS AS INDICATED ON THE PLANS.
- 11. CONTINUE PERFORMING WEEKLY SCDHEC SWPPP INSPECTIONS UNTIL SITE IS PERMANENTLY STABILIZED.
- 12. APPLY TOPSOIL AND INITIATE PERMANENT STABILIZATION MEASURES.
- 13. UPON COMPLETE STABILIZATION OF THE SITE, REMOVE ALL TEMPORARY EROSION CONTROL MEASURES.
- 14. SUBMIT NOTICE OF TERMINATION (NOT) TO SCDHEC AS APPROPRIATE (BY ENGINEER).

DURATION OF THE PROJECT.

GENERAL NOTES

- 1. REFERENCE IS MADE TO THE FOLLOWING: A. EXISTING CONDITION SURVEY BASE FILE PROVIDED BY UNIVERSITY OF SOUTH CAROLINA, DATED JULY 2008
- 2. ALL ELEVATIONS SHOWN REFER TO NAVD 88 DATUM.
- HORIZONTAL COORDINATES REFER TO NAD 83 SOUTH CAROLINA STATE PLANE COORDINATE SYSTEM.
- THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. VERIFY ALL FIELD CONDITIONS AND THE EXACT LOCATIONS OF ALL UNDERGROUND UTILITIES PRIOR TO BEGINNING DEMOLITION AND CONSTRUCTION. IF CONDITIONS ARE DIFFERENT FROM THAT SHOWN ON THE PLANS, STOP WORK AND NOTIFY THE ENGINEER.
- ALL WORK FOR THE PROJECT SHALL CONFORM TO THE PROJECT SPECIFICATIONS FOUND IN THE PROJECT MANUAL (CONTRACT DOCUMENTS AND
- CONTRACTOR IS RESPONSIBLE FOR THE LAYOUT AND STAKING OF THE PROPOSED SITE AND LIMITS OF WORK.
- ANY UTILITIES OR FACILITIES DAMAGED DURING THE PROJECT BY THE CONTRACTOR'S PERSONNEL OR EQUIPMENT SHALL BE PROMPTLY REPAIRED AT THE CONTRACTOR'S EXPENSE. HAND DIGGING TO PROTECT UTILITIES FROM DAMAGE SHOULD BE ANTICIPATED.
- THE CONTRACTOR IS RESPONSIBLE FOR CONDUCTING WORK IN ACCORDANCE WITH THE LATEST REQUIREMENTS AND REGULATIONS OF THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA).
- ALL DEMOLITION DEBRIS, INCLUDING CLEARING AND GRUBBING SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH ALL LOCAL, STATE AND FEDERAL REGULATIONS AND SPECIFICATIONS, LATEST REVISION.
- 10. PROMPTLY INFORM THE ENGINEER OF ANY ERROR OR DISCREPANCIES DISCOVERED IN THE DRAWINGS OR SPECIFICATIONS OR CONFLICTS BETWEEN THE DRAWING AND SPECIFICATIONS IN ORDER FOR CORRECTIONS TO BE MADE.
- 11. ALL WORK AND MATERIALS MUST CONFORM WITH UNIVERSITY OF SOUTH CAROLINA, CITY OF COLUMBIA AND SOUTH CAROLINA DEPARTMENT OF
- HEALTH AND ENVIRONMENTAL CONTROL (SCDHEC) REGULATIONS AND SPECIFICATIONS, LATEST REVISIONS AT THE BEGINNING OF CONSTRUCTION. 12. KEEP ALL ADJACENT AREAS TO THE LIMITS OF WORK CLEAN AND FREE OF DEBRIS/MATERIALS/EQUIPMENT AT ALL TIMES.
- 13. CONTRACTOR RESPONSIBLE FOR PREPARING AND OBTAINING APPROVAL OF ALL TRAFFIC CONTROL PLANS AND LAYOUT AS REQUIRED FOR THE
- 14. ANY POSSIBLE STOCKPILES, OFFSITE MATERIAL, WASTE, BORROW, OR CONSTRUCTION EQUIPMENT STORAGE / LAYDOWN AREAS SHALL BE LOCATED WITHIN THE LIMITS OF DISTURBANCE.

GRADING AND EROSION CONTROL NOTES

- 1. EXISTING UNDERGROUND UTILITIES SHALL BE FIELD VERIFIED PRIOR TO INSTALLATION OF ANY NEW PIPE LINES OR GRADING OPERATIONS.
- 2. WHEN GRADING BETWEEN CONTOURS AND BETWEEN POINTS OF SPOT ELEVATIONS, GRADE ON A UNIFORM SLOPE. PROPOSED GRADES SHOWN ARE
- 3. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE ON ALL FINISHED GRADE SURFACES.

PRODUCTS MUST BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.

- 4. EACH SECTION OF STORM DRAINAGE PIPE SHALL BE LAID TO SPECIFIED GRADE AND LAID UPGRADE.
- 5. ALL VEGETATION TOPSOIL SHALL BE STRIPPED AND STOCKPILED PRIOR TO PLACING FILL, PROTECT STOCKPILE FROM EROSION.
- 6. CONTRACTOR SHALL, FOR ALL GRASSED AREAS, BE RESPONSIBLE FOR REPLACING ERODED SOIL AND GRASS SEED UNTIL AN APPROVED STAND OF GRASS IS ESTABLISHED.
- 7. PROPOSED FILL SOILS SHALL BE SUITABLE MATERIAL AND FREE OF ORGANIC MATERIAL, RUBBLE, DEBRIS, AND HIGHLY PLASTIC CLAYS OR SILTS.
- 8. REMOVE ALL ORGANIC AND UNSUITABLE MATERIAL (MUCK AND/OR NON-COMPACTABLE MATERIAL) FROM AREAS TO BE FILLED.
- 9. CONTRACTOR SHALL, BEFORE BEGINNING GRADING WORK ON SITE, STAKE SILT FENCE AND INSTALL ALL PERIMETER EROSION CONTROLS AS SHOWN IN
- 10. CONTRACTOR SHALL BE AWARE OF EXISTING UTILITY LINES DURING PIPE LINE INSTALLATION. CONTRACTOR SHALL NOTIFY UTILITY COMPANIES SUCH AS THE LOCAL ELECTRIC COMPANY, AT&T, ETC. FOR LOCATION OF OTHER UTILITIES NOT SHOWN ON PLAN. CALL PALMETTO UTILITIES PROTECTION SERVICES (SC811) FOR UNDERGROUND UTILITY LINES LOCATION. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.
- 11. ALL NEWLY CONSTRUCTED SLOPES WHICH ARE STEEPER THAN OR EQUAL TO 2.5 TO 1 MUST BE STABILIZED BY INSTALLATION OF EROSION CONTROL MATTING. OTHER AREAS SUCH AS CHANNEL BOTTOMS, CHANNEL SIDESLOPES, AND SLOPES NEAR SENSITIVE WETLAND AREAS MAY ALSO REQUIRE EROSION CONTROL MATTING WHERE SHOWN ON PLANS. USE NORTH AMERICAN GREEN (NAG) ROLLMAX SC150 OR APPROVED EQUAL WHERE CHANNEL PROTECTION/EROSION CONTROL MATTING IS SPECIFIED ON THE PLANS UNLESS OTHER SPECIFIC MATERIAL IS CALLED OUT ON PLAN SHEET. EQUAL
- 12. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES AS MAY BE REQUIRED TO CONTROL SOIL EROSION DURING CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE SITE IMPROVEMENTS ARE COMPLETED.
- 13. ALL AREAS OUTSIDE OF THE LIMITS OF WORK WHICH ARE DISTURBED BY CONSTRUCTION ACTIVITIES SHALL BE SEEDED AT NO ADDITIONAL EXPENSE TO
- 14. INSTALL PERMANENT VEGETATIVE COVER AND THE LONG-TERM EROSION PROTECTION MEASURES OR STRUCTURES AS SOON AS PRACTICAL IN THE
- 15. ALL DISTURBED AREAS NOT PAVED SHALL BE GRASSED OR LANDSCAPED. USE TEMPORARY PLANT COVER, MULCHING, AND/OR STRUCTURES TO CONTROL RUNOFF AND PROTECT AREA SUBJECT TO EROSION DURING CONSTRUCTION.
- 16. ALL SEDIMENT AND EROSION CONTROLS ARE TO BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. MAINTENANCE OF SEDIMENT TRAPPING DEVICES SHALL BE PERFORMED AS
- NECESSARY PER THESE INSPECTIONS, DAMAGED OR INEFFECTIVE DEVICES SHALL BE REPAIRED OR REPLACED, AS NECESSARY. 17. ADDITIONAL EROSION CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION TO CONTROL EROSION AND/OR OFF SITE SEDIMENTATION.
- CONTRACTOR IS RESPONSIBLE FOR MAINTAINING THE STABILITY OF ALL GRADED AND/OR CLEARED AREAS UNTIL PERMANENT GROUND COVER IS ESTABLISHED. ANY AREAS DAMAGED BY EROSION SHALL BE REPAIRED TO ITS ORIGINAL CONDITION AND PROTECTED FROM FURTHER EROSION AT NO ADDITIONAL COST TO THE OWNER.
- 18. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETED AND THE SITE STABILIZED.
- 19. ALL EROSION CONTROL METHODS SHALL BE IN ACCORDANCE WITH "SCDHEC STORM WATER MANAGEMENT & SEDIMENT CONTROL BMP HANDBOOK FOR LAND DISTURBANCE ACTIVITY".
- 20. ALL DISTURBED AREAS, INCLUDING THE CONTRACTORS STAGING AREA, HAUL ROUTES, GRADING LIMITS, ETC., SHALL BE RESTORED TO A SMOOTH LINE AND GRADE WITH POSITIVE DRAINAGE. THE CONTRACTOR SHALL PERMANENTLY SEED ALL DISTURBED AREAS.
- 21. CONTRACTORS ARE REQUIRED TO HAVE RAIN GAUGES AT THE CONSTRUCTION SITE AND THE RAIN TOTALS DOCUMENTED FOR REVIEW BY SCDHEC.
- 22. THE INSTALLATIONS OF UTILITIES (CABLE, ELECTRICAL, NATURAL GAS, WATER, SEWER, ETC.) ARE TO BE WITHIN THE PERMITTED LIMITS OF DISTURBANCE AND THAT INSTALLATION OUTSIDE OF THESE AREAS WILL REQUIRE A MODIFICATION TO THE PERMIT.
- 23. THE STABILIZATION OF CONVEYANCE CHANNELS ARE TO BE COMPLETED WITHIN 7 DAYS OF CHANNEL CONSTRUCTION (IF THERE ARE CHANNELS).



ALL DISTURBED AREAS WHICH ARE TO BE LEFT IDLE FOR A PERIOD OF 14 DAYS OR LONGER ARE TO RECEIVE TEMPORARY VEGETATION OR MULCH.

EROSION CONTROL MAINTENANCE SCHEDULE


ALL SEDIMENT AND EROSION CONTROLS ARE TO BE INSPECTED AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS. CONTRACTOR TO DOCUMENT WITH SCDHEC APPROVED INSPECTION REPORTS AND LOGGED IN THE PROJECT SWPPP.



1320 MAIN STREET SUITE 400 COLUMBIA, SC 29201 (t)803-786-4261 (f)803-786-4263

WWW.WKDICKSON.COM

W. K. DICKSON & COMPANY, IN




PROFESSIONAL SEAL


NO


PROJ. MGR.: | BET DESIGN BY: MDJ DRAWN BY: BAD

PROJ. DATE: NOV. 2019 DRAWING NUMBER:

NKD PROJ. NO.: 20190363.00.CA







TYPE A - SEDIMENT TUBE INLET PROTECTION

GENERAL NOTES


- Sediment tubes are elongated tubes of compacted geotextiles curled excelsior wood, natural coconut fiber, or hardwood mulch. Straw, pine needle, and leaf mulch-filled sediment tubes are not permitted.
- The outer netting of the sediment tube should consist of seamless ultraviolet stabilizers or a seamless, high-density polyethylene non-degradable material.
- Sediment tube diameters shall range from 18-inches to 24-inches. 4. Remove accumulated sediment when it reaches 1/3 the height of the Sediment tunes with smaller diameters are prohibited when used as inlet protection.
- Curled excelsior wood, or natural coconut products that are rolled up to create a sediment tube are not allowed.
- Sediment tubes should be staked using wooden oak stakes (2-inch X 2-inch) or steel posts (standard "U" or "T" sections with a minimum weight of 1.25 pounds per foot) at a minimum of 48-inches in length placed on 2-foot centers.
- Install all sediment tubes to ensure that no gaps exist between the 7. Inlet protection structures should be removed after the disturbed soil and the bottom of the tube. Manufactuer's recommendations should always be consulted before installation.
- The ends of adjacent sediment tubes should be overlapped 6-inches to prevent flow and sediment from passing through the field joint.
- 8. Sediment tubes should not be stacked on top of one another
- 9. Each sediment tube should be installed in a trench with a depth egual to 1/5 the diameter of the sediment tube.
- 10. Install stakes at a diagonal facing incoming runoff.

INSPECTION & MAINTENANCE

- 1. The key to functional inlet protection is weekly inspections, routine maintenance, and regular sediment removal.
- 2. Regular inspections of sediment tube inlet protection shall be conducted once every calendar week and, as recommended, within 24-hours after each rainfall even that produces 1/2-inch or more of
- high-density polyethylene photodegradable materials treated with 3. Attention to sediment accumulations in front of the sediment tube is extremely important. Accumulated sediment should be continually monitored and removed when necessary.
 - sediment tube. When a sump is installed in front of the inlet protection, sediment shall be removed when if fills approximately 1/3 the depth of the sump.
 - 5. Removed sediment shall be placed in stockpile storage areas or spread thinly across disturbed area. Stabilize the removed sediment after it is relocated.
 - 6. Large debris, trash, and leaves should be removed from in front of tubes when found.
 - areas are permanently stabilized. Remove all construction material and sediment, and dispose of them properly. Grade the disturbed area to the elevation of the drop inlet structure crest. Stabilize all bare areas immediately.

or 1.25 #/FT STEEL POSTS

SEDIMENT TUBE INSTALLATION POST INSTALLATION DETAIL DETAIL




SEDIMENT TUBE BURIAL DETAIL

SEDIMENT TUBE INLET PROTECTION (DROP INLET OR YARD INLET)


2" x 2" WOOD STAKES -

NOT TO SCALE

Temporary Seeding - Upstate




Permanent Seeding - Upstate



- 1. AREAS TO BE GRASSED SHALL BE DEFINED AS ALL AREAS OF SITE WITHIN THE GRADING LIMITS AND NOT OCCUPIED BY PAVING, CRUSHED STONE SURFACING OR STRUCTURES. GRASSING SHALL INCLUDE FINAL SHAPING, LIMING, FERTILIZING AND SEEDING OR SODDING.
- RULES AND REGULATIONS UNDER FEDERAL SEED ACT IN EFFECT ON DATE BIDS ARE RECEIVED. SEED SHALL BE DELIVERED IN STANDARD CONTAINERS. SEED WHICH HAS
- SPREAD SEED AT A RATE AS NOTED ON THE DRAWINGS/SPECIFICATIONS
- ENGINEER. WHEN ANY PORTION OF SURFACE BECOMES GULLED OR OTHERWISE DAMAGED FOLLOWING SEEDING, OR SEEDLINGS HAVE BEEN WINTER-KILLED OR OTHERWISE DESTROYED, AFFECTED PORTION SHALL BE REPAIRED TO RE-ESTABLISH CONDITION AND
- ALL DISTURBED AREAS ARE TO BE GRASSED IMMEDIATELY AFTER CONSTRUCTION IN THE AREA. AT NO TIME WILL AN AREA BE LEFT BARE FOR MORE THAN 14 DAYS AFTER COMPLETION OF CONSTRUCTION.
- PERMANENT GRASS SHALL BE PROVIDED FOR ALL DISTURBED AREAS. SEED SHALL BE A AND FOREIGN MATERIAL AND DEBRIS REMOVED. FERTILIZER AND LIME SHALL BE THOROUGHLY WORKED INTO THE SOIL, AND THE SURFACE RAKED SMOOTH BEFORE APPLYING SEED. SEED SHALL BE APPLIED EVENLY AT THE MINIMUM RATE AND RAKED IN
- CONTRACTOR SHALL WATER AS NEEDED UNTIL GRASS IS ESTABLISHED.
- ALL DISTURBED AREAS SHALL BE HYDROSEEDED UNLESS SHOWN ON PLANS TO RECEIVE SODDING OR COMPOST BLANKET.

GRASS SEEDING NOTES / SCHEDULES

- SEEDS SHALL BE MIXTURE AS APPROVED BY THE ENGINEER AND SHALL MEET REQUIREMENTS OF SEED LAWS OF THE STATE AND THE U.S. DEPARTMENT OF AGRICULTURE BECOME WET, MOLDY OR DAMAGED IN TRANSIT OR STORAGE WILL NOT BE ACCEPTABLE.
- AREAS THAT REQUIRE RE-FERTILIZATION AND\OR RE-SEEDING WILL BE DESIGNATED BY THE GRADE OF SOIL PRIOR TO SEEDLING AND SHALL BE RE-SEEDED AS SPECIFIED ABOVE.
- MINIMUM 90% PURITY AND 80% GERMINATION. AREAS TO HAVE GRASS APPLIED SHALL BE SCARIFIED CULTIVATED TO A DEPTH OF 3 INCHES, WITH ALL CLODS OR CLUMPS BROKEN UP LIGHTLY.



HEAVY DUTY CONCRETE PAVEMENT

NOT TO SCALE

SEE PLANS

FINISHED GRADE

6" - 4,000 PSI CONCRETE

MAXIMUM DRY DENSITY

- 24" COMPACTED SUBGRADE

4" GRADED AGGREGATE BASE COURSE


COMPACTED TO 98% MODIFIED PROCTOR

98% STANDARD PROCTOR MAXIMUM DRY

- CONTRACTOR TO VERIFY PROPER BASE COMPACTION AND ELEVATIONS PRIOR TO PAVER INSTALLATION.
- 2. EXISTING GRASS PAVER SECTION CONSISTS OF APPROXIMATELY 1" OF GRASSPAVE PLASTIC CELL COMPONENTS AND 8"
- GRADED AGGREGATE BASE COURSE. 3. CONTRACTOR SHALL EXCAVATE APPROXIMATELY 2" INTO THE EXISTING GRADED AGGREGATE BASE COURSE,
- RE-COMPACT AND MAINTAIN A MINIMUM 6" SECTION EXISTING GRADED AGGREGATE BASE COURSE. 4. FINISHED GRADE OF BRICK PAVER FIRE LANE SECTION CAN BE SET A MAXIMUM 1" HIGHER THAN CURRENT EXISTING
- GRADES. CONSTRUCT SMOOTH TRANSITIONS BETWEEN EXISTING INLETS AND SURROUNDING SIDEWALKS.

BRICK PAVER FIRE LANE SECTION


NOT TO SCALE



NOTES:

1. JOINTS SHALL BE LOCATED AS SHOWN ON THE PLANS OR 30'-0" OC EW (MAX).

CONSTRUCTION JOINT



USE T=1" FOR NEW CONCRETE ADJACENT

TO BUILDINGS OR EXISTING SAW-CUT

PROVIDE 1/2" EXPANSION JOINT WHERE

CONCRETE PAVING AND SIDEWALK ABUTS

ADJACENT STRUCTURES AND DISSIMILAR

EXPANSION JOINT

NOT TO SCALE

PAVEMENT/CONCRETE.


NOTES:

NOT TO SCALE SEALANT — 1/8" SAWED JOINT — T/3*

OC EW (MAX).

2. JOINT DEPTH = 2 1/2" (MAX)

NOTES:



JOINTS SHALL BE LOCATED AS

CONTROL JOINT

NOT TO SCALE

SHOWN ON THE PLANS OR 15'-0"

1. MINIMUM THICKNESS = 4".

2. PROVIDE EXPANSION JOINTS @ INTERSECTIONS OF WALKS AND WHERE WALK ABUTTS OTHER STRUCTURES.

SPACING TO

WIDTH

6'-0" MAX

— CONTROL

JOINT -

MATCH SIDEWALK

98% MODIFIED PROCTOR MAXIMUM DRY

DENSITY

- 3. 4000 PSI MINIMUM CONCRETE FOR 28 DAY STRENGTH.
- 4. SIDEWALKS TO HAVE BROOM FINISH.

3/8" EXPANSION JOINT:

FILLER @ 30'-0" MAX


- EXPANSION JOINT


- 5. CONTROL JOINTS TO BE SAWED TO A MINIMUM DEPTH OF 1".
- 6. SMOOTH TROWEL 3" "PICTURE FRAME" EDGE, TYP.


CONCRETE SIDEWALK

NOT TO SCALE

DWK DICKSON 1320 MAIN STREET SUITE 400 COLUMBIA, SC 29201 (t)803-786-4261 (f)803-786-4263 WWW.WKDICKSON.COM







FOR UNIVERSITY OF SOUTH CAR(COLUMBIA, SOUTH CAROI

USE

00

BID

PROJ. MGR.: | BET DESIGN BY: MDJ DRAWN BY: BAD PROJ. DATE: NOV. 2019

DRAWING NUMBER:

WKD PROJ. NO.: 20190363.00.CA