



ADDENDUM 02

Project: Upstate Information Resource Center Renovations

Owner: USC

JCS Project #: 18104

State Project #: H34-9517

Date: 1/6/2021

GENERAL:

1. Bidders are directed to Note 1 on the Finish Schedule Notes, Sheet A501, which states "ALL FLOOR FINISHES AND BASE ARE PROVIDED BY OWNER (N.I.C.)."

SPECIFICATIONS:

1. **Section 12 3000, High Pressure Melamine Construction Modular Casework.**

Paragraphs 1.5 D & E, and 1.8: Delete paragraphs in their entirety. Certified participation in AWI's Quality Certification Program is not required for this project.

Paragraph 2.1 A: ADD items:

4. Lentz Cabinets
5. WoodCo Inc.

DRAWINGS:

1. **Sheet A301, First Floor Plan.** REVISE note at Rooms 119 and 120 to read "ROOMS 119 AND 120: EXTEND EXISTING WALLS TO DECK (DECK IS APPROX. 15' A.F.F.). REMOVE ONE LAYER OF GWB AND INSTALL SOUNDPROOFING INSULATION IN STUD CAVITY (SHEETBLOK OR QUIET BATT). REPLACE GWB (TO DECK EA. SIDE)."
2. **Sheet A300, A901 and A902, Ceiling Plan General Notes.** ADD note to read "9. EXISTING CEILING HANGER WIRES MAY BE USED AS LONG AS THEY MEET THE CEILING MANUFACTURER'S REQUIREMENTS FOR THE SEISMIC DESIGN CATEGORY."
3. **Sheet E203, 2nd Floor Power Plan.** ADD note to read "CONTRACTOR SHALL COORDINATE WITH MANUFACTURER FOR SIZE OF CORE DRILLING OF SLAB REQUIRED FOR POWER/COMMUNICATION POKE THROUGH DEVICES."

END OF ADDENDUM