

ADDENDUM NUMBER TWO

for

**UofSC Union- Nursing Program Upgrades
Project No.: U-971-20-1
State Project Number: H40-9528 / 50003415-3**

COLUMBIA, SOUTH CAROLINA

PREPARED BY:

The Boudreaux Group 1519 Sumter Street, Columbia, South Carolina 29201

DATE OF ISSUE: February 3, 2021

TO: ALL BIDDERS OF RECORD, CONSULTANTS, OWNER:

The following items shall take precedence over the drawings and specifications for the above named project and shall become a part of the contract documents. Where any item called for in the specifications, or indicated on the drawings, is not supplemented hereby, the original requirements shall remain in effect. Where any original item is amended, voided or superseded hereby, the provisions of such item not specifically amended, voided or superseded shall remain in effect.

CONTRACTOR SHALL ACKNOWLEDGE RECEIPT OF ADDENDUM.

This addendum consists of 3 page and the following attachments:

- D1.1 Demolition Floor Plan
- A0.1 Slab Preparation Plan
- A1.1 First Floor Plan
- E0.2 Lighting & Equipment Schedules
- E0.50 Electrical Panel Schedules
- E1.1 Lighting Plan
- E2.1 Power & Telecommunications Plan
- E4.1 Mechanical Power Plan

I. DRAWINGS

- A. Refer to Drawings D1.1, A0.1 and A1.1 and clouded keynotes and keynote descriptions for additional demolition, slab preparation and new construction items.
- B. **Revision:** Reference Drawing M2.1, Details, Notes, Schedules and Legend. Reference Rooftop Heat Pump Schedule, for RTU-2 delete reference to Remark 4. For RTU-3 delete reference to Remark 5.

UofSC Union- Nursing Program Upgrades
Addendum Number Two

C. Electrical Drawings:

- **Drawing E0.2:**

Add 'Lighting Fixture Prior Approved Schedule'.

Jademar Lighting type JFP22 series is approved substitute for type 'A2', 'A2E' fixture.

Jademar Lighting type JFP24 series is approved substitute for type 'A4', 'A4E' fixture.

HE Williams lighting 4PR series is approved substitute for type 'D', 'DE', 'DR', 'DRE' fixtures.

HE Williams lighting 75R series is approved substitute for type 'J4P', 'J4PE', 'J4WE' fixtures.

Pathway Lighting C73A series is approved substitute for type 'P' fixture.

Brownlee series 7027 is approved substitute for type 'RE' and type 'W' fixtures.

Emergillite series ELXN is approved substitute for type 'X1' and 'X2' fixtures.

Day-Brite Lighting 2FXP series is approved substitute for type 'A2', 'A2E', 'A4', and 'A4E' fixtures.

Vantage Lighting F-Class commercial series is approved substitute for type 'D', 'DE', 'DR', and 'DRE' fixtures.

Mercury Lighting LW4 series is approved substitute for type 'J4P', 'J4PE', and 'J4WE' fixtures.

Sonneman Wide Bath Bar series is approved substitute for type 'JV2' and 'JV6' fixtures.

Nora Lighting NYLM series is approved substitute for type 'P' fixture.

Gardco 104L series is approved substitute for type 'RE' and 'W' fixtures.

Entronix ILX series is approved substitute for type 'X1' and 'X2' fixtures.

Light Fixture Schedule:

Edit type 'JV2' and 'JV6' manufacturer to say "Modern Forms Lighting".

Delete types 'A2R', 'A2RE', and 'R' from light fixture scheduler.

Lighting Control Scheme Legend:

Edit Mark 3 as shown on drawing E0.2.

Equipment Connection Schedule:

Add note 4 to Equipment Connection Schedule Notes.

Add note 4 reference to EF-4 and EF-5.

- **Drawing E0.50:**

Delete 'Existing' from Panelboard LP description.

Add circuit# 31 description as indicated on drawing E0.50 to Panel LP.

- **Drawing E1.1:**

Add two type 'W' fixtures to plan west wall.

Change type 'A2R' fixtures to type 'A2'.

Change type 'A2RE' fixtures to type 'A2E'.

Change type 'R' fixtures on plan north wall to type 'RE'.

- **Drawing E2.1:**

Change Panel 'L1' to 'LP' in 'Enlarged Elect. Rm Plan'.

- **Drawing E4.1:**

Add circuit #31 for paper towel dispensers in First Floor Mechanical Equipment Plan.

Add note 3 to Key Notes.

Change EF-3 to EF-4 in First Floor Mechanical Equipment Plan.

Change EF-4 to EF-5 in First Floor Mechanical Equipment Plan.

Change EF-5 to EF-3 in First Floor Mechanical Equipment Plan.

II. SPECIFICATIONS

- A. Refer to Specification Section 064023 – Interior Architectural Woodwork. In-lieu of the casework fabricator providing AWI Quality Certification Program certificates, they may instead demonstrate that their shop has practiced AWI quality standards for at least 10 years, and that they are currently members of AWI. The casework is to be built to AWI standards.
- B. **Revision:** Reference Specification Section 230010 General Provisions – HVAC. The following manufacture is added as prior approved:

Unitary Heat Pump Units: Johnson Controls

- C. Refer to specification section 033000 Cast-In-Place Concrete; delete paragraph section 3.8.B.2. This section applies to finishing masonry which is not applicable to this project.

END OF ADDENDUM