

HASS & HILDERBRAND, INC.

133 Greenville St., S.W.
P.O. Box 3276
Aiken, SC 29802-3276
Telephone: (803) 649-1316

Project Name: UofSC REBID Aiken Parking Lot Seal Coating/Restriping
Project Number: FP00000345

Addendum Number Two

Date: October 8, 2020

From: Tilden Hilderbrand, P.E.

To: All Bidders:

The following items add to, modify, clarify or otherwise alter the Drawings and/ or specifications and will be a part of the Contract Documents. Where a portion of the Drawings and/or specification is added to, modified or otherwise altered, the portion not so affected shall remain. Bidder shall include all effects that these items may have on this proposal.

Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may subject Bidder to disqualification.

General:

1. Areas shown shaded on the plan sheet depict all areas on the Campus paved with asphalt. All asphalt is to be included in the bid.
2. Work defined in Alternate 1 can be performed by a properly licensed subcontractor. All work is to be performed by properly licensed contractors.
3. All curbs and light pole bases that are currently painted on the campus are to be prepared and re-painted.
4. Piles of sand and shipping containers in some asphalt areas will be moved by the owner before work commences.
5. UofSC will notify students and staff of contractor's work schedule. Any cars not moved will be removed by the owner.
6. A bid is required for the Alternate in order for the bid to be considered.
7. The contractor will be allowed to work up to 24 hours per day 7 days per week.
8. Students will be dismissed Tuesday November 24, 2020 and will not return until January 11, 2021.
9. The owner will allow one lot or possibly two lots to be closed for work at a time. Contractor is to provide barricades, barrels, signage and traffic control to accommodate these closures. Roads connecting parking lots and providing fire and service access to buildings will have to remain open. Contractor is to provide traffic control as required.
10. The contract will require the work to be performed within 60 calendar days. Based on the projected start date of the project, this time will be extended if temperatures and rainfall will not allow for the proper installation of the materials based on material manufacturer's warranty requirements.
11. SCDOT type D asphalt (compacted) may be used to patch larger, deeper cracks.

End of Addendum Two

Engineering - Surveying - G.P.S. - Forestry & Land Planning Services