

USC-Aiken Replace Roof Top Units at Student Activity Center

Project No.: H29-I363 50003417

April 1, 2021

Addendum No. 2

1. Clarification on electrical scope of work for each roof top unit being replaced. Electrical power to be disconnected, provide and install new fused electrical disconnect switch and then reconnect electrical power.
2. Building Automation System: Andover is the existing BMS brand in this building. This product is serviced by EMCOR Services Aircond. Contact David Sallerson at 404-859-3999 or email dsallerson@aircond.com to coordinate controls scope of work.
3. Reference M001, Gas Fired Rooftop Unit Schedule: Add Option 14 to all Tags which reads, "ELECTROMECHANICAL CONTROLS VIA THERMOSTAT TERMINAL STRIP"
4. Reference M001, Gas Fired Rooftop Unit Schedule: Add Option 15 to all Tags which reads, "COIL GUARDS"
5. Reference M001, Gas Fired Rooftop Unit Schedule: For RTU-1, RTU-7, and RTU-8; Revise IEER = 15.00 and EER = 12.1.
6. Reference M001, Gas Fired Rooftop Unit Schedule: For RTU-14; Revise IEER = 15.00 and EER = 12.6.
7. Reference M001, Gas Fired Rooftop Unit Schedule: For RTU-2; Revise Voltage/Phase = 208/230, 1Phase

Office: 706.774.1020
Fax: 706.774.0065

PO Box 1586
550 11th. Street
Augusta, Georgia 30903

ing
CONSULTING
MECHANICAL ENGINEERING
HVAC | PLUMBING | FIRE PROTECTION
www.ingconsultinginc.com