

University of South Carolina, Columbia Campus
USC Garden Lighting Renovation
Project Number: CP003858889
Project Manager: Emily Jones

Addendum Number Two

DATE: December 3, 2014

FROM: Clarissa G. Clark, CPPB
Procurement Manager

TO: All Bidders

The following items add to, modify, clarify, or otherwise alter the Drawings and/pr specifications and will become a part of the Contract Documents. Where a portion of the Drawings and/or specifications is added to, modified, clarified, or otherwise altered, the portion not so affected shall remain. Bidder shall include all effects that these items may have on their proposal.

Acknowledge receipt of this Addendum in the appropriate space on the bid form. Failure to do so may subject the bidder to disqualification.

General

1. One parking space for contractor's work vehicle will be provided in an adjacent lot (at Pinckney/Legare College). Laydown space will be provided at the Preston Green open space (between raised garden beds and existing construction fencing). Secured fencing (6' chain link fencing with privacy screen) for laydown area shall be provided by the contractor as desired.
2. Additional parking (e.g. employee personal vehicle parking) may be arranged through Parking Services. Spaces in campus garages may be rented for \$60/month, with a \$25 access card charge. Contact Parking Services at 777-4366 for additional information.
3. Excavation work shall be performed in a timely manner. Open trenches or other site disturbances shall be covered and/or restored at the end of the work week to allow reasonable access to the garden by the House residents during weekend periods.

Drawings:

1. Reference Sheet E2. Type 'F' fixtures without circuit numbers shall be fed with circuit B-21.
2. Reference Sheet E2, Lighting Fixture Schedule. For Type AN (New LED Post Top Lantern on USC-Supplied Pole), add the following note:
'Contractor shall cut down poles as needed to match existing height of other poles.'
3. Reference Sheet E2, Lighting Fixture Schedule. Add the following note:
'For each fixture listed, contractor shall provide two (2) fixtures and two (2) re-build kits for spare equipment to be turned over to Owner.'
4. The following products are approved for the project:

Type	Manufacturer	Catalog Number
C	BK LIGHTING	HP2-LED-TR-X22-SP-BLW-D15-120-GM-R
D	BK LIGHTING	PS-LED-E22-A9-BLW-A-PP-T
F	BK LIGHTING	DS-LED-E22-WFL-A9-FINISH-12-A-360SL/TRE20/WALL MOUNT CANOPY
G	BK LIGHTING	B-RM-AR-LED-E22-WFL-A9-MAC-12-E/RING MOUNT CANOPY/TR150
J	BK LIGHTING	DS-LED-E22-NSP-AP-BLW-A/PP-S-XXT-TRE20-B-BLW
K	BK LIGHTING	B-EC-LED-E22-NSP-A9-MAC-CAP STYLE-SQUARE CANOPY/TR150

5. Reference Sheet E3, Sound System Infrastructure Upgrade. At the Legend, the NEMA 4X J-box shall be mounted at 48" AFG, not 24" AFG.

END OF ADDENDUM TWO