

ADDENDUM NUMBER 2
Tuesday, April 21, 2015

PROJECT: **USC Upstate Modifications to Burroughs**
 USC PROJECT NO. CP00418380
 GMC PROJECT NO. AGRE140048

This addendum forms a part of the Construction Documents and modifies the original Bidding Documents dated 03.26.2015 as noted below. Acknowledge receipt of this addendum in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

GENERAL:

- A2G1 Asbestos has been found in the Burroughs Building, which is causing changes to the scope of work as described here within. No abatement work shall be done in this scope of work, and the Asbestos will be removed by others prior to construction.
- A2G2 The contractor shall not be responsible for removal of any existing carpet or vinyl flooring in this scope of work.
- A2G3 The contractor shall not be responsible for any above ceiling insulation.
- A2G4 The contractor shall not be responsible for re-installing Fire Alarm devices.

DRAWINGS:

- A2D1 Sheet A1.00, Demolition Plan, the following items will be removed by others prior to commencement of new work:
- All Interior gypsum board.
 - Acoustical ceiling tile and grid.
 - Wall hung plumbing fixtures.
 - Lighting and emergency fixtures.
 - Furniture.
 - Interior doors and trim.
 - Wall mounted electrical devices.
 - Fire Alarm devices
- A2D2 Sheet A1.01, Floor Plan, 1/A1.01, the Contractor shall provide new gypsum board on all interior existing walls. These walls shall be primed and painted with two topcoats. The inside face of the exterior wall is CMU and shall not receive gypsum board.
- A2D3 Sheet A1.01, Floor Plan, 3/A1.01, the Contractor shall provide new acoustical ceiling tile and grid throughout the entire building's interior.
- A2D4 Sheet E1.01, Electrical Plan, the Contractor shall install all new owner furnished ceiling mounted light fixtures.

END OF ADDENDUM NUMBER 2