
CAMPUS PLANNING AND CONSTRUCTION COLUMBIA, SC 29208

 Ω

sity

SHEET: HEET IN SET

 OF



GREENE AND SUMTER STREET INFRASTRUTURE UTILITY UPGRADE AT USC CAMPUS IN COLUMBIA

APPLICANT'S CERTIFICATION

"I (We) hereby certify that all clearing, grading, construction, and/or development will be done pursuant to this plan and I (we) are responsible for the land disturbance and related maintenance thereof. South Carolina Department of Health and Environmental Control authorities will be allowed to enter the project site for the purpose of on-site inspections."

Owner/Person Finacially Responsible

DESIGNER'S CERTIFICATION

"I hereby certify that this plan is designed to contain soil on the property concerned to the maximum extent, to provide for the protection of the property and the proposed improvements thereon from the effects of flooding, to provide for the control of the runoff from the property, and that all the provisions for sediment control and storm drainage are in accordance with the Stormwater Management and Sediment Control Ordinance for South Carolina Department of Health and Environmental Control."

SC Registered Professional Engineer

S.C. Registration Number

RICHLAND COUNTY MINIMUM GRASSING SPECIFICATIONS

. SUMMER: FERTILIZATION: 1000 LBS. OF 10-10-10 PER ACRE

PERMANENT COVER: BAHIA GRASS

40 LBS. PER ACRE ALONE 20 LBS. PER ACRE W/MIXTURE 8 LBS. PER ACRE ALONE 4 LBS. PER ACRE W/MIXTURE

LOVEGRASS, WEEPING 2 LBS. PER ACRE PLANT IN MIXTURES ONLY

BERMUDA SPRIGS (SCARIFIELD)

100 LBS. PER ACRE BROADCAST SERICEA LESPEDEZA 40 LBS. PER ACRE ALONE 40 LBS. PER ACRE IN MIXTURES

TEMPORARY SUMMER COVER:

LESPEDEZA, ANNUAL

7 LBS. PER ACRE IN MIXTURE (DO NOT PLANT ON SANDY SOILS) 40 LBS. PER ACRE ALONE

20 LBS. PER ACRE IN MIXTURES

BROWN TOP MILLET

A. WINTER PERMANENT:

2. WINTER:

OATS

1) TALL MEADON FESCUE, 40 LBS. PER ACRE FROM SEPT. 1 TO APRIL 15 ONLY ON FERTILE SANDY CLAY OR CLAY SOILS. 2) PLANTING FROM SEPT. 15 TO FEB. 15 ON SANDS MUST BE OF TEMPORARY WINTER

CLOVER AND THEN SEEDED TO A PERMANENT SUMMER COVER.

B. WINTER TEMPORARY: SEPT. 1 TO MAY 1 RYE GRASS

60 LBS. PER ACRE ALONE 20 LBS. PER ACRE IN MIXTURES 4 LBS. PER ACRE ALONE

SEPT. 1 TO MAR. 1

2 LBS. PER ACRE IN MIXTURE 1-1/2 LBS. PER ACRE ALONE 1 LB. PER ACRE IN MIXTURE


OTHER PLANTINGS OR SEEDING AS CONTAINED IN THE CRITICAL AREA STABILIZATION SECTION OF SCS HANDBOOK, EROSION AND SEDIMENT CONTROL IN DEVELOPING AREAS, MAY BE USED PROVIDED ALL APPLICABLE SPECIFICATIONS CONTAINED IN SAID HANDBOOK ARE COMPLIED WITH.

EROSION AND SEDIMENT CONTROL NOTES

STORM EVENT WHENEVER PRACTICAL.

- 1. IF NECESSARY, SLOPES WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
- STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE IN PORTIONS OF TH SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW.
- WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS, STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE. WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES
- -DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED EVERY SEVEN (7) DAYS. IF SITE INSPECTION IDENTIFY BMPs THAT ARE DAMAGED OR ARE NOT OPERATING EFFECTIVELY, MAINTENANCE MUST BE PERFORMED AS SOON AS PRACTICAL OR REASONABLY POSSIBLE AND BEFORE THE NEXT
- PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED AND GRADED AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER AND TEMPORARY SEEDING AT END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY
- ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- 6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
- RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH SC REG 72-300 ET SEQ AND SCR100000.
- 8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR DIVERT SEDIMENT LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
- ALL WATERS OF THE STATE(WoS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL Wos. A TEN-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WoS.

10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICAL THAT COULD BE EXPOSED TO STORMWATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.



CONTACT INFORMATION CONTACT: ANN DERRICK UNIVERSITY OF SOUTH CAROLINA 743 GREENE STREET COLUMBIA, S.C. 29208 TEL. (803)-777-5811

FAX. (803)-777-8739

