

ADDENDUM TO
SPECIFICATIONS ENTITLED
"Humanities Office and Classroom Buildings
Roof Replacement Project"
DATED May 2012

ADDENDUM NO. 3

August 3, 2012

1. The Specifications and Drawings contained in the project manual "Humanities Office and Classroom Buildings Roof Replacement Project May 2012" are amended as follows:

2. CHANGES TO SPECIFICATION:

SE-330 BID FORM

Delete page one of the Bid Form and replace with the attached new page one of the Bid Form.

3. CHANGES TO THE DRAWINGS:

None.

Nothing herein is interpreted or construed as changing any provisions of the specifications except as specifically stated herein.

END OF ADDENDUM NO.3

Attachment(s): ADD3 – BID FORM (1 page)

BID FORM – ADD 3

2011 Edition

SE-330

Bidders shall submit bids on only Bid Form SE-330.

BID SUBMITTED BY: _____
(Bidder's Name)

BID SUBMITTED TO: University of South Carolina
(Owner's Name)

FOR PROJECT: H27-6094 Humanities Office and Classroom Buildings
(Number) Roof Replacement Project
(Name)

OFFER

§ 1. In response to the Invitation for Construction Bids and in compliance with the Instructions to Bidders for the above-named Project, the undersigned Bidder proposes and agrees, if this Bid is accepted, to enter into a Contract with the Owner on the terms included in the Bidding Documents, and to perform all Work as specified or indicated in the Bidding Documents, for the prices and within the time frames indicated in this Bid and in accordance with the other terms and conditions of the Bidding Documents.

§ 2. Pursuant to Section 11-32-3030(1) of the SC Code of Laws, as amended, Bidder has submitted Bid Security as follows in the amount and form required by the Bidding Documents:
___ Bid Bond with Power of Attorney ___ Electronic Bid Bond ___ Cashier's Check
(Bidder check one)

§ 3. Bidder acknowledges the receipt of the following Addenda to the Bidding Documents and has incorporated the effects of said Addenda into this Bid:

ADDENDUM No: _____

§ 4. Bidder accepts all terms and conditions of the Invitation for Bids, including, without limitation, those dealing with the disposition of Bid Security. Bidder agrees that this Bid, including all Bid Alternates, if any, may not be revoked or withdrawn after the opening of bids, and shall remain open for acceptance for a period of 60 Days following the Bid Date, or for such longer period of time that Bidder may agree to in writing upon request of the Owner.

§ 5. Bidder herewith offers to provide all labor, materials, equipment, tools of trades and labor, accessories, appliances, warranties and guarantees, and to pay all royalties, fees, permits, licenses and applicable taxes necessary to complete the following items of construction work:

§ 6.1 INCREMENTAL PRICE No. 1 WORK (as indicated in the Bidding Documents and generally described as follows):

Work covered by this contract includes furnishing all labor, materials, and equipment necessary to perform the work on the Humanities Office Building RA1 in accordance with the Contract Documents.

Removals: Prior to the application of any new materials, the complete removal and disposal of the existing aggregate surfaced asphalt and fiberglass felt Built-Up Roofing (BUR) assembly (entire roofing assembly is considered ACM) and existing Lightweight Insulating Concrete (LWIC) down to the existing structural concrete decking; Remove and store for reinstallation the existing lightning protection system components. Note: *There are three Verizon telephone towers located on the roof with coaxial cables running from the tower frames across sleeper mounted concrete ballasted conduit supports. These conduits penetrate the roof in a single conduit roof penetration housing. The conduits will be raised in a temporary condition over the existing roofing membrane and the conduit supports removed and stored for reuse by Verizon contract employees prior to reroofing construction start. Roofing contractor is to provide wood blocking within the new roofing assembly to finish flush with the new insulation height below the conduit support sleepers. After the roofing system assembly is complete, Verizon Contractors will reposition their conduit and concrete conduit support sleepers over walkpads provided by the roofing contractor that are located over wood blocking buried in the system.*

Preparations: After removals are complete, prepare the substrate LWIC decking to include repairs to the existing decking as necessary, and the new installation of mechanically attached wood blocking and safety anchors.

Installations: Upon completion of all removals and preparations, install new base sheet, tapered insulation, insulation cover board, modified asphalt base ply, modified asphalt cap sheet, metal, bituminous & resin flashings, metal coping and associated miscellaneous work, as specified herein.

_____, which sum is hereafter called Incremental PRICE #1.
(enter INCREMENTAL BID #1 in figures only)