

#### **Project Manual**

# University of South Carolina Athletic Village Tennis Complex Addition

Columbia, South Carolina

State Project Number H27-6102-MJ Architect's Project Number 12.130.09

Re-Bid Set

June 5, 2014

Quackenbusharchitects.com

olina Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### PROJECT DIRECTORY

Owner University of South Carolina

Facilities Planning & Construction 743 Greene Street, Columbia, SC 29208 (803) 777-3126 Fax (803) 777-8739

Architect-of-Record Quackenbush Architects + Planners

1217 Hampton Street Columbia, SC 29201

(803) 771-2999 Fax (803) 788-2858 Marc W. Warren, AIA, LEED AP BD + C

**Project Consultants**:

Civil Engineer RB Todd Consulting Engineers

7436 Broad River Road, Suite 212

Irmo SC, 29063 (803) 781-3141

Bruce Todd, P.E., LEED AP BD+C

Structural Engineer Kyzer & Timmerman Structural Engineers

580 Chris Drive

West Columbia, SC 29169

(803) 791-4511 Ken Timmerman, P.E.

Plumbing / Mechanical Swygert & Associates, Ltd.

1315 State Street Cayce, SC 29033 (903) 791-9300

Todd Swygert (Plumbing Engineer)
Bill Livingston (Mechanical Engineer)

Electrical Engineer Belka Engineering Associates, Inc.

7 Clusters Court Columbia, SC 29210 (803) 731-0650 Cliff Stringfield

PROJECT DIRECTORY PD-1

#### SECTION 000100 - PROJECT MANUAL TABLE OF CONTENTS

The complete Project Manual for this project consists of this entire bound volume which is not to be separated for any reason. The Architect and Owner will not be responsible for any assumptions made by a Contractor or Subcontractor who does not receive a complete bound Project Manual containing all sections and documents listed in the Table of Contents.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

The following listed documents comprise the Project Manual for the **USC Tennis Complex Locker Room Addition.** Where numerical sequence of Sections or Divisions is interrupted, such interruptions are intentional.

#### PROJECT MANUAL

**Section No. Section Title** 

#### **DIVISION 00 – BIDDING AND CONTRACT REQUIREMENTS**

#### INTRODUCTORY INFORMATION

Cover Page Project Directory Project Manual Table of Contents

#### **BIDDING REQUIREMENTS**

Invitation to Bids (Request for Advertisement SE-310)

Instructions to Bidders (AIA Document A701 – 1997 Edition)

00201-OSE Standard Supplementary Instructions to Bidders (2011 Ed.)

Bid Bond (AIA Document A310)

**Standard Bid Form** (SE 330, 2011 Edition)

#### **CONTRACTING REQUIREMENTS**

**Standard Form of Agreement between Owner and Contractor** (AIA Document A101-2007 Edition)

**00501-OSE** Standard Modifications to Agreement Between Owner and Contractor AIA A101-201 (2011 Edition)

**General Conditions of the Contract for Construction** (AIA Document A201-2007 Edition)

**00811 – Standard Supplementary Conditions** (2011 Edition) (Supplement to AIA Document A201-2007 Edition General Conditions of the Contract)

**USC Supplemental General Conditions for Construction Projects** 

**Contractor's One Year Guarantee** 

**Performance Bond** (SE-355, 2011 Edition)

**Labor and Material Payment Bond** (SE-357, 2011 Edition)

**Income Tax Credit** (Minority Business)

**Construction Change Order SE-480** 

TABLE OF CONTENTS 000100 - 1

## **DIVISION 1 – GENERAL REQUIREMENTS**

DIVIDIONI	GENERAL REQUIREMENTS
01 10 00	Summary
01 23 00	Alternates
01 25 00	Substitution Procedures
	Substitution Request Form (During Bidding)
01 26 00	Contract Modification Procedures
01 29 00	Payment Procedures
01 31 00	Project Management and Coordination
01 32 00	Construction Progress Documentation
01 33 00	Submittal Procedures
01 40 00	Quality Requirements
	Quality Assurance Plan for Seismic Requirements
	Contractor's Statement of Responsibility Seismic Quality Assurance
	Statement of Special Inspections
01 42 00	References
01 50 00	Temporary Facilities and Controls
01 60 00	Product Requirements
01 73 00	Execution
01 77 00	Closeout Procedures
01 78 23	Operation and Maintenance Data
01 78 39	Project Record Documents

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### **DIVISION 2 – EXISTING CONDITIONS**

02 41 19 Selective Demolition

#### **DIVISION 3 – CONCRETE**

03 30 00 Cast-In-Place Concrete

#### **DIVISION 4 – MASONRY**

04 20 00 Unit Masonry

#### **DIVISION 5 – METALS**

05 12 00 Structural Steel Framing 05 31 00 Steel Decking

#### **DIVISION 6 – WOOD & PLASTICS**

06 41 10 Architectural Casework

## **DIVISION 7 – THERMAL & MOISTURE PROTECTION**

07 11 13	Bituminous Dampproofing
07 21 00	Thermal Insulation
07 24 13	Polymer-Based Exterior Finish System (EIFS and DEFS)
07 26 00	Under Slab Vapor Retarder
07 53 23	Ethylene-Propylene-Diene-Monomer (EPDM) Roofing
07 62 00	Sheet Metal Flashing and Trim
07 92 00	Joint Sealants
07 95 00	Expansion Control

TABLE OF CONTENTS 000100 - 2

#### Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### **DIVISION 8 – DOORS & WINDOWS**

08 11 13	Hollow Metal Doors and Frames
08 14 16	Flush Wood Doors
08 41 13	Aluminum-Framed Entrances and Storefront
08 71 00	Door Hardware
08 80 00	Glazing

#### **DIVISION 9 – FINISHES**

DIVISION 9 – FINISHES		
09 22 16	Non-Structural Metal Framing	
09 2900	Gypsum Board	
09 30 13	Ceramic Tiling	
09 51 23	Acoustic Tile Ceilings	
09 65 13	Resilient Base and Accessories	
09 91 13	Exterior Painting	
09 91 23	Interior Painting	
09 93 00	Staining and Transparent Finishing	

#### **DIVISION 10 – SPECIALTIES**

10 28 13	Toilet, Bath, and Laundry Accessories
10 44 16	Fire Extinguishers

#### **DIVISION 11 – EQUIPMENT**

Not Used

#### **DIVISION 12 – FURNISHINGS**

12 36 61 Simulated Stone Countertops

#### **DIVISION 13 – SPECIAL CONSTRUCTION**

Not Used

#### **DIVISION 14 – CONVEYING SYSTEMS**

Not Used

#### **DIVISION 21 – FIRE SUPPRESSION**

Not Used

#### **DIVISION 22 – PLUMBING**

22 00 10	General Provisions - Plumbing
22 05 00	Plumbing
22 07 00	Plumbing Insulation

#### **DIVISION 23 – HEATING VENTING AND AIR CONDITIONING (HVAC)**

21 1 101011 20	HEITH O VERTING IN E IMM CONDITION OF ON THE
23 00 10	General Provisions - HVAC
23 05 00	Heating, Ventilation, and Air Conditioning
23 07 00	HVAC Insulation

#### **DIVISION 26 – ELECTRICAL**

26 05 00 Basic Electrical Materials and Methods

TABLE OF CONTENTS 000100 - 3

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

26 05 19	Conductors and Cables
26 05 26	Grounding and Bonding
26 05 29	Electrical Supports and Seismic Restraints
26 05 33	Raceways and Boxes
26 05 53	Electrical Identification
26 22 00	Dry-Type Transformers
26 24 16	Panelboards
26 27 26	Wiring Devices
26 28 16	<b>Enclosed Switches and Circuit Breakers</b>
26 51 00	Interior Lighting

#### **DIVISION 27 – COMMUNICATIONS**

Not Used

#### **DIVISION 28 – ELECTRONIC SAFETY AND SECURITY**

Not Used

#### **DIVISION 31 – EARTHWORK**

31 10 00	Site Clearing
31 20 00	Earth Moving
31 31 16	Termite Control

## **DIVISION 32 – EXTERIOR IMPROVEMENTS**

32 13 13 Concrete Paving

**END OF SECTION** 

TABLE OF CONTENTS 000100 - 4

## SE-310 REQUEST FOR ADVERTISEMENT

Rev. 7/20/2011

TE QUEDITORTIE (ERTEDENTET)	
PROJECT NAME: Athletic Village Tennis Complex Addition -	RE-BID
PROJECT NUMBER: <u>H27-6102-MJ</u>	
PROJECT LOCATION: Columbia, South Carolina	
Contractor may be subject to performance appraisal at close of pr	oject
BID SECURITY REQUIRED? Yes 🗵 No 🗌	
PERFORMANCE & PAYMENT BONDS REQUIRED? Yes	s 🛛 No 🗌
CONSTRUCTION COST RANGE: <u>\$800,000.00 to \$900,000.0</u>	
DESCRIPTION OF PROJECT: The project scope consists of 3	
2) on the lower level of the existing tennis complex at the USC A engineering systems. Small & minority business partitipation is e	
nformation including updates from USC's website: www.purcha	
A/E NAME: Quackenbush Architects + Planners	
A/E CONTACT: Marc W. Warren, AIA, LEED AP BD + C	
A/E ADDRESS: Street/PO Box: 1217 Hampton St	
City: Columbia	
State: <u>SC</u> ZIP: <u>29201-</u>	
EMAIL: <a href="mwarren@quackbusharchitects.com">mwarren@quackbusharchitects.com</a>	
TELEPHONE: 803 771-2999	<b>FAX:</b> 803 771-2858
All questions & correspondence concerning this Invitation shall b	e addressed to the A/E.
BIDDING DOCUMENTS/PLANS MAY BE OBTAINED FR	OM: <a href="http://purchasing.sc.edu">http://purchasing.sc.edu</a> , see Facilities/Construction
Solicitations & Awards	
PLAN DEPOSIT AMOUNT: \$0.00 IS DEPOSIT REFUNDA	
Only those Bidding Documents/Plans obtained from the above lis Documents/Plans obtained from any other source at their own risl	
BIDDING DOCUMENTS/PLANS ARE ALSO ON FILE FO	
each plan room or other entity):	
N/A	
<del></del>	
DDE DID CONFEDENCES V. M. N. M. MANDATODI	ZATERDANGERO W. T. N. M.
PRE-BID CONFERENCE? Yes No MANDATORY	<del></del>
DATE: <u>6/12/2014</u> TIME: <u>11:00 AM</u> PLACE: <u>743 Gree</u>	ene Street, Columbia, SC 29208 - Rm 53 - Site Visit to Follow.
AGENCY: University of South Carolina	
NAME OF AGENCY PROCUREMENT OFFICER: Juaquan	a Brookins
ADDRESS: Street/PO Box: 743 Greene Street	
City: Columbia	
State: <u>SC</u> ZIP: <u>29208-</u>	
EMAIL: jbrookin@fmc.sc.edu	FAN, 000 555 5004
TELEPHONE: 803-777-3596	FAX: 803-777-7334
BID CLOSING DATE: 6/26/2014 TIME: 3:00PM LOCATI	ON: 743 Greene Street, Columbia, SC 29208 - Conf Rm 53
BID DELIVERY ADDRESSES:	
HAND-DELIVERY:	MAIL SERVICE:
Attn:	Attn:
USC Facilities Management Center	USC Facilities Management Center
<del>-</del>	<u> </u>
43 Greene Street 743 Greene Street	
Columbia, SC 29208	Columbia, SC 29208
S PROJECT WITHIN AGENCY CONSTRUCTION CERT	IFICATION? (Agency MUST check one) Yes 🗵 No 🗌
	, , , , , , , , , , , , , , , , , , , ,

APPROVED BY (Office of State Engineer):

**DATE:** \_\_\_\_\_

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## **INSTRUCTIONS TO BIDDERS**

INSTRUCTIONS TO BIDDERS is the AIA document A701-2007 Edition, published by the American Institute of Architects, and the attached OSE Form 002011 STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS.

The A701 document is not included, but may be viewed at the Architect's office or purchased from the American Institute of Architects.

**END OF SECTION** 

#### STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

OWNER: <u>University of South Carolina</u> PROJECT NUMBER: H27-6102-MJ

PROJECT NAME: Athletic Village Tennis Complex Addition - RE-BID

PROJECT LOCATION: Columbia, South Carolina

PROCUREMENT OFFICER: Juaquana Brookins

#### 1. STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

- **1.1.** These Standard Supplemental Instructions To Bidders amend or supplement Instructions To Bidders (AIA Document A701-1997) and other provisions of Bidding and Contract Documents as indicated below.
- **1.2.** Compliance with these Standard Supplemental Instructions is required by the Office of State Engineer (OSE) for all State projects when competitive sealed bidding is used as the method of procurement.
- 1.3. All provisions of A701-1997, which are not so amended or supplemented, remain in full force and effect.
- **1.4.** Bidders are cautioned to carefully examine the Bidding and Contract Documents for additional instructions or requirements.

#### 2. MODIFICATIONS TO A701-1997

- **2.1.** *Delete Section 1.1 and insert the following:* 
  - 1.1 Bidding Documents, collectively referred to as the Invitation for Bids, include the Bidding Requirements and the proposed Contract Documents. The Bidding Requirements consist of the Advertisement, Instructions to Bidders (A-701), Supplementary Instructions to Bidders, the bid form (SE-330), the Intent to Award Notice (SE-370), and other sample bidding and contract forms. The proposed Contract Documents consist of the form of Agreement between the Owner and Contractor, Conditions of the Contract (General, Supplementary and other Conditions), Drawings, Specifications, all Addenda issued prior to execution of the Contract, and other documents set forth in the Bidding Documents. Any reference in this document to the Agreement between the Owner and Contractor, AIA Document A101, or some abbreviated reference thereof, shall mean the AIA A101, 2007 Edition as modified by OSE Form 00501 Standard Modification to Agreement Between Owner and Contractor. Any reference in this document to the General Conditions of the Contract for Construction, AIA Document A201, or some abbreviated reference thereof, shall mean the AIA A201, 2007 Edition as modified by OSE Form 00811 Standard Supplementary Conditions.
- **2.2.** In Section 1.8, delete the words "and who meets the requirements set forth in the Bidding Documents".
- **2.3.** In Section 2.1, delete the word "making" and substitute the word "submitting."
- **2.4.** *In Section 2.1.1:*

After the words "Bidding Documents," delete the word "or" and substitute the word "and."

*Insert the following at the end of this section:* 

Bidders are expected to examine the Bidding Documents and Contract Documents thoroughly and should request an explanation of any ambiguities, discrepancies, errors, omissions, or conflicting statements. Failure to do so will be at the Bidder's risk. Bidder assumes responsibility for any patent ambiguity that Bidder does not bring to the Owner's attention prior to bid opening.

**2.5.** In Section 2.1.3, insert the following after the term "Contract Documents" and before the period: and accepts full responsibility for any pre-bid existing conditions that would affect the Bid that could have been ascertained by a site visit. As provided in Regulation 19-445.2042(B), A bidder's failure to attend an advertised pre-bid conference will not excuse its responsibility for estimating properly the difficulty and cost of successfully performing the work, or for proceeding to successfully perform the work without additional expense to the State.

#### STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

**2.6.** *Insert the following Sections* 2.2 *through* 2.6:

#### 2.2 CERTIFICATION OF INDEPENDENT PRICE DETERMINATION

GIVING FALSE, MISLEADING, OR INCOMPLETE INFORMATION ON THIS CERTIFICATION MAY RENDER YOU SUBJECT TO PROSECUTION UNDER SECTION 16-9-10 OF THE SOUTH CAROLINA CODE OF LAWS AND OTHER APPLICABLE LAWS.

- (a) By submitting an bid, the bidder certifies that—
  - (1) The prices in this bid have been arrived at independently, without, for the purpose of restricting competition, any consultation, communication, or agreement with any other bidder or competitor relating to—
    - (i) Those prices;
    - (ii) The intention to submit an bid; or
    - (iii) The methods or factors used to calculate the prices offered.
  - (2) The prices in this bid have not been and will not be knowingly disclosed by the bidder, directly or indirectly, to any other bidder or competitor before bid opening (in the case of a sealed bid solicitation) or contract award (in the case of a negotiated solicitation) unless otherwise required by law; and
  - (3) No attempt has been made or will be made by the bidder to induce any other concern to submit or not to submit an bid for the purpose of restricting competition.
- (b) Each signature on the bid is considered to be a certification by the signatory that the signatory—
  - (1) Is the person in the bidder's organization responsible for determining the prices being offered in this bid, and that the signatory has not participated and will not participate in any action contrary to paragraphs (a)(1) through (a)(3) of this certification; or
  - (2)(i) Has been authorized, in writing, to act as agent for the bidder's principals in certifying that those principals have not participated, and will not participate in any action contrary to paragraphs (a)(1) through (a)(3) of this certification [As used in this subdivision (b)(2)(i), the term "principals" means the person(s) in the bidder's organization responsible for determining the prices offered in this bid];
  - (ii) As an authorized agent, does certify that the principals referenced in subdivision (b)(2)(i) of this certification have not participated, and will not participate, in any action contrary to paragraphs (a)(1) through (a)(3) of this certification; and
  - (iii) As an agent, has not personally participated, and will not participate, in any action contrary to paragraphs (a)(1) through (a)(3) of this certification.
- (c) If the bidder deletes or modifies paragraph (a)(2) of this certification, the bidder must furnish with its offer a signed statement setting forth in detail the circumstances of the disclosure.

#### 2.3 DRUG FREE WORKPLACE

By submitting a bid, the Bidder certifies that Bidder will maintain a drug free workplace in accordance with the requirements of Title 44, Chapter 107 of South Carolina Code of Laws, as amended.

#### 2.4 CERTIFICATION REGARDING DEBARMENT AND OTHER RESPONSIBILITY MATTERS

- (a) (1) By submitting an Bid, Bidder certifies, to the best of its knowledge and belief, that-
  - (i) Bidder and/or any of its Principals-
    - (A) Are not presently debarred, suspended, proposed for debarment, or declared ineligible for the award of contracts by any state or federal agency;
    - (B) Have not, within a three-year period preceding this bid, been convicted of or had a civil judgment rendered against them for: commission of fraud or a criminal offense in

#### STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

connection with obtaining, attempting to obtain, or performing a public (Federal, state, or local) contract or subcontract; violation of Federal or state antitrust statutes relating to the submission of bids; or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, tax evasion, or receiving stolen property; and

- (C) Are not presently indicted for, or otherwise criminally or civilly charged by a governmental entity with, commission of any of the offenses enumerated in paragraph (a)(1)(i)(B) of this provision.
- (ii) Bidder has not, within a three-year period preceding this bid, had one or more contracts terminated for default by any public (Federal, state, or local) entity.
- (2) "Principals," for the purposes of this certification, means officers; directors; owners; partners; and, persons having primary management or supervisory responsibilities within a business entity (e.g., general manager; plant manager; head of a subsidiary, division, or business segment, and similar positions).
- (b) Bidder shall provide immediate written notice to the Procurement Officer if, at any time prior to contract award, Bidder learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- (c) If Bidder is unable to certify the representations stated in paragraphs (a)(1), Bid must submit a written explanation regarding its inability to make the certification. The certification will be considered in connection with a review of the Bidder's responsibility. Failure of the Bidder to furnish additional information as requested by the Procurement Officer may render the Bidder nonresponsible.
- (d) Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render, in good faith, the certification required by paragraph (a) of this provision. The knowledge and information of an Bidder is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- (e) The certification in paragraph (a) of this provision is a material representation of fact upon which reliance was placed when making award. If it is later determined that the Bidder knowingly or in bad faith rendered an erroneous certification, in addition to other remedies available to the State, the Procurement Officer may terminate the contract resulting from this solicitation for default.

#### 2.5 ETHICS CERTIFICATE

By submitting a bid, the bidder certifies that the bidder has and will comply with, and has not, and will not, induce a person to violate Title 8, Chapter 13 of the South Carolina Code of Laws, as amended (ethics act). The following statutes require special attention: Section 8-13-700, regarding use of official position for financial gain; Section 8-13-705, regarding gifts to influence action of public official; Section 8-13-720, regarding offering money for advice or assistance of public official; Sections 8-13-755 and 8-13-760, regarding restrictions on employment by former public official; Section 8-13-775, prohibiting public official with economic interests from acting on contracts; Section 8-13-790, regarding recovery of kickbacks; Section 8-13-1150, regarding statements to be filed by consultants; and Section 8-13-1342, regarding restrictions on contributions by contractor to candidate who participated in awarding of contract. The state may rescind any contract and recover all amounts expended as a result of any action taken in violation of this provision. If contractor participates, directly or indirectly, in the evaluation or award of public contracts, including without limitation, change orders or task orders regarding a public contract, contractor shall, if required by law to file such a statement, provide the statement required by Section 8-13-1150 to the procurement officer at the same time the law requires the statement to be filed.

#### 2.6 RESTRICTIONS APPLICABLE TO BIDDERS & GIFTS

Violation of these restrictions may result in disqualification of your bid, suspension or debarment, and may constitute a violation of the state Ethics Act. (a) After issuance of the solicitation, bidder agrees not to discuss this procurement activity in any way with the Owner or its employees, agents or officials. All communications must be solely with the Procurement Officer. This restriction may be lifted by express written permission from the Procurement Officer. This restriction expires once a contract has been formed. (b) Unless otherwise approved in writing by the Procurement

### STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

Officer, bidder agrees not to give anything to the Owner, any affiliated organizations, or the employees, agents or officials of either, prior to award. (c) Bidder acknowledges that the policy of the State is that a governmental body should not accept or solicit a gift, directly or indirectly, from a donor if the governmental body has reason to believe the donor has or is seeking to obtain contractual or other business or financial relationships with the governmental body. Regulation 19-445.2165(C) broadly defines the term donor.

#### **2.7.** *Delete Section 3.1.1 and substitute the following:*

**3.1.1** Bidders may obtain complete sets of the Bidding Documents from the issuing office designated in the Advertisement in the number and for the deposit sum, if any, stated therein. If so provided in the Advertisement, the deposit will be refunded to all plan holders who return the Bidding Documents in good condition within ten days after receipt of Bids. The cost of replacement of missing or damaged documents will be deducted from the deposit. A Bidder receiving a Contract award may retain the Bidding Documents and the Bidder's deposit will be refunded.

- **2.8.** Delete the language of Section 3.1.2 and insert the word "Reserved."
- 2.9. In Section 3.1.4, delete the words "and Architect may make" and substitute the words "has made."
- **2.10.** Insert the following Section 3.1.5

**3.1.5** All persons obtaining Bidding Documents from the issuing office designated in the Advertisement shall provide that office with Bidder's contact information to include the Bidder's name, telephone number, mailing address, and email address.

#### **2.11.** *In Section 3.2.2:*

Delete the words "and Sub-bidders"

Delete the word "seven" and substitute the word "ten"

#### **2.12.** *In Section 3.2.3:*

In the first Sentence, insert the word "written" before the word "Addendum."

*Insert the following at the end of the section:* 

As provided in Regulation 19-445.2042(B), nothing stated at the pre-bid conference shall change the Bidding Documents unless a change is made by written Addendum.

#### **2.13.** *Insert the following at the end of Section 3.3.1:*

Reference in the Bidding Documents to a designated material, product, thing, or service by specific brand or trade name followed by the words "or equal" and "or approved equal" shall be interpreted as establishing a standard of quality and shall not be construed as limiting competition.

#### **2.14.** *Delete Section 3.3.2 and substitute the following:*

**3.3.2** No request to substitute materials, products, or equipment for materials, products, or equipment described in the Bidding Documents and no request for addition of a manufacturer or supplier to a list of approved manufacturers or suppliers in the Bidding Documents will be considered prior to receipt of Bids unless written request for approval has been received by the Architect at least ten days prior to the date for receipt of Bids established in the Invitation for Bids. Any subsequent extension of the date for receipt of Bids by addendum shall not extend the date for receipt of such requests unless the addendum so specifies. Such requests shall include the name of the material or equipment for which it is to be substituted and a complete description of the proposed substitution including drawings, performance and test data, and other information necessary for an evaluation. A statement setting forth changes in other materials, equipment or other portions of the Work, including changes in the work of other contracts that incorporation of the proposed substitution would require, shall be included. The burden of proof of the merit of the proposed substitution is upon the proposer. The Architect's decision of approval or disapproval of a proposed substitution shall be final.

#### **2.15.** *Delete Section 3.4.3 and substitute the following:*

**3.4.3** Addenda will be issued no later than 120 hours prior to the time for receipt of Bids except an Addendum withdrawing the request for Bids or one which includes postponement of the date for receipt of Bids.

### STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

- **2.16.** *Insert the following Sections 3.4.5 and 3.4.6:* 
  - **3.4.5** When the date for receipt of Bids is to be postponed and there is insufficient time to issue a written Addendum prior to the original Bid Date, Owner will notify prospective Bidders by telephone or other appropriate means with immediate follow up with a written Addendum. This Addendum will verify the postponement of the original Bid Date and establish a new Bid Date. The new Bid Date will be no earlier than the fifth (5th) calendar day after the date of issuance of the Addendum postponing the original Bid Date.
  - **3.4.6.** If an emergency or unanticipated event interrupts normal government processes so that bids cannot be received at the government office designated for receipt of bids by the exact time specified in the solicitation, the time specified for receipt of bids will be deemed to be extended to the same time of day specified in the solicitation on the first work day on which normal government processes resume. In lieu of an automatic extension, an Addendum may be issued to reschedule bid opening. If state offices are closed at the time a pre-bid or pre-proposal conference is scheduled, an Addendum will be issued to reschedule the conference. Useful information may be available at: http://www.scemd.org/scgovweb/weather alert.html
- **2.17.** In Section 4.1.1, delete the word "forms" and substitute the words "SE-330 Bid Form."
- **2.18.** *Delete Section 4.1.2 and substitute the following:* 
  - **4.1.2** Any blanks on the bid form to be filled in by the Bidder shall be legibly executed in a non-erasable medium. Bids shall be signed in ink or other indelible media.
- **2.19.** *Delete Section 4.1.3 and substitute the following:* 
  - **4.1.3** Sums shall be expressed in figures.
- **2.20.** *Insert the following at the end of Section 4.1.4:*

Bidder shall not make stipulations or qualify his bid in any manner not permitted on the bid form. An incomplete Bid or information not requested that is written on or attached to the Bid Form that could be considered a qualification of the Bid, may be cause for rejection of the Bid.

- **2.21.** *Delete Section 4.1.5 and substitute the following:* 
  - **4.1.5** All requested Alternates shall be bid. The failure of the bidder to indicate a price for an Alternate shall render the Bid non-responsive. Indicate the change to the Base Bid by entering the dollar amount and marking, as appropriate, the box for "ADD TO" or "DEDUCT FROM". If no change in the Base Bid is required, enter "ZERO" or "No Change." For add alternates to the base bid, Subcontractor(s) listed on page BF-2 of the Bid Form to perform Alternate Work may be used for both Alternates and Base Bid Work if Alternates are accepted.
- **2.22.** *Delete Section 4.1.6 and substitute the following:* 
  - **4.1.6** Pursuant to Title 11, Chapter 35, Section 3020(b)(i) of the South Carolina Code of Laws, as amended, Section 7 of the Bid Form sets forth a list of subcontractor specialties for which Bidder is required to list only the subcontractors Bidder will use to perform the work of each listed specialty. Bidder must follow the Instructions in the Bid Form for filling out this section of the Bid Form. Failure to properly fill out Section 7 may result in rejection of Bidder's bid as non-responsive.
- **2.23.** *Delete Section 4.1.7 and substitute the following:* 
  - **4.1.7** Each copy of the Bid shall state the legal name of the Bidder and the nature of legal form of the Bidder. Each copy shall be signed by the person or persons legally authorized to bind the Bidder to a contract. A Bid submitted by an agent shall have a current power of attorney attached certifying the agent's authority to bind the Bidder.
- **2.24.** *Delete Section 4.2.1 and substitute the following:* 
  - **4.2.1** If required by the Invitation for Bids, each Bid shall be accompanied by a bid security in an amount of not less than five percent of the Base Bid. The bid security shall be a bid bond or a certified cashier's check. The Bidder pledges to enter into a Contract with the Owner on the terms stated in the Bid and will, if required, furnish bonds covering the faithful performance of the Contract and payment of all obligations arising thereunder. Should the Bidder refuse to enter into such Contract or fail to furnish such bonds if required, the amount of the bid security shall be forfeited to the Owner as liquidated damages, not as a penalty.

### STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

#### **2.25.** *Delete Section 4.2.2 and substitute the following:*

**4.2.2** If a surety bond is required, it shall be written on AIA Document A310, Bid Bond, and the attorney-in-fact who executes the bond on behalf of the surety shall affix to the bond a certified and current copy of the power of attorney. The bid bond shall:

- .1 Be issued by a surety company licensed to do business in South Carolina;
- .2 Be issued by a surety company having, at a minimum, a "Best Rating" of "A" as stated in the most current publication of "Best's Key Rating Guide, Property-Casualty", which company shows a financial strength rating of at least five (5) times the contract price.
- .3 Be enclosed in the bid envelope at the time of Bid Opening, either in paper copy or as an electronic bid bond authorization number provided on the Bid Form and issued by a firm or organization authorized by the surety to receive, authenticate and issue binding electronic bid bonds on behalf the surety.

#### **2.26.** *Delete Section 4.2.3 and substitute the following:*

**4.2.3** By submitting a bid bond via an electronic bid bond authorization number on the Bid Form and signing the Bid Form, the Bidder certifies that an electronic bid bond has been executed by a Surety meeting the standards required by the Bidding Documents and the Bidder and Surety are firmly bound unto the State of South Carolina under the conditions provided in this Section 4.2.

#### **2.27.** *Insert the following Section 4.2.4:*

**4.2.4** The Owner will have the right to retain the bid security of Bidders to whom an award is being considered until either (a) the Contract has been executed and performance and payment bonds, if required, have been furnished, or (b) the specified time has elapsed so that Bids may be withdrawn or (c) all Bids have been rejected.

#### **2.28.** *Delete Section 4.3.1 and substitute the following:*

**4.3.1** All copies of the Bid, the bid security, if any, and any other documents required to be submitted with the Bid shall be enclosed in a sealed opaque envelope. The envelope shall, unless hand delivered by the Bidder, be addressed to the Owner's designated purchasing office as shown in the Invitation for Bids. The envelope shall be identified with the Project name, the Bidder's name and address and, if applicable, the designated portion of the Work for which the Bid is submitted. If the Bid is sent by mail or special delivery service (UPS, Federal Express, etc.), the envelope should be labeled "BID ENCLOSED" on the face thereof. Bidders hand delivering their Bids shall deliver Bids to the place of the Bid Opening as shown in the Invitation for Bids. Whether or not Bidders attend the Bid Opening, they shall give their Bids to the Owner's procurement officer or his/her designee as shown in the Invitation for Bids prior to the time of the Bid Opening.

#### **2.29.** *Insert the following Section 4.3.6 and substitute the following:*

**4.3.5** The official time for receipt of Bids will be determined by reference to the clock designated by the Owner's procurement officer or his/her designee. The procurement officer conducting the Bid Opening will determine and announce that the deadline has arrived and no further Bids or bid modifications will be accepted. All Bids and bid modifications in the possession of the procurement officer at the time the announcement is completed will be timely, whether or not the bid envelope has been date/time stamped or otherwise marked by the procurement officer.

#### **2.30.** *Delete Section 4.4.2 and substitute the following:*

**4.4.2** Prior to the time and date designated for receipt of Bids, a Bid submitted may be withdrawn in person or by written notice to the party receiving Bids at the place designated for receipt of Bids. Withdrawal by written notice shall be in writing over the signature of the Bidder.

#### **2.31.** *In Section 5.1, delete everything following the caption "OPENING OF BIDS" and substitute the following:*

**5.1.1** Bids received on time will be publicly opened and will be read aloud. Owner will not read aloud Bids that Owner determines, at the time of opening, to be non-responsive.

- 5.1.2 At bid opening, Owner will announce the date and location of the posting of the Notice of Intended Award.
- **5.1.3** Owner will send a copy of the final Bid Tabulation to all Bidders within ten (10) working days of the Bid Opening.

#### STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

- **5.1.4** If Owner determines to award the Project, Owner will, after posting a Notice of Intended Award, send a copy of the Notice to all Bidders.
- **5.1.5** If only one Bid is received, Owner will open and consider the Bid.
- **2.32.** In Section 5.2, insert the section number "5.2.1" before the words of the "The Owner" at the beginning of the sentence.
- **2.33.** *Insert the following Sections 5.2.2 and 5.2.3:* 
  - **5.2.2** The reasons for which the Owner will reject Bids include, but are not limited to:
    - .1 Failure by a Bidder to be represented at a Mandatory Pre-Bid Conference or site visit;
    - **.2** Failure to deliver the Bid on time:
    - .3 Failure to comply with Bid Security requirements, except as expressly allowed by law;
    - .4 Listing an invalid electronic Bid Bond authorization number on the bid form;
    - .5 Failure to Bid an Alternate, except as expressly allowed by law;
    - **.6** Failure to list qualified Subcontractors as required by law;
    - .7 Showing any material modification(s) or exception(s) qualifying the Bid;
    - .8 Faxing a Bid directly to the Owner or their representative; or
    - **.9** Failure to include a properly executed Power-of-Attorney with the bid bond.
  - **5.2.3** The Owner may reject a Bid as nonresponsive if the prices bid are materially unbalanced between line items or sub-line items. A bid is materially unbalanced when it is based on prices significantly less than cost for some work and prices which are significantly overstated in relation to cost for other work, and if there is a reasonable doubt that the bid will result in the lowest overall cost to the Owner even though it may be the low evaluated bid, or if it is so unbalanced as to be tantamount to allowing an advance payment.
- **2.34.** *Delete Section 6.1 and substitute the following:*

#### 6.1 CONTRACTOR'S RESPONSIBILITY

Owner will make a determination of Bidder's responsibility before awarding a contract. Bidder shall provide all information and documentation requested by the Owner to support the Owner's evaluation of responsibility. Failure of Bidder to provide requested information is cause for the Owner, at its option, to determine the Bidder to be non-responsible

- **2.35.** Delete the language of Section 6.2 and insert the word "Reserved."
- **2.36.** Delete the language of Sections 6.3.2, 6.3.3, and 6.3.4 and insert the word "Reserved" after each Section Number.
- **2.37.** Insert the following Section 6.4

#### **6.4 CLARIFICATION**

Pursuant to Section 11-35-1520(8), the Procurement Officer may elect to communicate with a Bidder after opening for the purpose of clarifying either the Bid or the requirements of the Invitation for Bids. Such communications may be conducted only with Bidders who have submitted a Bid which obviously conforms in all material aspects to the Invitation for Bids and only in accordance with Appendix D (Paragraph A(6)) to the Manual for Planning and Execution of State Permanent Improvement, Part II. Clarification of a Bid must be documented in writing and included with the Bid. Clarifications may not be used to revise a Bid or the Invitation for Bids. [Section 11-35-1520(8); R.19-445.2080]

- **2.38.** *Delete Section 7.1.2 and substitute the following:* 
  - **7.1.2** The performance and payment bonds shall conform to the requirements of Section 11.4 of the General Conditions of the Contract. If the furnishing of such bonds is stipulated in the Bidding Documents, the cost shall be included in the Bid.
- **2.39.** Delete the language of Section 7.1.3 and insert the word "Reserved."
- **2.40.** In Section 7.2, insert the words "CONTRACT, CERTIFICATES OF INSURANCE" into the caption after the word "Delivery."

#### STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

#### **2.41.** *Delete Section 7.2.1 and substitute the following:*

**7.2.1** After expiration of the protest period, the Owner will tender a signed Contract for Construction to the Bidder and the Bidder shall return the fully executed Contract for Construction to the Owner within seven days thereafter. The Bidder shall deliver the required bonds and certificate of insurance to the Owner not later than three days following the date of execution of the Contract. Failure to deliver these documents as required shall entitle the Owner to consider the Bidder's failure as a refusal to enter into a contract in accordance with the terms and conditions of the Bidder's Bid and to make claim on the Bid Security for re-procurement cost.

#### **2.42.** Delete the language of Section 7.2.2 and insert the word "Reserved."

#### **2.43.** *Delete the language of Article 8 and insert the following:*

Unless otherwise required in the Bidding Documents, the Agreement for the Work will be written on South Carolina Modified AIA Document A101, 2007, Standard Form of Agreement Between Owner and Contractor as modified by OSE Form 00501 – Standard Modification to Agreement Between Owner and Contractor.

#### **2.44.** *Insert the following Article 9:*

#### **ARTICLE 9 MISCELLANEOUS**

# 9.1 NONRESIDENT TAXPAYER REGISTRATION AFFIDAVIT INCOME TAX WITHHOLDING IMPORTANT TAX NOTICE - NONRESIDENTS ONLY

Withholding Requirements for Payments to Nonresidents: Section 12-8-550 of the South Carolina Code of Laws requires persons hiring or contracting with a nonresident conducting a business or performing personal services of a temporary nature within South Carolina to withhold 2% of each payment made to the nonresident. The withholding requirement does not apply to (1) payments on purchase orders for tangible personal property when the payments are not accompanied by services to be performed in South Carolina, (2) nonresidents who are not conducting business in South Carolina, (3) nonresidents for contracts that do not exceed \$10,000 in a calendar year, or (4) payments to a nonresident who (a) registers with either the S.C. Department of Revenue or the S.C. Secretary of State and (b) submits a Nonresident Taxpayer Registration Affidavit - Income Tax Withholding, Form I-312 to the person letting the contract.

For information about other withholding requirements (e.g., employee withholding), contact the Withholding Section at the South Carolina Department of Revenue at 803-898-5383 or visit the Department's website at: www.sctax.org

This notice is for informational purposes only. This Owner does not administer and has no authority over tax issues. All registration questions should be directed to the License and Registration Section at 803-898-5872 or to the South Carolina Department of Revenue, Registration Unit, Columbia, S.C. 29214-0140. All withholding questions should be directed to the Withholding Section at 803-898-5383.

PLEASE SEE THE "NONRESIDENT TAXPAYER REGISTRATION AFFIDAVIT INCOME TAX WITHHOLDING" FORM (FORM NUMBER I-312) LOCATED AT: <a href="http://www.sctax.org/Forms+and+Instructions/withholding/default.htm">http://www.sctax.org/Forms+and+Instructions/withholding/default.htm</a>.

#### 9.2 CONTRACTOR LICENSING

Contractors and Subcontractors listed in Section 7 of the Bid Form who are required by the South Carolina Code of Laws to be licensed, must be licensed at the time of bidding.

#### 9.3 SUBMITTING CONFIDENTIAL INFORMATION

For every document Bidder submits in response to or with regard to this solicitation or request, Bidder must separately mark with the word "CONFIDENTIAL" every page, or portion thereof, that Bidder contends contains information that is exempt from public disclosure because it is either (a) a trade secret as defined in Section 30-4-40(a)(1), or (b) privileged & confidential, as that phrase is used in Section 11-35-410. For every document Bidder submits in response to or with regard to this solicitation or request, Bidder must separately mark with the words "TRADE SECRET" every page, or portion thereof, that Bidder contends contains a trade secret as that term is defined by Section 39-8-20 of the Trade Secrets Act. For every document Bidder submits in response to or with regard to this solicitation or request, Bidder must separately mark with the word "PROTECTED" every page, or portion thereof, that Bidder contends is protected by Section 11-35-1810. All markings must be conspicuous; use color, bold, underlining, or some other method in order to conspicuously distinguish the mark from the other text. Do not mark your entire bid as confidential, trade secret, or protected! If your bid, or any part thereof, is improperly marked as confidential or trade

#### STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

secret or protected, the State may, in its sole discretion, determine it nonresponsive. If only portions of a page are subject to some protection, do not mark the entire page. By submitting a response to this solicitation, Bidder (1) agrees to the public disclosure of every page of every document regarding this solicitation or request that was submitted at any time prior to entering into a contract (including, but not limited to, documents contained in a response, documents submitted to clarify a response, & documents submitted during negotiations), unless the page is conspicuously marked "TRADE SECRET" or "CONFIDENTIAL" or "PROTECTED", (2) agrees that any information not marked, as required by these bidding instructions, as a "Trade Secret" is not a trade secret as defined by the Trade Secrets Act, & (3) agrees that, notwithstanding any claims or markings otherwise, any prices, commissions, discounts, or other financial figures used to determine the award, as well as the final contract amount, are subject to public disclosure. In determining whether to release documents, the State will detrimentally rely on Bidders's marking of documents, as required by these bidding instructions, as being either "Confidential" or "Trade Secret" or "PROTECTED". By submitting a response, Bidder agrees to defend, indemnify & hold harmless the State of South Carolina, its officers & employees, from every claim, demand, loss, expense, cost, damage or injury, including attorney's fees, arising out of or resulting from the State withholding information that Bidder marked as "confidential" or "trade secret" or "PROTECTED".

#### 9.4 POSTING OF INTENT TO AWARD

Notice of Intent to Award, SE-370, will be posted at the following location:

Room or Area of Posting: Lobby

**Building Where Posted:** <u>Facilities Management Center</u> **Address of Building:** 743 Greene St. Columbia, SC 29208

WEB site address (if applicable): <a href="http://www.purchasing.sc.edu">http://www.purchasing.sc.edu</a> (see "Facilities/Construction Solicitation/Awards)

Posting date will be announced at bid opening. In addition to posting the notice, the Owner will promptly send all responsive bidders a copy of the notice of intent to award and the final bid tabulation

#### 9.5 PROTEST OF SOLICITATION OR AWARD

Any prospective bidder, offeror, contractor, or subcontractor who is aggrieved in connection with the solicitation of a contract shall protest within fifteen days of the date of issuance of the applicable solicitation document at issue. Any actual bidder, offeror, contractor, or subcontractor who is aggrieved in connection with the intended award or award of a contract shall protest within ten days of the date notification of intent to award is posted in accordance with Title 11, Chapter 35, Section 4210 of the South Carolina Code of Laws, as amended. A protest shall be in writing, shall set forth the grounds of the protest and the relief requested with enough particularity to give notice of the issues to be decided, and must be received by the State Engineer within the time provided.

Any protest must be addressed to the CPO, Office of State Engineer, and submitted in writing:

- (a) by email to protest-ose@mmo.sc.gov,
- (b) by facsimile at 803-737-0639, or
- (c) by post or delivery to 1201 Main Street, Suite 600, Columbia, SC 29201.

By submitting a protest to the foregoing email address, you (and any person acting on your behalf) consent to receive communications regarding your protest (and any related protests) at the e-mail address from which you sent your protest.

#### 9.6 SOLICITATION INFORMATION FROM SOURCES OTHER THAN OFFICIAL SOURCE

South Carolina Business Opportunities (SCBO) is the official state government publication for State of South Carolina solicitations. Any information on State agency solicitations obtained from any other source is unofficial and any reliance placed on such information is at the bidder's sole risk and is without recourse under the South Carolina Consolidated Procurement Code.

#### 9.7 BUILDER'S RISK INSURANCE

Bidder's are directed to Article 11.3 of the South Carolina Modified AIA Document A201, 2007 Edition, which, unless provided otherwise in the bid documents, requires the contractor to provide builder's risk insurance on the project.

#### STANDARD SUPPLEMENTAL INSTRUCTIONS TO BIDDERS

#### 9.8 TAX CREDIT FOR SUBCONTRACTING WITH MINORITY FIRMS

Pursuant to Section 12-6-3350, taxpayers, who utilize certified minority subcontractors, may take a tax credit equal to 4% of the payments they make to said subcontractors. The payments claimed must be based on work performed directly for a South Carolina state contract. The credit is limited to a maximum of fifty thousand dollars annually. The taxpayer is eligible to claim the credit for 10 consecutive taxable years beginning with the taxable year in which the first payment is made to the subcontractor that qualifies for the credit. After the above ten consecutive taxable years, the taxpayer is no longer eligible for the credit. The credit may be claimed on Form TC-2, "Minority Business Credit." A copy of the subcontractor's certificate from the Governor's Office of Small and Minority Business (OSMBA) is to be attached to the contractor's income tax return. Taxpayers must maintain evidence of work performed for a State contract by the minority subcontractor. Questions regarding the tax credit and how to file are to be referred to: SC Department of Revenue, Research and Review, Phone: (803) 898-5786, Fax: (803) 898-5888. The subcontractor must be certified as to the criteria of a "Minority Firm" by the Governor's Office of Small and Minority Business Assistance (OSMBA). Certificates are issued to subcontractors upon successful completion of the certification process. Questions regarding subcontractor certification are to be referred to: Governor's Office of Small and Minority Business Assistance, Phone: (803) 734-0657, Fax: (803) 734-2498. Reference: SC §11-35-5010 – Definition for Minority Subcontractor & SC §11-35-5230 (B) – Regulations for Negotiating with State Minority Firms.

#### § 9.9 OTHER SPECIAL CONDITIONS OF THE WORK

#### 9.9.1. BID DOCUMENT DISTRIBUTION:

A. The documents in "PDF" format will be posted at http://purchasing.sc.edu under Facilities / Construction
Solicitations & Awards. All addenda will also be posted on this website. Digital copies of the documents on websites
other than this are not legitimate and not authorized. Bidders using alternate websites to access drawings accept full
responsibility for any differences. Hardcopies of documents will not be distributed. All bidders are advised that
review of partial sets of documents is not recommended and bidders will be responsible for any discrepancies which
might have been avoided had a full set of documents been reviewed.

B. Two (2) sets of hardcopies will be provided to the successful bidder.

9.9.2. The "Substitution Request Form" (at the end of Section 012500) to request approval of "equal" products for
specific products listed.
<u>None</u>
END OF DOCUMENT

## BID BOND

BID BOND is the AIA document A310, latest edition, published by the American Institute of Architects.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

The A310 document is not included, but may be viewed at the Architect's office or purchased from the American Institute of Architects.

END OF SECTION

BID BOND 1

# $\begin{array}{c} \textbf{SE-330} - \textbf{LUMP SUM BID} \\ \textbf{BID FORM} \end{array}$

Bidders shall submit bids on only Bid Form SE-330.

BID SUBMITTED	BY:	
	(Bidder's Name)	
BID SUBMITTED	TO: University of Sou	uth Carolina
	(Owner's Name)	
FOR PROJECT:	PROJECT NAME	Athletic Village Tennis Complex Addition - RE-BID
	PROJECT NUMBER	R <u>H27-6102-MJ</u>
<u>OFFER</u>		
above-named Project with the Owner on the Bidding Documenter terms and concess 2. Pursuant to Section of the terms in the amounter terms in the amounter terms.	t, the undersigned Bide he terms included in the ments, for the prices and ditions of the Bidding E tion 11-32-3030(1) of the	the SC Code of Laws, as amended, Bidder has submitted Bid Security as the Bidding Documents:
	•	r check one)
§ 3. Bidder acknowl effects of said Adder ADDENDUM No:_	•	e following Addenda to the Bidding Documents and has incorporated the
§ 4. Bidder accepts with the disposition revoked or withdray	of Bid Security. Bidde wn after the opening of	ns of the Invitation for Bids, including, without limitation, those dealing der agrees that this Bid, including all Bid Alternates, if any, may not be of bids, and shall remain open for acceptance for a period of <u>60</u> Days reperiod of time that Bidder may agree to in writing upon request of the
appliances, warrantie	-	all labor, materials, equipment, tools of trades and labor, accessories, to pay all royalties, fees, permits, licenses and applicable taxes necessary etion work:
§ 6.1 BASE BID W	ORK_(as indicated in th	he Bidding Documents and generally described as follows): The project scope
consists of 5 new str	uctures on the lower le	vel of the existing tennis complex at the USC Athletics Village, including
exterior wall constru	ction and various interi	ior spaces with all associated engineering.,
(Bidder - in	nsert Base Bid Amount o	, which sum is hereafter called the Base Bid.

## SE-330 – LUMP SUM BID BID FORM

§ 6.2 BID ALTERNATES - as indicated in the Bidding Documents and generally described as follows:
<u>ALTERNATE # 1</u> (Brief Description): <u>Training Room Building from above the floor slab to the new construction</u>
roof above including interior finishes. All work below and within the floor slab including plumbing and electrical
infrastructure shall be included in the base bid.
☐ ADD TO or ☐ DEDUCT FROM BASE BID:
(Bidder to Mark appropriate box to clearly indicate the price adjustment offered for each alternate)
<u>ALTERNATE # 2</u> (Brief Description): <u>Meeting Room Building from above the floor slab to the new construction</u>
roof above including interior finishes. All work below and within the floor slab including plumbing and electrical
infrastructure shall be included in the base bid.
☐ ADD TO or ☐ DEDUCT FROM BASE BID:
(Bidder to Mark appropriate box to clearly indicate the price adjustment offered for each alternate)
ALTERNATE # 3 (Brief Description):
☐ ADD TO or ☐ DEDUCT FROM BASE BID:
(Bidder to Mark appropriate box to clearly indicate the price adjustment offered for each alternate)

## **BID FORM**

SE-330 - LUMP SUM BID

§ 7. LISTING OF PROPOSED SUBCONTRACTORS PURSUANT TO SECTION 3020(b)(i), CHAPTER 35, TITLE 11 OF THE SOUTH CAROLINA CODE OF LAWS, AS AMENDED – (See Instructions on the following page BF-2A)

Bidder shall use the below-listed Subcontractors in the performance of the Subcontractor Specialty work listed:

SUBCONTRACTOR SPECIALTY By License Classification and/or Subclassification (Completed by Owner)	SUBCONTRACTOR'S PRIME CONTRACTOR'S NAME (Must be completed by Bidder) BASE BID	SUBCONTRACTOR'S PRIME CONTRACTOR'S SC LICENSE NUMBER		
Plumbing Contractor License Classification - PB				
Mechanical Contractor				
License Classification - AC Electrical Contractor				
License Classification - EL				
	ALTERNATE 1			
None Required				
	ALTERNATE 2			
None Required				
ALTERNATE 3				
None Required				

If a Bid Alternate is accepted, Subcontractors listed for the Bid Alternate shall be used for the work of both the Alternate and the Base Bid work.

## SE-330 – LUMP SUM BID BID FORM

## INSTRUCTIONS FOR SUBCONTRACTOR LISTING

- 1. Section 7 of the Bid Form sets forth a list of subcontractor specialties for which bidder is required to identify by name the subcontractor(s) Bidder will use to perform the work of each listed specialty. Bidder must identify only the subcontractor(s) who will perform the work and no others.
- **2.** For purposes of subcontractor listing, a Subcontractor is an entity who will perform work or render service to the prime contractor to or about the construction site. Material suppliers, manufacturers, and fabricators that will not perform physical work at the site of the project but will only supply materials or equipment to the bidder or proposed subcontractor(s) are not subcontractors and Bidder should not insert their names in the spaces provided on the bid form. Likewise, Bidder should not insert the names of sub-subcontractors in the spaces provided on the bid form but only the names of those entities with which bidder will contract directly.
- 3. Bidder must only insert the names of subcontractors who are qualified to perform the work of the listed specialties as specified in the Bidding Documents and South Carolina Licensing Laws.
- **4.** If under the terms of the Bidding Documents, Bidder is qualified to perform the work of a specialty listed and Bidder does not intend to subcontract such work but to use Bidder's own employees to perform such work, the Bidder must insert its own name in the space provided for that specialty.
- **5.** If Bidder intends to use multiple subcontractors to perform the work of a single specialty listing, Bidder must insert the name of each subcontractor Bidder will use, preferably separating the name of each by the word "and". If Bidder intends to use both his own employees to perform a part of the work of a single specialty listing and to use one or more subcontractors to perform the remaining work for that specialty listing, bidder must insert his own name and the name of each subcontractor, preferably separating the name of each with the word "and".
- 6. Bidder may not list subcontractors in the alternative nor in a form that may be reasonably construed at the time of bid opening as a listing in the alternative. A listing that requires subsequent explanation to determine whether or not it is a listing in the alternative is non-responsive. If bidder intends to use multiple entities to perform the work for a single specialty listing, bidder must clearly set forth on the bid form such intent. Bidder may accomplish this by simply inserting the word "and" between the name of each entity listed for that specialty. Owner will reject as non-responsive a listing that contains the names of multiple subcontractors separated by a blank space, the word "or", a virgule (that is a /), or any separator that the Owner may reasonably interpret as a listing in the alternative.
- **7.** If Bidder is awarded the contract, bidder must, except with the approval of the owner for good cause shown, use the listed entities to perform the work for which they are listed.
- 8. If bidder is awarded the contract, bidder will not be allowed to substitute another entity as subcontractor in place of a subcontractor listed in Section 7 of the Bid except for one or more of the reasons allowed by the SC Code of Laws.
- 9. Bidder's failure to insert a name for each listed specialty subcontractor will render the Bid non-responsive.

## SE-330 – LUMP SUM BID BID FORM

§ 8. LIST OF MANUFACTURERS, MATERIAL SUPPLIERS, AND SUBCONTRACTORS OTHER THAN SUBCONTRACTORS LISTED IN SECTION 7 ABOVE (FOR INFORMATION ONLY): Pursuant to instructions in the Invitation for Bids, if any, Bidder will provide to Owner upon the Owner's request and within 24 hours of such request, a listing of manufacturers, material suppliers, and subcontractors, other than those listed in Section 7 above, that Bidder intends to use on the project. Bidder acknowledges and agrees that this list is provided for purposes of determining responsibility and not pursuant to the subcontractor listing requirements of SC Code Ann § 11-35-3020(b)(i).

#### § 9. TIME OF CONTRACT PERFORMANCE AND LIQUIDATED DAMAGES

- a. CONTRACT TIME: Bidder agrees that the Date of Commencement of the Work shall be established in a Notice to Proceed to be issued by the Owner. Bidder agrees to substantially complete the Work within <u>180</u> calendar days from the Date of Commencement, subject to adjustments as provided in the Contract Documents.
- b. LIQUIDATED DAMAGES: Bidder further agrees that from the compensation to be paid, the Owner shall retain as Liquidated Damages the sum of \$500.00 for each calendar day the actual construction time required to achieve Substantial Completion exceeds the specified or adjusted time for Substantial Completion as provided in the Contract Documents. This sum is intended by the parties as the predetermined measure of compensation for actual damages, not as a penalty for nonperformance.

#### § 10. AGREEMENTS

- a. Bidder agrees that this bid is subject to the requirements of the law of the State of South Carolina.
- b. Bidder agrees that at any time prior to the issuance of the Notice to Proceed for this Project, this Project may be canceled for the convenience of, and without cost to, the State.
- c. Bidder agrees that neither the State of South Carolina nor any of its agencies, employees or agents shall be responsible for any bid preparation costs, or any costs or charges of any type, should all bids be rejected or the Project canceled for any reason prior to the issuance of the Notice to Proceed.

#### § 11. ELECTRONIC BID BOND

By signing below, the Principal is affirming that the identified electronic bid bond has been executed and that the Principal and Surety are firmly bound unto the State of South Carolina under the terms and conditions of the AIA Document A310, Bid Bond, included in the Bidding Documents.

Electronic Bid Bond	Number:
Signature and Title:	

## SE-330 – LUMP SUM BID BID FORM

#### **BIDDER'S TAXPAYER IDENTIFICATION**

FEDERAL EMPLOYER'S IDENTIFICATION NUMB	ER:
OR	
SOCIAL SECURITY NUMBER:	
CONTRACTOR'S CLASSIFICATIONS AND SUB	CLASSIFICATIONS WITH LIMITATIONS
Classification(s)& Limits:	
Subclassification(s) & Limits:	
SC Contractor's License Number(s):	
CERTIFICATIONS MADE BY BOTH THE PERSON LIMITATION, THOSE APPEARING IN ARTICI	
BY:	DATE:
(Signature)	
TITLE:	
TELEPHONE:	
EMAIL:	

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## **FORM OF AGREEMENT**

FORM OF AGREEMENT is the AIA Document A101-2007 Edition, published by the American Institute of Architects.

The A101 document is not included, but may be viewed at the Architect's office or purchased from the American Institute of Architects.

**END OF SECTION** 

Rev. 7/11/2011

# STANDARD MODIFICATIONS TO AGREEMENT BETWEEN OWNER AND CONTRACTOR

OWNER: <u>University of South Carolina</u> PROJECT NUMBER: <u>H27-6102-MJ</u>

PROJECT NAME: Athletic Village Tennis Complex Addition - RE-BID

#### 1. STANDARD MODIFICATIONS TO AIA A101-2007

**1.1.** These Standard Modifications amend or supplement the *Standard Form of Agreement Between Owner and Contractor* (AIA Document A101-2007) and other provisions of Bidding and Contract Documents as indicated below.

**1.2.** All provisions of A101-2007, which are not so amended or supplemented, remain in full force and effect.

#### 2. MODIFICATIONS TO A101

**2.1.** *Insert the following at the end of Article 1:* 

Any reference in this document to the Agreement between the Owner and Contractor, AIA Document A101, or some abbreviated reference thereof, shall mean the AIA A101, 2007 Edition as modified by OSE Form 00501 – Standard Modification to Agreement Between Owner and Contractor. Any reference in this document to the General Conditions of the Contract for Construction, AIA Document A201, or some abbreviated reference thereof, shall mean the AIA A201, 2007 Edition as modified by OSE Form 00811 – Standard Supplementary Conditions.

- **2.2.** *Delete Section 3.1 and substitute the following:* 
  - **3.1** The Date of Commencement of the Work shall be the date fixed in a Notice to Proceed issued by the Owner. The Owner shall issue the Notice to Proceed to the Contractor in writing, no less than seven days prior to the Date of Commencement. Unless otherwise provided elsewhere in the contract documents, and provided the contractor has secured all required insurance and surety bonds, the contractor may commence work immediately after receipt of the Notice to Proceed.
- **2.3.** *Delete Section 3.2 and substitute the following:* 
  - **3.2** The Contract Time shall be measured from the Date of Commencement as provided in Section 9(a) of the Bid Form (SE-330) for this Project. Contractor agrees that if the Contractor fails to achieve Substantial Completion of the Work within the Contract Time, the Owner shall be entitled to withhold or recover from the Contractor liquidated damages in the amounts set forth in Section 9(b) of the Bid Form (SE-330, subject to adjustments of this Contract Time as provided in the Contract Documents.
- **2.4.** In Section 5.1.1, insert the words "and Owner" after the phrase "Payment submitted to the Architect."
- **2.5.** *Delete Section 5.1.3 and substitute the following:* 
  - **5.1.3** The Owner shall make payment of the certified amount to the Contractor not later than 21 days after receipt of the Application for Payment.
- **2.6.** In Section 5.1.6, Insert the following after the phrase "Subject to other provisions of the Contract Documents":

and subject to Title 12, Chapter 8, Section 550 of the South Carolina Code of Laws, as amended (Withholding Requirements for Payments to Non-Residents)

In the spaces provided in Sub-Sections 1 and 2 for inserting the retainage amount, insert "three and one-half percent (3.5%)."

2011 Edition

## OSE FORM 00501 Rev. 7/11/2011

# STANDARD MODIFICATIONS TO AGREEMENT BETWEEN OWNER AND CONTRACTOR

2.7. In Section 5.1.8, delete the word "follows" and the colon and substitute the following:

set forth in S.C. Code Ann. § 11-35-3030(4).

- **2.8.** In Section 5.1.9, delete the words "Except with the Owner's prior approval, the" before the word "Contractor."
- 2.9. In Section 5.2.2, delete the number 30 and substitute the number 21, delete everything following the words "Certificate for Payment" and place a period at the end of the resulting sentence.
- **2.10.** Delete the language of Sections 6.1 and 6.2 and substitute the word "Reserved" for the deleted language of each Section .
- **2.11.** Delete the language of Section 8.2 and substitute the word "Reserved."
- **2.12.** In Section 8.3, make the word "Representative" in the title plural, delete everything following the title, and substitute the following:
  - **8.3.1** Owner designates the individual listed below as its Senior Representative ("Owner's Senior Representative"), which individual has the responsibility for and, subject to Section 7.2.1 of the General Conditions, the authority to resolve disputes under Section 15.6 of the General Conditions:

Name: Tom Opal

Title: Senior Project Manager

Address: 743 Greene Street, Columbia, SC 29208

**Telephone:** (803)777-7076 **FAX:** (803) 777-8739

Email: tnopal@fmc.sc.edu

**8.3.2** Owner designates the individual listed below as its Owner's Representative, which individual has the authority and responsibility set forth in Section 2.1.1 of the General Conditions:

Name: <u>Ann Derrick</u>
Title: Project Manager

Address: 743 Greene Street, Columbia, SC 29208

**Telephone:** (803) 777-5811 **FAX:** (803) 777-8739

Email: aderrick@fmc.sc.edu

- **2.13.** In Section 8.4, make the word "Representative" in the title plural, delete everything following the title, and substitute the following:
  - **8.4.1** Contractor designates the individual listed below as its Senior Representative ("Contractor's Senior Representative"), which individual has the responsibility for and authority to resolve disputes under Section 15.6 of the General Conditions:

Name:	
Title:	
Address:	
Telephone:	<b>FAX:</b>
Email:	

2011 Edition

## **OSE FORM 00501** Rev. 7/11/2011

# STANDARD MODIFICATIONS TO AGREEMENT BETWEEN OWNER AND CONTRACTOR

**8.4.2** Contractor designates the individual listed below as its Contractor's Representative, which individual has the authority and responsibility set forth in Section 3.1.1 of the General Conditions:

Name:	
Title:	
Address:	
Telephone:	<b>FAX:</b>
Email:	

**2.14**. *Add the following Section 8.6.1:* 

**8.6.1** The Architect's representative:

Name: Marc W. Warren, AIA, LEED AP BD+C

Title: Project Manager

**Address:** <u>1217 Hampton Street, Columbia, SC 29201</u> **Telephone:** (803) 771-2999 **FAX:** (803) 771-2858

Email: <u>mwarren@quackenbusharchitects.com</u>

**2.15.** In Section 9.1.7, Sub-Section 2, list the following documents in the space provided for listing documents:

Invitation for Construction Bids (SE-310)

Instructions to Bidders (AIA Document A701-1997)

Standard Supplemental Instructions to Bidders (OSE Form 00201)

Contractor's Bid (Completed SE-330)

Notice of Intent to Award (Completed SE-370)

Certificate of procurement authority issued by the SC Budget & Control Board

**2.16.** *In Article 10, delete everything after the first sentence.* 

#### END OF DOCUMENT

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION

GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION is the AIA document A201-2007 Edition, published by the American Institute of Architects and the attached OSE Form 00811 STANDARD SUPPLEMENTARY CONDITIONS.

The A201 document is not included, but may be viewed at the Architect's office or purchased from the American Institute of Architects.

**END OF SECTION** 

Rev. 9/7/2011

OWNER: <u>University of South Carolina</u> PROJECT NUMBER: H27-6102-MJ

PROJECT NAME: Athletic Village Tennis Complex Addition - RE-BID

#### 1 GENERAL CONDITIONS

The *General Conditions of the Contract for Construction*, AIA Document A201, 2007 Edition, Articles 1 through 15 inclusive, is a part of this Contract and is incorporated as fully as if herein set forth. For brevity, AIA Document A201 is also referred to in the Contract Documents collectively as the "General Conditions."

#### 2 STANDARD SUPPLEMENTARY CONDITIONS

- 2.1 The following supplements modify, delete and/or add to the General Conditions. Where any portion of the General Conditions is modified or any paragraph, Section or clause thereof is modified or deleted by these Supplementary Conditions, the unaltered provisions of the General Conditions shall remain in effect.
- 2.2 Unless otherwise stated, the terms used in these Standard Supplementary Conditions which are defined in the General Conditions have the meanings assigned to them in the General Conditions.

#### 3 MODIFICATIONS TO A201-2007

3.1 *Insert the following at the end of Section 1.1.1:* 

Any reference in this document to the Agreement between the Owner and Contractor, AIA Document A101, or some abbreviated reference thereof, shall mean the AIA A101, 2007 Edition as modified by OSE Form 00501 – Standard Modification to Agreement Between Owner and Contractor. Any reference in this document to the General Conditions of the Contract for Construction, AIA Document A201, or some abbreviated reference thereof, shall mean the AIA A201, 2007 Edition as modified by OSE Form 00811 – Standard Supplementary Conditions.

- 3.2 Delete the language of Section 1.1.8 and substitute the word "Reserved."
- 3.3 Add the following Section 1.1.9:

#### 1.1.9 NOTICE TO PROCEED

Notice to Proceed is a document issued by the Owner to the Contractor, with a copy to the Architect, directing the Contractor to begin prosecution of the Work in accordance with the requirements of the Contract Documents. The Notice to Proceed shall fix the date on which the Contract Time will commence.

3.4 *Insert the following at the end of Section 1.2.1:* 

In the event of patent ambiguities within or between parts of the Contract Documents, the contractor shall 1) provide the better quality or greater quantity of Work, or 2) comply with the more stringent requirement, either or both in accordance with the Architect's interpretation.

- **3.5** *Delete Section 1.5.1 and substitute the following:* 
  - **1.5.1** The Architect and the Architect's consultants shall be deemed the authors and owners of their respective Instruments of Service and will retain all common law, statutory and other reserved rights, including copyrights. The Contractor, Subcontractors, Sub-subcontractors, and material or equipment suppliers shall not own or claim a copyright in the Instruments of Service. Submittal or distribution to meet official regulatory requirements or for other purposes in connection with this Project is not to be construed as a violation of the Architect's or Architect's consultants' reserved rights.

Rev. 9/7/2011

- **3.6** *Delete Section 2.1.1 and substitute the following:* 
  - **2.1.1** The Owner is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Owner shall designate in writing a representative who shall have express authority to bind the Owner with respect to all matters requiring the Owner's approval or authorization, except as provided in Section 7.1.2. Except as otherwise provided in Section 4.2.1, the Architect does not have such authority. The term "Owner" means the Owner or the Owner's Representative. [Reference § 8.2 of the Agreement.]
- 3.7 Delete Section 2.1.2 and substitute the following:
  - **2.1.2** The Owner shall furnish to the Contractor within fifteen days after receipt of a written request, information necessary and relevant for the Contractor to post Notice of Project Commencement pursuant to Title 29, Chapter 5, Section 23 of the South Carolina Code of Laws, as amended...
- **3.8** *Delete Section 2.2.3 and substitute the following:* 
  - **2.2.3** The Owner shall furnish surveys describing physical characteristics, legal limitations and utility locations for the site of the Project, and a legal description of the site. Subject to the Contractor's obligations, including those in Section 3.2, the Contractor shall be entitled to rely on the accuracy of information furnished by the Owner pursuant to this Section but shall exercise proper precautions relating to the safe performance of the Work.
- **3.9** Replace the period at the end of the last sentence of Section 2.2.4 with a semicolon and insert the following after the inserted semicolon:

"however, the Owner does not warrant the accuracy of any such information requested by the Contractor that is not otherwise required of the Owner by the Contract Documents. Neither the Owner nor the Architect shall be required to conduct investigations or to furnish the Contractor with any information concerning subsurface characteristics or other conditions of the area where the Work is to be performed beyond that which is provide in the Contract Documents."

- **3.10** *Delete Section 2.2.5 and substitute the following:* 
  - **2.2.5** Unless otherwise provided in the Contract Documents, the Owner shall furnish to the Contractor with ten copies of the Contract Documents. The Contractor may make reproductions of the Contract Documents pursuant to Section 1.5.2. All copies of the drawings and specifications, except the Contractor's record set, shall be returned or suitably accounted for to the Owner, on request, upon completion of the Work.
- 3.11 Add the following Sections 2.2.6 and 2.2.7:
  - **2.2.6** The Owner assumes no responsibility for any conclusions or interpretation made by the Contractor based on information made available by the Owner.
  - **2.2.7** The Owner shall obtain, at its own cost, general building and specialty inspection services as required by the Contract Documents. The Contractor shall be responsible for payment of any charges imposed for reinspections.
- 3.12 Delete Section 2.4 and substitute the following:
  - **2.4** If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents and fails within a ten-day period after receipt of written notice from the Owner to commence and continue correction of such default or neglect, including but not limited to providing necessary resources, with diligence and promptness, the Owner may, without prejudice to other remedies the Owner may have, correct such deficiencies. In such case an appropriate Change Directive shall be issued deducting from payments then or thereafter due the Contractor the reasonable cost of correcting such deficiencies, including Owner's expenses and compensation for the Architect's additional services made necessary by such default, neglect or failure. If payments then or thereafter due the Contractor are not sufficient to cover such amounts, the Contractor shall pay the difference to the Owner.

Rev. 9/7/2011

**3.13** *Insert the following at the end of Section 3.2.1:* 

The Contractor acknowledges that it has investigated and satisfied itself as to the general and local conditions which can affect the work or its cost, including but not limited to (1) conditions bearing upon transportation, disposal, handling, and storage of materials; (2) the availability of labor, water, electric power, and roads; (3) uncertainties of weather, river stages, tides, or similar physical conditions at the site; (4) the conformation and conditions of the ground; and (5) the character of equipment and facilities needed preliminary to and during work performance. The Contractor also acknowledges that it has satisfied itself as to the character, quality, and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information is reasonably ascertainable from an inspection of the site, including all exploratory work done by the Owner, as well as from the drawings and specifications made a part of this contract. Any failure of the Contractor to take the actions described and acknowledged in this paragraph will not relieve the Contractor from responsibility for estimating properly the difficulty and cost of successfully performing the work, or for proceeding to successfully perform the work without additional expense to the Owner.

- 3.14 In the third sentence of Section 3.2.4, insert the word "latent" before the word "errors."
- 3.15 In the last sentence of Section 3.3.1, insert the words "by the Owner in writing" after the word "instructed."
- **3.16** Delete the third sentence of Section 3.5 and substitute the following sentences:

Work, materials, or equipment not conforming to these requirements shall be considered defective. Unless caused by the Contractor or a subcontractor at any tier, the Contractor's warranty excludes remedy for damage or defect caused by abuse, alterations to the Work not executed by the Contractor, improper or insufficient maintenance, improper operation, or normal wear and tear and normal usage.

3.17 *Insert the following at the end of Section 3.6:* 

The Contractor shall comply with the requirements of Title 12, Chapter 9 of the South Carolina Code of Laws, as amended, regarding withholding tax for nonresidents, employees, contractors and subcontractors.

3.18 In Section 3.7.1, delete the words "the building permit as well as for other" and insert the following sentence at the end of this section:

Pursuant to Title 10, Chapter 1, Section 180 of the South Carolina Code of Laws, as amended, no local general or specialty building permits are required for state buildings.

**3.19** *Delete the last sentence of Section 3.7.5 and substitute the following:* 

Adjustments in the Contract Sum and Contract Time arising from the existence of such remains or features may be made as provided in Article 7.3.3.

**3.20** *Delete the last sentence of Section 3.8.2.3 and substitute the following:* 

The amount of the Change Order shall reflect the difference between actual costs, as documented by invoices, and the allowances under Section 3.8.2.1.

3.21 In Section 3.9.1, insert a comma after the word "superintendent" in the first sentence and insert the following after the inserted comma:

acceptable to the Owner,

3.22 Delete Section 3.9.2 and substitute the following:

**3.9.2** The Contractor, as soon as practicable after award of the Contract, shall furnish in writing to the Owner the name and qualifications of a proposed superintendent. The Owner may reply within 14 days to the Contractor in writing stating (1) whether the Owner has reasonable objection to the proposed superintendent or (2) that the

Owner requires additional time to review. Failure of the Owner to reply within the 14-day period shall constitute notice of no reasonable objection.

3.23 After the first sentence in Section 3.9.3, insert the following sentence:

The Contractor shall notify the Owner, in writing, of any proposed change in the superintendent, including the reason therefore, prior to making such change.

- **3.24** *Delete Section 3.10.3 and substitute the following:* 
  - **3.10.3** Additional requirements, if any, for the constructions schedule are as follows: (*Check box if applicable to this Contract*))
  - The construction schedule shall be in a detailed precedence-style critical path management (CPM) or primavera-type format satisfactory to the Owner and the Architect that shall also (1) provide a graphic representation of all activities and events that will occur during performance of the work; (2) identify each phase of construction and occupancy; and (3) set forth dates that are critical in ensuring the timely and orderly completion of the Work in accordance with the requirements of the Contract Documents (hereinafter referred to as "Milestone Dates"). Upon review and acceptance by the Owner and the Architect of the Milestone Dates, the construction schedule shall be deemed part of the Contract Documents and attached to the Agreement as Exhibit "A." If not accepted, the construction schedule shall be promptly revised by the Contractor in accordance with the recommendations of the Owner and the Architect and resubmitted for acceptance. The Contactor shall monitor the progress of the Work for conformance with the requirements of the construction schedule and shall promptly advise the Owner of any delays or potential delays. Whenever the approved construction schedule no longer reflects actual conditions and progress of the work or the Contract Time is modified in accordance with the terms of the Contract Documents, the Contractor shall update the accepted construction schedule to reflect such conditions. In the event any progress report indicates any delays, the Contractor shall propose an affirmative plan to correct the delay, including overtime and/or additional labor, if necessary. In no event shall any progress report constitute an adjustment in the Contract Time, any Milestone Date, or the Contract Sum unless any such adjustment is agreed to by the Owner and authorized pursuant to Change Order.
- 3.25 Add the following Section 3.10.4:
  - **3.10.4** Owner's review and acceptance of Contractor's schedule is not conducted for the purpose of either determining its accuracy and completeness or approving the construction means, methods, techniques, sequences or procedures. The Owner's approval shall not relieve the Contractor of any obligations. Unless expressly addressed in a Modification, the Owner's approval of a schedule shall not change the Contract Time.
- **3.26** Add the following Section 3.12.5.1:
  - **3.12.5.1** The fire sprinkler shop drawings shall be prepared by a licensed fire sprinkler contractor and shall accurately reflect actual conditions affecting the required layout of the fire sprinkler system. The fire sprinkler contractor shall certify the accuracy of his shop drawings prior to submitting them for review and approval. The fire sprinkler shop drawings shall be reviewed and approved by the Architect's engineer of record who, upon approving the sprinkler shop drawings will submit them to the State Fire Marshal or other authorities having jurisdiction for review and approval. The Architect's engineer of record will submit a copy of the State Fire Marshal's approval letter to the Contractor, Architect, and OSE. Unless authorized in writing by OSE, neither the Contractor nor subcontractor at any tier shall submit the fire sprinkler shop drawings directly to the State Fire Marshal or other authorities having jurisdiction for approval.
- 3.27 In the fourth sentence of Section 3.12.10, after the comma following the words "licensed design professional," insert the following:
  - who shall comply with reasonable requirements of the Owner regarding qualifications and insurance and
- 3.28 In Section 3.13, insert the section number "3.13.1" before the before the opening words "The Contractors shall."

Rev. 9/7/2011

- **3.29** Add the following Sections 3.13.2 and 3.13.3:
  - **3.13.2** Protection of construction materials and equipment stored at the Project site from weather, theft, vandalism, damage, and all other adversity is solely the responsibility of the Contractor. The Contractor shall perform the work in a manner that affords reasonable access, both vehicular and pedestrian, to the site of the Work and all adjacent areas. The Work shall be performed, to the fullest extent reasonably possible, in such a manner that public areas adjacent to the site of the Work shall be free from all debris, building materials, and equipment likely to cause hazardous conditions.
  - **3.13.3** The Contractor and any entity for whom the Contractor is responsible shall not erect any sign on the Project site without the prior written consent of the Owner.
- 3.30 In the first sentence of Section 3.18.1, after the parenthetical "...(other than the Work itself),..." and before the word "...but...", insert the following:

including loss of use resulting therefrom,

- **3.31** *Delete Section 4.1.1 and substitute the following:* 
  - **4.1.1** The Architect is that person or entity identified as the Architect in the Agreement and is referred to throughout the Contract Documents as if singular in number.
- **3.32** *Insert the following at the end of Section 4.2.1:*

Any reference in the Contract Documents to the Architect taking action or rendering a decision with a "reasonable time" is understood to mean no more than fourteen days, unless otherwise specified in the Contract Documents or otherwise agreed to by the parties.

**3.33** Delete the first sentence of Section 4.2.2 and substitute the following:

The Architect will visit the site as necessary to fulfill its obligation to the Owner for inspection services, if any, and, at a minimum, to assure conformance with the Architect's design as shown in the Contract Documents and to observe the progress and quality of the various components of the Contractor's Work, and to determine if the Work observed is being performed in a manner indicating that the Work, when fully completed, will be in accordance with the Contract Documents.

**3.34** *Delete the first sentence of Section 4.2.3 and substitute the following:* 

On the basis of the site visits, the Architect will keep the Owner informed about the progress and quality of the portion of the Work completed, and report to the Owner (1) deviations from the Contract Documents and from the most recent construction schedule submitted by the Contractor, and (2) defects and deficiencies observed in the Work.

3.35 In Section 4.2.5, after the words "evaluations of the" and before the word "Contractor's," insert the following:

Work completed and correlated with the

- **3.36** *Delete the first sentence of Section 4.2.11 and substitute the following:* 
  - **4.2.11** The Architect will, in the first instance, interpret and decide matters concerning performance under, and requirements of, the Contract Documents on written request of either the Owner or Contractor. Upon receipt of such request, the Architect will promptly provide the non-requesting party with a copy of the request.

Rev. 9/7/2011

**3.37** *Insert the following at the end of Section 4.2.12:* 

If either party disputes the Architects interpretation or decision, that party may proceed as provided in Article 15. The Architect's interpretations and decisions may be, but need not be, accorded any deference in any review conducted pursuant to law or the Contract Documents.

**3.38** *Delete Section 4.2.14 and substitute the following:* 

The Architect will review and respond to requests for information about the Contract Documents so as to avoid delay to the construction of the Project. The Architect's response to such requests will be made in writing with reasonable promptness. If appropriate, the Architect will prepare and issue supplemental Drawings and Specifications in response to the requests for information. Any response to a request for information must be consistent with the intent of, and reasonably inferable from, the Contract Documents and will be in writing or in the form of drawings. Unless issued pursuant to a Modification, supplemental Drawings or Specifications will not involve an adjustment to the Contract Sum or Contract Time.

- **3.39** *Delete Section 5.2.1 and substitute the following:* 
  - **5.2.1** Unless otherwise stated in the Contract Documents or the bidding requirements, the Contractor, within fourteen days after posting of the Notice of Intent to Award the Contract, shall furnish in writing to the Owner through the Architect the names of persons or entities (excluding Listed Subcontractors but including those who are to furnish materials or equipment fabricated to a special design) proposed for each principal portion of the Work. The Owner may reply within 14 days to the Contractor in writing stating (1) whether the Owner has reasonable objection to any such proposed person or entity. Failure of the Owner to reply within the 14 day period shall constitute notice of no reasonable objection.
- **3.40** *Delete Section 5.2.2 and substitute the following:* 
  - **5.2.2** The Contractor shall not contract with a proposed person or entity to whom the Owner has made reasonable and timely objection. The Owner shall not direct the Contractor to contract with any specific individual or entity for supplies or services unless such supplies and services are necessary for completion of the Work and the specified individual or entity is the only source of such supply or services.
- 3.41 In the first sentence of Section 5.2.3, delete the words "... or Architect..." in the two places they appear.
- 3.42 Delete the words "... or Architect..." in the in the first sentence of Section 5.2.4 and insert the following sentence at the end of Section 5.2.4:

The Contractor's request for substitution must be made to the Owner in writing accompanied by supporting information.

- **3.43** *Add the following Section 5.2.5:* 
  - **5.2.5** A Subcontractor identified in the Contractor's Bid in response the specialty subcontractor listing requirements of Section 7 of the Bid Form (SE-330) may only be substituted in accordance with and as permitted by the provisions of Title 11, Chapter 35, Section 3021 of the South Carolina Code of Laws, as amended. A proposed substitute for a Listed Subcontractor shall be subject to the Owner's approval as set forth is Section 5.2.3.
- 3.44 In Section 5.3, delete everything following the heading "SUBCONTRACTUAL RELATIONS" and insert the following Sections 5.3.1, 5.3.2, 5.3.3, and 5.3.4:
  - **5.3.1** By appropriate written agreement, the Contractor shall require each Subcontractor, to the extent of the Work to be performed by the Subcontractor, to be bound to the Contractor by terms of the Contract Documents, and to assume toward the Contractor all the obligations and responsibilities, including the responsibility for safety of the Subcontractor's Work, which the Contractor, by these Documents, assumes toward the Owner and Architect. Each subcontract agreement shall preserve and protect the rights of the Owner and Architect under the Contract Documents with respect to the Work to be performed by the Subcontractor so that subcontracting thereof will not

prejudice such rights, and shall allow to the Subcontractor, unless specifically provided otherwise herein or in the subcontract agreement, the benefit of all rights, remedies and redress against the Contractor that the Contractor, by the Contract Documents, has against the Owner. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with Sub-subcontractors. The Contractor shall make available to each proposed Subcontractor, prior to the execution of the subcontract agreement, copies of the Contract Documents to which the Subcontractor will be bound, and, upon written request of the Subcontractor, identify to the Subcontractor terms and conditions of the proposed subcontract agreement that may be at variance with the Contract Documents. Subcontractors will similarly make copies of applicable portions of such documents available to their respective proposed Sub-subcontractors.

- § 5.3.2 Without limitation on the generality of Section 5.3.1, each Subcontract agreement and each Sub-subcontract agreement shall include, and shall be deemed to include, the following Sections of these General Conditions: 3.2, 3.5, 3.18, 5.3, 5.4, 6.2.2, 7.3.3, 7.5, 7.6, 13.1, 13.12, 14.3, 14.4, and 15.1.6.
- § 5.3.3 Each Subcontract Agreement and each Sub-subcontract agreement shall exclude, and shall be deemed to exclude, Sections 13.2.1 and 13.6 and all of Article 15, except Section 15.1.6, of these General Conditions. In the place of these excluded sections of the General Conditions, each Subcontract Agreement and each Sub-subcontract may include Sections 13.2.1 and 13.6 and all of Article 15, except Section 15.1.6, of AIA Document A201-2007, Conditions of the Contract, as originally issued by the American Institute of Architects.
- § 5.3.4 The Contractor shall assure the Owner that all agreements between the Contractor and its Subcontractor incorporate the provisions of Subparagraph 5.3.1 as necessary to preserve and protect the rights of the Owner and the Architect under the Contract Documents with respect to the work to be performed by Subcontractors so that the subcontracting thereof will not prejudice such rights. The Contractor's assurance shall be in the form of an affidavit or in such other form as the Owner may approve. Upon request, the Contractor shall provide the Owner or Architect with copies of any or all subcontracts or purchase orders.
- **3.45** Delete the last sentence of Section 5.4.1.
- **3.46** *Add the following Sections 5.4.4, 5.4.5 and 5.4.6:* 
  - § 5.4.4 Each subcontract shall specifically provide that the Owner shall only be responsible to the subcontractor for those obligations of the Contractor that accrue subsequent to the Owner's exercise of any rights under this conditional assignment.
  - § 5.4.5 Each subcontract shall specifically provide that the Subcontractor agrees to perform portions of the Work assigned to the Owner in accordance with the Contract Documents.
  - § 5.4.6 Nothing in this Section 5.4 shall act to reduce or discharge the Contractor's payment bond surety's obligations to claims arising prior to the Owner's exercise of any rights under this conditional assignment.
- **3.47** Delete the language of Section 6.1.4 and substitute the word "Reserved."
- **3.48** *Insert the following at the end of Section 7.1.2:*

If the amount of a Modification exceeds the limits of the Owner's Construction Change Order Certification (reference Section 9.1.7.2 of the Agreement), then the Owner's agreement is not effective, and Work may not proceed, until approved in writing by the Office of State Engineer.

- **3.49** *Delete Section 7.2.1 and substitute the following:* 
  - **7.2.1** A Change Order is a written instrument prepared by the Architect (using State Form SE-480 "Construction Change Order") and signed by the Owner, Contractor and Architect stating their agreement upon all of the following:
    - .1 The change in the Work;

- .2 The amount of the adjustment, if any, in the Contract Sum; and
- .3 The extent of the adjustment, if any, in the Contract Time.
- **3.50** *Add the following Sections 7.2.2, 7.2.3, 7.2.4, and 7.2.5:* 
  - **7.2.2** If a Change Order provides for an adjustment to the Contract Sum, the adjustment must be calculated in accordance with Section 7.3.3.
  - **7.2.3** At the Owner's request, the Contractor shall prepare a proposal to perform the work of a proposed Change Order setting forth the amount of the proposed adjustment, if any, in the Contract Sum; and the extent of the proposed adjustment, if any, in the Contract Time. Any proposed adjustment in the Contract sum shall be prepared in accordance with Section 7.2.2. The Owner's request shall include any revisions to the Drawings or Specifications necessary to define any changes in the Work. Within fifteen days of receiving the request, the Contractor shall submit the proposal to the Owner and Architect along with all documentation required by Section 7.6.
  - **7.2.4** If the Contractor requests a Change Order, the request shall set forth the proposed change in the Work and shall be prepared in accordance with Section 7.2.3. If the Contractor requests a change to the Work that involves a revision to either the Drawings or Specifications, the Contractor shall reimburse the Owner for any expenditures associated with the Architects' review of the proposed revisions, except to the extent the revisions are accepted by execution of a Change Order.
  - **7.2.5** Agreement on any Change Order shall constitute a final settlement of all matters relating to the change in the Work that is the subject of the Change Order, including, but not limited to, any adjustments to the Contract Sum or the Contract Time.
- **3.51** *Delete 7.3.3 and substitute the following:*

#### 7.3.3 PRICE ADJUSTMENTS

- § 7.3.3.1 If any Modification, including a Construction Change Directive, provides for an adjustment to the Contract Sum, the adjustment shall be based on whichever of the following methods is the most valid approximation of the actual cost to the contractor, with overhead and profit as allowed by Section 7.5:
  - .1 Mutual acceptance of a lump sum;
  - **.2** Unit prices stated in the Contract Documents, except as provided in Section 7.3.4, or subsequently agreed upon;
  - .3 Cost attributable to the events or situations under applicable clauses with adjustment of profits or fee, all as specified in the contract, or subsequently agreed upon by the parties, or by some other method as the parties may agree; or
  - .4 As provided in Section 7.3.7.
- § 7.3.3.2Consistent with Section 7.6, costs must be properly itemized and supported by substantiating data sufficient to permit evaluation before commencement of the pertinent performance or as soon after that as practicable. All costs incurred by the Contractor must be justifiably compared with prevailing industry standards. Except as provided in Section 7.5, all adjustments to the Contract Price shall be limited to job specific costs and shall not include indirect costs, overhead, home office overhead, or profit.
- **3.52** *Delete Section 7.3.7 and substitute the following:* 
  - **7.3.7** If the Contractor does not respond promptly or disagrees with the method for adjustment in the Contract Sum, the Architect shall make an initial determination, consistent with Section 7.3.3, of the method and the adjustment on the basis of reasonable expenditures and savings of those performing the Work attributable to the change, including, in case of an increase in the Contract Sum, an amount for overhead and profit as set forth in Section 7.5. In such case, and also under Section 7.3.3.1.3, the Contractor shall keep and present, in such form as the Architect may prescribe, an itemized accounting together with appropriate supporting data. Unless otherwise provided in the Contract Documents, costs for the purposes of this Section 7.3.7 shall be limited to the following:

Rev. 9/7/2011

- .1 Costs of labor, including social security, old age and unemployment insurance, fringe benefits required by agreement or custom, and workers' compensation insurance;
- .2 Costs of materials, supplies and equipment, including cost of transportation, whether incorporated or consumed;
- .3 Rental costs of machinery and equipment, exclusive of hand tools, whether rented from the Contractor or others; and
- .4 Costs of premiums for all bonds and insurance, permit fees, and sales, use or similar taxes related to the Work.
- **3.53** *Delete Section 7.3.8 and substitute the following:* 
  - **7.3.8** Using the percentages stated in Section 7.5, any adjustment to the Contract Sum for deleted work shall include any overhead and profit attributable to the cost for the deleted Work.
- **3.54** *Add the following Sections 7.5 and 7.6:*

#### 7.5 AGREED OVERHEAD AND PROFIT RATES

- **7.5.1** For any adjustment to the Contract Sum for which overhead and profit may be recovered, other than those made pursuant to Unit Prices stated in the Contract Documents, the Contractor agrees to charge and accept, as full payment for overhead and profit, the following percentages of costs attributable to the change in the Work. The percentages cited below shall be considered to include all indirect costs including, but not limited to: field and office managers, supervisors and assistants, incidental job burdens, small tools, and general overhead allocations. The allowable percentages for overhead and profit are as follows:
  - .1 To the Contractor for work performed by the Contractor's own forces, 17% of the Contractor's actual costs.
  - .2 To each Subcontractor for work performed by the Subcontractor's own forces, 17% of the subcontractor's actual costs.
  - .3 To the Contractor for work performed by a subcontractor, 10% of the subcontractor's actual costs (not including the subcontractor's overhead and profit).

#### 7.6 PRICING DATA AND AUDIT

#### § 7.6.1 Cost or Pricing Data.

Upon request of the Owner or Architect, Contractor shall submit cost or pricing data prior to execution of a Modification which exceeds \$500,000. Contractor shall certify that, to the best of its knowledge and belief, the cost or pricing data submitted is accurate, complete, and current as of a mutually determined specified date prior to the date of pricing the Modification. Contractor's price, including profit, shall be adjusted to exclude any significant sums by which such price was increased because Contractor furnished cost or pricing data that was inaccurate, incomplete, or not current as of the date specified by the parties. Notwithstanding Subparagraph 9.10.4, such adjustments may be made after final payment to the Contractor.

§ 7.6.2 Cost or pricing data means all facts that, as of the date specified by the parties, prudent buyers and sellers would reasonably expect to affect price negotiations significantly. Cost or pricing data are factual, not judgmental; and are verifiable. While they do not indicate the accuracy of the prospective contractor's judgment about estimated future costs or projections, they do include the data forming the basis for that judgment. Cost or pricing data are more than historical accounting data; they are all the facts that can be reasonably expected to contribute to the soundness of estimates of future costs and to the validity of determinations of costs already incurred.

#### § 7.6.3 Records Retention.

As used in Section 7.6, the term "records" means any books or records that relate to cost or pricing data that Contractor is required to submit pursuant to Section 7.6.1. Contractor shall maintain records for three years from the date of final payment, or longer if requested by the chief procurement officer. The Owner may audit Contractor's records at reasonable times and places.

Rev. 9/7/2011

- **3.55** Delete Section 8.2.2 and substitute the following:
  - **8.2.2** The Contractor shall not knowingly commence operations on the site or elsewhere prior to the effective date of surety bonds and insurance required by Article 11 to be furnished by the Contractor and Owner. The date of commencement of the Work shall not be changed by the effective date of such surety bonds or insurance.
- **3.56** *Delete Section 8.3.1 and substitute the following:* 
  - **8.3.1** If the Contractor is delayed at any time in the commencement or progress of the Work by an act or neglect of the Owner or Architect, or of an employee of either, or of a separate contractor employed by the Owner; or by changes ordered in the Work; or by labor disputes, fire, unusual delay in deliveries, unavoidable casualties or other causes beyond the control of the Contractor and any subcontractor at any tier; or by delay authorized by the Owner pending dispute resolution; or by other causes that the Architect determines may justify delay, then to the extent such delay will prevent the Contractor from achieving Substantial Completion within the Contract Time and provided the delay (1) is not caused by the fault or negligence of the Contractor or a subcontractor at any tier and (2) is not due to unusual delay in the delivery of supplies, machinery, equipment, or services when such supplies, machinery, equipment, or services were obtainable from other sources in sufficient time for the Contractor to meet the required delivery, the Contract Time shall be extended by Change Order for such reasonable time as the Architect may determine.
- 3.57 *Insert the following at the end of Section 9.1:*

All changes to the Contract Sum shall be adjusted in accordance with Section 7.3.3.

**3.58** *Delete Section 9.2 and substitute the following:* 

#### 9.2 SCHEDULE OF VALUES

**9.2.1** The Contractor shall submit to the Architect, within ten days of full execution of the Agreement, a schedule of values allocating the entire Contract Sum to the various portions of the Work and prepared in such form and supported by such data to substantiate its accuracy as the Architect may require. This schedule, unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's Applications for Payment. As requested by the Architect, the Contractor and each Subcontractor shall prepare a trade payment breakdown for the Work for which each is responsible, such breakdown being submitted on a uniform standardized format approved by the Architect and Owner. The breakdown shall be divided in detail, using convenient units, sufficient to accurately determine the value of completed Work during the course of the Project. The Contractor shall update the schedule of values as required by either the Architect or Owner as necessary to reflect:

- .1 the description of Work (listing labor and material separately);
- .2 the total value;
- .3 the percent and value of the Work completed to date;
- .4 the percent and value of previous amounts billed; and
- .5 the current percent completed and amount billed.
- **9.2.2** Any schedule of values or trade breakdown that fails to include sufficient detail, is unbalanced, or exhibits "front-loading" of the value of the Work shall be rejected. If a schedule of values or trade breakdown is used as the basis for payment and later determined to be inaccurate, sufficient funds shall be withheld from future Applications for Payment to ensure an adequate reserve (exclusive of normal retainage) to complete the Work.
- **3.59** *Delete Section 9.3.1 and substitute the following:*

Monthly, the Contractor shall submit to the Architect an itemized Application for Payment prepared in accordance with the schedule of values, if required under Section 9.2., for completed portions of the Work. Such application shall be notarized, if required, and supported by such data substantiating the Contractor's right to payment as the Owner or Architect may require (such as copies of requisitions from Subcontractors and material suppliers) and shall reflect retainage and any other adjustments provided in Section 5 of the Agreement. If required by the Owner or Architect, the Application for Payment shall be accompanied by a current construction schedule.

## OSE FORM 00811

### STANDARD SUPPLEMENTARY CONDITIONS

3.60 In Section 9.3.2, add the following words to the end of the second sentence:

provided such materials or equipment will be subsequently incorporated in the Work

*Insert the following at the end of Section 9.3.2:* 

The Contractor shall 1) protect such materials from diversion, vandalism, theft, destruction, and damage, 2) mark such materials specifically for use on the Project, and 3) segregate such materials from other materials at the storage facility. The Architect and the Owner shall have the right to make inspections of the storage areas at any time.

3.61 In Section 9.4.2, in the first sentence, after the words "Work has progressed to the point indicated," insert the following:

in both the Application for Payment and, if required to be submitted by the Contractor, the accompanying current construction schedule

In the last sentence, delete the third item starting with "(3) reviewed copies" and ending with "Contractor's right to payment,"

3.62 In Section 9.5.1, in the first sentence, delete the word "may" after the opening words "The Architect" and substitute the word "shall."

*In Section 9.5.1, insert the following sentence after the first sentence:* 

The Architect shall withhold a Certificate of Payment if the Application for Payment is not accompanied by the current construction schedule required by Section 3.10.1.

3.63 In Section 9.6.2, delete the word "The..." at the beginning of the first sentence and substitute the following:

Pursuant to Chapter 6 of Title 29 of the South Carolina Code of Laws, as amended, the

**3.64** *Delete Section 9.7 and substitute following:* 

#### 9.7 FAILURE OF PAYMENT

If the Architect does not issue a Certificate for Payment to the Owner, through no fault of the Contractor, within seven days after receipt of the Contractor's Application for Payment, or if the Owner does not pay the Contractor within seven days after the time established in the Contract Documents the amount certified by the Architect or awarded by a final dispute resolution order, then the Contractor may, upon seven additional days' written notice to the Owner and Architect, stop the Work until payment of the amount owing has been received. The Contract Time shall be extended appropriately and the Contract Sum shall be increased, in accordance with the provisions of Section 7.3.3, by the amount of the Contractor's reasonable costs of shut-down, delay and start-up, plus interest as provided for in the Contract Documents.

**3.65** *Insert the following words at the end of the sentence in Section 9.8.1:* 

and when all required occupancy permits, if any, have been issued and copies of same have been delivered to the Owner.

- 3.66 In Section 9.8.2, insert the word "written" after the word "comprehensive" and before the word "list."
- **3.67** *Delete Section 9.8.3 and substitute the following:* 
  - **9.8.3.1** Upon receipt of the Contractor's list, the Architect, with the Owner and any other person the Architect or the Owner choose, will make an inspection on a date and at a time mutually agreeable to the Architect, Owner, and Contractor, to determine whether the Work or designated portion thereof is substantially complete. The Contractor shall furnish access for the inspection and testing as provided in this Contract. The inspection shall include a

Rev. 9/7/2011

demonstration by the Contractor that all equipment, systems and operable components of the Work function properly and in accordance with the Contract Documents. If the Architect's inspection discloses any item, whether or not included on the Contractor's list, which is not sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work or designated portion thereof for its intended use, the Contractor shall, before issuance of the Certificate of Substantial Completion, complete or correct such item upon notification by the Architect. In such case, the Contractor shall then submit a request for another inspection by the Architect to determine Substantial Completion. If more than one Substantial Completion inspection is required, the Contractor shall reimburse the Owner for all costs of reinspections or, at the Owner's option, the costs may be deducted from payments due to the Contractor.

**9.8.3.2** If the Architect and Owner concur in the Contractor's assessment that the Work or a portion of the Work is safe to occupy, the Owner and Contractor may arrange for a Certificate of Occupancy Inspection by OSE. The Owner, Architect, and Contractor shall be present at OSE's inspection. Upon verifying that the Work or a portion of the Work is substantially complete and safe to occupy, OSE will issue, as appropriate, a Full or Partial Certificate of Occupancy.

- **3.68** *In the second sentence of Section 9.8.5, delete the words "and consent of surety, if any."*
- 3.69 In the first sentence of Section 9.9.1, delete the words "Section 11.3.1.5" and substitute the words "Section 11.3.1.3."
- **3.70** *Delete Section 9.10.1 and substitute the following:* 
  - 9.10.1 Unless the parties agree otherwise in the Certificate of Substantial Completion, the Contractor shall achieve Final Completion no later than thirty days after Substantial Completion. Upon receipt of the Contractor's written notice that the Work is ready for final inspection and acceptance and upon receipt of a final Application for Payment, the Architect, with the Owner and any other person the Architect or the Owner choose, will make an inspection on a date and at a time mutually agreeable to the Architect, Owner, and Contractor, and, when the Architect finds the Work acceptable under the Contract Documents and the Contract fully performed, the Architect will promptly issue a final Certificate for Payment stating that to the best of the Architect's knowledge, information and belief, and on the basis of the Architect's on-site visits and inspections, the Work has been completed in accordance with terms and conditions of the Contract Documents and that the entire balance found to be due the Contractor and noted in the final Certificate is due and payable. The Architect's final Certificate for Payment will constitute a further representation that conditions listed in Section 9.10.2 as precedent to the Contractor's being entitled to final payment have been fulfilled. If more than one Final Completion inspection is required, the Contractor shall reimburse the Owner for all costs of reinspections or, at the Owner's option, the costs may be deducted from payments due to the Contractor. If the Contractor does not achieve final completion within thirty days after Substantial Completion or the timeframe agreed to by the parties in the Certificate of Substantial Completion, whichever is greater, the Contractor shall be responsible for any additional Architectural fees resulting from the delay.
- **3.71** *Delete the first sentence of Section 9.10.2 and substitute the following:*

Neither final payment nor any remaining retained percentage shall become due until the Contractor submits to the Architect (1) an affidavit that payrolls, bills for materials and equipment, and other indebtedness connected with the Work for which the Owner or the Owner's property might be responsible or encumbered (less amounts withheld by Owner) have been paid or otherwise satisfied, (2) a certificate evidencing that insurance required by the Contract Documents to remain in force after final payment is currently in effect and will not be canceled or allowed to expire until at least 30 days' prior written notice has been given to the Owner, (3) a written statement that the Contractor knows of no substantial reason that the insurance will not be renewable to cover the period required by the Contract Documents, (4) consent of surety, if any, to final payment (5), if required by the Owner, other data establishing payment or satisfaction of obligations, such as receipts, releases and waivers of liens, claims, security interests or encumbrances arising out of the Contract, to the extent and in such form as may be designated by the Owner, (6) required Training Manuals, (7) equipment Operations and Maintenance Manuals, (8) any certificates of testing, inspection or approval required by the Contract Documents and not previously provided (9) all warranties and guarantees required under or pursuant to the Contract Documents, and (10) one copy of the Documents required by Section 3.11.

Rev. 9/7/2011

Delete the first sentence of Section 9.10.3 and substitute the following:

If, after Substantial Completion of the Work, final completion thereof is delayed 60 days through no fault of the Contractor or by issuance of Change Orders affecting final completion, and the Architect so confirms, the Owner shall, upon application by the Contractor and certification by the Architect, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed and accepted.

3.73 Delete Section 9.10.5 and substitute the following:

> §9.10.5 Acceptance of final payment by the Contractor, a Subcontractor or material supplier shall constitute a waiver of claims by that payee except those specific claims in stated amounts that have been previously made in writing and identified by that payee as unsettled at the time of final Application for Payment.

3.74 Add the following Section 9.10.6:

> 9.10.6 If OSE has not previously issued a Certificate of Occupancy for the entire Project, the Parties shall arrange for a representative of OSE to participate in the Final Completion Inspection. Representatives of the State Fire Marshal's Office and other authorities having jurisdiction may be present at the Final Completion Inspection or otherwise inspect the completed Work and advise the Owner whether the Work meets their respective requirements for the Project.

3.75 Delete Section 10.3.1 and substitute the following:

> 10.3.1 If the Contractor encounters a hazardous material or substance which was not discoverable as provided in Section 3.2.1 and not required by the Contract Documents, and if reasonable precautions will be inadequate to prevent foreseeable bodily injury or death to persons or serious loss to real or personal property resulting from such material or substance encountered on the site by the Contractor, the Contractor shall, upon recognizing the condition, immediately stop Work in the affected area and report the condition to the Owner and Architect in writing. Hazardous materials or substances are those hazardous, toxic, or radioactive materials or substances subject to regulations by applicable governmental authorities having jurisdiction, such as, but not limited to, the S.C. Department of Health and Environmental Control, the U.S. Environmental Protection Agency, and the U.S. Nuclear Regulatory Commission.

3.76 Insert the following at the end of Section 10.3.2:

> In the absence of agreement, the Architect will make an interim determination regarding any delay or impact on the Contractor's additional costs. The Architect's interim determination of cost shall adjust the Contract Sum on the same basis as a Change Order, subject to the right of either party to disagree and assert a Claim in accordance with Article 15. Any adjustment in the Contract Sum shall be determined in accordance with Section 7.3.3.

3.77 Delete Section 10.3.3 and substitute the following:

> 10.3.3 The Work in the affected area shall be resumed immediately following the occurrence of any one of the following events: (a) the Owner causes remedial work to be performed that results in the absence of hazardous materials or substances; (b) the Owner and the Contractor, by written agreement, decide to resume performance of the Work; or (c) the Work may safely and lawfully proceed, as determined by an appropriate governmental authority or as evidenced by a written report to both the Owner and the Contractor, which is prepared by an environmental engineer reasonably satisfactory to both the Owner and the Contractor.

3.78 In Section 10.3.5, delete the word "The" at the beginning of the sentence and substitute the following:

In addition to its obligations under Section 3.18, the

3.79 Delete the language of Section 10.3.6 and substitute the word "Reserved."

Rev. 9/7/2011

**3.80** *Insert the following at the end of Section 10.4:* 

The Contractor shall immediately give the Architect notice of the emergency. This initial notice may be oral followed within five days by a written notice setting forth the nature and scope of the emergency. Within fourteen days of the start of the emergency, the Contractor shall give the Architect a written estimate of the cost and probable effect of delay on the progress of the Work.

#### **3.81** *Delete 11.1.2 and substitute the following:*

11.1.2 The insurance required by Section 11.1.1 shall be written for not less than limits of liability specified below or required by law, whichever coverage is greater. Coverages shall be written on an occurrence basis and shall be maintained without interruption from the date of commencement of the Work until the date of final payment and termination of any coverage required to be maintained after final payment, and, with respect to the Contractor's completed operations coverage, until the expiration of the period for correction of Work or for such other period for maintenance of completed operations coverage as specified in the Contract Documents.

#### (1) COMMERCIAL GENERAL LIABILITY:

(a) General Aggregate (per project)	\$1,000,000
(b) Products/Completed Operations	\$1,000,000
(c) Personal and Advertising Injury	\$1,000,000
(d) Each Occurrence	\$1,000,000
(e) Fire Damage (Any one fire)	\$50,000
(f) Medical Expense (Any one person)	\$5,000

(2) BUSINESS AUTO LIABILITY (including All Owned, Non-owned, and Hired Vehicles):

(a) Combined Single Limit \$1,000,000

#### (3) WORKER'S COMPENSATION:

(a) State Statutory

<b>(b)</b> Employers Liability	\$100,000 Per Acc.
	\$500,000 Disease, Policy Limit
	\$100,000 Disease, Each Employee

In lieu of separate insurance policies for Commercial General Liability, Business Auto Liability, and Employers Liability, the Contractor may provide an umbrella policy meeting or exceeding all coverage requirements set forth in this Section 11.1.2. The umbrella policy limits shall not be less than \$3,000,000.

#### **3.82** *Delete Section 11.1.3 and substitute the following:*

**11.1.3** Prior to commencement of the Work, and thereafter upon replacement of each required policy of insurance, Contractor shall provide to the Owner a written endorsement to the Contractor's general liability insurance policy that:

- (i) names the Owner as an additional insureds for claims caused in whole or in part by the Contractor's negligent acts or omissions during the Contractor's operations;
- (ii) provides that no material alteration, cancellation, non-renewal, or expiration of the coverage contained in such policy shall have effect unless all additional insureds have been given at least ten (10) days prior written notice of cancellation for non-payment of premiums and thirty (30) days prior written notice of cancellation for any other reason; and
- (iii) provides that the Contractor's liability insurance policy shall be primary, with any liability insurance of the Owner as secondary and noncontributory.

Prior to commencement of the Work, and thereafter upon renewal or replacement of each required policy of insurance, Contractor shall provide to the Owner a signed, original certificate of liability insurance (ACORD 25). Consistent with this Section 11.1, the certificate shall identify the types of insurance, state the limits of liability for each type of coverage, name the Owner a Consultants as Certificate Holder, provide that the general aggregate limit applies per project, and provide that coverage is written on an occurrence basis. Both the certificates and the

Rev. 9/7/2011

endorsements must be received directly from either the Contractor's insurance agent or the insurance company. An additional certificate evidencing continuation of liability coverage, including coverage for completed operations, naming the Owner as an additional insured for claims made under the Contractor's completed operations, and otherwise meeting the above requirements, shall be submitted with the final Application for Payment as required by Section 9.10.2 and thereafter upon renewal or replacement of such coverage until the expiration of the time required by Section 11.1.2. Information concerning reduction of coverage on account of revised limits or claims paid under the General Aggregate, or both, shall be furnished by the Contractor with reasonable promptness.

- **3.83** *Delete Section 11.1.4 and substitute the following:* 
  - **11.1.4** A failure by the Owner either (i) to demand a certificate of insurance or written endorsement required by Section 11.1, or (ii) to reject a certificate or endorsement on the grounds that it fails to comply with Section 11.1 shall not be considered a waiver of Contractor's obligations to obtain the required insurance.
- **3.84** *In Section 11.3.1, delete the first sentence and substitute the following:*

Unless otherwise provided in the Contract Documents, the Contractor shall purchase and maintain, in a company or companies lawfully authorized to do business in the jurisdiction in which the Project is located, property insurance written on a builder's risk "all-risk" or equivalent policy form in the amount of the initial Contract Sum, plus value of subsequent Contract Modifications and cost of materials supplied or installed by others, comprising total value for the entire Project at the site on a replacement cost basis.

- **3.85** Delete the language of Section 11.3.1.2 and substitute the word "Reserved."
- **3.86** Delete the language of Section 11.3.1.3 and substitute the word "Reserved."
- **3.87** *Delete Section 11.3.2 and substitute the following:*

#### 11.3.2 BOILER AND MACHINERY INSURANCE

The Contractor shall purchase and maintain boiler and machinery insurance required by the Contract Documents or by law, which shall specifically cover such insured objects during installation and until final acceptance by the Owner; this insurance shall include interests of the Owner, Contractor, Subcontractors and Sub-subcontractors in the Work, and the Owner and Contractor shall both be named insureds.

**3.88** *Delete Section 11.3.3 and substitute the following:* 

#### 11.3.3 LOSS OF USE INSURANCE

The Owner, at the Owner's option, may purchase and maintain such insurance as will insure the Owner against loss of use of the Owner's property due to fire or other hazards, however caused. To the extent any losses are covered and paid for by such insurance, the Owner waives all rights of action against the Contractor for loss of use of the Owner's property, including consequential losses due to fire or other hazards however caused.

- **3.89** *Delete Section 11.3.4 and substitute the following:* 
  - **11.3.4** If the Owner requests in writing that insurance for risks other than those described herein or other special causes of loss be included in the property insurance policy, the Contractor shall, if possible, include such insurance, and the cost thereof shall be charged to the Owner by appropriate Change Order.
- **3.90** Delete the language of Section 11.3.5 and substitute the word "Reserved."
- **3.91** *Delete Section 11.3.6 and substitute the following:* 
  - 11.3.6 Before an exposure to loss may occur, the Contractor shall file with the Owner a copy of each policy that includes insurance coverages required by this Section 11.3. Each policy shall contain all generally applicable conditions, definitions, exclusions and endorsements related to this Project. Each policy shall contain a provision that the policy will not be canceled or allowed to expire, and that its limits will not be reduced, until at least 30 days' prior written notice has been given to the Owner.

## OSE FORM 00811

Rev. 9/7/2011

#### STANDARD SUPPLEMENTARY CONDITIONS

3.92 Delete the first sentence of Section 11.3.7 and substitute the following:

The Owner and Contractor waive all rights against (1) each other and any of their subcontractors, subsubcontractors, agents and employees, each of the other, and (2) the Architect, Architect's consultants, separate contractors described in Article 6, if any, and any of their subcontractors, sub-subcontractors, agents and employees, for damages caused by fire or other causes of loss to the extent the property insurance provided by the Contractor pursuant to this Section 11.3 covers and pays for the damage, except such rights as they have to proceeds of such insurance held by the Contractor as fiduciary.

3.93 Delete the first sentence of Section 11.3.8 and substitute the following:

A loss insured under the Contractor's property insurance shall be adjusted by the Contractor as fiduciary and made payable to the Contractor as fiduciary for the insureds, as their interests may appear, subject to requirements of any applicable mortgagee clause and of Section 11.3.10.

**3.94** *Delete Section 11.3.9 and substitute the following:* 

11.3.9 If required in writing by a party in interest, the Contractor as fiduciary shall, upon occurrence of an insured loss, give bond for proper performance of the Contractor's duties. The cost of required bonds shall be charged against proceeds received as fiduciary. The Contractor shall deposit in a separate account proceeds so received, which the Contractor shall distribute in accordance with such agreement as the parties in interest may reach. If after such loss no other special agreement is made and unless the Owner terminates the Contract for convenience, replacement of damaged property shall be performed by the Contractor.

**3.95** *Delete Section 11.3.10 and substitute the following:* 

**11.3.10** The Contractor as fiduciary shall have power to adjust and settle a loss with insurers unless one of the parties in interest shall object in writing within five days after occurrence of loss to the Contractor's exercise of this power; if such objection is made, the dispute shall be resolved in the manner provided in the contract between the parties in dispute as the method of binding dispute resolution. The Contractor as fiduciary shall make settlement with insurers or, in the case of a dispute over distribution of insurance proceeds, in accordance with a final order or determination issued by the appropriate authority having jurisdiction over the dispute..

**3.96** *Delete Section 11.4.1 and substitute the following:* 

11.4.1 Before commencing any services hereunder, the Contractor shall provide the Owner with Performance and Payment Bonds, each in an amount not less than the Contract Price set forth in Article 4 of the Agreement. The Surety shall have, at a minimum, a "Best Rating" of "A" as stated in the most current publication of "Best's Key Rating Guide, Property-Casualty". In addition, the Surety shall have a minimum "Best Financial Strength Category" of "Class V", and in no case less than five (5) times the contract amount. The Performance Bond shall be written on Form SE-355, "Performance Bond" and the Payment Bond shall written on Form SE-357, "Labor and Material Payment Bond", and both shall be made payable to the Owner.

**3.97** *Delete Section 11.4.2 and substitute the following:* 

11.4.2 The Performance and Labor and Material Payment Bonds shall:

- .1 be issued by a surety company licensed to do business in South Carolina;
- .2 be accompanied by a current power of attorney and certified by the attorney-in-fact who executes the bond on the behalf of the surety company; and
- .3 remain in effect for a period not less than one (1) year following the date of Substantial Completion or the time required to resolve any items of incomplete Work and the payment of any disputed amounts, whichever time period is longer.

#### **OSE FORM 00811**

### Rev. 9/7/2011 STANDARD SUPPLEMENTARY CONDITIONS

- Add the following Sections 11.4.3 and 11.4.4:
  - 11.4.3 Any bonds required by this Contract shall meet the requirements of the South Carolina Code of Laws and Regulations, as amended.
  - 11.4.4 Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a copy of the bonds or shall authorize a copy to be furnished.
- 3.99 Delete Section 12.1.1 and substitute the following:
  - 12.1.1 If a portion of the Work is covered contrary to the to requirements specifically expressed in the Contract Documents, including inspections of work-in-progress required by all authorities having jurisdiction over the Project, it must, upon demand of the Architect or authority having jurisdiction, be uncovered for observation and be replaced at the Contractor's expense without change in the Contract Time.
- 3.100 In Section 12.2.2.1, delete the words "and to make a claim for breach of warranty" at the end of the third sentence.
- **3.101** *In Section 12.2.2.3, add the following to the end of the sentence:*

unless otherwise provided in the Contract Documents.

**3.102** *Insert the following at the end of Section 12.2.4:* 

If, prior to the date of Substantial Completion, the Contractor, a Subcontractor, or anyone for whom either is responsible, uses or damages any portion of the Work, including, without limitation, mechanical, electrical, plumbing, and other building systems, machinery, equipment, or other mechanical device, the Contractor shall cause such item to be restored to "like new" condition at no expense to the Owner.

**3.103** *Delete Section 13.1 and substitute the following:* 

#### 13.1 GOVERNING LAW

The Contract, any dispute, claim, or controversy relating to the Contract, and all the rights and obligations of the parties shall, in all respects, be interpreted, construed, enforced and governed by and under the laws of the State of South Carolina, except its choice of law rules.

**3.104** Delete Section 13.2, including its Sub-Sections 13.2.1 and 13.2.2, and substitute the following:

#### 13.2 SUCCESSORS AND ASSIGNS

The Owner and Contractor respectively bind themselves, their partners, successors, assigns and legal representatives to covenants, agreements and obligations contained in the Contract Documents. Neither party to the Contract shall assign the Contract as a whole, or in part, without written consent of the other and then only in accordance with and as permitted by Regulation 19-445.2180 of the South Carolina Code of Regulations, as amended. If either party attempts to make such an assignment without such consent, that party shall nevertheless remain legally responsible for all obligations under the Contract.

3.105 Delete Section 13.3 and substitute the following:

#### 13.3 WRITTEN NOTICE

Unless otherwise permitted herein, all notices contemplated by the Contract Documents shall be in writing and shall be deemed given:

- upon actual delivery, if delivery is by hand;
- upon receipt by the transmitting party of confirmation or reply, if delivery is by electronic mail, facsimile, telex or telegram;
- upon receipt, if delivery is by the United States mail.

Rev. 9/7/2011

Notice to Contractor shall be to the address provided in Section 8.3.2 of the Agreement. Notice to Owner shall be to the address provided in Section 8.2.2 of the Agreement. Either party may designate a different address for notice by giving notice in accordance with this paragraph.

**3.106** *In Section 13.4.1, insert the following at the beginning of the sentence:* 

Unless expressly provided otherwise,

**3.107** *Add the following Section 13.4.3:* 

**13.4.3** Notwithstanding Section 9.10.4, the rights and obligations which, by their nature, would continue beyond the termination, cancellation, rejection, or expiration of this contract shall survive such termination, cancellation, rejection, or expiration, including, but not limited to, the rights and obligations created by the following clauses:

1.5 Ownership and Use of Drawings, Specifications and Other Instruments of Service;

3.5 Warranty

3.17 Royalties, Patents and Copyrights

3.18 Indemnification

7.6 Cost or Pricing Data

11.1 Contractor's Liability Insurance

11.4 Performance and Payment Bond

15.1.6 Claims for Listed Damages

15.1.7 Waiver of Claims Against the Architect

15.6 Dispute Resolution

15.4 Service of Process

**3.108** *Delete Section 13.6 and substitute the following:* 

#### 13.6 INTEREST

Payments due to the Contractor and unpaid under the Contract Documents shall bear interest only if and to the extent allowed by Title 29, Chapter 6, Article 1 of the South Carolina Code of Laws. Amounts due to the Owner shall bear interest at the rate of one percent a month or a pro rata fraction thereof on the unpaid balance as may be due.

- **3.109** *Delete the language of Section 13.7 and substitute the word "Reserved."*
- **3.110** Add the following Sections 13.8 through 13.16:

#### 13.8 PROCUREMENT OF MATERIALS BY OWNER

The Contractor accepts assignment of all purchase orders and other agreements for procurement of materials and equipment by the Owner that are identified as part of the Contract Documents. The Contractor shall, upon delivery, be responsible for the storage, protection, proper installation, and preservation of such Owner purchased items, if any, as if the Contractor were the original purchaser. The Contract Sum includes, without limitation, all costs and expenses in connection with delivery, storage, insurance, installation, and testing of items covered in any assigned purchase orders or agreements. Unless the Contract Documents specifically provide otherwise, all Contractor warranty of workmanship and correction of the Work obligations under the Contract Documents shall apply to the Contractor's installation of and modifications to any Owner purchased items,.

#### 13.9 INTERPRETATION OF BUILDING CODES

As required by Title 10, Chapter 1, Section 180 of the South Caroline Code of Laws, as amended, OSE shall determine the enforcement and interpretation of all building codes and referenced standards on state buildings. The Contractor shall refer any questions, comments, or directives from local officials to the Owner and OSE for resolution.

Rev. 9/7/2011

#### STANDARD SUPPLEMENTARY CONDITIONS

#### 13.10 MINORITY BUSINESS ENTERPRISES

Contractor shall notify Owner of each Minority Business Enterprise (MBE) providing labor, materials, equipment, or supplies to the Project under a contract with the Contractor. Contractor's notification shall be via the first monthly status report submitted to the Owner after execution of the contract with the MBE. For each such MBE, the Contractor shall provide the MBE's name, address, and telephone number, the nature of the work to be performed or materials or equipment to be supplied by the MBE, whether the MBE is certified by the South Carolina Office of Small and Minority Business Assistance, and the value of the contract.

#### 13.11 SEVERABILITY

If any provision or any part of a provision of the Contract Documents shall be finally determined to be superseded, invalid, illegal, or otherwise unenforceable pursuant to any applicable Legal Requirements, such determination shall not impair or otherwise affect the validity, legality, or enforceability of the remaining provision or parts of the provision of the Contract Documents, which shall remain in full force and effect as if the unenforceable provision or part were deleted.

#### 13.12 ILLEGAL IMMIGRATION

Contractor certifies and agrees that it will comply with the applicable requirements of Title 8, Chapter 14 of the South Carolina Code of Laws and agrees to provide to the State upon request any documentation required to establish either: (a) that Title 8, Chapter 14 is inapplicable both to Contractor and its subcontractors or subsubcontractors; or (b) that Contractor and its subcontractors or sub-subcontractors are in compliance with Title 8, Chapter 14. Pursuant to Section 8-14-60, "A person who knowingly makes or files any false, fictitious, or fraudulent document, statement, or report pursuant to this chapter is guilty of a felony, and, upon conviction, must be fined within the discretion of the court or imprisoned for not more than five years, or both." Contractor agrees to include in any contracts with its subcontractors language requiring its subcontractors to (a) comply with the applicable requirements of Title 8, Chapter 14, and (b) include in their contracts with the sub-subcontractors language requiring the sub-subcontractors to comply with the applicable requirements of Title 8, Chapter 14. (An overview is available at www.procurement.sc.gov)

#### **13.13 SETOFF**

The Owner shall have all of its common law, equitable, and statutory rights of set-off.

#### 13.14 DRUG-FREE WORKPLACE

The Contractor certifies to the Owner that Contractor will provide a Drug-Free Workplace, as required by Title 44, Chapter 107 of the South Carolina Code of Laws, as amended.

#### 13.15 FALSE CLAIMS

According to the S.C. Code of Laws § 16-13-240, "a person who by false pretense or representation obtains the signature of a person to a written instrument or obtains from another person any chattel, money, valuable security, or other property, real or personal, with intent to cheat and defraud a person of that property is guilty" of a crime.

#### 13.16 NON-INDEMNIFICATION:

Any term or condition is void to the extent it requires the State to indemnify anyone. It is unlawful for a person charged with disbursements of state funds appropriated by the General Assembly to exceed the amounts and purposes stated in the appropriations. (§ 11-9-20) It is unlawful for an authorized public officer to enter into a contract for a purpose in which the sum is in excess of the amount appropriated for that purpose. It is unlawful for an authorized public officer to divert or appropriate the funds arising from any tax levied and collected for any one fiscal year to the payment of an indebtedness contracted or incurred for a previous year. (§ 11-1-40)

#### **3.111** *Delete Section 14.1.1 and substitute the following:*

- **14.1.1** The Contractor may terminate the Contract if the Work is stopped for a period of 45 consecutive days through no act or fault of the Contractor or a Subcontractor, Sub-subcontractor or their agents or employees or any other persons or entities performing portions of the Work under direct or indirect contract with the Contractor, for any of the following reasons:
  - .1 Issuance of an order of a court or other public authority having jurisdiction that requires substantially all Work to be stopped; or

- An act of government, such as a declaration of national emergency that requires substantially all Work to be stopped.
- .3 Because the Architect has not issued a Certificate for Payment and has not notified the Contractor of the reason for withholding certification as provided in Section 9.4.1, or because the Owner has not made payment on a Certificate for Payment within the time stated in the Contract Documents and the Contractor has stopped work in accordance with Section 9.7
- **3.112** *Insert the following at the end of Section 14.1.3:*

Any adjustment to the Contract Sum pursuant to this Section shall be made in accordance with the requirements of Article 7.

- 3.113 In Section 14.1.4, replace the word "repeatedly" with the word "persistently."
- **3.114** *Delete Section 14.2.1 and substitute the following:* 
  - 14.2.1 The Owner may terminate the Contract if the Contractor
    - .1 repeatedly refuses or fails to supply enough properly skilled workers or proper materials, or otherwise fails to prosecute the Work, or any separable part of the Work, with the diligence, resources and skill that will ensure its completion within the time specified in the Contract Documents, including any authorized adjustments;
    - .2 fails to make payment to Subcontractors for materials or labor in accordance with the Contract Documents and the respective agreements between the Contractor and the Subcontractors;
    - .3 repeatedly disregards applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of a public authority; or
    - .4 otherwise is guilty of substantial breach of a provision of the Contract Documents.
- 3.115 In Section 14.2.2, delete the parenthetical statement ", upon certification by the Initial Decision Maker that sufficient cause exists to justify such action," immediately following the word "Owner" in the first line.
- 3.116 In Section 14.2.4, replace the words "Initial Decision Maker" with the word "Architect"
- **3.117** Add the following Section 14.2.5:
  - **14.2.5** If, after termination for cause, it is determined that the Owner lacked justification to terminate under Section 14.2.1, or that the Contractor's default was excusable, the rights and obligations of the parties shall be the same as if the termination had been issued for the convenience of the Owner under Section 14.4.
- **3.118** *Delete the second sentence of Section 14.3.2 and substitute the following:*

Any adjustment to the Contract Sum made pursuant to this section shall be made in accordance with the requirements of Article 7.3.3.

- **3.119** *Delete Section 14.4.1 and substitute the following:* 
  - **14.4.1** The Owner may, at any time, terminate the Contract, in whole or in part for the Owner's convenience and without cause. The Owner shall give written notice of the termination to the Contractor specifying the part of the Contract terminated and when termination becomes effective.
- **3.120** *Delete Section 14.4.2 and substitute the following:* 
  - **14.4.2** Upon receipt of written notice from the Owner of such termination for the Owner's convenience, the Contractor shall
    - .1 cease operations as directed by the Owner in the notice;
    - .2 take actions necessary, or that the Owner may direct, for the protection and preservation of the Work;

Rev. 9/7/2011

- .3 except for Work directed to be performed prior to the effective date of termination stated in the notice, terminate all existing subcontracts and purchase orders and enter into no further subcontracts and purchase orders; and
- .4 complete the performance of the Work not terminated, if any.
- **3.121** *Delete Section 14.4.3 and substitute the following:* 
  - **14.4.3** In case of such termination for the Owner's convenience, the Contractor shall be entitled to receive payment for Work executed, costs incurred by reason of such termination, and any other adjustments otherwise allowed by the Contract. Any adjustment to the Contract Sum made pursuant to this Section 14.4 shall be made in accordance with the requirements of Article 7.3.3.
- **3.122** *Add the following Sections 14.4.4, 14.4.5, and 14.5:* 
  - **14.4.4** Contractor's failure to include an appropriate termination for convenience clause in any subcontract shall not (i) affect the Owner's right to require the termination of a subcontract, or (ii) increase the obligation of the Owner beyond what it would have been if the subcontract had contained an appropriate clause.
  - **14.4.5** Upon written consent of the Contractor, the Owner may reinstate the terminated portion of this Contract in whole or in part by amending the notice of termination if it has been determined that:
    - .1 the termination was due to withdrawal of funding by the General Assembly, Governor, or Budget and Control Board or the need to divert project funds to respond to an emergency as defined by Regulation 19-445.2110(B) of the South Carolina Code of Regulations, as amended;
    - .2 funding for the reinstated portion of the work has been restored;
    - .3 circumstances clearly indicate a requirement for the terminated work; and
    - .4 reinstatement of the terminated work is advantageous to the Owner.

#### 14.5 CANCELLATION AFTER AWARD BUT PRIOR TO PERFORMANCE

Pursuant to Title 11, Chapter 35 and Regulation 19-445.2085 of the South Carolina Code of Laws and Regulations, as amended, this contract may be canceled after award but prior to performance.

**3.123** *Insert the following sentence after the second sentence of Section 15.1.1:* 

A voucher, invoice, payment application or other routine request for payment that is not in dispute when submitted is not a Claim under this definition.

**3.124** *Delete Section 15.1.2 and substitute the following:* 

#### 15.1.2 NOTICE OF CLAIMS

Claims by either the Owner or Contractor must be initiated by written notice to the other party and to the Architect. Such notice shall include sufficient information to advise the Architect and other party of the circumstances giving rise to the claim, the specific contractual adjustment or relief requested and the basis of such request. Claims by either party arising prior to the date final payment is due must be initiated within 21 days after occurrence of the event giving rise to such Claim or within 21 days after the claimant first recognizes the condition giving rise to the Claim, whichever is later except as stated for adverse weather days in Section 15.1.5.2. By failing to give written notice of a Claim within the time required by this Section, a party expressly waives its claim.

**3.125** *Delete Section 15.1.3 and substitute the following:* 

#### 15.1.3 CONTINUING CONTRACT PERFORMANCE

Pending final resolution of a Claim, including any administrative review allowed under Section 15.6, except as otherwise agreed in writing or as provided in Section 9.7 and Article 14, the Contractor shall proceed diligently with performance of the Contract and the Owner shall continue to make payments in accordance with the Contract Documents. The Architect will issue Certificates for Payment in accordance with the initial decisions and determinations of the Architect.

Rev. 9/7/2011

3.126 *Insert the following at the end of Section 15.1.5.1:* 

Claims for an increase in the Contract Time shall be based on one additional calendar day for each full calendar day that the Contractor is prevented from working.

- **3.127** *Insert the following Sub-Sections at the end of Section 15.1.5.2:* 
  - Claims for adverse weather shall be based on actual weather conditions at the job site or other place of performance of the Work, as documented in the Contractor's job site log.
  - .2 For the purpose of this Contract, a total of five (5) calendar days per calendar month (non-cumulative) shall be anticipated as "adverse weather" at the job site, and such time will not be considered justification for an extension of time. If, in any month, adverse weather develops beyond the five (5) days, the Contractor shall be allowed to claim additional days to compensate for the excess weather delays only to the extent of the impact on the approved construction schedule. The remedy for this condition is for an extension of time only and is exclusive of all other rights and remedies available under the Contract Documents or imposed or available by law.
  - .3 The Contractor shall submit monthly with their pay application all claims for adverse weather conditions that occurred during the previous month. The Architect shall review each monthly submittal in accordance with Section 15.5 and inform the Contractor and the Owner promptly of its evaluation. Approved days shall be included in the next Change Order issued by the Architect. Adverse weather conditions not claimed within the time limits of this Subparagraph shall be considered to be waived by the Contractor. Claims will not be allowed for adverse weather days that occur after the scheduled (original or adjusted) date of Substantial Completion.
- **3.128** *Delete Section 15.1.6 and substitute the following:*

#### 15.1.6 CLAIMS FOR LISTED DAMAGES

Notwithstanding any other provision of the Contract Documents, including Section 1.2.1, but subject to a duty of good faith and fair dealing, the Contractor and Owner waive Claims against each other for listed damages arising out of or relating to this Contract.

- **15.1.6.1** For the Owner, listed damages are (i) lost revenue and profit, (ii) losses resulting from injury to business or reputation, (iii) additional or escalated overhead and administration expenses, (iv) additional financing costs, (v) costs suffered by a third party unable to commence work, (vi) attorney's fees, (vii) any interest, except to the extent allowed by Section 13.6 (Interest), (viii) lost revenue and profit for lost use of the property, (ix) costs resulting from lost productivity or efficiency.
- **15.1.6.2** For the Contractor, listed damages are (i) lost revenue and profit, (ii) losses resulting from injury to business or reputation, (iii) additional or escalated overhead and administration expenses, (iv) additional financing costs, (v) attorney's fees, (vi) any interest, except to the extent allowed by Section 13.6 (Interest); (vii) unamortized equipment costs; and, (viii) losses incurred by subcontractors for the types of damages the Contractor has waive as against the Owner. Without limitation, this mutual waiver is applicable to all damages due to either party's termination in accordance with Article 14. Nothing contained in this Section shall be deemed to preclude an award of liquidated damages, when applicable, in accordance with the requirements of the Contract Documents. This mutual waiver is not applicable to amounts due or obligations under Section 3.18 (Indemnification).
- **3.129** *Add the following Section 15.1.7:*

#### 15.1.7 WAIVER OF CLAIMS AGAINST THE ARCHITECT

Notwithstanding any other provision of the Contract Documents, including Section 1.2.1, but subject to a duty of good faith and fair dealing, the Contractor waives all claims against the Architect and any other design professionals who provide design and/or project management services to the Owner, either directly or as independent contractors or subcontractors to the Architect, for listed damages arising out of or relating to this Contract. The listed damages are (i) lost revenue and profit, (ii) losses resulting from injury to business or reputation, (iii) additional or escalated overhead and administration expenses, (iv) additional financing costs, (v)

OSE FORM 00811
Rev. 9/7/2011
STANDARD SUPPLEMENTARY CONDITIONS

attorney's fees, (vi) any interest; (vii) unamortized equipment costs; and, (viii) losses incurred by subcontractors for the types of damages the Contractor has waive as against the Owner. This mutual waiver is not applicable to amounts due or obligations under Section 3.18 (Indemnification).

- 3.130 Delete the language of Sections 15.2, 15.3, and 15.4, including all Sub-Sections, and substitute the word "Reserved" for the deleted language of each Section and Sub-Section.
- **3.131** *Add the following Sections 15.5 and 15.6 with their sub-sections:*

## 15.5 CLAIM AND DISPUTES - DUTY OF COOPERATION, NOTICE, AND ARCHITECTS INITIAL DECISION

- **15.5.1** Contractor and Owner are fully committed to working with each other throughout the Project to avoid or minimize claims. To further this goal, Contractor and Owner agree to communicate regularly with each other and the Architect at all times notifying one another as soon as reasonably possible of any issue that if not addressed may cause loss, delay, and/or disruption of the Work. If claims do arise, Contractor and Owner each commit to resolving such claims in an amicable, professional, and expeditious manner to avoid unnecessary losses, delays, and disruptions to the Work.
- **15.5.2** Claims shall first be referred to the Architect for initial decision. An initial decision shall be required as a condition precedent to resolution pursuant to Section 15.6 of any Claim arising prior to the date of final payment, unless 30 days have passed after the Claim has been referred to the Architect with no decision having been rendered, or after all the Architect's requests for additional supporting data have been answered, whichever is later. The Architect will not address claims between the Contractor and persons or entities other than the Owner.
- **15.5.3** The Architect will review Claims and within ten days of the receipt of a Claim (1) request additional supporting data from the claimant or a response with supporting data from the other party or (2) render an initial decision in accordance with Section 15.5.5.
- **15.5.4** If the Architect requests a party to provide a response to a Claim or to furnish additional supporting data, such party shall respond, within ten days after receipt of such request, and shall either (1) provide a response on the requested supporting data, (2) advise the Architect when the response or supporting data will be furnished or (3) advise the Architect that all supporting data has already been provided. Upon receipt of the response or supporting data, the Architect will render an initial decision in accordance with Section 15.5.5.
- 15.5.5 The Architect will render an initial decision in writing; (1) stating the reasons therefor; and (2) notifying the parties of any change in the Contract Sum or Contract Time or both. The Architect will deliver the initial decision to the parties within two weeks of receipt of any response or supporting data requested pursuant to Section 16.4, or within such longer period as may be mutually agreeable to the parties. If the parties accept the initial decision, the Architect shall prepare a Change Order with appropriate supporting documentation for the review and approval of the parties and the Office of State Engineer. If either the Contractor, Owner, or both, disagree with the initial decision, the Contractor and Owner shall proceed with dispute resolution in accordance with the provisions of Section 15.6.
- **15.5.6** In the event of a Claim against the Contractor, the Owner may, but is not obligated to, notify the surety, if any, of the nature and amount of the Claim. If the Claim relates to a possibility of a Contractor's default, the Owner may, but is not obligated to, notify the surety and request the surety's assistance in resolving the controversy.

#### 15.6 DISPUTE RESOLUTION

**15.6.1** If a claim is not resolved pursuant to Section 15.5 to the satisfaction of either party, both parties shall attempt to resolve the dispute at the field level through discussions between Contractor's Representative and Owner's Representative. If a dispute cannot be resolved through Contractor's Representative and Owner's Representative, then the Contractor's Senior Representative and the Owner's Senior Representative, upon the request of either party, shall meet as soon as conveniently possible, but in no case later than twenty-one days after such a request is made, to attempt to resolve such dispute. Prior to any meetings between the Senior Representatives, the parties will exchange relevant information that will assist the parties in resolving their dispute. The meetings required by this Section are a condition precedent to resolution pursuant to Section 15.6.2.

**OSE FORM 00811** Rev. 9/7/2011

### STANDARD SUPPLEMENTARY CONDITIONS

**15.6.2** If after meeting in accordance with the provisions of Section 15.6.1, the Senior Representatives determine that the dispute cannot be resolved on terms satisfactory to both the Contractor and the Owner, then either party may submit the dispute by written request to South Carolina's Chief Procurement Officer for Construction (CPOC). Except as otherwise provided in Article 15, all claims, claims, or controversies relating to the Contract shall be resolved exclusively by the appropriate Chief Procurement Officer in accordance with Title 11, Chapter 35, Article 17 of the South Carolina Code of Laws, or in the absence of jurisdiction, only in the Court of Common Pleas for, or in the absence of jurisdiction a federal court located in, Richland County, State of South Carolina. Contractor agrees that any act by the State regarding the Contract is not a waiver of either the State's sovereign immunity or the State's immunity under the Eleventh Amendment of the United State's Constitution.

**15.6.3** If any party seeks resolution to a dispute pursuant to Section 15.6.2, the parties shall participate in non-binding mediation to resolve the claim. If the claim is governed by Title 11, Chapter 35, Article 17 of the South Carolina Code of Laws as amended and the amount in controversy is \$100,000.00 or less, the CPOC shall appoint a mediator, otherwise, the mediation shall be conducted by an impartial mediator selected by mutual agreement of the parties, or if the parties cannot so agree, a mediator designated by the American Arbitration Association ("AAA") pursuant to its Construction Industry Mediation Rules. The mediation will be governed by and conducted pursuant to a mediation agreement negotiated by the parties or, if the parties cannot so agree, by procedures established by the mediator.

**15.6.4** Without relieving any party from the other requirements of Sections 15.5 and 15.6, either party may initiate proceedings in the appropriate forum prior to initiating or completing the procedures required by Sections 15.5 and 15.6 if such action is necessary to preserve a claim by avoiding the application of any applicable statutory period of limitation or repose.

#### 15.6.5 SERVICE OF PROCESS

Contractor consents that any papers, notices, or process necessary or proper for the initiation or continuation of any claims, claims, or controversies relating to the Contract; for any court action in connection therewith; or for the entry of judgment on any award made, may be served on Contractor by certified mail (return receipt requested) addressed to Contractor at the address provided for the Contractor's Senior Representative or by personal service or by any other manner that is permitted by law, in or outside South Carolina. Notice by certified mail is deemed duly given upon deposit in the United States mail.

**3.132** *Add the following Article 16:* 

ARTICLE 16 PROJECT-SPECIFIC REQUIREMENTS AND INFORMATION
<b>16.1. Inspection Requirements:</b> (Indicate the inspection services required by the Contract)
Special Inspections are required and are not part of the Contract Sum. (see section 01400)
Building Inspections are required and are not part of the Contract Sum. (see section 01400)
Building Inspections are required and are part of the Contract Sum. The inspections required for this Work
are: (Indicate which services are required and the provider)
☐ Civil:
Structural:
Mechanical:
Plumbing:
Electrical:
Gas:
Other ( <i>list</i> ):
Remarks: All inspections will be by USC

OSE FORM 00811

Rev. 9/7/2011

STANDARD SUPPLEMENTARY CONDITIONS

**16.1.1** Contractor shall schedule and request inspections in an orderly and efficient manner and shall notify the Owner whenever the Contractor schedules an inspection in accordance with the requirements of Section 16.1. Contractor shall be responsible for the cost of inspections scheduled and conducted without the Owner's knowledge and for any increase in the cost of inspections resulting from the inefficient scheduling of inspections.

- **16.2** List Cash Allowances, if any. (*Refer to attachments as needed* If *none, enter NONE*) None
- **16.3.** Requirements for Record Drawings, if any. (*Refer to attachments as needed.* If *none, enter NONE*) Refer to Section 017700 "Closeout Procedures" and "017839 Project Record Documents".
- **16.4.** Requirements for Shop Drawings and other submittals, if any, including number, procedure for submission, list of materials to be submitted, etc. (*Refer to attachments as needed. If none, enter NONE*)

  Refer to Section 013300 "Submittal Procedures".
- **16.5.** Requirements for signage, on-site office or trailer, utilities, restrooms, etc., in addition to the Contract, if any. (*Refer to attachments as needed. If none, enter NONE*)

  Refer to Section 015000 "Temporary Facilities and Controls"
- **16.6.** Requirements for Project Cleanup in addition to the Contract, if any. (*Refer to attachments as needed. If none, enter NONE*)

Refer to Section 017700 "Closeout Procedures."

**16.7.** List all attachments that modify these General Conditions. (*If none, enter NONE*) None

# USC SUPPLEMENTAL GENERAL CONDITIONS FOR CONSTRUCTION PROJECTS

- 1. Contractor's employees shall take all reasonable means not to interrupt the flow of student traffic in building corridors, lobbies and stairs. All necessary and reasonable safety precautions shall be taken to prevent injury to building occupants while transporting materials and equipment through the building to the work area. Providing safe, accessible, plywood pedestrian ways around construction may be required if a suitable alternative route is not available.
- 2. Fraternization between Contractor's employees and USC students, faculty or staff is strictly prohibited-zero tolerance!
- 3. USC will not tolerate rude, abusive or degrading behavior on the job site. Heckling and cat-calling directed toward students, faculty or staff or any other person on USC property is strictly prohibited. Any contractor whose employees violate this requirement will be assessed a fine of up to \$500 per violation.
- 4. Contractor's employees must adhere to the University's policy of maintaining a drug-free and smoke-free/tobacco free workplace.
- 5. Contractor must sign a Contractor Key Receipt/Return form before any keys are issued. Keys must be returned immediately upon the completion of the work. The Contractor will bear the cost of any re-keying necessary due to the loss of or failure to return keys.
- 6. A welding permit must be issued by the University Fire Marshall before any welding can begin inside a building. Project Manager will coordinate.
- 7. Contractor must notify the University immediately upon the discovery of suspect materials such as those potentially containing asbestos or other such hazardous materials. These materials **must not** be disturbed until approved by the USC Project Manager.
- 8. At the beginning of the project, the USC Project Manager will establish the Contractor's lay-down area. This area will also be used for the Contractor's work vehicles. No personal vehicles will be allowed in this area, or in any areas surrounding the construction site that are not regular or authorized parking lots. Personal vehicles must be parked in the perimeter parking lots. Parking permits can be obtained at the USC Parking Office located in the Pendleton Street parking garage. The laydown area will be clearly identified to the contractor by the PM, with a sketch or drawing provided to Parking. In turn, the contractor will mark off this area with a sign containing the project name, PM name, Contractor name and contact number, and end date. Where this area is subject to foot traffic, protective barriers will be provided as specified by the PM. The are will be maintained in a neat and orderly fashion. Vehicles parked in the laydown area (or designated parking areas) will be clearly marked or display a CPC furnished placard for identification.

- 9. Contractor will be responsible for providing its own temporary toilet facilities, unless prior arrangements are made with the USC Project Manager.
- 10. Use of USC communications facilities (telephones, computers, etc.) by the Contractor is prohibited, unless prior arrangements are made with the USC Project Manager.
- 11. For all projects over \$100,000, including IDC's, an SE-395, Contractor Performance Evaluation, will be completed by the USC Project Manager and reviewed with the GC at the beginning of the project and a copy given to the GC. At the end of the project the form will be completed and a Construction Performance rating will be established.
- 12. Contractor is responsible for removal of all debris from the site, and is required to provide the necessary dumpsters which will be emptied at least \_\_\_\_\_\_ times per week. Construction waste must not be placed in University dumpsters. THE CONSTRUCTION SITE MUST BE THOROUGHLY CLEANED WITH ALL TRASH PICKED UP AND PROPERLY DISPOSED OF ON A DAILY BASIS AND THE SITE MUST BE LEFT IN A SAFE AND SANITARY CONDITION EACH DAY. THE UNIVERSITY WILL INSPECT JOB SITES REGULARLY AND WILL FINE ANY CONTRACTOR FOUND TO BE IN VIOLATION OF THIS REQUIREMENT AN AMOUNT OF UP TO \$1,000 PER VIOLATION.
- 13. Contractor must provide all O&M manuals, as-built drawings, and training of USC personnel on new equipment, controls, etc. prior to Substantial Completion. Final payment will not be made until this is completed.
- 14. Tree protection fencing is required to protect existing trees and other landscape features to be preserved within a construction area. The limits of this fence will be evaluated for each situation with the consultant, USC Arborist and USC Project Manager. The tree protection fence shall be 5' high chain link fence unless otherwise approved by USC Project Manager. No entry or materials storage will be allowed inside the tree protection zone. A 4" layer of mulch shall be placed over the tree protection area to maintain moisture in the root zone.
- Where it is necessary to cross walks, tree root zones (i.e., under canopy) or lawns the following measures shall be taken: For single loads up to 9,000 lbs., a 3/4" minimum plywood base shall be placed over areas impacted. For single loads over 9,000 lbs., two layers of 3/4" plywood is required.
- 16. For projects requiring heavy loads to cross walks tree root zones or lawns. A construction entry road consisting of 10' X 16' oak logging mates on 12" coarse, chipped, hardwood base. Mulch and logging mats shall be supplemented throughout the project to keep matting structurally functional.
- 17. Any damage to existing landscaping (including lawn areas) will be remediated before final payment is made.
  - (USC Arborist, Kevin Curtis, may be contacted at 777-0033, cell 315-0319)

#### **Campus Vehicle Expectations**

- 1. All motorized vehicles on the University campus are expected to travel and park on roadways and/or in parking stalls.
- 2. All motorized vehicle traffic on USC walkways must first receive the Landscape Manager's authorization. Violators may be subject to fines and penalties.
- 3. All motorized vehicles that leak or drip liquids are prohibited from traveling or parking on walks or landscaped areas.
- 4. Contractors, vendors, and delivery personnel are required to obtain prior parking authorization before parking in a designated space. Violators may be subject to fines and/or penalties. See Item 10 below.
- 5. Drivers of equipment or motor vehicles that damage university hardscape or landscape will be held personally responsible for damages and restoration expense.
- 6. Vehicle drivers who park on landscape or drives must be able to produce written evidence of need or emergency requiring parking on same.
- 7. All vehicles parked on landscape, hardscape, or in the process of service delivery, must display adequate safety devices, i.e. flashing lights, cones, signage, etc.
- 8. All drivers of equipment and vehicles will be respectful of University landscape, equipment, structures, fixtures and signage.
- 9. All incidents of property damage will be reported to Parking Services or the Work Management Center.
- Parking on campus is restricted to spaces designated by Parking Services at the beginning of the project. Once the project manager and contractor agree on how many spaces are needed, the project manager will obtain a placard for each vehicle. This placard must be hung from the mirror of the vehicle, otherwise a ticket will be issued and these tickets cannot be "fixed". Parking spaces are restricted to work vehicles only; no personal vehicles.

## Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## CONTRACTOR'S ONE YEAR GUARANTEE

STATE PROJECT NAME: Athleti	ic Village Tennis Complex Addition – RE-BID
STATE PROJECT NUMBER: <u>H2</u>	7-6102-MJ
STATE OF	
COUNTY OF	
We	as General roject do hereby guarantee that all work executed under the
requirements of the Contract Docu workmanship for a period of one and/or Architect/Engineer, and he	ments shall be free from defects due to faulty materials and/or (1) year from date of acceptance of the work by the Owner creby agree to remedy defects due to faulty materials and/or mage resulting therefrom, at no cost to the Owner, provided
Defects or failures resulting	g from abuse by Owner.
Damage caused by fire, torn wars, riots, or civil commot	nado, hail, hurricane, acts of God, tion.
	(Name of Contracting Firm)
	*By
	Title
*Must be executed by an officer of	the Contracting Firm.
SWORN TO before me this	
day of	20(SEAL)
	(STATE)
My commission expires	

SE-355 2011 Edition

## **Performance Bond**

KNOW ALL MEN BY THESE PRESENTS, that (Insert	t full name or legal title and address of Contractor)
Name:	
Address:	
hereinafter referred to as "Contractor", and (Insert full name	and address of principal place of business of Surety)
Name:	
Address:	
hereinafter called the "surety", are jointly and severally he	eld and firmly bound unto (Insert full name and address of Agency)
Name: University of South Carolina - Columbi	
Address: 743 Greene Street,	<u>u.                                    </u>
Columbia, SC 29208	
hereinafter referred to as "Agency", or its successors or as	ssigns, the sum of(\$\\$), being the sum of the
± 7	ntractor and Surety bind themselves, their heirs, executors,
administrators, successors and assigns, jointly and several	ly, firmly by these presents.
WHEREAS, Contractor has by written agreement dated _	entered into a contract with Agency to construct
State Project Name: Athletic Village Tennis Con	nplex Addition
State Project Number: <u>H27-6102-MJ</u>	1 0F 000 PHF 0F 000 Y 0 PH
Brief Description of Awarded Work, as found or	-
in accordance with Drawings and Specifications prepared	by (Insert full name and address of A/E)
Name: Quackenbush Architects + Planners	
Address: 1217 Hampton Street	
Columbia, SC 29201	
which agreement is by reference made a part hereof, and i	s hereinafter referred to as the Contract.
IN WITNESS WHEREOF. Surety and Contractor, inter	ading to be legally bound hereby, subject to the terms stated
	executed on its behalf by its authorized officer, agent or
representative.	•
DATED 11: 1 C 2	ND NUMBER
DATED thisday of, 2 BO (shall be no earlier than Date of Contract)	ND NUMBER
(shall be no earlier man Dale of Contract)	
CONTRACTOR	SURETY
CONTRACTOR	SUREII
By:	Ву:
(Seal)	(Seal)
Print Name:	Print Name:
Tillit Name.	Time realise.
Print Title:	Print Title:
	(Attach Power of Attorney)
Witness	Witness
Witness:	Witness:
(Additional Constance if any appear on attached mace)	

(Additional Signatures, if any, appear on attached page)

#### **Performance Bond**

#### Performance Bond

#### NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION IS SUCH THAT:

- 1. The Contractor and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Agency for the full and faithful performance of the contract, which is incorporated herein by reference
- 2. If the Contractor performs the contract, the Surety and the Contractor have no obligation under this Bond, except to participate in conferences as provided in paragraph 3.1.
- 3. The Surety's obligation under this Bond shall arise after:
- **3.1** The Agency has notified the Contractor and the Surety at the address described in paragraph 10 below, that the Agency is considering declaring a Contractor Default and has requested and attempted to arrange a conference with the Contractor and the Surety to be held not later than 15 days after receipt of such notice to discuss methods of performing the Contract. If the Agency, the Contractor and the Surety agree, the Contractor shall be allowed a reasonable time to perform the Contract, but such an agreement shall not waive the Agency's right, if any, subsequently to declare a Contractor Default; or
- **3.2** The Agency has declared a Contractor Default and formally terminated the Contractor's right to complete the Contract.
- **4.** The Surety shall, within 15 days after receipt of notice of the Agency's declaration of a Contractor Default, and at the Surety's sole expense, take one of the following actions:
- **4.1** Arrange for the Contractor, with consent of the Agency, to perform and complete the Contract; or
- **4.2** Undertake to perform and complete the Contract itself, through its agents or through independent contractors; or
- **4.3** Obtain bids or negotiated proposals from qualified contractors acceptable to the Agency for a contract for performance and completion of the Contract, arrange for a contract to be prepared for execution by the Agency and the contractor selected with the Agency's concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the Bonds issued on the Contract, and pay to the Agency the amount of damages as described in paragraph 7 in excess of the Balance of the Contract Sum incurred by the Agency resulting from the Contractor Default; or
- **4.4** Waive its right to perform and complete, arrange for completion, or obtain a new contractor, and:
- **4.4.1** After investigation, determine the amount for which it may be liable to the Agency and, within 60 days of waiving its rights under this paragraph, tender payment thereof to the Agency; or
- **4.4.2** Deny liability in whole or in part and notify the Agency, citing the reasons therefore.
- **5.** Provided Surety has proceeded under paragraphs 4.1, 4.2, or 4.3, the Agency shall pay the Balance of the Contract Sum to either:
- **5.1** Surety in accordance with the terms of the Contract; or
- **5.2** Another contractor selected pursuant to paragraph 4.3 to perform the Contract.
- **5.3** The balance of the Contract Sum due either the Surety or another contractor shall be reduced by the amount of damages as described in paragraph 7.
- **6.** If the Surety does not proceed as provided in paragraph 4 with reasonable promptness, the Surety shall be deemed to be in default on this Bond 15 days after receipt of written notice from the Agency to the Surety demanding that the Surety perform its obligations under this Bond, and the Agency shall be entitled to enforce any remedy available to the Agency.

- **6.1** If the Surety proceeds as provided in paragraph 4.4, and the Agency refuses the payment tendered or the Surety has denied liability, in whole or in part, then without further notice the Agency shall be entitled to enforce any remedy available to the Agency.
- **6.2** Any dispute, suit, action or proceeding arising out of or relating to this Bond shall be governed by the Dispute Resolution process defined in the Contract Documents and the laws of the State of South Carolina.
- 7. After the Agency has terminated the Contractor's right to complete the Contract, and if the Surety elects to act under paragraph 4.1, 4.2, or 4.3 above, then the responsibilities of the Surety to the Agency shall be those of the Contractor under the Contract, and the responsibilities of the Agency to the Surety shall those of the Agency under the Contract. To a limit of the amount of this Bond, but subject to commitment by the Agency of the Balance of the Contract Sum to mitigation of costs and damages on the Contract, the Surety is obligated to the Agency without duplication for:
- **7.1** The responsibilities of the Contractor for correction of defective Work and completion of the Contract; and
- **7.2** Additional legal, design professional and delay costs resulting from the Contractor's Default, and resulting from the actions or failure to act of the Surety under paragraph 4; and
- **7.3** Damages awarded pursuant to the Dispute Resolution Provisions of the Contract. Surety may join in any Dispute Resolution proceeding brought under the Contract and shall be bound by the results thereof; and
- **7.4** Liquidated Damages, or if no Liquidated Damages are specified in the Contract, actual damages caused by delayed performance or non-performance of the Contractor.
- **8.** The Surety shall not be liable to the Agency or others for obligations of the Contractor that are unrelated to the Contract, and the Balance of the Contract Sum shall not be reduced or set-off on account of any such unrelated obligations. No right of action shall accrue on this Bond to any person or entity other than the Agency or its heirs, executors, administrators, or successors.
- **9.** The Surety hereby waives notice of any change, including changes of time, to the contract or to related subcontracts, purchase orders and other obligations.
- **10.** Notice to the Surety, the Agency or the Contractor shall be mailed or delivered to the address shown on the signature page.
- 11. Definitions
- 11.1 Balance of the Contract Sum: The total amount payable by the Agency to the Contractor under the Contract after all proper adjustments have been made, including allowance to the Contractor of any amounts to be received by the Agency in settlement of insurance or other Claims for damages to which the Contractor is entitled, reduced by all valid and proper payments made to or on behalf of the Contractor under the Contract.
- **11.2** Contractor Default: Failure of the Contractor, which has neither been remedied nor waived, to perform the Contract or otherwise to comply with the terms of the Contract.

2011 Edition

### SE-357 Labor and Material Payment Bond

Rev. 8/9/2011

Eusor una materiari ayment Bona	
KNOW ALL MEN BY THESE PRESENTS, that (Inser	t full name or legal title and address of Contractor)
Name:	
Address:	
hereinafter referred to as "Contractor", and (Insert full name	and address of principal place of business of Surety)
Name:	
Address:	
hereinafter called the "surety", are jointly and severally h	eld and firmly bound unto (Insert full name and address of Agency)
Name: <u>University of South Carolina - columbia</u>	<u>a</u>
Address: 743 Greene Street,	
Columbia, SC 29208	
hereinafter referred to as "Agency", or its successors or a Bond to which payment to be well and truly made, the Co administrators, successors and assigns, jointly and several	ontractor and Surety bind themselves, their heirs, executors,
WHEREAS, Contractor has by written agreement dated	entered into a contract with Agency to construct
Project Name: Athletic Village Tennis Complex	Addition
Project Number: H27-6102-MJ	4. CF 220 P.1F CF 220 I C P.1
•	n the SE-330, Bid Form: SE-330 Lump Sum Bid.
in accordance with Drawings and Specifications prepared	by (Insert full name and address of A/E)
Name: Quackenbush Architects + Planners	
Address: 1217 Hampton Street Columbia, SC 29201	
which agreement is by reference made a part hereof, and	is hereinafter referred to as the Contract
which agreement is by reference made a part hereof, and	is incremated referred to as the contract.
	nding to be legally bound hereby, subject to the terms stated a Bond to be duly executed on its behalf by its authorized
DATED thisday of, 2 BC (shall be no earlier than Date of Contract)	ND NUMBER
CONTRACTOR	SURETY
Ву:	Ву:
(Seal)	(Seal)
Print Name:	Print Name:
Print Title:	Print Title:
	(Attach Power of Attorney)
Witness:	Witness:

(Additional Signatures, if any, appear on attached page)

SE-357

### **Labor and Material Payment Bond**

#### NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION IS SUCH THAT:

- 1. The Contractor and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Agency to pay for all labor, materials and equipment required for use in the performance of the Contract, which is incorporated herein by reference.
- 2. With respect to the Agency, this obligation shall be null and void if the Contractor:
- **2.1** Promptly makes payment, directly or indirectly, for all sums due Claimants; and
- **2.2** Defends, indemnifies and holds harmless the Agency from all claims, demands, liens or suits by any person or entity who furnished labor, materials or equipment for use in the performance of the Contract.
- 3. With respect to Claimants, this obligation shall be null and void if the Contractor promptly makes payment, directly or indirectly, for all sums due.
- **4.** With respect to Claimants, and subject to the provisions of Title 29, Chapter 5 and the provisions of §11-35-3030(2)(c) of the SC Code of Laws, as amended, the Surety's obligation under this Bond shall arise as follows:
- **4.1** Every person who has furnished labor, material or rental equipment to the Contractor or its subcontractors for the work specified in the Contract, and who has not been paid in full therefore before the expiration of a period of ninety (90) days after the date on which the last of the labor was done or performed by him or material or rental equipment was furnished or supplied by him for which such claim is made, shall have the right to sue on the payment bond for the amount, or the balance thereof, unpaid at the time of institution of such suit and to prosecute such action for the sum or sums justly due him.
- **4.2** A remote claimant shall have a right of action on the payment bond upon giving written notice by certified or registered mail to the Contractor within ninety (90) days from the date on which such person did or performed the last of the labor or furnished or supplied the last of the material or rental equipment upon which such claim is made.
- **4.3** Every suit instituted upon a payment bond shall be brought in a court of competent jurisdiction for the county or circuit in which the construction contract was to be performed, but no such suit shall be commenced after the expiration of o ne year after the day on which the last of the labor was performed or material or rental equipment was supplied by the person bringing suit.
- **5.** When the Claimant has satisfied the conditions of paragraph 4, the Surety shall promptly and at the Surety's expense take the following actions:
- **5.1** Send an answer to the Claimant, with a copy to the Agency, within sixty (60) days after receipt of the claim, stating the amounts that are undisputed and the basis for challenging any amounts that are disputed.
- **5.2** Pay or arrange for payment of any undisputed amounts.
- **5.3** The Surety's failure to discharge its obligations under this paragraph 5 shall not be deemed to constitute a waiver of defenses the Surety or Contractor may have or acquire as to a claim. However, if the Surety fails to discharge its obligations under this paragraph 5, the Surety shall indemnify the Claimant for the reasonable attorney's fees the Claimant incurs to recover any sums found to be due and owing to the Claimant.
- 6. Amounts owed by the Agency to the Contractor under the

- Contract shall be used for the performance of the Contract and to satisfy claims, if any, under any Performance Bond. By the Contractor furnishing and the Agency accepting this Bond, they agree that all funds earned by the contractor in the performance of the Contract are dedicated to satisfy obligations of the Contractor and the Surety under this Bond, subject to the Agency's prior right to use the funds for the completion of the Work.
- 7. The Surety shall not be liable to the Agency, Claimants or others for obligations of the Contractor that are unrelated to the Contract. The Agency shall not be liable for payment of any costs or expenses of any claimant under this bond, and shall have under this Bond no obligations to make payments to, give notices on behalf of, or otherwise have obligations to Claimants under this Bond.
- **8.** The Surety hereby waives notice of any change, including changes of time, to the Contract or to related Subcontracts, purchase orders and other obligations.
- **9**. Notice to the Surety, the Agency or the Contractor shall be mailed or delivered to the addresses shown on the signature page. Actual receipt of notice by Surety, the Agency or the contractor, however accomplished, shall be sufficient compliance as of the date received at the address shown on the signature page.
- 10. By the Contractor furnishing and the Agency accepting this Bond, they agree that this Bond has been furnished to comply with the statutory requirements of the South Carolina Code of Laws, as amended, and further, that any provision in this Bond conflicting with said statutory requirements shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. The intent is that this Bond shall be construed as a statutory Bond and not as a common law bond.
- **11.** Upon request of any person or entity appearing to be a potential beneficiary of this bond, the Contractor shall promptly furnish a copy of this Bond or shall permit a copy to be made.
- **12**. Any dispute, suit, action or proceeding arising out of or relating to this Bond shall be governed by the laws of the State of South Carolina.

#### 13. DEFINITIONS

- 13.1 Claimant: An individual or entity having a direct contract with the Contractor or with a Subcontractor of the Contractor to furnish labor, materials, or equipment for use in the performance of the Contract. The intent of this Bond shall be to include without limitation in the terms "labor, materials or equipment" that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental equipment used in the Contract, architectural and engineering services required for performance of the Work of the Contractor and the Contractor's Subcontractors, and all other items for which a mechanic's lien might otherwise be asserted.
- **13.2** Remote Claimant: A person having a direct contractual relationship with a subcontractor of the Contractor or subcontractor, but no contractual relationship expressed or implied with the Contractor.
- 13.3 Contract: The agreement between the Agency and the Contractor identified on the signature page, including all Contract Documents and changes thereto.

## **INCOME TAX CREDIT!!**

Reference: SC §12-6-3350 – Income Tax Credit for State Contractors Having Subcontracts with MINORITY Firms

Taxpayers, who utilize certified minority subcontractors, may take a tax credit equal to 4% of the payments they make to said subcontractors. The payments claimed must be based on work performed directly for a **South Carolina** state contract. The credit is limited to a maximum of \$50,000 annually. A taxpayer is eligible to claim the credit for 10 taxable years beginning with the taxable year in which the credit is first claimed. After the above 10 taxable years, the taxpayer isno longer eligible for the credit regardless of whether or not the taxpayer claimed the credit in a year subsequent to the year in which the credit was first claimed.

The credit may be claimed on Form TC-2, "Minority Business Credit." A copy of the subcontractor's certificate from the Governor's Office of Small and Minority Business (OSMBA) is to be attached to the contractor's income tax return. Taxpayers must maintain evidence of work performed for a State contract by the minority subcontractor.

Questions regarding the tax credit and how to file are to be referred to:

SC Department of Revenue Research and Review Phone: (803) 898-5786 FAX: (803) 898-5888

References: SC §11-35-5010 – Definition for Minority Subcontractor SC §11-35-5230 (B) – Regulations for Negotiating with State Minority Firms

The subcontractor must be certified as to the criteria of a "Minority Firm" by the Governor's Office of Small and Minority Business Assistance (OSMBA). Certificates are issued to subcontractors upon successful completion of the certification process. Questions regarding subcontractor certification are to be referred to:

Governor's Office of Small and Minority Business Assistance Phone: (803) 734-0657

FAX: (803) 734-2498

SE-480			2011 Edition
CONSTRUCTION CHANGE ORDER	Change Order No.:		
Agency: University of South Carolina  Project Number: H27-6102-MJ  Project Name: Athletic Village Tennis Complex Addition			
Contractor: Contract Dated: For:			
This Contract is changed as follows: (Insert description of change in s	space provided below)		
Adjustments in the Contract Sum:			
1. Original Contract Sum:			
2. Change in Contract Sum by previously approved Change Orders:			
3. Contract Sum prior to this Change Order:			\$0.00
4. Amount of this Change Order:		<u> </u>	•
5. New Contract Sum, including this Change Order:			\$0.00
Adjustments in Contract Time:			
1. Original Substantial Completion Date:			
2. Sum of previously approved increases and decreases:	Days		
3. Changes in Days for this Change Order:	Days		
4. New Substantial Completion Date:			
Contractor Acceptance:			
BY:	Date:		
(Signature of Representative Print Name:			
Architect Recommendation for Acceptance:			
BY:	Date:		
(Signature of Representative			
Print Name:			
Agency Acceptance and Certification			
BY:	Date:		
(Signature of Representative			
Print Name:			
Change is within Agency Construction Procurement	t Certification amount	of	
Change is not within Agency Construction Procurer	ment Certification amo	ount	

Office of the State Engineer Authorization for change not within Agency Construction Procurement Certification:

Signature of OSE Project Manager: \_\_\_\_\_\_

Date: \_\_\_\_\_

#### SECTION 011000 - SUMMARY

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 1.2 SUMMARY

#### A. Section Includes:

- 1. Project information.
- 2. Work covered by Contract Documents.
- 3. Work by Owner.
- 4. Owner-furnished products.
- 5. Contractor-furnished, Owner-installed products.
- 6. Access to site.
- 7. Coordination with occupants.
- 8. Work restrictions.
- 9. Specification and drawing conventions.
- 10. Miscellaneous provisions.

### B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.

#### 1.3 PROJECT INFORMATION

- A. Project Identification: UC Tennis Complex Locker Room Renovation
  - 1. Project Location: 1316 Heyward St., Columbia, SC 29201
- B. Owner: University of South Carolina, 743 Greene Street, Columbia, SC 29208.
  - 1. Owner's Representative: Ann Derrick, Facilities Design and Construction.
- C. Architect: Quackenbush Architects + Planners, 1217 Hampton Street, Columbia, SC 29201
  - 1. Architect: Marc W. Warren, AIA LEED AP BD+C.
- D. Architect's Consultants: The Architect has retained the following design professionals who have prepared designated portions of the Contract Documents:
  - 1. Civil Engineer: RB Todd Consulting Engineers.

- 2. Structural Engineer: Kyzer & Timmerman Structural Engineers.
  - 3. Mechanical, Plumbing: Swygert & Associates, Ltd.
  - 4. Electrical: Belka Engineering Associates, Inc.

#### 1.4 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work of Project is defined by the Contract Documents and consists of the following:
  - 1. The project scope consists of 5 new structures on the existing lower level of the existing tennis complex at the USC Athletics Village, including exterior wall construction and various interior spaces along with all associated engineering components described in the construction document set.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### B. Type of Contract:

1. Project will be constructed under a single prime contract.

#### 1.5 WORK BY OWNER

- A. General: Cooperate fully with Owner so work may be carried out smoothly, without interfering with or delaying work under this Contract or work by Owner. Coordinate the Work of this Contract with work performed by Owner.
- B. Concurrent Work: Owner will perform the following construction operations at Project site. Those operations will be conducted simultaneously with work under this Contract.
  - 1. The Owner will provide all wood lockers, including installation, under separate contract. Contractor is required to coordinate with Owner's Contractors.
  - 2. The Owner will provide Plumbing and HVAC equipment including the Toilets (fixture only), Urinals (fixture only), Water Heater, HVAC Heat Pump, Condensing Units and Air Handlers, under separate contract. The General Contractor is to include installation of equipment in the base bid.
  - 3. The Owner will provide the toilet partitions and listed accessories under separate contract. Contractor is required to coordinate with Owner's Contractors.
  - 4. Owner will provide and install technology and data wiring, terminations, devices and equipment. Contractor is required to coordinate with Owner's Contractors.
  - 5. Under a separate contract, Owner will provide and install all carpet. Contractor shall include the scope for the wall base and shall coordinate the installation with the Owner's Contractor.
  - 6. Under a separate contract, Owner will provide and install all graphics and graphic components.

7. Under a separate contract, Owner will provide and install all residential appliances. Model numbers have been provided for coordination purposes for fit within architectural casework.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 1.6 OWNER-FURNISHED PRODUCTS

- A. Owner will furnish products indicated. The Contractor's Work includes receiving, unloading, handling, storing, protecting, and installing Owner-furnished products and making building services connections.
  - 1. Owner-Furnished Products:
    - a. Plumbing and HVAC equipment including the Toilets (fixture only), Urinals (fixture only), Water Heater, HVAC Heat Pump, Condensing Units and Air Handlers.
- B. Owner will furnish and install products indicated. The Contractor's Work includes coordination with the Owner's Contractor only.
  - 1. Owner-Furnished Owner-Installed Products:
    - a. Toilet Partitions and toilet accessories indicated.
    - b. Wood Locker Casework (Lockers only)
    - c. Residential Appliances including ice maker, refrigerators and freezers. Contractor shall coordinate opening sizes.
    - d. All Tile Carpeting, Contractor shall coordinate the installation of the base material.

#### 1.7 ACCESS TO SITE

- A. Use of Site: Limit use of Project site to work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.
  - 1. Limits: Confine construction operations to area of work, plus a laydown space as designated by the University of South Carolina.
  - 2. Driveways, Walkways and Entrances: Keep driveways, loading areas, and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.
    - a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
    - b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- B. Condition of Existing Building: Maintain portions of existing building affected by construction operations in a weathertight condition throughout construction period. Repair damage caused by construction operations.

#### 1.8 COORDINATION WITH OCCUPANTS

A. Partial Owner Occupancy: Owner will occupy the premises during entire construction period, with the exception of areas under construction. Cooperate with Owner during construction

operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with Owner's operations. Maintain existing exits unless otherwise indicated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Owner and authorities having jurisdiction.
- 2. Provide not less than 72 hours' notice to Owner of activities that will affect Owner's operations.
- B. Owner Limited Occupancy of Completed Areas of Construction: Owner reserves the right to occupy and to place and install equipment in completed portions of the Work, prior to Substantial Completion of the Work, provided such occupancy does not interfere with completion of the Work. Such placement of equipment and limited occupancy shall not constitute acceptance of the total Work.
  - 1. Architect will prepare a Certificate of Substantial Completion for each specific portion of the Work to be occupied prior to Owner acceptance of the completed Work.
  - 2. Obtain a Certificate of Occupancy from authorities having jurisdiction before limited Owner occupancy.
  - 3. Before limited Owner occupancy, mechanical and electrical systems shall be fully operational, and required tests and inspections shall be successfully completed. On occupancy, Owner will operate and maintain mechanical and electrical systems serving occupied portions of Work.
  - 4. On occupancy, Owner will assume responsibility for maintenance and custodial service for occupied portions of Work.

#### 1.9 WORK RESTRICTIONS

- A. Work Restrictions, General: Comply with restrictions on construction operations.
  - 1. Comply with limitations on use of public streets and with other requirements of authorities having jurisdiction.
- B. Contractor is not permitted to photograph stadium or practices occurring within stadium.
- C. Contractor is not permitted to talk or interact with students, student athletes or coaches.
- D. On-Site Work Hours: Limit work in the existing building to normal business working hours of 7 a.m. to 6 p.m., Monday through Friday, unless otherwise indicated.
  - 1. Weekend Hours: Not restricted.
  - 2. Early Morning Hours: Not restricted.
  - 3. Hours for Utility Shutdowns: Notify in advance.
  - 4. Hours for core drilling or high levels of noise activity: Notify in advance.
  - 5. Tennis practice may be held on the existing, adjacent stadium courts from time to time, but this should not limited access to construction work. If USC requires that due to an event, no construction activity is to occur on site, then the contract time will be extended accordingly.

- E. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner (in particular, the tennis court lighting) or others unless permitted under the following conditions and then only after providing temporary utility services according to requirements indicated:
  - 1. Notify Architect and Owner not less than two days in advance of proposed utility interruptions.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Obtain Architect's and Owner's written permission before proceeding with utility interruptions.
- F. Noise, Vibration, and Odors: Coordinate operations that may result in high levels of noise and vibration, odors, or other disruption to Owner occupancy with Owner.
  - 1. Notify Architect and Owner not less than two days in advance of proposed disruptive operations.
- G. Controlled Substances: Use of tobacco products and other controlled substances within the existing building and on Project site is not permitted.

#### 1.10 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
  - 1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
  - 2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.
- B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.
- C. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:
  - 1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
  - 2. Abbreviations: Materials and products are identified by abbreviations published as part of the U.S. National CAD Standard and scheduled on Drawings.
  - 3. Keynoting: Materials and products are identified by reference keynotes referencing Specification Section numbers found in this Project Manual.

#### 1.11 OWNER APPROVAL OF SUBCONTRACTORS AND PERSONNEL

A. The Contractor shall not employ any subcontractor, superintendent or workmen whose employment on the project is objectionable to the Owner or Architect/Engineer.

### 1.12 MATERIAL DELIVERY, STORAGE AND HANDLING

A. The Contractor supplying and delivering equipment or materials must provide personnel and equipment to unload these materials at the time they arrive on site, or make provisions for receiving and unloading the shipment for Contractor inventory purposes.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. All materials shall be shipped and stored and handled in a manner that will afford protection and insure their being in first-class condition at the time they are incorporated in the work. After installation, they shall be properly protected against damage insure their being in first-class condition when the construction as a whole is completed and accepted by the Owner.

### 1.13 EXISTING CONDITIONS

A. The Contractor, subcontractors and material suppliers shall be responsible for inspecting all job conditions affecting the installation of an item and taking all field measurements required prior to fabrication of an item to insure that the item concerned will integrate properly with all adjacent materials and fit all other conditions as they exist or will exist in the finished construction. Work in connection with installation of an item shall be coordinated with all other affected work and trades. Sleeves, anchors, and other items that must be embodied in or that otherwise affect other portions of the work will be located and set while such portions of the work are in progress.

### 1.14 QUALITY OF WORK

- A. All items shall be installed in a workmanlike manner in accordance with the best recognized practice in the field concerned. Manufactured items shall be installed in strict accordance with manufacturer's printed directions, specifications and/or recommendations for installation of highest quality. All working parts shall be properly adjusted after installation and left in perfect working order. Unless otherwise indicated, items exposed to weather or subject to flooding or wetting shall be installed so as to shed and not hold water. Items shall in all cases be installed plumb and true and/or in proper relation to surrounding materials.
- B. All materials entering into the construction of the building covered by this Contract including but not limited to those mentioned below, shall be securely anchored and/or tied together in accordance with the best recognized practice in the field concerned whether shown, specified or not. Ties and anchors shall be best quality for the purpose. All veneers, finishes, and applied items shall be securely anchored and tied to the backing material. The purpose of this paragraph is that each and every piece of otherwise secured in place in a permanent manner that will permit expansion, contraction and other minor movements and normal use of the structure without structural features of the building becoming impaired and without any of its parts becoming loose.
- C. Unless otherwise specifically mentioned, all anchors, bolts, screws, fittings, fillers, hardware, accessories, trim and other parts required for or in connection with an item of material to make a complete, serviceable, finished and first quality installation shall be furnished and installed as part of the item whether or not called for by the Specifications.

SUMMARY 011000 - 6

D. Should the Contractor's work require sealant to compete the 'finished product' appearance of any item he is installing, at the direction of the Architect, that Contractor shall furnish and install that

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

sealant whether or not called for on plans or in specifications.

E. Unless otherwise specifically specified, all items and parts thereof that are made of steel, iron or other ferrous metal that are not galvanized, plated, or otherwise specified to be factory finished, shall be cleaned and painted with one shop coat of the best quality rust inhibitive metallic primer. After installation, all exposed metal connections and abrasions shall be touched up with the same materials as the shop coat and left in good condition for final finishing.

### 1.15 CONTRACTOR SUPERVISION

- A. The Contractor shall have on-site for the duration of his work a competent representative, capable of the following:
  - 1. Supervision of tradesmen.
  - 2. Reading and interpreting the Contract Documents.
  - 3. Orderly coordination of this work with the Architect in the daily execution of the work.
  - 4. Laying out his work.
  - 5. Representing the Contractor with the Owner and Architect in the daily execution of the work.
  - 6. Controlling and establishing good quality in the completed work.
  - 7. Communicating with all the workers in the Contractor's Employment.
- B. The Contractor's representative shall be the sole supervisor of the Contractor's Labor Force. He shall attend the regularly scheduled progress meetings on-site, keep himself and his company informed of scheduled requirements, safety hazards, and general job conditions. He shall plan and pursue the work under his supervision and expeditious manner.

### 1.16 INSPECTIONS, TESTING AND SPECIAL INSPECTIONS

- A. The Owner will hire inspectors, testing companies and special inspections. See 014000 for additional information and Contractor's responsibilities.
- B. The Contractor shall be responsible for notifying the Testing Agency, Third-Party Inspectors and/or State Inspectors when their services or inspection are required. Expedite notification to insure proper lead time. Cost of re-inspections for work that is not ready or does not comply with Contract Documents shall be borne by the Contractor

### 1.17 ASBESTOS AND HAZARDOUS MATERIALS

A. The intent of the specifications is to call for materials which are entirely free of asbestos and all other hazardous materials. If materials specified contain asbestos or other hazardous materials, it shall be the responsibility of the material supplier and Contractor to call this to the attention of the Architect in writing. Such material shall not be delivered to the job site.

SUMMARY 011000 - 7

University of South Carolina Athletic Village Tennis Complex Addition Re-Bid Set

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

SUMMARY 011000 - 8

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

### SECTION 012300 - ALTERNATES

### PART 1 - GENERAL

#### 1.1 **RELATED DOCUMENTS**

Drawings and general provisions of the Contract, including General and Supplementary A. Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 **SUMMARY**

Section includes administrative and procedural requirements for alternates. A.

#### 1.3 **DEFINITIONS**

- Alternate: An amount proposed by bidders and stated on the Bid Form for certain work defined A. in the bidding requirements that may be added to or deducted from the base bid amount if Owner decides to accept a corresponding change either in the amount of construction to be completed or in the products, materials, equipment, systems, or installation methods described in the Contract Documents.
  - 1. Alternates described in this Section are part of the Work only if enumerated in the
  - 2. The cost or credit for each alternate is the net addition to or deduction from the Contract Sum to incorporate alternate into the Work. No other adjustments are made to the Contract Sum.

#### 1.4 **PROCEDURES**

- Coordination: Revise or adjust affected adjacent work as necessary to completely integrate A. work of the alternate into Project.
  - Include as part of each alternate, miscellaneous devices, accessory objects, and similar 1. items incidental to or required for a complete installation whether or not indicated as part of alternate.
- Notification: Immediately following award of the Contract, notify each party involved, in В. writing, of the status of each alternate. Indicate if alternates have been accepted, rejected, or deferred for later consideration. Include a complete description of negotiated revisions to alternates.
- Execute accepted alternates under the same conditions as other work of the Contract. C.

**ALTERNATES** 012300 - 1 Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

D. Schedule: A schedule of alternates is included at the end of this Section. Specification Sections referenced in schedule contain requirements for materials necessary to achieve the work described under each alternate.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

#### 3.1 SCHEDULE OF ALTERNATES

- A. Alternate #1: Training Room Building from above the floor slab to the new construction roof above including interior finishes. All work below and within the floor slab including plumbing and electrical infrastructure shall be included in the base bid.
- B. Alternate #2: Meeting Room Building from above the floor slab to the new construction roof above including interior finishes. All work below and within the floor slab including plumbing and electrical infrastructure shall be included in the base bid.

END OF SECTION 012300

ALTERNATES 012300 - 2

## SECTION 012500 - SUBSTITUTION PROCEDURES

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Requirements:
  - 1. Section 012300 "Alternates" for products selected under an alternate.
  - 2. Section 016000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

### 1.3 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.
  - 1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
  - 2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required in order to meet other Project requirements but may offer advantage to Contractor or Owner.

### 1.4 ACTION SUBMITTALS

- A. Substitution Requests: Submit one copy of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
  - 1. Substitution Request Form: Use facsimile of form provided at the end of this specification section.
  - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
    - a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- b. Coordination information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors, that will be necessary to accommodate proposed substitution.
- c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
- d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
- e. Samples, where applicable or requested.
- f. Certificates and qualification data, where applicable or requested.
- g. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.
- h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
- i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
- j. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
- k. Cost information, including a proposal of change, if any, in the Contract Sum.
- 1. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
- m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
- 3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
  - a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
  - b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

### 1.5 QUALITY ASSURANCE

A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

Issue Date: 06/05/2014

### 1.6 PROCEDURES

A. Coordination: Revise or adjust affected work as necessary to integrate work of the approved substitutions.

#### PART 2 - PRODUCTS

### 2.1 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
  - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
    - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
    - b. Requested substitution provides sustainable design characteristics that specified product provided.
    - c. Substitution request is fully documented and properly submitted.
    - d. Requested substitution will not adversely affect Contractor's construction schedule.
    - e. Requested substitution has received necessary approvals of authorities having jurisdiction.
    - f. Requested substitution is compatible with other portions of the Work.
    - g. Requested substitution has been coordinated with other portions of the Work.
    - h. Requested substitution provides specified warranty.
    - i. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- B. Substitutions for Convenience: Architect will consider requests for substitution if received within 30 days after the Notice to Proceed. Requests received after that time may be considered or rejected at discretion of Architect.
  - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
    - a. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.

Issue Date: 06/05/2014

- b. Requested substitution does not require extensive revisions to the Contract Documents.
- c. Requested substitution is consistent with the Contract Documents and will produce indicated results.
- d. Requested substitution provides sustainable design characteristics that specified product provided.
- e. Substitution request is fully documented and properly submitted.
- f. Requested substitution will not adversely affect Contractor's construction schedule.
- g. Requested substitution has received necessary approvals of authorities having jurisdiction.
- h. Requested substitution is compatible with other portions of the Work.
- i. Requested substitution has been coordinated with other portions of the Work.
- j. Requested substitution provides specified warranty.
- k. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

PART 3 - EXECUTION (Not Used)

END OF SECTION 012500

Issue Date: 06/05/2014

## SUBSTITUTION REQUEST FORM (During Bidding)

Project: USC Tennis Complex Locker Room Addition State Project No. H27-6102-MJ Architect's Project No. 12.130.09				
То	Quackenbush Architects + Planners	Fax	803.771.2858	
	1217 Hampton Street Columbia, South Carolina 29201	Attn	Marc W. Warren, AIA LEED AP BD+C mwarren@quackenbusharchitects.com	
Requ	ested By			
Contract For				
Bid Date Substitution Request Date		Request Date		
Sectio	on Name			
Section No Paragraph				
Relat	ed Dwgs.			
Required Information for Specified Product  Point by Point Comparative Product Data Test Reports Fabrication Drawings Samples (Where Applicable)  Attached				
Propo	osed Product/Fabrication Method (List tr	rade name/o	lescription; model no.; manufacturer)	
Required Information for <i>Proposed</i> Product Attached				
Point by Point Comparative Product Data Test Reports Fabrication Drawings Samples (Where Applicable)				

**Attach Additional Sheets if Required** 

ASSUMPTION OF LIABILITY FOR EQUAL PERFORMANCE

# CERTIFICATE OF EQUAL PERFORMANCE AND

Undersigned certifies:

- 1. Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product, except as noted herein.
- 2. Qualifications of manufacturer, installer, and other specified parties meet the specified qualifications.
- 3. Same special warranty will be furnished for proposed substitution as for specified product.
- 4. Same maintenance service and source for replacement parts, as applicable, is available as that specified.
- 5. Proposed substitution does not affect dimensions and functional clearances, except as noted herein.

Submitted By				
Signed				
Firm				
Address				
Telephone				
Fax				
9	n having authority to legally bind his firm to the above terms. Failure to adding signature will result in rejection of proposed substitution.			
FOR QUACKENBUSH ARCHITECTS + PLANNERS USE ONLY				
☐ Substitution Approved – I	Included in Addendum No			
☐ Substitution Approved as	Noted – Included in Addendum No			
Substitution Rejected – U	se Specified Materials			
Substitution Request Rece	eived Too Late for Review Prior to Bid – Use Specified Materials			
By	Date			

Architect's Project #: 12.130.09

### SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

## B. Related Requirements:

1. Section 012500 "Substitution Procedures" for administrative procedures for handling requests for substitutions made after the Contract award.

## 1.3 MINOR CHANGES IN THE WORK

A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time.

## 1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
  - 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
  - 2. Within time specified in Proposal Request or 10 days, when not otherwise specified, after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
    - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
    - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
    - c. Include costs of labor and supervision directly attributable to the change.
    - d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
    - e. Quotation Form: Use forms acceptable to Architect.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.
  - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
  - 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
  - 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
  - 4. Include costs of labor and supervision directly attributable to the change.
  - 5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
  - 6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
  - 7. Proposal Request Form: Use form acceptable to Architect.

### 1.5 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Work Changes Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on SE-480 (2011 edition).

## 1.6 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
  - 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
  - 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

## SECTION 012900 - PAYMENT PROCEDURES

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.

## B. Related Requirements:

- 1. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
- 2. Section 013200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

## 1.3 DEFINITIONS

A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

### 1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.
  - 1. Coordinate line items in the schedule of values with other required administrative forms and schedules, including the following:
    - a. Application for Payment forms with continuation sheets.
    - b. Submittal schedule.
    - c. Items required to be indicated as separate activities in Contractor's construction schedule.
  - 2. Submit the schedule of values to Architect at earliest possible date, but no later than seven days before the date scheduled for submittal of initial Applications for Payment.

Architect's Project #: 12.130.09

- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
  - 1. Identification: Include the following Project identification on the schedule of values:
    - a. Project name and location.
    - b. Name of Architect.
    - c. Architect's project number.
    - d. Contractor's name and address.
    - e. Date of submittal.
  - 2. Arrange schedule of values consistent with format of AIA Document G703.
  - 3. Arrange the schedule of values in tabular form with separate columns to indicate the following for each item listed:
    - a. Related Specification Section or Division.
    - b. Description of the Work.
    - c. Name of subcontractor.
    - d. Name of manufacturer or fabricator.
    - e. Name of supplier.
    - f. Change Orders (numbers) that affect value.
    - g. Dollar value of the following, as a percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.
      - 1) Labor.
      - 2) Materials.
      - 3) Equipment.
  - 4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with Project Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
  - 5. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
  - 6. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
    - a. Differentiate between items stored on-site and items stored off-site. If required, include evidence of insurance.
  - 7. Provide separate line items in the schedule of values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
  - 8. Schedule Updating: Update and resubmit the schedule of values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

## 1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
  - 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.

Architect's Project #: 12.130.09

- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
  - 1. Submit (via e-mail) draft copy of Application for Payment seven days prior to due date for review by Architect.
- C. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
  - 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
  - 2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
  - 3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
  - 4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.
- E. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored on-site and items stored off-site.
  - 1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment, for stored materials.
  - 2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
  - 3. Provide summary documentation for stored materials indicating the following:
    - a. Value of materials previously stored and remaining stored as of date of previous Applications for Payment.
    - b. Value of previously stored materials put in place after date of previous Application for Payment and on or before date of current Application for Payment.
    - c. Value of materials stored since date of previous Application for Payment and remaining stored as of date of current Application for Payment.

- F. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
  - 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from entities lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
  - 1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
  - 2. When an application shows completion of an item, submit conditional final or full waivers.
  - 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
  - 4. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.
- H. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
  - 1. List of subcontractors.
  - 2. Schedule of values.
  - 3. Contractor's construction schedule (preliminary if not final).
  - 4. List of Contractor's staff assignments.
  - 5. List of Contractor's principal consultants.
- I. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
  - 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
  - 2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
  - 1. Evidence of completion of Project closeout requirements.
  - 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
  - 3. Updated final statement, accounting for final changes to the Contract Sum.
  - 4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
  - 5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
  - 6. AIA Document G707, "Consent of Surety to Final Payment."
  - 7. Evidence that claims have been settled.

Issue Date: 06/05/2014

- 8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
- 9. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

### SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
  - 1. General coordination procedures.
  - 2. Requests for Information (RFIs).
  - 3. Project meetings.
- B. Each contractor shall participate in coordination requirements. Certain areas of responsibility are assigned to a specific contractor.

## C. Related Requirements:

- 1. Section 013200 "Construction Progress Documentation" for preparing and submitting Contractor's construction schedule.
- 2. Section 017300 "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
- 3. Section 017700 "Closeout Procedures" for coordinating closeout of the Contract.

### 1.3 DEFINITIONS

A. RFI: Request from Owner, Architect, or Contractor seeking information required by or clarifications of the Contract Documents.

### 1.4 INFORMATIONAL SUBMITTALS

- A. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
  - 1. Name, address, and telephone number of entity performing subcontract or supplying products.
  - 2. Number and title of related Specification Section(s) covered by subcontract.
  - 3. Drawing number and detail references, as appropriate, covered by subcontract.

Architect's Project #: 12.130.09

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

B. Key Personnel Names: Within 5 days of starting construction operations, submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers, including home, office, and cellular telephone numbers and e-mail addresses. Provide names, addresses, and telephone numbers of individuals assigned as alternates in the absence of individuals assigned to Project.

1. Post copies of list in project meeting room, in temporary field office, and by each temporary telephone. Keep list current at all times.

### 1.5 GENERAL COORDINATION PROCEDURES

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, that depend on each other for proper installation, connection, and operation.
  - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
  - 2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
  - 3. Make adequate provisions to accommodate items scheduled for later installation.
- B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
  - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.
- C. Conservation: Coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials. Coordinate use of temporary utilities to minimize waste.

### 1.6 REQUESTS FOR INFORMATION (RFIs)

- A. General: Immediately on discovery of the need for additional information or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.
  - 1. Architect will return RFIs submitted to Architect by other entities controlled by Contractor with no response.
  - 2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 1. Project name.
- 2. Project number.
- 3. Date.
- 4. Name of Contractor.
- 5. Name of Architect.
- 6. RFI number, numbered sequentially.
- 7. RFI subject.
- 8. Specification Section number and title and related paragraphs, as appropriate.
- 9. Drawing number and detail references, as appropriate.
- 10. Field dimensions and conditions, as appropriate.
- 11. Contractor's suggested resolution. If Contractor's suggested resolution impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
- 12. Contractor's signature.
- 13. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
  - a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.
- C. RFI Forms: Software-generated form with substantially the same content as indicated above, acceptable to Architect.
  - 1. Attachments shall be electronic files in Adobe Acrobat PDF format.
- D. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow seven working days for Architect's response for each RFI. RFIs received by Architect after 1:00 p.m. will be considered as received the following working day.
  - 1. The following Contractor-generated RFIs will be returned without action:
    - a. Requests for approval of submittals.
    - b. Requests for approval of substitutions.
    - c. Requests for approval of Contractor's means and methods.
    - d. Requests for coordination information already indicated in the Contract Documents.
    - e. Requests for adjustments in the Contract Time or the Contract Sum.
    - f. Requests for interpretation of Architect's actions on submittals.
    - g. Incomplete RFIs or inaccurately prepared RFIs.
  - 2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt of additional information.
  - 3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."
    - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.

E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly. Include the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Project name.
- 2. Name and address of Contractor.
- 3. Name and address of Architect.
- 4. RFI number including RFIs that were returned without action or withdrawn.
- 5. RFI description.
- 6. Date the RFI was submitted.
- 7. Date Architect's response was received.
- F. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within seven days if Contractor disagrees with response.
  - 1. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
  - 2. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.

### 1.7 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site unless otherwise indicated.
  - 1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
  - 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
  - 3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within three days of the meeting.
- B. Preconstruction Conference: Schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 5 days after execution of the Agreement.
  - 1. Conduct the conference to review responsibilities and personnel assignments.
  - 2. Attendees: Authorized representatives of Owner Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
  - 3. Agenda: Discuss items of significance that could affect progress, including the following:
    - a. Tentative construction schedule.
    - b. Phasing.
    - c. Critical work sequencing and long-lead items.
    - d. Designation of key personnel and their duties.

- e. Lines of communications.
- f. Procedures for processing field decisions and Change Orders.
- g. Procedures for RFIs.
- h. Procedures for testing and inspecting.
- i. Procedures for processing Applications for Payment.
- j. Distribution of the Contract Documents.
- k. Submittal procedures.
- 1. Preparation of record documents.
- m. Use of the premises and existing building.
- n. Work restrictions.
- o. Working hours.
- p. Owner's occupancy requirements.
- q. Responsibility for temporary facilities and controls.
- r. Procedures for moisture and mold control.
- s. Procedures for disruptions and shutdowns.
- t. Construction waste management and recycling.
- u. Parking availability.
- v. Office, work, and storage areas.
- w. Equipment deliveries and priorities.
- x. First aid.
- y. Security.
- z. Progress cleaning.
- 4. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.
  - 1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
  - 2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
    - a. Contract Documents.
    - b. Options.
    - c. Related RFIs.
    - d. Related Change Orders.
    - e. Purchases.
    - f. Deliveries.
    - g. Submittals.
    - h. Review of mockups.
    - i. Possible conflicts.
    - j. Compatibility requirements.
    - k. Time schedules.
    - 1. Weather limitations.
    - m. Manufacturer's written instructions.
    - n. Warranty requirements.

- o. Compatibility of materials.
- p. Acceptability of substrates.
- q. Temporary facilities and controls.
- r. Space and access limitations.
- s. Regulations of authorities having jurisdiction.
- t. Testing and inspecting requirements.
- u. Installation procedures.
- v. Coordination with other work.
- w. Required performance results.
- x. Protection of adjacent work.
- y. Protection of construction and personnel.
- 3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
- 4. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
- 5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Project Closeout Conference: Schedule and conduct a project closeout conference, at a time convenient to Owner and Architect, but no later than 90 days prior to the scheduled date of Substantial Completion.
  - 1. Conduct the conference to review requirements and responsibilities related to Project closeout.
  - 2. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the meeting. Participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
  - 3. Agenda: Discuss items of significance that could affect or delay Project closeout, including the following:
    - a. Preparation of record documents.
    - b. Procedures required prior to inspection for Substantial Completion and for final inspection for acceptance.
    - c. Submittal of written warranties.
    - d. Requirements for preparing operations and maintenance data.
    - e. Requirements for delivery of material samples, attic stock, and spare parts.
    - f. Requirements for demonstration and training.
    - g. Preparation of Contractor's punch list.
    - h. Procedures for processing Applications for Payment at Substantial Completion and for final payment.
    - i. Submittal procedures.
    - j. Owner's partial occupancy requirements.
    - k. Installation of Owner's furniture, fixtures, and equipment.
    - 1. Responsibility for removing temporary facilities and controls.
  - 4. Minutes: Entity conducting meeting will record and distribute meeting minutes.

- E. Progress Meetings: Conduct progress meetings at weekly intervals.
  - 1. Coordinate dates of meetings with preparation of payment requests.
  - 2. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.

- 3. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
  - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
    - 1) Review schedule for next period.
  - b. Review present and future needs of each entity present, including the following:
    - 1) Interface requirements.
    - 2) Sequence of operations.
    - 3) Status of submittals.
    - 4) Deliveries.
    - 5) Off-site fabrication.
    - 6) Access.
    - 7) Site utilization.
    - 8) Temporary facilities and controls.
    - 9) Progress cleaning.
    - 10) Quality and work standards.
    - 11) Status of correction of deficient items.
    - 12) Field observations.
    - 13) Status of RFIs.
    - 14) Status of proposal requests.
    - 15) Pending changes.
    - 16) Status of Change Orders.
    - 17) Pending claims and disputes.
    - 18) Documentation of information for payment requests.
- 4. Minutes: Entity responsible for conducting the meeting will record and distribute the meeting minutes to each party present and to parties requiring information.
  - a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.
- F. Coordination Meetings: Conduct Project coordination meetings at weekly intervals. Project coordination meetings are in addition to specific meetings held for other purposes, such as progress meetings and preinstallation conferences.

Issue Date: 06/05/2014

- 1. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meetings shall be familiar with Project and authorized to conclude matters relating to the Work.
- 2. Agenda: Review and correct or approve minutes of the previous coordination meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
  - a. Combined Contractor's Construction Schedule: Review progress since the last coordination meeting. Determine whether each contract is on time, ahead of schedule, or behind schedule, in relation to combined Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
  - b. Schedule Updating: Revise combined Contractor's construction schedule after each coordination meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with report of each meeting.
  - c. Review present and future needs of each contractor present, including the following:
    - 1) Interface requirements.
    - 2) Sequence of operations.
    - 3) Status of submittals.
    - 4) Deliveries.
    - 5) Off-site fabrication.
    - 6) Access.
    - 7) Site utilization.
    - 8) Temporary facilities and controls.
    - 9) Work hours.
    - 10) Hazards and risks.
    - 11) Progress cleaning.
    - 12) Quality and work standards.
    - 13) Change Orders.
- 3. Reporting: Record meeting results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013100

### SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
  - 1. Startup construction schedule.
  - 2. Contractor's construction schedule.
  - 3. Construction schedule updating reports.
  - 4. Material location reports.
  - 5. Site condition reports.
  - 6. Special reports.

### B. Related Requirements:

- 1. Section 013300 "Submittal Procedures" for submitting schedules and reports.
- 2. Section 014000 "Quality Requirements" for submitting a schedule of tests and inspections.

## 1.3 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.
  - 1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
  - 2. Predecessor Activity: An activity that precedes another activity in the network.
  - 3. Successor Activity: An activity that follows another activity in the network.
- B. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.
- C. Event: The starting or ending point of an activity.
- D. Float: The measure of leeway in starting and completing an activity.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a 1. jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.

Architect's Project #: 12.130.09

- Free float is the amount of time an activity can be delayed without adversely affecting the 2. early start of the successor activity.
- Total float is the measure of leeway in starting or completing an activity without 3. adversely affecting the planned Project completion date.

#### 1.4 INFORMATIONAL SUBMITTALS

- Format for Submittals: Submit required submittals in the following format: A.
  - Working electronic copy of schedule file, where indicated. 1.
  - PDF electronic file. 2.
- B. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.
- Construction Schedule Updating Reports: Submit with Applications for Payment. C.
- Site Condition Reports: Submit at time of discovery of differing conditions. D.
- Special Reports: Submit at time of unusual event. E.
- Qualification Data: For scheduling consultant. F.

#### 1.5 **COORDINATION**

- Coordinate Contractor's construction schedule with the schedule of values, submittal schedule, A. progress reports, payment requests, and other required schedules and reports.
  - 1. Secure time commitments for performing critical elements of the Work from entities involved.
  - 2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

### PART 2 - PRODUCTS

#### 2.1 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Time Frame: Extend schedule from date established for the Notice to Proceed to date of Substantial Completion.
  - Contract completion date shall not be changed by submission of a schedule that shows an 1. early completion date, unless specifically authorized by Change Order.
- B. Activities: Treat each story or separate area as a separate numbered activity for each main element of the Work. Comply with the following:

Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
- 2. Procurement Activities: Include procurement process activities for the following long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
- 3. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's construction schedule with submittal schedule.
- 4. Startup and Testing Time: Include no fewer than 15 days for startup and testing.
- 5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
- 6. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and final completion.
- C. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.
  - 1. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
  - 2. Owner-Furnished Products: Include a separate activity for each product. Include delivery date indicated in Section 011000 "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
  - 3. Work Restrictions: Show the effect of the following items on the schedule:
    - a. Coordination with existing construction.
    - b. Environmental control.
  - 4. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:
    - a. Submittals.
    - b. Fabrication.
    - c. Installation.
    - d. Curing.
- D. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and final completion.
- E. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:
  - 1. Unresolved issues.
  - 2. Unanswered Requests for Information.
  - 3. Rejected or unreturned submittals.
  - 4. Notations on returned submittals.
  - 5. Pending modifications affecting the Work and Contract Time.
- F. Recovery Schedule: When periodic update indicates the Work is **14** or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule. Indicate changes to working

Issue Date: 06/05/2014

hours, working days, crew sizes, and equipment required to achieve compliance, and date by which recovery will be accomplished.

Architect's Project #: 12.130.09

Computer Scheduling Software: Prepare schedules using current version of a program that has G. been developed specifically to manage construction schedules.

#### 2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE

- Submit a comprehensive, fully developed, horizontal, Contractor's construction schedule within A. 10 days of date established for the Notice to Proceed. Base schedule on the startup construction schedule and additional information received since the start of Project.
- Preparation: Indicate each significant construction activity separately. Identify first workday of B. each week with a continuous vertical line.

#### 2.3 **REPORTS**

Site Condition Reports: Immediately on discovery of a difference between site conditions and A. the Contract Documents, prepare and submit a detailed report. Submit with a Request for Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

#### 2.4 SPECIAL REPORTS

- A. General: Submit special reports directly to Owner within one day(s) of an occurrence. Distribute copies of report to parties affected by the occurrence.
- В. Reporting Unusual Events: When an event of an unusual and significant nature occurs at Project site, whether or not related directly to the Work, prepare and submit a special report. List chain of events, persons participating, response by Contractor's personnel, evaluation of results or effects, and similar pertinent information. Advise Owner in advance when these events are known or predictable.

### PART 3 - EXECUTION

#### 3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

- Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect A. actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.
  - Revise schedule immediately after each meeting or other activity where revisions have 1. been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
  - 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.

Le-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 3. As the Work progresses, indicate final completion percentage for each activity.
- B. Distribution: Distribute copies of approved schedule to Architect Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
  - 1. Post copies in Project meeting rooms and temporary field offices.
  - 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION 013200

## SECTION 013300 - SUBMITTAL PROCEDURES

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.

### B. Related Requirements:

- 1. Section 012900 "Payment Procedures" for submitting Applications for Payment and the schedule of values.
- 2. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
- 3. Section 017823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
- 4. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

### 1.3 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."
- C. Portable Document Format (PDF): An open standard file format licensed by Adobe Systems used for representing documents in a device-independent and display resolution-independent fixed-layout document format.

#### 1.4 ACTION SUBMITTALS

A. Submittal Schedule: Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.

- 1. Coordinate submittal schedule with list of subcontracts, the schedule of values, and Contractor's construction schedule.
- 2. Initial Submittal: Submit concurrently with startup construction schedule. Include submittals required during the first 30 days of construction. List those submittals required to maintain orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
- 3. Final Submittal: Submit concurrently with the first complete submittal of Contractor's construction schedule.
  - a. Submit revised submittal schedule to reflect changes in current status and timing for submittals.
- 4. Format: Arrange the following information in a tabular format:
  - a. Scheduled date for first submittal.
  - b. Specification Section number and title.
  - c. Submittal category: Action; informational.
  - d. Name of subcontractor.
  - e. Description of the Work covered.
  - f. Scheduled date for Architect's final release or approval.
  - g. Scheduled date of fabrication.
  - h. Scheduled dates for installation.
  - i. Activity or event number.

### 1.5 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. Architect's Digital Data Files: Electronic digital data files of the Contract Drawings will be provided by Architect for Contractor's use in preparing submittals.
  - 1. Architect will furnish Contractor one set of digital data drawing files of the Contract Drawings for use in preparing Shop Drawings.
    - a. Architect makes no representations as to the accuracy or completeness of digital data drawing files as they relate to the Contract Drawings.
    - b. Digital Drawing Software Program: The Contract Drawings are available in AutoCAD.
    - c. Contractor shall execute a data licensing agreement in the form of Agreement included at the end of this specification section.
    - d. The following digital data files will by furnished for each appropriate discipline:
      - 1) Floor plans.
      - 2) Reflected ceiling plans.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
  - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.

Re-Bid Set Issue Date: 06/05/2014

2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.

- 3. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
  - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.

Architect's Project #: 12.130.09

- C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
  - 1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
  - 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
  - 3. Resubmittal Review: Allow 15 days for review of each resubmittal.
  - 4. Sequential Review: Where sequential review of submittals by Architect's consultants, Owner, or other parties is indicated, allow 21 days for initial review of each submittal.
  - 5. Concurrent Consultant Review: Where the Contract Documents indicate that submittals may be transmitted simultaneously to Architect and to Architect's consultants, allow 15 days for review of each submittal. Submittal will be returned to Architect before being returned to Contractor.
- D. Electronic Submittals: Identify and incorporate information in each electronic submittal file as follows:
  - 1. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
  - 2. Name file with submittal number or other unique identifier, including revision identifier.
    - a. File name shall use project identifier and Specification Section number followed by a decimal point and then a sequential number (e.g., USCT-061000.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., USCT-061000.01.A).
  - 3. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by Architect.
  - 4. Transmittal Form for Electronic Submittals: Use electronic form acceptable to Architect, containing the following information:
    - a. Project name.
    - b. Date.
    - c. Name and address of Architect.
    - d. Name of Construction Manager.
    - e. Name of Contractor.
    - f. Name of firm or entity that prepared submittal.
    - g. Names of subcontractor, manufacturer, and supplier.
    - h. Category and type of submittal.

uplex Addition

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- i. Submittal purpose and description.
- j. Specification Section number and title.
- k. Specification paragraph number or drawing designation and generic name for each of multiple items.
- 1. Drawing number and detail references, as appropriate.
- m. Location(s) where product is to be installed, as appropriate.
- n. Related physical samples submitted directly.
- o. Indication of full or partial submittal.
- p. Transmittal number, numbered consecutively.
- q. Submittal and transmittal distribution record.
- r. Other necessary identification.
- s. Remarks.
- 5. Metadata: Include the following information as keywords in the electronic submittal file metadata:
  - a. Project name.
  - b. Number and title of appropriate Specification Section.
  - c. Manufacturer name.
  - d. Product name.
- E. Options: Identify options requiring selection by Architect.
- F. Deviations and Additional Information: On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Architect on previous submittals, and deviations from requirements in the Contract Documents, including minor variations and limitations. Include same identification information as related submittal.
- G. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
  - 1. Note date and content of previous submittal.
  - 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
  - 3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.
- H. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- I. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.
- J. Paper Submittals: Paper submittals shall be used for samples and material/color selection charts only. Place a permanent label or title block on each submittal item for identification.
  - 1. Indicate name of firm or entity that prepared each submittal on label or title block.
  - 2. Provide a space approximately 6 by 8 inches (150 by 200 mm) on label or beside title block to record Contractor's review and approval markings and action taken by Architect.
  - 3. Include the following information for processing and recording action taken:

- a. Project name.
- b. Date.
- c. Name of Architect.
- d. Name of Construction Manager.
- e. Name of Contractor.
- f. Name of subcontractor.
- g. Name of supplier.
- h. Name of manufacturer.
- i. Submittal number or other unique identifier, including revision identifier.
  - 1) Submittal number shall use Specification Section number followed by a decimal point and then a sequential number (e.g., WBS-061000.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., WBS-061000.01.A).
- j. Number and title of appropriate Specification Section.
- k. Drawing number and detail references, as appropriate.
- 1. Location(s) where product is to be installed, as appropriate.
- m. Other necessary identification.
- 4. Additional Paper Copies: Unless additional copies are required for final submittal, and unless Architect observes noncompliance with provisions in the Contract Documents, initial submittal may serve as final submittal.
  - a. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Architect.
- 5. Transmittal for Paper Submittals: Assemble each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Architect will return without review submittals received from sources other than Contractor.
  - a. Transmittal Form for Paper Submittals: Provide locations on form for the following information:
    - 1) Project name.
    - 2) Date.
    - 3) Destination (To:).
    - 4) Source (From:).
    - 5) Name and address of Architect.
    - 6) Name of Construction Manager.
    - 7) Name of Contractor.
    - 8) Name of firm or entity that prepared submittal.
    - 9) Names of subcontractor, manufacturer, and supplier.
    - 10) Category and type of submittal.
    - 11) Submittal purpose and description.
    - 12) Specification Section number and title.
    - 13) Specification paragraph number or drawing designation and generic name for each of multiple items.
    - 14) Drawing number and detail references, as appropriate.
    - 15) Indication of full or partial submittal.

Issue Date: 06/05/2014

- 16) Transmittal number, numbered consecutively.
- 17) Submittal and transmittal distribution record.
- 18) Remarks.
- 19) Signature of transmitter.

### PART 2 - PRODUCTS

### 2.1 SUBMITTAL PROCEDURES

- A. General Submittal Procedure Requirements: Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.
  - 1. Submit electronic submittals via email as PDF electronic files.
    - a. Architect will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.
  - 2. Action Submittals: For paper submittals, submit seven paper copies of each submittal unless otherwise indicated. Architect will return two copies.
  - 3. Informational Submittals: Submit one digital copy of each submittal unless otherwise indicated. Architect will not return copies.
  - 4. Certificates and Certifications Submittals: Provide a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.
    - a. Provide a digital signature with digital certificate on electronically submitted certificates and certifications where indicated.
    - b. Provide a notarized statement on original paper copy certificates and certifications where indicated.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
  - 1. If information must be specially prepared for submittal because standard published data are not suitable for use, submit as Shop Drawings, not as Product Data.
  - 2. Mark each copy of each submittal to show which products and options are applicable.
  - 3. Include the following information, as applicable:
    - a. Manufacturer's catalog cuts.
    - b. Manufacturer's product specifications.
    - c. Standard color charts.
    - d. Statement of compliance with specified referenced standards.
    - e. Testing by recognized testing agency.
    - f. Application of testing agency labels and seals.
    - g. Notation of coordination requirements.
    - h. Availability and delivery time information.
  - 4. For equipment, include the following in addition to the above, as applicable:

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- a. Wiring diagrams showing factory-installed wiring.
- b. Printed performance curves.
- c. Operational range diagrams.
- d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.
- 5. Submit Product Data before or concurrent with Samples.
- 6. Submit Product Data in the following format:
  - a. PDF electronic file.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data, unless submittal based on Architect's digital data drawing files is otherwise permitted.
  - 1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
    - a. Identification of products.
    - b. Schedules.
    - c. Compliance with specified standards.
    - d. Notation of coordination requirements.
    - e. Notation of dimensions established by field measurement.
    - f. Relationship and attachment to adjoining construction clearly indicated.
    - g. Seal and signature of professional engineer if specified.
  - 2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches (215 by 280 mm), but no larger than 30 by 42 inches (750 by 1067 mm).
  - 3. Submit Shop Drawings in the following format:
    - a. PDF electronic file.
- D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.
  - 1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
  - 2. Identification: Attach label on unexposed side of Samples that includes the following:
    - a. Generic description of Sample.
    - b. Product name and name of manufacturer.
    - c. Sample source.
    - d. Number and title of applicable Specification Section.
    - e. Specification paragraph number and generic name of each item.
  - 3. For projects where electronic submittals are required, provide corresponding electronic submittal of Sample transmittal, digital image file illustrating Sample characteristics, and identification information for record.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 4. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
  - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
  - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
- 5. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
  - a. Number of Samples: Submit one full set(s) of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return submittal with options selected.
- 6. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
  - a. Number of Samples: Submit three sets of Samples. Architect will retain two Sample sets; remainder will be returned. Mark up and retain one returned Sample set as a project record sample.
    - 1) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least three sets of paired units that show approximate limits of variations.
- E. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
  - 1. Submit product schedule in the following format:
    - a. PDF electronic file.
- F. Coordination Drawing Submittals: Comply with requirements specified in Section 013100 "Project Management and Coordination."
- G. Contractor's Construction Schedule: Comply with requirements specified in Section 013200 "Construction Progress Documentation."
- H. Application for Payment and Schedule of Values: Comply with requirements specified in Section 012900 "Payment Procedures."
- I. Test and Inspection Reports and Schedule of Tests and Inspections Submittals: Comply with requirements specified in Section 014000 "Quality Requirements."

- J. Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Section 017700 "Closeout Procedures."
- K. Maintenance Data: Comply with requirements specified in Section 017823 "Operation and Maintenance Data."
- L. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- M. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of Welding Procedure Specification and Procedure Qualification Record on AWS forms. Include names of firms and personnel certified.
- N. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
- O. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
- P. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.
- Q. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.
- R. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
- S. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- T. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
  - 1. Name of evaluation organization.
  - 2. Date of evaluation.
  - 3. Time period when report is in effect.
  - 4. Product and manufacturers' names.
  - 5. Description of product.
  - 6. Test procedures and results.
  - 7. Limitations of use.

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- U. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
- V. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
- W. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
- X. Design Data: Prepare and submit written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.

### 2.2 DELEGATED-DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
  - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF electronic file and three paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.
  - 1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

### PART 3 - EXECUTION

### 3.1 CONTRACTOR'S REVIEW

- A. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Project Closeout and Maintenance Material Submittals: See requirements in Section 017700 "Closeout Procedures."

C. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

#### 3.2 ARCHITECT'S ACTION

- Action Submittals: Architect will review each submittal, make marks to indicate corrections or A. revisions required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.
- B. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- Partial submittals prepared for a portion of the Work will be reviewed when use of partial C. submittals has received prior approval from Architect.
- D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.
- E. Submittals not required by the Contract Documents may be returned by the Architect without action.

END OF SECTION 013300

# REQUEST FOR ELECTRONIC DRAWING FILES

PROJECT: University of South Carolina

USC Tennis Complex Locker Room Addition

Architect's Project No. 12.130.09

Data contained on these electronic files are part of Quackenbush Architects + Planners instruments of service and shall not be used by anyone receiving these files for any purpose other than a bid or submittal document. Any use of this file, either all or inpart, for other than its initial use as a bid or submittal document shall be full and sufficient cause to hold Quackenbush Architects + Planners (or their consultants) as author of the original electronic file harmless against any claim or liability resulting from any discrepancy, error or omission in the file's original or modified form.

Furthermore, you shall, to the fullest extent permitted by law, indemnify and hold Quackenbush Architects + Planners harmless against all damages, liabilities or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from your use of these electronic files.

Because information presented on the electronic files can be modified, unintentionally or otherwise, Quackenbush Architects + Planners reserves the right to remove all indications of ownership and/or involvement from each electronic display.

The transfer of the data or any copy of the data, in any form to a third party without the prior written consent of Quackenbush Architects + Planners shall not be permitted.

Under no circumstances shall delivery of the electronic files for use by you be deemed a sale by us, and we make no warranties, either express or implied of merchantability and fitness for any particular purpose. In no event shall Quackenbush Architects + Planners be liable for any loss of profit or any consequential damages as a result of your use or reuse of these electronic files.

Signing this letter indicates your agreement to the terms stated above and that you have the authority to bind your firm with respect to the terms stated above.

Accepted and Agreed by					
Printed Name		Company			
Title		Date			
Signature					
Sheets Requested					
Sheet No.	Sheet Title				

Architect's Project #: 12.130.09

## SECTION 014000 - QUALITY REQUIREMENTS

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
  - 1. Specific quality-assurance and -control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
  - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
  - 3. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.
  - 4. Specific test and inspection requirements are not specified in this Section.

### 1.3 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.
- C. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- D. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- E. Source Quality-Control Testing: Tests and inspections that are performed at the source, e.g., plant, mill, factory, or shop.
- F. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- G. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- H. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
  - 1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).
- I. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

### 1.4 CONFLICTING REQUIREMENTS

- A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

### 1.5 INFORMATIONAL SUBMITTALS

- A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.
- B. Qualification Data: For Contractor's quality-control personnel.

Re-Bid Set Issue Date: 06/05/2014

C. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility sent to authorities having jurisdiction before starting work on the following systems:

1. Seismic-force-resisting system, designated seismic system, or component listed in the designated seismic system quality-assurance plan prepared by Architect.

Architect's Project #: 12.130.09

- D. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- E. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
  - 1. Specification Section number and title.
  - 2. Entity responsible for performing tests and inspections.
  - 3. Description of test and inspection.
  - 4. Identification of applicable standards.
  - 5. Identification of test and inspection methods.
  - 6. Number of tests and inspections required.
  - 7. Time schedule or time span for tests and inspections.
  - 8. Requirements for obtaining samples.
  - 9. Unique characteristics of each quality-control service.

### 1.6 CONTRACTOR'S QUALITY-CONTROL PLAN

- A. Quality-Control Plan, General: Submit quality-control plan within 10 days of Notice to Proceed, and not less than five days prior to preconstruction conference. Submit in format acceptable to Architect. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities. Coordinate with Contractor's construction schedule.
- B. Quality-Control Personnel Qualifications: Engage qualified full-time personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.
  - 1. Project quality-control manager may also serve as Project superintendent.
- C. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.
- D. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:
  - 1. Contractor-performed tests and inspections including subcontractor-performed tests and inspections. Include required tests and inspections and Contractor-elected tests and inspections.
  - 2. Special inspections required by authorities having jurisdiction and indicated on the "Statement of Special Inspections."

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 3. Owner-performed tests and inspections indicated in the Contract Documents.
- E. Continuous Inspection of Workmanship: Describe process for continuous inspection during construction to identify and correct deficiencies in workmanship in addition to testing and inspection specified. Indicate types of corrective actions to be required to bring work into compliance with standards of workmanship established by Contract requirements and approved mockups.
- F. Monitoring and Documentation: Maintain testing and inspection reports including log of approved and rejected results. Include work Architect has indicated as nonconforming or defective. Indicate corrective actions taken to bring nonconforming work into compliance with requirements. Comply with requirements of authorities having jurisdiction.

#### 1.7 REPORTS AND DOCUMENTS

- Test and Inspection Reports: Prepare and submit certified written reports specified in other A. Sections. Include the following:
  - 1. Date of issue.
  - 2. Project title and number.
  - Name, address, and telephone number of testing agency. 3.
  - Dates and locations of samples and tests or inspections.
  - Names of individuals making tests and inspections.
  - Description of the Work and test and inspection method. 6.
  - 7. Identification of product and Specification Section.
  - Complete test or inspection data. 8.
  - Test and inspection results and an interpretation of test results. 9.
  - 10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
  - Comments or professional opinion on whether tested or inspected Work complies with 11. the Contract Document requirements.
  - Name and signature of laboratory inspector. 12.
  - Recommendations on retesting and reinspecting. 13.
- Prepare written information Manufacturer's Technical Representative's Field Reports: B. documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:
  - 1. Name, address, and telephone number of technical representative making report.
  - 2. Statement on condition of substrates and their acceptability for installation of product.
  - Statement that products at Project site comply with requirements. 3.
  - Summary of installation procedures being followed, whether they comply with 4. requirements and, if not, what corrective action was taken.
  - Results of operational and other tests and a statement of whether observed performance 5. complies with requirements.
  - Statement whether conditions, products, and installation will affect warranty. 6.
  - Other required items indicated in individual Specification Sections. 7.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:
  - 1. Name, address, and telephone number of factory-authorized service representative making report.
  - 2. Statement that equipment complies with requirements.
  - 3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
  - 4. Statement whether conditions, products, and installation will affect warranty.
  - 5. Other required items indicated in individual Specification Sections.
- D. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

### 1.8 QUALITY ASSURANCE

- A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- D. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar in material, design, and extent to those indicated for this Project.
- F. Specialists: Certain Specification Sections require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.
  - 1. Requirements of authorities having jurisdiction shall supersede requirements for specialists.
- G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according

to ASTM E 329; and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
- 2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.
- H. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- I. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- J. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:
  - 1. Build mockups in location and of size indicated or, if not indicated, as directed by Architect.
  - 2. Notify Architect seven days in advance of dates and times when mockups will be constructed.
  - 3. Employ supervisory personnel who will oversee mockup construction. Employ workers that will be employed during the construction at Project.
  - 4. Demonstrate the proposed range of aesthetic effects and workmanship.
  - 5. Obtain Architect's approval of mockups before starting work, fabrication, or construction.
    - a. Allow seven days for initial review and each re-review of each mockup.
  - 6. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
  - 7. Demolish and remove mockups when directed unless otherwise indicated.

### 1.9 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
  - 1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
  - 2. Payment for these services will be made from testing and inspecting allowances, as authorized by Change Orders.
  - 3. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.

e-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.

- 1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
- 2. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.
  - a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
- 3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
- 4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
- 5. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
- 6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Section 013300 "Submittal Procedures."
- D. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.
- E. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.
- F. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
  - 1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
  - 2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
  - 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
  - 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
  - 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 6. Do not perform any duties of Contractor.
- G. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
  - 1. Access to the Work.
  - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
  - Adequate quantities of representative samples of materials that require testing and 3. inspecting. Assist agency in obtaining samples.
  - 4. Facilities for storage and field curing of test samples.
  - Preliminary design mix proposed for use for material mixes that require control by testing 5.
  - Security and protection for samples and for testing and inspecting equipment at Project 6. site.
- H. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
  - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.

#### 1.10 SPECIAL TESTS AND INSPECTIONS

- A. Special Tests and Inspections: Owner will engage a qualified testing agency and special inspector to conduct special tests and inspections required by authorities having jurisdiction as the responsibility of Owner, as indicated in Statement of Special Inspections attached to this Section, and as follows:
  - 1. Verifying that manufacturer maintains detailed fabrication and quality-control procedures and reviews the completeness and adequacy of those procedures to perform the Work.
  - 2. Notifying Architect and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
  - Submitting a certified written report of each test, inspection, and similar quality-control 3. service to Architect with copy to Contractor and to authorities having jurisdiction.
  - 4. Submitting a final report of special tests and inspections at Substantial Completion, which includes a list of unresolved deficiencies.
  - Interpreting tests and inspections and stating in each report whether tested and inspected 5. work complies with or deviates from the Contract Documents.
  - 6. Retesting and reinspecting corrected work.

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

### PART 2 - PRODUCTS (Not Used)

### PART 3 - EXECUTION

### 3.1 TEST AND INSPECTION LOG

- A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:
  - 1. Date test or inspection was conducted.
  - 2. Description of the Work tested or inspected.
  - 3. Date test or inspection results were transmitted to Architect.
  - 4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

### 3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
  - 1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

### END OF SECTION 014000

# Quality Assurance Plan for Seismic Requirements (2012 IBC Section 1705.3)

Architect's Project #: 12.130.09

- 1) Seismic Force Resisting Systems
  - a) Masonry walls
- 2) Special inspections for the seismic force resisting systems in item 1 above are specified in "Schedule of Special Inspections".
- 3) Testing:
  - a) Provide certificates of compliance for concrete masonry units in accordance with specification section 042000, paragraph 1.5 prior to the commencement of construction.
  - b) Provide test reports of grout and mortar in accordance with specification section 04200, paragraph 1.5 and 3.11.
  - c) Testing of concrete is specified in specification section 033000, paragraph 3.9 D.
  - d) Testing of steel is specified in specification section 051200, paragraph 3.5
- 4) The type and frequency of masonry testing required is included in 042000, paragraph 3.11. The type and frequency of concrete testing is specified in specification section 033000, paragraph 3.9. The type and frequency of steel testing is specified in specification section 051200, paragraph 3.5.
- 5) The type and frequency of special inspections required are specified in, "Schedule of Special Inspections."
- 6) Testing and special inspection reports shall be distributed weekly to the Architect, Contractor, Owner, and Structural Engineer.
- 7) An engineer from Kyzer & Timmerman Structural Engineers, LLC will perform structural observations of the structural system for general conformance with the approved construction documents at significant construction stages and at completion of the structural system.
- 8) A report of each structural observation will be prepared and distributed to the architect for distribution to the Contractor and Owner.

# Quality Assurance Plan for Seismic Requirements (20012 IBC Section 1705.11.5 and 1705.11.6)

Architect's Project #: 12.130.09

- 1) Additional Systems and Structures
  - a) Piping systems and mechanical units containing flammable, combustible or highly toxic materials.
- 2) Special inspections for additional systems in structure in item 1 above are specified in "Schedule of Special Inspections".
- 3) Testing:
  - a) Submit certificates of compliance as required in Submittal paragraphs listed in specification reference column of "Schedule of Special Inspections."
- 4) Type and frequency of special inspections for additional systems are specified in "Schedule of Special Inspections."
- 5) Testing and special inspection reports shall be distributed weekly to the Architect, Contractor, Owner, and Engineer.
- 6) A representative from Quackenbush Architects + Planners will perform regular observations of the construction progress for general conformance with the approved construction documents.
- 7) An engineer from Swygert and Associates will perform mechanical observations of the mechanical and plumbing systems for general conformance with construction documents at significant construction stages and at completion of the project.
- 8) An engineer from Belka Engineering will perform mechanical observations of the electrical systems for general conformance with construction documents at significant construction stages and at completion of the project.
- 9) A report of each observation will be prepared and distributed to the Architect for distribution to the Contractor and Owner.

### Contractor's Statement of Responsibility Seismic Quality Assurance

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

To be completed by the General Contractor and every Subcontractor responsible for the construction of designated systems and components listed in the Seismic Quality Assurance Plan. Submit separate copies to the Building Official and the Owner.

**Project Name**: USC Tennis Complex Locker Room Addition

**Architect's Project No:** 12.130.09

Owner: University of South Carolina

A Seismic Quality Assurance Plan as required by Section 1705 of the 2012 International Building Code has been defined for this project. The required Seismic Quality Assurance program entitled "Quality Assurance Plan for Seismic Resistance" is an attachment to Section 014000 – Quality Requirements of the Project Specifications. The program designates building elements covered and references requiring Special Inspections that are part of the Seismic Quality Assurance Plan.

As a Contractor responsible for the construction of the designated systems and components listed in the quality assurance plan, I acknowledge the following:

- 1. We acknowledge awareness of the special requirements contained in the quality assurance plan.
- 2. We acknowledge that control will be exercised to obtain conformance with the construction documents approved by the Office of State Engineer (OSE).
- 3. Procedures will be maintained for exercising control within our organization to ensure compliance for the method and frequency of reporting, and for the distribution of the reports. (Attach description of the procedures to be instituted.)
- 4. Person(s) in our organization exercising control of the quality assurance plan requirements and their qualifications are identified in the attachment provided. (Attach list of personnel with qualifications.)

Submitted by:				
(True or Driet None of	F:)			
(Type or Print Name of )	ririii)			
(Type or Print Name of	Firm Owner, Partner or Corp. Sec.)			
Signature	Date			
Owner's Authorization:				
Signature	Date			

Submitted by:

### STATEMENT OF SPECIAL INSPECTIONS

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Project Name: <u>USC Tennis Complex Locker Room Addition</u>

**Architect's Project No:** 12.130.09

Architect/Engineer: Quackenbush Architects + Planners, Kyzer & Timmerman Structural Engineers, LLC

The following firms and/or individuals are designated to perform the Special Inspections of the material or work designated below. (*Ex: Foundations, Concrete, etc.*) The firms and/or individuals have the experience, qualifications, certifications and/or licenses required to perform the special inspections indicated.

Material/Work to be Inspected:	Concrete	
Firm/Individual Name:	Inspection service to be provided by the Owner	_
Address:	Inspection Agency to be determined	_
Material/Work to be Inspected:	Masonry	
	Inspection service to be provided by the Owner	
Address:	Inspection Agency to be determined	- -
Material/Work to be Inspected:	Structural Steel, Steel Deck	
Firm/Individual Name:	Inspection service to be provided by the Owner	_
Address:	Inspection Agency to be determined	_
Discrepancies shall be brought to	aspectors are indicated on the attached Schedule of the immediate attention of the Contractor so the pies of all test reports and test data shall be obtain	at corrective action can
(Print or Type Name of A/E Re	presentative)	
(Signature) (Date)		

### STATEMENT OF SPECIAL INSPECTIONS

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

**Project Name:** USC Tennis Complex Locker Room Addition

**Architect's Project No:** 12.130.09

Architect/Engineer: Quackenbush Architects + Planners, Belka Engineering Associates, Inc, Swygert &

Associates, Ltd.

The following firms and/or individuals are designated to perform the Special Inspections of the material or work designated below. (Ex: Anchoring, Hazardous Ductwork.) The firms and/or individuals have the

· ·	fications and/or licenses required to perform the special inspections indi-
Material/Work to be Inspected:	Mechanical & Plumbing Components
Firm/Individual Name:Address:	Inspection service to be provided by the Owner Inspection Agency to be determined
Material/Work to be Inspected:	Electrical Components
Firm/Individual Name: Address:	Inspection service to be provided by the Owner Inspection Agency to be determined
Discrepancies shall be brought t	aspectors are indicated on the attached Schedule of Special Inspections. of the immediate attention of the Contractor so that corrective action can pies of all test reports and test data shall be obtained from the inspectors
(Print or Type Name of A/E Rep	presentative)
(Signature) (Date)	

e-Bid Set Issue Date: 06/05/2014

## SCHEDULE OF SPECIAL INSPECTIONS (2 Pages)

Project Name: Athletic Village Tennis Complex Addition

State Project No: H27-6102-MJ

Owner: University of South Carolina

Special Inspection requirements based on Section 1704 of Chapter 17 of the 2012 International Building Code and Chapter 1 of the 2012 International Building Code

MATERIALS	TYPE OF INSPECTION	SPECIFICATION OR CODE REFERENCE	INSPECTION BY		
			ARCH	ENG	Testing Company
Soils	See sheet S3.1	See sheet S3.1			To be determined
Soils -	Compaction	Specification Section 31 20 00			
Subgrade	Once per 200 cubic yard	·			To be determined
SABC	Compaction after placement	Section 31 20 00			To be determined
Soil Fill	Suitability, each source	Section 31 20 00			To be determined
Concrete Foundations	See sheet S3.1	See sheet S3.1			To be determined
Concrete Masonry Units	See sheet S3.1	See sheet S3.1			To be determined
Structural Steel	See sheet S3.1	See sheet S3.1			To be determined
Structural Steel High strength Bolting (and mechanical fastening of metal deck)	See sheet S3.1	See sheet S3.1			To be determined
Structural Steel Weld- ing	See sheet S3.1	See sheet S3.1			To be determined
Suspended Ceiling Sys- tems	Inspection of installation and an- chorage of suspension system (Periodic)	Section 095123, International Building Code 2012Chapter 17 – ASCE7			To be determined
Footing & Foundation inspections	Inspection after excavation for footing of reinforcing steel and any formwork	International Building Code 2012 - 110.3.1			To be determined
Concrete slab & under floor inspec- tion	Inspection after in-slab or under- floor reinforcing and building ser- vice equipment, conduit, piping, etc are in place, but prior to concrete placement	International Building Code 2012 - 110.3.2			To be determined
Frame In- spections	Inspection of framing and items that will be concealed	International Building Code 2012 - 110.3.4			To be determined

Issue Date: 04/10/2014

MATERIALS	TYPE OF INSPECTION	SPECIFICATION OR CODE REFERENCE	INSPECTION BY		
			ARCH	ENG	Testing Company
Fire Resistance Penetration Inspections	Inspection of joint and penetration protection required by IBC 712 and IBC 713 before concealed from view	International Building Code 2012 - 110.3.6			To be determined
Energy Efficiency Inspections	Inspection to determine compliance with IBC Chapter 13	International Building Code 2012 - 110.3.7			To be determined
'	a) Envelope Insulation (R-Value)	Specification 04200, 071200			To be determined
	b) Fenestration U-Value	Specification 088000			To be determined
	c) Duct System R-Value	Specification 230700			To be determined
	d) HVAC & Water Heating Equipment efficiency				To be determined
Mechanical Inspections	Underground inspection after trenches or ditches are excavated and piping installed, prior to backfill in place.	International Mechanical Code 2012 - 107.1			To be determined
	Rough-in inspection prior to wall or ceiling membranes	International Mechanical Code 2012 - 107.1			To be determined
Plumbing Inspections	Underground inspection after trenches or ditches are excavated and piping installed, prior to backfill in place.	International Plumbing Code 2012 - 107.1			To be determined
	Rough-in inspection prior to wall or ceiling membranes	International Plumbing Code 2012 - 107.1			To be determined
Electrical Inspections	Underground inspection after trenches or ditches are excavated and conduit installed, prior to backfill in place.	National Electrical Code 2012			To be determined
	Rough-in inspection prior to wall or ceiling membranes	National Electrical Code 2012			To be determined
Architectural Mechanical	Architectural Components -Exterior Cladding	International Building Code 2012 – 1705.11.5 – ASCE-7			To be determined
Plumbing & Electrical Components - Seismic Isolation Systems	Mechanical Components -Above ceiling units and ductwork	International Building Code 2012 – 1705.11.6 – ASCE-7			To be determined
	Plumbing Components -NA (unless required by ASCE-7)	International Building Code 2012 – 1705.11.6 – ASCE-7			To be determined
	Electrical Components -NA (unless required by ASCE-7)	International Building Code 2012 – 1705.11.6 – ASCE-7			To be determined

END OF SECTION 014100

### SECTION 014200 - REFERENCES

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

### 1.3 INDUSTRY STANDARDS

A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.

B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.
  - 1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

### 1.4 ABBREVIATIONS AND ACRONYMS

- A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States."
- B. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.
  - 1. AABC Associated Air Balance Council; www.aabc.com.
  - 2. AAMA American Architectural Manufacturers Association; www.aamanet.org.
  - 3. AAPFCO Association of American Plant Food Control Officials; www.aapfco.org.
  - 4. AASHTO American Association of State Highway and Transportation Officials; www.transportation.org.
  - 5. AATCC American Association of Textile Chemists and Colorists; www.aatcc.org.
  - 6. ABMA American Bearing Manufacturers Association; www.americanbearings.org.
  - 7. ACI American Concrete Institute; (Formerly: ACI International); www.concrete.org.
  - 8. ACPA American Concrete Pipe Association; www.concrete-pipe.org.
  - 9. AEIC Association of Edison Illuminating Companies, Inc. (The); www.aeic.org.
  - 10. AF&PA American Forest & Paper Association; www.afandpa.org.
  - 11. AGA American Gas Association; www.aga.org.
  - 12. AHAM Association of Home Appliance Manufacturers; www.aham.org.
  - 13. AHRI Air-Conditioning, Heating, and Refrigeration Institute (The); www.ahrinet.org.
  - 14. AI Asphalt Institute; www.asphaltinstitute.org.
  - 15. AIA American Institute of Architects (The); www.aia.org.
  - 16. AISC American Institute of Steel Construction; www.aisc.org.
  - 17. AISI American Iron and Steel Institute; www.steel.org.
  - 18. AITC American Institute of Timber Construction; www.aitc-glulam.org.
  - 19. AMCA Air Movement and Control Association International, Inc.; www.amca.org.
  - 20. ANSI American National Standards Institute; www.ansi.org.
  - 21. AOSA Association of Official Seed Analysts, Inc.; www.aosaseed.com.
  - 22. APA APA The Engineered Wood Association; www.apawood.org.
  - 23. APA Architectural Precast Association; www.archprecast.org.
  - 24. API American Petroleum Institute; www.api.org.
  - 25. ARI Air-Conditioning & Refrigeration Institute; (See AHRI).
  - 26. ARI American Refrigeration Institute; (See AHRI).

- 27. ARMA Asphalt Roofing Manufacturers Association; www.asphaltroofing.org.
- 28. ASCE American Society of Civil Engineers; www.asce.org.
- 29. ASCE/SEI American Society of Civil Engineers/Structural Engineering Institute; (See ASCE).

Issue Date: 06/05/2014

- 30. ASHRAE American Society of Heating, Refrigerating and Air-Conditioning Engineers; www.ashrae.org.
- 31. ASME ASME International; (American Society of Mechanical Engineers); www.asme.org.
- 32. ASSE American Society of Safety Engineers (The); www.asse.org.
- 33. ASSE American Society of Sanitary Engineering; www.asse-plumbing.org.
- 34. ASTM ASTM International; (American Society for Testing and Materials International); www.astm.org.
- 35. ATIS Alliance for Telecommunications Industry Solutions; www.atis.org.
- 36. AWEA American Wind Energy Association; www.awea.org.
- 37. AWI Architectural Woodwork Institute; www.awinet.org.
- 38. AWMAC Architectural Woodwork Manufacturers Association of Canada; www.awmac.com.
- 39. AWPA American Wood Protection Association; (Formerly: American Wood-Preservers' Association); www.awpa.com.
- 40. AWS American Welding Society; www.aws.org.
- 41. AWWA American Water Works Association; www.awwa.org.
- 42. BHMA Builders Hardware Manufacturers Association; www.buildershardware.com.
- 43. BIA Brick Industry Association (The); www.gobrick.com.
- 44. BICSI BICSI, Inc.; www.bicsi.org.
- 45. BIFMA BIFMA International; (Business and Institutional Furniture Manufacturer's Association); www.bifma.com.
- 46. BISSC Baking Industry Sanitation Standards Committee; www.bissc.org.
- 47. BOCA BOCA; (Building Officials and Code Administrators International Inc.); (See ICC).
- 48. BWF Badminton World Federation; (Formerly: International Badminton Federation); www.bwfbadminton.org.
- 49. CDA Copper Development Association; www.copper.org.
- 50. CEA Canadian Electricity Association; www.electricity.ca.
- 51. CEA Consumer Electronics Association; www.ce.org.
- 52. CFFA Chemical Fabrics & Film Association, Inc.; www.chemicalfabricsandfilm.com.
- 53. CFSEI Cold-Formed Steel Engineers Institute; www.cfsei.org.
- 54. CGA Compressed Gas Association; www.cganet.com.
- 55. CIMA Cellulose Insulation Manufacturers Association; www.cellulose.org.
- 56. CISCA Ceilings & Interior Systems Construction Association; www.cisca.org.
- 57. CISPI Cast Iron Soil Pipe Institute; www.cispi.org.
- 58. CLFMI Chain Link Fence Manufacturers Institute; www.chainlinkinfo.org.
- 59. CPA Composite Panel Association; www.pbmdf.com.
- 60. CRI Carpet and Rug Institute (The); www.carpet-rug.org.
- 61. CRRC Cool Roof Rating Council; www.coolroofs.org.
- 62. CRSI Concrete Reinforcing Steel Institute; www.crsi.org.
- 63. CSA Canadian Standards Association; www.csa.ca.
- 64. CSA CSA International; (Formerly: IAS International Approval Services); www.csa-international.org.
- 65. CSI Construction Specifications Institute (The); www.csinet.org.
- 66. CSSB Cedar Shake & Shingle Bureau; www.cedarbureau.org.

67. CTI - Cooling Technology Institute; (Formerly: Cooling Tower Institute); www.cti.org.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 68. CWC Composite Wood Council; (See CPA).
- 69. DASMA Door and Access Systems Manufacturers Association; www.dasma.com.
- 70. DHI Door and Hardware Institute; www.dhi.org.
- 71. ECA Electronic Components Association; www.ec-central.org.
- 72. ECAMA Electronic Components Assemblies & Materials Association; (See ECA).
- 73. EIA Electronic Industries Alliance; (See TIA).
- 74. EIMA EIFS Industry Members Association; www.eima.com.
- 75. EJMA Expansion Joint Manufacturers Association, Inc.; www.ejma.org.
- 76. ESD ESD Association; (Electrostatic Discharge Association); www.esda.org.
- 77. ESTA Entertainment Services and Technology Association; (See PLASA).
- 78. EVO Efficiency Valuation Organization; www.evo-world.org.
- 79. FIBA Federation Internationale de Basketball; (The International Basketball Federation); www.fiba.com.
- 80. FIVB Federation Internationale de Volleyball; (The International Volleyball Federation); www.fivb.org.
- 81. FM Approvals FM Approvals LLC; www.fmglobal.com.
- 82. FM Global FM Global; (Formerly: FMG FM Global); www.fmglobal.com.
- 83. FRSA Florida Roofing, Sheet Metal & Air Conditioning Contractors Association, Inc.; www.floridaroof.com.
- 84. FSA Fluid Sealing Association; www.fluidsealing.com.
- 85. FSC Forest Stewardship Council U.S.; www.fscus.org.
- 86. GA Gypsum Association; www.gypsum.org.
- 87. GANA Glass Association of North America; www.glasswebsite.com.
- 88. GS Green Seal; www.greenseal.org.
- 89. HI Hydraulic Institute; www.pumps.org.
- 90. HI/GAMA Hydronics Institute/Gas Appliance Manufacturers Association; (See AHRI).
- 91. HMMA Hollow Metal Manufacturers Association; (See NAAMM).
- 92. HPVA Hardwood Plywood & Veneer Association; www.hpva.org.
- 93. HPW H. P. White Laboratory, Inc.; www.hpwhite.com.
- 94. IAPSC International Association of Professional Security Consultants; www.iapsc.org.
- 95. IAS International Approval Services; (See CSA).
- 96. ICBO International Conference of Building Officials; (See ICC).
- 97. ICC International Code Council; www.iccsafe.org.
- 98. ICEA Insulated Cable Engineers Association, Inc.; www.icea.net.
- 99. ICPA International Cast Polymer Alliance: www.icpa-hq.org.
- 100. ICRI International Concrete Repair Institute, Inc.; www.icri.org.
- 101. IEC International Electrotechnical Commission; www.iec.ch.
- 102. IEEE Institute of Electrical and Electronics Engineers, Inc. (The); www.ieee.org.
- 103. IES Illuminating Engineering Society; (Formerly: Illuminating Engineering Society of North America); www.ies.org.
- 104. IESNA Illuminating Engineering Society of North America; (See IES).
- 105. IEST Institute of Environmental Sciences and Technology; www.iest.org.
- 106. IGMA Insulating Glass Manufacturers Alliance; www.igmaonline.org.
- 107. IGSHPA International Ground Source Heat Pump Association; www.igshpa.okstate.edu.
- 108. ILI Indiana Limestone Institute of America, Inc.; www.iliai.com.
- 109. Intertek Intertek Group; (Formerly: ETL SEMCO; Intertek Testing Service NA); www.intertek.com.

110. ISA - International Society of Automation (The); (Formerly: Instrumentation, Systems, and Automation Society); www.isa.org.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 111. ISAS Instrumentation, Systems, and Automation Society (The); (See ISA).
- 112. ISFA International Surface Fabricators Association; (Formerly: International Solid Surface Fabricators Association); www.isfanow.org.
- 113. ISO International Organization for Standardization; www.iso.org.
- 114. ISSFA International Solid Surface Fabricators Association; (See ISFA).
- 115. ITU International Telecommunication Union; www.itu.int/home.
- 116. KCMA Kitchen Cabinet Manufacturers Association; www.kcma.org.
- 117. LMA Laminating Materials Association; (See CPA).
- 118. LPI Lightning Protection Institute; www.lightning.org.
- 119. MBMA Metal Building Manufacturers Association; www.mbma.com.
- 120. MCA Metal Construction Association; www.metalconstruction.org.
- 121. MFMA Maple Flooring Manufacturers Association, Inc.; www.maplefloor.org.
- 122. MFMA Metal Framing Manufacturers Association, Inc.; www.metalframingmfg.org.
- 123. MHIA Material Handling Industry of America; www.mhia.org.
- 124. MIA Marble Institute of America; www.marble-institute.com.
- 125. MMPA Moulding & Millwork Producers Association; (Formerly: Wood Moulding & Millwork Producers Association); www.wmmpa.com.
- 126. MPI Master Painters Institute; www.paintinfo.com.
- 127. MSS Manufacturers Standardization Society of The Valve and Fittings Industry Inc.; www.mss-hq.org.
- 128. NAAMM National Association of Architectural Metal Manufacturers; www.naamm.org.
- 129. NACE NACE International; (National Association of Corrosion Engineers International); www.nace.org.
- 130. NADCA National Air Duct Cleaners Association; www.nadca.com.
- 131. NAIMA North American Insulation Manufacturers Association; www.naima.org.
- 132. NBGQA National Building Granite Quarries Association, Inc.; www.nbgqa.com.
- 133. NCAA National Collegiate Athletic Association (The); www.ncaa.org.
- 134. NCMA National Concrete Masonry Association; www.ncma.org.
- 135. NEBB National Environmental Balancing Bureau; www.nebb.org.
- 136. NECA National Electrical Contractors Association; www.necanet.org.
- 137. NeLMA Northeastern Lumber Manufacturers Association; www.nelma.org.
- 138. NEMA National Electrical Manufacturers Association; www.nema.org.
- 139. NETA InterNational Electrical Testing Association; www.netaworld.org.
- 140. NFHS National Federation of State High School Associations; www.nfhs.org.
- 141. NFPA NFPA; (National Fire Protection Association); www.nfpa.org.
- 142. NFPA NFPA International; (See NFPA).
- 143. NFRC National Fenestration Rating Council; www.nfrc.org.
- 144. NHLA National Hardwood Lumber Association; www.nhla.com.
- 145. NLGA National Lumber Grades Authority; www.nlga.org.
- 146. NOFMA National Oak Flooring Manufacturers Association; (See NWFA).
- 147. NOMMA National Ornamental & Miscellaneous Metals Association; www.nomma.org.
- 148. NRCA National Roofing Contractors Association; www.nrca.net.
- 149. NRMCA National Ready Mixed Concrete Association; www.nrmca.org.
- 150. NSF NSF International; (National Sanitation Foundation International); www.nsf.org.
- 151. NSPE National Society of Professional Engineers; www.nspe.org.
- 152. NSSGA National Stone, Sand & Gravel Association; www.nssga.org.
- 153. NTMA National Terrazzo & Mosaic Association, Inc. (The); www.ntma.com.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 154. NWFA National Wood Flooring Association; www.nwfa.org.
- 155. PCI Precast/Prestressed Concrete Institute; www.pci.org.156. PDI Plumbing & Drainage Institute; www.pdionline.org.
- 157. PLASA PLASA; (Formerly: ESTA Entertainment Services and Technology Association); www.plasa.org.
- 158. RCSC Research Council on Structural Connections; www.boltcouncil.org.
- 159. RFCI Resilient Floor Covering Institute; www.rfci.com.
- 160. RIS Redwood Inspection Service; www.redwoodinspection.com.
- 161. SAE SAE International; (Society of Automotive Engineers); www.sae.org.
- 162. SCTE Society of Cable Telecommunications Engineers; www.scte.org.
- 163. SDI Steel Deck Institute; www.sdi.org.
- 164. SDI Steel Door Institute; www.steeldoor.org.
- 165. SEFA Scientific Equipment and Furniture Association; www.sefalabs.com.
- 166. SEI/ASCE Structural Engineering Institute/American Society of Civil Engineers; (See ASCE).
- 167. SIA Security Industry Association; www.siaonline.org.
- 168. SJI Steel Joist Institute; www.steeljoist.org.
- 169. SMA Screen Manufacturers Association; www.smainfo.org.
- 170. SMACNA Sheet Metal and Air Conditioning Contractors' National Association; www.smacna.org.
- 171. SMPTE Society of Motion Picture and Television Engineers; www.smpte.org.
- 172. SPFA Spray Polyurethane Foam Alliance; www.sprayfoam.org.
- 173. SPIB Southern Pine Inspection Bureau; www.spib.org.
- 174. SPRI Single Ply Roofing Industry; www.spri.org.
- 175. SRCC Solar Rating and Certification Corporation; www.solar-rating.org.
- 176. SSINA Specialty Steel Industry of North America; www.ssina.com.
- 177. SSPC SSPC: The Society for Protective Coatings; www.sspc.org.
- 178. STI Steel Tank Institute; www.steeltank.com.
- 179. SWI Steel Window Institute: www.steelwindows.com.
- 180. SWPA Submersible Wastewater Pump Association; www.swpa.org.
- 181. TCA Tilt-Up Concrete Association; www.tilt-up.org.
- 182. TCNA Tile Council of North America, Inc.; (Formerly: Tile Council of America); www.tileusa.com.
- 183. TEMA Tubular Exchanger Manufacturers Association, Inc.; www.tema.org.
- 184. TIA Telecommunications Industry Association; (Formerly: TIA/EIA Telecommunications Industry Association/Electronic Industries Alliance); www.tiaonline.org.
- 185. TIA/EIA Telecommunications Industry Association/Electronic Industries Alliance; (See TIA).
- 186. TMS The Masonry Society; www.masonrysociety.org.
- 187. TPI Truss Plate Institute; www.tpinst.org.
- 188. TPI Turfgrass Producers International; www.turfgrasssod.org.
- 189. TRI Tile Roofing Institute; www.tileroofing.org.
- 190. UBC Uniform Building Code; (See ICC).
- 191. UL Underwriters Laboratories Inc.; www.ul.com.
- 192. UNI Uni-Bell PVC Pipe Association; www.uni-bell.org.
- 193. USAV USA Volleyball; www.usavolleyball.org.
- 194. USGBC U.S. Green Building Council; www.usgbc.org.
- 195. USITT United States Institute for Theatre Technology, Inc.; www.usitt.org.
- 196. WASTEC Waste Equipment Technology Association; www.wastec.org.

- 197. WCLIB West Coast Lumber Inspection Bureau; www.wclib.org.
- 198. WCMA Window Covering Manufacturers Association; www.wcmanet.org.
- 199. WDMA Window & Door Manufacturers Association; www.wdma.com.
- 200. WI Woodwork Institute; (Formerly: WIC Woodwork Institute of California); www.wicnet.org.

Issue Date: 06/05/2014

- 201. WMMPA Wood Moulding & Millwork Producers Association; (See MMPA).
- 202. WSRCA Western States Roofing Contractors Association; www.wsrca.com.
- 203. WPA Western Wood Products Association; www.wwpa.org.
- C. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. This information is believed to be accurate as of the date of the Contract Documents.
  - 1. DIN Deutsches Institut für Normung e.V.; www.din.de.
  - 2. IAPMO International Association of Plumbing and Mechanical Officials; www.iapmo.org.
  - 3. ICC International Code Council; www.iccsafe.org.
  - 4. ICC-ES ICC Evaluation Service, LLC; www.icc-es.org.
- D. Federal Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. Information is subject to change and is up-to-date as of the date of the Contract Documents.
  - 1. COE Army Corps of Engineers; www.usace.army.mil.
  - 2. CPSC Consumer Product Safety Commission; www.cpsc.gov.
  - 3. DOC Department of Commerce; National Institute of Standards and Technology; www.nist.gov.
  - 4. DOD Department of Defense; http://dodssp.daps.dla.mil.
  - 5. DOE Department of Energy; www.energy.gov.
  - 6. EPA Environmental Protection Agency; www.epa.gov.
  - 7. FAA Federal Aviation Administration; www.faa.gov.
  - 8. FG Federal Government Publications; www.gpo.gov.
  - 9. GSA General Services Administration; www.gsa.gov.
  - 10. HUD Department of Housing and Urban Development; www.hud.gov.
  - 11. LBL Lawrence Berkeley National Laboratory; Environmental Energy Technologies Division; http://eetd.lbl.gov.
  - 12. OSHA Occupational Safety & Health Administration; www.osha.gov.
  - 13. SD Department of State; www.state.gov.
  - 14. TRB Transportation Research Board; National Cooperative Highway Research Program; www.trb.org.
  - 15. USDA Department of Agriculture; Agriculture Research Service; U.S. Salinity Laboratory; www.ars.usda.gov.
  - 16. USDA Department of Agriculture; Rural Utilities Service; www.usda.gov.
  - 17. USDJ Department of Justice; Office of Justice Programs; National Institute of Justice; www.ojp.usdoj.gov.
  - 18. USP U.S. Pharmacopeia; www.usp.org.
  - 19. USPS United States Postal Service; www.usps.com.

- E. Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the standards and regulations in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.
  - 1. CFR Code of Federal Regulations; Available from Government Printing Office; www.gpo.gov/fdsys.

Issue Date: 06/05/2014

- 2. DOD Department of Defense; Military Specifications and Standards; Available from Department of Defense Single Stock Point; http://dodssp.daps.dla.mil.
- 3. DSCC Defense Supply Center Columbus; (See FS).
- 4. FED-STD Federal Standard; (See FS).
- 5. FS Federal Specification; Available from Department of Defense Single Stock Point; http://dodssp.daps.dla.mil.
  - a. Available from Defense Standardization Program; www.dsp.dla.mil.
  - b. Available from General Services Administration; www.gsa.gov.
  - c. Available from National Institute of Building Sciences/Whole Building Design Guide; www.wbdg.org/ccb.
- 6. MILSPEC Military Specification and Standards; (See DOD).
- 7. USAB United States Access Board; www.access-board.gov.
- 8. USATBCB U.S. Architectural & Transportation Barriers Compliance Board; (See USAB).
- F. State Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.
  - 1. CBHF State of California; Department of Consumer Affairs; Bureau of Electronic Appliance and Repair, Home Furnishings and Thermal Insulation; www.bearhfti.ca.gov.
  - 2. CCR California Code of Regulations; Office of Administrative Law; California Title 24 Energy Code; www.calregs.com.
  - 3. CDHS California Department of Health Services; (See CDPH).
  - 4. CDPH California Department of Public Health; Indoor Air Quality Program; www.caliaq.org.
  - 5. CPUC California Public Utilities Commission; www.cpuc.ca.gov.
  - 6. SCAQMD South Coast Air Quality Management District; www.aqmd.gov.
  - 7. TFS Texas Forest Service; Forest Resource Development and Sustainable Forestry; http://txforestservice.tamu.edu.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 014200

## SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.

### B. Related Requirements:

1. Section 01 10 00 "Summary" for work restrictions and limitations on utility interruptions.

### 1.3 USE CHARGES

- A. General: Installation and removal of and use charges for temporary facilities shall be included in the Contract Sum unless otherwise indicated.
- B. Water and Sewer Service from Existing System: Water from Owner's existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.
- C. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

### 1.4 QUALITY ASSURANCE

- A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.
- C. Accessible Temporary Egress: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines and ICC/ANSI A117.1.

Architect's Project #: 12.130.09

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

### 1.5 PROJECT CONDITIONS

A. Temporary Use of Permanent Facilities: Engage Installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

### PART 2 - PRODUCTS

### 2.1 MATERIALS

- A. Temporary Partitions: Provide temporary partitions of wood stud construction separating the existing tennis courts from the construction area as follows:
  - 1. At opening locations with existing chain link fencing with windscreen provide 2x4 stud framing with 10-mil polyethylene sheet up to 8'-0" high. Provide air gap at top of partition for ventilation of construction area. At the contractors discretion, provide solid panel plywood partitions up to 24" a.f.f. for additional protection of the existing fencing.
  - 2. At court access opening locations without chain link fencing and windscreen provide 2x4 stud framing with plywood sheathing on courtside.

### 2.2 TEMPORARY FACILITIES

- A. Field Offices, General: Field Office Trailer is NOT required. Utilize the existing rooms on the lower level of the existing Tennis Facility as the construction field office.
  - 1. Protect and preserve all existing equipment that is to remain in like-new or current condition. Repair or replace any damage to the existing space. Vacate space at least 2 weeks prior to substantial completion or as directed by the owner.
- B. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment for construction operations.
  - 1. Store combustible materials apart from building.

### 2.3 EQUIPMENT

- A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.
- B. HVAC Equipment: Unless Owner authorizes use of permanent HVAC system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.
  - 1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
  - 2. Heating Units: Listed and labeled for type of fuel being consumed, by a qualified testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.

### PART 3 - EXECUTION

3.1

INSTALLATION, GENERAL

A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

### 3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Install temporary service or connect to existing service.
  - 1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.
- B. Water Service: Connect to Owner's existing water service facilities. Clean and maintain water service facilities in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.
- C. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.
- D. Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.
- E. Isolation of Work Areas in Occupied Facilities: Prevent dust, fumes, and odors from entering occupied areas.
- F. Ventilation and Humidity Control: Provide temporary ventilation required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed. Coordinate ventilation requirements to produce ambient condition required and minimize energy consumption.
  - 1. Provide dehumidification systems when required to reduce substrate moisture levels to level required to allow installation or application of finishes.
- G. Electric Power Service: Connect to Owner's existing electric power service. Maintain equipment in a condition acceptable to Owner.
- H. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.

1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

2. Install lighting for Project identification sign.

### 3.3 SUPPORT FACILITIES INSTALLATION

- A. Parking: Use designated areas of Owner's existing parking areas for construction personnel.
- B. Project Signs: Provide Project signs as indicated. Unauthorized signs are not permitted.
  - 1. Identification Signs: Provide Project identification signs as indicated on Drawings.
  - 2. Temporary Signs: Provide other signs as indicated and as required to inform public and individuals seeking entrance to Project.
    - a. Provide temporary, directional signs for construction personnel and visitors.
  - 3. Maintain and touchup signs so they are legible at all times.
- C. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of authorities having jurisdiction. Comply with progress cleaning requirements in Section 017300 "Execution."
- D. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.
  - 1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.
  - 2. The use of the existing tennis courts with lifts, hoists, cranes, and heavy equipment of any type is strictly prohibited.
- E. Existing Stair: The contractor, at his option, may demolish the lower run of the existing stair to provide equipment and material access to the project area. At Substantial Completion, reconstruct the removed portion of the stair and restore the remaining portion of the stairs to condition existing before initial demolition / use.
  - 1. Means of egress will be limited on the upper level due to construction activity, including a portion of the stair being removed. As such:
    - a. Provide protective coverings, barriers, devices, signs, or other procedures to protect stairs and hazardous opening.
    - b. Provide a temporary barrier on the upper level concourse not more than 75' from the main entrance gate stating the following:
      - "Do not enter Authorized Personnel Only"
  - 2. If any portion of the stairs or railings that is to remain in place during construction become damaged, restore damaged areas so no evidence remains of correction work

#### 3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.
  - 1. Provide temporary partitions that separate the work are from the existing tennis courts, fencing, and wind screen.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

2. Provide a temporary barrier on the upper level concourse not more than 75' from the main entrance gate stating the following

"Do not enter – Authorized Personnel Only

- B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.
  - 1. Comply with work restrictions specified in Section 011000 "Summary."
- C. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals so Project will be free of pests and their residues at Substantial Completion. Perform control operations lawfully, using environmentally safe materials.
- D. Security Enclosure and Lockup: Install temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each work day.
- E. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities.
  - 1. Where heating or cooling is needed and permanent enclosure is incomplete, insulate temporary enclosures.
- F. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire-prevention program.
  - 1. Prohibit smoking in construction areas.
  - 2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition according to requirements of authorities having jurisdiction.
  - 3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.

#### 3.5 MOISTURE AND MOLD CONTROL

A. Contractor's Moisture-Protection Plan: Avoid trapping water in finished work. Document visible signs of mold that may appear during construction.

B. Exposed Construction Phase: Before installation of weather barriers, when materials are subject

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Protect porous materials from water damage.
- 2. Protect stored and installed material from flowing or standing water.

to wetting and exposure and to airborne mold spores, protect as follows:

- 3. Keep porous and organic materials from coming into prolonged contact with concrete.
- 4. Remove standing water from decks.
- 5. Keep deck openings covered or dammed.
- C. Partially Enclosed Construction Phase: After installation of weather barriers but before full enclosure and conditioning of building, when installed materials are still subject to infiltration of moisture and ambient mold spores, protect as follows:
  - 1. Do not load or install drywall or other porous materials or components, or items with high organic content, into partially enclosed building.
  - 2. Keep interior spaces reasonably clean and protected from water damage.
  - 3. Periodically collect and remove waste containing cellulose or other organic matter.
  - 4. Discard or replace water-damaged material.
  - 5. Do not install material that is wet.
  - 6. Discard, replace, or clean stored or installed material that begins to grow mold.
  - 7. Perform work in a sequence that allows any wet materials adequate time to dry before enclosing the material in drywall or other interior finishes.
- D. Controlled Construction Phase of Construction: After completing and sealing of the building enclosure but prior to the full operation of permanent HVAC systems, maintain as follows:
  - 1. Control moisture and humidity inside building by maintaining effective dry-in conditions.
  - 2. Use permanent HVAC system to control humidity.
  - 3. Comply with manufacturer's written instructions for temperature, relative humidity, and exposure to water limits.
    - a. Hygroscopic materials that may support mold growth, including wood and gypsum-based products, that become wet during the course of construction and remain wet for 48 hours are considered defective.
    - b. Measure moisture content of materials that have been exposed to moisture during construction operations or after installation. Record readings beginning at time of exposure and continuing daily for 48 hours. Identify materials containing moisture levels higher than allowed. Report findings in writing to Architect.
    - c. Remove materials that cannot be completely restored to their manufactured moisture level within 48 hours.

#### 3.6 OPERATION, TERMINATION, AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Maintenance: Maintain facilities in good operating condition until removal.

- Re-Bid Set Issue Date: 06/05/2014
  - 1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.

- C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.
- D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
  - 1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
  - 2. At Substantial Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Section 017700 "Closeout Procedures."

END OF SECTION 015000

# Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

## SECTION 016000 - PRODUCT REQUIREMENTS

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.

#### B. Related Requirements:

- 1. Section 012300 "Alternates" for products selected under an alternate.
- 2. Section 012500 "Substitution Procedures" for requests for substitutions.
- 3. Section 014200 "References" for applicable industry standards for products specified.

#### 1.3 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
  - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
  - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
  - 3. Comparable Product: Product that is demonstrated and approved through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a specific manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of additional manufacturers named in the specification.

#### 1.4 ACTION SUBMITTALS

- A. Comparable Product Requests: Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
  - 1. Include data to indicate compliance with the requirements specified in "Comparable Products" Article.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
  - a. Form of Approval: As specified in Section 013300 "Submittal Procedures."
  - b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.
- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Section 013300 "Submittal Procedures." Show compliance with requirements.

#### 1.5 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.
  - 1. Each contractor is responsible for providing products and construction methods compatible with products and construction methods of other contractors.
  - 2. If a dispute arises between contractors over concurrently selectable but incompatible products, Architect will determine which products shall be used.

#### 1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

#### B. Delivery and Handling:

- 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
- 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
- 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.

Re-Bid Set Issue Date: 06/05/2014

4. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.

Architect's Project #: 12.130.09

## C. Storage:

- 1. Store products to allow for inspection and measurement of quantity or counting of units.
- 2. Store materials in a manner that will not endanger Project structure.
- 3. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
- 4. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
- 5. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
- 6. Protect stored products from damage and liquids from freezing.
- 7. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

#### 1.7 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
  - 1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
  - 2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.
  - 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
  - 2. Specified Form: When specified forms are included with the Specifications, prepare a written document using indicated form properly executed.
  - 3. See other Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Section 017700 "Closeout Procedures."

#### PART 2 - PRODUCTS

#### 2.1 PRODUCT SELECTION PROCEDURES

A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
- 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
- 3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
- 4. Where products are accompanied by the term "as selected," Architect will make selection.
- 5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
- 6. Or Equal: For products specified by name and accompanied by the term "or equal," or "or approved equal," or "or approved," comply with requirements in "Comparable Products" Article to obtain approval for use of an unnamed product.

#### B. Product Selection Procedures:

- 1. Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
- 2. Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.

#### 3. Products:

a. Nonrestricted List: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed, or an unnamed product, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product.

#### 4. Manufacturers:

- a. Nonrestricted List: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed, or a product by an unnamed manufacturer, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed manufacturer's product.
- 5. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.

Issue Date: 06/05/2014

- C. Visual Matching Specification: Where Specifications require "match Architect's sample", provide a product that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches.
  - 1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Section 012500 "Substitution Procedures" for proposal of product.
- D. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

#### 2.2 COMPARABLE PRODUCTS

- A. Conditions for Consideration: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:
  - 1. Evidence that the proposed product does not require revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
  - 2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
  - 3. Evidence that proposed product provides specified warranty.
  - 4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
  - 5. Samples, if requested.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

#### SECTION 017300 - EXECUTION

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 1.2 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work including, but not limited to, the following:
  - 1. Construction layout.
  - 2. Field engineering and surveying.
  - 3. Installation of the Work.
  - 4. Cutting and patching.
  - 5. Coordination of Owner-installed products.
  - 6. Progress cleaning.
  - 7. Starting and adjusting.
  - 8. Protection of installed construction.
  - 9. Correction of Work.

#### B. Related Requirements:

1. Section 011000 "Summary" for limits on use of Project site.

## 1.3 DEFINITIONS

- A. Cutting: Removal of in-place construction necessary to permit installation or performance of other work.
- B. Patching: Fitting and repair work required to restore construction to original conditions after installation of other work.

#### 1.4 QUALITY ASSURANCE

- A. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.
  - 1. Structural Elements: When cutting and patching structural elements, notify Architect of locations and details of cutting and await directions from Architect before proceeding. Shore, brace, and support structural elements during cutting and patching. Do not cut and

patch structural elements in a manner that could change their load-carrying capacity or increase deflection

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety. Operational elements include the following:
  - a. Primary operational systems and equipment.
  - b. Mechanical systems piping and ducts.
  - c. Fire-detection and -alarm systems.
  - d. Electrical wiring systems.
  - e. Operating systems of special construction.
- 3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety.
  - a. Water, moisture, or vapor barriers.
  - b. Membranes and flashings.
  - c. Equipment supports.
  - d. Piping, ductwork, vessels, and equipment.
  - e. Noise- and vibration-control elements and systems.
- 4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- B. Cutting and Patching Conference: Before proceeding, meet at Project site with parties involved in cutting and patching, including mechanical and electrical trades. Review areas of potential interference and conflict. Coordinate procedures and resolve potential conflicts before proceeding.
- C. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of products and equipment.

## PART 2 - PRODUCTS

#### 2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.
- B. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.

Re-Bid Set Issue Date: 06/05/2014

1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place materials.

Architect's Project #: 12.130.09

#### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Existing Conditions: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities, mechanical and electrical systems, and other construction affecting the Work.
  - 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; underground electrical services, and other utilities.
  - 2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
  - 1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
  - 2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
  - 3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Written Report: Where a written report listing conditions detrimental to performance of the Work is required by other Sections, include the following:
  - 1. Description of the Work.
  - 2. List of detrimental conditions, including substrates.
  - 3. List of unacceptable installation tolerances.
  - 4. Recommended corrections.
- D. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

#### 3.2 PREPARATION

A. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before

Re-Bid Set Issue Date: 06/05/2014

fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

Architect's Project #: 12.130.09

- B. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- C. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents caused by differing field conditions outside the control of Contractor, submit a request for information to Architect according to requirements in Section 013100 "Project Management and Coordination."

#### 3.3 CONSTRUCTION LAYOUT

- A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks. If discrepancies are discovered, notify Architect promptly.
- B. General: Lay out the Work using accepted surveying practices.
  - 1. Establish benchmarks and control points to set lines and levels at each story of construction and elsewhere as needed to locate each element of Project.
  - 2. Establish limits on use of Project site.
  - 3. Establish dimensions within tolerances indicated. Do not scale Drawings to obtain required dimensions.
  - 4. Inform installers of lines and levels to which they must comply.
  - 5. Check the location, level and plumb, of every major element as the Work progresses.
  - 6. Notify Architect when deviations from required lines and levels exceed allowable tolerances.
- C. Building Lines and Levels: Locate and lay out control lines and levels for structures, building foundations, column grids, and floor levels, including those required for mechanical and electrical work. Transfer survey markings and elevations for use with control lines and levels. Level foundations and piers from two or more locations.

#### 3.4 FIELD ENGINEERING

- A. Identification: Owner will identify existing benchmarks, control points, and property corners.
- B. Reference Points: Locate existing permanent benchmarks, control points, and similar reference points before beginning the Work. Preserve and protect permanent benchmarks and control points during construction operations.
  - 1. Do not change or relocate existing benchmarks or control points without prior written approval of Architect. Report lost or destroyed permanent benchmarks or control points promptly. Report the need to relocate permanent benchmarks or control points to Architect before proceeding.
  - 2. Replace lost or destroyed permanent benchmarks and control points promptly. Base replacements on the original survey control points.

#### 3.5 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
  - 1. Make vertical work plumb and make horizontal work level.
  - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 3. Conceal pipes, ducts, and wiring in finished areas unless otherwise indicated.
- 4. Maintain minimum headroom clearance and ceiling heights specified. Notify the Architect if ceiling heights cannot be reasonably achieved through coordination between trades and if any obstruction less than 96" is encountered.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on site and placement in permanent locations.
- F. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- G. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions.
  - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
  - 2. Allow for building movement, including thermal expansion and contraction.
  - 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.
- I. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
- J. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

#### 3.6 CUTTING AND PATCHING

- A. Cutting and Patching, General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
  - 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Temporary Support: Provide temporary support of work to be cut.
- C. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- D. Adjacent Occupied Areas: Where interference with use of adjoining areas or interruption of free passage to adjoining areas is unavoidable, coordinate cutting and patching according to requirements in Section 011000 "Summary."
- E. Existing Utility Services and Mechanical/Electrical Systems: Where existing services/systems are required to be removed, relocated, or abandoned, bypass such services/systems before cutting to minimize interruption to occupied areas.
- F. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
  - 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
  - 2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
  - 3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
  - 4. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
  - 5. Proceed with patching after construction operations requiring cutting are complete.
- G. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other work. Patch with durable seams that are as invisible as practicable. Provide materials and comply with installation requirements specified in other Sections, where applicable.
  - 1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
  - 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will minimize evidence of patching and refinishing.

a. Clean piping, conduit, and similar features before applying paint or other finishing materials.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- b. Restore damaged pipe covering to its original condition.
- 3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.
  - a. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch. Provide additional coats until patch blends with adjacent surfaces.
- 4. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition and ensures thermal and moisture integrity of building enclosure.
- H. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

#### 3.7 OWNER-INSTALLED PRODUCTS

- A. Site Access: Provide access to Project site for Owner's construction personnel.
- B. Coordination: Coordinate construction and operations of the Work with work performed by Owner's construction personnel.
  - 1. Construction Schedule: Inform Owner of Contractor's preferred construction schedule for Owner's portion of the Work. Adjust construction schedule based on a mutually agreeable timetable. Notify Owner if changes to schedule are required due to differences in actual construction progress.
  - 2. Preinstallation Conferences: Include Owner's construction personnel at preinstallation conferences covering portions of the Work that are to receive Owner's work. Attend preinstallation conferences conducted by Owner's construction personnel if portions of the Work depend on Owner's construction.

## 3.8 PROGRESS CLEANING

- A. General: Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.
  - 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
  - 2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F (27 deg C).
  - 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.

- a. Use containers intended for holding waste materials of type to be stored.
- 4. Coordinate progress cleaning for joint-use areas where Contractor and other contractors are working concurrently.

Issue Date: 06/05/2014

- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
  - 1. Remove liquid spills promptly.
  - 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.
- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.
- F. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways. Comply with waste disposal requirements in Section 015000 "Temporary Facilities and Controls."
- H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- J. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

#### 3.9 STARTING AND ADJUSTING

- A. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- B. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.

e-Bid Set

Issue Date: 06/05/2014

C. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties.

Architect's Project #: 12.130.09

D. Manufacturer's Field Service: Comply with qualification requirements in Section 014000 "Quality Requirements."

## 3.10 PROTECTION OF INSTALLED CONSTRUCTION

Replace damaged and malfunctioning controls and equipment.

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.

END OF SECTION 017300

Issue Date: 06/05/2014

#### SECTION 017700 - CLOSEOUT PROCEDURES

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
  - 1. Substantial Completion procedures.
  - 2. Final completion procedures.
  - 3. Warranties.
  - 4. Final cleaning.
  - 5. Repair of the Work.

## B. Related Requirements:

- 1. Section 017300 "Execution" for progress cleaning of Project site.
- 2. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.
- 3. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For cleaning agents.
- B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- C. Certified List of Incomplete Items: Final submittal at Final Completion.

#### 1.4 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.
- C. Field Report: For pest control inspection.

# Issue Date: 06/05/2014

Architect's Project #: 12.130.09

#### 1.5 MAINTENANCE MATERIAL SUBMITTALS

Schedule of Maintenance Material Items: For maintenance material submittal items specified in A. other Sections.

#### 1.6 SUBSTANTIAL COMPLETION PROCEDURES

- A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.
- B. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
  - 1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
  - 2. Submit closeout submittals specified in other Division 01 Sections, including project record documents, operation and maintenance manuals, final completion construction photographic documentation, damage or settlement surveys, property surveys, and similar final record information.
  - 3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
  - Submit maintenance material submittals specified in individual Sections, including tools, 4. spare parts, extra materials, and similar items, and deliver to location designated by Architect. Label with manufacturer's name and model number where applicable.
    - Schedule of Maintenance Material Items: Prepare and submit schedule of a. maintenance material submittal items, including name and quantity of each item and name and number of related Specification Section. Obtain Architect's signature for receipt of submittals.
  - 5. Submit test/adjust/balance records.
  - Submit changeover information related to Owner's occupancy, use, operation, and 6. maintenance.
- C. Procedures Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
  - 1. Advise Owner of pending insurance changeover requirements.
  - 2. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
  - 3. Complete startup and testing of systems and equipment.
  - Perform preventive maintenance on equipment used prior to Substantial Completion. 4.
  - Instruct Owner's personnel in operation, adjustment, and maintenance of products, 5. equipment, and systems.

6. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 7. Complete final cleaning requirements, including touchup painting.
- 8. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- D. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 10 days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.
  - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
  - 2. Results of completed inspection will form the basis of requirements for final completion.

#### 1.7 FINAL COMPLETION PROCEDURES

- A. Submittals Prior to Final Completion: Before requesting final inspection for determining final completion, complete the following:
  - 1. Submit a final Application for Payment according to Section 012900 "Payment Procedures."
  - 2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
  - 3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
- B. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 10 days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
  - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

## 1.8 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
  - 1. Organize list of spaces in sequential order, starting with exterior areas first.

Re-Bid Set Issue Date: 06/05/2014

2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.

Architect's Project #: 12.130.09

- 3. Include the following information at the top of each page:
  - a. Project name.
  - b. Date.
  - c. Name of Architect.
  - d. Name of Contractor.
  - e. Page number.
- 4. Submit list of incomplete items in the following format:
  - a. MS Excel electronic file. Architect will return annotated file.
  - b. PDF electronic file. Architect will return annotated file.

## 1.9 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated, or when delay in submittal of warranties might limit Owner's rights under warranty.
- B. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.
  - 1. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch (215-by-280-mm) paper.
  - 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
  - 3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
  - 4. Warranty Electronic File: Scan warranties and bonds and assemble complete warranty and bond submittal package into a single indexed electronic PDF file with links enabling navigation to each item. Provide bookmarked table of contents at beginning of document.
- C. Provide additional copies of each warranty to include in operation and maintenance manuals.

#### PART 2 - PRODUCTS

#### 2.1 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

FINAL CLEANING

# PART 3 - EXECUTION

3.1

# A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.

- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
  - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
    - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
- c. Remove tools, construction equipment, machinery, and surplus material from Project site.
- d. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
- e. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
- f. Sweep concrete floors broom clean in unoccupied spaces.
- g. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.
- h. Remove labels that are not permanent.
- i. Wipe surfaces of mechanical and electrical equipment and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
- j. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
- k. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
- 1. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency.
- m. Leave Project clean and ready for occupancy.
- C. Construction Waste Disposal: Comply with waste disposal requirements in Section 015000 "Temporary Facilities and Controls."

## 3.2 REPAIR OF THE WORK

A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Repair or remove and replace defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.
  - 1. Remove and replace chipped, scratched, and broken glass, reflective surfaces, and other damaged transparent materials.
  - 2. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that that already show evidence of repair or restoration.
    - a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.
  - 3. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.
  - 4. Replace burned-out bulbs, bulbs noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.

END OF SECTION 017700

## SECTION 017823 - OPERATION AND MAINTENANCE DATA

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
  - 1. Operation and maintenance documentation directory.
  - 2. Emergency manuals.
  - 3. Operation manuals for systems, subsystems, and equipment.
  - 4. Product maintenance manuals.
  - 5. Systems and equipment maintenance manuals.

## B. Related Requirements:

1. Section 013300 "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.

#### 1.3 DEFINITIONS

- A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.
- B. Subsystem: A portion of a system with characteristics similar to a system.

#### 1.4 CLOSEOUT SUBMITTALS

- A. Manual Content: Operations and maintenance manual content is specified in individual Specification Sections to be reviewed at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.
  - 1. Architect will comment on whether content of operations and maintenance submittals are acceptable.
  - 2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.
- B. Format: Submit operations and maintenance manuals in the following format:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- Re-Bid Set Issue Date: 06/05/2014
  - 1. PDF electronic file. Assemble each manual into a composite electronically indexed file. Submit on digital media acceptable to Architect.
    - a. Name each indexed document file in composite electronic index with applicable item name. Include a complete electronically linked operation and maintenance directory.

- b. Enable inserted reviewer comments on draft submittals.
- 2. Two paper copies. Include a complete operation and maintenance directory. Enclose title pages and directories in clear plastic sleeves. Architect will return two copies to te owner after varification.
- C. Initial Manual Submittal: Submit draft copy of each manual at least 30 days before commencing demonstration and training. Architect will comment on whether general scope and content of manual are acceptable.
- D. Final Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Architect will return copy with comments.
  - 1. Correct or revise each manual to comply with Architect's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's comments and prior to commencing demonstration and training.

## PART 2 - PRODUCTS

#### 2.1 OPERATION AND MAINTENANCE DOCUMENTATION DIRECTORY

- A. Directory: Prepare a single, comprehensive directory of emergency, operation, and maintenance data and materials, listing items and their location to facilitate ready access to desired information. Include a section in the directory for each of the following:
  - 1. List of documents.
  - 2. List of systems.
  - 3. List of equipment.
  - 4. Table of contents.
- B. List of Systems and Subsystems: List systems alphabetically. Include references to operation and maintenance manuals that contain information about each system.
- C. List of Equipment: List equipment for each system, organized alphabetically by system. For pieces of equipment not part of system, list alphabetically in separate list.
- D. Tables of Contents: Include a table of contents for each emergency, operation, and maintenance manual.
- E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the

Issue Date: 06/05/2014

Contract Documents. If no designation exists, assign a designation according to ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

Architect's Project #: 12.130.09

#### 2.2 **OPERATION MANUALS**

- A. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:
  - System, subsystem, and equipment descriptions. Use designations for systems and 1. equipment indicated on Contract Documents.
  - 2. Performance and design criteria if Contractor has delegated design responsibility.
  - Operating standards. 3.
  - Operating procedures. 4.
  - 5. Operating logs.
  - Wiring diagrams. 6.
  - Control diagrams. 7.
  - Piped system diagrams. 8.
  - 9. Precautions against improper use.
  - License requirements including inspection and renewal dates. 10.

#### B. Descriptions: Include the following:

- 1. Product name and model number. Use designations for products indicated on Contract Documents.
- 2. Manufacturer's name.
- Equipment identification with serial number of each component. 3.
- Equipment function.
- Operating characteristics. 5.
- Limiting conditions. 6.
- Performance curves. 7.
- 8. Engineering data and tests.
- 9. Complete nomenclature and number of replacement parts.

#### C. Operating Procedures: Include the following, as applicable:

- 1. Startup procedures.
- Equipment or system break-in procedures. 2.
- Routine and normal operating instructions. 3.
- Regulation and control procedures. 4.
- 5. Instructions on stopping.
- 6. Normal shutdown instructions.
- 7. Seasonal and weekend operating instructions.
- Required sequences for electric or electronic systems. 8.
- 9. Special operating instructions and procedures.
- D. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

E. Piped Systems: Diagram piping as installed, and identify color-coding where required for identification.

#### 2.3 PRODUCT MAINTENANCE MANUALS

- Content: Organize manual into a separate section for each product, material, and finish. A. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
- Source Information: List each product included in manual, identified by product name and B. arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.
- C. Product Information: Include the following, as applicable:
  - 1. Product name and model number.
  - 2. Manufacturer's name.
  - 3. Color, pattern, and texture.
  - Material and chemical composition. 4.
  - Reordering information for specially manufactured products. 5.
- Maintenance Procedures: Include manufacturer's written recommendations and the following: D.
  - 1. Inspection procedures.
  - Types of cleaning agents to be used and methods of cleaning. 2.
  - List of cleaning agents and methods of cleaning detrimental to product. 3.
  - Schedule for routine cleaning and maintenance. 4.
  - 5. Repair instructions.
- E. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.
- F. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
  - 1. Include procedures to follow and required notifications for warranty claims.

#### 2.4 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

- Content: For each system, subsystem, and piece of equipment not part of a system, include A. source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranty and bond information, as described below.
- В. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product,

Issue Date: 06/05/2014

list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.

- C. Manufacturers' Maintenance Documentation: Manufacturers' maintenance documentation including the following information for each component part or piece of equipment:
  - 1. Standard maintenance instructions and bulletins.
  - 2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
  - 3. Identification and nomenclature of parts and components.
  - 4. List of items recommended to be stocked as spare parts.
- D. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:
  - 1. Test and inspection instructions.
  - 2. Troubleshooting guide.
  - 3. Precautions against improper maintenance.
  - 4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
  - 5. Aligning, adjusting, and checking instructions.
  - 6. Demonstration and training video recording, if available.
- E. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.
  - 1. Scheduled Maintenance and Service: Tabulate actions for daily, weekly, monthly, quarterly, semiannual, and annual frequencies.
  - 2. Maintenance and Service Record: Include manufacturers' forms for recording maintenance.
- F. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.
- G. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
  - 1. Include procedures to follow and required notifications for warranty claims.

#### PART 3 - EXECUTION

#### 3.1 MANUAL PREPARATION

A. Operation and Maintenance Documentation Directory: Prepare a separate manual that provides an organized reference to emergency, operation, and maintenance manuals.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- B. Emergency Manual: Assemble a complete set of emergency information indicating procedures for use by emergency personnel and by Owner's operating personnel for types of emergencies indicated.
- C. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.
- D. Operation and Maintenance Manuals: Assemble a complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.
  - 1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
  - 2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.
- E. Manufacturers' Data: Where manuals contain manufacturers' standard printed data, include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
  - 1. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.
- F. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.
  - 1. Do not use original project record documents as part of operation and maintenance manuals.
  - 2. Comply with requirements of newly prepared record Drawings in Section 017839 "Project Record Documents."
- G. Comply with Section 017700 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

END OF SECTION 017823

## SECTION 017839 - PROJECT RECORD DOCUMENTS

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for project record documents, including the following:
  - 1. Record Drawings.
  - 2. Record Product Data.
  - 3. Miscellaneous record submittals.
- B. Related Requirements:
  - 1. Section 017700 "Closeout Procedures" for general closeout procedures.
  - 2. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.

## 1.3 CLOSEOUT SUBMITTALS

- A. Record Drawings: Comply with the following:
  - 1. Number of Copies: Submit copies of record Drawings as follows:
    - a. Initial Submittal:
      - 1) Submit PDF electronic files of scanned record prints.
      - 2) Architect will indicate whether general scope of changes, additional information recorded, and quality of drafting are acceptable.
    - b. Final Submittal:
      - 1) Submit PDF electronic files of scanned record prints and 1 set(s) of prints.
      - 2) Print each drawing, whether or not changes and additional information were recorded.
- B. Record Product Data: Submit annotated PDF electronic files and directories of each submittal.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Re-Bid Set Issue Date: 06/05/2014

1. Where record Product Data are required as part of operation and maintenance manuals, submit duplicate marked-up Product Data as a component of manual.

Architect's Project #: 12.130.09

C. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Submit annotated PDF electronic files and directories of each submittal.

#### PART 2 - PRODUCTS

#### 2.1 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.
  - 1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
    - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
    - b. Accurately record information in an acceptable drawing technique.
    - c. Record data as soon as possible after obtaining it.
    - d. Record and check the markup before enclosing concealed installations.
  - 2. Content: Types of items requiring marking include, but are not limited to, the following:
    - a. Dimensional changes to Drawings.
    - b. Revisions to details shown on Drawings.
    - c. Revisions to routing of piping and conduits.
    - d. Revisions to electrical circuitry.
    - e. Actual equipment locations.
    - f. Duct size and routing.
    - g. Locations of concealed internal utilities.
    - h. Changes made by Change Order or Construction Change Directive.
    - i. Changes made following Architect's written orders.
    - j. Details not on the original Contract Drawings.
    - k. Field records for variable and concealed conditions.
    - 1. Record information on the Work that is shown only schematically.
  - 3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
  - 4. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
  - 5. Mark important additional information that was either shown schematically or omitted from original Drawings.

- Re-Bid Set Issue Date: 06/05/2014
  - 6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

- B. Format: Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.
  - 1. Record Prints: Organize record prints into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
  - 2. Format: Annotated PDF electronic file with comment function enabled.
  - 3. Identification: As follows:
    - a. Project name.
    - b. Date.
    - c. Designation "PROJECT RECORD DRAWINGS."
    - d. Name of Architect.
    - e. Name of Contractor.

#### 2.2 RECORD PRODUCT DATA

- A. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.
  - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
  - 2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
  - 3. Note related Change Orders and record Drawings where applicable.
- B. Format: Submit record Product Data as annotated PDF electronic file.
  - 1. Include record Product Data directory organized by Specification Section number and title, electronically linked to each item of record Product Data.

## 2.3 MISCELLANEOUS RECORD SUBMITTALS

- A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.
- B. Format: Submit miscellaneous record submittals as PDF electronic file or scanned PDF electronic file(s) of marked-up miscellaneous record submittals.
  - 1. Include miscellaneous record submittals directory organized by Specification Section number and title, electronically linked to each item of miscellaneous record submittals.

#### **PART 3 - EXECUTION**

#### 3.1 RECORDING AND MAINTENANCE

- A. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.
- B. Maintenance of Record Documents and Samples: Store record documents and Samples in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Architect's reference during normal working hours.

END OF SECTION 017839

Issue Date: 06/05/2014

# SECTION 024119 - SELECTIVE DEMOLITION

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

#### A. Section Includes:

- 1. Demolition and removal of selected portions of building or structure.
- 2. Demolition and removal of selected site elements.

#### B. Related Requirements:

- 1. Section 011000 "Summary" for restrictions on the use of the premises, Owner-occupancy requirements, and phasing requirements.
- 2. Section 017300 "Execution" for cutting and patching procedures.

#### 1.3 DEFINITIONS

- A. Remove: Detach items from existing construction and legally dispose of them off-site unless indicated to be removed and salvaged or removed and reinstalled.
- B. Remove and Salvage: Carefully detach from existing construction, in a manner to prevent damage, and deliver to Owner.
- C. Remove and Reinstall: Detach items from existing construction, prepare for reuse, and reinstall where indicated.
- D. Existing to Remain: Existing items of construction that are not to be permanently removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

#### 1.4 MATERIALS OWNERSHIP

- A. Unless otherwise indicated, demolition waste becomes property of Contractor.
- B. Historic items, relics, antiques, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, and other items of interest or value to Owner that may be uncovered during demolition remain the property of Owner.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

1. Carefully salvage in a manner to prevent damage and promptly return to Owner.

#### 1.5 PREINSTALLATION MEETINGS

- A. Pre-demolition Conference: Conduct conference at Project site.
  - 1. Inspect and discuss condition of construction to be selectively demolished.
  - 2. Review structural load limitations of existing structure.
  - Review and finalize selective demolition schedule and verify availability of materials, 3. demolition personnel, equipment, and facilities needed to make progress and avoid
  - 4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
  - Review areas where existing construction is to remain and requires protection. 5.

#### 1.6 INFORMATIONAL SUBMITTALS

- A. Proposed Protection Measures: Submit report, including drawings, that indicates the measures proposed for protecting individuals and property, for dust control. Indicate proposed locations and construction of barriers.
- B. Schedule of Selective Demolition Activities: Indicate the following:
  - 1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure occupants on-site operations are uninterrupted.
  - 2. Interruption of utility services. Indicate how long utility services will be interrupted.
  - Coordination for shutoff, capping, and continuation of utility services. 3.
  - Coordination of Owner's continuing occupancy of portions of existing building and of 4. Owner's partial occupancy of completed Work.
- C. Inventory: Submit a list of items to be removed and salvaged and deliver to Owner prior to start of demolition.
- Pre-demolition Photographs or Video: Submit before Work begins. D.
- E. Warranties: Documentation indicated that existing warranties are still in effect after completion of selective demolition.

#### 1.7 **CLOSEOUT SUBMITTALS**

Inventory: Submit a list of items that have been removed and salvaged. A.

#### 1.8 **OUALITY ASSURANCE**

Refrigerant Recovery Technician Qualifications: Certified by an EPA-approved certification A. program.

Issue Date: 06/05/2014

#### 1.9 FIELD CONDITIONS

- A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.
- B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
  - 1. Before selective demolition, Owner will remove the following items:
    - a. Furnishings and equipment.
- C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- D. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.
  - 1. HAZMAT Survey will be conducted by the owner and, if found, Hazardous materials will be removed by Owner before start of the Work.
- E. Storage or sale of removed items or materials on-site is not permitted.
- F. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
  - 1. Maintain fire-protection facilities in service during selective demolition operations.

#### 1.10 WARRANTY

- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties. Notify warrantor before proceeding.
- B. Notify warrantor on completion of selective demolition, and obtain documentation verifying that existing system has been inspected and warranty remains in effect. Submit documentation at Project closeout.

#### PART 2 - PRODUCTS

#### 2.1 PEFORMANCE REQUIREMENTS

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ANSI/ASSE A10.6 and NFPA 241.

Issue Date: 06/05/2014

### **PART 3 - EXECUTION**

#### 3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped before starting selective demolition operations.
- B. Review record documents of existing construction provided by Owner. Owner does not guarantee that existing conditions are same as those indicated in record documents.
- C. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- D. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Architect.
- E. Survey of Existing Conditions: Record existing conditions by use of measured drawings and preconstruction photographs.
  - 1. Before selective demolition or removal of existing building elements that will be reproduced or duplicated in final Work, make permanent record of measurements, materials, and construction details required to make exact reproduction.

# 3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.
  - 1. Comply with requirements for existing services/systems interruptions specified in Section 011000 "Summary."
- B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off indicated utility services and mechanical/electrical systems serving areas to be selectively demolished.
  - 1. Arrange to shut off indicated utilities with utility companies.
  - 2. If services/systems are required to be removed, relocated, or abandoned, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
  - 3. Disconnect, demolish, and remove plumbing and electrical systems, equipment, and components indicated to be removed.
    - a. Piping to Be Removed: Remove portion of piping indicated to be removed and cap or plug remaining piping with same or compatible piping material.
    - b. Piping to Be Abandoned in Place: Drain piping and cap or plug piping with same or compatible piping material.
    - c. Equipment to Be Removed: Disconnect and cap services and remove equipment.

Re-Bid Set

Issue Date: 06/05/2014

d. Equipment to Be Removed and Reinstalled: Disconnect and cap services and remove, clean, and store equipment; when appropriate, reinstall, reconnect, and make equipment operational.

Architect's Project #: 12.130.09

e. Equipment to Be Removed and Salvaged: Disconnect and cap services and remove equipment and deliver to Owner.

#### 3.3 PREPARATION

- A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
  - 1. Comply with requirements for access and protection specified in Section 015000 "Temporary Facilities and Controls."
  - 2. Access to the existing tennis courts is strictly prohibited unless written request from the contractor is submitted including provisions for how the courts are to be protected and then expressly allowed in writing by the owner.
- B. Temporary Facilities: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
  - 1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
  - 2. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
  - 3. Protect walls, ceilings, floors, and other existing finish work (including the existing tennis courts) that are to remain or that are exposed during selective demolition operations.
  - 4. Cover and protect furniture, furnishings, and equipment that have not been removed.
  - 5. Comply with requirements for temporary enclosures, dust control, heating, and cooling specified in Section 015000 "Temporary Facilities and Controls."

# 3.4 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
  - 1. Proceed with selective demolition systematically, from higher to lower level. Complete selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.
  - 2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.

existing finished surfaces.

3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain fire watch and portable fire-suppression devices during flame-cutting operations.
- 5. Maintain adequate ventilation when using cutting torches.
- 6. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
- 7. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
- 8. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
- 9. Dispose of demolished items and materials promptly.

# B. Removed and Salvaged Items:

- 1. Clean salvaged items.
- 2. Pack or crate items after cleaning. Identify contents of containers.
- 3. Store items in a secure area until delivery to Owner.
- 4. Transport items to Owner's storage area off-site designated by Owner.
- 5. Protect items from damage during transport and storage.

### C. Removed and Reinstalled Items:

- 1. Clean and repair items to functional condition adequate for intended reuse.
- 2. Pack or crate items after cleaning and repairing. Identify contents of containers.
- 3. Protect items from damage during transport and storage.
- 4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.
- D. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and cleaned and reinstalled in their original locations after selective demolition operations are complete.

# 3.5 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

- A. Concrete: Demolish in sections. Cut concrete full depth at junctures with construction to remain and at regular intervals using power-driven saw, then remove concrete between saw cuts.
- B. Concrete Slabs-on-Grade: Saw-cut perimeter of area to be demolished, then break up and remove.

# 3.6 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Except for items or materials indicated to be recycled, reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, remove demolished materials from Project site and legally dispose of them.
  - 1. Do not allow demolished materials to accumulate on-site.
  - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Burning: Do not burn demolished materials.
- C. Disposal: Transport demolished materials and dispose of at designated spoil areas on Owner's property.
- D. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

## 3.7 CLEANING

A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 024119

Issue Date: 06/05/2014

# SECTION 033000 - CAST-IN-PLACE CONCRETE

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes cast-in-place concrete, including formwork, reinforcement, concrete materials, mixture design, placement procedures, and finishes, for the following:
  - 1. Footings.
  - 2. Slabs-on-grade.
  - 3. Concrete Water Vapor Reducing Admixture

# B. Related Sections:

- 1. Division 03 Section "Architectural Concrete" for general building applications of specially finished formed concrete.
- 2. Division 31 Section "Earth Moving" for drainage fill under slabs-on-grade.
- 3. Division 32 Section "Concrete Paving" for concrete pavement and walks.
- 4. Division 32 Section "Decorative Concrete Paving" for decorative concrete pavement and walks.

## 1.3 DEFINITIONS

A. Cementitious Materials: Portland cement alone or in combination with one or more of the following: blended hydraulic cement, fly ash and other pozzolans, ground granulated blast-furnace slag, and silica fume; subject to compliance with requirements.

# 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Design Mixtures: For each concrete mixture. Submit alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.
  - 1. Indicate amounts of mixing water to be withheld for later addition at Project site.
- C. Steel Reinforcement Shop Drawings: Placing drawings that detail fabrication, bending, and placement. Include bar sizes, lengths, material, grade, bar schedules, stirrup spacing, bent bar

Issue Date: 06/05/2014

diagrams, bar arrangement, splices and laps, mechanical connections, tie spacing, hoop spacing, and supports for concrete reinforcement.

- D. Formwork Shop Drawings: Prepared by or under the supervision of a qualified professional engineer detailing fabrication, assembly, and support of formwork.
  - 1. Shoring and Reshoring: Indicate proposed schedule and sequence of stripping formwork, shoring removal, and reshoring installation and removal.
- E. Construction Joint Layout: Indicate proposed construction joints required to construct the structure.
  - 1. Location of construction joints is subject to approval of the Architect.

### 1.5 INFORMATIONAL SUBMITTALS

- A. Material Certificates: For each of the following, signed by manufacturers:
  - 1. Cementitious materials.
  - 2. Admixtures, including Concrete Water Vapor Reducing Admixture
  - 3. Steel reinforcement and accessories.
  - 4. Curing compounds.
  - 5. Floor and slab treatments.
  - 6. Bonding agents.
  - 7. Adhesives.
  - 8. Vapor retarders.
  - 9. Semirigid joint filler.
  - 10. Joint-filler strips.
  - 11. Repair materials.
- B. Floor surface flatness and levelness measurements indicating compliance with specified tolerances.
- C. Field quality-control reports.

# 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs on Project personnel qualified as ACI-certified Flatwork Technician and Finisher and a supervisor who is an ACI-certified Concrete Flatwork Technician.
- B. Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C 94/C 94M requirements for production facilities and equipment.
  - 1. Manufacturer certified according to NRMCA's "Certification of Ready Mixed Concrete Production Facilities."

Issue Date: 06/05/2014

- C. Source Limitations: Obtain each type or class of cementitious material of the same brand from the same manufacturer's plant, obtain aggregate from single source, and obtain admixtures from single source from single manufacturer.
- D. Welding Qualifications: Qualify procedures and personnel according to AWS D1.4/D 1.4M, "Structural Welding Code Reinforcing Steel."
- E. ACI Publications: Comply with the following unless modified by requirements in the Contract Documents:
  - 1. ACI 301, "Specifications for Structural Concrete," Sections 1 through 5.
  - 2. ACI 117, "Specifications for Tolerances for Concrete Construction and Materials."

## 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Steel Reinforcement: Deliver, store, and handle steel reinforcement to prevent bending and damage.
- B. Waterstops: Store waterstops under cover to protect from moisture, sunlight, dirt, oil, and other contaminants.

### PART 2 - PRODUCTS

## 2.1 FORM-FACING MATERIALS

- A. Smooth-Formed Finished Concrete: Form-facing panels that will provide continuous, true, and smooth concrete surfaces. Furnish in largest practicable sizes to minimize number of joints.
  - 1. Plywood, metal, or other approved panel materials.
  - 2. Exterior-grade plywood panels, suitable for concrete forms, complying with DOC PS 1, and as follows:
    - a. High-density overlay, Class 1 or better.
    - b. Medium-density overlay, Class 1 or better; mill-release agent treated and edge sealed.
    - c. Structural 1, B-B or better; mill oiled and edge sealed.
    - d. B-B (Concrete Form), Class 1 or better; mill oiled and edge sealed.
- B. Rough-Formed Finished Concrete: Plywood, lumber, metal, or another approved material. Provide lumber dressed on at least two edges and one side for tight fit.
- C. Chamfer Strips: Wood, metal, PVC, or rubber strips, 3/4 by 3/4 inch (19 by 19 mm), minimum.
- D. Form-Release Agent: Commercially formulated form-release agent that will not bond with, stain, or adversely affect concrete surfaces and will not impair subsequent treatments of concrete surfaces.

Issue Date: 06/05/2014

- 1. Formulate form-release agent with rust inhibitor for steel form-facing materials.
- E. Form Ties: Factory-fabricated, removable or snap-off metal or glass-fiber-reinforced plastic form ties designed to resist lateral pressure of fresh concrete on forms and to prevent spalling of concrete on removal.
  - 1. Furnish units that will leave no corrodible metal closer than 1 inch (25 mm) to the plane of exposed concrete surface.
  - 2. Furnish ties that, when removed, will leave holes no larger than 1 inch (25 mm) in diameter in concrete surface.
  - 3. Furnish ties with integral water-barrier plates to walls indicated to receive dampproofing or waterproofing.

### 2.2 STEEL REINFORCEMENT

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Reinforcing Bars: ASTM A 615/A 615M, Grade 60 (Grade 420), deformed.
- C. Steel Bar Mats: ASTM A 184/A 184M, fabricated from ASTM A 615/A 615M, Grade 60 (Grade 420), deformed bars, assembled with clips.
- D. Plain-Steel Welded Wire Reinforcement: ASTM A 185/A 185M, plain, fabricated from asdrawn steel wire into flat sheets.

# 2.3 REINFORCEMENT ACCESSORIES

- A. Joint Dowel Bars: ASTM A 615/A 615M, Grade 60 (Grade 420), plain-steel bars, cut true to length with ends square and free of burrs.
- B. Epoxy Repair Coating: Liquid, two-part, epoxy repair coating; compatible with epoxy coating on reinforcement and complying with ASTM A 775/A 775M.
- C. Bar Supports: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars and welded wire reinforcement in place. Manufacture bar supports from steel wire, plastic, or precast concrete according to CRSI's "Manual of Standard Practice," of greater compressive strength than concrete and as follows:
  - 1. For concrete surfaces exposed to view where legs of wire bar supports contact forms, use CRSI Class 1 plastic-protected steel wire or CRSI Class 2 stainless-steel bar supports.
  - 2. For epoxy-coated reinforcement, use epoxy-coated or other dielectric-polymer-coated wire bar supports.
  - 3. For zinc-coated reinforcement, use galvanized wire or dielectric-polymer-coated wire bar supports.

# 2.4 CONCRETE MATERIALS

A. Cementitious Material: Use the following cementitious materials, of the same type, brand, and source, throughout Project:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Portland Cement: ASTM C 150, Type I/II.
- B. Silica Fume: ASTM C 1240, amorphous silica.
- C. Normal-Weight Aggregates: ASTM C 33, coarse aggregate or better, graded. Provide aggregates from a single source.
  - 1. Maximum Coarse-Aggregate Size: 1-1/2 inches (38 mm) nominal.
  - 2. Fine Aggregate: Free of materials with deleterious reactivity to alkali in cement.
- D. Water: ASTM C 94/C 94M.

## 2.5 ADMIXTURES

- A. Air-Entraining Admixture: ASTM C 260.
- B. Chemical Admixtures: Provide admixtures certified by manufacturer to be compatible with other admixtures and that will not contribute water-soluble chloride ions exceeding those permitted in hardened concrete. Do not use calcium chloride or admixtures containing calcium chloride.
  - 1. Water-Reducing Admixture: ASTM C 494/C 494M, Type A.
  - 2. Retarding Admixture: ASTM C 494/C 494M, Type B.
  - 3. Water-Reducing and Retarding Admixture: ASTM C 494/C 494M, Type D.
  - 4. High-Range, Water-Reducing Admixture: ASTM C 494/C 494M, Type F.
  - 5. High-Range, Water-Reducing and Retarding Admixture: ASTM C 494/C 494M, Type G.
  - 6. Plasticizing and Retarding Admixture: ASTM C 1017/C 1017M, Type II.
- C. CONCRETE WATER VAPOR REDUCING ADMIXTURE (At Building Slab on Grade Only)
  - 1. Manufacturer:
    - a. Basis-of-Design Product: The concrete water vapor reducing admixture is based on Vapor Lock 20/20 manufactured by Specialty Products Group (SPG), 6254 Skyway Road, PO Box 915, Smithville ON, LOR 2A0, Canada
    - b. Substitutions may be considered.
  - 2. Materials:
    - a. Concrete Water Vapor Reducing Admixture (WVRA): A complex admixture for cementitious materials, free of volatile organic compounds (VOC), designed to naturally chemically react with pre-existing elements within the cementitious material to eliminate the route of moisture vapor emission by integrally and permanently closing the capillary system in the concrete with the following characteristics:
      - 1) Waterproofing: Minimum 1×10-8 cm/s in accordance with ASTM D5084.
      - 2) Toxicity: None.

Issue Date: 06/05/2014

- 3) Flammability: None.
- 4) Solvent: Water.
- 5) Acid Resistance: Excellent.
- 6) Hazardous Vapors: None.
- 7) Capillary Break: Calcium Silicate Hydrate.
- 8) Installation: All cementitious materials.
- 9) VOC Levels: Zero (0).
- 10) Inhibit mold and bacteria growth by eliminating moisture vapor emission.

## 2.6 VAPOR RETARDERS

- A. Sheet Vapor Retarder: Polyethylene sheet, ASTM D 4397, not less than 10 mils (0.25 mm) thick.
- B. Granular Fill: Clean mixture of crushed stone or crushed or uncrushed gravel; ASTM D 448, Size 57, with 100 percent passing a 1-1/2-inch (37.5-mm) sieve and 0 to 5 percent passing a No. 8 (2.36-mm) sieve.
- C. Fine-Graded Granular Material: Clean mixture of crushed stone, crushed gravel, and manufactured or natural sand; ASTM D 448, Size 10, with 100 percent passing a 3/8-inch (9.5-mm) sieve, 10 to 30 percent passing a No. 100 (0.15-mm) sieve, and at least 5 percent passing No. 200 (0.075-mm) sieve; complying with deleterious substance limits of ASTM C 33 for fine aggregates.

# 2.7 CURING MATERIALS

- A. Evaporation Retarder: Waterborne, monomolecular film forming, manufactured for application to fresh concrete surfaces for temporary protection from rapid moisture loss.
- B. Absorptive Cover: AASHTO M 182, Class 2, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd. (305 g/sq. m) when dry.
- C. Moisture-Retaining Cover: ASTM C 171, polyethylene film or white burlap-polyethylene sheet.
- D. Water: Potable.
- E. Clear, Waterborne, Membrane-Forming Curing Compound: ASTM C 309, Type 1, Class B, dissipating.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Conspec by Dayton Superior; W.B. Resin Cure.
    - b. Meadows, W. R., Inc.; 1100-CLEAR.
- F. Clear, Solvent-Borne, Membrane-Forming Curing and Sealing Compound: ASTM C 1315, Type 1, Class A.

- Re-Bid Set Issue Date: 06/05/2014
  - 1. VOC Content: Curing and sealing compounds shall have a VOC content of 200 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

- G. Clear, Waterborne, Membrane-Forming Curing and Sealing Compound: ASTM C 1315, Type 1, Class A.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Conspec by Dayton Superior; Sealcure 1315 WB.
    - b. Meadows, W. R., Inc.; Vocomp-30.
  - 2. VOC Content: Curing and sealing compounds shall have a VOC content of 200 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

#### 2.8 RELATED MATERIALS

- A. Latex Bonding Agent: ASTM C 1059, Type II, non-redispersible, acrylic emulsion or styrene butadiene.
- B. Epoxy-Bonding Adhesive: ASTM C 881, two-component epoxy resin, capable of humid curing and bonding to damp surfaces, of class suitable for application temperature and of grade to suit requirements, and as follows:
  - 1. Types IV and V, load bearing, for bonding hardened or freshly mixed concrete to hardened concrete.
- C. Epoxy Anchoring Adhesive: ASTM C 881, two-component epoxy resin, supplied in manufacturer's standard side-by-side cartridge and dispensed through a mixing nozzle supplied by the manufacturer, of class and grade to suit requirements.
- D. Expansion and Isolation Joint-Filler Strips: ASTM D 1751, asphalt-saturated cellulosic fiber. Thickness 1/2 inch unless otherwise indicated. Acceptable products include, but are not limited to:
  - 1. Fibre Expansion Joint, W.R. Meadows, Inc.

# 2.9 REPAIR MATERIALS

- A. Repair Underlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/8 inch (3.2 mm) and that can be feathered at edges to match adjacent floor elevations.
  - 1. Cement Binder: ASTM C 150, portland cement or hydraulic or blended hydraulic cement as defined in ASTM C 219.
  - 2. Primer: Product of underlayment manufacturer recommended for substrate, conditions, and application.
  - 3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch (3.2 to 6 mm) or coarse sand as recommended by underlayment manufacturer.
  - 4. Compressive Strength: Not less than 4100 psi (29 MPa) at 28 days when tested according to ASTM C 109/C 109M.

Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- B. Repair Overlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/4 inch (6.4 mm) and that can be filled in over a scarified surface to match adjacent floor elevations.
  - 1. Cement Binder: ASTM C 150, portland cement or hydraulic or blended hydraulic cement as defined in ASTM C 219.
  - 2. Primer: Product of topping manufacturer recommended for substrate, conditions, and application.
  - 3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch (3.2 to 6 mm) or coarse sand as recommended by topping manufacturer.
  - 4. Compressive Strength: Not less than 5000 psi (34.5 MPa) at 28 days when tested according to ASTM C 109/C 109M.

# 2.10 CONCRETE MIXTURES, GENERAL

- A. Prepare design mixtures for each type and strength of concrete, proportioned on the basis of laboratory trial mixture or field test data, or both, according to ACI 301.
  - 1. Use a qualified independent testing agency for preparing and reporting proposed mixture designs based on laboratory trial mixtures.

#### B. Cementitious Materials:

- 1. Fly Ash: 25 percent.
- 2. Combined Fly Ash and Pozzolan: 25 percent.
- 3. Ground Granulated Blast-Furnace Slag: 50 percent.
- 4. Combined Fly Ash or Pozzolan and Ground Granulated Blast-Furnace Slag: 50 percent portland cement minimum, with fly ash or pozzolan not exceeding 25 percent.
- 5. Silica Fume: 10 percent.
- 6. Combined Fly Ash, Pozzolans, and Silica Fume: 35 percent with fly ash or pozzolans not exceeding 25 percent and silica fume not exceeding 10 percent.
- 7. Combined Fly Ash or Pozzolans, Ground Granulated Blast-Furnace Slag, and Silica Fume: 50 percent with fly ash or pozzolans not exceeding 25 percent and silica fume not exceeding 10 percent.
- C. Limit water-soluble, chloride-ion content in hardened concrete to [0.06] [0.15] [0.30] [1.00] percent by weight of cement.
- D. Admixtures: Use admixtures according to manufacturer's written instructions.
  - 1. Use water-reducing admixture in concrete, as required, for placement and workability.
  - 2. Use water-reducing and retarding admixture when required by high temperatures, low humidity, or other adverse placement conditions.
  - 3. Use water-reducing admixture in pumped concrete, concrete for heavy-use industrial slabs and parking structure slabs, concrete required to be watertight, and concrete with a water-cementitious materials ratio below 0.50.
  - 4. Use corrosion-inhibiting admixture in concrete mixtures where indicated.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

E. Color Pigment: Add color pigment to concrete mixture according to manufacturer's written instructions and to result in hardened concrete color consistent with approved mockup.

#### 2.11 CONCRETE MIXTURES FOR BUILDING ELEMENTS

- All concrete: Proportion normal-weight concrete mixture as follows: A.
  - 1. Minimum Compressive Strength: See structural drawings.
  - Maximum Water-Cementitious Materials Ratio: 0.50. 2.
  - Slump Limit: 5 inches (125 mm), plus or minus 1 inch (25 mm). 3.
  - Air Content: 5.5 percent, plus or minus 1.5 percent at point of delivery for 1-1/2-inch 4. (38-mm) nominal maximum aggregate size.

#### 2.12 FABRICATING REINFORCEMENT

Fabricate steel reinforcement according to CRSI's "Manual of Standard Practice." A.

#### 2.13 CONCRETE MIXING

- Measure, batch, mix, and deliver concrete according to A. Ready-Mixed Concrete: ASTM C 94/C 94M, and furnish batch ticket information.
  - 1. When air temperature is between 85 and 90 deg F (30 and 32 deg C), reduce mixing and delivery time from 1-1/2 hours to 75 minutes; when air temperature is above 90 deg F (32 deg C), reduce mixing and delivery time to 60 minutes.
- B. Project-Site Mixing: Measure, batch, and mix concrete materials and concrete according to ASTM C 94/C 94M. Mix concrete materials in appropriate drum-type batch machine mixer.
  - 1. For mixer capacity of 1 cu. yd. (0.76 cu. m) or smaller, continue mixing at least 1-1/2 minutes, but not more than 5 minutes after ingredients are in mixer, before any part of batch is released.
  - 2. For mixer capacity larger than 1 cu. yd. (0.76 cu. m), increase mixing time by 15 seconds for each additional 1 cu. yd. (0.76 cu. m).
  - Provide batch ticket for each batch discharged and used in the Work, indicating Project 3. identification name and number, date, mixture type, mixture time, quantity, and amount of water added. Record approximate location of final deposit in structure.

#### PART 3 - EXECUTION

#### 3.1 **FORMWORK**

Design, erect, shore, brace, and maintain formwork, according to ACI 301, to support vertical, A. lateral, static, and dynamic loads, and construction loads that might be applied, until structure can support such loads.

Fennis Complex Addition

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- B. Construct formwork so concrete members and structures are of size, shape, alignment, elevation, and position indicated, within tolerance limits of ACI 117.
- C. Limit concrete surface irregularities, designated by ACI 347 as abrupt or gradual, as follows:
  - 1. Class A, 1/8 inch (3.2 mm) for smooth-formed finished surfaces.
  - 2. Class B, 1/4 inch (6 mm) for rough-formed finished surfaces.
- D. Construct forms tight enough to prevent loss of concrete mortar.
- E. Fabricate forms for easy removal without hammering or prying against concrete surfaces. Provide crush or wrecking plates where stripping may damage cast concrete surfaces. Provide top forms for inclined surfaces steeper than 1.5 horizontal to 1 vertical.
  - 1. Install keyways, reglets, recesses, and the like, for easy removal.
  - 2. Do not use rust-stained steel form-facing material.
- F. Set edge forms, bulkheads, and intermediate screed strips for slabs to achieve required elevations and slopes in finished concrete surfaces. Provide and secure units to support screed strips; use strike-off templates or compacting-type screeds.
- G. Provide temporary openings for cleanouts and inspection ports where interior area of formwork is inaccessible. Close openings with panels tightly fitted to forms and securely braced to prevent loss of concrete mortar. Locate temporary openings in forms at inconspicuous locations.
- H. Chamfer exterior corners and edges of permanently exposed concrete.
- I. Form openings, chases, offsets, sinkages, keyways, reglets, blocking, screeds, and bulkheads required in the Work. Determine sizes and locations from trades providing such items.
- J. Clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt, and other debris just before placing concrete.
- K. Retighten forms and bracing before placing concrete, as required, to prevent mortar leaks and maintain proper alignment.
- L. Coat contact surfaces of forms with form-release agent, according to manufacturer's written instructions, before placing reinforcement.

#### 3.2 EMBEDDED ITEMS

- A. Place and secure anchorage devices and other embedded items required for adjoining work that is attached to or supported by cast-in-place concrete. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
  - 1. Install anchor rods, accurately located, to elevations required and complying with tolerances in Section 7.5 of AISC's "Code of Standard Practice for Steel Buildings and Bridges."

Issue Date: 06/05/2014

- 2. Install reglets to receive waterproofing and to receive through-wall flashings in outer face of concrete frame at exterior walls, where flashing is shown at lintels, shelf angles, and other conditions.
- 3. Install dovetail anchor slots in concrete structures as indicated.

### 3.3 VAPOR RETARDERS

- A. Sheet Vapor Retarders: Place, protect, and repair sheet vapor retarder according to ASTM E 1643 and manufacturer's written instructions.
  - 1. Lap joints 6 inches (150 mm) and seal with manufacturer's recommended tape.

# 3.4 CONCRETE WATER VAPOR REDUCING ADMIXTURE:

- A. Comply with the requirements of this section for the concrete mixing, placing and curing.
- B. Add water vapor reducing admixture to concrete in accordance with manufacturer's written instructions.

### 3.5 STEEL REINFORCEMENT

- A. General: Comply with CRSI's "Manual of Standard Practice" for placing reinforcement.
  - 1. Do not cut or puncture vapor retarder. Repair damage and reseal vapor retarder before placing concrete.
- B. Clean reinforcement of loose rust and mill scale, earth, ice, and other foreign materials that would reduce bond to concrete.
- C. Accurately position, support, and secure reinforcement against displacement. Locate and support reinforcement with bar supports to maintain minimum concrete cover. Do not tack weld crossing reinforcing bars.
  - 1. Weld reinforcing bars according to AWS D1.4/D 1.4M, where indicated.
- D. Set wire ties with ends directed into concrete, not toward exposed concrete surfaces.
- E. Install welded wire reinforcement in longest practicable lengths on bar supports spaced to minimize sagging. Lap edges and ends of adjoining sheets at least one mesh spacing. Offset laps of adjoining sheet widths to prevent continuous laps in either direction. Lace overlaps with wire.

## 3.6 JOINTS

A. General: Construct joints true to line with faces perpendicular to surface plane of concrete.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- B. Construction Joints: Install so strength and appearance of concrete are not impaired, at locations indicated or as approved by Architect.
  - 1. Place joints perpendicular to main reinforcement. Continue reinforcement across construction joints unless otherwise indicated. Do not continue reinforcement through sides of strip placements of floors and slabs.
  - 2. Use a bonding agent at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
  - 3. Use epoxy-bonding adhesive at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
- C. Contraction Joints in Slabs-on-Grade: Form weakened-plane contraction joints, sectioning concrete into areas as indicated. Construct contraction joints for a depth equal to at least one-third of concrete thickness as follows:
  - 1. Grooved Joints: Form contraction joints after initial floating by grooving and finishing each edge of joint to a radius of 1/8 inch (3.2 mm). Repeat grooving of contraction joints after applying surface finishes. Eliminate groover tool marks on concrete surfaces.
  - 2. Sawed Joints: Form contraction joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch- (3.2-mm-) wide joints into concrete when cutting action will not tear, abrade, or otherwise damage surface and before concrete develops random contraction cracks.
- D. Doweled Joints: Install dowel bars and support assemblies at joints where indicated. Lubricate or asphalt coat one-half of dowel length to prevent concrete bonding to one side of joint.

# 3.7 CONCRETE PLACEMENT

- A. Before placing concrete, verify that installation of formwork, reinforcement, and embedded items is complete and that required inspections have been performed.
- B. Do not add water to concrete during delivery, at Project site, or during placement unless approved by Architect.
- C. Before test sampling and placing concrete, water may be added at Project site, subject to limitations of ACI 301.
  - 1. Do not add water to concrete after adding high-range water-reducing admixtures to mixture.
- D. Deposit concrete continuously in one layer or in horizontal layers of such thickness that no new concrete will be placed on concrete that has hardened enough to cause seams or planes of weakness. If a section cannot be placed continuously, provide construction joints as indicated. Deposit concrete to avoid segregation.
  - 1. Deposit concrete in horizontal layers of depth to not exceed formwork design pressures and in a manner to avoid inclined construction joints.
  - 2. Consolidate placed concrete with mechanical vibrating equipment according to ACI 301.

Re-Bid Set Issue Date: 06/05/2014

3. Do not use vibrators to transport concrete inside forms. Insert and withdraw vibrators vertically at uniformly spaced locations to rapidly penetrate placed layer and at least 6 inches (150 mm) into preceding layer. Do not insert vibrators into lower layers of concrete that have begun to lose plasticity. At each insertion, limit duration of vibration to time necessary to consolidate concrete and complete embedment of reinforcement and other embedded items without causing mixture constituents to segregate.

Architect's Project #: 12.130.09

- E. Deposit and consolidate concrete for floors and slabs in a continuous operation, within limits of construction joints, until placement of a panel or section is complete.
  - 1. Consolidate concrete during placement operations so concrete is thoroughly worked around reinforcement and other embedded items and into corners.
  - 2. Maintain reinforcement in position on chairs during concrete placement.
  - 3. Screed slab surfaces with a straightedge and strike off to correct elevations.
  - 4. Slope surfaces uniformly to drains where required.
  - 5. Begin initial floating using bull floats or darbies to form a uniform and open-textured surface plane, before excess bleedwater appears on the surface. Do not further disturb slab surfaces before starting finishing operations.
- F. Cold-Weather Placement: Comply with ACI 306.1 and as follows. Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.
  - 1. When average high and low temperature is expected to fall below 40 deg F (4.4 deg C) for three successive days, maintain delivered concrete mixture temperature within the temperature range required by ACI 301.
  - 2. Do not use frozen materials or materials containing ice or snow. Do not place concrete on frozen subgrade or on subgrade containing frozen materials.
  - 3. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators unless otherwise specified and approved in mixture designs.
- G. Hot-Weather Placement: Comply with ACI 301 and as follows:
  - 1. Maintain concrete temperature below 90 deg F (32 deg C) at time of placement. Chilled mixing water or chopped ice may be used to control temperature, provided water equivalent of ice is calculated to total amount of mixing water. Using liquid nitrogen to cool concrete is Contractor's option.
  - 2. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade uniformly moist without standing water, soft spots, or dry areas.

# 3.8 FINISHING FORMED SURFACES

- A. Rough-Formed Finish: As-cast concrete texture imparted by form-facing material with tie holes and defects repaired and patched. Remove fins and other projections that exceed specified limits on formed-surface irregularities.
  - 1. Apply to concrete surfaces not exposed to public view.

Issue Date: 06/05/2014

B. Smooth-Formed Finish: As-cast concrete texture imparted by form-facing material, arranged in an orderly and symmetrical manner with a minimum of seams. Repair and patch tie holes and defects. Remove fins and other projections that exceed specified limits on formed-surface irregularities.

- 1. Apply to concrete surfaces exposed to public view,.
- C. Related Unformed Surfaces: At tops of walls, horizontal offsets, and similar unformed surfaces adjacent to formed surfaces, strike off smooth and finish with a texture matching adjacent formed surfaces. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces unless otherwise indicated.

# 3.9 FINISHING FLOORS AND SLABS

- A. General: Comply with ACI 302.1R recommendations for screeding, restraightening, and finishing operations for concrete surfaces. Do not wet concrete surfaces.
- B. Float Finish: All Slabs shall first receive a float finish. Machine floating shall not be used until the concrete surface will support a finisher on foot without more than a 1/4 inch indentation.
- C. Trowel Finish: After applying float finish, apply first troweling and consolidate concrete by hand or power-driven trowel. Continue troweling passes and restraighten until surface is free of trowel marks and uniform in texture and appearance. Grind smooth any surface defects that would telegraph through applied coatings or floor coverings.
  - 1. Apply a trowel finish to surfaces indicated and to floor slabs to be covered with resilient flooring, carpet, ceramic or quarry tile set over a cleavage membrane, paint, or another thin-film-finish coating system.
  - 2. Finish surfaces to the following tolerances, according to ASTM E 1155 (ASTM E 1155M), for a randomly trafficked floor surface:
    - a. Specified overall values of flatness, F(F) 30; and of levelness, F(L) 20; with minimum local values of flatness, F(F) 24; and of levelness, F(L) 15; for suspended slabs.
- D. Trowel and Fine-Broom Finish: Apply a first trowel finish to surfaces where ceramic or quarry tile is to be installed by either thickset or thin-set method. While concrete is still plastic, slightly scarify surface with a fine broom.
  - 1. Comply with flatness and levelness tolerances for trowel-finished floor surfaces.
- E. Broom Finish: Apply a broom finish to exterior concrete platforms, steps, ramps, and elsewhere as indicated.
  - 1. Immediately after float finishing, slightly roughen trafficked surface by brooming with fiber-bristle broom perpendicular to main traffic route. Coordinate required final finish with Architect before application.

### 3.10 MISCELLANEOUS CONCRETE ITEMS

A. Filling In: Fill in holes and openings left in concrete structures after work of other trades is in place unless otherwise indicated. Mix, place, and cure concrete, as specified, to blend with inplace construction. Provide other miscellaneous concrete filling indicated or required to complete the Work.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Curbs: Provide monolithic finish to interior curbs by stripping forms while concrete is still green and by steel-troweling surfaces to a hard, dense finish with corners, intersections, and terminations slightly rounded.
- C. Equipment Bases and Foundations: Provide machine and equipment bases and foundations as shown on Drawings. Set anchor bolts for machines and equipment at correct elevations, complying with diagrams or templates from manufacturer furnishing machines and equipment.
- D. Steel Pan Stairs: Provide concrete fill for steel pan stair treads, landings, and associated items. Cast-in inserts and accessories as shown on Drawings. Screed, tamp, and trowel finish concrete surfaces.

# 3.11 CONCRETE PROTECTING AND CURING

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures. Comply with ACI 306.1 for cold-weather protection and ACI 301 for hotweather protection during curing.
- B. Evaporation Retarder: Apply evaporation retarder to unformed concrete surfaces if hot, dry, or windy conditions cause moisture loss approaching 0.2 lb/sq. ft. x h (1 kg/sq. m x h) before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding, and bull floating or darbying concrete, but before float finishing.
- C. Formed Surfaces: Cure formed concrete surfaces, including underside of beams, supported slabs, and other similar surfaces. If forms remain during curing period, moist cure after loosening forms. If removing forms before end of curing period, continue curing for the remainder of the curing period.
- D. Unformed Surfaces: Begin curing immediately after finishing concrete. Cure unformed surfaces, including floors and slabs, concrete floor toppings, and other surfaces.
- E. Cure concrete according to ACI 308.1, by one or a combination of the following methods:
  - 1. Moisture Curing: Keep surfaces continuously moist for not less than seven days with the following materials:
    - a. Water.
    - b. Continuous water-fog spray.
    - c. Absorptive cover, water saturated, and kept continuously wet. Cover concrete surfaces and edges with 12-inch (300-mm) lap over adjacent absorptive covers.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches (300 mm), and sealed by waterproof tape or adhesive. Cure for not less than seven days. Immediately repair any holes or tears during curing period using cover material and waterproof tape.
  - a. Moisture cure or use moisture-retaining covers to cure concrete surfaces to receive floor coverings.
  - b. Moisture cure or use moisture-retaining covers to cure concrete surfaces to receive penetrating liquid floor treatments.
  - c. Cure concrete surfaces to receive floor coverings with either a moisture-retaining cover or a curing compound that the manufacturer certifies will not interfere with bonding of floor covering used on Project.
- 3. Curing Compound: Apply uniformly in continuous operation by power spray or roller according to manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Maintain continuity of coating and repair damage during curing period.
  - a. Removal: After curing period has elapsed, remove curing compound without damaging concrete surfaces by method recommended by curing compound manufacturer.
- 4. Curing and Sealing Compound: Apply uniformly to floors and slabs indicated in a continuous operation by power spray or roller according to manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Repeat process 24 hours later and apply a second coat. Maintain continuity of coating and repair damage during curing period.

# 3.12 LIQUID FLOOR TREATMENTS

- A. Penetrating Liquid Floor Treatment: Prepare, apply, and finish penetrating liquid floor treatment according to manufacturer's written instructions.
  - 1. Remove curing compounds, sealers, oil, dirt, laitance, and other contaminants and complete surface repairs.
  - 2. Do not apply to concrete that is less than 14 days' old.
  - 3. Apply liquid until surface is saturated, scrubbing into surface until a gel forms; rewet; and repeat brooming or scrubbing. Rinse with water; remove excess material until surface is dry. Apply a second coat in a similar manner if surface is rough or porous.
- B. Sealing Coat: Uniformly apply a continuous sealing coat of curing and sealing compound to hardened concrete by power spray or roller according to manufacturer's written instructions.

# 3.13 JOINT FILLING

A. Prepare, clean, and install joint filler according to manufacturer's written instructions.

Re-Bid Set Issue Date: 06/05/2014

1. Defer joint filling until concrete has aged at least one month(s). Do not fill joints until construction traffic has permanently ceased.

Architect's Project #: 12.130.09

- B. Remove dirt, debris, saw cuttings, curing compounds, and sealers from joints; leave contact faces of joint clean and dry.
- C. Install semirigid joint filler full depth in saw-cut joints and at least 2 inches (50 mm) deep in formed joints. Overfill joint and trim joint filler flush with top of joint after hardening.

## 3.14 BONDING NEW CONCRETE TO EXISTING CONCRETE

A. At locations where new concrete is placed adjacent to existing concrete, unless indicated otherwise, clean and roughen the face of the existing concrete and provide a bonding agent in accordance with the manufacturer's recommendations.

# 3.15 CONCRETE SURFACE REPAIRS

- A. Patching Mortar: Mix dry-pack patching mortar, consisting of one part portland cement to two and one-half parts fine aggregate passing a No. 16 (1.18-mm) sieve, using only enough water for handling and placing.
- B. Repairing Formed Surfaces: Surface defects include color and texture irregularities, cracks, spalls, air bubbles, honeycombs, rock pockets, fins and other projections on the surface, and stains and other discolorations that cannot be removed by cleaning.
  - 1. Immediately after form removal, cut out honeycombs, rock pockets, and voids more than 1/2 inch (13 mm) in any dimension to solid concrete. Limit cut depth to 3/4 inch (19 mm). Make edges of cuts perpendicular to concrete surface. Clean, dampen with water, and brush-coat holes and voids with bonding agent. Fill and compact with patching mortar before bonding agent has dried. Fill form-tie voids with patching mortar or cone plugs secured in place with bonding agent.
  - 2. Repair defects on surfaces exposed to view by blending white portland cement and standard portland cement so that, when dry, patching mortar will match surrounding color. Patch a test area at inconspicuous locations to verify mixture and color match before proceeding with patching. Compact mortar in place and strike off slightly higher than surrounding surface.
  - 3. Repair defects on concealed formed surfaces that affect concrete's durability and structural performance as determined by Architect.
- C. Repairing Unformed Surfaces: Test unformed surfaces, such as floors and slabs, for finish and verify surface tolerances specified for each surface. Correct low and high areas. Test surfaces sloped to drain for trueness of slope and smoothness; use a sloped template.
  - 1. Repair finished surfaces containing defects. Surface defects include spalls, popouts, honeycombs, rock pockets, crazing and cracks in excess of 0.01 inch (0.25 mm) wide or that penetrate to reinforcement or completely through unreinforced sections regardless of width, and other objectionable conditions.
  - 2. After concrete has cured at least 14 days, correct high areas by grinding.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 3. Correct localized low areas during or immediately after completing surface finishing operations by cutting out low areas and replacing with patching mortar. Finish repaired areas to blend into adjacent concrete.
- 4. Correct other low areas scheduled to receive floor coverings with a repair underlayment. Prepare, mix, and apply repair underlayment and primer according to manufacturer's written instructions to produce a smooth, uniform, plane, and level surface. Feather edges to match adjacent floor elevations.
- 5. Correct other low areas scheduled to remain exposed with a repair topping. Cut out low areas to ensure a minimum repair topping depth of 1/4 inch (6 mm) to match adjacent floor elevations. Prepare, mix, and apply repair topping and primer according to manufacturer's written instructions to produce a smooth, uniform, plane, and level surface.
- 6. Repair defective areas, except random cracks and single holes 1 inch (25 mm) or less in diameter, by cutting out and replacing with fresh concrete. Remove defective areas with clean, square cuts and expose steel reinforcement with at least a 3/4-inch (19-mm) clearance all around. Dampen concrete surfaces in contact with patching concrete and apply bonding agent. Mix patching concrete of same materials and mixture as original concrete except without coarse aggregate. Place, compact, and finish to blend with adjacent finished concrete. Cure in same manner as adjacent concrete.
- 7. Repair random cracks and single holes 1 inch (25 mm) or less in diameter with patching mortar. Groove top of cracks and cut out holes to sound concrete and clean off dust, dirt, and loose particles. Dampen cleaned concrete surfaces and apply bonding agent. Place patching mortar before bonding agent has dried. Compact patching mortar and finish to match adjacent concrete. Keep patched area continuously moist for at least 72 hours.
- D. Perform structural repairs of concrete, subject to Architect's approval, using epoxy adhesive and patching mortar.
- E. Repair materials and installation not specified above may be used, subject to Architect's approval.

# 3.16 FIELD QUALITY CONTROL

- A. Testing and Inspecting: Owner will engage a special inspector to perform field tests and inspections and prepare test reports.
- B. Testing and Inspecting: Engage a qualified testing and inspecting agency to perform tests and inspections and to submit reports.

# C. Inspections:

- 1. Steel reinforcement placement.
- 2. Steel reinforcement welding.
- 3. Headed bolts and studs.
- 4. Verification of use of required design mixture.
- 5. Concrete placement, including conveying and depositing.
- 6. Curing procedures and maintenance of curing temperature.
- 7. Verification of concrete strength before removal of shores and forms from beams and slabs.

Issue Date: 06/05/2014

- D. Concrete Tests: Testing of composite samples of fresh concrete obtained according to ASTM C 172 shall be performed according to the following requirements:
  - 1. Testing Frequency: Obtain one composite sample for each day's pour of each concrete mixture exceeding 5 cu. yd. (4 cu. m), but less than 25 cu. yd. (19 cu. m), plus one set for each additional 50 cu. yd. (38 cu. m) or fraction thereof.
  - 2. Testing Frequency: Obtain at least one composite sample for each 100 cu. yd. (76 cu. m) or fraction thereof of each concrete mixture placed each day.
    - a. When frequency of testing will provide fewer than five compressive-strength tests for each concrete mixture, testing shall be conducted from at least five randomly selected batches or from each batch if fewer than five are used.
  - 3. Slump: ASTM C 143/C 143M; one test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mixture. Perform additional tests when concrete consistency appears to change.
  - 4. Air Content: ASTM C 231, pressure method, for normal-weight concrete; one test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
  - 5. Concrete Temperature: ASTM C 1064/C 1064M; one test hourly when air temperature is 40 deg F (4.4 deg C) and below and when 80 deg F (27 deg C) and above, and one test for each composite sample.
  - 6. Unit Weight: ASTM C 567, fresh unit weight of structural lightweight concrete; one test for each composite sample, but not less than one test for each day's pour of each concrete mixture
  - 7. Compression Test Specimens: ASTM C 31/C 31M.
    - a. Cast and laboratory cure two sets of two standard cylinder specimens for each composite sample.
    - b. Cast and field cure two sets of two standard cylinder specimens for each composite sample.
  - 8. Compressive-Strength Tests: ASTM C 39/C 39M; test one set of two laboratory-cured specimens at 7 days and one set of two specimens at 28 days.
    - a. Test one set of two field-cured specimens at 7 days and one set of two specimens at 28 days.
    - b. A compressive-strength test shall be the average compressive strength from a set of two specimens obtained from same composite sample and tested at age indicated.
  - 9. When strength of field-cured cylinders is less than 85 percent of companion laboratory-cured cylinders, Contractor shall evaluate operations and provide corrective procedures for protecting and curing in-place concrete.
  - 10. Strength of each concrete mixture will be satisfactory if every average of any three consecutive compressive-strength tests equals or exceeds specified compressive strength and no compressive-strength test value falls below specified compressive strength by more than 500 psi (3.4 MPa).
  - 11. Test results shall be reported in writing to Architect, concrete manufacturer, and Contractor within 48 hours of testing. Reports of compressive-strength tests shall contain Project identification name and number, date of concrete placement, name of concrete

Issue Date: 06/05/2014

- testing and inspecting agency, location of concrete batch in Work, design compressive strength at 28 days, concrete mixture proportions and materials, compressive breaking strength, and type of break for both 7- and 28-day tests.
- 12. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.
- 13. Additional Tests: Testing and inspecting agency shall make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Architect. Testing and inspecting agency may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C 42/C 42M or by other methods as directed by Architect.
- 14. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.
- 15. Correct deficiencies in the Work that test reports and inspections indicate do not comply with the Contract Documents.
- E. Measure floor and slab flatness and levelness according to ASTM E 1155 (ASTM E 1155M) within 48 hours of finishing.

END OF SECTION 033000

#### SECTION 042000 - UNIT MASONRY

### PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 SUMMARY

### A. Section Includes:

- 1. Concrete masonry units.
- 2. Brick masonry.
- 3. Mortar and grout.
- 4. Steel reinforcing bars.
- 5. Masonry-joint reinforcement.
- 6. Ties and anchors.
- 7. Embedded flashing.
- 8. Miscellaneous masonry accessories.
- 9. Steel lintels in unit masonry.

### B. Products Installed but not Furnished under This Section:

1. Cavity wall insulation.

# C. Related Requirements:

- 1. Section 055000 "Metal Fabrications" for Steel lintels and angles.
- 2. Section 072100 "Thermal Insulation" for cavity wall insulation.
- 3. Section 076200 "Sheet Metal Flashing and Trim" for exposed sheet metal flashing and for furnishing manufactured reglets installed in masonry joints.

### 1.3 DEFINITIONS

- A. CMU(s): Concrete masonry unit(s).
- B. Reinforced Masonry: Masonry containing reinforcing steel in grouted cells.

# 1.4 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For the following:
  - 1. Masonry Units: Show sizes, profiles, coursing, and locations of special or solid shapes.
  - 2. Reinforcing Steel: Detail bending, lap lengths, and placement of unit masonry reinforcing bars. Comply with ACI 315. Show elevations of reinforced walls.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 3. Fabricated Flashing: Detail corner units, end-dam units, and other special applications.
- C. Samples for Verification: For each type and color of the following:
  - 1. Brick Veneer masonry, in the form of straps of five or more bricks.
  - 2. Special or solid brick shapes.
  - 3. Mortar. Make Samples using same sand and mortar ingredients to be used on Project.
  - 4. Weep holes and cavity vents.
  - 5. Accessories embedded in masonry.

### 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For testing agency.
- B. Material Certificates: For each type and size of the following:
  - 1. Masonry units.
    - a. Include data on material properties.
    - b. Manufacturer's certification letter stating that all lightweight aggregates used in the manufacture of CMU concrete masonry units were expanded shale, clay, slate or slag, and that no combustible matter and organic impurities such as coal, coke, cinder/bottom ash or similar type aggregates were used.
    - c. For brick, include size-variation data verifying that actual range of sizes falls within specified tolerances.
    - d. For exposed brick, include test report for efflorescence according to ASTM C 67.
    - e. For masonry units, include data and calculations establishing average net-area compressive strength of units.
  - 2. Cementitious materials. Include name of manufacturer, brand name, and type.
  - 3. Mortar admixtures.
  - 4. Preblended, dry mortar mixes. Include description of type and proportions of ingredients.
  - 5. Grout mixes. Include description of type and proportions of ingredients.
  - 6. Reinforcing bars.
  - 7. Joint reinforcement.
  - 8. Anchors, ties, and metal accessories.
- C. Mix Designs: For each type of mortar and grout. Include description of type and proportions of ingredients.

1. Include test reports for mortar mixes required to comply with property specification. Test according to ASTM C 109/C 109M for compressive strength, ASTM C 1506 for water retention, and ASTM C 91/C 91M for air content.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Include test reports, according to ASTM C 1019, for grout mixes required to comply with compressive strength requirement.
- D. Statement of Compressive Strength of Masonry: For each combination of masonry unit type and mortar type, provide statement of average net-area compressive strength of masonry units, mortar type, and resulting net-area compressive strength of masonry determined according to TMS 602/ACI 530.1/ASCE 6.
- E. Cold-Weather and Hot-Weather Procedures: Detailed description of methods, materials, and equipment to be used to comply with requirements.

# 1.7 QUALITY ASSURANCE

A. Testing Agency Qualifications: Qualified according to ASTM C 1093 for testing indicated.

# 1.8 DELIVERY, STORAGE, AND HANDLING

- A. Store masonry units on elevated platforms in a dry location. If units are not stored in an enclosed location, cover tops and sides of stacks with waterproof sheeting, securely tied. If units become wet, do not install until they are dry.
- B. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.
- C. Store aggregates where grading and other required characteristics can be maintained and contamination avoided.
- D. Deliver preblended, dry mortar mix in moisture-resistant containers. Store preblended, dry mortar mix in delivery containers on elevated platforms in a dry location or in covered weatherproof dispensing silos.
- E. Store masonry accessories, including metal items, to prevent corrosion and accumulation of dirt and oil.

# 1.9 FIELD CONDITIONS

- A. Protection of Masonry: During construction, cover tops of walls, projections, and sills with waterproof sheeting at end of each day's work. Cover partially completed masonry when construction is not in progress.
  - 1. Extend cover a minimum of 24 inches (600 mm) down both sides of walls, and hold cover securely in place.

2. Where one wythe of multiwythe masonry walls is completed in advance of other wythes, secure cover a minimum of 24 inches (600 mm) down face next to unconstructed wythe, and hold cover in place.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Do not apply uniform floor or roof loads for at least 12 hours and concentrated loads for at least three days after building masonry walls or columns.
- C. Stain Prevention: Prevent grout, mortar, and soil from staining the face of masonry to be left exposed. Immediately remove grout, mortar, and soil that come in contact with such masonry.
  - 1. Protect base of walls from rain-splashed mud and from mortar splatter by spreading coverings on ground and over wall surface.
  - 2. Protect sills, ledges, and projections from mortar droppings.
  - 3. Protect surfaces of window and door frames, as well as similar products with painted and integral finishes, from mortar droppings.
  - 4. Turn scaffold boards near the wall on edge at the end of each day to prevent rain from splashing mortar and dirt onto completed masonry.
- D. Cold-Weather Requirements: Do not use frozen materials or materials mixed or coated with ice or frost. Do not build on frozen substrates. Remove and replace unit masonry damaged by frost or by freezing conditions. Comply with cold-weather construction requirements contained in TMS 602/ACI 530.1/ASCE 6.
  - 1. Cold-Weather Cleaning: Use liquid cleaning methods only when air temperature is 40 deg F (4 deg C) and higher and will remain so until masonry has dried, but not less than seven days after completing cleaning.
- E. Hot-Weather Requirements: Comply with hot-weather construction requirements contained in TMS 602/ACI 530.1/ASCE 6.

### PART 2 - PRODUCTS

# 2.1 MANUFACTURERS

- A. Source Limitations for Masonry Units: Obtain exposed masonry units of a uniform texture and color, or a uniform blend within the ranges accepted for these characteristics, from single source from single manufacturer for each product required.
- B. Source Limitations for Mortar Materials: Obtain mortar ingredients of a uniform quality, including color for exposed masonry, from single manufacturer for each cementitious component and from single source or producer for each aggregate.

# 2.2 PERFORMANCE REQUIREMENTS

A. Provide structural unit masonry that develops indicated net-area compressive strengths at 28 days.

1. Determine net-area compressive strength of masonry from average net-area compressive strengths of masonry units and mortar types (unit-strength method) according to TMS 602/ACI 530.1/ASCE 6.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# 2.3 UNIT MASONRY, GENERAL

- A. Masonry Standard: Comply with TMS 602/ACI 530.1/ASCE 6, except as modified by requirements in the Contract Documents.
- B. Defective Units: Referenced masonry unit standards may allow a certain percentage of units to contain chips, cracks, or other defects exceeding limits stated. Do not use units where such defects are exposed in the completed Work.
- C. Aggregate: Lightweight aggregates shall be expanded shale, clay, slate or slag.
  - 1. CMU shall be free of combustible matter and organic impurities that may cause rust, staining or material pop outs. The use of coal, coke, cinder/bottom ash or similar type aggregates is prhibited.

### 2.4 CONCRETE MASONRY UNITS

- A. Shapes: Provide shapes indicated and as follows, with exposed surfaces matching exposed faces of adjacent units unless otherwise indicated.
  - 1. Provide special shapes for lintels, corners, jambs, sashes, movement joints, headers, bonding, and other special conditions.
  - 2. Provide square edge units for outside corners.

## B. CMUs: ASTM C 90.

- 1. Density Classification: Lightweight.
- 2. Size (Width): Manufactured to dimensions 3/8 inch (10 mm) less than nominal dimensions.
- 3. Faces To Receive Plaster: Where units are indicated to receive a direct application of plaster, provide textured-face units made with gap-graded aggregates.

# 2.5 MASONRY LINTELS

A. Masonry Lintels: Prefabricated or built-in-place masonry lintels made from bond beam CMUs matching adjacent CMUs in color, texture, and density classification, with reinforcing bars placed as indicated and filled with coarse grout. Cure precast lintels before handling and installing. Temporarily support built-in-place lintels until cured.

# 2.6 BRICK

A. General: Provide shapes indicated and as follows, with exposed surfaces matching finish and color of exposed faces of adjacent units:

1. For ends of sills and caps and for similar applications that would otherwise expose unfinished brick surfaces, provide units without cores or frogs and with exposed surfaces finished.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Face Brick: Facing brick complying with ASTM C 216.
  - 1. Products: Subject to compliance with requirements, provide the following:
    - a. BR-1 Field Brick:
      - 1) Palmetto Brick Company, .75 Greystone, Modular
  - 2. Grade: SW.
  - 3. Type: FBS.
  - 4. Initial Rate of Absorption: Less than 30 g/30 sq. in. (30 g/194 sq. cm) per minute when tested according to ASTM C 67.
  - 5. Efflorescence: Provide brick that has been tested according to ASTM C 67 and is rated "not effloresced."
  - 6. Size (Actual Dimensions): Modular Size units of 3-5/8 inches wide by 2-1/4" inches high by 7-5/8 inches long.

# 2.7 MORTAR AND GROUT MATERIALS

- A. Portland Cement: ASTM C 150/C 150M, Type I or II, except Type III may be used for cold-weather construction. Provide natural color or white cement as required to produce mortar color indicated.
  - 1. Alkali content shall not be more than 0.1 percent when tested according to ASTM C 114.
- B. Hydrated Lime: ASTM C 207, Type S.
- C. Portland Cement-Lime Mix: Packaged blend of portland cement and hydrated lime containing no other ingredients.
- D. Masonry Cement: ASTM C 91/C 91M.
- E. Mortar Cement: ASTM C 1329/C 1329M.
  - 1. Natural Gray, manufacturer's standard gray mortar color
- F. Aggregate for Mortar: ASTM C 144.
  - 1. For mortar that is exposed to view, use washed aggregate consisting of natural sand or crushed stone.
  - 2. For joints less than 1/4 inch (6 mm) thick, use aggregate graded with 100 percent passing the No. 16 (1.18-mm) sieve.
  - 3. Colored-Mortar Aggregates: Natural sand or crushed stone of color necessary to produce required mortar color.
- G. Aggregate for Grout: ASTM C 404.

H. Cold-Weather Admixture: Nonchloride, noncorrosive, accelerating admixture complying with ASTM C 494/C 494M, Type C, and recommended by manufacturer for use in masonry mortar of composition indicated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- I. Water: Potable.
- J. Color: As selected by the Architect from the Manufacturer's standard selections to match the buff color mortar of the existing building.

# 2.8 REINFORCEMENT

- A. Uncoated-Steel Reinforcing Bars: ASTM A 615/A 615M or ASTM A 996/A 996M, Grade 60 (Grade 420).
- B. Masonry-Joint Reinforcement, General: ASTM A 951/A 951M.
  - 1. Interior Walls: Hot-dip galvanized carbon steel.
  - 2. Exterior Walls: Hot-dip galvanized carbon steel.
  - 3. Wire Size for Side Rods: 0.148-inch (3.77-mm) diameter.
  - 4. Wire Size for Cross Rods: 0.148-inch (3.77-mm) diameter.
  - 5. Wire Size for Veneer Ties: 0.148-inch (3.77-mm) diameter.
  - 6. Spacing of Cross Rods, Tabs, and Cross Ties: Not more than 16 inches (407 mm) o.c.
  - 7. Provide in lengths of not less than 10 feet (3 m), with prefabricated corner and tee units.
- C. Masonry-Joint Reinforcement for Single-Wythe Masonry: Ladder type with single pair of side rods.
- D. Masonry-Joint Reinforcement for Multiwythe Masonry:
  - 1. Adjustable (two-piece) type, ladder type, with one side rod at each face shell of backing wythe and with separate adjustable ties with pintle-and-eye connections having a maximum horizontal play of 1/16 inch (1.5 mm) and maximum vertical adjustment of 1-1/4 inches (32 mm). Size ties to extend at least halfway through facing wythe but with at least 5/8-inch (16-mm) cover on outside face.

# 2.9 TIES AND ANCHORS

- A. General: Ties and anchors shall extend at least 1-1/2 inches (38 mm) into veneer but with at least a 5/8-inch (16-mm) cover on outside face. Outer ends of wires are bent 90 degrees and extend 2 inches (50 mm) parallel to face of veneer.
- B. Materials: Provide ties and anchors specified in this article that are made from materials that comply with the following unless otherwise indicated:
  - 1. Hot-Dip Galvanized, Carbon-Steel Wire: ASTM A 82/A 82M, with ASTM A 153/A 153M, Class B-2 coating.
  - 2. Steel Sheet, Galvanized after Fabrication: ASTM A 1008/A 1008M, Commercial Steel, with ASTM A 153/A 153M, Class B coating.
  - 3. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M.
  - 4. Stainless-Steel Bars: ASTM A 276 or ASTM A 666, Type 304.

- C. Individual Wire Ties: Rectangular units with closed ends and not less than 4 inches (100 mm) wide.
  - 1. Z-shaped ties with ends bent 90 degrees to provide hooks not less than 2 inches (50 mm) long may be used for masonry constructed from solid units.

Issue Date: 06/05/2014

- 2. Where wythes are of different materials, use adjustable ties with pintle-and-eye connections having a maximum adjustment of 1-1/4 inches (32 mm).
- 3. Wire: Fabricate from 3/16-inch- (4.76-mm-) diameter, hot-dip galvanized steel wire.
- D. Adjustable Anchors for Connecting to Concrete: Provide anchors that allow vertical or horizontal adjustment but resist tension and compression forces perpendicular to plane of wall.
  - 1. Connector Section: Dovetail tabs for inserting into dovetail slots in concrete and attached to tie section; formed from 0.060-inch- (1.52-mm-) thick steel sheet, galvanized after fabrication.
  - 2. Tie Section: Triangular-shaped wire tie made from 0.187-inch- (4.76-mm-) diameter, hot-dip galvanized steel wire.
- E. Partition Top Anchors: 0.105-inch- (2.66-mm-) thick metal plate with a 3/8-inch- (9.5-mm-) diameter metal rod 6 inches (152 mm) long welded to plate and with closed-end plastic tube fitted over rod that allows rod to move in and out of tube. Fabricate from steel, hot-dip galvanized after fabrication.
- F. Adjustable Masonry-Veneer Anchors:
  - 1. General: Provide anchors that allow vertical adjustment but resist a 100-lbf (445-N) load in both tension and compression perpendicular to plane of wall without deforming or developing play in excess of 1/16 inch (1.5 mm).
  - 2. Fabricate sheet metal anchor sections and other sheet metal parts from 0.105-inch- (2.66-mm-) thick steel sheet, galvanized after fabrication.
  - 3. Fabricate wire ties from 0.187-inch- (4.76-mm-) diameter, hot-dip galvanized-steel wire unless otherwise indicated.
  - 4. Screw-Attached, Masonry-Veneer Anchors: Wire tie and a corrosion-resistant, self-drilling, eye-screw designed to receive wire tie. Eye-screw has spacer that seats directly against framing and is same thickness as sheathing and has gasketed washer head that covers hole in sheathing.
    - a. <u>Products:</u> Subject to compliance with requirements, provide one of the following:
      - 1) <u>Heckmann Building Products, Inc.</u>; Pos-I-Tie.
      - 2) <u>Hohmann & Barnard, Inc;</u> 2-Seal Tie.
      - 3) Wire-Bond; SureTie.

# 2.10 EMBEDDED FLASHING MATERIALS

A. Flexible Flashing: Use the following unless otherwise indicated:

- 1. Copper-Laminated Flashing: 5-oz./sq. ft. (1.5-kg/sq. m) copper sheet bonded between two layers of glass-fiber cloth. Use only where flashing is fully concealed in masonry.
  - a. <u>Products:</u> Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to the following:

Issue Date: 06/05/2014

- 1) Advanced Building Products Inc.; Copper Fabric Flashing.
- 2) <u>Hohmann & Barnard, Inc;</u> Copper Fabric Flashing.
- 3) York Manufacturing, Inc; Multi-Flash 500.
- 2. Self-Adhering, High-Temperature Sheet: Minimum 30 mils (0.76 mm) thick, consisting of a slip-resistant polyethylene- or polypropylene-film top surface laminated to a layer of butyl- or SBS-modified asphalt adhesive, with release-paper backing; specifically designed to withstand high metal temperatures beneath metal roofing. Provide primer according to written recommendations of underlayment manufacturer.
  - a. <u>Manufacturers:</u> Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - 1) Carlisle Coatings & Waterproofing Inc.
    - 2) Grace Construction Products; W.R. Grace & Co. -- Conn.
    - 3) Henry Company.
    - 4) Metal-Fab Manufacturing, LLC.
    - 5) Owens Corning.
  - b. Thermal Stability: ASTM D 1970; stable after testing at 240 deg F (116 deg C) or higher.
  - c. Low-Temperature Flexibility: ASTM D 1970; passes after testing at minus 20 deg F (29 deg C) or lower.
- B. Application: Unless otherwise indicated, use the following:
  - 1. Where flashing is indicated to be turned down at or beyond the wall face, use Copper-Laminated Flashing.
  - 2. Where flashing is partly exposed and is indicated to terminate at the wall face, use Copper-Laminated Flashing.
  - 3. Where flashing is fully concealed, use self-adhering flexible flashing.
- C. Adhesives, Primers, and Seam Tapes for Flashings: Flashing manufacturer's standard products or products recommended by flashing manufacturer for bonding flashing sheets to each other and to substrates.
- D. Termination Bars for Flexible Flashing: Stainless-steel sheet 0.019 inch by 1-1/2 inches (0.48 mm by 38 mm) with a 3/8 inch (10-mm) sealant flange at top.

# 2.11 MISCELLANEOUS MASONRY ACCESSORIES

A. Compressible Filler: Premolded filler strips complying with ASTM D 1056, Grade 2A1; compressible up to 35 percent; of width and thickness indicated; formulated from urethane.

B. Preformed Control-Joint Gaskets: Made from styrene-butadiene-rubber compound, complying with ASTM D 2000, Designation M2AA-805 and designed to fit standard sash block and to maintain lateral stability in masonry wall; size and configuration as indicated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- C. Bond-Breaker Strips: Asphalt-saturated felt complying with ASTM D 226/D 226M, Type I (No. 15 asphalt felt).
- D. Weep/Cavity Vent Products: Use the following unless otherwise indicated:
  - 1. Cellular Plastic Weep/Vent: One-piece, flexible extrusion made from UV-resistant polypropylene copolymer, full height and width of head joint and depth 1/8 inch (3 mm) less than depth of outer wythe, in color selected from manufacturer's standard.
    - a. <u>Products:</u> Subject to compliance with requirements, provide one of the following:
      - 1) Advanced Building Products Inc.; Mortar Maze Cell Vent.
      - 2) Heckmann Building Products, Inc.; No. 85 Cell Vent.
      - 3) Hohmann & Barnard, Inc; QV Quadro-Vent.
      - 4) Wire-Bond; Cell Vent.
- E. Cavity Drainage Material: Free-draining mesh, made from polymer strands that will not degrade within the wall cavity (typically not shown on drawings for clarity).
  - 1. <u>Products:</u> Subject to compliance with requirements, provide one of the following:
    - a. Advanced Building Products Inc.; Mortar Break.
    - b. <u>CavClear/Archovations, Inc.</u>; CavClear Masonry Mat.
    - c. <u>Wire-Bond</u>;Cavity Net I.
  - 2. Configuration: Provide one of the following:
    - a. Strips, 3/4" Thickness and 16 inches (406 mm) high, lay in strips for full height and width of cavity.
    - b. Or Sheets, 3/4" Thickness and 48 inches wide, lay in strips for full height and width of cavity.
- F. Reinforcing Bar Positioners: Wire Units designed to fit into mortar bed joints spanning masonry unit cells and hold reinforcing bars in center of cells. Units are formed from 0.148-inch (3.77-mm) steel wire, hot-dip galvanized after fabrication. Provide units designed for number of bars indicated.

# 2.12 CAVITY INSULATION

A. Refer to Section 07 21 00, "Thermal Insulation".

#### 2.13 MASONRY CLEANERS

- A. Proprietary Acidic Cleaner: Manufacturer's standard-strength cleaner designed for removing mortar/grout stains, efflorescence, and other new construction stains from new masonry without discoloring or damaging masonry surfaces. Use product expressly approved for intended use by cleaner manufacturer and manufacturer of masonry units being cleaned.
  - 1. Products: Subject to compliance with requirements, provide one of the following:

- a. <u>Diedrich Technologies, Inc.</u>
- b. <u>EaCo Chem, Inc.</u>
- c. PROSOCO, Inc

### 2.14 MORTAR AND GROUT MIXES

- A. General: Do not use admixtures, including pigments, air-entraining agents, accelerators, retarders, water-repellent agents, antifreeze compounds, or other admixtures unless otherwise indicated.
  - 1. Do not use calcium chloride in mortar or grout.
  - 2. Use mortar cement mortar unless otherwise indicated.
  - 3. Add cold-weather admixture (if used) at same rate for all mortar that will be exposed to view, regardless of weather conditions, to ensure that mortar color is consistent.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Preblended, Dry Mortar Mix: Furnish dry mortar ingredients in form of a preblended mix. Measure quantities by weight to ensure accurate proportions, and thoroughly blend ingredients before delivering to Project site.
- C. Mortar for Unit Masonry: Comply with ASTM C 270, Proportion Specification. Provide the following types of mortar for applications stated unless another type is indicated.
  - 1. For masonry below grade or in contact with earth, use Type S.
  - 2. For reinforced masonry, use Type S.
  - 3. For mortar parge coats, use Type S.
  - 4. For exterior, above-grade, load-bearing and nonload-bearing walls and parapet walls; for interior load-bearing walls; for interior nonload-bearing partitions; and for other applications where another type is not indicated, use Type N.
  - 5. For brick veneer above grade, use Type "N"
- D. Mortar Color: Use cement product or select and proportion pigments with other ingredients to produce color required. Do not add pigments to colored cement products.
  - 1. Pigments shall not exceed 5 percent of mortar cement by weight.
  - 2. Color: Natural Gray
  - 3. Application: Use gray mortar for exposed mortar joints with the following units:
    - a. Exposed CMUs.
    - b. Brick Veneer.
- E. Grout for Unit Masonry: Comply with ASTM C 476.
  - 1. Use grout of type indicated or, if not otherwise indicated, of type (fine or coarse) that will comply with TMS 602/ACI 530.1/ASCE 6 for dimensions of grout spaces and pour height.
  - 2. Proportion grout in accordance with ASTM C 476, Table 1 or paragraph 4.2.2 for specified 28-day compressive strength indicated, but not less than 2500 psi (17.23 MPa).
  - 3. Provide grout with a slump of 8 to 11 inches (200 to 280 mm) as measured according to ASTM C 143/C 143M.

### PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
  - 1. For the record, prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Verify that foundations are within tolerances specified.
- 3. Verify that reinforcing dowels are properly placed.
- 4. Verify that substrates are free of substances that impair mortar bond.
- B. Before installation, examine rough-in and built-in construction for piping systems to verify actual locations of piping connections.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 INSTALLATION, GENERAL

- A. Thickness: Build cavity and composite walls and other masonry construction to full thickness shown. Build single-wythe walls to actual widths of masonry units, using units of widths indicated.
- B. Build chases and recesses to accommodate items specified in this and other Sections.
- C. Leave openings for equipment to be installed before completing masonry. After installing equipment, complete masonry to match construction immediately adjacent to opening.
- D. Use full-size units without cutting if possible. If cutting is required to provide a continuous pattern or to fit adjoining construction, cut units with motor-driven saws; provide clean, sharp, unchipped edges. Allow units to dry before laying unless wetting of units is specified. Install cut units with cut surfaces and, where possible, cut edges concealed.
- E. Select and arrange units for exposed unit masonry to produce a uniform blend of colors and textures. Mix units from several pallets or cubes as they are placed.
- F. Wetting of Brick: Wet brick before laying if initial rate of absorption exceeds 30 g/30 sq. in. (30 g/194 sq. cm) per minute when tested according to ASTM C 67. Allow units to absorb water so they are damp but not wet at time of laying.

# 3.3 TOLERANCES

- A. Dimensions and Locations of Elements:
  - 1. For dimensions in cross section or elevation, do not vary by more than plus 1/2 inch (12 mm) or minus 1/4 inch (6 mm).

2. For location of elements in plan, do not vary from that indicated by more than plus or minus 1/2 inch (12 mm).

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

3. For location of elements in elevation, do not vary from that indicated by more than plus or minus 1/4 inch (6 mm) in a story height or 1/2 inch (12 mm) total.

#### B. Lines and Levels:

- 1. For bed joints and top surfaces of bearing walls, do not vary from level by more than 1/4 inch in 10 feet (6 mm in 3 m), or 1/2-inch (12-mm) maximum.
- 2. For conspicuous horizontal lines, such as lintels, sills, parapets, and reveals, do not vary from level by more than 1/8 inch in 10 feet (3 mm in 3 m), 1/4 inch in 20 feet (6 mm in 6 m), or 1/2-inch (12-mm) maximum.
- 3. For vertical lines and surfaces, do not vary from plumb by more than 1/4 inch in 10 feet (6 mm in 3 m), 3/8 inch in 20 feet (9 mm in 6 m), or 1/2-inch (12-mm) maximum.
- 4. For conspicuous vertical lines, such as external corners, door jambs, reveals, and expansion and control joints, do not vary from plumb by more than 1/8 inch in 10 feet (3 mm in 3 m), 1/4 inch in 20 feet (6 mm in 6 m), or 1/2-inch (12-mm) maximum.
- 5. For lines and surfaces, do not vary from straight by more than 1/4 inch in 10 feet (6 mm in 3 m), 3/8 inch in 20 feet (9 mm in 6 m), or 1/2-inch (12-mm) maximum.
- 6. For vertical alignment of exposed head joints, do not vary from plumb by more than 1/4 inch in 10 feet ((6 mm in 3 m),) or 1/2-inch (12-mm) maximum.
- 7. For faces of adjacent exposed masonry units, do not vary from flush alignment by more than 1/16 inch (1.5 mm) except due to warpage of masonry units within tolerances specified for warpage of units.

#### C. Joints:

- 1. For bed joints, do not vary from thickness indicated by more than plus or minus 1/8 inch (3 mm), with a maximum thickness limited to 1/2 inch (12 mm).
- 2. For exposed bed joints, do not vary from bed-joint thickness of adjacent courses by more than 1/8 inch (3 mm).
- 3. For head and collar joints, do not vary from thickness indicated by more than plus 3/8 inch (9 mm) or minus 1/4 inch (6 mm).
- 4. For exposed head joints, do not vary from thickness indicated by more than plus or minus 1/8 inch (3 mm). Do not vary from adjacent bed-joint and head-joint thicknesses by more than 1/8 inch (3 mm).

#### 3.4 LAYING MASONRY WALLS

- A. Lay out walls in advance for accurate spacing of surface bond patterns with uniform joint thicknesses and for accurate location of openings, movement-type joints, returns, and offsets. Avoid using less-than-half-size units, particularly at corners, jambs, and, where possible, at other locations.
- B. Bond Pattern for Exposed Masonry: Unless otherwise indicated, lay exposed masonry in one-third running bond; do not use units with less-than-nominal 4-inch (100-mm) horizontal face dimensions at corners or jambs.

C. Lay concealed masonry with all units in a wythe in running bond or bonded by lapping not less than 4 inches (100 mm). Bond and interlock each course of each wythe at corners. Do not use units with less-than-nominal 4-inch (100-mm) horizontal face dimensions at corners or jambs.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- D. Stopping and Resuming Work: Stop work by stepping back units in each course from those in course below; do not tooth. When resuming work, clean masonry surfaces that are to receive mortar, remove loose masonry units and mortar, and wet brick if required before laying fresh masonry.
- E. Built-in Work: As construction progresses, build in items specified in this and other Sections. Fill in solidly with masonry around built-in items.
- F. Fill space between steel frames and masonry solidly with mortar unless otherwise indicated.
- G. Where built-in items are to be embedded in cores of hollow masonry units, place a layer of metal lath, wire mesh, or plastic mesh in the joint below, and rod mortar or grout into core.
- H. Fill cores in hollow CMUs with grout 24 inches (600 mm) under bearing plates, beams, lintels, posts, and similar items unless otherwise indicated.
- I. Build nonload-bearing interior partitions full height of story to underside of solid roof structure above unless otherwise indicated.
  - 1. Install compressible filler in joint between top of partition and underside of structure above.
  - 2. Fasten partition top anchors to structure above and build into top of partition. Grout cells of CMUs solidly around plastic tubes of anchors and push tubes down into grout to provide 1/2-inch (13-mm) clearance between end of anchor rod and end of tube. Space anchors 48 inches (1200 mm) o.c. unless otherwise indicated.

# 3.5 MORTAR BEDDING AND JOINTING

- A. Lay brick and CMUs as follows:
  - 1. Bed face shells in mortar and make head joints of depth equal to bed joints.
  - 2. Bed webs in mortar in all courses of piers, columns, and pilasters.
  - 3. Bed webs in mortar in grouted masonry, including starting course on footings.
  - 4. Fully bed entire units, including areas under cells, at starting course on footings where cells are not grouted.
  - 5. Fully bed units and fill cells with mortar at anchors and ties as needed to fully embed anchors and ties in mortar.
- B. Lay solid masonry units with completely filled bed and head joints; butter ends with sufficient mortar to fill head joints and shove into place. Do not deeply furrow bed joints or slush head joints.
- C. Set cast-stone trim units in full bed of mortar with full vertical joints. Fill dowel, anchor, and similar holes.

1. Clean soiled surfaces with fiber brush and soap powder and rinse thoroughly with clear water.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Wet joint surfaces thoroughly before applying mortar.
- D. Tool exposed joints slightly concave when thumbprint hard, using a jointer larger than joint thickness unless otherwise indicated.
- E. Cut joints flush for masonry walls to receive plaster or other direct-applied finishes (other than paint) unless otherwise indicated.

#### 3.6 CAVITY WALLS

- A. Bond wythes of cavity walls together using one of the following methods:
  - 1. Masonry-Joint Reinforcement: Installed in horizontal mortar joints.
    - a. Where one wythe is of clay masonry and the other of concrete masonry, use adjustable-type (two-piece-type) reinforcement to allow for differential movement regardless of whether bed joints align.
  - 2. Masonry-Veneer Anchors: Comply with requirements for anchoring masonry veneers.
- B. Keep cavities clean of mortar droppings and other materials during construction. Bevel beds away from cavity, to minimize mortar protrusions into cavity. Do not attempt to trowel or remove mortar fins protruding into cavity.
- C. Coat Cavity face of backup wythe to comply with Section 071113 "Bituminuous Dampproofing".
- D. Installing Cavity Wall Insulation: Place small dabs of adhesive, spaced approximately 12 inches (300 mm) o.c. both ways, on inside face of insulation boards, or attach with plastic fasteners designed for this purpose. Fit courses of insulation between wall ties and other confining obstructions in cavity, with edges butted tightly both ways. Press units firmly against inside wythe of masonry or other construction as shown.
  - 1. Fill cracks and open gaps in insulation with crack sealer compatible with insulation and masonry.
- E. Install Cavity Drainage Material for full height and width of cavity walls in horizontal rows between reinforcing ties. Butt joints in cavity drainage material tightly without gaps.
  - 1. If larger sheets are used, allow masonry reinforcing ties to pass through the cavity drainage material.

#### 3.7 ANCHORED MASONRY VENEERS

- A. Anchor masonry veneers to wall framing with masonry-veneer anchors to comply with the following requirements:
  - 1. Fasten screw-attached anchors through sheathing to wall framing with metal fasteners of type indicated. Use two fasteners unless anchor design only uses one fastener.

- 2. Embed tie sections in masonry joints.
- 3. Locate anchor sections to allow maximum vertical differential movement of ties up and down.

Issue Date: 06/05/2014

- 4. Space anchors as indicated, but not more than 16 inches (406 mm) o.c. vertically and 16 inches (406 mm) o.c. horizontally, with not less than one anchor for each 2 sq. ft. (0.2 sq. m) of wall area. Install additional anchors within 12 inches (305 mm) of openings and at intervals, not exceeding 8 inches (203 mm), around perimeter.
- B. Provide not less than 1 inches (25 mm) of airspace between back of masonry veneer and face of sheathing.
  - 1. Keep airspace clean of mortar droppings and other materials during construction. Bevel beds away from airspace, to minimize mortar protrusions into airspace. Do not attempt to trowel or remove mortar fins protruding into airspace.

#### 3.8 MASONRY-JOINT REINFORCEMENT

- A. General: Where otherwise not indicated on the structural drawings, install entire length of longitudinal side rods in mortar with a minimum cover of 5/8 inch (16 mm) on exterior side of walls, 1/2 inch (13 mm) elsewhere. Lap reinforcement a minimum of 6 inches (150 mm).
  - 1. Space reinforcement not more than 16 inches (406 mm) o.c.
  - 2. Space reinforcement not more than 8 inches (203 mm) o.c. in foundation walls and parapet walls.
  - 3. Provide reinforcement not more than 8 inches (203 mm) above and below wall openings and extending 12 inches (305 mm) beyond openings in addition to continuous reinforcement.
- B. Interrupt joint reinforcement at control and expansion joints unless otherwise indicated.
- C. Provide continuity at wall intersections by using prefabricated T-shaped units.
- D. Provide continuity at corners by using prefabricated L-shaped units.
- E. Cut and bend reinforcing units as directed by manufacturer for continuity at corners, returns, offsets, column fireproofing, pipe enclosures, and other special conditions.

#### 3.9 CONTROL AND EXPANSION JOINTS

- A. General: Install control- and expansion-joint materials in unit masonry as masonry progresses. Do not allow materials to span control and expansion joints without provision to allow for inplane wall or partition movement.
- B. Form control joints in concrete masonry as follows:
  - 1. Install preformed control-joint gaskets designed to fit standard sash block.
- C. Form expansion joints in brick as follows:

1. Form open joint full depth of brick wythe and of width indicated, but not less than 3/8 inch (10 mm) for installation of sealant and backer rod specified in Section 079200 "Joint Sealants."

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 3.10 LINTELS

- A. Install steel lintels where indicated.
- B. Provide masonry or steel lintels as indicated on the structural drawings. Where openings of more than 12 inches (305 mm) for brick-size units and 24 inches (610 mm) for block-size units are shown without structural steel or other supporting lintels, provide masonry lintels.
- C. Provide minimum bearing of 8 inches (200 mm) at each jamb unless otherwise indicated.

# 3.11 FLASHING, WEEP HOLES, AND CAVITY VENTS

- A. General: Install embedded flashing and weep holes in masonry at shelf angles, lintels, ledges, other obstructions to downward flow of water in wall, and where indicated. Install cavity vents at shelf angles, ledges, and other obstructions to upward flow of air in cavities, and where indicated.
- B. Install flashing as follows unless otherwise indicated:
  - 1. Prepare masonry surfaces so they are smooth and free from projections that could puncture flashing. Where flashing is within mortar joint, place through-wall flashing on sloping bed of mortar and cover with mortar. Before covering with mortar, seal penetrations in flashing with adhesive, sealant, or tape as recommended by flashing manufacturer.
  - 2. At multiwythe masonry walls, including cavity walls, extend flashing through outer wythe, turned up a minimum of 8 inches (200 mm), and through inner wythe to within 1/2 inch (13 mm) of the interior face of wall in exposed masonry. Where interior face of wall is to receive furring or framing, carry flashing completely through inner wythe and turn flashing up approximately 2 inches (50 mm) on interior face.
  - 3. At lintels and angles, extend flashing a minimum of 6 inches (150 mm) into masonry at each end. At heads and sills, extend flashing 6 inches (150 mm) at ends and turn up not less than 2 inches (50 mm) to form end dams.
- C. Install reglets and nailers for flashing and other related construction where they are shown to be built into masonry.
- D. Install weep holes in exterior wythes and veneers in head joints of first course of masonry immediately above embedded flashing.
  - 1. Use specified weep/cavity vent products to form weep holes.
  - 2. Space weep holes 24 inches (600 mm) o.c. unless otherwise indicated.
- E. Place cavity drainage material in cavities to comply with configuration requirements for cavity drainage material in "Miscellaneous Masonry Accessories" Article.

- F. Install cavity vents in head joints in exterior wythes at spacing indicated. Use specified weep/cavity vent products to form cavity vents.
  - 1. Close cavities off vertically and horizontally with blocking in manner indicated. Install through-wall flashing and weep holes above horizontal blocking.

Issue Date: 06/05/2014

#### 3.12 REINFORCED UNIT MASONRY INSTALLATION

- A. Temporary Formwork and Shores: Construct formwork and shores as needed to support reinforced masonry elements during construction.
  - 1. Construct formwork to provide shape, line, and dimensions of completed masonry as indicated. Make forms sufficiently tight to prevent leakage of mortar and grout. Brace, tie, and support forms to maintain position and shape during construction and curing of reinforced masonry.
  - 2. Do not remove forms and shores until reinforced masonry members have hardened sufficiently to carry their own weight and that of other loads that may be placed on them during construction.
- B. Placing Reinforcement: Comply with requirements in TMS 602/ACI 530.1/ASCE 6.
- C. Grouting: Do not place grout until entire height of masonry to be grouted has attained enough strength to resist grout pressure.
  - 1. Comply with requirements in TMS 602/ACI 530.1/ASCE 6 for cleanouts and for grout placement, including minimum grout space and maximum pour height.
  - 2. Limit height of vertical grout pours to not more than 60 inches (1520 mm).

# 3.13 FIELD QUALITY CONTROL

- A. Testing and Inspecting: Owner will engage special inspectors to perform tests and inspections and prepare reports. Allow inspectors access to scaffolding and work areas as needed to perform tests and inspections. Retesting of materials that fail to comply with specified requirements shall be done at Contractor's expense.
- B. Inspections: Level 1 Special inspections according to the International building Code.
  - 1. Begin masonry construction only after inspectors have verified proportions of siteprepared mortar.
  - 2. Place grout only after inspectors have verified compliance of grout spaces and of grades, sizes, and locations of reinforcement.
  - 3. Place grout only after inspectors have verified proportions of site-prepared grout.
- C. Testing Prior to Construction: One set of tests.
- D. Testing Frequency: One set of tests for each 5000 sq. ft. (464 sq. m) of wall area or portion thereof.

E. Concrete Masonry Unit Test: For each type of unit provided, according to ASTM C 140 for compressive strength.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- F. Mortar Test (Property Specification): For each mix provided, according to ASTM C 780. Test mortar for compressive strength.
- G. Grout Test (Compressive Strength): For each mix provided, according to ASTM C 1019.

# 3.14 REPAIRING, POINTING, AND CLEANING

- A. Remove and replace masonry units that are loose, chipped, broken, stained, or otherwise damaged or that do not match adjoining units. Install new units to match adjoining units; install in fresh mortar, pointed to eliminate evidence of replacement.
- B. Pointing: During the tooling of joints, enlarge voids and holes, except weep holes, and completely fill with mortar. Point up joints, including corners, openings, and adjacent construction, to provide a neat, uniform appearance. Prepare joints for sealant application, where indicated.
- C. In-Progress Cleaning: Clean unit masonry as work progresses by dry brushing to remove mortar fins and smears before tooling joints.
- D. Final Cleaning: After mortar is thoroughly set and cured, clean exposed masonry as follows:
  - 1. Remove large mortar particles by hand with wooden paddles and nonmetallic scrape hoes or chisels.
  - 2. Test cleaning methods on sample wall panel; leave one-half of panel uncleaned for comparison purposes. Obtain Architect's approval of sample cleaning before proceeding with cleaning of masonry.
  - 3. Protect adjacent stone, cast stone and nonmasonry surfaces from contact with cleaner by covering them with liquid strippable masking agent or polyethylene film and waterproof masking tape.
  - 4. Wet wall surfaces with water before applying cleaners; remove cleaners promptly by rinsing surfaces thoroughly with clear water.
  - 5. Clean brick by bucket-and-brush hand-cleaning method described in BIA Technical Notes 20.
  - 6. Clean concrete masonry by applicable cleaning methods indicated in NCMA TEK 8-4A.
  - 7. Clean masonry with a proprietary acidic cleaner applied according to manufacturer's written instructions.
  - 8. Clean stone trim to comply with stone supplier's written instructions.

# 3.15 MASONRY WASTE DISPOSAL

A. Salvageable Materials: Unless otherwise indicated, excess masonry materials are Contractor's property. At completion of unit masonry work, remove from Project site.

END OF SECTION 042000

#### SECTION 051200 - STRUCTURAL STEEL FRAMING

# PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Structural steel.

#### B. Related Sections:

- 1. Division 01 Section "Quality Requirements" for independent testing agency procedures and administrative requirements.
- 2. Division 05 Section "Steel Decking" for field installation of shear connectors through deck.
- 3. Division 09 painting Sections for surface-preparation and priming requirements.

### 1.3 DEFINITIONS

A. Structural Steel: Elements of structural-steel frame, as classified by AISC 303, "Code of Standard Practice for Steel Buildings and Bridges."

# 1.4 PERFORMANCE REQUIREMENTS

- A. Connections: Provide details of simple shear connections required by the Contract Documents to be selected or completed by structural-steel fabricator to withstand loads indicated and comply with other information and restrictions indicated.
  - 1. Select and complete connections using AISC 360.

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Show fabrication of structural-steel components.
  - 1. Include details of cuts, connections, splices, camber, holes, and other pertinent data.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

South Carolina Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Include embedment drawings.
- 3. Indicate welds by standard AWS symbols, distinguishing between shop and field welds, and show size, length, and type of each weld. Show backing bars that are to be removed and supplemental fillet welds where backing bars are to remain.
- 4. Indicate type, size, and length of bolts, distinguishing between shop and field bolts. Identify pretensioned and slip-critical high-strength bolted connections.

# 1.6 INFORMATIONAL SUBMITTALS

- A. Welding certificates.
- B. Paint Compatibility Certificates: From manufacturers of topcoats applied over shop primers, certifying that shop primers are compatible with topcoats.
- C. Mill test reports for structural steel, including chemical and physical properties.
- D. Source quality-control reports.

# 1.7 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code Steel."
- B. Comply with applicable provisions of the following specifications and documents:
  - 1. AISC 303.
  - 2. AISC 341 and AISC 341s1.
  - 3. AISC 360.
  - 4. RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts."

# 1.8 DELIVERY, STORAGE, AND HANDLING

- A. Store materials to permit easy access for inspection and identification. Keep steel members off ground and spaced by using pallets, dunnage, or other supports and spacers. Protect steel members and packaged materials from corrosion and deterioration.
  - 1. Do not store materials on structure in a manner that might cause distortion, damage, or overload to members or supporting structures. Repair or replace damaged materials or structures as directed.
- B. Store fasteners in a protected place in sealed containers with manufacturer's labels intact.
  - 1. Fasteners may be repackaged provided Owner's testing and inspecting agency observes repackaging and seals containers.
  - 2. Clean and relubricate bolts and nuts that become dry or rusty before use.

Re-Bid Set

Issue Date: 06/05/2014

3. Comply with manufacturers' written recommendations for cleaning and lubricating ASTM F 1852 fasteners and for retesting fasteners after lubrication.

Architect's Project #: 12.130.09

# 1.9 COORDINATION

- A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' recommendations to ensure that shop primers and topcoats are compatible with one another.
- B. Coordinate installation of anchorage items to be embedded in or attached to other construction without delaying the Work. Provide setting diagrams, sheet metal templates, instructions, and directions for installation.

# PART 2 - PRODUCTS

#### 2.1 STRUCTURAL-STEEL MATERIALS

- A. W-Shapes: ASTM A 992/A 992M.
- B. Channels, Angles-Shapes: ASTM A 36/A 36M.
- C. Plate and Bar: ASTM A 36/A 36M.
- D. Welding Electrodes: Comply with AWS requirements.

# 2.2 BOLTS, CONNECTORS, AND ANCHORS

- A. High-Strength Bolts, Nuts, and Washers: ASTM A 325 (ASTM A 325M), Type 1, heavy-hex steel structural bolts; ASTM A 563, Grade C, (ASTM A 563M, Class 8S) heavy-hex carbon-steel nuts; and ASTM F 436 (ASTM F 436M), Type 1, hardened carbon-steel washers; all with plain finish.
  - 1. Direct-Tension Indicators: ASTM F 959, Type 325 (ASTM F 959M, Type 8.8), compressible-washer type with plain finish.
- B. Shear Connectors: ASTM A 108, Grades 1015 through 1020, headed-stud type, cold-finished carbon steel; AWS D1.1/D1.1M, Type B.

### 2.3 PRIMER

A. Low-Emitting Materials: Paints and coatings shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

Issue Date: 06/05/2014

- B. Primer: Comply with Division 09 painting Sections.
- C. Primer: SSPC-Paint 25, Type I or Type II, zinc oxide, alkyd, linseed oil primer.
- D. Primer: Fabricator's standard lead- and chromate-free, nonasphaltic, rust-inhibiting primer complying with MPI#79 and compatible with topcoat.

#### 2.4 GROUT

- A. Metallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, metallic aggregate grout, mixed with water to consistency suitable for application and a 30-minute working time.
- B. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive and nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

#### 2.5 FABRICATION

- A. Structural Steel: Fabricate and assemble in shop to greatest extent possible. Fabricate according to AISC's "Code of Standard Practice for Steel Buildings and Bridges" and AISC 360.
  - 1. Camber structural-steel members where indicated.
  - 2. Fabricate beams with rolling camber up.
  - 3. Identify high-strength structural steel according to ASTM A 6/A 6M and maintain markings until structural steel has been erected.
  - 4. Mark and match-mark materials for field assembly.
  - 5. Complete structural-steel assemblies, including welding of units, before starting shop-priming operations.
- B. Thermal Cutting: Perform thermal cutting by machine to greatest extent possible.
  - 1. Plane thermally cut edges to be welded to comply with requirements in AWS D1.1/D1.1M.
- C. Bolt Holes: Cut, drill or punch standard bolt holes perpendicular to metal surfaces.
- D. Finishing: Accurately finish ends of columns and other members transmitting bearing loads.
- E. Cleaning: Clean and prepare steel surfaces that are to remain unpainted according to SSPC-SP 1, "Solvent Cleaning, SSPC-SP 2, "Hand Tool Cleaning or SSPC-SP 3, "Power Tool Cleaning."
- F. Shear Connectors: Prepare steel surfaces as recommended by manufacturer of shear connectors. Use automatic end welding of headed-stud shear connectors according to AWS D1.1/D1.1M and manufacturer's written instructions.

·

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- G. Holes: Provide holes required for securing other work to structural steel and for other work to pass through steel framing members.
  - 1. Cut, drill, or punch holes perpendicular to steel surfaces.
  - 2. Baseplate Holes: Cut, drill, mechanically thermal cut, or punch holes perpendicular to steel surfaces.
  - 3. Weld threaded nuts to framing and other specialty items indicated to receive other work.

#### 2.6 SHOP CONNECTIONS

- A. High-Strength Bolts: Shop install high-strength bolts according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts" for type of bolt and type of joint specified.
  - 1. Joint Type: Snug tightened.
- B. Weld Connections: Comply with AWS D1.1/D1.1M for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.
  - 1. Assemble and weld built-up sections by methods that will maintain true alignment of axes without exceeding tolerances in AISC 303 for mill material.

#### 2.7 SHOP PRIMING

- A. Shop prime steel surfaces except the following:
  - 1. Surfaces embedded in concrete or mortar. Extend priming of partially embedded members to a depth of 2 inches (50 mm).
  - 2. Surfaces to be field welded.
  - 3. Surfaces to be high-strength bolted with slip-critical connections.
  - 4. Surfaces to receive sprayed fire-resistive materials (applied fireproofing).
  - 5. Galvanized surfaces.
- B. Surface Preparation: Clean surfaces to be painted. Remove loose rust and mill scale and spatter, slag, or flux deposits. Prepare surfaces according to the following specifications and standards:
  - 1. SSPC-SP 2, "Hand Tool Cleaning."
  - 2. SSPC-SP 3, "Power Tool Cleaning."
  - 3. SSPC-SP 7/NACE No. 4, "Brush-Off Blast Cleaning."
  - 4. SSPC-SP 11, "Power Tool Cleaning to Bare Metal."
  - 5. SSPC-SP 14/NACE No. 8, "Industrial Blast Cleaning."
  - 6. SSPC-SP 6/NACE No. 3, "Commercial Blast Cleaning."
  - 7. SSPC-SP 10/NACE No. 2, "Near-White Blast Cleaning."
  - 8. SSPC-SP 5/NACE No. 1, "White Metal Blast Cleaning."
  - 9. SSPC-SP 8, "Pickling."

e-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- C. Priming: Immediately after surface preparation, apply primer according to manufacturer's written instructions and at rate recommended by SSPC to provide a minimum dry film thickness of 1.5 mils (0.038 mm). Use priming methods that result in full coverage of joints, corners, edges, and exposed surfaces.
  - 1. Stripe paint corners, crevices, bolts, welds, and sharp edges.
  - 2. Apply two coats of shop paint to surfaces that are inaccessible after assembly or erection. Change color of second coat to distinguish it from first.
- D. Painting: Prepare steel and apply a one-coat, nonasphaltic primer complying with SSPC-PS Guide 7.00, "Painting System Guide 7.00: Guide for Selecting One-Coat Shop Painting Systems," to provide a dry film thickness of not less than 1.5 mils (0.038 mm).

#### 2.8 GALVANIZING

- A. Hot-Dip Galvanized Finish: Apply zinc coating by the hot-dip process to structural steel according to ASTM A 123/A 123M.
  - 1. Fill vent and drain holes that will be exposed in the finished Work unless they will function as weep holes, by plugging with zinc solder and filing off smooth.
  - 2. Galvanize lintels, shelf angles and welded door frames attached to structural-steel frame and located in exterior walls.

# 2.9 SOURCE QUALITY CONTROL

- A. Testing Agency: Owner will engage an independent testing and inspecting agency to perform shop tests and inspections and prepare test reports.
  - 1. Provide testing agency with access to places where structural-steel work is being fabricated or produced to perform tests and inspections.
- B. Correct deficiencies in Work that test reports and inspections indicate does not comply with the Contract Documents.
- C. Bolted Connections: Shop-bolted connections will be inspected according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts."
- D. Welded Connections: In addition to visual inspection, shop-welded connections will be tested and inspected according to AWS D1.1/D1.1M.

Issue Date: 06/05/2014

#### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Verify, with steel Erector present, elevations of concrete- and masonry-bearing surfaces and locations of anchor rods, bearing plates, and other embedments for compliance with requirements.
  - 1. Prepare a certified survey of bearing surfaces, anchor rods, bearing plates, and other embedments showing dimensions, locations, angles, and elevations.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Provide temporary shores, guys, braces, and other supports during erection to keep structural steel secure, plumb, and in alignment against temporary construction loads and loads equal in intensity to design loads. Remove temporary supports when permanent structural steel, connections, and bracing are in place unless otherwise indicated.
  - 1. Do not remove temporary shoring supporting composite deck construction until cast-inplace concrete has attained its design compressive strength.

# 3.3 ERECTION

- A. Set structural steel accurately in locations and to elevations indicated and according to AISC 303 and AISC 360.
- B. Maintain erection tolerances of structural steel within AISC's "Code of Standard Practice for Steel Buildings and Bridges."
- C. Align and adjust various members that form part of complete frame or structure before permanently fastening. Before assembly, clean bearing surfaces and other surfaces that will be in permanent contact with members. Perform necessary adjustments to compensate for discrepancies in elevations and alignment.
  - 1. Level and plumb individual members of structure.
  - 2. Make allowances for difference between temperature at time of erection and mean temperature when structure is completed and in service.
- D. Splice members only where indicated.
- E. Shear Connectors: Prepare steel surfaces as recommended by manufacturer of shear connectors. Use automatic end welding of headed-stud shear connectors according to AWS D1.1/D1.1M and manufacturer's written instructions.

Issue Date: 06/05/2014

# 3.4 FIELD CONNECTIONS

- A. High-Strength Bolts: Install high-strength bolts according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts" for type of bolt and type of joint specified.
  - 1. Joint Type: Snug tightened.
- B. Weld Connections: Comply with AWS D1.1/D1.1M for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.

# 3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified independent testing and inspecting agency to inspect field welds.
- B. Bolted Connections: Bolted connections will be inspected according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts."
- C. Welded Connections: Field welds will be visually inspected according to AWS D1.1/D1.1M.
- D. Correct deficiencies in Work that test reports and inspections indicate does not comply with the Contract Documents.

#### 3.6 REPAIRS AND PROTECTION

- A. Touchup Painting: Immediately after erection, clean exposed areas where primer is damaged or missing and paint with the same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.
  - 1. Clean and prepare surfaces by SSPC-SP 2 hand-tool cleaning or SSPC-SP 3 power-tool cleaning.
- B. Touchup Painting: Cleaning and touchup painting are specified in Division 09 painting Sections.

# END OF SECTION 051200

# SECTION 053100 - STEEL DECKING

# PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Roof deck.
- B. Related Requirements:
  - 1. Division 05 Section "Structural Steel Framing" for shop- and field-welded shear connectors.
  - 2. Division 09 painting Sections for repair painting of primed deck and finish painting of deck.

### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of deck, accessory, and product indicated.
- B. Shop Drawings:
  - 1. Include layout and types of deck panels, anchorage details, reinforcing channels, pans, cut deck openings, special jointing, accessories, and attachments to other construction.

# 1.4 INFORMATIONAL SUBMITTALS

- A. Welding certificates.
- B. Product Certificates: For each type of steel deck.
- C. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, indicating that each of the following complies with requirements:
  - 1. Power-actuated mechanical fasteners.
- D. Evaluation Reports: For steel deck.

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

E. Field quality-control reports.

# 1.5 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Qualified according to ASTM E 329 for testing indicated.
- B. Welding Qualifications: Qualify procedures and personnel according to AWS D1.3, "Structural Welding Code Sheet Steel."
- C. Electrical Raceway Units: Provide UL-labeled cellular floor-deck units complying with UL 209 and listed in UL's "Electrical Construction Equipment Directory" for use with standard header ducts and outlets for electrical distribution systems.
- D. FM Global Listing: Provide steel roof deck evaluated by FM Global and listed in its "Approval Guide, Building Materials" for Class 1 fire rating and Class 1-90 windstorm ratings.

### 1.6 DELIVERY, STORAGE, AND HANDLING

- A. Protect steel deck from corrosion, deformation, and other damage during delivery, storage, and handling.
- B. Stack steel deck on platforms or pallets and slope to provide drainage. Protect with a waterproof covering and ventilate to avoid condensation.
  - 1. Protect and ventilate acoustical cellular roof deck with factory-installed insulation to maintain insulation free of moisture.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. AISI Specifications: Comply with calculated structural characteristics of steel deck according to AISI's "North American Specification for the Design of Cold-Formed Steel Structural Members."
- B. Fire-Resistance Ratings: Comply with ASTM E 119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  - 1. Indicate design designations from UL's "Fire Resistance Directory" or from the listings of another qualified testing agency.
- C. Low-Emitting Materials: Paints and coatings shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

# 2.2 ROOF DECK

- A. Roof Deck: Fabricate panels, without top-flange stiffening grooves, to comply with "SDI Specifications and Commentary for Steel Roof Deck," in SDI Publication No. 31, and with the following:
  - 1. Galvanized-Steel Sheet: ASTM A 653/A 653M, Structural Steel (SS), Grade 33 (230), G60 (Z180) zinc coating.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Deck Profile: As indicated.
- 3. Profile Depth: As indicated.
- 4. Design Uncoated-Steel Thickness: As indicated.
- 5. Design Uncoated-Steel Thicknesses; Deck Unit/Bottom Plate: As indicated.
- 6. Side Laps: Overlapped or interlocking seam at Contractor's option.

# 2.3 ACCESSORIES

- A. General: Provide manufacturer's standard accessory materials for deck that comply with requirements indicated.
- B. Mechanical Fasteners: Corrosion-resistant, low-velocity, power-actuated or pneumatically driven carbon-steel fasteners; or self-drilling, self-threading screws.
- C. Side-Lap Fasteners: Corrosion-resistant, hexagonal washer head; self-drilling, carbon-steel screws, No. 10 (4.8-mm) minimum diameter.
- D. Flexible Closure Strips: Vulcanized, closed-cell, synthetic rubber.
- E. Miscellaneous Sheet Metal Deck Accessories: Steel sheet, minimum yield strength of 33,000 psi (230 MPa), not less than 0.0359-inch (0.91-mm) design uncoated thickness, of same material and finish as deck; of profile indicated or required for application.
- F. Flat Sump Plates: Single-piece steel sheet, 0.0747 inch (1.90 mm) thick, of same material and finish as deck. For drains, cut holes in the field.

# PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine supporting frame and field conditions for compliance with requirements for installation tolerances and other conditions affecting performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 INSTALLATION, GENERAL

A. Install deck panels and accessories according to applicable specifications and commentary in SDI Publication No. 31, manufacturer's written instructions, and requirements in this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Install temporary shoring before placing deck panels if required to meet deflection limitations.
- C. Locate deck bundles to prevent overloading of supporting members.
- D. Place deck panels on supporting frame and adjust to final position with ends accurately aligned and bearing on supporting frame before being permanently fastened. Do not stretch or contract side-lap interlocks.
  - 1. Align cellular deck panels over full length of cell runs and align cells at ends of abutting panels.
- E. Place deck panels flat and square and fasten to supporting frame without warp or deflection.
- F. Cut and neatly fit deck panels and accessories around openings and other work projecting through or adjacent to deck.
- G. Provide additional reinforcement and closure pieces at openings as required for strength, continuity of deck, and support of other work.
- H. Comply with AWS requirements and procedures for manual shielded metal arc welding, appearance and quality of welds, and methods used for correcting welding work.
- I. Mechanical fasteners may be used in lieu of welding to fasten deck. Locate mechanical fasteners and install according to deck manufacturer's written instructions.

# 3.3 ROOF-DECK INSTALLATION

- A. Fasten roof-deck panels to steel supporting members by arc spot (puddle) welds of the surface diameter indicated or arc seam welds with an equal perimeter that is not less than 1-1/2 inches (38 mm) long, and as follows:
  - 1. Weld Diameter: 5/8 inch (16 mm), nominal.
  - 2. Weld Spacing: Weld edge and interior ribs of deck units with a minimum of two welds per deck unit at each support. Space welds 18 inches (457 mm) apart, maximum.
  - 3. Weld Washers: Install weld washers at each weld location.
- B. Side-Lap and Perimeter Edge Fastening: Fasten side laps and perimeter edges of panels between supports, at intervals not exceeding the lesser of 1/2 of the span or 18 inches (457 mm), and as follows:
  - 1. Mechanically fasten with self-drilling, No. 10 (4.8-mm-) diameter or larger, carbon-steel screws.
  - 2. Mechanically clinch or button punch.

- e-Bid Set Issue Date: 06/05/2014
  - 3. Fasten with a minimum of 1-1/2-inch- (38-mm-) long welds.
- C. End Bearing: Install deck ends over supporting frame with a minimum end bearing of 1-1/2 inches (38 mm), with end joints as follows:

- 1. End Joints: Lapped 2 inches (51 mm) minimum.
- D. Flexible Closure Strips: Install flexible closure strips over partitions, walls, and where indicated. Install with adhesive according to manufacturer's written instructions to ensure complete closure.

# 3.4 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Field welds will be subject to inspection.
- C. Testing agency will report inspection results promptly and in writing to Contractor and Architect.
- D. Remove and replace work that does not comply with specified requirements.

# 3.5 PROTECTION

- A. Galvanizing Repairs: Prepare and repair damaged galvanized coatings on both surfaces of deck with galvanized repair paint according to ASTM A 780 and manufacturer's written instructions.
- B. Provide final protection and maintain conditions to ensure that steel deck is without damage or deterioration at time of Substantial Completion.

END OF SECTION 053100

# SECTION 064113 - ARCHITECTURAL CASEWORK

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

#### A. Section Includes:

- 1. Miscellaneous wood blocking and substrate plywood.
- 2. Architectural wood cabinets, (Lockers: Owner Furnished Owner Installed)
- 3. Plastic-laminate-faced architectural cabinets.
- 4. Wood furring, blocking, shims, and hanging strips for installing architectural wood cabinets unless concealed within other construction before cabinet installation.
- 5. Shop finishing of architectural wood cabinets, (Lockers: Owner Furnished Owner Installed)

#### B. Related Requirements:

- 1. Section 012300 "Alternates" for a description Plastic Laminate Casework associated with Alternate Building #1.
- 2. Section 123661 "Simulated Stone Countertops" for countertops associated with Architectural Casework.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product, including high-pressure decorative laminate, adhesive for bonding plastic laminate cabinet hardware and accessories and finishing materials and processes.
- B. Shop Drawings: Show location of each item, dimensioned plans and elevations, large-scale details, attachment devices, and other components.
  - 1. Show details full size.
  - 2. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement specified in other Sections.
  - 3. Show locations and sizes of cutouts and holes for electrical switches and outlets and other items installed in architectural wood cabinets.
  - 4. Show veneer leaves with dimensions, grain direction, exposed face, and identification numbers indicating the flitch and sequence within the flitch for each leaf.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# C. Samples for Initial Selection:

- 1. Shop-applied transparent finishes.
- 2. PVC edge material.

# D. Samples for Verification:

1. Lumber for transparent finish, not less than 5 inches (125 mm) wide by 12 inches (300 mm) long, for each species and cut, finished on one side and one edge.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Veneer leaves representative of and selected from flitches to be used for transparent-finished cabinets.
- 3. Plastic laminates, 8 by 10 inches (200 by 250 mm), for each type, color, pattern, and surface finish, with one sample applied to core material and specified edge material applied to one edge.
- 4. Exposed cabinet hardware and accessories, one unit for each type and finish.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer and fabricator.
- B. Product Certificates: For the following:
  - 1. High-pressure decorative laminate.
  - 2. Adhesives.
- C. Woodwork Quality Standard: acknowledge that all casework is to be fabricated and installed in accordance with the AWI Quality Certification Program. This program establishes the quality for all casework, however, AWI certification is not required.

# 1.5 QUALITY ASSURANCE

- A. Fabricator Qualifications: Shop that employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful inservice performance.
- B. Installer Qualifications: Installer that employs skilled workers who install custom fabricated products similar to those required for this Project and whose products have a record of successful in-service performance.

### 1.6 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver cabinets until painting and similar operations that could damage woodwork have been completed in installation areas. If cabinets must be stored in other than installation areas, store only in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

# 1.7 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install cabinets until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature between 60 and 90 deg F (16 and 32 deg C) and relative humidity between 25 and 55 percent during the remainder of the construction period.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Field Measurements: Where cabinets are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
  - 1. Locate concealed framing, blocking, and reinforcements that support cabinets by field measurements before being enclosed, and indicate measurements on Shop Drawings.
- C. Established Dimensions: Where cabinets are indicated to fit to other construction, establish dimensions for areas where cabinets are to fit. Provide allowance for trimming at site, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

# 1.8 COORDINATION

A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to ensure that wood-veneer-faced architectural cabinets can be supported and installed as indicated.

# PART 2 - PRODUCTS

# 2.1 ARCHITECTURAL CABINET FABRICATORS

A. Source Limitations: Engage a qualified woodworking firm to assume undivided responsibility for production of architectural wood cabinets with sequence-matched wood veneers wood doors with face veneers that are sequence matched with woodwork and transparent-finished wood doors that are required to be of same species as woodwork.

# 2.2 ARCHITECTURAL WOOD AND PLASTIC-LAMINATE FACED CABINETS, GENERAL

- A. Quality Standard: Unless otherwise indicated, comply with the "Architectural Woodwork Standards" for grades of architectural wood and plastic laminate cabinets indicated for construction, finishes, installation, and other requirements.
  - 1. Provide woodwork, including installation, that complies with requirements of grades specified in accordance with AWI certification program. Note that certification by AWI is not required.
  - 2. The Contract Documents contain selections chosen from options in the quality standard and additional requirements beyond those of the quality standard. Comply with those selections and requirements in addition to the quality standard.

- 2.3 WOOD CABINETS FOR TRANSPARENT FINISH (Owner Furnished Owner Installed Lockers)
  - Grade: Premium. A.
  - B. Type of Construction: Frameless.
  - C. Cabinet and Door and Drawer Front Interface Style: Full overlay.
  - D. Reveal Dimension: 1/4 inch (7 mm).
  - E. Wood for Exposed Surfaces:
    - 1. Species: Select White Maple.
    - Cut: Plain sliced/plain sawn. 2.
    - Match between Veneer Leaves: Slip match. 3.
    - Grain Direction: Vertically for doors and fixed panels, horizontally for drawer fronts. 4.
    - Veneer Matching within Room: Provide cabinet veneers in each room or other space 5. from a single flitch with doors, drawer fronts, and other surfaces matched in a sequenced set with continuous match where veneers are interrupted perpendicular to the grain.
  - F. Semiexposed Surfaces: Provide surface materials indicated below:
    - Surfaces Other Than Drawer Bodies: Same species and cut indicated for exposed 1. surfaces.
      - Edges of Plastic Laminate Shelves: PVC or polyester edge banding.
    - 2. Drawer Subfronts, Backs, and Sides: Solid-hardwood lumber, same species indicated for exposed surfaces.
    - 3. Drawer Bottoms: Hardwood plywood.
  - Dust Panels: 1/4-inch (6.4-mm) plywood or tempered hardboard above compartments and G. drawers unless located directly under tops.
  - H. Drawer Construction: Fabricate with exposed fronts fastened to subfront with mounting screws from interior of body.
    - 1. Join subfronts, backs, and sides with glued rabbeted joints supplemented by mechanical fasteners.
- 2.4 PLASTIC-LAMINATE-FACED ARCHITECTURAL **CABINETS** (KITCHENETTE. LOUNGE AND RESTROOM CASEWORK)
  - A. Grade: Premium.
  - Type of Construction: Frameless. В.
  - C. Cabinet, Door, and Drawer Front Interface Style: Full overlay.
  - Reveal Dimension: 1/4 inch (7 mm). D.

Issue Date: 06/05/2014

e-Bid Set

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- E. High-Pressure Decorative Laminate: NEMA LD 3, grades as indicated or if not indicated, as required by woodwork quality standard.
  - 1. As scheduled, refer to the drawings.
- F. Laminate Cladding for Exposed Surfaces:
  - 1. Horizontal Surfaces: Grade HGS.
  - 2. Vertical Surfaces: Grade HGS.
  - 3. Edges: PVC edge banding, 0.12 inch (3 mm) thick, matching laminate in color, pattern, and finish.
  - 4. Pattern Direction: Vertically for doors and fixed panels, horizontally for drawer fronts.
- G. Materials for Semiexposed Surfaces:
  - 1. Surfaces Other Than Drawer Bodies: High-pressure decorative laminate, NEMA LD 3, Grade VGS.
    - a. Edges of Plastic-Laminate Shelves: PVC edge banding, 0.12 inch (3 mm) thick, matching laminate in color, pattern, and finish.
    - b. For semiexposed backs of panels with exposed plastic-laminate surfaces, provide surface of high-pressure decorative laminate, NEMA LD 3, Grade VGS.
  - 2. Drawer Sides and Backs: Solid-hardwood lumber.
  - 3. Drawer Bottoms: Hardwood plywood.
- H. Dust Panels: 1/4-inch (6.4-mm) plywood or tempered hardboard above compartments and drawers unless located directly under tops.
- I. Concealed Backs of Panels with Exposed Plastic-Laminate Surfaces: High-pressure decorative laminate, NEMA LD 3, Grade BKL.
- J. Drawer Construction: Fabricate with exposed fronts fastened to subfront with mounting screws from interior of body.
  - 1. Join subfronts, backs, and sides with glued rabbeted joints supplemented by mechanical fasteners.
- K. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed laminate surfaces complying with the following requirements:
  - 1. As noted in the finish schedule.

#### 2.5 WOOD MATERIALS

- A. Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of woodwork and quality grade specified unless otherwise indicated.
  - 1. Do not use plain-sawn softwood lumber with exposed, flat surfaces more than 3 inches (75 mm) wide.
  - 2. Wood Moisture Content: 8 to 13 percent.

Issue Date: 06/05/2014

B. Composite Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of woodwork and quality grade specified unless otherwise indicated.

Veneer-Faced Panel Products (Hardwood Plywood): HPVA HP-1, made with adhesive 1. containing no urea formaldehyde.

Architect's Project #: 12.130.09

#### 2.6 WOOD-PRESERVATIVE-TREATED MATERIALS

- Preservative Treatment by Pressure Process: AWPA U1; Use Category UC2 for interior A. construction not in contact with the ground, Use Category UC3b for exterior construction not in contact with the ground, and Use Category UC4a for items in contact with the ground.
  - 1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.
- B. Marine grade designation for plywood material for construction not in contact with the ground or in wet areas such as sinks and therapy tub.
- C. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or does not comply with requirements for untreated material.
- Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board D. of Review.
- E. Application: Treat items indicated on Drawings, and the following:
  - 1. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.
  - Wood, sleepers, blocking, furring, stripping, and similar concealed members in contact 2. with masonry or concrete.
  - Wood floor plates that are installed over concrete slabs-on-grade. 3.
  - 4. Marine Grade Plywood nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.

#### 2.7 CABINET HARDWARE AND ACCESSORIES

- General: Provide cabinet hardware and accessory materials associated with architectural A. cabinets except for items specified in Section 087111 "Door Hardware (Descriptive Specification)."
- B. Frameless Concealed Hinges (European Type): BHMA A156.9, B01602, 100 degrees of opening, self-closing.
- C. Pocket Door Hardware: Heavy duty pocket door slide system with adjustable hinges and guides.
- D. **Back-Mounted Pulls:** 
  - Aluminum pulls, #124.02.920 by Hafele

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 2. Stainless Steel Pulls:
  - a. 18" long pulls at base and wall cabinets, #117.05.650 by Hafele
  - b. 12" long pulls at lower locker cabinets, #117.05.640 by Hafele
  - c. 8" long pulls at upper locker cabinets #117.05.630 by Hafele
- E. Catches: Automatic latching catches
  - 1. Elbow catch on non-locking leaf at pair of cabinet doors.
  - 2. Spring release catch on non-locking leaves of upper cabinet. Automatically latch upon closing the doors.
- F. Adjustable Shelf Standards and Supports: BHMA A156.9, B04071; with shelf rests, B04081.
- G. Shelf Rests: BHMA A156.9, B04013; metal.
- H. Drawer Slides: BHMA A156.9.
  - 1. Grade 1 and Grade 2: Side mounted and extending under bottom edge of drawer; full-extension type, self-closing; zinc-plated steel with polymer rollers.
  - 2. Grade 1HD-100 and Grade 1HD-200: Side mounted; full-extension type, self-closing; zinc-plated-steel ball-bearing slides.
  - 3. For drawers not more than 3 inches (75 mm) high and not more than 24 inches (600 mm) wide, provide Grade 1.
  - 4. For drawers more than 3 inches (75 mm) high but not more than 6 inches (150 mm) high and not more than 24 inches (600 mm) wide, provide Grade 1HD-100.
  - 5. For drawers more than 6 inches (150 mm) high or more than 24 inches (600 mm) wide, provide Grade 1HD-200.
- I. Door Locks: For Lockers
  - 1. Men's and Women's Lockers: provide Digilock model # SS-DAK1-SPS-DEN-010114.
  - 2. For Visitor Lockers: provide individually keyed locks (University Standard keying with a master key) with Key Retaining Lock Function whereby the key can only be removed in the locked position.
    - a. Provide the University with 10 keys for each lock.
- J. Door and Drawer Locks for Training Room: BHMA A156.11, E07041.
  - 1. Provide locks, keyed alike for all upper cabinet doors and lower cabinet drawers only.
- K. Door and Drawer Silencers: BHMA A156.16, L03011.
  - 1. Slow Close function
- L. Accessory Items:
  - 1. Coat Hooks, Robe Hooks, and hanger rods: provide items as indicated in the drawings.
- M. Exposed Hardware Finishes: For exposed hardware, provide finish that complies with BHMA A156.18 for BHMA finish number indicated.
  - 1. Satin Stainless Steel: BHMA 630.
- N. For concealed hardware, provide manufacturer's standard finish that complies with product class requirements in BHMA A156.9.

# 2.8 MISCELLANEOUS MATERIALS

- A. Furring, Blocking, Shims, and Hanging Strips: Softwood or hardwood lumber, kiln dried to less than 15 percent moisture content.
  - 1. For concealed items of dimension lumber size, provide Construction or No. 2 grade lumber and the following species:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- a. Pressure treated
- b. Mixed southern pine; SPIB.
- 2. For blocking and nailers used for attachment of other construction, select and cut lumber to eliminate knots and other defects that will interfere with attachment of other work.
- 3. For plywood substrate, provide marine grade.
- B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide metal expansion sleeves or expansion bolts for post-installed anchors. Use nonferrousmetal or hot-dip galvanized anchors and inserts at inside face of exterior walls and at floors.
- C. Adhesives: Do not use adhesives that contain urea formaldehyde.

# 2.9 FABRICATION

- A. Fabricate woodwork to dimensions, profiles, and details indicated. Ease edges to radius indicated for the following:
  - 1. Corners of Cabinets: 1/16 inch (1.5 mm) unless otherwise indicated.
- B. Complete fabrication, including assembly, finishing, and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.
  - 1. Notify Architect seven days in advance of the dates and times woodwork fabrication will be complete.
  - 2. Trial fit assemblies at fabrication shop that cannot be shipped completely assembled. Install dowels, screws, bolted connectors, and other fastening devices that can be removed after trial fitting. Verify that various parts fit as intended and check measurements of assemblies against field measurements before disassembling for shipment.
- C. Shop-cut openings to maximum extent possible to receive hardware, appliances, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.
  - 1. Seal edges of openings in countertops with a coat of varnish.

# 2.10 SHOP FINISHING

A. General: Finish architectural wood cabinets at fabrication shop as specified in this Section. Defer only final touchup, cleaning, and polishing until after installation.

Re-Bid Set

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

B. General: All items are to be shop finished. Finish such items at fabrication shop as specified in this Section. Refer to Section 099300 "Staining and Transparent Finishing" for field finishing architectural woodwork not indicated to be shop finished.

# PART 3 - EXECUTION

#### 3.1 PREPARATION

- A. Before installation, condition cabinets to average prevailing humidity conditions in installation areas.
- B. Before installing cabinets, examine shop-fabricated work for completion and complete work as required, including removal of packing and backpriming.

# 3.2 INSTALLATION

- A. Furring, Blocking, Shims, and Hanging Strips: Install at locations indicted in the drawings to provide surface for attaching finish materials.
- B. Grade: Install cabinets to comply with same grade as item to be installed.
- C. Assemble cabinets and complete fabrication at Project site to the extent that it was not completed in the shop.
- D. Install cabinets level, plumb, true, and straight. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches (3 mm in 2400 mm).
- E. Scribe and cut cabinets to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.
- F. Anchor cabinets to anchors or blocking built in or directly attached to substrates. Secure with countersunk, concealed fasteners and blind nailing. Use fine finishing nails or finishing screws for exposed fastening, countersunk and filled flush with woodwork.
  - 1. For shop finished items use filler matching finish of items being installed.
- G. Cabinets: Install without distortion so doors and drawers fit openings properly and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.
  - 1. Install cabinets with no more than 1/8 inch in 96-inch (3 mm in 2400-mm) sag, bow, or other variation from a straight line.
  - 2. Maintain veneer sequence matching of cabinets with transparent finish.
  - 3. Fasten wall cabinets through back, near top and bottom, and at ends not more than 16 inches (400 mm) o.c. with No. 10 wafer-head screws sized for not less than 1-1/2-inch (38-mm) penetration into wood, blocking, or hanging strips.
- H. Touch up finishing work specified in this Section after installation of woodwork. Fill nail holes with matching filler where exposed.

Issue Date: 06/05/2014

1. Apply specified finish coats, including stains and paste fillers if any, to exposed surfaces where only sealer/prime coats are applied in shop.

Architect's Project #: 12.130.09

#### 3.3 COUNTERTOP INSTALLATION

- Refer to section 123661 "Simulated Stone Countertops" for countertops installation. A.
  - Grade: Install countertops to comply with same grade as item to be installed.

#### 3.4 ADJUSTING AND CLEANING

- Repair damaged and defective cabinets, where possible, to eliminate functional and visual A. defects; where not possible to repair, replace woodwork. Adjust joinery for uniform appearance.
- B. Clean, lubricate, and adjust hardware.
- C. Clean cabinets on exposed and semiexposed surfaces. Touch up shop-applied finishes to restore damaged or soiled areas.

END OF SECTION 064113

# SECTION 071113 - BITUMINOUS DAMPPROOFING

# PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Cold-applied, emulsified-asphalt dampproofing.
- B. Related Requirements:
  - 1. Section 042000 "Unit Masonry".

# 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product, including data substantiating that materials comply with requirements for project specific application.
  - 1. Include recommended method of application, recommended primer, number of coats, coverage thickness, and recommended protection course.
  - 2. Include recommendations for product setting temperature, curing time and protection and coverage recommendations.
- B. Material Certificates: For each product, signed by manufacturer.

# 1.4 FIELD CONDITIONS

- A. Weather Limitations: Proceed with application only when existing and forecasted weather conditions permit dampproofing to be performed according to manufacturers' written instructions.
- B. Ventilation: Provide adequate ventilation during application of dampproofing in enclosed spaces. Maintain ventilation until dampproofing has cured.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# PART 2 - PRODUCTS

### 2.1 MATERIALS, GENERAL

A. Source Limitations: Obtain primary dampproofing materials and primers from single source from single manufacturer. Provideauxiliary materials recommended in writing by manufacturer of primary materials.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# 2.2 COLD-APPLIED, EMULSIFIED-ASPHALT DAMPPROOFING

- A. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by one of the following:
  - 1. BASF Construction Chemicals Building Systems,
  - 2. Euclid Chemical Company (The); an RPM company.
  - 3. <u>Karnak Corporation</u>.
  - 4. Koppers Inc.
  - 5. W.R. Meadows, Inc.
- B. Fibered Brush and Spray Coats: ASTM D 1227, Type II, Class 1.
- C. VOC Content: 30 g/L or less.
- D. Low-Emitting Materials: Dampproofing shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

### 2.3 AUXILIARY MATERIALS

- A. General: Furnish auxiliary materials recommended in writing by dampproofing manufacturer for intended use and compatible with bituminous dampproofing.
- B. Emulsified-Asphalt Primer: ASTM D 1227, Type III, Class 1, except diluted with water as recommended in writing by manufacturer.
- C. Asphalt-Coated Glass Fabric: ASTM D 1668, Type I.
- D. Patching Compound: Manufacturer's fibered mastic of type recommended in writing by dampproofing manufacturer.

Issue Date: 06/05/2014

#### **PART 3 - EXECUTION**

#### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions with Applicator present, for compliance with requirements for surface smoothness, surface moisture, and other conditions affecting performance of bituminous dampproofing work.
  - 1. Test for surface moisture according to ASTM D 4263.
- B. Proceed with application only after substrate construction and penetrating work have been completed and unsatisfactory conditions have been corrected.

#### 3.2 PREPARATION

- A. Mask or otherwise protect adjoining exposed surfaces from being stained, spotted, or coated with dampproofing. Prevent dampproofing materials from entering and clogging weep holes and drains.
- B. Clean substrates of projections and substances detrimental to the dampproofing work; fill voids, seal joints, and remove bond breakers if any, as recommended in writing by prime material manufacturer.
- C. Apply patching compound to patch and fill tie holes, honeycombs, reveals, and other imperfections; cover with asphalt-coated glass fabric.

#### 3.3 APPLICATION, GENERAL

- A. Comply with manufacturer's written instructions for dampproofing application, cure time between coats, and drying time before backfilling unless more stringent requirements are indicated.
  - 1. Apply dampproofing to provide continuous plane of protection.
  - 2. Apply additional coats if recommended in writing by manufacturer or to achieve a smooth surface and uninterrupted coverage.
  - 3. Allow each coat of dampproofing to cure for time duration recommended by the manufacturer prior to installing additional coats.
  - 4. Allow each coat of dampproofing to cure for time duration recommended by the manufacturer prior backfill.
- B. Where dampproofing footings and foundation walls, apply from finished-grade line to top of footing; extend over top of footing and down a minimum of 6 inches (150 mm) over outside face of footing.
  - 1. Extend dampproofing 12 inches (300 mm) onto intersecting walls and footings, but do not extend onto surfaces exposed to view when Project is completed.

e Tennis Complex Addition

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 2. Install flashings and corner protection stripping at internal and external corners, changes in plane, construction joints, cracks, and where shown as "reinforced," by embedding an 8-inch- (200-mm-) wide strip of asphalt-coated glass fabric in a heavy coat of dampproofing. Dampproofing coat for embedding fabric is in addition to other coats required.
- C. Where dampproofing exterior face of inner wythe of exterior masonry cavity walls, lap dampproofing at least 1/4 inch (6 mm) onto flashing, masonry reinforcement, veneer ties, and other items that penetrate inner wythe.
  - 1. Extend dampproofing over outer face of structural members and concrete slabs that interrupt inner wythe.
  - 2. Lap dampproofing at least 1/4 inch (6 mm) onto shelf angles supporting veneer.

### 3.4 COLD-APPLIED, EMULSIFIED-ASPHALT DAMPPROOFING

- A. Unparged Masonry Foundation Walls: Apply primer and two brush or spray coats at not less than 1.5 gal./100 sq. ft. (0.6 L/sq. m) for first coat and 1 gal./100 sq. ft. (0.4 L/sq. m) for second coat or primer and one fibered brush or spray coat at not less than 3 gal./100 sq. ft. (1.2 L/sq. m).
- B. Exterior Face of Inner Wythe of Cavity Walls: Apply primer and one brush or spray coat at not less than 1 gal./100 sq. ft. (0.4 L/sq. m).

#### 3.5 CLEANING

A. Clean spillage and soiling from adjacent construction using cleaning agents and procedures recommended in writing by manufacturer of affected construction.

END OF SECTION 071113

Issue Date: 06/05/2014

# SECTION 072100 - THERMAL INSULATION

# PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

#### A. Section Includes:

- 1. Foam-plastic board insulation.
- 2. Spray polyurethane foam insulation.

#### B. Related Sections:

- 1. Section 042000 "Unit Masonry" for insulation installed in cavity walls and masonry cells.
- 2. Section 075323 "Ethylene-Propylene-Diene-Monomer (EPDM) Roofing".

# 1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for each product.
- B. Research/Evaluation Reports: For foam-plastic insulation, from ICC-ES.

# 1.5 QUALITY ASSURANCE

A. Surface-Burning Characteristics: As determined by testing identical products according to ASTM E 84 by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

# 1.6 DELIVERY, STORAGE, AND HANDLING

A. Protect insulation materials from physical damage and from deterioration due to moisture, soiling, and other sources. Store inside and in a dry location. Comply with manufacturer's written instructions for handling, storing, and protecting during installation.

Issue Date: 06/05/2014

- B. Protect foam-plastic board insulation as follows:
  - 1. Do not expose to sunlight except to necessary extent for period of installation and concealment.
  - 2. Protect against ignition at all times. Do not deliver foam-plastic board materials to Project site before installation time.
  - 3. Quickly complete installation and concealment of foam-plastic board insulation in each area of construction.

#### PART 2 - PRODUCTS

# 2.1 FOAM-PLASTIC BOARD INSULATION

- A. Extruded-Polystyrene Board Insulation: ASTM C 578, of type and minimum compressive strength indicated below, with maximum flame-spread and smoke-developed indexes of 25 and 450, respectively, per ASTM E 84.
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide Dow Chemical Company "Cavitymate Ultra" or compatible products by one of the following:
    - a. DiversiFoam Products.
    - b. Owens Corning.
    - c. <u>Pactiv Corporation</u>.
  - 2. Type IV, 25 psi (173 kPa).
  - 3. Fire Propagation Characteristics: Passes NFPA 285 testing as part of an approved assembly.
- B. Adhesive for Bonding Insulation: Product with demonstrated capability to bond insulation securely to substrates without damaging insulation and substrates.

# 2.2 SPRAY POLYURETHANE FOAM INSULATION

- A. Closed-Cell Polyurethane Foam Insulation: ASTM C 1029, Type II, with maximum flame-spread and smoke-developed indexes of 25 and 450, respectively, per ASTM E 84.
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide Dow Chemical Company, Styrofoam CM2045 or compatible products by one of the following:
    - a. Gaco Western LLC, 183M.
    - b. Icynene Inc, ProSeal MD-C-200 V3.
    - c. NCFI Polyurethanes; a division of Barnhardt Manufacturing Company.
  - 2. Minimum density of 2.0 lb/cu. ft. (24 kg/cu. m), thermal resistivity of 6.2 deg F x h x sq. ft./Btu x in. at 75 deg F (43 K x m/W at 24 deg C).
    - a. R-Value: Provide continuous roof insulation equal to R-19 minimum.
  - 3. Fire Propagation Characteristics: Class 1 / Class A material

# 2.3 TERMAL BARRIER FOR SPRAY POLYURETHANE FOAM INSULATION

- A. Spray Applied Thermal Barrier: fluid applied, water based Fire Retardant Paint as an alternative barrier system tested to the criteria of NFPA 286, UL-1715 for a duration of 15 minutes.
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide International Fireproof Technology In., DC315 or compatible products submitted for preapproval along with the associated evaluation sheet.
  - 2. Spreading Rate: For 15 minute Thermal Barrier
    - a. (88.88 sq. ft./gal @ 18 mil wet and 12 mils Dry) coverage rate of 1.136 gallons (4.3 L) per 100 square feet (9.3 m<sup>2</sup>)

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 2.4 INSULATION FASTENERS

- A. Anchor Adhesive: Product with demonstrated capability to bond insulation anchors securely to substrates indicated without damaging insulation, fasteners, and substrates.
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. AGM Industries, Inc.
    - b. Gemco.

### PART 3 - EXECUTION

### 3.1 PREPARATION

A. Clean substrates of substances that are harmful to insulation or that interfere with insulation attachment.

### 3.2 INSTALLATION, GENERAL

- A. Comply with insulation manufacturer's written instructions applicable to products and applications indicated.
- B. Install insulation that is undamaged, dry, and unsoiled and that has not been left exposed to ice, rain, or snow at any time.
- C. Extend insulation to envelop entire area to be insulated. Cut and fit tightly around obstructions and fill voids with insulation. Remove projections that interfere with placement.

Re-Bid Set

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

D. Provide sizes to fit applications indicated and selected from manufacturer's standard thicknesses, widths, and lengths. Apply single layer of insulation units to produce thickness indicated unless multiple layers are otherwise shown or required to make up total thickness.

### 3.3 INSTALLATION OF CAVITY-WALL INSULATION

- A. Foam-Plastic Board Insulation: Install pads of adhesive spaced approximately 24 inches (610 mm) o.c. both ways on inside face, and as recommended by manufacturer. Fit courses of insulation between wall ties and other obstructions, with edges butted tightly in both directions. Press units firmly against inside substrates.
  - 1. Supplement adhesive attachment of insulation by securing boards with two-piece wall ties designed for this purpose and specified in Section 042000 "Unit Masonry."

### 3.4 INSTALLATION OF INSULATION FOR ROOF FRAMED CONSTRUCTION

- A. Spray-Applied Insulation: Apply spray-applied insulation according to manufacturer's written instructions. Do not apply insulation until installation of pipes, ducts, conduits, wiring, and electrical outlets in walls is completed and windows, electrical boxes, and other items not indicated to receive insulation are masked.
  - 1. After insulation is applied and properly cured, apply fluid applied, water based Fire Retardant Paint to achieve 15 minute Thermal Barrier.
- B. Miscellaneous Voids: Install insulation in miscellaneous voids and cavity spaces where required to prevent gaps in insulation using the following materials:
  - 1. Spray Polyurethane Insulation: Apply according to manufacturer's written instructions.

# 3.5 PROTECTION

A. Protect installed insulation from damage due to harmful weather exposures, physical abuse, and other causes. Provide temporary coverings or enclosures where insulation is subject to abuse and cannot be concealed and protected by permanent construction immediately after installation.

END OF SECTION 072100

# SECTION 072413 - POLYMER-BASED EXTERIOR FINISH SYSTEM (EIFS and DEFS)

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

### A. Section Includes:

- 1. EIFS-clad barrier-wall assemblies that are field applied over substrate.
- 2. DEFS-clad barrier-ceiling assemblies that are applied over Glass-Mat Gypsum sheathing substrate.

### B. Related Sections:

- 1. Division 06 Section "Sheathing" for Glass-Mat Gypsum sheathing.
- 2. Division 07 Section "Joint Sealants" for sealing joints with elastomeric joint sealants.
- C. Products furnished, but not installed, under this Section include connections and other attachment devices including framing systems.

### 1.3 DEFINITIONS

- A. Definitions in ASTM E 2110 apply to Work of this Section.
- B. EIFS: Exterior Insulation and Finish System(s).
- C. DEFS: Direct (applied) Exterior Finish System
- D. IBC: International Building Code.
- E. Polymer-Based Exterior Insulation and Finish System: Class PB EIFS, as defined in ASTM E 2568.

### 1.4 SYSTEM DESCRIPTION

A. Exterior Insulation and Finish System (EIFS): Exterior assemblies composed of an inner layer of board insulation and an outer layer composed of a glass-fiber0mesh-reinforced base coat applied directly to board insulation and a textured protective finish coat. These assemblies are applied to supporting substrates of construction indicated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

e-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

B. Direct Applied Exterior Finish System (DEFS): A non-load-bearing, exterior cladding system that consists of a exterior sheathing substrate; an integrally reinforced base coat; and a textured protective finish coat.

### 1.5 ACTION SUBMITTALS

- A. Product Data: For each EIFS and DEFS component, trim, and accessory.
- B. Shop Drawings: For EIFS and DEFS systems.
  - 1. Include plans, elevations, sections, details of components, details of penetrations and terminations, flashing details, joint locations and configurations, lifting points, fastening and anchorage details including mechanical fasteners, and connections and attachments to other work.
- C. Samples: For each exposed product and for each color and texture specified, 8 inches (200 mm) square in size.
- D. Samples for Initial Selection: For each type of finish-coat color and texture indicated.
  - 1. Include similar Samples of exposed accessories involving color selection.

### 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer AND fabricator/erector.
- B. Manufacturer Certificates: Signed by EIFS/DEFS manufacturer certifying the following:
  - 1. EIFS substrate is acceptable to EIFS manufacturer.
  - 2. DEFS substrate is acceptable to DEFS manufacturer.
  - 3. Accessory products installed with EIFS/DEFS, including joint sealants, flashing, water-resistant barriers, trim, whether or not furnished by EIFS/DEFS manufacturer and whether or not specified in this Section, are acceptable to EIFS/DEFS manufacturer.
- C. Product Test Reports: For each EIFS/DEFS assembly and component, for tests performed by a qualified testing agency.
- D. Field quality-control reports and special inspection reports.
- E. Evaluation Reports: For EIFS, including insulation fasteners, flexible membrane flashing, from ICC-ES.
- F. Sample Warranty: For manufacturer's special warranty.

### 1.7 CLOSEOUT SUBMITTALS

A. Maintenance Data: For EIFS/DEFS to include in maintenance manuals.

# 1.8 QUALITY ASSURANCE

A. Installer Qualifications: An installer certified in writing by EIFS/DEFS manufacturer as qualified to install manufacturer's system using trained workers.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. Fabricator/Erector Qualifications: Certified in writing by EIFS/DEFS manufacturer as qualified to fabricate and erect manufacturer's prefabricated panel system using skilled and trained workers.

### 1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials in original, unopened packages with manufacturers' labels intact and clearly identifying products.
- B. Store materials inside and under cover; keep them dry and protected from weather, direct sunlight, surface contamination, aging, corrosion, damaging temperatures, construction traffic, and other causes.
  - 1. Stack insulation board flat and off the ground.
  - 2. Protect plastic insulation against ignition at all times. Do not deliver plastic insulating materials to Project site before installation time.
  - 3. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

### 1.10 FIELD CONDITIONS

A. Weather Limitations: Maintain ambient temperatures above 40 deg F (4.4 deg C) for a minimum of 24 hours before, during, and after adhesives or coatings are applied. Do not apply EIFS adhesives or coatings during rainfall. Proceed with installation only when existing and forecasted weather conditions and ambient outdoor air, humidity, and substrate temperatures permit EIFS to be applied, dried, and cured according to manufacturers' written instructions and warranty requirements.

### 1.11 WARRANTY

- A. Manufacturer's Special Warranty: Manufacturer agrees to repair or replace EIFS/DEFS that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Bond integrity and weathertightness.
    - b. Deterioration of EIFS/DEFS finishes and other EIFS/DEFS materials beyond normal weathering.
  - 2. Warranty coverage includes the following EIFS/DEFS components:
    - a. Material, Labor, and Performance.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- b. Warrant the Entire System including the following:
  - 1) EIFS/DEFS finish, including base and finish coats and reinforcing mesh.
  - 2) Backing:
    - a) Insulation installed as part of EIFS/DEFS.
    - b) Insulation adhesive.
    - c) Backing, Glass-Mat Gypsum sheathing.
  - 3) EIFS/DEFS accessories, including trim components and flashing.
- c. Warrant the Entire System from system failure includes:
  - 1) Excess water, moisture, or vapor penetration that reached the base coat, insulation, sheathing, or interior structure.
  - 2) Cracking, crazing, chipping, splitting, delaminating, alligatoring, bubbling, or blistering of the finish coat.
  - 3) Fading or discoloration of the finish coat.
  - 4) Separation from the support or at termination points.
- 3. Warranty Period: Ten years from date of Substantial Completion.

### PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by one of the following:
  - 1. BASF Wall Systems.
  - 2. Dryvit Systems, Inc.
  - 3. Finestone.
  - 4. Sto Corp.
- B. Source Limitations: Obtain EIFS/DEFS from single source from single EIFS/DEFS manufacturer and from sources approved by EIFS/DEFS manufacturer as tested and compatible with EIFS/DEFS components.

### 2.2 PERFORMANCE REQUIREMENTS

- A. EIFS Performance: Comply with ASTM E 2568 and ICC-ES AC219 and with the following:
  - 1. Weathertightness: Resistant to water penetration from exterior.
  - 2. Structural Performance: EIFS assembly and components shall comply with ICC-ES AC219 when tested according to ASTM E 2568.
    - a. Wind Loads: Uniform pressure as indicated on Drawings.
  - 3. Bond Integrity: Free from bond failure within EIFS components or between EIFS and substrates, resulting from exposure to fire, wind loads, weather, or other in-service conditions.

4. Mildew Resistance of Finish Coat: Sample applied to 2-by-2-inch (50.8-by-50.8-mm) clean glass substrate; cured for 28 days and shows no growth when tested according to ASTM D 3273 and evaluated according to ASTM D 3274.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. DEFS Performance: Comply with the following:
  - 1. Bond Integrity: Free from bond failure within DEFS components or between system and supporting construction assemblies, resulting from exposure to fire, wind loads, weather, or other in-service conditions.
  - 2. Weathertightness: Resistant to water penetration from exterior into DEFS and assemblies behind it or through them into interior of building that results in deterioration of DEFS and assemblies behind it, including substrates, supporting wall construction, and interior finish.

### 2.3 EIFS/DEFS MATERIALS

- A. Primer/Sealer: EIFS/DEFS manufacturer's standard substrate conditioner designed to protect substrates from moisture penetration and to improve the bond between substrate and insulation adhesive.
- B. Flexible-Membrane Flashing: Cold-applied, self-adhering, self-healing, rubberized-asphalt and polyethylene-film composite sheet or tape and primer; EIFS/DEFS manufacturer's standard or product recommended in writing by EIFS/DEFS manufacturer.
- C. Insulation Adhesive: (EIFS only) manufacturer's standard formulation designed for indicated use; compatible with substrate; complying with one of the following:
  - 1. Factory-blended dry formulation of portland cement, dry polymer admixture, and fillers specified for base coat.
- D. Molded, (Expanded) Rigid Cellular Polystyrene Board Insulation (EPS) (EIFS ONLY): Comply with ASTM C 578, Type I; and with EIFS manufacturer's requirements for most stringent requirements for material performance and qualities of insulation, including dimensions and permissible variations, and the following:
  - 1. Aging: Before cutting and shipping, age insulation in block form by air drying for not less than six weeks.
  - 2. Flame-Spread and Smoke-Developed Indexes: 25 and 450 or less, respectively, according to ASTM E 84.
  - 3. Dimensions: Provide insulation boards of not more than 24 by 48 inches (610 by 1219 mm) thick or in other thickness indicated, but not more than 4 inches (102 mm) thick or less than the thickness allowed by ASTM C 1397.
  - 4. Foam Build-Outs: Provide with profiles, reveals and dimensions indicated on Drawings.
    - a. Manufacturer to verify compatibility of EPS insulation board with continuous insulation specified in Section 072100, Thermal Insulation.
- E. Reinforcing Mesh: Balanced, alkali-resistant, open-weave, glass-fiber mesh treated for compatibility with other EIFS/DEFS materials, made from continuous multiend strands with retained mesh tensile strength of not less than 120 lbf/in. (21 dN/cm) according to ASTM E 2098 and the following:

1. Reinforcing Mesh for EIFS/DEFS, General: Not less than weight required to meet impact-performance level specified in "Performance Requirements" Article.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Strip Reinforcing Mesh: Not less than 3.75 oz./sq. yd. (127 g/sq. m).
- 3. Detail Reinforcing Mesh: Not less than 4.0 oz./sq. yd. (136 g/sq. m).
- 4. Corner Reinforcing Mesh: Not less than 7.2 oz./sq. yd. (244 g/sq. m).
- F. Base-Coat Materials: EIFS/DEFS manufacturer's standard mixture complying with the following:
  - 1. Factory-blended dry formulation of portland cement, dry polymer admixture, and inert fillers to which only water is added at Project site.
- G. Waterproof Adhesive/Base-Coat Materials: EIFS/DEFS manufacturer's standard waterproof formulation and complying with the following:
  - 1. Job-combined formulation of manufacturer's standard polymer-emulsion adhesive and manufacturer's standard dry mix containing portland cement.
- H. Mechanical Fasteners: (EIFS Only) provide manufacturer's standard corrosion-resistant fasteners consisting of thermal cap, standard washer and shaft attachments, and fastener indicated below; designed to resist Project's design loads; capable of pulling fastener head below surface of insulation board; and complying with the following:
  - 1. For attachment to steel studs from 0.033 to 0.112 inch (0.84 to 2.84 mm) in thickness, provide steel drill screws complying with ASTM C 954.
  - 2. For attachment to light-gage steel framing members not less than 0.0179 inch (0.45 mm) in thickness, provide steel drill screws complying with ASTM C 1002.
  - 3. For attachment to masonry and concrete substrates, provide sheathing dowel in form of a plastic wing-tipped fastener with thermal cap, sized to fit insulation thickness indicated and to penetrate substrate to depth required to secure anchorage.
- I. Primer: EIFS/DEFS manufacturer's standard factory-mixed, elastomeric-polymer primer for preparing base-coat surface for application of finish coat.
- J. Finish-Coat Materials: EIFS manufacturer's standard acrylic-based coating complying with the following:
  - 1. Factory-mixed formulation of polymer-emulsion binder, colorfast mineral pigments, sound stone particles, and fillers.
  - 2. Colors: As selected by Architect from manufacturer's full range, including Designer Color Collections.
  - 3. Textures: Matching the manufacturer's Fine (1.0) texture.
- K. Water: Potable.
- L. Trim Accessories: Type as designated or required to suit conditions indicated and to comply with EIFS/DEFS manufacturer's written instructions; manufactured from UV-stabilized PVC; and complying with ASTM D 1784 and ASTM C 1063.

Re-Bid Set Issue Date: 06/05/2014

1. Casing Bead: Prefabricated, one-piece type for attachment behind insulation, of depth required to suit thickness of coating and insulation, with face leg perforated for bonding to coating and back leg.

Architect's Project #: 12.130.09

- 2. Drip Screed/Track: Prefabricated, one-piece type for attachment behind insulation with face leg extended to form a drip, of depth required to suit thickness of coating and insulation, with face leg perforated for bonding to coating and back leg.
- 3. Expansion Joint: Prefabricated, one-piece V profile; designed to relieve stress of movement.
- 4. Sill Flashing: Prefabricated type for both flashing and sloping sill over framing beneath windows; with end and back dams; designed to direct water to exterior.

### 2.4 ELASTOMERIC SEALANTS

- A. Elastomeric Sealant Products: Provide DEFS manufacturer's listed and recommended chemically curing, elastomeric sealant that is compatible with joint fillers, joint substrates, and other related materials, and complies with requirements for products and testing indicated in ASTM C 1481 and with requirements in Division 07 Section "Joint Sealants" for products corresponding to description indicated below:
  - 1. Single-component, nonsag, neutral-curing silicone sealant.
- B. Sealant Color: As selected by Architect from manufacturer's full range.

### 2.5 MIXING

A. Comply with EIFS/DEFS manufacturer's requirements for combining and mixing materials. Do not introduce admixtures, water, or other materials except as recommended by EIFS/DEFS manufacturer. Mix materials in clean containers. Use materials within time period specified by EIFS/DEFS manufacturer or discard.

### PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roof edges, wall framing, flashings, openings, substrates, and junctures at other construction for suitable conditions where EIFS/DEFS will be installed.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.
  - 1. Begin coating application only after surfaces are dry.
  - 2. Application of coating indicates acceptance of surfaces and conditions.

### 3.2 PREPARATION

A. Protect contiguous work from moisture deterioration and soiling caused by application of EIFS/DEFS. Provide temporary covering and other protection needed to prevent spattering of exterior finish coats on other work.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Protect EIFS/DEFS, substrates, and wall construction behind them from inclement weather during installation. Prevent penetration of moisture behind EIFS/DEFS and deterioration of substrates.
- C. Prepare and clean substrates to comply with EIFS/DEFS manufacturer's written instructions to obtain optimum bond between substrate and adhesive for insulation.

# 3.3 EIFS/DEFS INSTALLATION, GENERAL

A. Comply with ASTM C 1397, ASTM E 2511, and EIFS/DEFS manufacturer's written instructions for installation of EIFS as applicable to each type of substrate.

### 3.4 SUBSTRATE PROTECTION APPLICATION

- A. Primer/Sealer: Apply over gypsum sheathing substrates and where required by EIFS/DEFS manufacturer for improving adhesion of insulation to substrate.
- B. Flexible-Membrane Flashing: Apply and lap to shed water; seal at openings, penetrations, terminations, and where required by EIFS/DEFS manufacturer. Prime substrates if required and install flashing to comply with EIFS/DEFS manufacturer's written instructions and details.

### 3.5 TRIM INSTALLATION

- A. Trim: Apply trim accessories at perimeter of EIFS/DEFS, at expansion joints, at sills, and elsewhere as indicated. Coordinate with installation of insulation.
  - 1. Drip Screed/Track: Use at bottom edges of EIFS/DEFS unless otherwise indicated.
  - 2. Sill Flashing: Use at base of EIFS/DEFS unless otherwise indicated.
  - 3. Expansion Joint: Use where indicated on Drawings.
  - 4. Casing Bead: Use at other locations.
  - 5. Soffit Vents: Use where indicated on Drawings.

# 3.6 INSULATION INSTALLATION (EIFS Only)

- A. Board Insulation: Adhesively and mechanically attach insulation to substrate in compliance with ASTM C 1397 and the following:
  - 1. Concrete or Masonry: Apply adhesive by ribbon-and-dab method.
  - 2. Press and slide insulation into place. Apply pressure over the entire surface of insulation to accomplish uniform contact, high initial grab, and overall level surface.

3. Allow adhered insulation to remain undisturbed for not less than 24 hours, before installing mechanical fasteners, beginning rasping and sanding insulation or before

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

applying base coat and reinforcing mesh.

4. Mechanically attach insulation to substrate. Install top surface of fastener heads flush with plane of insulation. Install fasteners into or through substrates with the following minimum penetration:

- a. Steel Framing: 5/16 inch (8 mm).
- b. Concrete and Masonry: 1 inch (25 mm).
- 5. Apply insulation over dry substrates in courses with long edges of boards oriented horizontally.
- 6. Begin first course of insulation from screed/track and work upward. Work from perimeter casing beads toward interior of panels if possible.
- 7. Stagger vertical joints of insulation boards in successive courses to produce running bond pattern. Locate joints so no piece of insulation is less than 12 inches (300 mm) wide or 6 inches (150 mm) high. Offset joints not less than 6 inches (150 mm) from corners of window and door openings and not less than 4 inches (100 mm) from aesthetic reveals.
  - a. Adhesive Attachment: Offset joints of insulation not less than 6 inches (150 mm) from horizontal and 4 inches (100 mm) from vertical joints in sheathing.
  - b. Mechanical Attachment: Offset joints of insulation from horizontal joints in sheathing.
- 8. Interlock ends at internal and external corners.
- 9. Abut insulation tightly at joints within and between each course to produce flush, continuously even surfaces without gaps or raised edges between boards. If gaps greater than 1/16 inch (1.6 mm) occur, fill with insulation cut to fit gaps exactly; insert insulation without using adhesive or other material.
- 10. Cut insulation to fit openings, corners, and projections precisely and to produce edges and shapes complying with details indicated.
- 11. Rasp or sand flush entire surface of insulation to remove irregularities projecting more than 1/16 inch (1.6 mm) from surface of insulation and to remove yellowed areas due to sun exposure; do not create depressions deeper than 1/16 inch (1.6 mm). Prevent airborne dispersal and immediately collect insulation raspings or sandings.
- 12. Interrupt insulation for expansion joints where indicated.
- 13. Form joints for sealant application with back-to-back casing beads for joints within EIFS and with perimeter casing beads at dissimilar adjoining surfaces. Make gaps between casing beads and between perimeter casing beads and adjoining surfaces of width indicated
- 14. Fully wrap board edges with strip reinforcing mesh.
- 15. Treat exposed edges of insulation as follows:
  - a. Except for edges forming substrates of sealant joints, encapsulate with base coat, reinforcing mesh, and finish coat.
  - b. Encapsulate edges forming substrates of sealant joints within EIFS or between EIFS and other work with base coat and reinforcing mesh.
  - c. At edges trimmed by accessories, extend base coat, reinforcing mesh, and finish coat over face leg of accessories.

16. Coordinate installation of flashing and insulation to produce wall assembly that does not allow water to penetrate behind flashing and EIFS lamina.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Expansion Joints: Install at locations indicated, where required by EIFS manufacturer, and as follows:
  - 1. At expansion joints in substrates behind EIFS.
  - 2. Where EIFS adjoin dissimilar substrates, materials, and construction, including other EIFS
  - 3. At floor lines in multilevel wood-framed construction.
  - 4. Where wall height or building shape changes.
  - 5. Where EIFS manufacturer requires joints in long continuous elevations.

### 3.7 BASE-COAT INSTALLATION

- A. Base Coat: Apply to exposed surfaces of insulation (EIFS Only) or Sheathing (DEFS) in minimum thickness recommended in writing by EIFS/DEFS manufacturer, but not less than 1/16-inch (1.6-mm) dry-coat thickness.
- B. Reinforcing Mesh: Embed reinforcing mesh in wet base coat to produce wrinkle-free installation with mesh continuous at corners, overlapped not less than 2-1/2 inches (64 mm) or otherwise treated at joints to comply with ASTM C 1397 and EIFS/DEFS manufacturer's written instructions. Do not lap reinforcing mesh within 8 inches (200 mm) of corners. Completely embed mesh, applying additional base-coat material if necessary, so reinforcing-mesh color and pattern are invisible.
- C. Additional Reinforcing Mesh: Apply strip reinforcing mesh around openings, extending 4 inches (100 mm) beyond perimeter. Apply additional 9-by-12-inch (230-by-300-mm) strip reinforcing mesh diagonally at corners of openings (re-entrant corners). Apply 8-inch- (200-mm-) wide, strip reinforcing mesh at both inside and outside corners unless base layer of mesh is lapped not less than 4 inches (100 mm) on each side of corners.
  - 1. At aesthetic reveals and trim accessories, apply strip reinforcing mesh not less than 8 inches (200 mm) wide.
  - 2. Embed strip reinforcing mesh in base coat before applying first layer of reinforcing mesh.
- D. Double Base-Coat Application: Where indicated, apply second base coat in same manner and thickness as first application, except without reinforcing mesh. Do not apply until first base coat has cured.

### 3.8 FINISH-COAT INSTALLATION

- A. Primer: Apply over dry base coat according to EIFS/DEFS manufacturer's written instructions.
- B. Finish Coat: Apply over dry primed base coat, maintaining a wet edge at all times for uniform appearance, in thickness required by EIFS/DEFS manufacturer to produce a uniform finish of color and texture matching approved sample and free of cold joints, shadow lines, and texture variations.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

C. Sealer Coat: Apply over dry finish coat, in number of coats and thickness required by EIFS/DEFS manufacturer.

# 3.9 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. EIFS Tests and Inspections: According to ASTM E 2568.
- C. EIFS will be considered defective if it does not pass tests and inspections.
- D. Prepare test and inspection reports.

### 3.10 CLEANING AND PROTECTION

A. Remove temporary covering and protection of other work. Promptly remove coating materials from window and door frames and other surfaces outside areas indicated to receive EIFS coatings.

END OF SECTION 072413

# SECTION 07 26 00 – UNDER SLAB VAPOR RETARDER

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Products furnished under this section, and installed in coordination with related sections include the following:
  - 1. Vapor Retarder, seam tape, vapor proofing mastic, pipe boots, detail strip for installation under concrete slabs.

### B. Related Sections:

1. Division 03 Section "Cast-In-Place Concrete" for concrete floor slabs.

### 1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Material Certificates: For each product, signed by manufacturers.
- C. Samples for verification: (2) 6" x 6" samples of plastic vapor retarder, seamed together along one side using manufacturer's seam tape, to form a single 6" x 12" sample.

### 1.4 QUALITY ASSURANCE

A. Source Limitations: Obtain primary materials and accessories through one source from a single manufacturer.

### 1.5 PROJECT CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit vapor retarder to be installed according to manufacturers' written instructions.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### PART 2 - PRODUCTS

### 2.1 PLASTIC VAPOR RETARDER

- A. Basis-of-Design Product: Subject to compliance with requirements, furnish and install products by Stego Industries LLC, or comparable products meeting performance requirements and properties by other manufacturers.
- B. Vapor retarder membrane that meets or exceeds the following properties:
  - 1. Permeance rating: ASTM E 96 or ASTM F 1249, meets permeance requirements for both new material, and after ASTM E-1745 mandatory conditioning tests (ASTM E 154; Sections 8, 11, 12, 13):
    - a. New material: Less than 0.01 perms (gr/ft²/hr/in-Hg).
    - b. After conditioning: Less than 0.01 perms (gr/ft²/hr/in-Hg).
  - 2. Water Vapor Retarder: ASTM E 1745, Class A
  - 3. Minimum thickness: 15 mils, ACI 302.1R-06.
  - 4. Manufactured from prime virgin resins.
  - 5. Woven materials are not acceptable.

### 2.2 MISCELLANEOUS MATERIALS

- A. Seam Tape: ASTM E 96, Water Vapor Transmission Rate 0.3 perms or lower.
- B. Vapor Proofing mastic: ASTM E 96, Water Vapor Transmission Rate 0.3 perms or lower.
- C. Pipe boots: Construct pipe boots from vapor retarder material, pressure sensitive tape and/or mastic per manufacturer's instructions.

### PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine slab base course, with Installer present, for compliance with requirements for surface stability and other conditions affecting performance of work.
  - 1. Proceed with vapor retarder installation only after base course construction and penetrating work have been completed and unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION, GENERAL

A. Coordinate installation of the under slab vapor retarder in conjunction with the drawings and with the work specified in Division 3, Section 03 30 00 "Cast-In-Place Concrete".

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- B. Comply with manufacturer's written recommendations and ASTM E 1643-98 (2005), unless more stringent requirements are indicated or required by Project conditions to ensure satisfactory performance of vapor retarder.
  - 1. Unroll vapor retarder with the longest dimension parallel in the direction of the concrete pour.
  - 2. Lap vapor retarder over footings or seal to foundation walls.
  - 3. Overlap joints 6 inches and seal with manufacturer's tape.
  - 4. Seal all penetrations (including pipes) per manufacturer's instructions.
  - 5. Do not penetrate the vapor retarder except where necessary for reinforcing steel and permanent utilities.
  - 6. Repair damaged areas by cutting patches of vapor retarder, overlapping damaged area 6 inches and taping all four sides with seam tape.

END OF SECTION 07 26 00

# SECTION 075323 - ETHYLENE-PROPYLENE-DIENE-MONOMER (EPDM) ROOFING

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

### A. Section Includes:

- 1. Adhered ethylene-propylene-diene-monomer (EPDM) roofing system.
- 2. Substrate Cover Board

### B. Related Requirements:

- 1. Section 053100 "Steel Decking" for furnishing acoustical deck rib insulation.
- 2. Section 072100 "Thermal Insulation" for insulation beneath the roof deck.
- 3. Section 076200 "Sheet Metal Flashing and Trim" for metal roof flashings and counterflashings.
- 4. Section 077129 "Manufactured Roof Expansion Joints" for proprietary manufactured roof expansion-joint assemblies.
- 5. Section 079200 "Joint Sealants" for joint sealants, joint fillers, and joint preparation.

### 1.3 DEFINITIONS

A. Roofing Terminology: Definitions in ASTM D 1079 and glossary of NRCA's "The NRCA Roofing and Waterproofing Manual" apply to work of this Section.

### 1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Roofing Conference: Conduct conference at Project site.
  - 1. Meet with Owner, Architect, Owner's insurer if applicable, testing and inspecting agency representative, roofing Installer, roofing system manufacturer's representative, deck Installer, and installers whose work interfaces with or affects roofing, including installers of roof accessories and roof-mounted equipment.
  - 2. Review methods and procedures related to roofing installation, including manufacturer's written instructions.
  - 3. Review and finalize construction schedule, and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
  - 4. Examine deck substrate conditions and finishes for compliance with requirements, including flatness and fastening.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Issue Date: 06/05/2014

- 5. Review structural loading limitations of roof deck during and after roofing.
- Review base flashings, special roofing details, roof drainage, roof penetrations, 6. equipment curbs, and condition of other construction that affects roofing system.

Architect's Project #: 12.130.09

- Review governing regulations and requirements for insurance and certificates if 7. applicable.
- Review temporary protection requirements for roofing system during and after 8. installation.
- 9. Review roof observation and repair procedures after roofing installation.

#### 1.5 **ACTION SUBMITTALS**

- Product Data: For each type of product. A.
- B. Shop Drawings: For roofing system. Include plans, elevations, sections, details, and attachments to other work, including:
  - 1. Base flashings and membrane terminations.
  - Roof plan showing orientation of steel roof deck and orientation of roofing and fastening 2. spacings and patterns for mechanically fastened roofing.
  - 3. Insulation fastening patterns for corner, perimeter, and field-of-roof locations.
- C. Samples for Verification: For the following products:
  - Sheet roofing, of color required. 1.

#### 1.6 INFORMATIONAL SUBMITTALS

- Qualification Data: For Installer and manufacturer. A.
- B. Manufacturer Certificates: Signed by roofing manufacturer certifying that roofing system complies with requirements specified in "Performance Requirements" Article.
  - 1. Submit evidence of complying with performance requirements.
- C. Product Test Reports: For components of roofing system, tests performed by manufacturer and witnessed by a qualified testing agency.
- D. Research/Evaluation Reports: For components of roofing system, from ICC-ES.
- E. Field quality-control reports.
- F. Sample Warranties: For manufacturer's special warranties.

#### 1.7 **CLOSEOUT SUBMITTALS**

Maintenance Data: For roofing system to include in maintenance manuals. A.

### 1.8 QUALITY ASSURANCE

A. Manufacturer Qualifications: A qualified manufacturer that is UL listed for roofing system identical to that used for this Project.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. Installer Qualifications: A qualified firm that is approved, authorized, or licensed by roofing system manufacturer to install manufacturer's product and that is eligible to receive manufacturer's special warranty.

### 1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver roofing materials to Project site in original containers with seals unbroken and labeled with manufacturer's name, product brand name and type, date of manufacture, approval or listing agency markings, and directions for storing and mixing with other components.
- B. Store liquid materials in their original undamaged containers in a clean, dry, protected location and within the temperature range required by roofing system manufacturer. Protect stored liquid material from direct sunlight.
  - 1. Discard and legally dispose of liquid material that cannot be applied within its stated shelf life.
- C. Protect roof insulation materials from physical damage and from deterioration by sunlight, moisture, soiling, and other sources. Store in a dry location. Comply with insulation manufacturer's written instructions for handling, storing, and protecting during installation.
- D. Handle and store roofing materials, and place equipment in a manner to avoid permanent deflection of deck.

### 1.10 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed according to manufacturer's written instructions and warranty requirements.

### 1.11 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of roofing system that fail in materials or workmanship within specified warranty period.
  - 1. Special warranty includes membrane roofing, base flashings, fasteners, substrate board, roofing accessories, and other components of roofing system.
  - 2. Warranty Period: 20 years from date of Substantial Completion.

### PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

A. Source Limitations: Obtain components including fasteners, adhesives, etc. for roofing system from same manufacturer as membrane roofing or manufacturer approved by membrane roofing manufacturer.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# 2.2 PERFORMANCE REQUIREMENTS

- A. General Performance: Installed roofing and base flashings shall withstand specified uplift pressures, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Roofing and base flashings shall remain watertight.
  - 1. Accelerated Weathering: Roofing system shall withstand 2000 hours of exposure when tested according to ASTM G 152, ASTM G 154, or ASTM G 155.
  - 2. Impact Resistance: Roofing system shall resist impact damage when tested according to ASTM D 3746 or ASTM D 4272.
- B. Material Compatibility: Roofing materials shall be compatible with one another and adjacent materials under conditions of service and application required, as demonstrated by roofing manufacturer based on testing and field experience.
- C. Roofing System Design: Tested by a qualified testing agency to resist the following uplift pressures:
  - 1. Corner Uplift Pressure: 34.3 lbf/sq. ft. (kPa/sq. m).
  - 2. Perimeter Uplift Pressure: 23.2 lbf/sq. ft. (kPa/sq. m).
  - 3. Field-of-Roof Uplift Pressure: 13.3 lbf/sq. ft. (kPa/sq. m).
- D. Exterior Fire-Test Exposure: ASTM E 108 or UL 790, Class A; for application and roof slopes indicated; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

### 2.3 EPDM ROOFING

- A. EPDM: ASTM D 4637, Type I, nonreinforced, uniform, flexible EPDM sheet.
  - a. <u>Manufacturers:</u> Subject to compliance with requirements, provide JM EPDM NR membrane by <u>Johns Manville</u>; a <u>Berkshire Hathaway company</u>, or equivalent by one of the following manufacturers:
  - b. Carlisle SynTec Incorporated.
  - c. Firestone Building Products.
  - d. GAF Materials Corporation.
  - 2. Thickness: 60 mils (1.5 mm), nominal.

e-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

3. Exposed Face Color: Black.

### 2.4 AUXILIARY ROOFING MATERIALS

- A. General: Auxiliary materials recommended by roofing system manufacturer for intended use and compatible with roofing.
  - 1. Liquid-type auxiliary materials shall comply with VOC limits of authorities having jurisdiction.
- B. Sheet Flashing: 60-mil- (1.5-mm-) thick EPDM self-adhering type, partially cured or cured, according to application.
- C. Bonding Adhesive: Manufacturer's standard, water based.
- D. Seaming Material: Manufacturer's standard, synthetic-rubber polymer primer and 3-inch- (75-mm-) wide minimum, butyl splice tape with release film.
- E. Lap Sealant: Manufacturer's standard, single-component sealant, colored to match membrane roofing.
- F. Water Cutoff Mastic: Manufacturer's standard butyl mastic sealant.
- G. Metal Termination Bars: Manufacturer's standard, predrilled stainless-steel or aluminum bars, approximately 1 by 1/8 inch (25 by 3 mm) thick; with anchors.
- H. Metal Battens: Manufacturer's standard, aluminum-zinc-alloy-coated or zinc-coated steel sheet, approximately 1 inch wide by 0.05 inch thick (25 mm wide by 1.3 mm thick), prepunched.
- I. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Global 4470, designed for fastening membrane to substrate, and acceptable to roofing system manufacturer.
- J. Miscellaneous Accessories: Provide pourable sealers, preformed cone and vent sheet flashings, molded pipe boot flashings, preformed inside and outside corner sheet flashings, reinforced EPDM securement strips, T-joint covers, in-seam sealants, termination reglets, cover strips, and other accessories.
  - 1. Provide black flashing accessories for black EPDM membrane roofing.
- K. Sheet Metal Flashing and Trim: Refer to Section 076200 Sheet Metal Flashing and Trim for low-slope roof sheet metal fabrications.

### 2.5 SUBSTRATE COVER BOARDS

A. Substrate Board: ASTM C 1177/C 1177M, glass-mat, water-resistant gypsum substrate, 1/2 inch (13 mm) thick.

1. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by one of the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- a. CertainTeed Corporation.
- b. Georgia-Pacific Building Products.
- c. National Gypsum Company.
- d. Temple-Inland Building Products by Georgia-Pacific.
- e. <u>United States Gypsum Company</u>.
- B. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Global 4470, designed for fastening substrate panel to roof deck.

### 2.6 ROOF INSULATION

A. General: Refer to section 072100 Thermal Insulation for requirements regarding continuous spray polyurethane foam insulation below the roof deck.

### **PART 3 - EXECUTION**

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements and other conditions affecting performance of the Work:
  - 1. Verify that roof openings and penetrations are in place, curbs are set and braced, and roof-drain bodies are securely clamped in place.
  - 2. Verify that wood blocking, curbs, and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thicknesses of insulation.
  - 3. Verify that surface plane flatness and fastening of steel roof deck complies with requirements in Section 053100 "Steel Decking."
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Clean substrate of dust, debris, moisture, and other substances detrimental to roofing installation according to roofing system manufacturer's written instructions. Remove sharp projections.
- B. Prevent materials from entering and clogging roof drains and conductors and from spilling or migrating onto surfaces of other construction. Remove roof-drain plugs when no work is taking place or when rain is forecast.

### 3.3 ROOFING INSTALLATION, GENERAL

A. Install roofing system according to roofing system manufacturer's written instructions.

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

B. Complete terminations and base flashings and provide temporary seals to prevent water from entering completed sections of roofing system at the end of the workday or when rain is forecast. Remove and discard temporary seals before beginning work on adjoining roofing.

### 3.4 SUBSTRATE COVER BOARD INSTALLATION

- A. Install substrate cover board with long joints in continuous straight lines, perpendicular to roof slopes with end joints staggered between rows. Tightly butt substrate boards together.
  - 1. Fasten substrate board to top flanges of steel deck to resist uplift pressure at corners, perimeter, and field of roof according to roofing system manufacturers' written instructions.

### 3.5 ADHERED MEMBRANE ROOFING INSTALLATION

- A. Adhere roofing over area to receive roofing according to membrane roofing system manufacturer's written instructions. Unroll membrane roofing and allow to relax before installing.
- B. Start installation of roofing in presence of roofing system manufacturer's technical personnel.
- C. Accurately align roofing, and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps.
- D. Bonding Adhesive: Apply to substrate and underside of roofing at rate required by manufacturer, and allow to partially dry before installing roofing. Do not apply to splice area of roofing.
- E. In addition to adhering, mechanically fasten roofing securely at terminations, penetrations, and perimeters.
- F. Apply roofing with side laps shingled with slope of roof deck where possible.
- G. Tape Seam Installation: Clean and prime both faces of splice areas, apply splice tape, and firmly roll side and end laps of overlapping roofing according to manufacturer's written instructions to ensure a watertight seam installation. Apply lap sealant and seal exposed edges of roofing terminations.
- H. Repair tears, voids, and lapped seams in roofing that do not comply with requirements.
- I. Spread sealant or mastic bed over deck-drain flange at roof drains, and securely seal membrane roofing in place with clamping ring.
  - 1. kg/sq. m).

### 3.6 BASE FLASHING INSTALLATION

A. Install sheet flashings and preformed flashing accessories, and adhere to substrates according to roofing system manufacturer's written instructions.

-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- B. Apply bonding adhesive to substrate and underside of sheet flashing at required rate, and allow to partially dry. Do not apply to seam area of flashing.
- C. Flash penetrations and field-formed inside and outside corners with cured or uncured sheet flashing.
- D. Clean splice areas, apply splicing cement, and firmly roll side and end laps of overlapping sheets to ensure a watertight seam installation. Apply lap sealant and seal exposed edges of sheet flashing terminations.
- E. Terminate and seal top of sheet flashings and mechanically anchor to substrate through termination bars.

# 3.7 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to inspect substrate conditions, surface preparation, membrane application, flashings, protection, and drainage components, and to furnish reports to Architect.
- B. Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion.
- C. Repair or remove and replace components of roofing system where inspections indicate that they do not comply with specified requirements.
- D. Additional testing and inspecting, at Contractor's expense, will be performed to determine if replaced or additional work complies with specified requirements.

### 3.8 PROTECTING AND CLEANING

- A. Protect membrane roofing system from damage and wear during remainder of construction period. When remaining construction does not affect or endanger roofing, inspect roofing for deterioration and damage, describing its nature and extent in a written report, with copies to Architect and Owner.
- B. Correct deficiencies in or remove membrane roofing system that does not comply with requirements, repair substrates, and repair or reinstall membrane roofing system to a condition free of damage and deterioration at time of Substantial Completion and according to warranty requirements.

### 3.9 ROOFING INSTALLER'S WARRANTY

A.	WHEREAS called the "Roofing Installer," following project:		of has performed roofing and associated			work ("work") on the	
	1	Owner:					
	2.	Address:			•		
	3.	Building Name/Type:			·		
	3. 4.	Address:			·		
					•		
	5.	Area of Work:			•		
	6.	Acceptance Date:			•		
	7.	Warranty Period:			•		
	8	Expiration Date:					

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. AND WHEREAS Roofing Installer has contracted (either directly with Owner or indirectly as a subcontractor) to warrant said work against leaks and faulty or defective materials and workmanship for designated Warranty Period,
- C. NOW THEREFORE Roofing Installer hereby warrants, subject to terms and conditions herein set forth, that during Warranty Period he will, at his own cost and expense, make or cause to be made such repairs to or replacements of said work as are necessary to correct faulty and defective work and as are necessary to maintain said work in a watertight condition.
- D. This Warranty is made subject to the following terms and conditions:
  - 1. Specifically excluded from this Warranty are damages to work and other parts of the building, and to building contents, caused by:
    - a. lightning:
    - b. peak gust wind speed exceeding 70 mph;
    - c. fire;
    - d. failure of roofing system substrate, including cracking, settlement, excessive deflection, deterioration, and decomposition;
    - e. faulty construction of parapet walls, copings, chimneys, skylights, vents, equipment supports, and other edge conditions and penetrations of the work;
    - f. vapor condensation on bottom of roofing; and
    - g. activity on roofing by others, including construction contractors, maintenance personnel, other persons, and animals, whether authorized or unauthorized by Owner.
  - 2. When work has been damaged by any of foregoing causes, Warranty shall be null and void until such damage has been repaired by Roofing Installer and until cost and expense thereof have been paid by Owner or by another responsible party so designated.
  - 3. Roofing Installer is responsible for damage to work covered by this Warranty but is not liable for consequential damages to building or building contents resulting from leaks or faults or defects of work.
  - 4. During Warranty Period, if Owner allows alteration of work by anyone other than Roofing Installer, including cutting, patching, and maintenance in connection with penetrations, attachment of other work, and positioning of anything on roof, this Warranty shall become null and void on date of said alterations, but only to the extent

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- said alterations affect work covered by this Warranty. If Owner engages Roofing Installer to perform said alterations, Warranty shall not become null and void unless Roofing Installer, before starting said work, shall have notified Owner in writing, showing reasonable cause for claim, that said alterations would likely damage or deteriorate work, thereby reasonably justifying a limitation or termination of this Warranty.
- 5. During Warranty Period, if original use of roof is changed and it becomes used for, but was not originally specified for, a promenade, work deck, spray-cooled surface, flooded basin, or other use or service more severe than originally specified, this Warranty shall become null and void on date of said change, but only to the extent said change affects work covered by this Warranty.
- 6. Owner shall promptly notify Roofing Installer of observed, known, or suspected leaks, defects, or deterioration and shall afford reasonable opportunity for Roofing Installer to inspect work and to examine evidence of such leaks, defects, or deterioration.
- 7. This Warranty is recognized to be the only warranty of Roofing Installer on said work and shall not operate to restrict or cut off Owner from other remedies and resources lawfully available to Owner in cases of roofing failure. Specifically, this Warranty shall not operate to relieve Roofing Installer of responsibility for performance of original work according to requirements of the Contract Documents, regardless of whether Contract was a contract directly with Owner or a subcontract with Owner's General Contractor.

E.		/ITNESS THEREOF, thi	s instrument has been duly executed this	day of
	1.	Authorized Signature:	<del>-</del>	
	2.	Name:	·	
	3.	Title:	·	

END OF SECTION 075323

### SECTION 076200 - SHEET METAL FLASHING AND TRIM

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

### A. Section Includes:

- 1. Formed low-slope roof sheet metal fabrications.
- 2. Formed wall sheet metal fabrications.

### B. Related Requirements:

- 1. Section 075323 Ethylene-Propylene-Diene-Monomer (Epdm) Roofing for installation of sheet metal flashing and trim integral with roofing.
- 2. Section 079500 "Expansion Control" for manufactured expansion-joint covers.

### 1.3 COORDINATION

- A. Coordinate sheet metal flashing and trim layout and seams with sizes and locations of penetrations to be flashed, and joints and seams in adjacent materials.
- B. Coordinate sheet metal flashing and trim installation with adjoining roofing and wall materials, joints, and seams to provide leakproof, secure, and noncorrosive installation.

### 1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
  - 1. Review construction schedule. Verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
  - 2. Review special roof details, roof drainage, roof-penetration flashing, equipment curbs, and condition of other construction that affect sheet metal flashing and trim.
  - 3. Review sheet metal flashing observation and repair procedures after flashing installation.

# 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each manufactured product and accessory.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# B. Shop Drawings: For sheet metal flashing and trim.

- 1. Include plans, elevations, sections, and attachment details.
- 2. Detail fabrication and installation layouts, expansion-joint locations, and keyed details. Distinguish between shop- and field-assembled work.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 3. Include identification of material, thickness, weight, and finish for each item and location in Project.
- 4. Include details for forming, including profiles, shapes, seams, and dimensions.
- 5. Include details for joining, supporting, and securing, including layout and spacing of fasteners, cleats, clips, and other attachments. Include pattern of seams.
- 6. Include details of termination points and assemblies.
- 7. Include details of expansion joints and expansion-joint covers, including showing direction of expansion and contraction from fixed points.
- 8. Include details of roof-penetration flashing.
- 9. Include details of special conditions.
- 10. Include details of connections to adjoining work.
- 11. Detail formed flashing and trim at scale of not less than 1-1/2 inches per 12 inches (1:10).

### C. Samples for Verification: For each type of exposed finish.

- 1. Sheet Metal Flashing: 12 inches (300 mm) long by actual width of unit, including finished seam and in required profile. Include fasteners, cleats, clips, closures, and other attachments.
- 2. Trim, Metal Closures, Expansion Joints, Joint Intersections, and Miscellaneous Fabrications: 12 inches (300 mm) long and in required profile. Include fasteners and other exposed accessories.
- 3. Unit-Type Accessories and Miscellaneous Materials: Full-size Sample.
- 4. Anodized Aluminum Samples: Samples to show full range to be expected for each color required.

### 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For fabricator.
- B. Product Test Reports: For each product, for tests performed by a qualified testing agency.
- C. Sample Warranty: For special warranty.

### 1.7 CLOSEOUT SUBMITTALS

A. Maintenance Data: For sheet metal flashing and trim, and its accessories, to include in maintenance manuals.

# 1.8 QUALITY ASSURANCE

A. Fabricator Qualifications: Employs skilled workers who custom fabricate sheet metal flashing and trim similar to that required for this Project and whose products have a record of successful in-service performance.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for fabrication and installation.
  - 1. Build mockup of typical roof edge, including Coping, approximately 10 feet (3.0 m) long, including supporting construction cleats, seams, attachments, underlayment, and accessories.
  - 2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
  - 3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

### 1.9 DELIVERY, STORAGE, AND HANDLING

- A. Do not store sheet metal flashing and trim materials in contact with other materials that might cause staining, denting, or other surface damage. Store sheet metal flashing and trim materials away from uncured concrete and masonry.
- B. Protect strippable protective covering on sheet metal flashing and trim from exposure to sunlight and high humidity, except to extent necessary for period of sheet metal flashing and trim installation.

### 1.10 WARRANTY

- A. Special Warranty on Finishes: Manufacturer agrees to repair finish or replace sheet metal flashing and trim that shows evidence of deterioration of factory-applied finishes within specified warranty period.
  - 1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:
    - a. Color fading more than 5 Hunter units when tested according to ASTM D 2244.
    - b. Chalking in excess of a No. 8 rating when tested according to ASTM D 4214.
    - c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.
  - 2. Finish Warranty Period: 20 years from date of Substantial Completion.

Architect's Project #: 12.130.09

### PART 2 - PRODUCTS

#### 2.1 PERFORMANCE REQUIREMENTS

- A. General: Sheet metal flashing and trim assemblies shall withstand wind loads, structural movement, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Completed sheet metal flashing and trim shall not rattle, leak, or loosen, and shall remain watertight.
- Thermal Movements: Allow for thermal movements from ambient and surface temperature B. changes to prevent buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
  - 1. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

#### 2.2 SHEET METALS

- General: Protect mechanical and other finishes on exposed surfaces from damage by applying A. strippable, temporary protective film before shipping.
- B. Aluminum Sheet: ASTM B 209 (ASTM B 209M), alloy as standard with manufacturer for finish required, with temper as required to suit forming operations and performance required; with smooth, flat surface.
  - 1. **Exposed Coil-Coated Finish:** 
    - Paint Finish: Kynar 500 a.
    - Color: Black. h.

#### 2.3 **UNDERLAYMENT MATERIALS**

- Felt: ASTM D 226/D 226M, Type II (No. 30), asphalt-saturated organic felt; nonperforated. A.
- Self-Adhering, High-Temperature Sheet: Minimum 30 mils (0.76 mm) thick, consisting of a B. slip-resistant polyethylene- or polypropylene-film top surface laminated to a layer of butyl- or SBS-modified asphalt adhesive, with release-paper backing; specifically designed to withstand high metal temperatures beneath metal roofing. Provide primer according to written recommendations of underlayment manufacturer.
  - Manufacturers: Subject to compliance with requirements, available manufacturers 1. offering products that may be incorporated into the Work include, but are not limited to the following:
    - Carlisle Coatings & Waterproofing Inc. a.
    - Grace Construction Products; W.R. Grace & Co. -- Conn. b.
    - Henry Company. c.
    - Metal-Fab Manufacturing, LLC. d.

Issue Date: 06/05/2014

# e. Owens Corning.

2. Thermal Stability: ASTM D 1970; stable after testing at 240 deg F (116 deg C) or higher.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 3. Low-Temperature Flexibility: ASTM D 1970; passes after testing at minus 20 deg F (29 deg C) or lower.
- C. Slip Sheet: Rosin-sized building paper, 3 lb/100 sq. ft. (0.16 kg/sq. m)minimum.

### 2.4 MISCELLANEOUS MATERIALS

- A. General: Provide materials and types of fasteners, solder, protective coatings, sealants, and other miscellaneous items as required for complete sheet metal flashing and trim installation and as recommended by manufacturer of primary sheet metal unless otherwise indicated.
- B. Fasteners: Wood screws, annular threaded nails, self-tapping screws, self-locking rivets and bolts, and other suitable fasteners designed to withstand design loads and recommended by manufacturer of primary sheet metal.
  - 1. General: Blind fasteners or self-drilling screws, gasketed, with hex-washer head.
    - a. Exposed Fasteners: Heads matching color of sheet metal using plastic caps or factory-applied coating. Provide metal-backed EPDM or PVC sealing washers under heads of exposed fasteners bearing on weather side of metal.
    - b. Blind Fasteners: High-strength aluminum or stainless-steel rivets suitable for metal being fastened.
    - c. Spikes and Ferrules: Same material as gutter; with spike with ferrule matching internal gutter width.
  - 2. Fasteners for Aluminum Sheet: Aluminum or Series 300 stainless steel.
  - 3. Fasteners for Stainless-Steel Sheet: Series 300 stainless steel.
  - 4. Fasteners for Zinc-Tin Alloy-Coated Stainless-Steel Sheet: Series 300 stainless steel.
- C. Sealant Tape: Pressure-sensitive, 100 percent solids, polyisobutylene compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape 1/2 inch (13 mm) wide and 1/8 inch (3 mm) thick.
- D. Elastomeric Sealant: ASTM C 920, elastomeric silicone polymer sealant; of type, grade, class, and use classifications required to seal joints in sheet metal flashing and trim and remain watertight.
- E. Bituminous Coating: Cold-applied asphalt emulsion according to ASTM D 1187.

### 2.5 FABRICATION, GENERAL

A. General: Custom fabricate sheet metal flashing and trim to comply with details shown and recommendations in cited sheet metal standard that apply to design, dimensions, geometry, metal thickness, and other characteristics of item required. Fabricate sheet metal flashing and trim in shop to greatest extent possible.

Carolina Architect's Project #: 12.130.09
nnis Complex Addition

Issue Date: 06/05/2014

- 1. Fabricate sheet metal flashing and trim in thickness or weight needed to comply with performance requirements, but not less than that specified for each application and metal.
- 2. Obtain field measurements for accurate fit before shop fabrication.
- 3. Form sheet metal flashing and trim to fit substrates without excessive oil canning, buckling, and tool marks; true to line, levels, and slopes; and with exposed edges folded back to form hems.
- 4. Conceal fasteners and expansion provisions where possible. Do not use exposed fasteners on faces exposed to view.
- B. Fabrication Tolerances: Fabricate sheet metal flashing and trim that is capable of installation to a tolerance of 1/4 inch in 20 feet (6 mm in 6 m) on slope and location lines indicated on Drawings and within 1/8-inch (3-mm) offset of adjoining faces and of alignment of matching profiles.
- C. Expansion Provisions: Form metal for thermal expansion of exposed flashing and trim.
  - 1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch (25 mm) deep, filled with butyl sealant concealed within joints.
- D. Sealant Joints: Where movable, nonexpansion-type joints are required, form metal to provide for proper installation of elastomeric sealant according to cited sheet metal standard.
- E. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal.
- F. Fabricate cleats and attachment devices of sizes as recommended by cited sheet metal standard and by FM Global Property Loss Prevention Data Sheet 1-49 for application, but not less than thickness of metal being secured.
- G. Seams: Fabricate nonmoving seams with flat-lock seams. Form seams and seal with elastomeric sealant unless otherwise recommended by sealant manufacturer for intended use. Rivet joints where necessary for strength.
- H. Do not use graphite pencils to mark metal surfaces.

### 2.6 LOW-SLOPE ROOF SHEET METAL FABRICATIONS

- A. Roof Edge Flashing (Gravel Stop): Fabricate in minimum 96-inch- (2400-mm-) long, but not exceeding 12-foot- (3.6-m-) long sections. Furnish with 6-inch- (150-mm-) wide, joint cover plates. Shop fabricate interior and exterior corners.
  - 1. Joint Style: Overlapped, 4 inches (100 mm) wide.
  - 2. Fabricate from the Following Materials:
    - a. Aluminum: 0.050 inch (1.27 mm) thick.
    - b. Color: Black

### PART 3 - EXECUTION

3.1

**EXAMINATION** 

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, substrate, and other conditions affecting performance of the Work.
  - 1. Verify compliance with requirements for installation tolerances of substrates.
  - 2. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 3. Verify that air- or water-resistant barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.
- B. For the record, prepare written report, endorsed by the installer, listing conditions detrimental to performance of the work as unsatisfactory.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 UNDERLAYMENT INSTALLATION

- A. Self-Adhering Sheet Underlayment: Install self-adhering sheet underlayment, wrinkle free. Prime substrate if recommended by underlayment manufacturer. Comply with temperature restrictions of underlayment manufacturer for installation; use primer for installing underlayment at low temperatures. Apply in shingle fashion to shed water, with end laps of not less than 6 inches (150 mm) staggered 24 inches (600 mm) between courses. Overlap side edges not less than 3-1/2 inches (90 mm). Roll laps and edges with roller. Cover underlayment within 14 days.
- B. Apply slip sheet, wrinkle free, over underlayment before installing sheet metal flashing and trim.

# 3.3 INSTALLATION, GENERAL

- A. General: Anchor sheet metal flashing and trim and other components of the Work securely in place, with provisions for thermal and structural movement. Use fasteners, solder, protective coatings, separators, sealants, and other miscellaneous items as required to complete sheet metal flashing and trim system.
  - 1. Install sheet metal flashing and trim true to line, levels, and slopes. Provide uniform, neat seams with minimum exposure of solder, welds, and sealant.
  - 2. Install sheet metal flashing and trim to fit substrates and to result in watertight performance. Verify shapes and dimensions of surfaces to be covered before fabricating sheet metal.
  - 3. Space cleats not more than 12 inches (300 mm) apart. Attach each cleat with at least two fasteners. Bend tabs over fasteners.

4. Install exposed sheet metal flashing and trim with limited oil canning, and free of buckling and tool marks.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 5. Install sealant tape where indicated.
- 6. Torch cutting of sheet metal flashing and trim is not permitted.
- 7. Do not use graphite pencils to mark metal surfaces.
- B. Metal Protection: Where dissimilar metals contact each other, or where metal contacts pressuretreated wood or other corrosive substrates, protect against galvanic action or corrosion by painting contact surfaces with bituminous coating or by other permanent separation as recommended by sheet metal manufacturer or cited sheet metal standard.
  - 1. Coat concealed side of uncoated-aluminum and stainless-steel sheet metal flashing and trim with bituminous coating where flashing and trim contact wood, ferrous metal, or cementitious construction.
  - 2. Underlayment: Where installing sheet metal flashing and trim directly on cementitious or wood substrates, install underlayment and cover with slip sheet.
- C. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at maximum of **10 feet (3 m)** with no joints within 24 inches (600 mm) of corner or intersection.
  - 1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch (25 mm) deep, filled with sealant concealed within joints.
- D. Fasteners: Use fastener sizes that penetrate wood blocking or sheathing not less than 1-1/4 inches (32 mm) for nails and not less than 3/4 inch (19 mm) for wood screws.
- E. Conceal fasteners and expansion provisions where possible in exposed work and locate to minimize possibility of leakage. Cover and seal fasteners and anchors as required for a tight installation.
- F. Seal joints as required for watertight construction.
  - 1. Use sealant-filled joints unless otherwise indicated. Embed hooked flanges of joint members not less than 1 inch (25 mm) into sealant. Form joints to completely conceal sealant. When ambient temperature at time of installation is between 40 and 70 deg F (4 and 21 deg C), set joint members for 50 percent movement each way. Adjust setting proportionately for installation at higher ambient temperatures. Do not install sealant-type joints at temperatures below 40 deg F (4 deg C).
  - 2. Prepare joints and apply sealants to comply with requirements in Section 079200 "Joint Sealants."

### 3.4 ROOF FLASHING INSTALLATION

A. General: Install sheet metal flashing and trim to comply with performance requirements and SMACMA's "Architectural Sheet Metal Manual". Provide concealed fasteners where possible, and set units true to line, levels, and slopes. Install work with laps, joints, and seams that are permanently watertight and weather resistant.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Roof Edge Flashing: Anchor to resist uplift and outward forces according to recommendations in FM Global Property Loss Prevention Data Sheet 1-49 for FM Approvals' listing for required windstorm classification.
- C. Counterflashing: Coordinate installation of counterflashing with installation of base flashing. Insert counterflashing in reglets or receivers and fit tightly to base flashing. Extend counterflashing 4 inches (100 mm) over base flashing. Lap counterflashing joints minimum of 4 inches (100 mm). Secure in waterproof manner by means of interlocking folded seam or blind rivets and sealant unless otherwise indicated.
- D. Roof-Penetration Flashing: Coordinate installation of roof-penetration flashing with installation of roofing and other items penetrating roof. Seal with elastomeric sealant and clamp flashing to pipes that penetrate roof.

### 3.5 WALL FLASHING INSTALLATION

- A. General: Install sheet metal wall flashing to intercept and exclude penetrating moisture according to SMACMA's "Architectural Sheet Metal Manual" standard unless otherwise indicated. Coordinate installation of wall flashing with installation of wall-opening components such as windows, doors, and louvers.
- B. Through-Wall Flashing: Installation of through-wall flashing is specified in Section 042000 "Unit Masonry".

### 3.6 MISCELLANEOUS FLASHING INSTALLATION

A. Equipment Support Flashing: Coordinate installation of equipment support flashing with installation of roofing and equipment. Weld or seal flashing with elastomeric sealant to equipment support member.

### 3.7 ERECTION TOLERANCES

A. Installation Tolerances: Shim and align sheet metal flashing and trim within installed tolerance of 1/4 inch in 20 feet (6 mm in 6 m) on slope and location lines indicated on Drawings and within 1/8-inch (3-mm) offset of adjoining faces and of alignment of matching profiles.

### 3.8 CLEANING AND PROTECTION

- A. Clean exposed metal surfaces of substances that interfere with uniform oxidation and weathering.
- B. Clean off excess sealants.
- C. Remove temporary protective coverings and strippable films as sheet metal flashing and trim are installed unless otherwise indicated in manufacturer's written installation instructions. On completion of sheet metal flashing and trim installation, remove unused materials and clean

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

finished surfaces as recommended by sheet metal flashing and trim manufacturer. Maintain sheet metal flashing and trim in clean condition during construction.

D. Replace sheet metal flashing and trim that have been damaged or that have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION 076200

### SECTION 079200 - JOINT SEALANTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 1.2 SUMMARY

#### A. Section Includes:

- 1. Silicone joint sealants.
- 2. Urethane joint sealants.
- 3. Latex joint sealants.
- 4. Solvent-release-curing joint sealants.
- 5. Acoustical joint sealants.

### B. Related Requirements:

- 1. Division 4 Section "Unit Masonry" for masonry control and expansion joints.
- 2. Division 8 Section "Glazing" for glazing sealants
- 3. Division 9 Section "Gypsum Board assemblies" for sealing perimeter joints.
- 4. Division 9 Section "Tiling" for sealing tile joints
- 5. Division 9 Section "Acoustical Panel Ceilings" for sealing edge moldings at perimeters with acoustic sealants.

#### 1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

### 1.4 ACTION SUBMITTALS

- A. Product Data: For each joint-sealant product.
- B. Samples for Initial Selection: Manufacturer's color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.
- C. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch- (13-mm-) wide joints formed between two 6-inch- (150-mm-) long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.
- D. Joint-Sealant Schedule: Include the following information:
  - 1. Joint-sealant application, joint location, and designation.

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 2. Joint-sealant manufacturer and product name.
- 3. Joint-sealant formulation.
- 4. Joint-sealant color.

### 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified testing agency.
- B. Product Test Reports: For each kind of joint sealant, for tests performed by a qualified testing agency indicating that sealants comply with requirements.
- C. Preconstruction Laboratory Test Schedule: Include the following information for each joint sealant and substrate material to be tested:
  - 1. Joint-sealant location and designation.
  - 2. Manufacturer and product name.
  - 3. Type of substrate material.
  - 4. Proposed test.
  - 5. Number of samples required.
- D. Preconstruction Field-Adhesion-Test Reports: Indicate which sealants and joint preparation methods resulted in optimum adhesion to joint substrates based on testing specified in "Preconstruction Testing" Article.
- E. Field-Adhesion-Test Reports: For each sealant application tested.
- F. Sample Warranties: For special warranties.

### 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An authorized representative who is trained and approved by manufacturer.
- B. Product Testing: Test joint sealants using a qualified testing agency.
  - 1. Testing Agency Qualifications: Qualified according to ASTM C 1021 to conduct the testing indicated.

## 1.7 FIELD CONDITIONS

- A. Do not proceed with installation of joint sealants under the following conditions:
  - 1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F (5 deg C).
  - 2. When joint substrates are wet.
  - 3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
  - 4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

#### 1.8 WARRANTY

A. Special Installer's Warranty: Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Warranty Period: Two years from date of Substantial Completion.
- B. Special Manufacturer's Warranty: Manufacturer agrees to furnish joint sealants to repair or replace those joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
  - 1. Warranty Period: Five years from date of Substantial Completion.
- C. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:
  - 1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
  - 2. Disintegration of joint substrates from causes exceeding design specifications.
  - 3. Mechanical damage caused by individuals, tools, or other outside agents.
  - 4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

#### PART 2 - PRODUCTS

## 2.1 JOINT SEALANTS, GENERAL

- A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.
- B. VOC Content of Interior Sealants: Sealants and sealant primers used inside the weatherproofing system shall comply with the following:
  - 1. Architectural sealants shall have a VOC content of 250 g/L or less.
  - 2. Sealants and sealant primers for nonporous substrates shall have a VOC content of 250 g/L or less.
  - 3. Sealants and sealant primers for nonporous substrates shall have a VOC content of 775 g/L or less.
- C. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

## 2.2 SILICONE JOINT SEALANTS

A. Silicone, S, NS, 100/50, NT: Single-component, nonsag, plus 100 percent and minus 50 percent movement capability, nontraffic-use, neutral-curing silicone joint sealant; ASTM C 920, Type S, Grade NS, Class 100/50, Use NT.

1. <u>Products</u>: Subject to compliance with requirements, provide one of the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- a. <u>Dow Corning Corporation</u>; 790.
- b. <u>GE Advanced Materials</u> Silicones; SilPruf LM SCS2700.
- c. Pecora Corporation; 890.
- d. Sika Corporation, Construction Products Division; SikaSil-C990.
- e. Tremco Incorporated; Spectrem 1.

#### 2.3 URETHANE JOINT SEALANTS

- A. Urethane, S, NS, 25, NT: Single-component, nonsag, nontraffic-use, plus 25 percent and minus 25 percent movement capability, urethane joint sealant; ASTM C 920, Type S, Grade NS, Class 25, Use NT.
  - 1. <u>Products:</u> Subject to compliance with requirements, provide one of the following:
    - a. <u>Sika Corporation, Construction Products Division;</u> Sikaflex 1CSL.
    - b. <u>Tremco Incorporated</u>; Vulkem 45.

#### 2.4 IMMERSIBLE JOINT SEALANTS

- A. Immersible Joint Sealants. Suitable for immersion in liquids; ASTM C 1247, Class 1; tested in deionized water unless otherwise indicated
- B. Urethane, Immersible, S, P, 25, T, NT, I: Immersible, single-component, pourable, plus 25 percent and minus 25 percent movement capability, traffic- and nontraffic-use, urethane joint sealant; ASTM C 920, Type S, Grade P, Class 25, Uses T, NT, and I.
  - 1. <u>Products:</u> Subject to compliance with requirements, provide one of the following:
    - a. <u>Sika Corporation, Construction Products Division;</u> Sikaflex 1CSL.
    - b. <u>Tremco Incorporated</u>; Vulkem 45.

#### 2.5 MILDEW-RESISTANT JOINT SEALANTS

- A. Mildew-Resistant Joint Sealants: Formulated for prolonged exposure to humidity with fungicide to prevent mold and mildew growth.
- B. Silicone, Mildew Resistant, Acid Curing, S, NS, 25, NT: Mildew-resistant, single-component, nonsag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, acid-curing silicone joint sealant; ASTM C 920, Type S, Grade NS, Class 25, Use NT.
  - 1. <u>Products</u>: Subject to compliance with requirements, provide one of the following:
    - a. <u>BASF Building Systems</u>; Omniplus.
    - b. <u>Dow Corning Corporation</u>; 786 Mildew Resistant.
    - c. GE Advanced Materials Silicones; Sanitary SCS1700.
    - d. May National Associates, Inc.; Bondaflex Sil 100 WF.
    - e. <u>Tremco Incorporated</u>; Tremsil 200 Sanitary.

#### 2.6 POLYSULFIDE JOINT SEALANTS

A. Polysulfide, M, P, 25, T, NT: Multicomponent, pourable, plus 25 percent and minus 25 percent movement capability, traffic- and nontraffic-use, polysulfide joint sealant; ASTM C 920, Type M, Grade P, Class 25, Uses T and NT.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. <u>Products</u>: Subject to compliance with requirements, provide one of the following:
  - a. <u>BASF Building Systems</u>; Sonolastic Polysulfide Sealant.
  - b. Pecora Corporation; Synthacalk GC-2+.

#### 2.7 BUTYL JOINT SEALANTS

- A. Butyl-Rubber-Based Joint Sealants: ASTM C 1311.
  - 1. <u>Products</u>: Subject to compliance with requirements, provide one of the following:
    - a. Bostik, Inc.; Chem-Calk 300.
    - b. Pecora Corporation; BC-158.
    - c. <u>Tremco Incorporated</u>; Tremco Butyl Sealant.
  - 2. Location: mastic under thresholds.

#### 2.8 LATEX JOINT SEALANTS

- A. Acrylic Latex: Acrylic latex or siliconized acrylic latex, ASTM C 834, Type OP, Grade NF.
  - 1. <u>Products</u>: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
    - a. BASF Building Systems; Sonolac.
    - b. Bostik, Inc.; Chem-Calk 600.
    - c. <u>Pecora Corporation</u>; AC-20+.
    - d. <u>Tremco Incorporated</u>; Tremflex 834.

#### 2.9 JOINT-SEALANT BACKING

- A. Sealant Backing Material, General: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
- B. Cylindrical Sealant Backings: ASTM C 1330, Type C (closed-cell material with a surface skin) or any of the preceding types, as approved in writing by joint-sealant manufacturer for joint application indicated, and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.
- C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

#### 2.10 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.
- C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

#### **PART 3 - EXECUTION**

#### 3.1 EXAMINATION

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:
  - 1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
  - 2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:
    - a. Concrete.
    - b. Masonry.
    - c. Unglazed surfaces of ceramic tile.
    - d. Exterior insulation and finish systems.
  - 3. Remove laitance and form-release agents from concrete.
  - 4. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:

- a. Metal.
- b. Glass.
- c. Porcelain enamel.
- d. Glazed surfaces of ceramic tile.
- B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

Issue Date: 06/05/2014

C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

## 3.3 INSTALLATION OF JOINT SEALANTS

- A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.
- B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- C. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
  - 1. Do not leave gaps between ends of sealant backings.
  - 2. Do not stretch, twist, puncture, or tear sealant backings.
  - 3. Remove absorbent sealant backings that have become wet before sealant application, and replace them with dry materials.
- D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.
- E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:
  - 1. Place sealants so they directly contact and fully wet joint substrates.
  - 2. Completely fill recesses in each joint configuration.
  - 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.
  - 1. Remove excess sealant from surfaces adjacent to joints.

2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 3. Provide concave joint profile per Figure 8A in ASTM C 1193 unless otherwise indicated.
- 4. Provide flush joint profile at locations indicated on Drawings according to Figure 8B in ASTM C 1193.

#### 3.4 FIELD QUALITY CONTROL

- A. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:
  - 1. Extent of Testing: Test completed and cured sealant joints as follows:
    - a. Perform 10 tests for the first 1000 feet (300 m) of joint length for each kind of sealant and joint substrate and one test for each 1000 feet (300 m) of joint length thereafter.
  - 2. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.
    - a. For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.
  - 3. Inspect tested joints and report on the following:
    - a. Whether sealants filled joint cavities and are free of voids.
    - b. Whether sealant dimensions and configurations comply with specified requirements.
    - c. Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. Compare these results to determine if adhesion complies with sealant manufacturer's field-adhesion hand-pull test criteria.
  - 4. Record test results in a field-adhesion-test log. Include dates when sealants were installed, names of persons who installed sealants, test dates, test locations, whether joints were primed, adhesion results and percent elongations, sealant material, sealant configuration, and sealant dimensions.
  - 5. Repair sealants pulled from test area by applying new sealants following same procedures used originally to seal joints. Ensure that original sealant surfaces are clean and that new sealant contacts original sealant.
- B. Evaluation of Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

#### 3.5 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 3.6 PROTECTION

A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

## 3.7 JOINT-SEALANT SCHEDULE

- A. Joint-Sealant Application: Exterior joints in horizontal traffic surfaces JS-1.
  - 1. Joint Locations:
    - a. Control and expansion joints in brick pavers.
    - b. Isolation and contraction joints in cast-in-place concrete slabs.
    - c. Joints between different materials listed above.
    - d. Other joints as indicated on Drawings.
  - 2. Polysulfide Joint Sealant: Multicomponent, nonsag, traffic grade.
  - 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- B. Joint-Sealant Application: Exterior joints in horizontal traffic surfaces subject to water immersion JS-2.
  - 1. Joint Locations pedestrian and vehicular paving
  - 2. Urethane Joint Sealant: Immersible, single component, pourable, traffic grade.
  - 3. Polysulfide Joint Sealant: Immersible, multicomponent, nonsag, traffic grade.
  - 4. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- C. Joint-Sealant Application: Exterior joints in vertical surfaces and horizontal nontraffic surfaces JS-3.
  - 1. Joint Locations:
    - a. Construction joints in cast-in-place concrete.
    - b. Joints between cast stone units.
    - c. Control and expansion joints in unit masonry.
    - d. Joints between metal panels.
    - e. Joints between different materials listed above.
    - f. Perimeter joints between materials listed above and frames of doors, windows, and
    - g. Control and expansion joints in ceilings and other overhead surfaces.
    - h. Other joints as indicated.
  - 2. Silicone Joint Sealant: Single component, nonsag, neutral curing, Class 100/50.
  - 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

- D. Joint-Sealant Application: Interior joints in horizontal traffic surfaces JS-4.
  - 1. Joint Locations:
    - a. Isolation joints in cast-in-place concrete slabs.
    - b. Other joints as indicated.
  - 2. Silicone Joint Sealant: Single component, nonsag, traffic grade, neutral curing.
  - 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

Issue Date: 06/05/2014

- E. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces JS-5.
  - 1. Joint Locations:
    - a. Control and expansion joints on exposed interior surfaces of exterior walls.
    - b. Perimeter joints of exterior openings where indicated.
    - c. Other joints as indicated.
  - 2. Silicone Joint Sealant: Single component, nonsag, neutral curing, Class 100/50.
  - 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- F. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces JS-6.
  - 1. Joint Locations:
    - a. Vertical joints on exposed surfaces of interior unit masonry and partitions.
    - b. Perimeter joints between interior wall surfaces and frames of interior doors, windows and elevator entrances.
    - c. Other joints as indicated.
  - 2. Joint Sealant: Latex.
  - 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- G. Joint-Sealant Application: Mildew-resistant interior joints in vertical surfaces and horizontal nontraffic surfaces **JS-7**.
  - 1. Joint Sealant Location:
    - a. Joints between plumbing fixtures and adjoining walls, floors, and counters.
    - b. Tile control and expansion joints where indicated.
    - c. Other joints as indicated.
  - 2. Joint Sealant: Single component, nonsag, mildew resistant, acid curing.
  - 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- H. Joint-Sealant Application: Interior acoustical joints in vertical surfaces and horizontal nontraffic surfaces JS-8.
  - 1. Joint Location:
    - a. Acoustical joints where indicated.
    - b. Other joints as indicated.
  - 2. Joint Sealant: Acoustical.
  - 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range.

END OF SECTION 079200

# SECTION 079500 - EXPANSION CONTROL

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Exterior Roof expansion control systems.
- B. Related Requirements:
  - 1. Section 079200 "Joint Sealants" for liquid-applied joint sealants and for elastomeric sealants without metal frames.

#### 1.3 ACTION SUBMITTALS

- A. Shop Drawings: For each expansion control system specified. Include plans, elevations, sections, details, splices, blockout requirement, attachments to other work, and line diagrams showing entire route of each expansion control system. Where expansion control systems change planes, provide isometric or clearly detailed drawing depicting how components interconnect.
- B. Samples: For each exposed expansion control system and for each color and texture specified, full width by 6 inches (150 mm) long in size.
- C. Samples for Initial Selection: For each type of expansion control system indicated.
  - 1. Include manufacturer's color charts showing the full range of colors and finishes available for each exposed metal and elastomeric seal material.
- D. Samples for Verification: For each type of expansion control system indicated, full width by 6 inches (150 mm) long in size.
- E. Product Schedule: Prepared by or under the supervision of the supplier. Include the following information in tabular form:
  - 1. Manufacturer and model number for each expansion control system.
  - 2. Expansion control system location cross-referenced to Drawings.
  - 3. Nominal joint width.
  - 4. Movement capability.
  - 5. Classification as thermal or seismic.
  - 6. Materials, colors, and finishes.

EXPANSION CONTROL 079500 - 1

- 7. Product options.
- 8. Fire-resistance ratings.

#### 1.4 INFORMATIONAL SUBMITTALS

Product Test Reports: For each fire barrier provided as part of an expansion control system, for A. tests performed by a qualified testing agency.

#### B. Qualification Data: For Installer.

- An entity that employs installers and supervisors who have been trained and approved by expansion joint manufacturer.
- 2. An entity that employs installers and supervisors who have been trained and approved SMACNA to fabricate and install field fabricated joints.

#### 1.5 WARRANTY

- Material and Workmanship: Two years for floor, ceiling, and wall joints. Twenty years A. included in the roofing warranty for roof expansion joints and connection to vertical exterior joints.
  - Roof Expansion Joint assembly and connection to vertical wall expansion joint shall be 1. included in the roof warranty.

#### PART 2 - PRODUCTS

#### 2.1 SYSTEM DESCRIPTION

- General: Provide expansion control systems of design, basic profile, materials, and operation A. indicated. Provide units with capability to accommodate variations in adjacent surfaces.
  - 1. Furnish units in longest practicable lengths to minimize field splicing. Install with hairline mitered corners where expansion control systems change direction or abut other materials.
  - Include factory-fabricated closure materials and transition pieces, T-joints, corners, curbs, 2. cross-connections, and other accessories as required to provide continuous expansion control systems.
- Coordination: Coordinate installation of exterior wall and soffit expansion control systems with B. roof expansion control systems to ensure that wall transitions are watertight. Roof expansion joint assemblies are specified elsewhere.

#### 2.2 PERFORMANCE REQUIREMENTS

Seismic Performance: Expansion control systems shall withstand the effects of earthquake A. motions determined according to ASCE/SEI 7.

Issue Date: 06/05/2014

Re-Bid Set Issue Date: 06/05/2014

1. The term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified and the system will be fully operational after the seismic event."

Architect's Project #: 12.130.09

2. Component Importance Factor is 1.0.

#### 2.3 ROOF EXPANSION ASSEMBLY

- A. <u>Manufacturers:</u> Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. Balco, Inc.
  - 2. <u>MM Systems Corporation</u>.
  - 3. <u>Tremco Incorporated.</u>
  - 4. <u>Watson Bowman Acme Corp.</u>
- B. Source Limitations: Obtain expansion control systems from single source from single manufacturer.
- C. Roof Expansion Joints
  - 1. Basis-of-Design Product: Provide fabricated expansion joint cover. Including the following conditions:
    - a. Roof-to-Wall (existing concrete beams): BRBA-1-2-SE by Balco Inc.
      - 1) Material: Aluminum: 4" wide flanges
        - a) ASTM B221, alloy 6063-T5 for extrusions.
        - b) ASTM B209, alloy 6061-T6 for plate.
        - c) ASTM B209, alloy 5052-H32 for sheet.
      - 2) Joint Material: EPDM Cover with Closed Cell Foam.
        - a) Moisture Barrier: Flexible elastomeric material, EPDM, minimum 45 mils thick.
        - b) Color: Black.
  - 2. Design Criteria:
    - a. Nominal Joint Width: 2"
    - b. Movement Capability: 50% min.
    - c. Type of Movement: Thermal and Seismic.

## 2.4 ACCESSORIES

- A. Moisture Barriers: Manufacturer's standard moisture barrier consisting of a continuous, waterproof membrane within joint and attached to substrate on sides of joint below the primary cover.
  - 1. Drain-Tube Assemblies: Equip moisture barrier with drain tubes and seals to direct collected moisture to drain to exterior-wall expansion control system.
- B. Insulation: Manufacturer's standard insulation maintaining continuous insulation at building envelope within joint and attached to substrate on sides of joint below the primary cover.

### 2.5 ACCESSORY MATERIALS

- A. Aluminum: ASTM B 221 (ASTM B 221M), Alloy 6063-T5 for extrusions; ASTM B 209 (ASTM B 209M), Alloy 6061-T6 for sheet and plate.
  - 1. Apply manufacturer's standard protective coating on aluminum surfaces to be placed in contact with cementitious materials.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. Accessories: Manufacturer's standard insulation, anchors, clips, fasteners, set screws, spacers, and other accessories compatible with material in contact, as indicated or required for complete installations.

#### 2.6 FABRICATION

- A. Fabricate expansion joint cover assemblies as detailed. Provide centering bars, sealing washers, gaskets, splice covers, and closures as necessary for complete installation.
  - 1. Fabricate special transitions and corner fittings as required.
  - 2. Miter and weld joint systems as applicable.
  - 3. Provide necessary and related parts, devices, water barrier (if specified), anchors, form clips and other items required for water-resistant installation.
  - 4. Provide corners, tees, transitions, curb risers, etc. assembled with connection mitered or interlocking and secured to ensure proper fit and alignment as applicable.
  - 5. Special conditions shall be shop fabricated to the fullest extent possible. Field fabricate joints only when necessary for proper fitting.
  - 6. Cover plates shall have a smooth exposed surface.
- B. Shop assemble components and package with anchors and fittings. Provide components in single lengths where possible; minimize site splicing.

### 2.7 GENERAL FINISH REQUIREMENTS

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

## 2.8 ALUMINUM FINISHES

- A. Mill finish.
  - 1. Provide "Black" painted finish on visible trim, field applied.

Issue Date: 06/05/2014

#### **PART 3 - EXECUTION**

#### 3.1 EXAMINATION

- A. Examine surfaces where expansion control systems will be installed for installation tolerances and other conditions affecting performance of work.
  - 1. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 PREPARATION

- A. Prepare substrates according to expansion control system manufacturer's written instructions.
- B. Coordinate and furnish anchorages, setting drawings, and instructions for installing expansion control systems. Provide fasteners of metal, type, and size to suit type of construction indicated and to provide for secure attachment of expansion control systems.
- C. Cast-In Frames: Coordinate and furnish frames to be cast into concrete.

### 3.3 INSTALLATION

- A. Comply with manufacturer's written instructions for storing, handling, and installing expansion control systems and materials unless more stringent requirements are indicated.
- B. Metal Frames: Perform cutting, drilling, and fitting required to install expansion control systems.
  - 1. Install in true alignment and proper relationship to joints and adjoining finished surfaces measured from established lines and levels.
  - 2. Adjust for differences between actual structural gap and nominal design gap due to ambient temperature at time of installation. Notify Architect where discrepancies occur that will affect proper expansion control system installation and performance.
  - 3. Cut and fit ends to accommodate thermal expansion and contraction of metal without buckling of frames.
  - 4. Repair or grout blockout as required for continuous frame support using nonmetallic, shrinkage-resistant grout.
  - 5. Install frames in continuous contact with adjacent surfaces.
    - a. Shimming is not permitted.
    - b. Seal to adjacent wall construction
    - c. Seal to adjacent roof construction, coordinate with roofing installer to provide a waterproof joint.
  - 6. Locate anchors at interval recommended by manufacturer, but not less than 3 inches (75 mm) from each end and not more than 24 inches (600 mm) o.c.

- Re-Bid Set

  Issue Date: 06/05/2014
  - C. Seals in Metal Frames: Install elastomeric seals and membranes in frames to comply with manufacturer's written instructions. Install with minimum number of end joints.
    - 1. Provide in continuous lengths for straight sections.
    - 2. Seal transitions according to manufacturer's written instructions. Vulcanize or heat-weld field-spliced joints as recommended by manufacturer.

- 3. Installation: Mechanically lock seals into frames or adhere to frames with adhesive or pressure-sensitive tape as recommended by manufacturer.
- D. Terminate exposed ends of expansion control systems with field- or factory-fabricated termination devices.
- E. Moisture Barrier: Provide at all exterior joints and where indicated on Drawings.

#### 3.4 PROTECTION

- A. Do not remove protective covering until finish work in adjacent areas is complete. When protective covering is removed, clean exposed metal surfaces to comply with manufacturer's written instructions.
- B. Protect the installation from damage by work of other Sections. Where necessary due to heavy construction traffic, remove and properly store cover plates or seals and install temporary protection over expansion control systems. Reinstall cover plates or seals prior to Substantial Completion of the Work.

END OF SECTION 079500

### SECTION 081113 - HOLLOW METAL DOORS AND FRAMES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 1.2 SUMMARY

- A. Section includes hollow-metal work.
- B. Related Requirements:
  - 1. Section 087100 "Door Hardware" for door hardware for hollow-metal doors.

#### 1.3 DEFINITIONS

A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or SDI A250.8.

### 1.4 COORDINATION

A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.

### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, core descriptions, fire-resistance ratings, temperature-rise ratings, and finishes.
- B. Shop Drawings: Include the following:
  - 1. Elevations of each door type.
  - 2. Details of doors, including vertical- and horizontal-edge details and metal thicknesses.
  - 3. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
  - 4. Locations of reinforcement and preparations for hardware.
  - 5. Details of each different wall opening condition.
  - 6. Details of anchorages, joints, field splices, and connections.
  - 7. Details of accessories.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

C. Schedule: Provide a schedule of hollow-metal work prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final Door Hardware Schedule.

#### 1.6 INFORMATIONAL SUBMITTALS

A. Product Test Reports: For each type of hollow-metal door and frame assembly, for tests performed by a qualified testing agency.

#### 1.7 DELIVERY, STORAGE, AND HANDLING

- Deliver hollow-metal work palletized, packaged, or crated to provide protection during transit A. and Project-site storage. Do not use nonvented plastic.
  - 1. Provide additional protection to prevent damage to factory-finished units.
- B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.
- C. Store hollow-metal work vertically under cover at Project site with head up. Place on minimum 4-inch- (102-mm-) high wood blocking. Provide minimum 1/4-inch (6-mm) space between each stacked door to permit air circulation.

#### PART 2 - PRODUCTS

#### 2.1 **MANUFACTURERS**

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - Ceco Door Products; an Assa Abloy Group company. 1.
  - 2. Curries Company; an Assa Abloy Group company.
  - Custom Metal Products. 3.
  - Mesker Door Inc. 4.
  - National Custom Hollow Metal. 5.
  - Republic Doors and Frames. 6.
  - Steelcraft; an Ingersoll-Rand company. 7.
- Source Limitations: Obtain hollow-metal work from single source from single manufacturer. B.

#### 2.2 **INTERIOR FRAMES**

- A. Construct interior frames to comply with the standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.
- B. Commercial Frames: NAAMM-HMMA 861...

Issue Date: 06/05/2014

- 1. Physical Performance: Level A according to SDI A250.4.
- 2. Frames:
  - a. Materials: Uncoated steel sheet, minimum thickness of 0.053 inch (1.3 mm).
  - b. Construction: Full profile welded.
- 3. Exposed Finish: Prime.

#### 2.3 EXTERIOR HOLLOW-METAL DOORS AND FRAMES

- A. Construct exterior doors and frames to comply with the standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.
- B. Commercial Doors and Frames: NAAMM-HMMA 861..
  - 1. Physical Performance: Level A according to SDI A250.4.
  - 2. Doors:
    - a. Type: As indicated in the Door and Frame Schedule.
    - b. Thickness: 1-3/4 inches (44.5 mm.)
    - c. Face: Metallic-coated steel sheet, minimum thickness of 0.053 inch (1.30 mm), with minimum G60 (Z180 or)A60 (ZF180) coating.
    - d. Edge Construction: Continuously welded with no visible seam.
    - e. Core: Steel stiffened.
      - 1) Thermal-Rated Doors: Provide doors fabricated with thermal-resistance value (R-value) of not less than 2.1 deg F x h x sq. ft./Btu (0.370 K x sq. m/W) when tested according to ASTM C 1363.
  - 3. Frames:
    - a. Materials: Metallic-coated steel sheet, minimum thickness of 0.067 inch (1.7 mm), with minimum G60 (Z180 or)A60 (ZF180) coating.
    - b. Construction: Full profile welded.
  - 4. Exposed Finish: Prime.

#### 2.4 FRAME ANCHORS

- A. Jamb Anchors:
  - 1. Masonry Type: Adjustable strap-and-stirrup or T-shaped anchors to suit frame size, not less than 0.042 inch (1.0 mm) thick, with corrugated or perforated straps not less than 2 inches (51 mm) wide by 10 inches (254 mm) long; or wire anchors not less than 0.177 inch (4.5 mm) thick.

Issue Date: 06/05/2014

- 2. Postinstalled Expansion Type for In-Place Concrete or Masonry: Minimum 3/8-inch-(9.5-mm-) diameter bolts with expansion shields or inserts. Provide pipe spacer from frame to wall, with throat reinforcement plate, welded to frame at each anchor location.
- B. Floor Anchors: Formed from same material as frames, minimum thickness of 0.042 inch (1.0 mm), and as follows:
  - 1. Monolithic Concrete Slabs: Clip-type anchors, with two holes to receive fasteners.

#### 2.5 MATERIALS

- A. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B; suitable for exposed applications.
- B. Hot-Rolled Steel Sheet: ASTM A 1011/A 1011M, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.
- C. Metallic-Coated Steel Sheet: ASTM A 653/A 653M, Commercial Steel (CS), Type B.
- D. Frame Anchors: ASTM A 879/A 879M, Commercial Steel (CS), 04Z (12G) coating designation; mill phosphatized.
  - For anchors built into exterior walls, steel sheet complying with ASTM A 1008/A 1008M or ASTM A 1011/A 1011M, hot-dip galvanized according to ASTM A 153/A 153M, Class B.
- E. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A 153/A 153M.
- F. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow-metal frames of type indicated.
- G. Grout: ASTM C 476, except with a maximum slump of 4 inches (102 mm), as measured according to ASTM C 143/C 143M.
- H. Mineral-Fiber Insulation: ASTM C 665, Type I (blankets without membrane facing); consisting of fibers manufactured from slag or rock wool; with maximum flame-spread and smokedeveloped indexes of 25 and 50, respectively; passing ASTM E 136 for combustion characteristics.
- I. Glazing: Comply with requirements in Section 088000 "Glazing."
- J. Bituminous Coating: Cold-applied asphalt mastic, compounded for 15-mil (0.4-mm) dry film thickness per coat. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

#### 2.6 FABRICATION

A. Fabricate hollow-metal work to be rigid and free of defects, warp, or buckle. Accurately form metal to required sizes and profiles, with minimum radius for metal thickness. Where practical, fit and assemble units in manufacturer's plant. To ensure proper assembly at Project site, clearly identify work that cannot be permanently factory assembled before shipment.

#### B. Hollow-Metal Doors:

- 1. Steel-Stiffened Door Cores: Provide minimum thickness 0.026 inch (0.66 mm), steel vertical stiffeners of same material as face sheets extending full-door height, with vertical webs spaced not more than 6 inches (152 mm) apart. Spot weld to face sheets no more than 5 inches (127 mm) o.c. Fill spaces between stiffeners with glass- or mineral-fiber insulation.
- 2. Fire Door Cores: As required to provide fire-protection and temperature-rise ratings indicated.
- 3. Vertical Edges for Single-Acting Doors: Bevel edges 1/8 inch in 2 inches (3.2 mm in 51 mm).
- 4. Top Edge Closures: Close top edges of doors with inverted closures, except provide flush closures at exterior doors of same material as face sheets.
- 5. Bottom Edge Closures: Close bottom edges of doors where required for attachment of weather stripping with end closures or channels of same material as face sheets.
- 6. Exterior Doors: Provide weep-hole openings in bottoms of exterior doors to permit moisture to escape. Seal joints in top edges of doors against water penetration.
- C. Hollow-Metal Frames: Where frames are fabricated in sections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of same thickness metal as frames.
  - 1. Sidelight and Transom Bar Frames: Provide closed tubular members with no visible face seams or joints, fabricated from same material as door frame. Fasten members at crossings and to jambs by butt welding.
  - 2. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
  - 3. Grout Guards: Weld guards to frame at back of hardware mortises in frames to be grouted.
  - 4. Floor Anchors: Weld anchors to bottoms of jambs with at least four spot welds per anchor; however, for slip-on drywall frames, provide anchor clips or countersunk holes at bottoms of jambs.
  - 5. Jamb Anchors: Provide number and spacing of anchors as follows:
    - a. Masonry Type: Locate anchors not more than 16 inches (406 mm) from top and bottom of frame. Space anchors not more than 32 inches (813 mm) o.c., to match coursing, and as follows:
      - 1) Two anchors per jamb up to 60 inches (1524 mm) high.
      - 2) Three anchors per jamb from 60 to 90 inches (1524 to 2286 mm) high.
      - 3) Four anchors per jamb from 90 to 120 inches (2286 to 3048 mm) high.
      - 4) Four anchors per jamb plus one additional anchor per jamb for each 24 inches (610 mm) or fraction thereof above 120 inches (3048 mm) high.

b. Postinstalled Expansion Type: Locate anchors not more than 6 inches (152 mm) from top and bottom of frame. Space anchors not more than 26 inches (660 mm)

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

o.c.

- 6. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers as follows. Keep holes clear during construction.
  - a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
  - b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.
- D. Fabricate concealed stiffeners and edge channels from either cold- or hot-rolled steel sheet.
- E. Hardware Preparation: Factory prepare hollow-metal work to receive templated mortised hardware; include cutouts, reinforcement, mortising, drilling, and tapping according to SDI A250.6, the Door Hardware Schedule, and templates.
  - 1. Reinforce doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.
  - 2. Comply with applicable requirements in SDI A250.6 and BHMA A156.115 for preparation of hollow-metal work for hardware.
- F. Stops and Moldings: Provide stops and moldings around glazed lites and louvers where indicated. Form corners of stops and moldings with mitered hairline joints.
  - 1. Single Glazed Lites: Provide fixed stops and moldings welded on secure side of hollow-metal work.
  - 2. Provide fixed frame moldings on outside of exterior and on secure side of interior doors and frames.
  - 3. Provide loose stops and moldings on inside of hollow-metal work.
  - 4. Coordinate rabbet width between fixed and removable stops with glazing and installation types indicated.

#### 2.7 STEEL FINISHES

- A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.
  - 1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

#### 2.8 ACCESSORIES

A. Grout Guards: Formed from same material as frames, not less than 0.016 inch (0.4 mm) thick.

## PART 3 - EXECUTION

## 3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Examine roughing-in for embedded and built-in anchors to verify actual locations before frame installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

## 3.2 PREPARATION

- A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces.
- B. Drill and tap doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.

#### 3.3 INSTALLATION

- A. General: Install hollow-metal work plumb, rigid, properly aligned, and securely fastened in place. Comply with Drawings and manufacturer's written instructions.
- B. Hollow-Metal Frames: Install hollow-metal frames of size and profile indicated. Comply with SDI A250.11 or NAAMM-HMMA 840 as required by standards specified.
  - 1. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces, leaving surfaces smooth and undamaged.
    - a. Where frames are fabricated in sections because of shipping or handling limitations, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces.
    - b. Install frames with removable stops located on secure side of opening.
    - c. Install door silencers in frames before grouting.
    - d. Remove temporary braces necessary for installation only after frames have been properly set and secured.
    - e. Check plumb, square, and twist of frames as walls are constructed. Shim as necessary to comply with installation tolerances.
    - f. Field apply bituminous coating to backs of frames that will be filled with grout containing antifreezing agents.
  - 2. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor, and secure with postinstalled expansion anchors.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- a. Floor anchors may be set with power-actuated fasteners instead of postinstalled expansion anchors if so indicated and approved on Shop Drawings.
- 3. Masonry Walls: Coordinate installation of frames to allow for solidly filling space between frames and masonry with grout.
- 4. Installation Tolerances: Adjust hollow-metal door frames for squareness, alignment, twist, and plumb to the following tolerances:
  - a. Squareness: Plus or minus 1/16 inch (1.6 mm), measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
  - b. Alignment: Plus or minus 1/16 inch (1.6 mm), measured at jambs on a horizontal line parallel to plane of wall.
  - c. Twist: Plus or minus 1/16 inch (1.6 mm), measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
  - d. Plumbness: Plus or minus 1/16 inch (1.6 mm), measured at jambs at floor.
- C. Hollow-Metal Doors: Fit hollow-metal doors accurately in frames, within clearances specified below. Shim as necessary.
  - 1. Non-Fire-Rated Steel Doors:
    - a. Between Door and Frame Jambs and Head: 1/8 inch (3.2 mm) plus or minus 1/32 inch (0.8 mm).
    - b. Between Edges of Pairs of Doors: 1/8 inch (3.2 mm) to 1/4 inch (6.3 mm) plus or minus 1/32 inch (0.8 mm).
    - c. At Bottom of Door: 5/8 inch (15.8 mm) plus or minus 1/32 inch (0.8 mm).
    - d. Between Door Face and Stop: 1/16 inch (1.6 mm) to 1/8 inch (3.2 mm) plus or minus 1/32 inch (0.8 mm).

#### 3.4 ADJUSTING AND CLEANING

- A. Final Adjustments: Check and readjust operating hardware items immediately before final inspection. Leave work in complete and proper operating condition. Remove and replace defective work, including hollow-metal work that is warped, bowed, or otherwise unacceptable.
- B. Remove grout and other bonding material from hollow-metal work immediately after installation.
- C. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.
- D. Metallic-Coated Surface Touchup: Clean abraded areas and repair with galvanizing repair paint according to manufacturer's written instructions.
- E. Touchup Painting: Cleaning and touchup painting of abraded areas of paint are specified in painting Sections.

END OF SECTION 081113

## SECTION 081416 - FLUSH WOOD DOORS

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Solid-core doors with wood-veneer faces.
  - 2. Factory finishing flush wood doors.
  - 3. Factory fitting flush wood doors to frames and factory machining for hardware.
- B. Related Requirements:
  - 1. Section 088000 "Glazing" for glass view panels in flush wood doors.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of door. Include details of core and edge construction, louvers, and trim for openings. Include factory-finishing specifications.
- B. Shop Drawings: Indicate location, size, and hand of each door; elevation of each kind of door; construction details not covered in Product Data; and the following:
  - 1. Dimensions and locations of blocking.
  - 2. Dimensions and locations of mortises and holes for hardware.
  - 3. Dimensions and locations of cutouts.
  - 4. Undercuts.
  - 5. Requirements for veneer matching.
  - 6. Doors to be factory finished and finish requirements.
  - 7. Fire-protection ratings for fire-rated doors.
- C. Samples for Initial Selection: For factory-finished doors.
- D. Samples for Verification:
  - 1. Factory finishes applied to actual door face materials, approximately 8 by 10 inches (200 by 250 mm), for each material and finish. For each wood species and transparent finish, provide set of three Samples showing typical range of color and grain to be expected in finished Work.

FLUSH WOOD DOORS 081416-1

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Sample Warranty: For special warranty.
- B. Quality Standard Compliance Certificates: AWI Quality Certification Program certificates.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 1.5 DELIVERY, STORAGE, AND HANDLING

- A. Comply with requirements of referenced standard and manufacturer's written instructions.
- B. Package doors individually in plastic bags or cardboard cartons.
- C. Mark each door on top and bottom rail with opening number used on Shop Drawings.

#### 1.6 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install doors until spaces are enclosed and weathertight, wet work in spaces is complete and dry, and HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during remainder of construction period.

#### 1.7 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace doors that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Warping (bow, cup, or twist) more than 1/4 inch (6.4 mm) in a 42-by-84-inch (1067-by-2134-mm) section.
    - b. Telegraphing of core construction in face veneers exceeding 0.01 inch in a 3-inch (0.25 mm in a 76.2-mm) span.
  - 2. Warranty shall also include installation and finishing that may be required due to repair or replacement of defective doors.
  - 3. Warranty Period for Solid-Core Interior Doors: Life of installation.

### PART 2 - PRODUCTS

## 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by the following:
  - 1. Algoma Hardwoods, Inc.
  - 2. <u>Eggers Industries</u>.
  - 3. Graham Wood Doors; an Assa Abloy Group company.

FLUSH WOOD DOORS 081416-2

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 4. Marshfield Door Systems, Inc.
- Mohawk Doors; a Masonite company. 5.
- Oshkosh Door Company. 6.
- VT Industries, Inc. 7.

#### 2.2 FLUSH WOOD DOORS, GENERAL

- Quality Standard: In addition to requirements specified, comply with AWI's, AWMAC's, and A. WI's "Architectural Woodwork Standards or WDMA I.S.1-A. "Architectural Wood Flush Doors."
  - 1. Contract Documents contain selections chosen from options in quality standard and additional requirements beyond those of quality standard. Comply with those selections and requirements in addition to quality standard.
- B. WDMA I.S.1-A Performance Grade: Extra Heavy Duty.
- **C**. Particleboard-Core Doors:
  - 1. Particleboard: ANSI A208.1, Grade LD-2.
  - 2. Provide doors with structural-composite-lumber cores instead of particleboard cores for doors indicated to receive exit devices.
  - Edge Construction: At hinge stiles, provide laminated-edge construction with improved 3. screw-holding capability and split resistance. Comply with specified requirements for exposed edges.
    - Screw-Holding Capability: 550 lbf (2440 N) per WDMA T.M.-10. a.

#### 2.3 VENEER-FACED DOORS FOR TRANSPARENT FINISH

- A. **Interior Solid-Core Doors** 
  - 1. Grade: Premium, with Grade AA faces.
  - Species: Select white maple. 2.
  - Cut: Plain sliced (flat sliced). 3.
  - Match between Veneer Leaves: Slip match. 4.
  - Assembly of Veneer Leaves on Door Faces: Running match.
  - Pair and Set Match: Provide for doors hung in same opening or separated only by 6. mullions.
  - 7. Room Match: Provide door faces of compatible color and grain within each separate room or area of building.
  - Exposed Vertical Edges: Same species as faces or a compatible species edge Type A. 8.
  - Core: Particleboard.
  - Construction: Five plies. Stiles and rails are bonded to core, then entire unit is abrasive 10. planed before veneering.
  - WDMA I.S.1-A Performance Grade: Extra Heavy Duty. 11.

FLUSH WOOD DOORS 081416-3

### 2.4 FABRICATION

A. Factory fit doors to suit frame-opening sizes indicated. Comply with clearance requirements of referenced quality standard for fitting unless otherwise indicated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Factory machine doors for hardware that is not surface applied. Locate hardware to comply with DHI-WDHS-3. Comply with final hardware schedules, door frame Shop Drawings, BHMA-156.115-W, and hardware templates.
  - 1. Coordinate with hardware mortises in metal frames to verify dimensions and alignment before factory machining.

#### 2.5 FACTORY FINISHING

- A. General: Comply with referenced quality standard for factory finishing. Complete fabrication, including fitting doors for openings and machining for hardware that is not surface applied, before finishing.
  - 1. Finish faces, all four edges, edges of cutouts, and mortises. Stains and fillers may be omitted on top and bottom edges, edges of cutouts, and mortises.
- B. Factory finish doors.
- C. Transparent Finish:
  - 1. Grade: Premium.
  - 2. Finish: AWI's, AWMAC's, and WI's "Architectural Woodwork Standards" System 11, catalyzed polyurethane.
  - 3. Finish: WDMA TR-6 catalyzed polyurethane.
  - 4. Staining: Match Plastic Laminate 7923-07, Versailles Anigre by Wilsonart.
  - 5. Sheen: Satin.

#### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine doors and installed door frames, with Installer present, before hanging doors.
  - 1. Verify that installed frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
  - 2. Reject doors with defects.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

A. Hardware: For installation, see Section 087100 "Door Hardware."

FLUSH WOOD DOORS 081416-4

Issue Date: 06/05/2014

- B. Installation Instructions: Install doors to comply with manufacturer's written instructions and referenced quality standard, and as indicated.
- Factory-Fitted Doors: Align in frames for uniform clearance at each edge. C.
- D. Factory-Finished Doors: Restore finish before installation if fitting or machining is required at Project site.

#### 3.3 **ADJUSTING**

- A. Operation: Rehang or replace doors that do not swing or operate freely.
- B. Finished Doors: Replace doors that are damaged or that do not comply with requirements. Doors may be repaired or refinished if Work complies with requirements and shows no evidence of repair or refinishing.

END OF SECTION 081416

FLUSH WOOD DOORS 081416-5

## SECTION 084113 - ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Exterior storefront framing.
  - 2. Storefront framing for punched openings.
  - 3. Exterior manual-swing entrance doors and door-frame units.
- B. Related Requirements:
  - 1. Section 088000 "Glazing" for aluminum-framed entrances and storefront glazing.
  - 2. Section 087100 "Door Hardware" for door hardware at entrances.

## 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
- B. Shop Drawings: For aluminum-framed entrances and storefronts. Include plans, elevations, sections, full-size details, and attachments to other work.
  - 1. Include details of provisions for assembly expansion and contraction and for draining moisture occurring within the assembly to the exterior.
  - 2. Include full-size isometric details of each vertical-to-horizontal intersection of aluminum-framed entrances and storefronts, showing the following:
    - a. Joinery, including concealed welds.
    - b. Anchorage.
    - c. Expansion provisions.
    - d. Glazing.
    - e. Flashing and drainage.
  - 3. Show connection to and continuity with adjacent thermal, weather, air, and vapor barriers.
- C. Samples for Initial Selection: For units with factory-applied color finishes.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- D. Samples for Verification: For each type of exposed finish required, in manufacturer's standard sizes.
- E. Fabrication Sample: Of each vertical-to-horizontal intersection of assemblies, made from 12-inch (300-mm) lengths of full-size components and showing details of the following:
  - 1. Joinery, including concealed welds.
  - 2. Anchorage.
  - 3. Expansion provisions.
  - 4. Glazing.
  - 5. Flashing and drainage.
- F. Entrance Door Hardware Schedule: Prepared by or under supervision of supplier, detailing fabrication and assembly of entrance door hardware, as well as procedures and diagrams. Coordinate final entrance door hardware schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of entrance door hardware.
- G. Delegated-Design Submittal: For aluminum-framed entrances and storefronts indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Energy Performance Certificates: For aluminum-framed entrances and storefronts, accessories, and components, from manufacturer.
  - 1. Basis for Certification: NFRC-certified energy performance values for each aluminum-framed entrance and storefront.
- C. Sample Warranties: For special warranties.

#### 1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For aluminum-framed entrances and storefronts to include in maintenance manuals.

## 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.
- B. Product Options: Information on Drawings and in Specifications establishes requirements for aesthetic effects and performance characteristics of assemblies. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction.

Re-Bid Set Issue Date: 06/05/2014

1. Do not change intended aesthetic effects, as judged solely by Architect, except with Architect's approval. If changes are proposed, submit comprehensive explanatory data to Architect for review.

Architect's Project #: 12.130.09

#### 1.7 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of aluminum-framed entrances and storefronts that do not comply with requirements or that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Structural failures including, but not limited to, excessive deflection.
    - b. Noise or vibration created by wind and thermal and structural movements.
    - c. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
    - d. Water penetration through fixed glazing and framing areas.
    - e. Failure of operating components.
  - 2. Warranty Period: Five years from date of Substantial Completion.

#### PART 2 - PRODUCTS

## 2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design aluminum-framed entrances and storefronts.
- B. General Performance: Comply with performance requirements specified, as determined by testing of aluminum-framed entrances and storefronts representing those indicated for this Project without failure due to defective manufacture, fabrication, installation, or other defects in construction.
  - 1. Aluminum-framed entrances and storefronts shall withstand movements of supporting structure including, but not limited to, story drift, twist, column shortening, long-term creep, and deflection from uniformly distributed and concentrated live loads.
  - 2. Failure also includes the following:
    - a. Thermal stresses transferring to building structure.
    - b. Glass breakage.
    - c. Noise or vibration created by wind and thermal and structural movements.
    - d. Loosening or weakening of fasteners, attachments, and other components.
    - e. Failure of operating units.

#### C. Structural Loads:

- 1. Wind Loads: As indicated on Drawings.
- 2. Other Design Loads: As indicated on Drawings.

### D. Deflection of Framing Members: At design wind pressure, as follows:

1. Deflection Normal to Wall Plane: Limited to edge of glass in a direction perpendicular to glass plane not exceeding 1/175 of the glass edge length for each individual glazing lite or an amount that restricts edge deflection of individual glazing lites to 3/4 inch (19.1 mm), whichever is less.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Deflection Parallel to Glazing Plane: Limited to 1/360 of clear span or 1/8 inch (3.2 mm), whichever is smaller.
  - a. Operable Units: Provide a minimum 1/16-inch (1.6-mm) clearance between framing members and operable units.
- 3. Cantilever Deflection: Where framing members overhang an anchor point, as follows:
  - a. Perpendicular to Plane of Wall: No greater than 1/240 of clear span plus 1/4 inch (6.35 mm) for spans greater than 11 feet 8-1/4 inches (3.6 m) or 1/175 times span, for spans less than 11 feet 8-1/4 inches (3.6 m).

## E. Structural: Test according to ASTM E 330 as follows:

- 1. When tested at positive and negative wind-load design pressures, assemblies do not evidence deflection exceeding specified limits.
- 2. When tested at 150 percent of positive and negative wind-load design pressures, assemblies, including anchorage, do not evidence material failures, structural distress, or permanent deformation of main framing members exceeding 0.2 percent of span.
- F. Air Infiltration: Test according to ASTM E 283 for infiltration as follows:
  - 1. Fixed Framing and Glass Area:
    - a. Maximum air leakage of 0.06 cfm/sq. ft. (0.30 L/s per sq. m) at a static-air-pressure differential of.
  - 2. Entrance Doors:
    - a. Pair of Doors: Maximum air leakage of 1.0 cfm/sq. ft. (5.08 L/s per sq. m) at a static-air-pressure differential of 1.57 lbf/sq. ft. (75 Pa).
    - b. Single Doors: Maximum air leakage of 0.5 cfm/sq. ft. (2.54 L/s per sq. m) at a static-air-pressure differential of 1.57 lbf/sq. ft. (75 Pa).
- G. Water Penetration under Static Pressure: Test according to ASTM E 331 as follows:
  - 1. No evidence of water penetration through fixed glazing and framing areas when tested according to a minimum static-air-pressure differential of 20 percent of positive wind-load design pressure, but not less than 6.24 lbf/sq. ft. (300 Pa).
- H. Water Penetration under Dynamic Pressure: Test according to AAMA 501.1 as follows:
  - 1. No evidence of water penetration through fixed glazing and framing areas when tested at dynamic pressure equal to 20 percent of positive wind-load design pressure, but not less than 6.24 lbf/sq. ft. (300 Pa).
- I. Seismic Performance: Aluminum-framed entrances and storefronts shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

1. Seismic Drift Causing Glass Fallout: Complying with criteria for passing based on building occupancy type when tested according to AAMA 501.6 at design displacement and 1.5 times the design displacement.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- J. Energy Performance: Certify and label energy performance according to NFRC as follows:
  - 1. Thermal Transmittance (U-factor): Fixed glazing and framing areas shall have U-factor of not more than 0.45 Btu/sq. ft. x h x deg F (2.55 W/sq. m x K) as determined according to NFRC 100.
  - 2. Condensation Resistance: Fixed glazing and framing areas shall have an NFRC-certified condensation resistance rating of no less than 15 as determined according to NFRC 500.
- K. Thermal Movements: Allow for thermal movements resulting from ambient and surface temperature changes:
  - 1. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.
  - 2. Thermal Cycling: No buckling; stress on glass; sealant failure; excess stress on framing, anchors, and fasteners; or reduction of performance when tested according to AAMA 501.5.
    - a. High Exterior Ambient-Air Temperature: That which produces an exterior metal-surface temperature of 180 deg F (82 deg C).
    - b. Low Exterior Ambient-Air Temperature: 0 deg F (minus 18 deg C).
    - c. Interior Ambient-Air Temperature: 75 deg F (24 deg C).

### 2.2 MANUFACTURERS

- A. <u>Manufacturers:</u> Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. EFCO Corporation.
  - 2. Kawneer North America; an Alcoa company.
  - 3. TRACO.
  - 4. YKK AP America Inc.
- B. Basis of Design: Subject to the compliance requirements, provide 2" x 4 1/2" storefront system.
  - 1. YES45TU storefront by YKK AP America, Inc.
- C. Source Limitations: Obtain all components of aluminum-framed entrance and storefront system, including framing, entrance doors, and accessories from single manufacturer.

### 2.3 FRAMING

- A. Framing Members: Manufacturer's extruded- or formed-aluminum framing members of thickness required and reinforced as required to support imposed loads.
  - 1. Construction: Thermally broken.
  - 2. Glazing System: Retained mechanically with gaskets on four sides.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 3. Glazing Plane: Center set.
- 4. Finish: Clear anodic finish.
- 5. Fabrication Method: Field-fabricated stick system.
- B. Backer Plates: Manufacturer's standard, continuous backer plates for framing members, if not integral, where framing abuts adjacent construction.
- C. Brackets and Reinforcements: Manufacturer's standard high-strength aluminum with nonstaining, nonferrous shims for aligning system components.

### D. Materials:

- 1. Aluminum: Alloy and temper recommended by manufacturer for type of use and finish indicated.
  - a. Sheet and Plate: ASTM B 209 (ASTM B 209M).
  - b. Extruded Bars, Rods, Profiles, and Tubes: ASTM B 221 (ASTM B 221M).
  - c. Extruded Structural Pipe and Tubes: ASTM B 429/B 429M.
  - d. Structural Profiles: ASTM B 308/B 308M.
- 2. Steel Reinforcement: Manufacturer's standard zinc-rich, corrosion-resistant primer complying with SSPC-PS Guide No. 12.00; applied immediately after surface preparation and pretreatment. Select surface preparation methods according to recommendations in SSPC-SP COM, and prepare surfaces according to applicable SSPC standard.
  - a. Structural Shapes, Plates, and Bars: ASTM A 36/A 36M.
  - b. Cold-Rolled Sheet and Strip: ASTM A 1008/A 1008M.
  - c. Hot-Rolled Sheet and Strip: ASTM A 1011/A 1011M.

### 2.4 ENTRANCE DOOR SYSTEMS

- A. Entrance Doors: Manufacturer's standard glazed entrance doors for manual-swing operation.
  - 1. Door Construction: 1-3/4-inch (44.5-mm) overall thickness, with minimum 0.125-inch-(3.2-mm-) thick, extruded-aluminum tubular rail and stile members. Mechanically fasten corners with reinforcing brackets that are deeply penetrated and fillet welded or that incorporate concealed tie rods.
  - 2. Door Design: Wide stile; 5-inch (88.9-mm) nominal width with 10" bottom rail.
  - 3. Glazing Stops and Gaskets: Square, snap-on, extruded-aluminum stops and preformed gaskets.
    - a. Basis of Design: 50D Entrance Doors by YKK AP America, Inc.
    - b. Provide non-removable glazing stops on outside of door.

#### 2.5 ENTRANCE DOOR HARDWARE

A. Entrance Door Hardware: Provide balance of Hardware not specified in this Section as specified in Section 087100 "Door Hardware".

- B. General: Provide entrance door hardware for each entrance door to comply with requirements in this Section.
  - 1. Entrance Door Hardware Sets: Provide quantity, item, size, finish or color indicated, and products complying with BHMA standard referenced.
  - 2. Sequence of Operation: Provide electrified door hardware function, sequence of operation, and interface with other building control systems indicated.
  - 3. Opening-Force Requirements:
    - a. Egress Doors: Not more than 15 lbf (67 N) to release the latch and not more than 30 lbf (133 N)to set the door in motion and not more than 15 lbf (67 N) to open the door to its minimum required width.

Issue Date: 06/05/2014

- b. Accessible Interior Doors: Not more than 5 lbf (22.2 N) to fully open door.
- C. Designations: Requirements for design, grade, function, finish, size, and other distinctive qualities of each type of entrance door hardware are indicated in "Entrance Door Hardware Sets" Article. Products are identified by using entrance door hardware designations as follows:
  - 1. Named Manufacturers' Products: Manufacturer and product designation are listed for each door hardware type required for the purpose of establishing minimum requirements.

    Manufacturers' names are abbreviated in "Entrance Door Hardware Sets" Article.
  - 2. References to BHMA Standards: Provide products complying with these standards and requirements for description, quality, and function.
- D. Continuous-Gear Hinges: Manufacturer's standard with stainless-steel bearings between knuckles, fabricated to full height of door and frame.
- E. Panic Exit Devices: BHMA A156.3, Grade 1, listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for panic protection, based on testing according to UL 305, refer to Section 087100 "Door Hardware".
- F. Cylinders: At all aluminum entrance doors.
  - 1. Keying: Master key system. Permanently inscribe each key with a visual key control number and include notation "DO NOT DUPLICATE" to be furnished by Owner.
    - a. Coordinate with the Owner so that keying is on the existing facility master key system.
- G. Strikes: Provide strike with black-plastic dust box for each latch or lock bolt; fabricated for aluminum framing.
- H. Operating Trim: BHMA A156.6.
  - 1. Provide 48" high vertical pulls on the exterior of each aluminum entrance door.
- I. Closers: BHMA A156.4, Grade 1, with accessories required for a complete installation, sized as required by door size, exposure to weather, and anticipated frequency of use; adjustable to comply with field conditions and requirements for opening force.
- J. Weather Stripping: Manufacturer's standard replaceable components.
  - 1. Compression Type: Made of ASTM D 2000, molded neoprene, or ASTM D 2287, molded PVC.
  - 2. Sliding Type: AAMA 701/702, made of wool, polypropylene, or nylon woven pile with nylon-fabric or aluminum-strip backing.

Pennis Complex Addition

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- K. Weather Sweeps: Manufacturer's standard exterior-door bottom sweep with concealed fasteners on mounting strip.
- L. Silencers: BHMA A156.16, Grade 1.
- M. Thresholds: BHMA A156.21, raised thresholds beveled with a slope of not more than 1:2, with maximum height of 1/2 inch (12.7 mm).
- N. Finger Guards: Manufacturer's standard collapsible neoprene or PVC gasket anchored to frame hinge-jamb at center-pivoted doors.

## 2.6 GLAZING

- A. Glazing: Comply with Section 088000 "Glazing."
- B. Glazing Gaskets: Manufacturer's standard sealed-corner pressure-glazing system of black, resilient elastomeric glazing gaskets, setting blocks, and shims or spacers.
- C. Glazing Sealants: Comply with Section 088000 "Glazing."
- D. Sealants used inside the weatherproofing system shall have a VOC content of 250 g/L.
- E. Sealants used inside the weatherproofing system shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- F. Weatherseal Sealants: ASTM C 920 for Type S; Grade NS; Class 25; Uses NT, G, A, and O; chemically curing silicone formulation that is compatible with structural sealant and other system components with which it comes in contact; recommended by structural-sealant, weatherseal-sealant, and structural-sealant-glazed storefront manufacturers for this use.
  - 1. Color: As selected by the Architect.

## 2.7 ACCESSORIES

- A. Sill Receptor: Manufacturer's standard Aluminum Sill Receptor with integral weeps in color to match aluminum storefront system.
- B. Fasteners and Accessories: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding fasteners and accessories compatible with adjacent materials.
  - 1. Use self-locking devices where fasteners are subject to loosening or turning out from thermal and structural movements, wind loads, or vibration.
  - 2. Reinforce members as required to receive fastener threads.
- C. Anchors: Three-way adjustable anchors with minimum adjustment of 1 inch (25.4 mm) that accommodate fabrication and installation tolerances in material and finish compatible with adjoining materials and recommended by manufacturer.

1. Concrete and Masonry Inserts: Hot-dip galvanized cast-iron, malleable-iron, or steel inserts complying with ASTM A 123/A 123M or ASTM A 153/A 153M requirements.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- D. Concealed Flashing: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding flashing compatible with adjacent materials.
- E. Bituminous Paint: Cold-applied asphalt-mastic paint complying with SSPC-Paint 12 requirements except containing no asbestos, formulated for 30-mil (0.762-mm) thickness per coat.

## 2.8 FABRICATION

- A. Form or extrude aluminum shapes before finishing.
- B. Weld in concealed locations to greatest extent possible to minimize distortion or discoloration of finish. Remove weld spatter and welding oxides from exposed surfaces by descaling or grinding.
- C. Fabricate components that, when assembled, have the following characteristics:
  - 1. Profiles that are sharp, straight, and free of defects or deformations.
  - 2. Accurately fitted joints with ends coped or mitered.
  - 3. Physical and thermal isolation of glazing from framing members.
  - 4. Accommodations for thermal and mechanical movements of glazing and framing to maintain required glazing edge clearances.
  - 5. Provisions for field replacement of glazing from exterior.
  - 6. Fasteners, anchors, and connection devices that are concealed from view to greatest extent possible.
- D. Mechanically Glazed Framing Members: Fabricate for flush glazing without projecting stops.
- E. Storefront Framing: Fabricate components for assembly using shear-block system or screw-spline system with sill-receptor system.
- F. Entrance Door Frames: Reinforce as required to support loads imposed by door operation and for installing entrance door hardware.
  - 1. At exterior doors, provide compression weather stripping at fixed stops.
  - 2. At interior doors, provide silencers at stops to prevent metal-to-metal contact. Install three silencers on strike jamb of single-door frames and two silencers on head of frames for pairs of doors.
- G. Entrance Doors: Reinforce doors as required for installing entrance door hardware.
  - 1. At pairs of exterior doors, provide sliding-type weather stripping retained in adjustable strip and mortised into door edge.
  - 2. At exterior doors, provide weather sweeps applied to door bottoms.
- H. Entrance Door Hardware Installation: Factory install entrance door hardware to the greatest extent possible. Cut, drill, and tap for factory-installed entrance door hardware before applying finishes.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

I. After fabrication, clearly mark components to identify their locations in Project according to Shop Drawings.

#### 2.9 **ALUMINUM FINISHES**

Clear Anodic Finish: AAMA 611, AA-M12C22A41, Class I, 0.018 mm or thicker. A.

#### PART 3 - EXECUTION

#### 3.1 **EXAMINATION**

- Examine areas, with Installer present, for compliance with requirements for installation A. tolerances and other conditions affecting performance of the Work.
- Proceed with installation only after unsatisfactory conditions have been corrected. В.

#### 3.2 **PREPARATION**

A. Prepare surfaces that are in contact with structural sealant according to sealant manufacturer's written instructions to ensure compatibility and adhesion. Preparation includes, but is not limited to, cleaning and priming surfaces.

#### 3.3 **INSTALLATION**

#### A. General:

- Comply with manufacturer's written instructions. 1.
- 2. Do not install damaged components.
- Fit joints to produce hairline joints free of burrs and distortion. 3.
- Rigidly secure nonmovement joints. 4.
- 5. Install anchors with separators and isolators to prevent metal corrosion and electrolytic deterioration and to prevent impeding movement of moving joints.
- Seal perimeter and other joints watertight unless otherwise indicated. 6.

#### В. Metal Protection:

- Where aluminum is in contact with dissimilar metals, protect against galvanic action by painting contact surfaces with materials recommended by manufacturer for this purpose or by installing nonconductive spacers.
- 2. Where aluminum is in contact with concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint.
- C. Set continuous sill members and flashing in full sealant bed as specified in Section 079200 "Joint Sealants" to produce weathertight installation.
- D. Install components plumb and true in alignment with established lines and grades.

- E. Install glazing as specified in Section 088000 "Glazing."
- F. Install weatherseal sealant according to Section 079200 "Joint Sealants" and according to sealant manufacturer's written instructions to produce weatherproof joints. Install joint filler behind sealant as recommended by sealant manufacturer.
- G. Entrance Doors: Install doors to produce smooth operation and tight fit at contact points.
  - 1. Exterior Doors: Install to produce weathertight enclosure and tight fit at weather stripping.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

2. Field-Installed Entrance Door Hardware: Install surface-mounted entrance door hardware according to entrance door hardware manufacturers' written instructions using concealed fasteners to greatest extent possible.

## 3.4 ERECTION TOLERANCES

- A. Erection Tolerances: Install aluminum-framed entrances and storefronts to comply with the following maximum tolerances:
  - 1. Plumb: 1/8 inch in 10 feet (3.2 mm in 3 m); 1/4 inch in 40 feet (6.35 mm in 12.2 m).
  - 2. Level: 1/8 inch in 20 feet (3.2 mm in 6 m); 1/4 inch in 40 feet (6.35 mm in 12.2 m).
  - 3. Alignment:
    - a. Where surfaces abut in line or are separated by reveal or protruding element up to 1/2 inch (12.7 mm) wide, limit offset from true alignment to 1/16 inch (1.6 mm).
    - b. Where surfaces are separated by reveal or protruding element from 1/2 to 1 inch (12.7 to 25.4 mm) wide, limit offset from true alignment to 1/8 inch (3.2 mm).
    - c. Where surfaces are separated by reveal or protruding element of 1 inch (25.4 mm) wide or more, limit offset from true alignment to 1/4 inch (6 mm).
  - 4. Location: Limit variation from plane to 1/8 inch in 12 feet (3.2 mm in 3.6 m); 1/2 inch (12.7 mm) over total length.

# 3.5 FIELD QUALITY CONTROL

- A. Field Quality-Control Testing: Perform the following test on representative areas of aluminum-framed entrances and storefronts.
  - 1. Water-Spray Test: Before installation of interior finishes has begun, areas designated by Architect shall be tested according to AAMA 501.2 and shall not evidence water penetration.
    - a. Perform a minimum of three tests in areas as directed by Architect after 30% complete.
- B. Aluminum-framed entrances and storefronts will be considered defective if they do not pass tests and inspections.
- C. Prepare test and inspection reports.

## 3.6 MAINTENANCE SERVICE

## A. Entrance Door Hardware:

1. Maintenance Tools and Instructions: Furnish a complete set of specialized tools and maintenance instructions as needed for Owner's continued adjustment, maintenance, and removal and replacement of entrance door hardware.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

2. Initial Maintenance Service: Beginning at Substantial Completion, provide Twelve months' full maintenance by skilled employees of entrance door hardware Installer. Include quarterly preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper entrance door hardware operation at rated speed and capacity. Use parts and supplies that are the same as those used in the manufacture and installation of original equipment.

## 3.7 ADJUSTING

- A. Adjust operating entrance door hardware to function smoothly as recommended by manufacturer.
  - 1. For entrance doors accessible to people with disabilities, adjust closers to provide a 3-second closer sweep period for doors to move from a 70-degree open position to 3 inches (75 mm) from the latch, measured to the leading door edge.

END OF SECTION 084113

# SECTION 087100 - DOOR HARDWARE

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 1.2 SUMMARY

#### A. Section includes:

- 1. Mechanical door hardware for the following:
  - a. Swinging doors.
- 2. Cylinders for door hardware specified in other Sections.
- 3. Electrified door hardware.

## B. Related Sections:

- 1. Section 064023 "Interior Architectural Woodwork" for cabinet door hardware provided as part of architectural woodwork.
- 2. Section 081113 "Hollow Metal Doors and Frames" and for door silencers provided as part of hollow-metal frames.
- 3. Section 081416 "Flush Wood Doors" for integral intumescent seals provided as part of labeled fire-rated assemblies.
- 4. Section 084113 "Aluminum-Framed Entrances and Storefronts" for entrance door hardware, except cylinders.

## 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include construction and installation details, material descriptions, dimensions of individual components and profiles, and finishes.
- B. Shop Drawings: Details of electrified door hardware, indicating the following:
  - 1. Wiring Diagrams: For power, signal, and control wiring and including the following:
    - a. Details of interface of electrified door hardware and building safety and security systems.
    - b. Schematic diagram of systems that interface with electrified door hardware.
    - c. Point-to-point wiring.
    - d. Risers.
    - e. Elevations doors controlled by electrified door hardware.

hardware.

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

#### C. Other Action Submittals:

2.

1. Door Hardware Schedule: Prepared by or under the supervision of Installer, detailing fabrication and assembly of door hardware, as well as installation procedures and diagrams. Coordinate final door hardware schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of door hardware.

Operation Narrative: Describe the operation of doors controlled by electrified door

- a. Submittal Sequence: Submit door hardware schedule concurrent with submissions of Product Data, Samples, and Shop Drawings. Coordinate submission of door hardware schedule with scheduling requirements of other work to facilitate the fabrication of other work that is critical in Project construction schedule.
- b. Format: Use same scheduling sequence and format and use same door numbers as in the Contract Documents.
- c. Content: Include the following information:
  - 1) Identification number, location, hand, fire rating, size, and material of each door and frame.
  - 2) Locations of each door hardware set, cross-referenced to Drawings on floor plans and to door and frame schedule.
  - 3) Complete designations, including name and manufacturer, type, style, function, size, quantity, function, and finish of each door hardware product.
  - 4) Description of electrified door hardware sequences of operation and interfaces with other building control systems.
  - 5) Fastenings and other pertinent information.
  - 6) Explanation of abbreviations, symbols, and codes contained in schedule.
  - 7) Mounting locations for door hardware.
  - 8) List of related door devices specified in other Sections for each door and frame.
- 2. Keying Schedule: Prepared by or under the supervision of Installer, detailing Owner's final keying instructions for locks. Include schematic keying diagram and index each key set to unique door designations that are coordinated with the Contract Documents.

## 1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer and Supplier.
- B. Product Certificates: For electrified door hardware, from the manufacturer.
  - 1. Certify that door hardware approved for use on types and sizes of labeled fire-rated doors complies with listed fire-rated door assemblies.
- C. Product Test Reports: For compliance with accessibility requirements, based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified testing agency, for door hardware on doors located in accessible routes.

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

D. Warranty: Special warranty specified in this Section.

#### 1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of door hardware to include in maintenance manuals. Include final hardware and keying schedule.

## 1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish specialty tools required for maintenance.

## 1.7 QUALITY ASSURANCE

- A. Submittal and Coordination Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." In addition to Owner Contractor, Electrical Sub-contractor and Architect, conference participants shall also include Installer's Architectural Hardware Consultant. Meeting shall include coordination of all electrical requirements for specific hardware.
- B. Installer Qualifications: Supplier of products and an employer of workers trained and approved by product manufacturers and an Architectural Hardware Consultant who is available during the course of the Work to consult with Contractor, Architect, and Owner about door hardware and keying.
  - 1. Warehousing Facilities: In Project's vicinity.
  - 2. Scheduling Responsibility: Preparation of door hardware and keying schedules.
  - 3. Engineering Responsibility: Preparation of data for electrified door hardware, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project.
- C. Architectural Hardware Consultant Qualifications: A person who is experienced in providing consulting services for door hardware installations that are comparable in material, design, and extent to that indicated for this Project and who is currently certified by DHI as follows:
  - 1. For door hardware, an Architectural Hardware Consultant (AHC).
- D. Source Limitations: Obtain each type of door hardware from a single manufacturer.
  - 1. Provide electrified door hardware from same manufacturer as mechanical door hardware, unless otherwise indicated. Manufacturers that perform electrical modifications and that are listed by a testing and inspecting agency acceptable to authorities having jurisdiction are acceptable.
- E. Means of Egress Doors: Latches do not require more than 15 lbf (67 N) to release the latch. Locks do not require use of a key, tool, or special knowledge for operation.

- F. Accessibility Requirements: For door hardware on doors in an accessible route, comply with the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines and ICC/ANSI A117.1.
  - 1. Provide operating devices that do not require tight grasping, pinching, or twisting of the wrist and that operate with a force of not more than 5 lbf (22.2 N).
  - 2. Comply with the following maximum opening-force requirements:
    - a. Interior, Non-Fire-Rated Hinged Doors: 5 lbf (22.2 N) applied perpendicular to door.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 3. Bevel raised thresholds with a slope of not more than 1:2. Provide thresholds not more than 1/2 inch (13 mm) high.
- 4. Adjust door closer sweep periods so that, from an open position of 70 degrees, the door will take at least 3 seconds to move to a point 3 inches (75 mm) from the latch, measured to the leading edge of the door.
- G. Keying Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." In addition to Owner Contractor, and Architect, conference participants shall also include Installer's Architectural Hardware Consultant. Incorporate keying conference decisions into final keying schedule after reviewing door hardware keying system including, but not limited to, the following:
  - 1. Function of building, flow of traffic, purpose of each area, degree of security required, and plans for future expansion.
  - 2. Preliminary key system schematic diagram.
  - 3. Requirements for key control system.
  - 4. Requirements for access control.
  - 5. Address for delivery of keys.

## 1.8 DELIVERY, STORAGE, AND HANDLING

- A. Inventory door hardware on receipt and provide secure lock-up for door hardware delivered to Project site.
- B. Tag each item or package separately with identification coordinated with the final door hardware schedule, and include installation instructions, templates, and necessary fasteners with each item or package.

## 1.9 COORDINATION

- A. Installation Templates: Distribute for doors, frames, and other work specified to be factory prepared. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing door hardware to comply with indicated requirements.
- B. Security: Coordinate installation of door hardware, keying, and access control with Owner's security consultant.

C. Electrical System Roughing-In: Coordinate layout and installation of electrified door hardware with connections to power supplies and building safety and security systems.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 1.10 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of door hardware that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Structural failures including excessive deflection, cracking, or breakage.
    - b. Faulty operation of doors and door hardware.
    - c. Deterioration of metals, metal finishes, and other materials beyond normal weathering and use.
  - 2. Warranty Period: Three years from date of Substantial Completion, unless otherwise indicated.
    - a. Electromagnetic and Delayed-Egress Locks: Five years from date of Substantial Completion.
    - b. Exit Devices: Two years from date of Substantial Completion.
    - c. Manual Closers: 10 years from date of Substantial Completion.

## 1.11 MAINTENANCE SERVICE

A. Maintenance Tools and Instructions: Furnish a complete set of specialized tools and maintenance instructions for Owner's continued adjustment, maintenance, and removal and replacement of door hardware.

#### PART 2 - PRODUCTS

## 2.1 SCHEDULED DOOR HARDWARE

- A. Provide door hardware for each door as scheduled in Part 3 "Door Hardware Schedule" Article and on Drawings to comply with requirements in this Section.
  - 1. Door Hardware Sets: Provide quantity, item, size, finish or color indicated, and named manufacturers' products.
  - 2. Sequence of Operation: Provide electrified door hardware function, sequence of operation, and interface with other building control systems indicated.
- B. Designations: Requirements for design, grade, function, finish, size, and other distinctive qualities of each type of door hardware are indicated in Part 3 "Door Hardware Schedule" Article. Products are identified by using door hardware designations, as follows:

Re-Bid Set Issue Date: 06/05/2014

1. Named Manufacturers' Products: Manufacturer and product designation are listed for each door hardware type required for the purpose of establishing minimum requirements.

Manufacturers' names are abbreviated in Part 3 "Door Hardware Schedule" Article.

Architect's Project #: 12.130.09

## 2.2 HINGES

- A. Hinges: BHMA A156.1. Provide template-produced hinges for hinges installed on hollow-metal doors and hollow-metal frames.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. McKinney Products Company; an ASSA ABLOY Group company.
    - b. <u>Hager Companies</u>.
    - c. Stanley Commercial Hardware; Div. of The Stanley Works.

# 2.3 CONTINUOUS HINGES

- A. Continuous Hinges: BHMA A156.26; minimum 0.120-inch- (3.0-mm-) thick, hinge leaves with minimum overall width of 4 inches (102 mm); fabricated to full height of door and frame and to template screw locations; with components finished after milling and drilling are complete.
- B. Pin-and-Barrel-Type Hinges:
- C. Continuous, Gear-Type Hinges: Extruded-aluminum, pinless, geared hinge leaves joined by a continuous extruded-aluminum channel cap; with concealed, self-lubricating thrust bearings.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. Pemko Products Company; an ASSA ABLOY Group company.
    - b. Hager Companies.
    - c. Stanley Commercial Hardware; Div. of The Stanley Works.

## 2.4 MECHANICAL LOCKS AND LATCHES

- A. Lock Functions: As indicated in door hardware schedule.
- B. Lock Throw: Comply with testing requirements for length of bolts required for labeled fire doors, and as follows:
  - 1. Mortise Locks: Minimum 3/4-inch (19-mm) latchbolt throw.
- C. Lock Backset: 2-3/4 inches (70 mm), unless otherwise indicated.
- D. Lock Trim:
  - 1. Description: As indicated in Schedule.
  - 2. Levers: Cast.
  - 3. Escutcheons (Roses): Wrought.
  - 4. Dummy Trim: Match lever lock trim and escutcheons.

- 5. Operating Device: Lever with escutcheons (roses).
- E. Strikes: Provide manufacturer's standard strike for each lock bolt or latchbolt complying with requirements indicated for applicable lock or latch and with strike box and curved lip extended to protect frame; finished to match lock or latch.
  - 1. Flat-Lip Strikes: For locks with three-piece antifriction latchbolts, as recommended by manufacturer.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Aluminum-Frame Strike Box: Manufacturer's special strike box fabricated for aluminum framing.
- 3. Rabbet Front and Strike: Provide on locksets for rabbeted meeting stiles.
- F. Mortise Locks: BHMA A156.13; Operational Grade 1; stamped steel case with steel or brass parts; Series 1000.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. Corbin Russwin; an ASSA ABLOY Group company.

## 2.5 AUXILIARY LOCKS

- A. Mortise Auxiliary Locks: BHMA A156.5; Grade 1; with strike that suits frame.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. Corbin Russwin; an ASSA ABLOY Group company.
    - b. <u>Best Access Systems; Div. of Stanley Security Solutions, Inc.</u>
    - c. SARGENT Manufacturing Company; an ASSA ABLOY Group company.
    - d. Schlage Commercial Lock Division; an Ingersoll-Rand company.
    - e. Yale Security Inc.; an ASSA ABLOY Group company.

## 2.6 ELECTRIC STRIKES

- A. Electric Strikes: BHMA A156.31; Grade [1] [2]; with faceplate to suit lock and frame.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. HES, Inc.; an ASSA ABLOY Group company.
    - b. <u>Dortronics Systems, Inc.</u>
    - c. <u>DynaLock Corp.</u>
    - d. Rutherford Controls Int'l. Corp.
    - e. Security Door Controls.
    - f. Trine Access Technology.
    - g. <u>Von Duprin; an Ingersoll-Rand company</u>.

# 2.7 MANUAL FLUSH BOLTS

A. Manual Flush Bolts: BHMA A156.16; minimum 3/4-inch (19-mm) throw; designed for mortising into door edge.

1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- a. Rockwood.; an ASSA ABLOY Group company.
- b. <u>Burns Manufacturing</u> Incorporated.
- c. <u>Door Controls International, Inc.</u>
- d. IVES Hardware; an Ingersoll-Rand company.
- e. Trimco.

#### 2.8 EXIT DEVICES AND AUXILIARY ITEMS

- A. Exit Devices and Auxiliary Items: BHMA A156.3.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. Corbin Russwin Architectural Hardware; an ASSA ABLOY Group company.
    - b. SARGENT Manufacturing Company; an ASSA ABLOY Group company.
    - c. Yale Security Inc.; an ASSA ABLOY Group company.

## 2.9 LOCK CYLINDERS

- A. Lock Cylinders: Tumbler type, constructed from brass or bronze, stainless steel, or nickel silver.
  - 1. Best Cylinder 1E74-C4-RP3-626 Cylinder to match campus standard

## 2.10 KEYING

- A. Keying System: Factory registered, complying with guidelines in BHMA A156.28, Appendix A. Incorporate decisions made in keying conference.
  - 1. Existing System:
    - a. Master key or grand master key locks to Owner's existing system.
  - 2. Provide blank cylinders for Owner to key.

## 2.11 OPERATING TRIM

- A. Operating Trim: BHMA A156.6; stainless steel, unless otherwise indicated.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. <u>Hager Companies</u>.
    - b. IVES Hardware; an Ingersoll-Rand company.
    - c. Rockwood Manufacturing Company.
    - d. Trimco.

# 2.12 ACCESSORIES FOR PAIRS OF DOORS

A. Astragals: BHMA A156.22.

## 2.13 SURFACE CLOSERS

- A. Surface Closers: BHMA A156.4; rack-and-pinion hydraulic type with adjustable sweep and latch speeds controlled by key-operated valves and forged-steel main arm. Comply with manufacturer's written recommendations for size of door closers depending on size of door, exposure to weather, and anticipated frequency of use. Provide factory-sized closers, adjustable to meet field conditions and requirements for opening force.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- a. Norton; an ASSA ABLOY Group company.
- b. <u>SARGENT Manufacturing Company</u>; an ASSA ABLOY Group company.
- c. Yale Security Inc.; an ASSA ABLOY Group company.

## 2.14 MECHANICAL STOPS AND HOLDERS

- A. Wall- and Floor-Mounted Stops: BHMA A156.16; polished cast brass, bronze, or aluminum base metal.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. Rockwood Manufacturing Company.
    - b. Architectural Builders Hardware Mfg., Inc.
    - c. <u>Baldwin Hardware Corporation</u>.
    - d. <u>Hager Companies</u>.
    - e. IVES Hardware; an Ingersoll-Rand company.
    - f. Stanley Commercial Hardware; Div. of The Stanley Works.
    - g. <u>Trimco</u>.

## 2.15 DOOR GASKETING

- A. Door Gasketing: BHMA A156.22; air leakage not to exceed 0.50 cfm per foot (0.000774 cu. m/s per m) of crack length for gasketing other than for smoke control, as tested according to ASTM E 283; with resilient or flexible seal strips that are easily replaceable and readily available from stocks maintained by manufacturer.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. Pemko; an ASSA ABLOY Group company.
    - b. National Guard Products.
    - c. Pemko Manufacturing Co.; an ASSA ABLOY Group company.

## 2.16 THRESHOLDS

- A. Thresholds: BHMA A156.21; fabricated to full width of opening indicated.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. Pemko Manufacturing Co.; an ASSA ABLOY Group company.

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- b. <u>Hager Companies</u>.
- c. National Guard Products.

## 2.17 METAL PROTECTIVE TRIM UNITS

- A. Metal Protective Trim Units: BHMA A156.6; fabricated from 0.050-inch- (1.3-mm-) thick stainless steel; with manufacturer's standard machine or self-tapping screw fasteners.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. McKinney Products Company; an ASSA ABLOY Group company.
    - b. Rockwood Manufacturing Company.

## 2.18 AUXILIARY DOOR HARDWARE

- A. Auxiliary Hardware: BHMA A156.16.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide product indicated on schedule or comparable product by one of the following:
    - a. <u>Baldwin Hardware Corporation</u>.
    - b. <u>Cal-Royal Products, Inc.</u>
    - c. Don-Jo Mfg., Inc.
    - d. Hager Companies.
    - e. Rockwood Manufacturing Company.
    - f. Stanley Commercial Hardware; Div. of The Stanley Works.
    - g. Trimco.

## 2.19 FABRICATION

- A. Base Metals: Produce door hardware units of base metal indicated, fabricated by forming method indicated, using manufacturer's standard metal alloy, composition, temper, and hardness. Furnish metals of a quality equal to or greater than that of specified door hardware units and BHMA A156.18.
- B. Fasteners: Provide door hardware manufactured to comply with published templates prepared for machine, wood, and sheet metal screws. Provide screws that comply with commercially recognized industry standards for application intended, except aluminum fasteners are not permitted. Provide Phillips flat-head screws with finished heads to match surface of door hardware, unless otherwise indicated.
  - 1. Fire-Rated Applications:
    - a. Wood or Machine Screws: For the following:
      - 1) Hinges mortised to doors or frames.
      - 2) Strike plates to frames.
      - 3) Closers to doors and frames.

b. Steel Through Bolts: For the following unless door blocking is provided:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1) Surface hinges to doors.
- 2) Closers to doors and frames.
- 3) Surface-mounted exit devices.
- 2. Spacers or Sex Bolts: For through bolting of hollow-metal doors.
- 3. Fasteners for Wood Doors: Comply with requirements in DHI WDHS.2, "Recommended Fasteners for Wood Doors."
- 4. Gasketing Fasteners: Provide noncorrosive fasteners for exterior applications and elsewhere as indicated.

## 2.20 FINISHES

- A. Provide finishes complying with BHMA A156.18 as indicated in door hardware schedule.
- B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

## **PART 3 - EXECUTION**

## 3.1 EXAMINATION

- A. Examine doors and frames, with Installer present, for compliance with requirements for installation tolerances, labeled fire-rated door assembly construction, wall and floor construction, and other conditions affecting performance.
- B. Examine roughing-in for electrical power systems to verify actual locations of wiring connections before electrified door hardware installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

## 3.2 PREPARATION

- A. Steel Doors and Frames: For surface applied door hardware, drill and tap doors and frames according to ANSI/SDI A250.6.
- B. Wood Doors: Comply with DHI WDHS.5 "Recommended Hardware Reinforcement Locations for Mineral Core Wood Flush Doors."

## 3.3 INSTALLATION

- A. Mounting Heights: Mount door hardware units at heights to comply with the following unless otherwise indicated or required to comply with governing regulations.
  - 1. Standard Steel Doors and Frames: ANSI/SDI A250.8.
  - 2. Custom Steel Doors and Frames: HMMA 831.
  - 3. Wood Doors: DHI WDHS.3, "Recommended Locations for Architectural Hardware for Wood Flush Doors."

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Install each door hardware item to comply with manufacturer's written instructions. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be painted or finished in another way, coordinate removal, storage, and reinstallation of surface protective trim units with finishing. Do not install surface-mounted items until finishes have been completed on substrates involved.
  - 1. Set units level, plumb, and true to line and location. Adjust and reinforce attachment substrates as necessary for proper installation and operation.
  - 2. Drill and countersink units that are not factory prepared for anchorage fasteners. Space fasteners and anchors according to industry standards.
- C. Hinges: Install types and in quantities indicated in door hardware schedule but not fewer than the number recommended by manufacturer for application indicated or one hinge for every 30 inches (750 mm) of door height, whichever is more stringent, unless other equivalent means of support for door, such as spring hinges or pivots, are provided.
- D. Lock Cylinders: Install construction cores to secure building and areas during construction period.
  - 1. Replace construction cores with permanent cores as indicated in keying schedule and as directed by Owner.
- E. Key Control System: Tag keys and place them on markers and hooks in key control system cabinet, as determined by final keying schedule.
- F. Boxed Power Supplies: Locate power supplies as indicated or, if not indicated, above accessible ceilings. Verify location with Architect.
  - 1. Configuration: Provide one power supply for each door opening with electrified door hardware.
- G. Thresholds: Set thresholds for exterior doors and other doors indicated in full bed of sealant complying with requirements specified in Section 079200 "Joint Sealants."
- H. Stops: Provide floor stops for doors unless wall or other type stops are indicated in door hardware schedule. Do not mount floor stops where they will impede traffic.
- I. Perimeter Gasketing: Apply to head and jamb, forming seal between door and frame.
- J. Meeting Stile Gasketing: Fasten to meeting stiles, forming seal when doors are closed.

K. Door Bottoms: Apply to bottom of door, forming seal with threshold when door is closed.

#### 3.4 ADJUSTING

- A. Initial Adjustment: Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.
  - 1. Spring Hinges: Adjust to achieve positive latching when door is allowed to close freely from an open position of 30 degrees.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Electric Strikes: Adjust horizontal and vertical alignment of keeper to properly engage lock bolt.
- 3. Door Closers: Adjust sweep period to comply with accessibility requirements and requirements of authorities having jurisdiction.
- B. Occupancy Adjustment: Approximately three months after date of Substantial Completion, Installer's Architectural Hardware Consultant shall examine and readjust each item of door hardware, including adjusting operating forces, as necessary to ensure function of doors, door hardware, and electrified door hardware.

## 3.5 CLEANING AND PROTECTION

- A. Clean adjacent surfaces soiled by door hardware installation.
- B. Clean operating items as necessary to restore proper function and finish.
- C. Provide final protection and maintain conditions that ensure that door hardware is without damage or deterioration at time of Substantial Completion.

## 3.6 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain door hardware and door hardware finishes. Refer to Section 017900 "Demonstration and Training."

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

PART 4 - DOOR HARDWARE SCHEDULE (See Attached Hardware Schedule)

Note: Provide Cylinders keyed to master keying system for hardware provided by storefront.

## Hardware Sets

		Hardware Sets			
Set #0	1 – DR. 109 and 118				
3	Hinges	T4A3786 4 1/2 x 4 1/2	26D	MC	
1	Push Plate	70C 4 x 16	US32D	RO	
1	Door Pull	102 x 70C	US32D	RO	
1	Closer	CLP-8301 SN-134 (110 ° max)	689	NO	
1	Protective Plate	K 1050 8" x 34"	US32D	RO	
3	Door Silencers	608	GREY	RO	
_					
Set #02 – DR. 110, 117					
3	Hinges	TA2714 4 1/2 x 4 1/2	26D	MC	
1	Lockset	ML2055 NSA	630	CR	
1	Closer	CLP-8301 SN-134 (110 ° max)	689	NO	
3	Door Silencers	608	GREY	RO	
Set #03 – DR. 112 and 116					
3	Hinges	TA2714 4 1/2 x 4 1/2	26D	MC	
1	Passage Set	ML2010 NSA MK VKC2	630	CR	
3	Door Silencers	608	GREY	RO	
3	Door Shelicers	008	GKE I	KO	
Set #04 – DR. 111, 113, 114, 115, and 119					
1	Continuous Hinge	CFS 85 HD1		PE	
1	Exit Device	ED5200 x K157 6P	630	CR	
1	Electric Strike	1006CS	630	HS	
1	Power Supply	BPS-24-1		CR	
1	Closer	PR8301 TBGN-134	689	NO	
1	Exterior Pull	RM2112 x 48	US32D	RO	
	NOTE: card reader by				
S 4 1/05 DD 120					
	5 – DR. 120	TA 0714 4 1 /0 4 1 /0	ACD.	MO	
3	Hinges	TA2714 4 1/2 x 4 1/2	26D	MC	
1	Privacy Set	ML2030 NSA M19V	630	CR	
1	Wall Bumper	409	US32D	RO	
3	Door Silencers	608	GREY	RO	
Set #0	6 – DR. 122				
2	Continuous Hinge	CFS 85 HD1		PE	
2	Flush Bolts	555	US26D	RO	
1	Lockset	ML2059 NSA MK VKC2	630	CR	
2	Closer	PR8301 TBGN-134	689	NO	
1	Weatherstrip	297 APK 1 x 72" 2 x 86"		PE	
2	Door Bottom	315 CN 36"		PE	
1	Threshold	171 A 72"		PE	
1	11110011010	11111			

END OF SECTION 087100

## SECTION 088000 - GLAZING

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 1.2 SUMMARY

- A. Section includes:
  - 1. Glass for windows, doors interior, storefront framing.
  - 2. Glazing sealants and accessories.
- B. Related Requirements:
  - 1. Section 084113 "Aluminum-Framed Entrances and Storefronts."

## 1.3 DEFINITIONS

- A. Glass Manufacturers: Firms that produce primary glass, fabricated glass, or both, as defined in referenced glazing publications.
- B. Glass Thicknesses: Indicated by thickness designations in millimeters according to ASTM C 1036.
- C. IBC: International Building Code.
- D. Interspace: Space between lites of an insulating-glass unit.

## 1.4 COORDINATION

A. Coordinate glazing channel dimensions to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances.

## 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Glass Samples: For each type of glass product other than clear monolithic vision glass; 12 inches (300 mm) square.
- C. Glazing Accessory Samples: For sealants and colored spacers, in 12-inch (300-mm) lengths. Install sealant Samples between two strips of material representative in color of the adjoining framing system.

D. Glazing Schedule: List glass types and thicknesses for each size opening and location. Use same designations indicated on Drawings.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

E. Delegated-Design Submittal: For glass indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

## 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer and sealant testing agency.
- B. Product Certificates: For glass.
- C. Product Test Reports: For coated glass, insulating glass and glazing sealants, for tests performed by a qualified testing agency.
  - 1. For glazing sealants, provide test reports based on testing current sealant formulations within previous 36-month period.
- D. Preconstruction adhesion and compatibility test report.
- E. Sample Warranties: For special warranties.

# 1.7 QUALITY ASSURANCE

- A. Manufacturer Qualifications for Insulating-Glass Units with Low-E Coatings: A qualified insulating-glass manufacturer who is approved and certified by coated-glass manufacturer.
- B. Installer Qualifications: A qualified installer who employs glass installers for this Project who are certified under the National Glass Association's Certified Glass Installer Program.
- C. Glass Testing Agency Qualifications: A qualified independent testing agency accredited according to the NFRC CAP 1 Certification Agency Program.
- D. Sealant Testing Agency Qualifications: An independent testing agency qualified according to ASTM C 1021 to conduct the testing indicated.
- E. Mockups: Build mockups to demonstrate aesthetic effects and to set quality standards for materials and execution.
  - 1. Install glazing in mockups specified in Section 084113 "Aluminum-Framed Entrances and Storefronts" to match glazing systems required for Project, including glazing methods.

## 1.8 PRECONSTRUCTION TESTING

- A. Preconstruction Adhesion and Compatibility Testing: Test each glass product, tape sealant, gasket, glazing accessory, and glass-framing member for adhesion to and compatibility with elastomeric glazing sealants.
  - 1. Testing is not required if data are submitted based on previous testing of current sealant products and glazing materials matching those submitted.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Use ASTM C 1087 to determine whether priming and other specific joint-preparation techniques are required to obtain rapid, optimum adhesion of glazing sealants to glass, tape sealants, gaskets, and glazing channel substrates.
- 3. Test no fewer than Four Samples of each type of material, including joint substrates, shims, sealant backings, secondary seals, and miscellaneous materials.
- 4. Schedule enough time for testing and analyzing results to prevent delaying the Work.
- 5. For materials failing tests, submit sealant manufacturer's written instructions for corrective measures including the use of specially formulated primers.

## 1.9 DELIVERY, STORAGE, AND HANDLING

- A. Protect glazing materials according to manufacturer's written instructions. Prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.
- B. Comply with insulating-glass manufacturer's written instructions for venting and sealing units to avoid hermetic seal ruptures due to altitude change.

## 1.10 FIELD CONDITIONS

- A. Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.
  - 1. Do not install glazing sealants when ambient and substrate temperature conditions are outside limits permitted by sealant manufacturer or are below 40 deg F (4.4 deg C).

## 1.11 WARRANTY

- A. Manufacturer's Special Warranty for Coated-Glass Products: Manufacturer agrees to replace coated-glass units that deteriorate within specified warranty period. Deterioration of coated glass is defined as defects developed from normal use that are not attributed to glass breakage or to maintaining and cleaning coated glass contrary to manufacturer's written instructions. Defects include peeling, cracking, and other indications of deterioration in coating.
  - 1. Warranty Period: 10 years from date of Substantial Completion.
- B. Manufacturer's Special Warranty for Insulating Glass: Manufacturer agrees to replace insulating-glass units that deteriorate within specified warranty period. Deterioration of

insulating glass is defined as failure of hermetic seal under normal use that is not attributed to glass breakage or to maintaining and cleaning insulating glass contrary to manufacturer's written instructions. Evidence of failure is the obstruction of vision by dust, moisture, or film on interior surfaces of glass.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

1. Warranty Period: 10 years from date of Substantial Completion.

## PART 2 - PRODUCTS

## 2.1 MANUFACTURERS

- 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide glass units by <u>Guardian Industries Corp.</u>; <u>SunGuard</u> or compatible products by one of the following:
  - 1. <u>Oldcastle BuildingEnvelope<sup>TM</sup></u>.
  - 2. <u>Pilkington North America</u>.
  - 3. <u>PPG Industries, Inc.</u>
- B. Source Limitations for Glass: Obtain from single source from single manufacturer for each glass type.
  - 1. Obtain tinted glass from single source from single manufacturer.
  - 2. Obtain reflective-coated glass from single source from single manufacturer.
- C. Source Limitations for Glazing Accessories: Obtain from single source from single manufacturer for each product and installation method.

## 2.2 PERFORMANCE REQUIREMENTS

- A. General: Installed glazing systems shall withstand normal thermal movement and wind and impact loads (where applicable) without failure, including loss or glass breakage attributable to the following: defective manufacture, fabrication, or installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; or other defects in construction.
- B. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design glazing.
- C. Structural Performance: Glazing shall withstand the following design loads within limits and under conditions indicated determined according to the IBC and ASTM E 1300.
  - 1. Design Wind Pressures: Determine design wind pressures applicable to Project according to ASCE/SEI 7, based on heights above grade indicated on Drawings.
  - 2. Probability of Breakage for Sloped Glazing: For glass surfaces sloped more than 15 degrees from vertical, design glass for a probability of breakage not greater than 0.001.
  - 3. Maximum Lateral Deflection: For glass supported on all four edges, limit center-of-glass deflection at design wind pressure to not more than 1/50 times the short-side length or 1 inch (25 mm), whichever is less.

D. Safety Glazing: Where safety glazing is indicated, provide glazing that complies with 16 CFR 1201, Category II.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- E. Thermal and Optical Performance Properties: Provide glass with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below:
  - 1. For monolithic-glass lites, properties are based on units with lites 6 mm thick.
  - 2. For laminated-glass lites, properties are based on products of construction indicated.
  - 3. For insulating-glass units, properties are based on units of thickness indicated for overall unit and for each lite.
  - 4. U-Factors: Center-of-glazing values, according to NFRC 100 and based on LBL's WINDOW 5.2 computer program, expressed as Btu/sq. ft. x h x deg F (W/sq. m x K).
  - 5. Solar Heat-Gain Coefficient and Visible Transmittance: Center-of-glazing values, according to NFRC 200 and based on LBL's WINDOW 5.2 computer program.
  - 6. Visible Reflectance: Center-of-glazing values, according to NFRC 300.

## 2.3 GLASS PRODUCTS, GENERAL

- A. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below unless more stringent requirements are indicated. See these publications for glazing terms not otherwise defined in this Section or in referenced standards.
  - 1. GANA Publications: "Laminated Glazing Reference Manual" and "Glazing Manual."
  - 2. AAMA Publications: AAMA GDSG-1, "Glass Design for Sloped Glazing," and AAMA TIR A7, "Sloped Glazing Guidelines."
  - 3. IGMA Publication for Sloped Glazing: IGMA TB-3001, "Guidelines for Sloped Glazing."
  - 4. IGMA Publication for Insulating Glass: SIGMA TM-3000, "North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial and Residential Use."
- B. Safety Glazing Labeling: Where safety glazing is indicated, permanently mark glazing with certification label of the SGCC or another certification agency acceptable to authorities having jurisdiction. Label shall indicate manufacturer's name, type of glass, thickness, and safety glazing standard with which glass complies.
- C. Insulating-Glass Certification Program: Permanently marked either on spacers or on at least one component lite of units with appropriate certification label of IGCC.
- D. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass that complies with performance requirements and is not less than the thickness indicated.
  - 1. Minimum Glass Thickness for Exterior Lites: 6 mm.
- E. Strength: Where annealed float glass is indicated, provide annealed float glass, heatstrengthened float glass, or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where heat-strengthened float glass is indicated, provide heatstrengthened float glass or fully tempered float glass as needed to comply with "Performance

Requirements" Article. Where fully tempered float glass is indicated, provide fully tempered float glass.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 2.4 GLASS PRODUCTS

- A. Clear Annealed Float Glass: ASTM C 1036, Type I, Class 1 (clear), Quality-Q3.
- B. Fully Tempered Float Glass: ASTM C 1048, Kind FT (fully tempered), Condition A (uncoated) unless otherwise indicated, Type I, Class 1 (clear) or Class 2 (tinted) as indicated, Quality-Q3.
- C. Heat-Strengthened Float Glass: ASTM C 1048, Kind HS (heat strengthened), Type I, Condition A (uncoated) unless otherwise indicated, Type I, Class 1 (clear) or Class 2 (tinted) as indicated, Quality-Q3.
- D. Ceramic-Coated Spandrel Glass: ASTM C 1048, Type I, Condition B, Quality-Q3.

## 2.5 INSULATING GLASS

- A. Insulating-Glass Units: Factory-assembled units consisting of sealed lites of glass separated by a dehydrated interspace, qualified according to ASTM E 2190.
  - 1. Sealing System: Dual seal, with manufacturer's standard primary and secondary sealants.
  - 2. Spacer: Manufacturer's standard spacer material and construction.

## 2.6 DECORATIVE FILMS

- A. Interior Applied Decorative Film: Shop applied decorative film on the #4 surface of insulating-glass units.
  - 1. 3M Fasara Glass Finish SH2MACRX2 Mat Crystal 2.

## 2.7 GLAZING SEALANTS

## A. General:

- 1. Compatibility: Compatible with one another and with other materials they contact, including glass products, seals of insulating-glass units, and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
- 2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.
- 3. Field-applied sealants shall have a VOC content of not more than 250 g/L.
- 4. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range.

- B. Glazing Sealant: Neutral-curing silicone glazing sealant complying with ASTM C 920, Type S, Grade NS, Class 100/50, Use NT.
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. <u>Dow Corning Corporation</u>.
- 2. Pecora Corporation.
- 3. <u>Sika Corporation</u>.
- 4. <u>Tremco Incorporated</u>.

## 2.8 GLAZING TAPES

- A. Back-Bedding Mastic Glazing Tapes: Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C 1281 and AAMA 800 for products indicated below:
  - 1. AAMA 804.3 tape, where indicated.
  - 2. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.
  - 3. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.
- B. Expanded Cellular Glazing Tapes: Closed-cell, PVC foam tapes; factory coated with adhesive on both surfaces; and complying with AAMA 800 for the following types:
  - 1. AAMA 810.1, Type 1, for glazing applications in which tape acts as the primary sealant.
  - 2. AAMA 810.1, Type 2, for glazing applications in which tape is used in combination with a full bead of liquid sealant.

## 2.9 MISCELLANEOUS GLAZING MATERIALS

- A. General: Provide products of material, size, and shape complying with referenced glazing standard, with requirements of manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.
- B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.
- C. Setting Blocks: Elastomeric material with a Shore, Type A durometer hardness of 85, plus or minus 5.
- D. Spacers: Elastomeric blocks or continuous extrusions of hardness required by glass manufacturer to maintain glass lites in place for installation indicated.

E. Edge Blocks: Elastomeric material of hardness needed to limit glass lateral movement (side walking).

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

F. Cylindrical Glazing Sealant Backing: ASTM C 1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

## 2.10 FABRICATION OF GLAZING UNITS

- A. Fabricate glazing units in sizes required to fit openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing publications, to comply with system performance requirements.
  - 1. Allow for thermal movements from ambient and surface temperature changes acting on glass framing members and glazing components.
    - 1. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.
- B. Clean-cut or flat-grind vertical edges of butt-glazed monolithic lites to produce square edges with slight chamfers at junctions of edges and faces.
- C. Grind smooth and polish exposed glass edges and corners.

## PART 3 - EXECUTION

## 3.1 EXAMINATION

- A. Examine framing, glazing channels, and stops, with Installer present, for compliance with the following:
  - 1. Manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
  - 2. Presence and functioning of weep systems.
  - 3. Minimum required face and edge clearances.
  - 4. Effective sealing between joints of glass-framing members.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 PREPARATION

A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings not firmly bonded to substrates.

B. Examine glazing units to locate exterior and interior surfaces. Label or mark units as needed so that exterior and interior surfaces are readily identifiable. Do not use materials that leave visible marks in the completed Work.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 3.3 GLAZING, GENERAL

- A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.
- B. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass includes glass with edge damage or other imperfections that, when installed, could weaken glass, impair performance, or impair appearance.
- C. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.
- D. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.
- E. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.
- F. Provide spacers for glass lites where length plus width is larger than 50 inches (1270 mm).
  - 1. Locate spacers directly opposite each other on both inside and outside faces of glass. Install correct size and spacing to preserve required face clearances, unless gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and to comply with system performance requirements.
  - 2. Provide 1/8-inch (3-mm) minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.
- G. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and according to requirements in referenced glazing publications.
- H. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.
- I. Set glass lites with proper orientation so that coatings face exterior or interior as specified.
- J. Where wedge-shaped gaskets are driven into one side of channel to pressurize sealant or gasket on opposite side, provide adequate anchorage so gasket cannot walk out when installation is subjected to movement.
- K. Square cut wedge-shaped gaskets at corners and install gaskets in a manner recommended by gasket manufacturer to prevent corners from pulling away; seal corner joints and butt joints with sealant recommended by gasket manufacturer.

## 3.4 TAPE GLAZING

A. Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sightline of stops.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.
- C. Cover vertical framing joints by applying tapes to heads and sills first, then to jambs. Cover horizontal framing joints by applying tapes to jambs, then to heads and sills.
- D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.
- E. Do not remove release paper from tape until right before each glazing unit is installed.
- F. Apply heel bead of elastomeric sealant.
- G. Center glass lites in openings on setting blocks, and press firmly against tape by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.
- H. Apply cap bead of elastomeric sealant over exposed edge of tape.

# 3.5 GASKET GLAZING (DRY)

- A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.
- B. Insert soft compression gasket between glass and frame or fixed stop so it is securely in place with joints miter cut and bonded together at corners.
- C. Installation with Drive-in Wedge Gaskets: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended by gasket manufacturer.
- D. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket. Install dense compression gaskets and pressure-glazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended by gasket manufacturer.
- E. Install gaskets so they protrude past face of glazing stops.

## 3.6 CLEANING AND PROTECTION

- A. Immediately after installation remove nonpermanent labels and clean surfaces.
- B. Protect glass from contact with contaminating substances resulting from construction operations. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains.
  - 1. If, despite such protection, contaminating substances do come into contact with glass, remove substances immediately as recommended in writing by glass manufacturer. Remove and replace glass that cannot be cleaned without damage to coatings.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- C. Remove and replace glass that is damaged during construction period.
- D. Wash glass on both exposed surfaces not more than four days before date scheduled for inspections that establish date of Substantial Completion. Wash glass as recommended in writing by glass manufacturer.

## 3.7 INSULATING GLASS SCHEDULE

A. Basis-of-Design Product: Guardian Sunguard, SuperNeutral 54 (#2 surface) or compatible products by complying with the following performance characteristics when used as insulated glass with Clear Inboard and outboard lites.

1.	Visible light transmittance %:	54%
2.	Reflectance Out %:	13%
3.	Reflectance In %:	18%
4.	U-Value:	0.29
5.	Shading Coefficient:	0.32
6.	Solar Heat Gain:	0.28
7.	Light to Solar Gain (LSG):	1.91

- B. Glass Type "G1": Clear insulating glass.
  - 1. Overall Unit Thickness: 1 inch (25 mm).
  - 2. Minimum Thickness of Each Glass Lite: 6 mm.
  - 3. Outdoor Lite: Clear Annealed float glass.
  - 4. Interspace Content: Air.
  - 5. Indoor Lite: Clear Annealed float glass.
- C. Glass Type "G1T": Clear insulating glass.
  - 1. Overall Unit Thickness: 1 inch (25 mm).
  - 2. Minimum Thickness of Each Glass Lite: 6 mm.
  - 3. Outdoor Lite: Clear annealed, fully tempered float glass.
  - 4. Interspace Content: Air.
  - 5. Indoor Lite: Clear annealed, fully tempered float glass.
  - 6. Safety glazing required (label all units).
- D. Glass Type "G1F": Clear insulating glass.

e-Bid Set

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 1. Overall Unit Thickness: 1 inch (25 mm).
- 2. Minimum Thickness of Each Glass Lite: 6 mm.
- 3. Outdoor Lite: Clear Annealed float glass.
- 4. Interspace Content: Air.
- 5. Indoor Lite: Clear Annealed float glass.
- 6. Interior Applied Decorative Film: 3M Fasara Glass Finish SH2MACRX2 Mat Crystal 2
- E. Glass Type "G1TF": Clear insulating glass.
  - 1. Overall Unit Thickness: 1 inch (25 mm).
  - 2. Minimum Thickness of Each Glass Lite: 6 mm.
  - 3. Outdoor Lite: Clear annealed, fully tempered float glass.
  - 4. Interspace Content: Air.
  - 5. Indoor Lite: Clear annealed, fully tempered float glass.
  - 6. Safety glazing required (label all units).
  - 7. Interior Applied Decorative Film: 3M Fasara Glass Finish SH2MACRX2 Mat Crystal 2
- F. Glass Type "G2" Ceramic-coated, insulating spandrel glass.
  - 1. Coating Color: Dark Gary, as selected by the Architect from the Manufacturer's standard color selections.
  - 2. Overall Unit Thickness: 1 inch (25 mm).
  - 3. Minimum Thickness of Each Glass Lite: 6 mm.
  - 4. Outdoor Lite: Clear annealed float glass.
  - 5. Interspace Content: Air.
  - 6. Indoor Lite: Clear annealed float glass.
  - 7. Coating Location: Fourth surface.
- G. Glass Type "G2T" Ceramic-coated, insulating spandrel glass.
  - 1. Coating Color: Dark Gary, as selected by the Architect from the Manufacturer's standard color selections.
  - 2. Overall Unit Thickness: 1 inch (25 mm).
  - 3. Minimum Thickness of Each Glass Lite: 6 mm.
  - 4. Outdoor Lite: Clear annealed, fully tempered float glass.
  - 5. Interspace Content: Air.
  - 6. Indoor Lite: Clear annealed, fully tempered float glass.
  - 7. Coating Location: Fourth surface.
  - 8. Safety glazing required (label all units).

END OF SECTION 088000

# SECTION 092216 - NON-STRUCTURAL METAL FRAMING

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Non-load-bearing steel framing systems for interior gypsum board assemblies.
  - 2. Suspension systems for interior gypsum ceilings, soffits, and grid systems.
  - 3. Suspension systems for exterior soffits to receive DEFS system.

# 1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

## 1.4 INFORMATION SUBMITTALS

A. Evaluation Reports: For dimpled steel studs and runners firestop tracks, from ICC-ES.

## PART 2 - PRODUCTS

# 2.1 FRAMING SYSTEMS

- A. Framing Members, General: Comply with ASTM C 754 for conditions indicated.
  - 1. Steel Sheet Components: Comply with ASTM C 645 requirements for metal unless otherwise indicated.
  - 2. Protective Coating: ASTM A 653/A 653M, G40 (Z120), hot-dip galvanized, unless otherwise indicated.
- B. Studs and Runners: ASTM C 645. Use either steel studs and runners or dimpled steel studs and runners.
  - 1. Steel Studs and Runners:
    - a. Minimum Base-Metal Thickness: 0.033 inch (0.84 mm).
    - b. Depth: As indicated on Drawings.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 2. Dimpled Steel Studs and Runners:
  - a. Minimum Base-Metal Thickness: 0.025 inch (0.64 mm).
  - b. Depth: As indicated on Drawings.
- C. Flat Strap and Backing Plate: Steel sheet for blocking and bracing in length and width indicated.
  - 1. Minimum Base-Metal Thickness: 0.033 inch (0.84 mm).
- D. Cold-Rolled Channel Bridging: Steel, 0.053-inch (1.34-mm) minimum base-metal thickness, with minimum 1/2-inch- (13-mm-) wide flanges.
  - 1. Depth: 1-1/2 inches (38 mm).
  - 2. Clip Angle: Not less than 1-1/2 by 1-1/2 inches (38 by 38 mm), 0.068-inch- (1.72-mm-) thick, galvanized steel.
- E. Hat-Shaped, Rigid Furring Channels: ASTM C 645.
  - 1. Minimum Base-Metal Thickness: 0.018 inch (0.45 mm).
  - 2. Depth: As indicated on Drawings.
- F. Cold-Rolled Furring Channels: 0.053-inch (1.34-mm) uncoated-steel thickness, with minimum 1/2-inch- (13-mm-) wide flanges.
  - 1. Depth: As indicated on Drawings.
  - 2. Furring Brackets: Adjustable, corrugated-edge type of steel sheet with minimum uncoated-steel thickness of 0.033 inch (0.8 mm).
  - 3. Tie Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.062-inch- (1.59-mm-) diameter wire, or double strand of 0.048-inch- (1.21-mm-) diameter wire.

# 2.2 SUSPENSION SYSTEMS

- A. Tie Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.062-inch- (1.59-mm-) diameter wire, or double strand of 0.048-inch- (1.21-mm-) diameter wire.
- B. Wire Hangers: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.16 inch (4.12 mm) in diameter.
- C. Carrying Channels: Cold-rolled, commercial-steel sheet with a base-metal thickness of 0.053 inch (1.34 mm) and minimum 1/2-inch- (13-mm-) wide flanges.
  - 1. Depth: As indicated on Drawings.
- D. Furring Channels (Furring Members):
  - 1. Cold-Rolled Channels: 0.053-inch (1.34-mm) uncoated-steel thickness, with minimum 1/2-inch- (13-mm-) wide flanges, 3/4 inch (19 mm) deep.
  - 2. Steel Studs and Runners: ASTM C 645.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- a. Minimum Base-Metal Thickness: 0.033 inch (0.84 mm).
- b. Depth: As indicated on Drawings.
- 3. Dimpled Steel Studs and Runners: ASTM C 645.
  - a. Minimum Base-Metal Thickness: 0.025 inch (0.64 mm).
  - b. Depth: As indicated on Drawings.
- 4. Hat-Shaped, Rigid Furring Channels: ASTM C 645, 7/8 inch (22 mm) deep.
  - a. Minimum Base-Metal Thickness: 0.018 inch (0.45 mm).
- E. Grid Suspension System for Gypsum Board Ceilings: ASTM C 645, direct-hung system composed of main beams and cross-furring members that interlock.
  - 1. <u>Products</u>: Subject to compliance with requirements, provide one of the following:
    - a. Armstrong World Industries, Inc.; Drywall Grid Systems.
    - b. Chicago Metallic Corporation; Drywall Grid System.
    - c. USG Corporation; Drywall Suspension System.

## 2.3 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards.
  - 1. Fasteners for Metal Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.
- B. Isolation Strip at Exterior Walls: Provide the following:
  - 1. Foam Gasket: Adhesive-backed, closed-cell vinyl foam strips that allow fastener penetration without foam displacement, 1/8 inch (3.2 mm) thick, in width to suit steel stud size.

## PART 3 - EXECUTION

## 3.1 EXAMINATION

- A. Examine areas and substrates, with Installer present, and including welded hollow-metal frames, cast-in anchors, and structural framing, for compliance with requirements and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

## 3.2 INSTALLATION, GENERAL

A. Installation Standard: ASTM C 754, except comply with framing sizes and spacing indicated.

1. Gypsum Board Assemblies: Also comply with requirements in ASTM C 840 that apply

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.
- C. Install bracing at terminations in assemblies.

to framing installation.

D. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.

## 3.3 INSTALLING FRAMED ASSEMBLIES

- A. Where studs are installed directly against exterior masonry walls or dissimilar metals at exterior walls, install isolation strip between studs and exterior wall.
- B. Install studs so flanges within framing system point in same direction.
- C. Install tracks (runners) at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings, except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts penetrating partitions above ceiling.
  - 1. Slip-Type Head Joints: Where framing extends to overhead structural supports, install to produce joints at tops of framing systems that prevent axial loading of finished assemblies.
  - 2. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install runner track section (for cripple studs) at head and secure to jamb studs.
    - a. Install two studs at each jamb unless otherwise indicated.
    - b. Install cripple studs at head adjacent to each jamb stud, with a minimum 1/2-inch (13-mm) clearance from jamb stud to allow for installation of control joint in finished assembly.
    - c. Extend jamb studs through suspended ceilings and attach to underside of overhead structure.
  - 3. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.

## D. Direct Furring:

- 1. Attach to concrete or masonry with stub nails, screws designed for masonry attachment, or powder-driven fasteners spaced 24 inches (610 mm) o.c.
- E. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch (3 mm) from the plane formed by faces of adjacent framing.

## 3.4 INSTALLING SUSPENSION SYSTEMS

A. Install suspension system components in sizes and spacings indicated on Drawings, but not less than those required by referenced installation standards for assembly types and other assembly components indicated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Isolate suspension systems from building structure where they abut or are penetrated by building structure to prevent transfer of loading imposed by structural movement.
- C. Suspend hangers from building structure as follows:
  - 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structural or suspension system.
    - a. Splay hangers only where required to miss obstructions and offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
  - 2. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with locations of hangers required to support standard suspension system members, install supplemental suspension members and hangers in the form of trapezes or equivalent devices.
    - a. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced installation standards.
  - 3. Wire Hangers: Secure by looping and wire tying, either directly to structures or to inserts, eye screws, or other devices and fasteners that are secure and appropriate for substrate, and in a manner that will not cause hangers to deteriorate or otherwise fail.
  - 4. Flat Hangers: Secure to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices and fasteners that are secure and appropriate for structure and hanger, and in a manner that will not cause hangers to deteriorate or otherwise fail.
  - 5. Do not attach hangers to steel roof deck.
  - 6. Do not attach hangers to permanent metal forms. Furnish cast-in-place hanger inserts that extend through forms.
  - 7. Do not attach hangers to rolled-in hanger tabs of composite steel floor deck.
  - 8. Do not connect or suspend steel framing from ducts, pipes, or conduit.
- D. Seismic Bracing: Sway-brace suspension systems with hangers used for support.
- E. Grid Suspension Systems: Attach perimeter wall track or angle where grid suspension systems meet vertical surfaces. Mechanically join main beam and cross-furring members to each other and butt-cut to fit into wall track.
- F. Installation Tolerances: Install suspension systems that are level to within 1/8 inch in 12 feet (3 mm in 3.6 m) measured lengthwise on each member that will receive finishes and transversely between parallel members that will receive finishes.

END OF SECTION 092216

# SECTION 092900 - GYPSUM BOARD

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Interior gypsum board.
- B. Related Requirements:
  - 1. Section 092216 "Non-Structural Metal Framing" for non-structural framing and suspension systems that support gypsum board panels.
  - 2. Section 093013 "Tiling" for cementitious backer units installed as substrates for ceramic tile.

# 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Show location of each item, dimensioned plans and elevations, large-scale details, thicknesses, finishes, joining, attachment devices, relationship of adjoining work and other components.
  - 1. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement.
- C. Samples: For the following products:
  - 1. Aluminum Trim Accessories: Full-size Sample minimum 12-inch- (300-mm-) long for each trim accessory indicated.

# 1.4 DELIVERY, STORAGE AND HANDLING

A. Store materials inside under cover and keep them dry and protected against weather, condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

# 1.5 FIELD CONDITIONS

A. Environmental Limitations: Comply with ASTM C 840 requirements or gypsum board manufacturer's written recommendations, whichever are more stringent.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Do not install paper-faced gypsum panels until installation areas are enclosed and conditioned.
- C. Do not install panels that are wet, those that are moisture damaged, and those that are mold damaged.
  - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
  - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

# PART 2 - PRODUCTS

# 2.1 GYPSUM BOARD, GENERAL

A. Size: Provide maximum lengths and widths available that will minimize joints in each area and that correspond with support system indicated.

# 2.2 INTERIOR GYPSUM BOARD

- A. Manufacturers: Gold Bond XP or equal
- B. Moisture- and Mold-Resistant Gypsum Board: Gold Bond XP with moisture- and mold-resistant core and paper surfaces.
  - 1. Core: 5/8 inch (15.9 mm), Type X mold and moisture resistant core
  - 2. Mold and moisture resistant face paper each side.
  - 3. Long Edges: Tapered.
  - 4. Mold Resistance: ASTM D 3273, score of 10 as rated according to ASTM D 3274.

# 2.3 TRIM ACCESSORIES

- A. Interior Trim: ASTM C 1047.
  - 1. Material: Galvanized or aluminum-coated steel sheet, rolled zinc, or paper-faced galvanized steel sheet.
  - 2. Shapes:
    - a. Cornerbead.
    - b. LC-Bead: J-shaped; exposed long flange receives joint compound.
    - c. L-Bead: L-shaped; exposed long flange receives joint compound.
    - d. U-Bead: J-shaped; exposed short flange does not receive joint compound.

# 2.4 JOINT TREATMENT MATERIALS

- A. General: Comply with ASTM C 475/C 475M.
- B. Joint Tape:
  - 1. Interior Gypsum Board: MESH TYPE.
- C. Joint Compound for Interior Gypsum Board: For each coat use formulation that is compatible with other compounds applied on previous or for successive coats.
  - 1. Prefilling: At open joints and damaged surface areas, use setting-type taping compound.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use setting-type taping compound.
  - a. Use setting-type compound for installing paper-faced metal trim accessories.
- 3. Fill Coat: For second coat, use setting-type, sandable topping compound.
- 4. Finish Coat: For third coat, use drying-type, all-purpose compound.

# 2.5 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards and manufacturer's written recommendations.
- B. Laminating Adhesive: Adhesive or joint compound recommended for directly adhering gypsum panels to continuous substrate.
  - 1. Laminating adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- C. Steel Drill Screws: ASTM C 1002, unless otherwise indicated.
  - 1. Use screws complying with ASTM C 954 for fastening panels to steel members from 0.033 to 0.112 inch (0.84 to 2.84 mm) thick.
- D. Acoustical Joint Sealant: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834. Product effectively reduces airborne sound transmission through perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.
  - 1. <u>Products</u>: Subject to compliance with requirements, provide one of the following:
    - a. Accumetric LLC; BOSS 824 Acoustical Sound Sealant.
    - b. Grabber Construction Products; Acoustical Sealant GSC.
    - c. <u>Pecora Corporation</u>; AC-20 FTR, AIS-919.
    - d. Specified Technologies, Inc.; Smoke N Sound Acoustical Sealant.

e. <u>USG Corporation; SHEETROCK Acoustical Sealant.</u>

2. Acoustical joint sealant shall have a VOC content of 250 g/L or less when calculated

according to 40 CFR 59, Subpart D (EPA Method 24).

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine areas and substrates including welded hollow-metal frames and framing, with Installer present, for compliance with requirements and other conditions affecting performance.
- B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 APPLYING AND FINISHING PANELS, GENERAL

- A. Comply with ASTM C 840.
- B. Install ceiling panels across framing to minimize the number of abutting end joints and to avoid abutting end joints in central area of each ceiling. Stagger abutting end joints of adjacent panels not less than one framing member.
- C. Install panels with face side out. Butt panels together for a light contact at edges and ends with not more than 1/16 inch (1.5 mm) of open space between panels. Do not force into place.
- D. Locate edge and end joints over supports, except in ceiling applications where intermediate supports or gypsum board back-blocking is provided behind end joints. Do not place tapered edges against cut edges or ends. Stagger vertical joints on opposite sides of partitions. Do not make joints other than control joints at corners of framed openings.
- E. Form control and expansion joints with space between edges of adjoining gypsum panels.
- F. Cover both faces of support framing with gypsum panels in concealed spaces (above ceilings, etc.), except in chases braced internally.
  - 1. Unless concealed application is indicated or required for sound, fire, air, or smoke ratings, coverage may be accomplished with scraps of not less than 8 sq. ft. (0.7 sq. m) in area.
  - 2. Fit gypsum panels around ducts, pipes, and conduits.
  - 3. Where partitions intersect structural members projecting below underside of floor/roof slabs and decks, cut gypsum panels to fit profile formed by structural members; allow 1/4- to 3/8-inch- (6.4- to 9.5-mm-) wide joints to install sealant.
- G. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments, except floors. Provide 1/4- to 1/2-inch- (6.4- to 12.7-mm-) wide spaces at these

Re-Bid Set

Issue Date: 06/05/2014

locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.

Architect's Project #: 12.130.09

H. Attachment to Steel Framing: Attach panels so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.

# 3.3 APPLYING INTERIOR GYPSUM BOARD

- A. Install Moisture- and Mold-Resistant Type interior gypsum board at all locations indicated in the drawings.
- B. Single-Layer Application:
  - 1. On ceilings, apply gypsum panels before wall/partition board application to greatest extent possible and at right angles to framing unless otherwise indicated.
  - 2. On partitions/walls, apply gypsum panels vertically (parallel to framing) unless otherwise indicated.
    - a. Stagger abutting end joints not less than one framing member in alternate courses of panels.
  - 3. Fastening Methods: Apply gypsum panels to supports with steel drill screws.

# 3.4 INSTALLING TRIM ACCESSORIES

- A. General: For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.
- B. Control Joints: Install control joints at locations indicated on Drawings.
- C. Interior Trim: Install in the following locations:
  - 1. Cornerbead: Use at outside corners.
  - 2. LC-Bead: Use at exposed panel edges.
  - 3. L-Bead: Use where indicated.
  - 4. U-Bead: Use where indicated.

# 3.5 FINISHING GYPSUM BOARD

- A. General: Treat gypsum board joints, interior angles, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare gypsum board surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.
- B. Prefill open joints and damaged surface areas.
- C. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.

- D. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C 840:
  - 1. Level 1: Ceiling plenum areas, concealed areas, and where indicated.
  - 2. Level 2: Panels that are substrates for tile.
  - 3. Level 3: Not used.
  - 4. Level 4: At panel surfaces that will be exposed to view unless otherwise indicated, and at panel surfaces to receive wall coverings.
    - a. Primer and its application to surfaces are specified in other Section 099123 "Interior Painting."

Issue Date: 06/05/2014

# 3.6 PROTECTION

- A. Protect adjacent surfaces from drywall compound and promptly remove from floors and other non-drywall surfaces. Repair surfaces stained, marred, or otherwise damaged during drywall application.
- B. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.
- C. Remove and replace panels that are wet, moisture damaged, and mold damaged.
  - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
  - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

END OF SECTION 092900

# SECTION 093013 - TILING

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# 1.2 SUMMARY

- A. Section Includes:
  - 1. Porcelain tile.
  - 2. Mosaic tile.
  - 3. Waterproof membrane.
  - 4. Metal edge strips.
- B. Related Requirements:
  - 1. Section 079200 "Joint Sealants" for sealing of expansion, contraction, control, and isolation joints in tile surfaces.

# 1.3 DEFINITIONS

- A. General: Definitions in the ANSI A108 series of tile installation standards and in ANSI A137.1 apply to Work of this Section unless otherwise specified.
- B. ANSI A108 Series: ANSI A108.01, ANSI A108.02, ANSI A108.1A, ANSI A108.1B, ANSI A108.1C, ANSI A108.4, ANSI A108.5, ANSI A108.6, ANSI A108.8, ANSI A108.9, ANSI A108.10, ANSI A108.11, ANSI A108.12, ANSI A108.13, ANSI A108.14, ANSI A108.15, ANSI A108.16, and ANSI A108.17, which are contained in its "Specifications for Installation of Ceramic Tile."

# 1.4 PREINSTALLATION MEETINGS

# 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Show locations of each type of tile and tile pattern. Show widths, details, and locations of expansion, contraction, control, and isolation joints in tile substrates and finished tile surfaces.
- C. Samples for Verification:

Re-Bid Set Issue Date: 06/05/2014

1. Full-size units of each type and composition of tile and for each color and finish required.

Architect's Project #: 12.130.09

2. Metal edge strips in 6-inch (150-mm) lengths.

# 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Master Grade Certificates: For each shipment, type, and composition of tile, signed by tile manufacturer and Installer.
- C. Product Certificates: For each type of product.
- D. Product Test Reports: For tile-setting and -grouting products and certified porcelain tile.

# 1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match and are from same production runs as products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Tile and Trim Units: Furnish quantity of full-size units equal to 3 percent of amount installed for each type, composition, color, pattern, and size indicated.
  - 2. Grout: Furnish quantity of grout equal to 3 percent of amount installed for each type, composition, and color indicated.

# 1.8 QUALITY ASSURANCE

- A. Installer Qualifications:
  - 1. Installer is a five-star member of the National Tile Contractors Association.
  - 2. Installer's supervisor for Project holds the International Masonry Institute's Foreman Certification.
  - 3. Installer employs Ceramic Tile Education Foundation Certified Installers or installers recognized by the U.S. Department of Labor as Journeyman Tile Layers.

# 1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver and store packaged materials in original containers with seals unbroken and labels intact until time of use. Comply with requirements in ANSI A137.1 for labeling tile packages.
- B. Store tile and cementitious materials on elevated platforms, under cover, and in a dry location.
- C. Store aggregates where grading and other required characteristics can be maintained and contamination can be avoided.
- D. Store liquid materials in unopened containers and protected from freezing.

# 1.10 FIELD CONDITIONS

A. Environmental Limitations: Do not install tile until construction in spaces is complete and ambient temperature and humidity conditions are maintained at the levels indicated in referenced standards and manufacturer's written instructions.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# PART 2 - PRODUCTS

# 2.1 PRODUCTS, GENERAL

- A. ANSI Ceramic Tile Standard: Provide tile that complies with ANSI A137.1 for types, compositions, and other characteristics indicated.
  - 1. Provide tile complying with Standard grade requirements unless otherwise indicated.
- B. ANSI Standards for Tile Installation Materials: Provide materials complying with ANSI A108.02, ANSI standards referenced in other Part 2 articles, ANSI standards referenced by TCNA installation methods specified in tile installation schedules, and other requirements specified.
- C. Factory Blending: For tile exhibiting color variations within ranges, blend tile in factory and package so tile units taken from one package show same range in colors as those taken from other packages and match approved Samples.
- D. Mounting: For factory-mounted tile, provide back- or edge-mounted tile assemblies as standard with manufacturer unless otherwise indicated.

# 2.2 TILE PRODUCTS

- A. Ceramic Tile Type PT-1: Glazed porcelain tile.
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by the following:
    - a. <u>Emil Ceramica Series: Stone Box Concept</u>
  - 2. Certification: Tile certified by the Porcelain Tile Certification Agency.
  - 3. Face Size: 5 7/8" by 35 7/16" (15MM x 90MM) Refer to drawings for tile cut pattern
  - 4. Face Size Variation: Rectified.
  - 5. Thickness: 10.5mm
  - 6. Face: Natural Rectified
  - 7. Tile Color, Glaze, and Pattern: Bright Grey
  - 8. Grout Color: As specified in drawings
  - 9. Trim Units: Coordinated with sizes and coursing of adjoining flat tile where applicable.
- B. Ceramic Tile Type PT-2: Glazed porcelain tile.
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by the following:
    - a. ROCA TILE GROUP SERIES: ANTIBES

- 2. Certification: Tile certified by the Porcelain Tile Certification Agency.
- 3. Face Size: 10" by 28"
- 4. Thickness: 3/8"
- 5. Face: Undulated surface Satin finish.
- 6. Tile Color, Glaze, and Pattern: Blanco
- 7. Grout Color: As specified in drawings.
- 8. Trim Units: Coordinated with sizes and coursing of adjoining flat tile where applicable.

Issue Date: 06/05/2014

# C. Ceramic Tile Type PT-3: Glazed porcelain tile. (ALTERNATE #1)

- 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by the following:
  - a. Mosa Tiles Series: Greys
- 2. Certification: Tile certified by the Porcelain Tile Certification Agency.
- 3. Face Size: 12" by 12"
- 4. Product Code: V
- 5. Face Size Variation: Rectified.
- 6. Face: Pattern matt
- 7. Tile Color, Glaze, and Pattern: 225 Light cool grey
- 8. Grout Color: As specified in drawings.
- 9. Trim Units: Coordinated with sizes and coursing of adjoining flat tile where applicable.

# D. Ceramic Tile Type PT-4: Glazed porcelain tile. (ALTERNATE #1)

- 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by the following:
  - a. Mosa Tiles Series: Greys
- 2. Certification: Tile certified by the Porcelain Tile Certification Agency.
- 3. Face Size: 12" by 12"
- 4. Product Code: T
- 5. Face Size Variation: Rectified.
- 6. Thickness: 3/8"
- 7. Face: Pattern matt
- 8. Style: Stair tread (straight edge)
- 9. Tile Color, Glaze, and Pattern: 225 Light cool grey
- 10. Grout Color: As specified in drawings.
- 11. Trim Units: Coordinated with sizes and coursing of adjoining flat tile where applicable.

# E. Mosaic Tile Type MT-1:

- 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by the following:
  - a. <u>Bedrosians Series: Eclipse</u>
- 2. Certification: Tile certified by the Porcelain Tile Certification Agency.
- 3. Face Size: 12" by 12" sheets
- 4. Face Size Variation: Rectified.
- 5. Thickness: 3/8"
- 6. Style: Linear glass / stone blend mosaic
- 7. Item #: GLSECPLNR-ET

Re-Bid Set

Issue Date: 06/05/2014

- 8. Grout Color: As specified in drawings.
- 9. Trim Units: Coordinated with sizes and coursing of adjoining flat tile where applicable.

Architect's Project #: 12.130.09

# 2.3 TILE BACKING PANELS (ALTERNATE #1)

- A. Cementitious Backer Units: ANSI A118.9 or ASTM C 1325, Type A, in maximum lengths available to minimize end-to-end butt joints
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by USG Corporation or of complying products by one of the following:
    - a. C-Cure
    - b. Custom Building Products
  - 2. Thickness: 3/8, 1/2 and 5/8 inch.

# 2.4 WATERPROOF MEMBRANE FOR SHOWER FLOORS

- A. General: Manufacturer's standard product that complies with ANSI A118.10 and is recommended by the manufacturer for the applications indicated. Include reinforcement and accessories recommended by manufacturer.
- B. Fabric-Reinforced, Fluid-Applied Membrane: System consisting of liquid-latex rubber or elastomeric polymer and continuous fabric reinforcement.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide <u>Laticrete International, Inc.</u>; Laticrete 9235 Waterproof Membrane or approved equal.

# 2.5 WATERPROOF MEMBRANE FOR SHOWER WALLS

- A. General: Manufacturer's standard product that complies with ANSI A118.10 and is recommended by the manufacturer for the application indicated. Include taped corners and other accessories recommended by manufacturer.
- B. Fluid-Applied Membrane: Single component, self-curing liquid rubber polymer.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide <u>Laticrete International, Inc.</u>; Hydro Ban or approved equal.

# 2.6 SETTING MATERIALS

- A. Latex-Portland Cement Mortar (Thinset): ANSI A118.4.
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by Laticrete International, Inc. or of complying products by one of the following:
    - a. Custom Building Products
    - b. MAPEI Corporation
  - 2. For wall applications, provide mortar that complies with requirements for nonsagging mortar in addition to the other requirements in ANSI A118.4.

# 2.7 GROUT MATERIALS

- A. High-Performance Tile Grout: ANSI A118.7.
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by Laticrete International, Inc. or of complying products by one of the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- a. Custom Building Products.
- b. MAPEI Corporation.
- B. Water-Cleanable Epoxy Grout: ANSI A118.3.
  - 1. <u>Basis-of-Design Product</u>: Subject to compliance with requirements, provide <u>Laticrete International, Inc.</u>; SpectraLOCK PRO Premium Grout, or approved equal.

# 2.8 MISCELLANEOUS MATERIALS

- A. Trowelable Underlayments and Patching Compounds: Latex-modified, portland cement-based formulation provided or approved by manufacturer of tile-setting materials for installations indicated.
- B. Metal Trim: Prefabricated stainless steel shapes and profiles designed specifically for the applications indicated; height to match tile and setting-bed thickness.
  - 1. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by Schluter Systems L.P. or one of the following:
    - a. Ceramic Tool Company, Inc.
  - 2. Transition strips:
    - a. Carpet to tile: Reno-TK MTK100
    - b. Wall tile to tile corner: Rondec, RO100E
    - c. Wall tile to other material: Rondec Step, 1 ½", RO100 L46AE
- C. Tile Cleaner: A neutral cleaner capable of removing soil and residue without harming tile and grout surfaces, specifically approved for materials and installations indicated by tile and grout manufacturers.
- D. Grout Sealer: Manufacturer's standard product for sealing grout joints and that does not change color or appearance of grout.
- E. Mix mortars and grouts to comply with referenced standards and mortar and grout manufacturers' written instructions.
- F. Add materials, water, and additives in accurate proportions.
- G. Obtain and use type of mixing equipment, mixer speeds, mixing containers, mixing time, and other procedures to produce mortars and grouts of uniform quality with optimum performance characteristics for installations indicated.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions where tile will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
  - 1. Verify that substrates for setting tile are firm; dry; clean; free of coatings that are incompatible with tile-setting materials, including curing compounds and other substances that contain soap, wax, oil, or silicone; and comply with flatness tolerances required by ANSI A108.01 for installations indicated.
  - 2. Verify that concrete substrates for tile installed with thinset mortar comply with surface finish requirements in ANSI A108.01 for installations indicated.
    - a. Verify that surfaces that received a steel trowel finish have been mechanically scarified.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- b. Verify that protrusions, bumps, and ridges have been removed by sanding or grinding.
- 3. Verify that installation of grounds, anchors, recessed frames, electrical and mechanical units of work, and similar items located in or behind tile has been completed.
- 4. Verify that joints and cracks in tile substrates are coordinated with tile joint locations; if not coordinated, adjust joint locations in consultation with Architect.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 PREPARATION

- A. Fill cracks, holes, and depressions in concrete substrates for tile floors installed with thinset mortar with trowelable leveling and patching compound specifically recommended by tile-setting material manufacturer.
- B. Where indicated, prepare substrates to receive waterproofing by applying a reinforced mortar bed that complies with ANSI A108.1A and is sloped 1/4 inch per foot (1:50) toward drains.
- C. Blending: For tile exhibiting color variations, verify that tile has been factory blended and packaged so tile units taken from one package show same range of colors as those taken from other packages and match approved Samples. If not factory blended, either return to manufacturer or blend tiles at Project site before installing.

#### 3.3 TILE INSTALLATION

A. Comply with 2011 TCNA's "Handbook for Ceramic, Glass, and Stone Tile Installation" for TCNA installation methods specified in tile installation schedules. Comply with parts of the ANSI A108 series "Specifications for Installation of Ceramic Tile" that are referenced in TCNA installation methods, specified in tile installation schedules, and apply to types of setting and grouting materials used.

1. For the following installations, follow procedures in the ANSI A108 Series of tile installation standards for providing 95 percent mortar coverage:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- a. Tile floors in wet areas.
- B. Extend tile work into recesses and under or behind equipment and fixtures to form complete covering without interruptions unless otherwise indicated. Terminate work neatly at obstructions, edges, and corners without disrupting pattern or joint alignments.
- C. Accurately form intersections and returns. Perform cutting and drilling of tile without marring visible surfaces. Carefully grind cut edges of tile abutting trim, finish, or built-in items for straight aligned joints. Fit tile closely to electrical outlets, piping, fixtures, and other penetrations so plates, collars, or covers overlap tile.
- D. Provide manufacturer's standard trim shapes where necessary to eliminate exposed tile edges.
- E. Jointing Pattern: Lay tile in running bond pattern unless otherwise indicated. Lay out tile work and center tile fields in both directions in each space or on each wall area. Lay out tile work to minimize the use of pieces that are less than half of a tile. Provide uniform joint widths unless otherwise indicated.
  - 1. For tile mounted in sheets, make joints between tile sheets same width as joints within tile sheets so joints between sheets are not apparent in finished work.
  - 2. Where adjoining tiles on floor, base, walls, or trim are specified or indicated to be same size, align joints.
  - 3. Where tiles are specified or indicated to be whole integer multiples of adjoining tiles on floor, base, walls, or trim, align joints unless otherwise indicated.
- F. Joint Widths: Unless otherwise indicated, install tile with the following joint widths:
  - 1. All Tiles: 1/8".
- G. Lay out tile wainscots to dimensions indicated or to next full tile beyond dimensions indicated. Align wall and floor tiles to the maximum extent possible.
- H. Expansion Joints: Provide expansion joints and other sealant-filled joints, including control, contraction, and isolation joints, where indicated. Form joints during installation of setting materials, mortar beds, and tile. Do not saw-cut joints after installing tiles.
  - 1. Where joints occur in concrete substrates, locate joints in tile surfaces directly above them.
- I. Metal Edge Strips: Install where exposed edge of tile intersect outside corners.

# 3.4 TILE BACKING PANEL INSTALLATION

A. Install panels and treat joints according to ANSI A108.11 and manufacturer's written instructions for type of application indicated. Use latex-portland cement mortar for bonding material unless otherwise directed in manufacturer's written instructions.

# 3.5 WATERPROOFING INSTALLATION

A. Install waterproofing to comply with ANSI A108.13 and manufacturer's written instructions to produce waterproof membrane of uniform thickness and bonded securely to substrate.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Do not install tile or setting materials over waterproofing until waterproofing has cured and been tested to determine that it is watertight.
- C. Test Concession waterproofing and drainage fittings for leaks before commencing tile work.
- D. Test Shower receptor and drainage fitting for leaks before commencing tile work.

# 3.6 ADJUSTING AND CLEANING

- A. Remove and replace tile that is damaged or that does not match adjoining tile. Provide new matching units, installed as specified and in a manner to eliminate evidence of replacement.
- B. Cleaning: On completion of placement and grouting, clean all ceramic tile surfaces so they are free of foreign matter.
  - 1. Remove grout residue from tile as soon as possible.
  - 2. Clean grout smears and haze from tile according to tile and grout manufacturer's written instructions but no sooner than 10 days after installation. Use only cleaners recommended by tile and grout manufacturers and only after determining that cleaners are safe to use by testing on samples of tile and other surfaces to be cleaned. Protect metal surfaces and plumbing fixtures from effects of cleaning. Flush surfaces with clean water before and after cleaning.

# 3.7 PROTECTION

- A. Protect installed tile during construction period to prevent staining, damage, and wear. If recommended by tile manufacturer, apply coat of neutral protective cleaner to completed tile walls and floors.
- B. Before final inspection, remove protective coverings and rinse neutral protective cleaner from tile surfaces.

# 3.8 INTERIOR TILE INSTALLATION SCHEDULE

- A. Interior Floor Installations, Concrete Subfloor:
  - 1. Tile Installation F113: Thin-set mortar; TCNA F113.
    - a. Tile Type: Porcelain Tile
    - b. Thin-Set Mortar: Latex- portland cement mortar.
    - c. Grout: Epoxy Grout (Laticrete SpectraLOCK PRO Premium Grout or approved equal).
- B. Interior Wall Installations, Masonry or Concrete:
  - 1. Tile Installation W202E: Thin-set mortar; TCNA W202E.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- a. Tile Type: Porcelain Tile and Mosaic Tile
- b. Thin-Set Mortar: Latex- portland cement mortar.
- c. Grout: Epoxy Grout (Laticrete SpectraLOCK PRO Premium Grout or approved equal).
- C. Shower Floor and Wall Installations, Concrete or Masonry:
  - 1. Tile Installation B421: Thin-set mortar on waterproof membrane; TCNA B421.
    - a. Tile Type: Porcelain Tile
    - b. Membrane: Continuous Waterproof membrane <u>Laticrete International, Inc.</u>; Hydro Ban
    - c. Thin-Set Mortar: Latex-portland cement mortar.
    - d. Grout: Epoxy Grout (Laticrete SpectraLOCK PRO Premium Grout or approved equal).
- D. Tub Deck installations, Backer board on metal stud framing:
  - 1. Tile Installation W244C: Thin-set mortar on waterproof membrane; TCNA W244C.
    - a. Tile Type: Porcelain Tile
    - b. Membrane: Continuous Waterproof membrane <u>Laticrete International, Inc.</u>; Hydro Ban
    - c. Thin-Set Mortar: Latex-portland cement mortar.
    - d. Grout: Epoxy Grout (Laticrete SpectraLOCK PRO Premium Grout or approved equal).

END OF SECTION 093013

# SECTION 095123 - ACOUSTICAL CEILING PANELS

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

# 1.2 SUMMARY

- A. Section Includes:
  - 1. Acoustical tiles for ceilings.
  - 2. Suspension systems.
  - 3. Open Cell metal ceiling with wood look veneer.
- B. Products furnished, but not installed under this Section, include anchors, clips, and other ceiling attachment devices to be cast in concrete.

# 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each exposed product and for each color and texture specified, 6-inches- (150-mm-) in size.
- C. Samples for Verification: For each component indicated and for each exposed finish required, prepared on Samples of size indicated below.
  - 1. Acoustical Tile: 6" x 6" Samples of each type, color, pattern, and texture.
  - 2. Exposed Moldings and Trim: Set of 6-inch- (150-mm-) long Samples of each type and color.

# 1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
  - 1. Ceiling suspension-system members.
  - 2. Method of attaching hangers to building structure.
    - a. Furnish layouts for cast-in-place anchors, clips, and other ceiling attachment devices whose installation is specified in other Sections.
  - 3. Size and location of initial access modules for acoustical tile.
  - 4. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 5. Minimum Drawing Scale: 1/8 inch = 1 foot (1:96).
- B. Qualification Data: For testing agency.
- C. Product Test Reports: For each acoustical tile ceiling, for tests performed by manufacturer and witnessed by a qualified testing agency.
- Evaluation Reports: For each acoustical tile ceiling suspension system and anchor and fastener D. type, from ICC-ES.
- E. Field quality-control reports.

#### 1.5 **CLOSEOUT SUBMITTALS**

Maintenance Data: For finishes to include in maintenance manuals. A.

#### 1.6 MAINTENANCE MATERIAL SUBMITTALS

- Furnish extra materials that match products installed and that are packaged with protective A. covering for storage and identified with labels describing contents.
  - Acoustical Ceiling Units: Full-size tiles equal to 2 percent of quantity installed. 1.
  - 2. Suspension-System Components: Quantity of each concealed grid and exposed component equal to 2 percent of quantity installed.

#### 1.7 **QUALITY ASSURANCE**

Testing Agency Qualifications: Qualified according to the National Voluntary Laboratory A. Accreditation Program (NVLAP) for testing indicated.

#### 1.8 DELIVERY, STORAGE, AND HANDLING

- Deliver acoustical tiles, suspension-system components, and accessories to Project site in A. original, unopened packages and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.
- В. Before installing acoustical tiles, permit them to reach room temperature and a stabilized moisture content.
- C. Handle acoustical tiles carefully to avoid chipping edges or damaging units in any way.

#### 1.9 FIELD CONDITIONS

Environmental Limitations: Do not install acoustical tile ceilings until spaces are enclosed and A. weatherproof, wet work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

1. Pressurized Plenums: Operate ventilation system for not less than 48 hours before beginning acoustical tile ceiling installation.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

when occupied for its intended use.

- A. Seismic Performance: Acoustical ceiling shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
  - 1. Site is classified as a Seismic Design Category "C".
- B. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  - 1. Flame-Spread Index: Comply with ASTM E 1264 for Class A materials.
  - 2. Smoke-Developed Index: 50 or less.

# 2.2 ACOUSTICAL TILES, GENERAL

- A. Source Limitations:
  - 1. Acoustical Ceiling Tile: Obtain each type from single source from single manufacturer.
  - 2. Suspension System: Obtain each type from single source from single manufacturer.
- B. Source Limitations: Obtain each type of acoustical ceiling tile and supporting suspension system from single source from single manufacturer.
- C. Acoustical Tile Standard: Provide manufacturer's standard tiles of configuration indicated that comply with ASTM E 1264 classifications as designated by types, patterns, acoustical ratings, and light reflectances unless otherwise indicated.
  - 1. Mounting Method for Measuring NRC: Type E-400; plenum mounting in which face of test specimen is 15-3/4 inches (400 mm) away from test surface according to ASTM E 795.
- D. Acoustical Tile Colors and Patterns: Match appearance characteristics indicated for each product type.

# 2.3 ACOUSTICAL TILES

- A. <u>Manufacturers:</u> Subject to compliance with requirements, Provide Products by USG Interiors, Inc. or of complying products by one of the following:
  - 1. Armstrong World Industries, Inc.
  - 2. <u>CertainTeed Corporation</u>.
- B. Acoustic Ceiling Tiles:
  - 1. ACP-1: Eclipse ClimaPlus

Issue Date: 06/05/2014

- a. Color: White.
- b. LR: Not less than 0.85.
- c. NRC: Not less than 0.70.
- d. CAC: Not less than 35.
- e. Edge/Joint Detail: Tegular
- f. Thickness: 3/4 inch (19 mm).
- g. Modular Size: 24 by 24 inches (610 by 610 mm).
- 2. ACP-2: NOT USED
- 3. ACP-3: Vinyl Coated Sheetrock ClimaPlus
  - a. Color: White.
  - b. LR: Not less than .77.
  - c. CAC: Not less than 35.
  - d. Edge/Joint Detail: Square edge
  - e. Thickness: 1/2" (13 mm).

Modular Size: 24 by 24 inches (610 by 610 mm).

# 2.4 METAL SUSPENSION SYSTEMS, GENERAL

- A. Metal Suspension-System Standard: Provide manufacturer's standard metal suspension systems of types, structural classifications, and finishes indicated that comply with applicable requirements in ASTM C 635/C 635M.
  - 1. High-Humidity Finish: Comply with ASTM C 635/C 635M requirements for "Coating Classification for Severe Environment Performance" where high-humidity finishes are indicated. (All spaces without HVAC with door direct to exterior— Group restrooms, custodial, data, etc.)
- B. Attachment Devices: Size for five times the design load indicated in ASTM C 635/C 635M, Table 1, "Direct Hung," unless otherwise indicated. Comply with seismic design requirements.
- C. Wire Hangers, Braces, and Ties: Provide wires complying with the following requirements:
  - 1. Zinc-Coated, Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
  - 2. Size: Select wire diameter so its stress at three times hanger design load (ASTM C 635/C 635M, Table 1, "Direct Hung") will be less than yield stress of wire, but provide not less than 0.106-inch- (2.69-mm-) diameter wire.
- D. Hanger Rods: Mild steel, zinc coated or protected with rust-inhibitive paint.
- E. Seismic Clips: Manufacturer's standard seismic clips designed and spaced to secure acoustical panels in place.

# 2.5 METAL SUSPENSION SYSTEM

A. <u>Manufacturers:</u> Subject to compliance with requirements, Provide Products by USG Interiors, Inc., Donn DX/DXL 15/16" or of complying products by one of the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. <u>Armstrong World Industries, Inc.</u>
- B. Direct-Hung, Double-Web Suspension System: Main and cross runners roll formed from and capped with cold-rolled steel sheet, prepainted, electrolytically zinc coated, or hot-dip galvanized according to ASTM A 653/A 653M, G30 (Z90) coating designation.
  - 1. Structural Classification: Intermediate-duty system.
  - 2. Access: Upward and end pivoted or side pivoted, with initial access openings of size indicated below and located throughout ceiling within each module formed by main and cross runners, with additional access available by progressively removing remaining acoustical tiles.
- C. Color: Metal suspension system color to match color of tile.

# 2.6 METAL EDGE MOLDINGS AND TRIM

- A. <u>Manufacturers:</u> Subject to compliance with requirements, Provide Products by USG Interiors, Inc., 7/8" wall molding or of complying products by one of the following:
  - 1. Armstrong World Industries, Inc.
- B. Roll-Formed, Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations complying with seismic design requirements; formed from sheet metal of same material, finish, and color as that used for exposed flanges of suspension-system runners.
  - 1. Provide manufacturer's standard edge moldings that fit acoustical tile edge details and suspension systems indicated and that match width and configuration of exposed runners unless otherwise indicated.
  - 2. Baked-Enamel or Powder-Coat Finish: Minimum dry film thickness of 1.5 mils (0.04 mm). Comply with ASTM C 635/C 635M and coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.
    - a. Color: Metal edge moldings and trim to match color of tile.

# 2.7 OPEN CELL METAL CEILING

- A. Provide "Luxalon" Open Cell Frame Ceiling System manufactured by Hunter Douglas Architectural Products or of complying products by one of the following:
  - 1. Armstrong World Industries, Inc.
- B. Open Cell Ceiling System:
  - 1. Material / thickness: Roll-formed 0.020 inch aluminum.

Issue Date: 06/05/2014

- 2. Blade size: 6 inch high U-shaped section with 2 inch wide exposed face width and 3/32 inch top return flange.
- 3. Cell module / pattern dimensions: Square: 12 inches by 12 inches.
- 4. Structural Classification: Heavy Duty, comply with Seismic Design Category "D".

# C. Trim And Accessory Components

- 1. Splice Connectors: Manufacturer's standard main runner splice connectors and splice hanger clips.
- 2. Fascia / Soffit Panels: Custom 0.032 inch aluminum panels fabricated to fit irregular, angled, and/or stepped ceiling conditions.
- 3. Perimeter trim: Provide manufacturer's wall moulding for wall to wall floating trim application.

# D. FINISHES

- 1. Finish: Factory applied polyester baked enamel.
  - a. Color: Cherry 8742

# 2.8 MISCELLANEOUS MATERIALS

A. Hold Down Clips: Provide hold down clips for tiles in airlocks and/or adjacent to exterior doors for 6'-0" from door and locker rooms.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, including structural framing and substrates to which acoustical tile ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine acoustical tiles before installation. Reject acoustical tiles that are wet, moisture damaged, or mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 PREPARATION

A. Testing Substrates: Before installing adhesively applied tiles on wet-placed substrates such as cast-in-place concrete or plaster, test and verify that moisture level is below tile manufacturer's recommended limits.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. Measure each ceiling area and establish layout of acoustical tiles to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width tiles at borders, and comply with layout shown on reflected ceiling plans.

# 3.3 INSTALLATION OF SUSPENDED ACOUSTICAL TILE CEILINGS

- A. General: Install acoustical panel ceilings to comply with ASTM C 636/C 636M and seismic design requirements indicated, according to manufacturer's written instructions and CISCA's "Ceiling Systems Handbook."
- B. Suspend ceiling hangers from building's structural members and as follows:
  - 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
  - 2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
  - 3. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension-system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices.
  - 4. Secure wire hangers to ceiling suspension members and to supports above with a minimum of three tight turns. Connect hangers directly either to structures or to inserts, eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
  - 5. Secure flat, angle, channel, and rod hangers to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices that are secure and appropriate for both the structure to which hangers are attached and the type of hanger involved. Install hangers in a manner that will not cause them to deteriorate or fail due to age, corrosion, or elevated temperatures.
  - 6. Do not support ceilings directly from permanent metal forms or floor deck. Fasten hangers to cast-in-place hanger inserts, postinstalled mechanical or adhesive anchors, or power-actuated fasteners that extend through forms into concrete.
  - 7. When steel framing does not permit installation of hanger wires at spacing required, install carrying channels or other supplemental support for attachment of hanger wires.
  - 8. Do not attach hangers to steel deck tabs.
  - 9. Do not attach hangers to steel roof deck. Attach hangers to structural members.
  - 10. Space hangers not more than 48 inches (1200 mm) o.c. along each member supported directly from hangers unless otherwise indicated; provide hangers not more than 8 inches (200 mm) from ends of each member.
  - 11. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards and publications.

- C. Install edge moldings and trim of type indicated at perimeter of acoustical tile ceiling area and
  - 1. Screw attach moldings to substrate at intervals not more than 16 inches (400 mm) o.c. and not more than 3 inches (75 mm) from ends, leveling with ceiling suspension system to a tolerance of 1/8 inch in 12 feet (3.2 mm in 3.6 m). Miter corners accurately and connect securely.

Issue Date: 06/05/2014

2. Do not use exposed fasteners, including pop rivets, on moldings and trim.

where necessary to conceal edges of acoustical tiles.

- D. Install suspension-system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- E. Install acoustical panels with undamaged edges and fit accurately into suspension-system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide a neat, precise fit.
  - 1. For square-edged panels, install panels with edges fully hidden from view by flanges of suspension-system runners and moldings.
  - 2. For tegular-edged panels, cut panel edges to match tegular edge profile, touch up color to match factory fabricated edges. Install panels with tegular edge exposed to view with consistent reveal on all tile edges.
  - 3. Install hold-down clips in areas indicated, in areas required by authorities having jurisdiction, and for fire-resistance ratings; space as recommended by panel manufacturer's written instructions unless otherwise indicated.

# 3.4 INSTALLATION OF OPEN CELL METAL CEILING

- A. Install metal cell ceiling system in accordance with manufacturer's installation instructions, submittals, applicable industry standards, and governing regulatory requirements for the work.
- B. Suspension System Installation:
  - 1. Install suspension system to comply with requirements of ASTM C-636.
  - 2. Support hangers securely from building structure using hanger wires or rods directly attached to structure, or to inserts or other devices with eye-screws, by looping and wiretying.
  - 3. Fabricate suspension system by forming into a two directional pattern with main runners at 48 inches on center, and cross runners at (12), (24), (48) inches on center as appropriate for selected module size.
- C. Install ceiling grid and trim pieces with neat, tight joints and to comply with approved details.
  - 1. Install grid perpendicular to main runners. Scribe and cut grid components as necessary to fit at borders and other penetrations.
- D. Install air distribution devices and lighting fixtures at indicated locations.
  - 1. Support devices and fixtures from building structure above, independent from ceiling suspension system.

e-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- E. Plenum Access:
  - 1. Access plenum by removing panels.
- F. Install edge moulding at perimeter of metal cell ceiling system and at other locations where required to conceal edges of ceiling.

# 3.5 CLEANING ACOUSTICAL CEILING TILES

A. Clean exposed surfaces of acoustical tile ceilings, including trim and edge moldings. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage. Remove and replace tiles and other ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

# 3.6 CLEANING LINEAR METAL CEILING / OPEN CELL METAL CEILING

- A. Adjust components to provide uniform tolerances.
- B. Replace all ceiling panels that are scratched, dented or otherwise damaged.
- C. Clean exposed surfaces with non-solvent, non-abrasive commercial type cleaner.

# 3.7 FIELD QUALITY CONTROL

- A. Special Inspections: Owner will engage a qualified special inspector to perform the following special inspections:
  - 1. Compliance of seismic design.
- B. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections and prepare test reports.
- C. Perform the following tests and inspections of completed installations of acoustical panel ceiling hangers and anchors and fasteners in successive stages. Do not proceed with installations of acoustical panel ceiling hangers for the next area until test results for previously completed installations show compliance with requirements.
  - 1. Extent of Each Test Area: When installation of ceiling suspension systems on each floor has reached 20 percent completion but no panels have been installed.
    - a. Within each test area, testing agency will select one of every 10 power-actuated fasteners and postinstalled anchors used to attach hangers to concrete and will test them for 200 lbf (890 N) of tension; it will also select one of every two postinstalled anchors used to attach bracing wires to concrete and will test them for 440 lbf (1957 N) of tension.
    - b. When testing discovers fasteners and anchors that do not comply with requirements, testing agency will test those anchors not previously tested until 20 pass consecutively and then will resume initial testing frequency.

Issue Date: 06/05/2014

- D. Acoustical panel ceiling hangers and anchors and fasteners will be considered defective if they do not pass tests and inspections.
- E. Prepare test and inspection reports.

# 3.8 CLEANING

A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension-system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 095123

# SECTION 096513 - RESILIENT BASE AND ACCESSORIES

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Resilient base.

# 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each exposed product and for each color and texture specified, not less than 12 inches (300 mm) long.
- C. Samples for Initial Selection: For each type of product indicated.
- D. Samples for Verification: For each type of product indicated and for each color, texture, and pattern required in manufacturer's standard-size Samples, but not less than 12 inches (300 mm) long.
- E. Product Schedule: For resilient base and accessory products.

# 1.4 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Furnish not less than 10 linear feet (3 linear m) for every 500 linear feet (150 linear m) or fraction thereof, of each type, color, pattern, and size of resilient product installed.

# 1.5 DELIVERY, STORAGE, AND HANDLING

A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F (10 deg C) or more than 90 deg F (32 deg C).

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Issue Date: 06/05/2014

# 1.6 FIELD CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F (21 deg C) or more than 95 deg F (35 deg C), in spaces to receive resilient products during the following time periods:
  - 1. 48 hours before installation.
  - 2. During installation.
  - 3. 48 hours after installation.
- B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F (13 deg C) or more than 95 deg F (35 deg C).
- C. Install resilient products after other finishing operations, including painting, have been completed.

# PART 2 - PRODUCTS

# 2.1 RUBBER BASE

- A. <u>Manufacturers:</u> Subject to compliance with requirements, provide rubber base by Johnsonite or, subject to compliance, products by one of the following:
  - 1. Burke Mercer Flooring Products; a division of Burke Industries Inc.
  - 2. <u>Flexco</u>.
  - 3. Roppe Corporation, USA.
- B. Product Standard: ASTM F 1861, Type TS (rubber, vulcanized thermoset), Group I (solid, homogeneous).
  - 1. Style and Location:
    - a. Style B, Cove: Provide in all floor areas as scheduled.
- C. Thickness: 0.125 inch (3.2 mm).
- D. Height: 4 inches (102 mm).
- E. Lengths: Coils in manufacturer's standard length.
- F. Outside Corners: Job formed.
- G. Inside Corners: Job formed.
- H. Colors: As selected by Architect from full range of industry colors.

Issue Date: 06/05/2014

# 2.2 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.
  - 1. Adhesives shall have a VOC content of 50 g/L or less except that adhesive for rubber stair treads shall have a VOC content of 60 g/L or less.
- C. Metal Edge Strips: Extruded aluminum with mill finish of width shown, of height required to protect exposed edges of flooring, and in maximum available lengths to minimize running joints.
- D. Floor Polish: Provide protective, liquid floor-polish products recommended by resilient stair-tread manufacturer.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
  - 1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
  - 1. Installation of resilient products indicates acceptance of surfaces and conditions.

# 3.2 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.
- B. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- C. Do not install resilient products until they are the same temperature as the space where they are to be installed.
  - 1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.

Issue Date: 06/05/2014

D. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

# 3.3 RESILIENT BASE INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient base.
- B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.
- C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.
- D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
- E. Do not stretch resilient base during installation.
- F. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient base with manufacturer's recommended adhesive filler material.

# G. Job-Formed Corners:

- 1. Outside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 6 inches (152 mm) in length.
  - a. Form without producing discoloration (whitening) at bends.
- 2. Inside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches (76 mm) in length.
  - a. Miter or cope corners to minimize open joints.

# 3.4 RESILIENT ACCESSORY INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient accessories.
- B. Resilient Molding Accessories: Butt to adjacent materials and tightly adhere to substrates throughout length of each piece. Install reducer strips at edges of floor covering that would otherwise be exposed.

# 3.5 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.
- B. Perform the following operations immediately after completing resilient-product installation:

Architect's Project #: 12.130.09
Addition

Issue Date: 06/05/2014

- 1. Remove adhesive and other blemishes from exposed surfaces.
- 2. Sweep and vacuum horizontal surfaces thoroughly.
- 3. Damp-mop horizontal surfaces to remove marks and soil.
- C. Protect resilient products from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.
- D. Floor Polish: Remove soil, visible adhesive, and surface blemishes from resilient stair treads before applying liquid floor polish.
- E. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION 096513

# SECTION 099113 - EXTERIOR PAINTING

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# 1.2 SUMMARY

- A. Section includes surface preparation and the application of paint systems on the following exterior substrates:
  - 1. Concrete.
  - 2. Brick Masonry.
  - 3. Galvanized metal, non-galvanized metal and steel.

# B. Related Requirements:

- 1. Section 051200 "Structural Steel Framing" for shop priming of metal substrates with primers specified in this Section.
- 2. Section 099123 "Interior Painting" for surface preparation and the application of paint systems on interior substrates.

# 1.3 DEFINITIONS

- A. Gloss Level 1: Not more than 5 units at 60 degrees and 10 units at 85 degrees, according to ASTM D 523.
- B. Gloss Level 3: 10 to 25 units at 60 degrees and 10 to 35 units at 85 degrees, according to ASTM D 523.
- C. Gloss Level 4: 20 to 35 units at 60 degrees and not less than 35 units at 85 degrees, according to ASTM D 523.
- D. Gloss Level 5: 35 to 70 units at 60 degrees, according to ASTM D 523.
- E. Gloss Level 6: 70 to 85 units at 60 degrees, according to ASTM D 523.
- F. Gloss Level 7: More than 85 units at 60 degrees, according to ASTM D 523.

# 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include preparation requirements and application instructions.
- B. Samples for Verification: For each type of paint system and each color and gloss of topcoat.
  - 1. Submit Samples on rigid backing, 8 inches (200 mm) square.
  - 2. Step coats on Samples to show each coat required for system.

Re-Bid Set Issue Date: 06/05/2014

- 3. Label each coat of each Sample.
- 4. Label each Sample for location and application area.

# C. Product List: For each product indicated, include the following:

1. Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in schedules.

Architect's Project #: 12.130.09

- 2. Printout of current "MPI Approved Products List" for each product category specified, with the proposed product highlighted.
- 3. VOC content.

# 1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Paint: 5 percent, but not less than 1 gal. (3.8 L) of each material and color applied.

# 1.6 DELIVERY, STORAGE, AND HANDLING

- A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F (7 deg C).
  - 1. Maintain containers in clean condition, free of foreign materials and residue.
  - 2. Remove rags and waste from storage areas daily.

# 1.7 FIELD CONDITIONS

- A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F (10 and 35 deg C).
- B. Do not apply paints in snow, rain, fog, or mist; when relative humidity exceeds 85 percent; at temperatures less than 5 deg F (3 deg C) above the dew point; or to damp or wet surfaces.

# PART 2 - PRODUCTS

# 2.1 MANUFACTURERS

- A. <u>Manufacturers</u>: Subject to compliance with requirements, provide products by <u>Sherwin-Williams Company (The)</u> or, subject to compliance, products by one of the following:
  - 1. Benjamin Moore & Co.
  - 2. Duron, Inc.
  - 3. Kelly-Moore Paints.
  - 4. PPG Architectural Finishes, Inc.
  - 5. Rose Talbert

# 2.2 PAINT, GENERAL

A. MPI Standards: Provide products that comply with MPI standards indicated and that are listed in its "MPI Approved Products List."

# B. Material Compatibility:

1. Provide materials for use within each paint system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. For each coat in a paint system, provide products recommended in writing by manufacturers of topcoat for use in paint system and on substrate indicated.
- C. VOC Content: Provide materials that comply with VOC limits of authorities having jurisdiction.
- D. Colors: As selected by Architect from manufacturer's full range and as indicated on drawings.

# 2.3 BLOCK FILLERS

- A. Block Filler, Latex, Interior/Exterior: MPI #4.
  - 1. Sherwin Williams A24W200 Block Surfacer

# 2.4 METAL PRIMERS

- A. Primer, Galvanized, Water Based: MPI #134.
  - 1. Sherwin Williams B66-310 Pro-Industrial Pro-Cryl Universal Primer.

# 2.5 WATER-BASED PAINTS

- A. Light Industrial Coating, Exterior, Water Based, Gloss (Gloss Level 4):
  - 1. Sherwin Williams B66-660 Pro Industrial 0 VOC Acrylic Coating Egg-Shell
- B. Industrial Coating, Exterior, Water Based, Semi-Gloss (Gloss Level 5):
  - 1. Sherwin Williams B71-200 Series Bond-Plex Waterbased Acrylic Coating
- C. Coating, Waterborne dry-fall acrylic (Gloss Level 4)
  - 1. Sherwin Williams B42W17 Series Spraylastic Exterior Semi-gloss waterborne dryfall.

#### 2.6 SOLVENT-BASED PAINTS

- A. Elastomeric Coating (Dugout Roof)
  - 1. Uniflex Elastomeric Coating 100% acrylic polymer coating.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
  - 1. Concrete: 12 percent.
  - 2. Masonry (CMU): 12 percent.
- C. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.
- D. Proceed with coating application only after unsatisfactory conditions have been corrected.
  - 1. Application of coating indicates acceptance of surfaces and conditions.

# 3.2 PREPARATION

- A. Comply with manufacturer's written instructions and recommendations in "MPI Manual" applicable to substrates and paint systems indicated.
- B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.
  - 1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection.
- C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
  - 1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.
- D. Concrete Substrates: Remove release agents, curing compounds, efflorescence, and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces to be painted exceeds that permitted in manufacturer's written instructions.
- E. Masonry Substrates: Remove efflorescence and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces or mortar joints exceeds that permitted in manufacturer's written instructions.
- F. Steel Substrates: Remove rust, loose mill scale, and shop primer if any. Clean using methods recommended in writing by paint manufacturer[.] but not less than the following:

1. SSPC-SP 2, "Hand Tool Cleaning."

- 2. SSPC-SP 3, "Power Tool Cleaning."
- G. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and abraded areas of shop paint, and paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.

Issue Date: 06/05/2014

H. Galvanized-Metal Substrates: Remove grease and oil residue from galvanized sheet metal by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied paints.

# 3.3 APPLICATION

- A. Apply paints according to manufacturer's written instructions and recommendations in "MPI Manual."
  - 1. Use applicators and techniques suited for paint and substrate indicated.
  - 2. Paint surfaces behind movable items same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed items with prime coat only.
  - 3. Paint both sides and edges of exterior doors and entire exposed surface of exterior door frames.
  - 4. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
  - 5. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.
- B. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.
- C. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.
- D. Painting, Plumbing, HVAC, Electrical, Communication, and Electronic Safety and Security Work:
  - 1. Paint the following work where exposed to view and above 9'-4" A.F.F as determined by architect and indicated in the drawings:
    - a. Equipment, including panelboards.
    - b. Uninsulated metal piping.
    - c. Uninsulated plastic piping.
    - d. Pipe hangers and supports.
    - e. Metal conduit.
    - f. Plastic conduit.
    - g. Insulated Ductwork

# 3.4 FIELD QUALITY CONTROL

- A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test paint for dry film thickness.
  - 1. Contractor shall touch up and restore painted surfaces damaged by testing.

Re-Bid Set

Issue Date: 06/05/2014

2. If test results show that dry film thickness of applied paint does not comply with paint manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with paint manufacturer's written recommendations.

Architect's Project #: 12.130.09

### 3.5 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
- B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

### 3.6 EXTERIOR PAINTING SCHEDULE

- A. Brick / CMU Substrates:
  - 1. Water-Based Light Industrial Coating System:
    - a. Prime Coat: Block filler, latex, interior/exterior, MPI #4.
    - b. Intermediate Coat: Light Industrial Coating, Exterior, Water Based, Gloss Level 4
    - c. Topcoat: Light Industrial Coating, Exterior, Water Based, Gloss (Gloss Level 4).
- B. Concrete Substrates, Nontraffic Surfaces, (Existing concrete structure):
  - 1. Elastomeric Coating System
    - a. Prime Coat per manufacturer recommendations
      Topcoat: Elastomeric acrylic polymer coating (thickness per manufacturer recommendations).
- C. Galvanized and non-galvanized-Metal Substrates (Exposed steel fabrications, etc.):
  - 1. Water-Based Light Industrial Coating System:
    - a. Prime Coat: Primer, galvanized, water based, MPI #134.
    - b. Intermediate Coat: Light industrial coating, exterior, water based, match topcoat.
    - c. Topcoat: Light industrial coating, exterior, water based, Gloss Level 4.
- D. Galvanized-Metal Substrates:
  - 1. Waterborne Dryfall System: (Exposed Conduit, piping, fasteners, duct wrap, etc.).
    - a. Prime Coat: Shop primer specified in Section where substrate is specified.
    - b. Intermediate Coat: matching topcoat.
    - c. Topcoat: Acrylic, exterior, Gloss Level 4.

# END OF SECTION 099113

EXTERIOR PAINTING 099113 - 6

### SECTION 099123 - INTERIOR PAINTING

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 SUMMARY

- A. Section includes surface preparation and the application of paint systems on the following interior substrates:
  - 1. Concrete.
  - 2. Concrete masonry units (CMU).
  - 3. Steel.
  - 4. Galvanized metal.
  - 5. Gypsum board.

### B. Related Requirements:

- 1. Section 051200 "Structural Steel Framing" for shop priming of metal substrates with primers specified in this Section.
- 2. Section 099113 "Exterior Painting" for surface preparation and the application of paint systems on exterior substrates.
- 3. Section 099300 "Staining and Transparent Finishing" for surface preparation and the application of wood stains and transparent finishes on interior wood substrates.

### 1.3 DEFINITIONS

- A. Gloss Level 1: Not more than 5 units at 60 degrees and 10 units at 85 degrees, according to ASTM D 523.
- B. Gloss Level 2: Not more than 10 units at 60 degrees and 10 to 35 units at 85 degrees, according to ASTM D 523.
- C. Gloss Level 3: 10 to 25 units at 60 degrees and 10 to 35 units at 85 degrees, according to ASTM D 523.
- D. Gloss Level 4: 20 to 35 units at 60 degrees and not less than 35 units at 85 degrees, according to ASTM D 523.
- E. Gloss Level 5: 35 to 70 units at 60 degrees, according to ASTM D 523.
- F. Gloss Level 6: 70 to 85 units at 60 degrees, according to ASTM D 523.
- G. Gloss Level 7: More than 85 units at 60 degrees, according to ASTM D 523.

### 1.4 ACTION SUBMITTALS

A. Product Data: For each type of product. Include preparation requirements and application instructions.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Samples for Verification: For each type of paint system and in each color and gloss of topcoat.
  - 1. Submit Samples on rigid backing, 8 inches (200 mm) square.
  - 2. Step coats on Samples to show each coat required for system.
  - 3. Label each coat of each Sample.
  - 4. Label each Sample for location and application area.
- C. Product List: For each product indicated, include the following:
  - 1. Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in schedules.
  - 2. Printout of current "MPI Approved Products List" for each product category specified in Part 2, with the proposed product highlighted.
  - 3. VOC content.

### 1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Paint: 5 percent, but not less than 1 gal. (3.8 L) of each material and color applied.

### 1.6 OUALITY ASSURANCE

- A. Mockups: Apply mockups of each paint system indicated and each color and finish selected to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
  - 1. Architect will select one surface to represent surfaces and conditions for application of each paint system specified in Part 3.
    - a. Vertical and Horizontal Surfaces: Provide samples of at least 100 sq. ft. (9 sq. m).
    - b. Other Items: Architect will designate items or areas required.
  - 2. Final approval of color selections will be based on mockups.
    - a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Architect at no added cost to Owner.
  - 3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
  - 4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

### 1.7 DELIVERY, STORAGE, AND HANDLING

A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F (7 deg C).

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Maintain containers in clean condition, free of foreign materials and residue.
- 2. Remove rags and waste from storage areas daily.

### 1.8 FIELD CONDITIONS

- A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F (10 and 35 deg C).
- B. Do not apply paints when relative humidity exceeds 85 percent; at temperatures less than 5 deg F (3 deg C) above the dew point; or to damp or wet surfaces.

### PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. <u>Manufacturers</u>: Subject to compliance with requirements, provide products by <u>Sherwin-Williams Company (The)</u> or, subject to compliance, products by one of the following:
  - 1. Benjamin Moore & Co.
  - 2. Duron, Inc.
  - 3. Kelly-Moore Paints.
  - 4. PPG Architectural Finishes, Inc.
  - 5. Rose Talbert

### 2.2 PAINT, GENERAL

- A. MPI Standards: Provide products that comply with MPI standards indicated and that are listed in its "MPI Approved Products List."
- B. Material Compatibility:
  - 1. Provide materials for use within each paint system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
  - 2. For each coat in a paint system, provide products recommended in writing by manufacturers of topcoat for use in paint system and on substrate indicated.
- C. VOC Content: Products shall comply with VOC limits of authorities having jurisdiction and, for interior paints and coatings applied at Project site, the following VOC limits, exclusive of colorants added to a tint base, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 1. Flat Paints and Coatings: 50 g/L.
  - 2. Nonflat Paints and Coatings: 150 g/L.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 3. Dry-Fog Coatings: 400 g/L.
- 4. Primers, Sealers, and Undercoaters: 200 g/L.
- 5. Anticorrosive and Antirust Paints Applied to Ferrous Metals: 250 g/L.
- 6. Zinc-Rich Industrial Maintenance Primers: 340 g/L.
- 7. Pretreatment Wash Primers: 420 g/L.
- 8. Floor Coatings: 100 g/L.
- D. Colors: Match Architect's samples and as indicated in drawings.

### 2.3 BLOCK FILLERS

- A. Block Filler, Latex, Interior/Exterior: MPI #4.
  - 1. Sherwin Williams B25W25 PrepRite Block Filler Interior / Exterior Latex

# 2.4 PRIMERS/SEALERS

- A. Primer Sealer, Latex, Interior: MPI #50.
  - 1. Sherwin Williams B28W600 ProGreen 200 Low VOC Interior Latex Primer

### 2.5 METAL PRIMERS

- A. Primer, Rust-Inhibitive, Water Based: MPI #107.
  - 1. Sherwin Williams B66-310 Pro-Industrial Pro-Cryl Universal Primer
- B. Primer, Galvanized, Water Based: MPI #134.
  - 1. Sherwin Williams B66-310 Pro-Industrial Pro-Cryl Universal Primer

### 2.6 WATER-BASED PAINTS

- A. Latex, Interior, (Gloss Level 3): MPI #52 X Green
  - 1. Sherwin Williams B20-1600 Pro Green 200 Low VOC Interior Latex Egg-Shell
- B. Latex, Interior, (Gloss Level 4): MPI #43 X Green
  - 1. Sherwin Williams B31-600 Pro Green 200 Low VOC Interior Semi-Gloss
- C. Light Industrial Coating, Interior, Water Based, Gloss (Gloss Level 6): MPI #154.
  - 1. Sherwin Williams B66-650 Pro Industrial 0 VOC Acrylic Coating Semi-Gloss
- D. Epoxy, Interior, High Performance Architectural, Semi-Gloss (Gloss Level 5): MPI #141.
  - 1. Sherwin Williams K46-150 Series Pre-Catalyzed Waterbased Epoxy

### 2.7 SOLVENT-BASED PAINTS

- A. Alkyd, Quick Dry, Semi-Gloss (Gloss Level 5):
  - 1. Sherwin Williams Pro Industrial Industrial Enamel 100 B54Z-200 Series

### 2.8 FLOOR COATINGS

- A. Sealer, Water Based, for Concrete Floors: MPI #99.
  - 1. Sherwin Williams H&C Wet Look Sealer

### PART 3 - EXECUTION

### 3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
  - 1. Concrete: 12 percent.
  - 2. Masonry (CMU): 12 percent.
  - 3. Gypsum Board: 12 percent.
- C. Gypsum Board Substrates: Verify that finishing compound is sanded smooth.
- D. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.
- E. Proceed with coating application only after unsatisfactory conditions have been corrected.
  - 1. Application of coating indicates acceptance of surfaces and conditions.

### 3.2 PREPARATION

- A. Comply with manufacturer's written instructions and recommendations in "MPI Manual" applicable to substrates indicated.
- B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.
  - 1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.
- C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
  - 1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.

D. Concrete Substrates: Remove release agents, curing compounds, efflorescence, and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces to be painted exceeds that permitted in manufacturer's written instructions.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- E. Masonry Substrates: Remove efflorescence and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces or mortar joints exceed that permitted in manufacturer's written instructions.
- F. Steel Substrates: Remove rust, loose mill scale, and shop primer, if any. Clean using methods recommended in writing by paint manufacturer[.] but not less than the following:
  - 1. SSPC-SP 2, "Hand Tool Cleaning."
  - 2. SSPC-SP 3, "Power Tool Cleaning."
- G. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and abraded areas of shop paint, and paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.
- H. Galvanized-Metal Substrates: Remove grease and oil residue from galvanized sheet metal fabricated from coil stock by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied paints.

### 3.3 APPLICATION

- A. Apply paints according to manufacturer's written instructions and to recommendations in "MPI Manual."
  - 1. Use applicators and techniques suited for paint and substrate indicated.
  - 2. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
  - 3. Paint front and backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
  - 4. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
  - 5. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.
- B. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.
- C. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks
- D. Painting Fire Suppression, Plumbing, HVAC, Electrical, Communication, and Electronic Safety and Security Work:
  - 1. Paint the following work where exposed in occupied spaces:

- a. Equipment, including panelboards.
- b. Uninsulated metal piping.
- c. Uninsulated plastic piping.
- d. Pipe hangers and supports.
- e. Metal conduit.
- f. Plastic conduit.
- g. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.

Issue Date: 06/05/2014

- h. Other items as directed by Architect.
- 2. Paint portions of internal surfaces of metal ducts, without liner, behind air inlets and outlets that are visible from occupied spaces.

### 3.4 FIELD QUALITY CONTROL

- A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test paint for dry film thickness.
  - 1. Contractor shall touch up and restore painted surfaces damaged by testing.
  - 2. If test results show that dry film thickness of applied paint does not comply with paint manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with paint manufacturer's written recommendations.

### 3.5 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
- B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

### 3.6 INTERIOR PAINTING SCHEDULE

- A. Concrete Substrates, Nontraffic Surfaces:
  - 1. Latex System:
    - a. Prime Coat: Primer sealer, latex, interior, MPI #50.
    - b. Intermediate Coat: Latex, interior, matching topcoat.
    - c. Topcoat: Latex, interior, (Gloss Level 4), MPI #43.

# B. Concrete Substrates, Traffic Surfaces:

- 1. Water-Based Clear Sealer System:
  - a. First Coat: Sealer, water based, for concrete floors, MPI #99.
  - b. Topcoat: Sealer, water based, for concrete floors, MPI #99.

### C. CMU Substrates:

- 1. Latex System:
  - a. Block Filler: Block filler, latex, interior/exterior, MPI #4.
  - b. Intermediate Coat: Light industrial coating, interior, water based, MP #107
  - c. Topcoat: Latex, interior, (Gloss Level 4), MPI #43.
- 2. High-Performance Architectural Epoxy System: (Walls in Shower areas, wet areas and training room)
  - a. Prime Coat: Primer sealer, latex, interior, MPI #50.
  - b. Intermediate Coat: Latex, interior, high performance architectural, matching topcoat.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

c. Topcoat: Epoxy, interior, high performance architectural, semi-gloss (Gloss Level 5), MPI #141.

### D. Steel Substrates:

- 1. Water-Based Light Industrial Coating System:
  - a. Prime Coat: Primer, rust-inhibitive, water based MPI #107.
  - b. Intermediate Coat:
    - 1) Light industrial coating, interior, water based, matching topcoat.
  - c. Topcoat:
    - 1) Light industrial coating, interior, water based, gloss (Gloss Level 6), MPI #154.
- E. Galvanized and Non-Galvanized Metal Substrates:
  - 1. Quick-Drying Enamel System:
    - a. Prime Coat: Touch-up with Anticorrosive metal primer
    - b. Intermediate Coat: Alkyd, quick dry, matching topcoat.
    - c. Topcoat: Alkyd, quick dry, semi-gloss (Gloss Level 5).

### F. Gypsum Board Substrates:

- 1. Latex System:
  - a. Prime Coat: Primer sealer, latex, interior, MPI #50.
  - b. Topcoat: Latex, interior, egg-shell finish (Gloss Level 3), MPI #52.
- 2. High-Performance Architectural Epoxy System: (ceilings and soffits at showers)
  - a. Prime Coat: Primer sealer, latex, interior, MPI #50.
  - b. Intermediate Coat: Latex, interior, high performance architectural, matching topcoat.
  - c. Topcoat: Epoxy, interior, high performance architectural, semi-gloss (Gloss level 5), MPI #141.

END OF SECTION 099123

# SECTION 099300 - STAINING AND TRANSPARENT FINISHING

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes surface preparation and application of wood finishes on the following substrates:
  - 1. Interior Substrates:
    - a. Dressed lumber (finish carpentry).
    - b. Exposed wood panel products.

### B. Related Requirements:

- 1. Section 099113 "Exterior Painting" for standard paint systems on exterior substrates.
- 2. Section 099123 "Interior Painting" for stains and transparent finishes on concrete floors.

### 1.3 DEFINITIONS

- A. Gloss Level 1: Not more than 5 units at 60 degrees and 10 units at 85 degrees, according to ASTM D 523.
- B. Gloss Level 4: 20 to 35 units at 60 degrees and not less than 35 units at 85 degrees, according to ASTM D 523.
- C. Gloss Level 5: 35 to 70 units at 60 degrees, according to ASTM D 523.
- D. Gloss Level 6: 70 to 85 units at 60 degrees, according to ASTM D 523.
- E. Gloss Level 7: More than 85 units at 60 degrees, according to ASTM D 523.

### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include preparation requirements and application instructions.
- B. Samples for Initial Selection: For each type of product indicated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- C. Samples for Verification: For each type of finish system and in each color and gloss of finish indicated.
  - 1. Submit Samples on representative samples of actual wood substrates, 12 inches (300
  - 2. Label each Sample for location and application area.
- D. Product List: For each product indicated, include the following:
  - 1. Cross-reference to finish system and locations of application areas. Use same designations indicated on Drawings and in schedules.
  - 2. Printout of current "MPI Approved Products List" for each product category specified in Part 2, with the product proposed for use highlighted.
  - 3. VOC content.

#### 1.5 DELIVERY, STORAGE, AND HANDLING

- Store materials not in use in tightly covered containers in well-ventilated areas with ambient A. temperatures continuously maintained at not less than 45 deg F (7 deg C).
  - Maintain containers in clean condition, free of foreign materials and residue. 1.
  - 2. Remove rags and waste from storage areas daily.

#### FIELD CONDITIONS 1.6

- Apply finishes only when temperature of surfaces to be finished and ambient air temperatures A. are between 50 and 95 deg F (10 and 35 deg C).
- B. Do not apply finishes when relative humidity exceeds 85 percent; at temperatures less than 5 deg F (3 deg C) above the dew point; or to damp or wet surfaces.
- C. Do not apply exterior finishes in snow, rain, fog, or mist.

### PART 2 - PRODUCTS

#### 2.1 **MANUFACTURERS**

- Manufacturers: Subject to compliance with requirements, provide products by one of the A. following:
  - 1. Benjamin Moore & Co.
  - 2. Duron, Inc.
  - Kelly-Moore Paints. 3.
  - 4. PPG Architectural Finishes, Inc.
  - Sherwin-Williams Company (The). 5.

Issue Date: 06/05/2014

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

B. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to products listed in other Part 2 articles for the category indicated.

### 2.2 MATERIALS, GENERAL

- A. MPI Standards: Provide products that comply with MPI standards indicated and that are listed in its "MPI Approved Products List."
- B. Material Compatibility:
  - 1. Provide materials for use within each finish system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
  - 2. For each coat in a finish system, provide products recommended in writing by manufacturers of topcoat for use in finish system and on substrate indicated.
- C. VOC Content: Products shall comply with VOC limits of authorities having jurisdiction and, for interior stains and finishes applied at project site, the following VOC limits, exclusive of colorants added to a tint base, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 1. Clear Wood Finishes, Varnishes: VOC not more than 350 g/L.
  - 2. Stains: VOC not more than 250 g/L.
  - 3. Primers, Sealers, and Undercoaters: 200 g/L.
- D. Low-Emitting Materials: Interior stains and finishes shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- E. Stain Colors: As follows:
  - 1. Wood Casework: Match the interior wood door stain, typical unless noted otherwise.
  - 2. Wood Running Trim: Match the interior wood door stain, typical unless noted otherwise.
  - 3. Wood Strip Stage Flooring: "Ebony"

### 2.3 WOOD FILLERS

A. Wood Filler Paste: MPI #91.

# 2.4 STAINS

- A. Stain, Semi-Transparent, for Interior Wood: MPI #90.
  - 1. MiniWax Water-Based Wood Stain

# 2.5 WATER-BASED VARNISHES

- A. Varnish, Water Based, Clear, Gloss (Gloss Level 6): MPI #130.
  - 1. Sherwin Williams A68 Series Wood Classics Waterborne Polyurethane Varnish.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

2. Use on wood casework and running trim.

### PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Maximum Moisture Content of Interior Wood Substrates: 10 percent, when measured with an electronic moisture meter.
- C. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.
- D. Proceed with finish application only after unsatisfactory conditions have been corrected.
  - 1. Beginning finish application constitutes Contractor's acceptance of substrates and conditions.

### 3.2 PREPARATION

- A. Comply with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual" applicable to substrates indicated.
- B. Remove hardware, covers, plates, and similar items already in place that are removable. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and finishing.
  - 1. After completing finishing operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.
- C. Clean and prepare surfaces to be finished according to manufacturer's written instructions for each particular substrate condition and as specified.
  - 1. Remove dust, dirt, oil, and grease by washing with a detergent solution; rinse thoroughly with clean water and allow to dry. Remove grade stamps and pencil marks by sanding lightly. Remove loose wood fibers by brushing.
  - 2. Remove mildew by scrubbing with a commercial wash formulated for mildew removal and as recommended by stain manufacturer.

### D. Interior Wood Substrates:

1. Apply wood filler paste to open-grain woods, as defined in "MPI Architectural Painting Specification Manual," to produce smooth, glasslike finish.

Issue Date: 06/05/2014

- 2. Sand surfaces that will be exposed to view and dust off.
- 3. After priming, fill holes and imperfections in the finish surfaces with putty or plastic wood filler. Sand smooth when dried.

### 3.3 APPLICATION

- A. Apply finishes according to manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual."
  - 1. Use applicators and techniques suited for finish and substrate indicated.
  - 2. Finish surfaces behind movable equipment and furniture same as similar exposed surfaces.
  - 3. Do not apply finishes over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
- B. Apply finishes to produce surface films without cloudiness, holidays, lap marks, brush marks, runs, ropiness, or other surface imperfections.

### 3.4 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
- B. After completing finish application, clean spattered surfaces. Remove spattered materials by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from finish application. Correct damage by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- D. At completion of construction activities of other trades, touch up and restore damaged or defaced finished wood surfaces.

### 3.5 INTERIOR WOOD-FINISH-SYSTEM SCHEDULE

- A. Wood substrates, nontraffic surfaces, including wood trim, architectural wood casework, and wood-based panel products.
  - 1. Water-Based Varnish over Stain System:
    - a. Stain Coat: Stain, semi-transparent, for interior wood, MPI #90.
    - b. First Intermediate Coat: Water-based varnish matching topcoat.
    - c. Second Intermediate Coat: Water-based varnish matching topcoat.
    - d. Topcoat: Varnish, water based, clear, gloss (Gloss Level 6), MPI #130.

END OF SECTION 099300

# SECTION 102800 - TOILET, BATH, AND LAUNDRY ACCESSORIES

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

### A. Section Includes:

- 1. Washroom accessories.
- 2. Shower room accessories.
- 3. Warm-air dryers.
- 4. Underlayatory guards.
- 5. Custodial accessories.
- 6. Paper Towel Dispensers in lab and classroom spaces.

### B. Owner-Furnished Material:

- 1. Soap Dispensers (SD); Owner Furnished Owner Installed.
- 2. Sanitary Napkin Disposal (ND); Owner Furnished Owner Installed.
- 3. Shower Curtain Rod and Curtain (SC R); Owner Furnished Owner Installed.
- 4. Toilet Tissue Dispensers (TTD-1); Owner Furnished Owner Installed.
- 5. Electric Hand Dryers (EHD); Owner Furnished Owner Installed.

### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include the following:
  - 1. Construction details and dimensions.
  - 2. Anchoring and mounting requirements, including requirements for cutouts in other work and substrate preparation.
  - 3. Material and finish descriptions.
  - 4. Features that will be included for Project.
  - 5. Manufacturer's warranty.
- B. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

a Carolina Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Identify locations using room designations indicated.
- 2. Identify products using designations indicated.

### 1.4 INFORMATIONAL SUBMITTALS

A. Warranty: Sample of special warranty.

### 1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For toilet and bath accessories to include in maintenance manuals.

### 1.6 QUALITY ASSURANCE

- A. Source Limitations: For products listed, obtain products from single source from single manufacturer.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

### 1.7 COORDINATION

- A. Coordinate accessory locations with other work to prevent interference with clearances required for access by people with disabilities, and for proper installation, adjustment, operation, cleaning, and servicing of accessories.
- B. Deliver inserts and anchoring devices set into concrete or masonry as required to prevent delaying the Work.

### 1.8 WARRANTY

- A. Special Mirror Warranty: Manufacturer's standard form in which manufacturer agrees to replace mirrors that develop visible silver spoilage defects and that fail in materials or workmanship within specified warranty period.
  - 1. Warranty Period: 15 years from date of Substantial Completion.

### PART 2 - PRODUCTS

### 2.1 MATERIALS

A. Stainless Steel: ASTM A 666, Type 304, 0.031-inch (0.8-mm) minimum nominal thickness unless otherwise indicated.

Issue Date: 06/05/2014

- B. Steel Sheet: ASTM A 1008/A 1008M, Designation CS (cold rolled, commercial steel), 0.036-inch (0.9-mm) minimum nominal thickness.
- C. Galvanized-Steel Sheet: ASTM A 653/A 653M, with G60 (Z180) hot-dip zinc coating.
- D. Galvanized-Steel Mounting Devices: ASTM A 153/A 153M, hot-dip galvanized after fabrication.
- E. Fasteners: Screws, bolts, and other devices of same material as accessory unit and tamper-and-theft resistant where exposed, and of galvanized steel where concealed.
- F. Chrome Plating: ASTM B 456, Service Condition Number SC 2 (moderate service).
- G. Mirrors: ASTM C 1503, Mirror Glazing Quality, clear-glass mirrors, nominal 6.0 mm thick.
- H. ABS Plastic: Acrylonitrile-butadiene-styrene resin formulation.

### 2.2 WASHROOM ACCESSORIES

- 1. Manufacturers: Subject to compliance with requirements, provide products by <u>Bobrick Washroom Equipment</u>, <u>Inc</u> or a product that complies with the requirements (including single source) by one of the following:
- 2. <u>A & J Washroom Accessories, Inc.</u>
- 3. <u>American Specialties, Inc.</u>
- 4. Bradley Corporation
- 5. GAMCO Specialty Accessories; a division of Bobrick Washroom Equipment, Inc.
- 6. <u>Tubular Specialties Manufacturing, Inc.</u>
- B. Toilet Tissue Dispenser (**TTD-1**): By Owner
- C. Paper Towel (Folded) Dispenser (**None Indicated**): Counter Set dispenser by Owner.
- D. Soap Dispenser (SD): By Owner
- E. Grab Bar (GB-1; GB-2; GB-3; GB-4; GB-5; GB-6; GB-7):
  - 1. Basis-of-Design Product: Bobrick B5806 series.
  - 2. Mounting: Flanges with concealed fasteners.
  - 3. Material: Stainless steel, 0.05 inch (1.3 mm) thick.
    - a. Finish: Smooth, No. 4 finish (satin) on ends and slip-resistant texture in grip area.
  - 4. Outside Diameter: 1-1/2 inches (38 mm).
  - 5. Configuration and Length: As indicated on Drawings.
- F. Sanitary-Napkin Disposal Unit (**ND**): By Owner
  - 1. Basis-of-Design Product: Bobrick #B270.
  - 2. Mounting: Surface mounted.
  - 3. Door or Cover: Self-closing, disposal-opening cover and hinged face panel with tumbler lockset.
  - 4. Receptacle: Removable.

Le-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

5. Material and Finish: Stainless steel, No. 4 finish (satin).

### G. Mirrors (**MI-1**):

- 1. Basis-of-Design: Frameless Glass Mirror
- 2. Mounting: 1" square x 2" barrel length Stainless Steel Standoffs
- 3. Material: 1/4" tempered float glass mirror with polished edges.
- 4. Finish: Stainless steel, No. 4 finish (satin).

### 2.3 SHOWER ROOM ACCESSORIES

- 1. Manufacturers: Subject to compliance with requirements, provide products by <u>Bobrick Washroom Equipment</u>, Inc or a product that complies with the requirements (including single source) by one of the following:
- 2. A & J Washroom Accessories, Inc.
- 3. <u>American Specialties, Inc.</u>
- 4. <u>Bradley Corporation</u>.
- 5. Tubular Specialties Manufacturing, Inc.

### B. Shower Curtain Rod (SCR): By Owner

- 1. Basis-of-Design Product: Bobrick #B6107 x 30.
- 2. Description: 1-inch (25.4-mm) OD; fabricated from nominal 0.0375-inch- (0.95-mm-) thick stainless steel.
- 3. Mounting Flanges: 1-3/8 inches (35mm) diameter chrome plated plastic with bright polished finish over concealed aluminum mounting brackets.
- 4. Finish: No. 4 (satin).

### C. Shower Curtain (C) By Owner

- 1. Size: Minimum 6 inches (152 mm) wider than opening by 72 inches (1828 mm) high.
- 2. Material: Nylon-reinforced vinyl, minimum 10 oz. (284 g) or 0.008-inch- (0.2-mm-) thick vinyl, with integral antibacterial agent.
- 3. Color: White.
- 4. Grommets: Corrosion resistant at minimum 6 inches (152 mm) o.c. through top hem.
- 5. Shower Curtain Hooks: Stainless-steel, spring wire curtain hooks with snap fasteners, sized to accommodate specified curtain rod. Provide one hook per curtain grommet.
- D. Folding Shower Seat (**SS**): NA provisions for future installation.

### E. Towel Hook (**TH**):

- 1. Basis-of-Design Product: Gedy #D027-13
- 2. Description: Single-prong unit.
- 3. Material and Finish: Stainless steel, No. 4 finish (satin).
- 4. Locations: Provide one (1) for each shower.

# 2.4 UNDERLAVATORY GUARDS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Plumberex Specialty Products, Inc.
- 2. Truebro by IPS Corporation.

# B. Underlayatory Guard:

- 1. Description: Insulating pipe covering for supply and drain piping assemblies that prevent direct contact with and burns from piping; allow service access without removing coverings.
- 2. Material and Finish: Antimicrobial, molded plastic, white.

# 2.5 CUSTODIAL ACCESSORIES

- A. Manufacturers: Subject to compliance with requirements, provide products by <u>Bradley Corporation</u> or a product that complies with the requirements by one of the following:
  - 1. <u>American Specialties, Inc.</u>
  - 2. <u>Bobrick Washroom Equipment, Inc.</u>
  - 3. <u>Tubular Specialties Manufacturing, Inc.</u>
- B. Mop Holder / Utility Shelf (**MH**):
  - 1. Basis-of-Design Product: Bradley 9984.
  - 2. Description: With exposed edges turned down not less than 3/4 inch (19 mm) and supported by two triangular brackets welded to shelf underside.
  - 3. Size: 30" inches (762 mm) long by 8 inches (203 mm) deep.
  - 4. Material and Finish: Not less than nominal 0.05-inch- (1.3-mm-) thick stainless steel, No. 4 finish (satin).

### 2.6 FABRICATION

- A. General: Fabricate units with tight seams and joints, and exposed edges rolled. Hang doors and access panels with full-length, continuous hinges. Equip units for concealed anchorage and with corrosion-resistant backing plates.
- B. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to Owner's representative.

### PART 3 - EXECUTION

#### 3.1 **INSTALLATION**

- A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.
- Grab Bars: Install to withstand a downward load of at least 250 lbf (1112 N), when tested B. according to ASTM F 446.

#### 3.2 ADJUSTING AND CLEANING

- Adjust accessories for unencumbered, smooth operation. Replace damaged or defective items. A.
- B. Remove temporary labels and protective coatings.
- C. Clean and polish exposed surfaces according to manufacturer's written recommendations.

END OF SECTION 102800

Issue Date: 06/05/2014

### SECTION 104416 - FIRE EXTINGUISHERS

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 SUMMARY

- A. Section includes portable fire extinguishers and mounting brackets for fire extinguishers.
- B. Related Sections:
  - 1. Section 104413 "Fire Extinguisher Cabinets."

### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include rating and classification, material descriptions, dimensions of individual components and profiles, and finishes for fire extinguisher and mounting brackets.
- B. Product Schedule: For fire extinguishers. Coordinate final fire extinguisher schedule with fire protection cabinet schedule to ensure proper fit and function. Use same designations indicated on Drawings.

### 1.4 INFORMATIONAL SUBMITTALS

A. Warranty: Sample of special warranty.

### 1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For fire extinguishers to include in maintenance manuals.

### 1.6 QUALITY ASSURANCE

- A. NFPA Compliance: Fabricate and label fire extinguishers to comply with NFPA 10, "Portable Fire Extinguishers."
- B. Fire Extinguishers: Listed and labeled for type, rating, and classification by an independent testing agency acceptable to authorities having jurisdiction.

FIRE EXTINGUISHERS 104416 - 1

### 1.7 COORDINATION

A. Coordinate type and capacity of fire extinguishers with fire protection cabinets to ensure fit and function.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.8 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace fire extinguishers that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Failure of hydrostatic test according to NFPA 10.
    - b. Faulty operation of valves or release levers.
  - 2. Warranty Period: Six years from date of Substantial Completion.

### PART 2 - PRODUCTS

# 2.1 PORTABLE, HAND-CARRIED FIRE EXTINGUISHERS

- A. Fire Extinguishers: Type, size, and capacity for each fire protection cabinet and mounting bracket indicated.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. <u>Ansul Incorporated; Tyco International Ltd.</u>
    - b. <u>Badger Fire Protection; a Kidde company</u>.
    - c. <u>Buckeye Fire Equipment Company</u>.
    - d. Fire End & Croker Corporation.
    - e. J. L. Industries, Inc.; a division of Activar Construction Products Group.
    - f. Larsen's Manufacturing Company.
  - 2. Valves: Manufacturer's standard.
  - 3. Handles and Levers: Manufacturer's standard.
  - 4. Instruction Labels: Include pictorial marking system complying with NFPA 10, Appendix B and bar coding for documenting fire extinguisher location, inspections, maintenance, and recharging.
- B. Multipurpose Dry-Chemical Type in Steel Container: UL-rated 4-A:60-B:C, 10-lb (4.5-kg) nominal capacity, with monoammonium phosphate-based dry chemical in enameled-steel container.
- C. Wet Chemical: UL rated K, 205 gal. capacity in enameled steel container. For class K fires in Kitchen Area.

FIRE EXTINGUISHERS 104416 - 2

# 2.2 MOUNTING BRACKETS – (FE-B)

- A. Mounting Brackets: Manufacturer's standard galvanized steel, designed to secure fire extinguisher to wall or structure, of sizes required for types and capacities of fire extinguishers indicated, with plated or red baked-enamel finish.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- a. Ansul Incorporated; Tyco International Ltd.
- b. Badger Fire Protection; a Kidde company.
- c. <u>Buckeye Fire Equipment Company</u>.
- d. Fire End & Croker Corporation.
- e. J. L. Industries, Inc.; a division of Activar Construction Products Group.
- f. <u>Larsen's Manufacturing Company</u>.
- B. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as indicated by Architect.
  - 1. Identify bracket-mounted fire extinguishers with the words "FIRE EXTINGUISHER" in red letter decals applied to mounting surface.
    - a. Orientation: Vertical.

### 2.3 FIRE EXTINGUISHER COVER

A. Fire extinguisher cover: Manufacturer's standard red, vinyl coated nylon fire extinguisher cover by mounting bracket manufacturer.

### PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine fire extinguishers for proper charging and tagging.
  - 1. Remove and replace damaged, defective, or undercharged fire extinguishers.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. General: Install fire extinguishers and mounting brackets in locations indicated and in compliance with requirements of authorities having jurisdiction.
  - 1. Mounting Brackets: 54 inches (1372 mm) above finished floor to top of fire extinguisher.
- B. Mounting Brackets: Fasten mounting brackets to surfaces, square and plumb, at locations indicated.
- C. Install fire extinguisher cover per manufacturer's instructions.

### END OF SECTION 104416

FIRE EXTINGUISHERS 104416 - 3

Issue Date: 06/05/2014

### SECTION 123661 - SIMULATED STONE COUNTERTOPS

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Refer to Section 01 23 00 Alternates for scope of alternate pricing associated with millwork and counter tops.

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Solid-surface-material countertops and backsplashes.
  - 2. Quartz agglomerate countertops and backsplashes.

### 1.3 ACTION SUBMITTALS

- A. Product Data: For countertop materials.
- B. Shop Drawings: For countertops. Show materials, finishes, edge and backsplash profiles, methods of joining, and cutouts for plumbing fixtures.
- C. Samples for Initial Selection: For each type of material exposed to view.
- D. Samples for Verification: For the following products:
  - 1. Countertop material, 6 inches (150 mm) square.

### 1.4 PROJECT CONDITIONS

A. Field Measurements: Verify dimensions of countertops by field measurements after base cabinets are installed but before countertop fabrication is complete.

### 1.5 COORDINATION

A. Coordinate locations of utilities that will penetrate countertops or backsplashes.

# Issue Date: 06/05/2014

Architect's Project #: 12.130.09

### PART 2 - PRODUCTS

#### 2.1 SOLID-SURFACE-MATERIAL COUNTERTOPS

- A. Configuration: Provide countertops with the following front and backsplash style:
  - 1. Front: 3/4-inch (19-mm) bullnose.
  - 2. Backsplash: Straight, slightly eased at corner.
  - Endsplash: Matching backsplash. 3.
- B. Countertops: 3/4-inch thick, solid surface material with front edge built up with same material for total thickness of 1 1/2 inches.
- C. Backsplashes: 1/2-inch- (12.7-mm-) thick, solid surface material.
- D. Fabrication: Fabricate tops in one piece with shop-applied edges and backsplashes unless otherwise indicated. Comply with solid-surface-material manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.
  - 1. Fabricate with loose backsplashes for field assembly.

#### 2.2 QUARTZ AGGLOMERATE COUNTERTOPS

- Configuration: Provide countertops with the following front and backsplash style: A.
  - 1. Front: 1-1/2-inch (38-mm) laminated bullnose.
  - 2. Backsplash: Straight, slightly eased at corner.
  - Endsplash: Matching backsplash.
- В. Countertops: 3/4-inch- (19-mm-) thick, quartz agglomerate with front edge built up with same material.
- C. Backsplashes: 1/2-inch- (12.7-mm-) thick, quartz agglomerate.
- Fabrication: Fabricate tops in one piece with shop-applied edges and backsplashes unless D. otherwise indicated. Comply with quartz agglomerate manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.
  - Fabricate with loose backsplashes for field assembly. 1.

#### 2.3 **COUNTERTOP MATERIALS**

- Plywood substrate: Exterior softwood plywood complying with DOC PS 1, Grade C-C Plugged, A. touch sanded.
- B. Adhesives: Adhesives shall not contain urea formaldehyde.

Issue Date: 06/05/2014

- C. Solid Surface Material: Homogeneous solid sheets of filled plastic resin complying with ANSI SS1.
  - 1. As specified in the finish schedule
- D. Quartz Agglomerate: Solid sheets consisting of quartz aggregates bound together with a matrix of filled plastic resin and complying with the "Physical Characteristics of Materials" Article of ANSI SS1.
  - 1. As specified in the finish schedule

### PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Assemble countertops and complete fabrication at Project site to the extent that it was not completed in the shop.
  - 1. Provide cutouts for appliances, plumbing fixtures, electrical work, and similar items.
  - 2. Seal edges of substrate cutouts by saturating with varnish.
- B. Install countertops level, plumb, true, and straight. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches (3 mm in 2400 mm).
- C. Scribe and cut countertops to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.
- D. Fasten countertops by screwing through corner blocks of base units into underside of countertop. Pre-drill holes for screws as recommended by manufacturer.
- E. Field Jointing: Prepare edges to be joined in shop so Project-site processing of top and edge surfaces is not required. Align adjacent surfaces and, using adhesive in color to match countertop, form seams to comply with manufacturer's written instructions.
  - 1. Locate field joints where shown on Shop Drawings.
  - 2. Joints shall have consistent width of not more than 3/16".
  - 3. Carefully dress joints smooth, remove surface scratches, and clean entire surface.
- F. Install backsplashes and endsplashes to comply with manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.

### END OF SECTION 123661

# SECTION 220010 - GENERAL PROVISIONS - PLUMBING

PART 1 - GENERAL

### 1.1 SCOPE:

A. Bids of work covered by each section of these specifications shall be based on the layout and equipment as shown and specified with only such approved substitutions as are allowed. Drawings show general arrangement of piping. Because of small scale of drawings, it is not possible to indicate all offsets, fittings, and accessories, which may be required. Contractor shall carefully investigate structural and finish conditions affecting his work and shall arrange such work accordingly, furnishing such fittings, traps, valves, and accessories as may be required to meet such conditions. Where locations make it necessary or desirable from Contractor's standpoint to make changes in arrangements or details shown on drawings, he may present suggestions for such changes and obtain Engineer's approval prior to making such changes.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 CODES:

A. All work under this division shall be in strict compliance with "International Codes" and all applicable Codes and Regulations of the City of Columbia, South Carolina.

### 1.3 MATERIAL AND SHOP DRAWINGS:

- A. Use only new materials and the standard product of a single manufacturer for each article of its type unless specifically mentioned otherwise. Materials and workmanship in the case of assembled items shall conform to the latest applicable requirements of NFPA, ASME, NEC, ASTM, AWWA, NEMA, and ANSI.
- B. Schedule submittals to expedite work. Unless otherwise indicated in this Section, submittals shall be submitted within 30 days of date of Notice to Proceed. Provide six (6) copies of submittals for review and approval. Provide folders or binders for each submittal. All submittals shall be bound in a single volume. Partial lists will not be considered and will be returned to the Contractor. Identify Project, Contractor, subcontractor, supplier, manufacturer, pertinent drawing sheet and detail numbers, and associated specification section numbers. A table of contents shall be included in the front of the submittal with tabs indicating each section. Identify variations from requirements of Contract Documents. Electronic submittal will be acceptable, but the submittal shall not contain miscellaneous data that is not pertinent to the project and the proposed equipment, materials, etc. that are to be used shall be clearly indicated.

# C. Contractor responsibilities:

1. Review submittals prior to transmittal. Verify compatibility with field conditions and dimensions, product selections and designations, quantities, and conformance of submittal with requirements of Contract Documents. Return non-conforming submittals to preparer for revision rather than submitting to Engineer. Coordinate submittals to avoid conflicts between various items of

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

work. Failure of Contractor to review submittals prior to transmittal to Engineer shall be cause for rejection. Incomplete, improperly packaged, and submittals from sources other than Contractor will not be accepted. Submittals not stamped APPROVED and signed by the Contractor will be returned to the Contractor.

- 2. Provide product data such as manufacturer's brochures, catalog pages, illustrations, diagrams, tables, performance charts, and other material which describe appearance, size, attributes, code and standard compliance, ratings, and other product characteristics. Provide all critical information such as reference standards, performance characteristics, capacities, power requirements, wiring and piping diagrams, controls, component parts, finishes, dimensions, and required clearances. Submit only data which are pertinent. Mark each copy of manufacturer's standard printed data to identify products, models, options, and other data pertinent to project.
- 3. Engineer will review and return submittals with comments. Do not fabricate products or begin work which requires submittals until return of submittal with Engineer acceptance. Promptly report any inability to comply with provisions. Revise and resubmit submittals as required within 15 days of return from Engineer. Make re-submittals under procedures specified for initial submittals. Identify all changes made since previous submittal.

# D. Engineer Review:

- 1. Engineer will review submittals for sole purpose of verifying general conformance with design concept and general compliance with Contract Documents. Approval of submittal by Engineer does not relieve Contractor of responsibility for correcting errors which may exist in submittal or from meeting requirements of Contract Documents. After review, Engineer will return submittals marked as follows to indicate action taken:
- 2. No Exception: Part of work covered by submittal may proceed provided it complies with requirements of Contract Documents. Final acceptance will depend upon that compliance. The term "approved" shall only indicate that there is no exception taken to the submittal.
- 3. No Exception As Corrected: Part of work covered by submittal may proceed provided it complies with notations and corrections on submittal and requirements of Contract documents. Final acceptance will depend upon that compliance.
- 4. Revise And Resubmit: Do not proceed with part of work covered by submittal including purchasing, fabricating, and delivering. Revise or prepare new submittal in accordance with notations and resubmit.

# E. Items Requiring Submittal are as Follows:

- 1. Insulation
- 2. All items listed in MANUFACTURERS: Section of 220010

### 1.4 ASBESTOS:

A. At any time the Contractor encounters asbestos, he shall immediately stop work in the immediate area and suspend any further work until asbestos is removed. Contractor shall, upon discovery of asbestos, notify owner, or owner's representative, who shall be responsible for the removal of the asbestos, all in accordance with NESHAP (National Emission Standard for Hazardous Air Pollutants). Any form of asbestos removal or demolition shall be by owner. Engineer is not an "Owner or Operator" as defined under NESHAP.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. Contractor is responsible for, and shall be aware of all state and federal laws pertaining to asbestos as well as NESHAP requirements.

### 1.5 LEAD FREE:

A. All solder, flux and pipe used in water system must be lead free. Lead free is defined as less than 0.2 percent lead in solder and flux and less than 8.0 percent lead in pipes and fittings.

### 1.6 AMERICANS WITH DISABILITIES ACT:

A. All items or work under this division of the specifications shall comply with guidelines as set forth in the Americans with Disabilities Act.

### 1.7 PERMITS AND FEES:

A. Obtain permits, licenses, pay fees, etc. as required for performance of Contract. Arrange for necessary inspections required by governing authority and deliver certificates of approval to Architects or their representatives. File plans required by governing body.

# 1.8 DEFINITIONS:

- A. In this division of the specifications and accompanying drawings, the following definitions apply:
- B. Provide: To purchase, pay for, transport to the job site, unpack, install, and connect complete and ready for operation; to include all permits, inspections, equipment, material, labor, hardware, and operations required for completion and operation.
- C. Install (Installed): To furnish and install complete and ready for operation.
- D. Furnish: To purchase, pay for, and deliver to the job site for installation by others.
- E. The Plumbing Contractor is cautioned that "furnish" requires coordination with others. Such coordination costs shall be included as part of Plumbing Contractor's bid.

### 1.9 CUTTING AND PATCHING:

A. Cutting of walls, floors, roofs, partitions, and ceiling, required for proper installation of the systems shall be performed under this contract.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Cutting shall be done in a neat, workmanlike manner. No joist, beams, girders, columns, or other structural members may be cut without written permission from the Engineer. When possible, holes shall be saw-cut or core drilled neat to minimize patching.
- C. Re-routing of existing pipes, insulation, etc. as required for installation of new system is included in this work. All work shall be done in accordance with specifications for new work of the particular type involved.
- D. Patching shall be performed to match existing structures, exterior walls and roofs, and shall form watertight installation.

### 1.10 VERIFICATION OF DIMENSIONS, ETC.:

A. The Contractor shall visit the premises and thoroughly familiarize himself with all details of the work, working conditions, verify all dimensions in the field, advise the Engineer of any discrepancy, and submit shop drawings of any changes he proposes to make in quadruplicate for approval before starting the work. Contractor shall install all equipment in a manner to avoid building interference.

### 1.11 COORDINATION WITH OTHER TRADES:

A. Coordinate all work of each section with work of other sections to avoid interference. Bidders are cautioned to check their equipment against space available as indicated on drawings, and shall make sure that proposed equipment can be accommodated. Before beginning work under each section, inspect installed work of other trades and verify that such work is complete to the point where the installation may properly begin.

# 1.12 PROTECTION OF ADJACENT WORK:

A. Protect work and adjacent work at all times with suitable covering. All damage to work in place caused by Contractor shall be repaired and restored to original good and acceptable condition using same quality and kinds of materials as required matching and finishing with adjacent work.

### 1.13 EXISTING EQUIPMENT AND MATERIALS:

A. All items of equipment removed under this section of the specifications shall become the property of this Contractor shall be promptly removed from this site.

### 1.14 FIRESTOPPING:

A. Provide firestopping for all mechanical penetrations through fire resistant walls and shaft enclosures, and floor, ceiling, and roof elements of fire resistant assemblies. Firestopping shall provide rating comparable to rating of structure it protects.

B. Firestopping materials currently classified with UL as "Through Penetration Firestop Systems".

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

C. Firestopping materials shall have been tested in accordance with UL 1479 "Fire Tests of Through Penetration Firestops".

### 1.15 CLEAN-UP:

A. At the completion of the contract work, all areas where work has been performed shall be left clean. All trash shall be removed from the site by the Contractor.

### 1.16 APPROVALS AND SUBSTITUTIONS:

- A. Notwithstanding any reference in the specifications to any article, device, product, material, fixture, form, or type of construction by name, make or catalog number, such references shall be interpreted as establishing a standard of quality and shall not be construed as limiting competition; and the Contractor, in such cases, may at his option use any article, device, product, material, fixture, or type of construction which, in the judgment of the Engineer, expressed in writing, is equal to that specified.
- B. Requests for written approval to substitute materials or equipment considered by the Contractor as equal to those specified, shall be submitted for approval to the Engineer ten (10) days prior to bid date. Requests shall be accompanied by samples, descriptive literature and engineering information as necessary to fully identify and evaluate the product. No increase in the contract sum will be considered when requests are not approved.

### 1.17 AS-BUILT DRAWINGS:

- A. The Contractor shall keep a record set of drawings on the job; and as construction progresses shall show the actual installed location of all items, material, and equipment on these job drawings. Indicate approved changes in red ink.
- B. At the time of final completion, a corrected set of As-Built drawings shall be delivered to the Engineer. A final set of reproducible drawings with job information that reflects the actual installation shall be prepared by the Engineer and given to the Owner.

### 1.18 WARRANTY:

- A. The Contractor for each section of the work under this division will furnish to the Owner a written warranty for the installation as installed, including controls and all other equipment covered under each section of the specifications, to perform in a quiet, efficient, and satisfactory manner with no more than normal service.
- B. Each warranty shall extend for a period of one year following substantial completion and acceptance of construction. They shall be endorsed by the Contractor.

# onstruction Documents Issue Date: 06/05/2014

### 1.19 MANUFACTURERS:

- A. In order to define requirements for quality and function of manufactured products, and requirements such as size, gauges, grade selection, color selections and like specifications requirements, the specifications as written hereinafter are based upon products of those manufacturers who are named hereinafter under various specifications for materials.
- B. In addition to products of manufacturers named hereinafter in the specifications, equivalent products of the following named manufacturers will be acceptable under the base bid:
  - 1. Insulation:
    - a) Owens Corning, Johns Manville, CertainTeed Corporation, Knauf Insulation

Architect's Project #: 12.130.09

- 2. Valves:
  - a) Crane Company, Grinnell Company, O.I.C. Valve Co., Chase Brass & Copper Company, Rockwell Manufacturing Company, Consolidated Brass Company, Hammond, Nibco.
- 3. Pipe Hangers:
  - a) Cooper B-Line, Fee and Mason Manufacturing Company, Anvil International, Erico Caddy, Tolco a Division of Nibco
- 4. Plumbing Fixtures:
  - a) Kohler Company, American-Standard Plumbing & Heating Division Company, Just Manufacturing Company, Elkay Manufacturing Company, Crane Company, Stern Williams, Fiat, Zurn Industries
- 5. Flush Valves:
  - a) Sloan Valve Company, Coyne & Delany Company, Zurn Industries (PL Model only)
- 6. Water Closet Seats:
  - a) Church Seat Company, Beneke, Olsonite Corp., Bemis Mfg. Co., Centoco
- 7. Floor Drains, Cleanouts, Floor Sinks, Etc.:
  - a) Wade, Inc., Zurn Industries, Inc., Josam Manufacturing Company, Jay R. Smith
- 8. Dielectric Fittings:

Issue Date: 06/05/2014

- a) Capitol Manufacturing Company, Dresser Manufacturing Company, Epco Sales, Inc.
- 9. Water Heating Equipment:
  - a) Rheem Manufacturing Company, Rudd, State Industries, Lochinvar, A.O. Smith
- 10. Plumbing Trim:
  - a) Delta Commercial Faucet Company, Chicago Faucets, Speakman, T & S Brass and Bronze Works, Inc., Zurn Industries, Symmons Engineering Company, Kohler Company
- 11. Pumps:
  - a) Bell & Gossett Company, Taco, Inc.
- 12. Electric Heat Tracing:
  - a) Thermon Manufacturing Company, Chromalox Inc., Raychem
- 13. Supplies, Traps, Etc.:
  - a) McGuire Manufacturing Company, Engineered Brass Company, Zurn Industries
- 14. Identification Items:
  - a) Seton Name Plate Company, W.H. Brady Company, Handley Industries, Inc.

### PART 2 - PRODUCTS

- 2.1 PAINTING:
  - A. Furnish touch up paint supplied by equipment manufacturer.
  - B. Coat ferrous metal surfaces that do not have factory painting or galvanizing with one coat of Sherwin Williams high heat aluminum paint.
- 2.2 CONCRETE EQUIPMENT FOUNDATIONS:
  - A. Use 3000-psi "batch plant" concrete or approved "precast" reinforced concrete foundations.

### 2.3 VALVES:

A. All valves provided under each section shall be of a single manufacturer unless otherwise specified. Leave packing for all valves in good condition, replacing as necessary for completion of work. Packing is to be of an approved material suitable for required service. Valve manufacturer and pressure rating shall be cast on side of valve body. Each threaded valve shall have a union installed adjacent to it. All valves shall be of listed manufacturer as scheduled hereinafter in other sections of Division 22.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 2.4 FIRESTOPPING MATERIALS:

A. The material used to fill the annular space shall prevent the passage of flame and hot gases sufficient to ignite cotton waste when subjected to ASTM E 119 time-temperature fire conditions under a minimum positive pressure differential of 0.01 inches of water at the location of the test specimen for the time period equivalent to the fire resistance rating of the construction penetrated. Material shall be capable of curing in the presence of atmospheric moisture to produce durable and flexible seal, and will form airtight and watertight bonds with most common building materials in any combination including cement, masonry, steel, and aluminum.

### 2.5 SLEEVES AND OPENINGS:

A. Provide UL certified fire stop sleeving system for all pipe penetrations through fire rated walls, floors, partitions, ceilings, floor-ceiling assemblies and roofs as tested under ASTM E814-02 "Standard Method of Fire Tests of Through Penetration Fire Stops".

### 2.6 SEISMIC RESTRAINTS:

A. Seismic restraints shall be provided per International Building Code Chapter 16 for Category D Buildings.

# PART 3 - EXECUTION

### 3.1 CONCRETE EQUIPMENT FOUNDATIONS:

A. Consult ASHRAE: A Practical Guide to Seismic Restraint, Chapter 6 for specific reinforcement and anchoring details, with respect to pad size and seismic forces. Unless otherwise noted, set all floor mounted and "on-grade" mounted equipment on 6" high concrete foundation pads. Concrete foundations shall be reinforced with #4 bars - 12" o.c. both ways, or as directed by A Practical Guide to Seismic Restraint. Pads shall be approximately 6" larger than equipment base, and have 1" x 1" chamfer on all edges. Pads shall have carborundum brick rubbed finish. Surface finish shall be uniformly smooth. Concrete floor shall be rough and foundation doweled to floor per A Practical Guide to Seismic Restraint.

### 3.2 EXCAVATION, TRENCHING AND BACKFILLING:

A. To accommodate mechanical work execute all excavation, trenching, shoring and backfilling in excess of that required for structures. Coordinate this work with that required for structures, and schedule such work to be consistent with other construction work. All work shall be in compliance with OSHA safety standards.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Perform all excavations of every description and whatever substances encountered, to depths indicated, or as otherwise specified. During excavation, material suitable for backfilling shall be piled a sufficient distance from banks of trench in an orderly manner. Avoid overloading to prevent slides or cave-ins. All excavated materials not required or suitable for backfill shall be removed and wasted as indicated on drawings or as directed. Execute such grading as may be necessary to prevent surface water from flowing into trenches or other excavations. Any water accumulating therein by surface flow, seepage or otherwise, shall be removed by pumping or by other approved method. Such sheeting, bracing and shoring shall be done as may be necessary for protection of work and for safety of personnel. Unless otherwise indicated, excavation shall be by open cut. Short section of a trench may be tunneled if, in the opinion of the Engineer, the pipe can be safely and properly installed and backfill can be properly tamped in such tunnel sections. Excavation shall be considered as unclassified and shall be executed complete.
- C. Width of trenches at any point below top of pipe shall not be greater than outside diameter of pipe plus 16" for pipes measuring up to thirty inches, and 24" for pipe measuring greater than thirty inches, to permit satisfactory jointing and thorough tamping of bedding material under and around pipe. Care shall be taken not to over-excavate. Correct over-excavation by means of backfilling with concrete, or tamped and compacted suitable backfill material as approved for other backfilling work.
- D. Remove rock in either ledge or boulder formation and replace with selected materials in such manner as to provide a compacted earth cushion having a thickness between unremoved rock and pipe of at least eight inches, or 1/2 inch for each foot of fill over top of pipe, whichever is greater, but not more than three-fourths nominal diameter of pipe. Where bell-and-spigot pipe is used, maintain cushion under bell as well as under straight portion of pipe.
- E. Whenever wet or otherwise unstable soil that is incapable of adequately supporting pipe is encountered in trench bottoms, remove such material to depth required and replace to the proper grade with selected material compacted as hereinafter specified for backfilling of pipe.
- F. Bedding surface for pipe shall provide a firm foundation of uniform density throughout entire length of pipe. Carefully bed pipe in a soil foundation that has been accurately shaped and rounded to conform to lowest one-fourth of outside portion of circular piped, or lower curved position of pipe arch for entire length of pipe or arch. When necessary, tamp bedding firmly. Bell holes and depressions for joints shall be only of such length, depth, and width as required for properly making particular type joint.
- G. Existing utility lines that are shown on drawings, or locations of which are made known to Contractor prior to excavation, and that are to be retained, as well as utility lines

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

constructed during excavation operation shall be protected from damage during excavation and backfilling and, if damaged, shall be repaired by Contractor at his expense. In event that Contractor damages any existing utility lines that are not shown on drawings or locations of which are not know to Contractor, report thereof shall be made immediately. If it is determined that repairs shall be made by Contractor, such repairs will be ordered under terms of "Changes in the Work" as set forth in the General Conditions.

- H. After bedding has been prepared and pipe installed, selected material from excavation or burrow, at a moisture content that will facilitate compaction shall be placed along both sides of pipe in layers not exceeding six inches in compacted depth. Bring backfill up evenly on both sides of pipe for its full length. Care shall be taken to ensure thorough compaction of fill under tampers and rammers. Continue this method of filling and compacting until fill has reached an elevation of at least 12 inches above top of pipe. Backfill and compact remainder of trench by spreading and rolling, or compact by mechanical rammers or tampers in layers not exceeding eight inches.
- In compacting by rolling or operating heavy equipment parallel with pipe, displacement of or injury to pipe shall be avoided. Movement of construction machinery over a culvert or storm drain at any stage on construction shall be at Contractor's risk. Any pipe damaged thereby shall be repaired or replaced at option of Engineer and expense of Contractor.
- J. Wet down all fill and backfill work, and each layer thereof to obtain optimum moisture content. Compaction shall then be executed to density of 95 percent of that obtainable in laboratory by Procter Method, or by AASHO Method T99.
- K. When fill or backfill is required to be compacted to any specified density factor, tests shall be executed by an approved laboratory to ascertain compliance with requirements. One test shall be made for each 50 linear feet of open trench. Repeat tests for any specific area which fails to meet requirements until conformance is obtained. Cost of laboratory services shall be borne by Contractor as part of costs for this section of work.
- L. Remove from site all excess earth, rock and other debris resultant from excavation and backfilling work.

### 3.3 PIPE FITTINGS:

- A. General: Provide complete systems of piping and fittings for all services as indicated. All pipe, valves, and fittings shall comply with American National Standards Institute, Inc. Code and/or local codes and ordinances. All fittings shall be domestically produced from domestic forgings. Cut pipe accurately to measurements established at building or site, and work into place without springing or forcing, properly clearing all windows, doors, and other openings or obstructions.
- B. Excessive cutting or other weakening of building to facilitate piping installation will not be permitted. Piping shall line up flanges and fittings freely and shall have adequate unions and flanges so that all equipment can be disassembled for repairs. Test all piping prior to insulation or concealing.

Issue Date: 06/05/2014

## 3.4 PIPE:

- A. All piping material shall be as specified in other sections of this division.
- B. Fittings and Connections: All turns and connections shall be made with long radius fittings as scheduled hereinafter.
- C. Pipe joints shall be made in accordance with the following applicable specifications:
- D. Make up flanged joints with ring-type gaskets, 1/16 inch thick.
- E. Make all solder joints with non-corrosive type flux 95 Percent tin and 5 percent antimony alloy solder.
- F. Cast Iron Pipe: Joints in cast iron soil pipe and fittings without hubs shall be made using cast iron No-Hub joint with "Clamp-All Corporation" clamp, or approved equal by Husky or Mission.
- G. Plastic Pipe: Joints for polyvinyl chloride pipe and fittings shall be made using solvent cement. Threaded joints shall be used only where required for disconnection and inspection.
- H. Make joints between earthenware fixtures and soil pipe by means of brass floor connections wiped to lead pipe. Joint shall be gas-tight and water-tight. Set all floor type water closets with a "no-seep" sleeve gasket. Caulk around perimeter of all floor mounted plumbing fixtures for leveling and prevention of water seepage.

## 3.5 SLEEVES:

A. Provide all sleeves in floors, beams, wall, roof, etc. as required for installing work of this division unless otherwise specified hereinafter. Size sleeves for insulated pipe to accommodate both pipe and insulation. Construct vertical sleeves in connection with concealed piping of 22 gauge galvanized iron. Sleeves thru fire-rated assemblies shall be firestopped as specified herein and insulation shall not pass thru sleeve unless material complies with firestopping specified.

## 3.6 PIPE HANGERS, SUPPORTS AND INSERTS:

- A. Pipe hangers, supports and inserts shall comply with Table 308.5 of the 2012 International Plumbing Code and be provided as follows:
- B. All piping shall be supported by forged steel hangers or brackets suitably fastened to structural portion. Wall brackets shall be Fee & Mason Fig. No. 151. Provide lock nuts on all adjustable hanger assemblies.

## PIPE SIZE - INCHES

	1/2 - 2	2-1/2-4	6 – Up	Wall Plate Hanger
Grinnel	104	260	171	139
Fee & Mason	199	239	170	302
Elcen	92	12	15	

- C. Hanger or Support Spacing (unless specified different hereinafter):
  - 1. Copper Pipe:

Nominal Pipe Size – Inches	Maximum Span - Feet
1-1/4" and under	6'
1-1/2" and above	10'

2. Cast Iron Pipe:

Length of Pipe – Feet	Maximum Span - Feet		
5'- 0"	5'		
10'- 0"	10'		

3. Plastic Pipe:

4'- 0" intervals

- D. Size hangers on insulated piping to permit insulation and saddles to pass full size through hanger.
- E. On Cast Iron Soil Pipe (horizontal):
  - 1. At least one hanger on each full length of pipe, close to hub where possible and at least one within 24 inches of each fitting, and wherever else required to prevent tendency toward deflection due to load. Hanger at upper angle of each drop. Where multiple fittings are used, hangers shall be located not more than 4 feet on centers and adjacent to hubs on fittings.
- F. On Chromium-plated Pipe:
  - 1. Provide chromium-plated supports on chromium-plated pipe and fittings.
- G. Trapeze Hangers:
  - 1. May be used for groups of pipes close together and parallel. Trapeze hangers may be constructed from structural channel or angle irons or from pre-formed channel shapes. All pipe lines must be held on specific centers by U bolts, clips or clamps.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# H. Inserts:

1. For each hanger on horizontal pipes, installed before concrete is poured. Inserts shall permit horizontal adjustment of the nut.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# I. Special and Additional Supports:

1. Special supports will be required where hangers cannot be used. Horizontal pipes shall be secured to prevent vibration or excessive sway. Where pipes must be laid on fill, they shall be supported at each joint by brick or concrete supports carried down into solid, natural earth. Where required, provide additional hangers to secure required level, slope or drainage, and also to prevent sagging. Provide a hanger within one foot of each elbow. Provide all miscellaneous steel required for pipe supports, anchors, etc.

## 3.7 INSULATION SHIELDS:

A. Provide all insulated piping with 10-inch long (16 gauge) protective galvanized sheet metal shields extending 120 degrees around bottom of insulated pipe.

## 3.8 FLOOR, WALL AND CEILING PLATES:

A. Where pipes pass through floors, finished walls, or ceilings, fit with chromium plate cast brass plates or chromium plated steel plates as specified hereinafter. Plates shall be large enough to completely close hole around pipes, and shall be square, octagonal, or round, with least dimension not less than 1-1/2 times larger than diameter of pipe. Secure plates in an approved manner. Plates shall be Beaton-Caldwell No. 3A for floors and No. 40 for walls and ceilings.

## 3.9 SWING CONNECTIONS:

A. Swing connections shall be provided at all points of expansion. Install all connections to equipment, etc. in a manner to allow for normal pipe movement due to thermal expansion without causing undue stresses to be exerted on said equipment.

#### 3.10 REDUCING FITTINGS:

A. Where pipe lines reduce in size, provide reducing fittings wherever possible. Provide eccentric fittings or reducers where horizontal runs of supply lines reduce in size, and install so that there will be no air trapped in hot or cold water systems. In screwed work, no bushings shall be used unless there is a difference of two standard pipe sizes between inner and outer threads.

## 3.11 DIELECTRIC CONNECTIONS:

A. Wherever any connection is made between dissimilar metals, provide dielectric pipe couplings or unions.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 3.12 CLEANING:

A. All surfaces on metal, pipe, insulation covered surfaces, and other equipment furnished and installed under this division of the specifications shall be thoroughly cleaned of grease, scale, dirt and other foreign material.

## 3.13 TESTING (PIPING):

- A. Upon completion of each system of work under this division, and at a designated time, all piping shall be pressure tested for leaks in the presence of the owner. Owner shall be notified five days before testing is to be conducted and all tests shall be conducted in the presence of the owner. All equipment required for test shall be furnished by contractor at his expense. All tests shall be performed as specified hereinafter. If inspection or tests show defects, such defective work or material shall be replaced and inspection and tests repeated at no additional cost to owner. Make tight any leaks. Repeat tests until system is proven tight. Caulking of leaks will not be permitted. All equipment not capable of withstanding the test pressure shall be valved off during the test.
- B. Drainage System: Drainage and venting system shall be tested in such a manner that cast iron soil pipe will not be subjected to excessive pressure. Testing of any portion of this system shall be executed by plugging all necessary openings of that portion of system being tested and filling with water to a height of not less than ten feet above highest floor, or a pump may be used to maintain an equivalent pressure. Test pressure shall be maintained to thirty minutes when using pump method. When using water column method, test period shall also be thirty minutes, and water level shall not drop. Hot poured joints shall not be tested with more than eighty feet head of water. No tests shall be made during freezing weather.
- C. Hot and Cold Water Piping: Upon completion of rough-in and before setting fixtures, entire hot and cold water systems shall be tested at a hydrostatic pressure of 1-1/2 times operating pressure, but not less than 150 psig, and be proved tight at this pressure. Where a portion of water system is to be concealed before completion, this portion shall be tested separately in a manner described for the entire system. Water used for testing shall be from a potable source of supply.
- D. Storm drainage piping shall be tested in a manner as specified hereinbefore for drainage system.

# 3.14 PIPE CODING:

A. All piping installed under this division shall be coded and marked with "Perma-Code" pipe markers as manufactured by W.H. Brady Company, 712 Glendale Avenue, Milwaukee, Wisconsin. Markers shall be applied to properly identify piping, but in no case shall they be applied more than 20 feet apart. Markers shall be 1-1/8 inch by 7 inches and shall be secured by spiral wrapping with 3/4 inch wide vinyl banding tape, color matching service, at each end of marker.

## 3.15 OPERATION AND MAINTENANCE INSTRUCTIONS, AND MAINTENANCE MANUAL:

A. Upon completion of work, and at a time designated by the engineer, a competent employee of the contractor shall be provided to instruct a representative of the owner in the operation and maintenance of the system.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Minimum instruction period shall be:
  - a) Plumbing System 1/2 day
- B. Maintenance Manuals: The contractor shall compile and bind five (5) sets of all manufacturer's instructions and descriptive literature on all items of equipment furnished under this work. These instructions shall be delivered through the general contractor to the engineer for approval prior to final inspection.
  - 1. Instructions shall include:
    - a) Warranty letter signed by the Mechanical Contractor.
    - b) Index for each section with each section properly identified.
    - c) Copy of sterilization report.
    - d) Copy of backflow preventer test.
    - e) Complete equipment list with model and serial numbers.
    - f) Copy of one complete, approved submittal for each equipment section.
    - g) Description of each system, including manufacturer's literature for all items.
    - h) Start-up and shut-down description for each system.
    - i) Suggested operating and maintenance instructions with frequency of maintenance indicated.
    - j) Parts list for all items of equipment.
    - k) Name, address, and telephone number of nearest sales and service organization for all items of equipment.
- C. Manuals shall be 8-1/2 x 11 inch text pages bound in three ring expansion binders with a hard durable cover with clear plastic pocket on front for title page. Prepare binder covers with printed subject title of manual, title of project, date, and volume number when multiple binders are required. Printing shall be on face and spine. Provide a table of contents for each volume. Internally subdivide the binder contents with divider sheets with typed tab titles under reinforced plastic tabs. Provide directory listing as appropriate with names addresses, and telephone numbers of design consultant, Contractor, subcontractors, equipment suppliers, and nearest service representatives.

End of Section 220010

SECTION 220500 - PLUMBING

#### PART 1 - GENERAL

## 1.1 WORK INCLUDED:

A. General Requirements: This Section of the Specifications and related drawings describe requirements pertaining to plumbing work including applicable insulation in separate Section 220700. All work shall conform to Section 220010, General Provisions - Plumbing. Work includes, but is not necessarily limited to:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. All fixtures noted or specified.
- 2. Cold water and hot water systems.
- 3. Storm drainage system.
- 4. Soil, waste and vent piping system.
- 5. Other plumbing indicated on drawings, specified herein, or required for complete and proper installation in accordance with applicable codes and regulations.
- 6. Insulation.
- B. Upon completion of work, all fixtures, devices, etc. for use by persons with disabilities shall meet all requirements as set forth by the Americans with Disabilities Act (ADA).

## PART 2 - PRODUCTS

## 2.1 SOIL, WASTE, DRAIN AND VENT PIPING AND FITTINGS:

- A. Materials shall conform to the following specifications requirements:
- B. Construct all building sewers and building drain lines underground and/or under floor slabs to a point indicated on the drawings, with Schedule 40 PVC plastic pipe and fittings conforming to ASTM D-2665 or ASTM D-2949. "Co-ex" piping is not allowed.
- C. Construct all soil, drain and waste piping, 2 inches and larger in diameter that is installed above floor slabs with standard weight, asphaltum-coated, cast iron, hubless type, soil pipe and fittings. Pipe and fittings shall be labeled with the Cast Iron Soil Pipe Institute's Collective Trademark of quality and permanence as illustrated in ASTM Standard A-74, which indicates that it complies with this standard. No import pipe will be allowed. Joints shall be made with "Clamp-All Corp." clamp, or approved equal by Husky or Mission, for aboveground piping.
- D. Plumbing Contractor will connect up soil pipe at a point five feet outside the building as indicated on the drawings.

E. Construct vent piping with standard weight asphaltum-coated, cast iron, hubless for sizes 2 inches and larger. Joints shall be made with "Clamp-All Corp." clamp, or approved equal by Husky or Mission, for aboveground piping.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 2.2 SUPPLY PIPING AND FITTINGS:

- A. Materials for supply piping and fittings shall conform to the following specification requirements:
- B. All water main 3 inches and smaller buried in earth and/or below slabs shall be seamless hard drawn type K copper tubing, ASTM B 88, with wrought copper ASA B16.22 fittings, Class 150.
- C. All water piping aboveground shall be seamless hard drawn type L copper tubing, ASTM B 88, with wrought copper ASA B16.22, fittings, Class No. 150.
- D. Valves: Materials for valves shall conform to the following specification requirements:
  - 1. Ball:
    - a) Ball valves 3" and smaller shall be two-piece bronze body, full port, chrome ball, RTFE seats, with adjustable packing, rated for 600 psig minimum working pressure, meeting WWV-35 and MSS-SP110.

## 2. Check:

- a) Valves 2 inches and smaller shall be of swing check, solder end type suitable for a minimum working pressure of 300 psig.
- E. Hose Bibb: Interior hose bibbs shall be on angle pattern for 3/4- inch hose connection with rough nickel plate finish with backflow preventer.
- F. Temperature and pressure relief valves shall be type N 40 XL as manufactured by Watts Regulator Company, Cash Acme, Conbraco, or equal.

#### 2.3 CLEANOUTS:

- A. Provide cleanouts as follows:
  - 1. Unfinished areas and chases Z-1450-7 C.I. cleanout ferrule with counter-sunk lead seal plug.
  - 2. Finished walls ZN-1440-4 C.I. wall cleanout ferrule with raised head lead seal plug and Nikaloy square scoriated frame and cover.
  - 3. Finished linoleum, asphalt, or vinyl tile floor ZN-1400-6 C.I. floor cleanout with seriated cut-off ferrule lead seal plug adjustable Nikaloy round scoriated frame and cover recessed for tile.

4. General use in Finished Floor - ZN-1400-3 C.I. floor cleanout with seriated cutoff ferrule lead seal plug adjustable Nikaloy square scoriated frame and cover.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

5. All cleanouts shall be as manufactured by Zurn Industries, Inc., Jay R. Smith, Josam, or equal.

## 2.4 DRAINS:

A. Provide floor drains of manufacturer's standard size at locations indicated on drawings. Construct drains of cast iron with polished brass strainer. Floor drains shall be as indicated on drawings. Drains shall be as manufactured by Zurn Industries, Inc., Jay R. Smith, Josam, or equal.

## 2.5 WATER HEATER:

A. Provide water heater complete, including all piping, specialties and connections as indicated on the drawings. All water heaters shall meet the minimum energy factor required by the U.S. Federal "National Appliance Energy Conservation Act of 2004".

#### 2.6 FIXTURES AND FIXTURE TRIM:

A. Fixtures and fixture trim shall be as called for on fixture schedule shown on drawings. All enamel on cast iron fixtures shall be acid resisting. Color of fixtures shall be white.

## 2.7 BACKFLOW PREVENTERS:

- A. Provide all backflow preventer in accordance with the requirements of the South Carolina State Board of Health. Backflow preventer for domestic water service shall be a Watts Model 007M1-QT-S double check backflow preventer assembly with quarter turn ball valves and strainer as sized and shown on plans. Backflow preventers shall be suitable for supply pressures up to 175 psi and water temperatures to 110°F. Backflow preventers shall be as manufactured by Watts Industries, Zurn Wilkins, FEBCO, or equal.
- B. Upon completion of installation, contractor shall test all backflow preventers in accordance with the requirements of SCDHEC Regulations, and send a copy of this test report to the engineer and include a copy in the closeout documents.

## 2.8 STORM DRAINAGE:

A. All pipes shall conform to sizes shown on drawings. All drain piping shall be similar to that indicated for sanitary waste piping.

## 2.9 RECIRCULATING PUMP:

A. Recirculating pump shall be Bell & Gossett, or approved equal, of high efficiency models indicated on drawings. Pumps shall be of a horizontal, permanently lubricated type for quiet operation. The motor shall be non-overloading at any point of the pump performance curve.

## 2.10 HEAT TRACE:

1. Provide Thermon, or equal, Model 5FLX-1-OJ automatic regulating heat trace with ambient sensing control (B4X-15140). System shall be complete with indicator panel (TC-101A) and shall be installed in Mechanical 122. Heat trace shall be installed around piping, valves, etc. per the manufacturer's instructions for the entire length of piping located exterior to the conditioned building. Each building shall be connected to electrical service in each building that it is closest too prior to becoming exterior.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## PART 3 - EXECUTION

## 3.1 EXISTING CONDITIONS:

- A. Verify locations and inverts of existing and proposed pipes. Location of structural elements, locations and sizes of chases, type and method of construction of floors, walls, partitions, etc.
- B. Drawings do not indicate all offsets, fittings, and specialties. Examine other drawings, investigate conditions to be encountered and arrange work accordingly, furnishing required fittings, valves, specialties, etc. without extra charge. Where conditions necessitate rearrangement, submit for approval sketches showing proposed arrangement.

## 3.2 INSTALLATION:

## A. GENERAL:

- 1. Protect pipe openings and drains by plugs or caps. Duct tape will not be acceptable. Clean all stoppages.
- 2. Unless otherwise shown, install piping concealed, straight, without sags or pockets and graded for drainage. Cut pipe ends square and ream. Before assembly, clean dirt, scale and chips.
- 3. Provide clearance between pipe and building structure so pipes can expand without damage to building structure.
- 4. Schedule meetings with other trades before and during installation to avoid conflicts and ensure that pipes and equipment are installed in best manner, taking into consideration headroom, maintenance, appearance and replacement.

## 3.3 PAINTING:

A. Clean damaged factory finishes and coat with matching touch-up paint. Paint all supports and hangers with two coats of high heat aluminum paint.

## 3.4 SOIL, WASTE, SEWER AND VENT PIPING:

A. Install sewer and water pipes in separate trenches with grades uniform to provide solid bearing. Dig bell holes at hubs. Piping through or under footings shall be provided with a pipe sleeve or relieving arch.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Run horizontal pipe, graded uniformly, not less than 1/4" per foot for pipes 2-1/2" and smaller; and 1/8" per foot for larger pipes. Offset as required to pass obstacles.
- C. Change size by reducing fittings. Change directions by 45-degree wyes and long-sweep bends. Use short-sweep bends only with written approval. No pipe shall be drilled, tapped, or welded. Saddle hubs and bands, tapped tees, and crosses will not be approved.
- D. Upon completion of tests and inspections, backfill with approved material, placed and tamped to prevent settlement.

#### 3.5 HOT AND COLD WATER PIPING:

- A. Unless otherwise indicated, run hot and cold water piping concealed, and uniformly pitched to ensure venting and drainage. Install drain valves at low points.
- B. Unless otherwise required, branches to small fixtures shall be 1/2" ID for single fixture and 3/4" ID for two fixtures. Pipe size indications are "nominal" sizes.

## 3.6 STORM DRAINAGE:

A. This work in general consists of drainage lines and connections to existing lines as indicated on drawings.

# 3.7 AIR CHAMBERS:

A. At each flush valve and other quick closing valves not protected by a shock arrestor, and at top of each hot and cold-water riser, provide a 12-inch long air chamber.

## 3.8 SHOCK ABSORBERS:

A. Provide sealed air chambers of PDI size models as indicated and as manufactured by Josam Manufacturing Company Series 7500 or Zurn series Z-1700. All shock absorbers shall bear PDI seal of approval. Locate shock absorbers so that they are accessible above lay-in ceiling or from all access panels installed by others.

## 3.9 TRAPS:

A. Provide each fixture with a trap when connection to drainage system is required. Place each trap as near to fixture as possible. No fixture shall be double trapped. Traps installed on bell-and-spigot pipe shall be cast iron. Traps installed on threaded pipe shall be recess drainage pattern.

## 3.10 FLASHING:

A. Vent pipes and stack vents shall be flashed and made watertight at roof with 16 ounce, soft, sheet copper or 4-pound sheet lead. Flashings shall extend not less than 8 inches from pipe in all directions. Flashing for pipe shall be extended up the pipe a minimum of 6 inches, at which point threaded standard cast iron or malleable iron recess roof coupling shall be installed to form counterflashing or rain guard.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 3.11 CLEANOUTS:

A. Provide an easily accessible cleanout at foot of each vertical soil or waste stack and where indicated on drawings. Cleanouts shall be of the same nominal size as pipe in which they are installed, up to 4 inches; and not less than 4 inches for larger sizes. A cleanout shall consist of a long sweep 1/4 bend or one or two 1/8 bends. Maximum spacing of cleanouts shall be one hundred feet.

#### 3.12 DRAINS:

A. Provide floor drains of manufacturer's standard size at locations indicated on drawings. Carefully set drains to grade to provide drainage of surrounding area, and trap.

## 3.13 FIXTURES AND FIXTURE TRIM:

- A. Provide lavatories with angle stops. Provide all other plumbing fixtures with either angle or straight stops, integral with faucets, or with concealed type lock shield or loose-key pattern.
- B. All fixtures and trimmings shall be designed to prevent backflow of polluted water or waste into water supply system.
- C. Except where noted otherwise, exposed piping fittings and trimmings shall be chromium plated over nickel-plated brass with polished, bright surfaces.
- D. Securely support fixtures with approved brackets, chairs, bolts, and metal expansion inserts. Where chases are provided or adjacent space in an undeveloped area, use through-bolts and heavy steel load distributing plate in addition to other means specified.

## 3.14 SANITARY SEWER SYSTEM:

A. Work includes providing of all materials and equipment, and performing all labor necessary to construct sewers and connections, including all pipe, wye branches, joint material, and appurtenances which may be reasonably implied as necessary to complete work shown on drawings or specified herein.

## 3.15 STERILIZATION:

A. All water piping installed under this section shall be thoroughly sterilized. The entire sterilization procedure shall be in strict accordance with the requirements of the State Board of Health and, upon completion of the sterilization; the potability of the water in

University of South Carolina Athletic Village Tennis Complex Addition Construction Documents

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

the system shall be checked and approved by the Engineer. All costs for testing shall be paid for by this Contractor.

End of Section 220500

Issue Date: 06/05/2014

## SECTION 220700 - PLUMBING INSULATION

## PART 1 - GENERAL

## 1.1 WORK INCLUDED:

- A. General Requirements: This section shall include all insulation as required for installation on all items as specified hereinafter and/or as indicated. All insulations shall be installed in a workmanlike manner by qualified workers in the employment of an independent insulation contractor. Costs of insulation shall be included as part of work by contractor as applicable to his section of work. No separate bid is to be included for insulation work.
- B. Fire hazard classification for all material shall not exceed flame spread of 25 and smoke development of 50 as classified by Underwriters Laboratories under Test Method ASTM E-84 and acceptable under NFPA Standards. This is to apply to the complete system and be a composite rating of insulation material with jacket or facings, vapor barrier, joint sealing tapes, mastic and fittings.
- C. Prior to commencing any work, submit data sheets for engineer's approval of all material proposed to be used on this project.

## PART 2 - PRODUCTS

## 2.1 ABOVE GROUND INDOOR PIPING:

## A. Pipe Insulation:

- 1. All water piping shall be insulated with heavy density fiberglass with all-service jacket Owens-Corning Double Self-Sealing Lap, ASJ/SSL-II, one piece, to be used on all lines above and below ambient temperature from 0°F to 850°F.
- 2. In block walls as construction progresses upwards, use Armacell Tubolit, or equal, in a thickness adequate to maintain an insulation surface temperature of 84°F. Miter elbows and seal with adhesive. Coat all joints with Childers CP-30 LO or CP-35 WB Vapor Barrier Coatings or equal.

## 2.2 JACKET FOR OUTDOOR PIPING:

- A. All insulation outside (including insulation options) shall be protected with aluminum jacketing with factory applied moisture barrier. The aluminum jacketing shall be 0.016 thickness and be of 3003 alloy and H-14 temper. Jacketing shall be applied with 2-inch circumferential and 1-1/2 inch longitudinal lap and secured with 3/8 inch wide aluminum bands, 8 inches on center.
- B. All elbows shall be covered with 2 piece aluminum insulation covers, manufactured from 110 aluminum alloy in .024" thickness, Childers Aluminum E11-Jacs or approved equal.

# 2.3 PIPE INSULATION THICKNESS:

A. Piping for the following systems shall be insulated to the thickness listed:

Item Insulation Thickness (Inches)

Fiberglass

K = .24

Cold Pipes:

Cold Water (Domestic) 1"

Hot Pipes:

Hot Water (Domestic -

Supply & Recirculating) 1"

## PART 3 - EXECUTION

## 3.1 PIPE INSULATION:

- A. All insulation shall be applied to clean, dry surfaces butting all sections firmly together and finishing as specified hereinafter.
- B. All vapor barriers shall be sealed, and shall be continuous throughout. No staples shall be used on any vapor barrier jacket unless sealed with vapor barrier coating or vapor barrier tape.
- C. Insulation of all insulated lines shall be interpreted as including all pipe, valves, fittings and specialties comprising the lines.
- D. Where sectional insulation is not practical, the proper insulation cement or block insulation shall be utilized by forming it to the applied surface.
- E. Pipe Insulation Protection: Direct contact between pipe and hangers shall be avoided. Hanger shall pass outside of a sheet metal protection saddle which shall cover a section of high density insulation (cellular glass or calcium silicate), of sufficient length to support the weight of the pipe without crushing the insulation. The vapor barrier shall be continuous behind the saddle or shall be lapped over the saddle and securely cemented thereto.
- F. All pipe covering shall be furnished with self-seal lap and 3" wide butt joint strips. The release paper is pulled from adhesive edge, pipe covering closed tightly around pipe and self-seal lap rubbed hard in place with the blunt edge of an insulation knife. This procedure applied to longitudinal as well as circumferential joints. Staple all longitudinal and circumferential joints with 9/16" staples 6" on center and seal over all staples with

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Childers CP-30 vapor barrier coating. Care shall be taken to keep jacket clean as it is the finish on all exposed work. All adjoining insulation sections shall be firmly butted together before butt joint strip is applied, and all chilled water and cold water service lines shall have vapor barrier coating thoroughly coated to pipe at butt joints and at all fittings. All fittings, valve bodies, unions, and flanges shall be finished as follows:

G. Apply fiberglass inserts to all other hot fittings and cold water fittings in conjunction with Proto PVC Fitting Covers. Seal cold applications as recommended by the manufacturer.

# 3.2 ALUMINUM JACKET:

A. Jacketing shall be applied with 2-inch circumferential and 1-1/2 inch longitudinal lap and secured with 3/8 inch wide aluminum bands, 8 inches on center and at joints.

End of Section 220700

Issue Date: 06/05/2014

SECTION 230010 - GENERAL PROVISIONS - HVAC

## PART 1 – GENERAL

## 1.1 SCOPE:

A. Bids of work covered by each section of these specifications shall be based on the layout and equipment as shown and specified with only such approved substitutions as are allowed. Drawings show general arrangement of ductwork and piping. Because of small scale of drawings, it is not possible to indicate all offsets, fittings, and accessories, which may be required. Contractor shall carefully investigate structural and finish conditions affecting his work and shall arrange such work accordingly, furnishing such fittings, traps, valves, and accessories as may be required to meet such conditions. Where locations make it necessary or desirable from Contractor's standpoint to make changes in arrangements or details shown on drawings, he may present suggestions for such changes and obtain Engineer's approval prior to making such changes.

## 1.2 CODES:

A. All work under this division shall be in strict compliance with "International Codes" and all applicable Codes and Regulations of the State of South Carolina.

## 1.3 MATERIAL AND SHOP DRAWINGS:

- A. Use only new materials and the standard product of a single manufacturer for each article of its type unless specifically mentioned otherwise. Materials and workmanship in the case of assembled items shall conform to the latest applicable requirements of NFPA, ASME, NEC, ASTM, AWWA, NEMA, and ANSI.
- B. Schedule submittals to expedite work. Unless otherwise indicated in this Section, submittals shall be submitted within 30 days of date of Notice to Proceed. Provide electronic format PDF or six (6) copies of submittals for review and approval. Provide folders or binders for each submittal. All submittals shall be bound in a single volume. Partial lists will not be considered and will be returned to the Contractor. Controls may be submitted separately and shall be submitted no later than 60 days of notice to proceed. Identify Project, Contractor, subcontractor, supplier, manufacturer, pertinent drawing sheet and detail numbers, and associated specification section numbers. A table of contents shall be included in the front of the submittal with tabs indicating each section. Identify variations from requirements of Contract Documents.

## C. Contractor responsibilities:

1. Review submittals prior to transmittal. Verify compatibility with field conditions and dimensions, product selections and designations, quantities, and conformance of submittal with requirements of Contract Documents. Return non-conforming submittals to preparer for revision rather than submitting to Engineer. Coordinate submittals to avoid conflicts between various items of work. Failure of Contractor to review submittals prior to transmittal to Engineer

Issue Date: 06/05/2014

shall be cause for rejection. Incomplete, improperly packaged, and submittals from sources other than Contractor will not be accepted. Submittals not stamped APPROVED and signed by the Contractor will be returned to the Contractor.

- 2. Where required by specifications or otherwise needed, prepare drawings illustrating portion of work for use in fabricating, interfacing with other work, and installing products. Prepare ½" per foot scale drawings of all mechanical rooms when substituting items of equipment that are not the basis for design. All equipment submitted shall be of adequate size and physical arrangement to allow unobstructed access when installed, for routine maintenance, coil removal, shaft removal, motor removal and other similar operations. Contract Drawings shall not be reproduced and submitted as shop drawings. Drawings shall be 8-1/2 by 11 inches minimum and 24 by 36 inches maximum. Title each drawing with Project name and reference the sheet the drawing corresponds to.
- 3. Provide product data such as manufacturer's brochures, catalog pages, illustrations, diagrams, tables, performance charts, and other material which describe appearance, size, attributes, code and standard compliance, ratings, and other product characteristics. Provide all critical information such as reference standards, performance characteristics, capacities, power requirements, wiring and piping diagrams, controls, component parts, finishes, dimensions, and required clearances. Submit only data which are pertinent. Mark each copy of manufacturer's standard printed data to identify products, models, options, and other data pertinent to project.
- 4. Control diagrams: Show relative positions of each component as a system diagram. Provide points list, wiring diagram and schedule of all products and components used in system.
- 5. Engineer will review and return submittals with comments. Do not fabricate products or begin work which requires submittals until return of submittal with Engineer acceptance. Promptly report any inability to comply with provisions. Revise and resubmit submittals as required within 15 days of return from Engineer. Make re-submittals under procedures specified for initial submittals. Identify all changes made since previous submittal.

## D. Engineer Review:

- 1. Engineer will review submittals for sole purpose of verifying general conformance with design concept and general compliance with Contract Documents. Approval of submittal by Engineer does not relieve Contractor of responsibility for correcting errors which may exist in submittal or from meeting requirements of Contract Documents. After review, Engineer will return submittals marked as follows to indicate action taken:
- 2. No Exception: Part of work covered by submittal may proceed provided it complies with requirements of Contract Documents. Final acceptance will depend upon that compliance. The term "approved" shall only indicate that there is no exception taken to the submittal.

- Architect's Project #: 12.130.09

  Issue Date: 06/05/2014
- 3. No Exception As Corrected: Part of work covered by submittal may proceed provided it complies with notations and corrections on submittal and requirements of Contract documents. Final acceptance will depend upon that compliance.
- 4. Revise And Resubmit: Do not proceed with part of work covered by submittal including purchasing, fabricating, and delivering. Revise or prepare new submittal in accordance with notations and resubmit.

## E. Samples:

1. Submit samples to illustrate functional and aesthetic characteristics of products with all integral parts and attachment devices. Include full range of manufacturer's standard finishes, indicating colors, textures, and patterns for A/E selection. Submit the number of samples specified in individual specification sections. One sample will be retained by A/E.

# F. Items Requiring Submittal are as Follows:

- 1. Test and Balance
- 2. Insulation
- 3. Ductwork
- 4. All items listed in MANUFACTURERS: Section of 230010

## 1.4 LEAD FREE:

A. All solder, flux and pipe used in water system must be lead free. Lead free is defined as less than 0.2 percent lead in solder and flux and less than 8.0 percent lead in pipes and fittings.

## 1.5 AMERICANS WITH DISABILITIES ACT:

A. All items or work under this division of the specifications shall comply with guidelines as set forth in the Americans With Disabilities Act.

#### 1.6 PERMITS AND FEES:

A. Obtain permits, licenses, pay fees, etc. as required for performance of Contract. Arrange for necessary inspections required by governing authority and deliver certificates of approval to Architects or their representatives. File plans required by governing body.

# 1.7 DEFINITIONS:

A. In this division of the specifications and accompanying drawings, the following definitions apply:

Issue Date: 06/05/2014

- B. Provide: To purchase, pay for, transport to the job site, unpack, install, and connect complete and ready for operation; to include all permits, inspections, equipment, material, labor, hardware, and operations required for completion and operation.
- C. Install (Installed): To furnish and install complete and ready for operation.
- D. Furnish: To purchase, pay for, and deliver to the job site for installation by others.
- E. The Mechanical Contractor is cautioned that "furnish" requires coordination with others. Such coordination costs shall be included as part of Mechanical Contractor's bid.

#### 1.8 CUTTING AND PATCHING:

- A. Cutting of walls, floors, roofs, partitions, and ceiling, required for proper installation of the systems shall be performed under this contract.
- B. Cutting shall be done in a neat, workmanlike manner. No joist, beams, girders, columns, or other structural members may be cut without written permission from the Engineer. When possible, holes shall be saw-cut or core drilled neat to minimize patching.
- C. Re-routing of existing pipes, insulation, etc. as required for installation of new system is included in this work. All work shall be done in accordance with specifications for new work of the particular type involved.
- D. Patching shall be performed to match existing structures, exterior walls and roofs, and shall form watertight installation.

## 1.9 VERIFICATION OF DIMENSIONS, ETC.:

A. The Contractor shall visit the premises and thoroughly familiarize himself with all details of the work, working conditions, verify all dimensions in the field, advise the Engineer of any discrepancy, and submit shop drawings of any changes he proposes to make in quadruplicate for approval before starting the work. Contractor shall install all equipment in a manner to avoid building interference.

## 1.10 COORDINATION WITH OTHER TRADES:

- A. Coordinate all work of each section with work of other sections to avoid interference. Bidders are cautioned to check their equipment against space available as indicated on drawings, and shall make sure that proposed equipment can be accommodated. Before beginning work under each section, inspect installed work of other trades and verify that such work is complete to the point where the installation may properly begin.
- B. Where equipment supplied by an approved manufacturer is substituted for the specified equipment, the Contractor will be responsible for coordinating any changes required in his work or other trades work, including but not limited to electrical requirements, structural steel requirements and space requirements. Any additional costs required to make changes to other trades work shall be borne by this contractor.

## 1.11 PROTECTION OF ADJACENT WORK:

A. Protect work and adjacent work at all times with suitable covering. All damage to work in place caused by Contractor shall be repaired and restored to original good and acceptable condition using same quality and kinds of materials as required to match and finish with adjacent work.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 1.12 CLEAN-UP:

A. At the completion of the contract work, all areas where work has been performed shall be left clean. All trash shall be removed from the site by the Contractor.

## 1.13 APPROVALS AND SUBSTITUTIONS:

- A. Notwithstanding any reference in the specifications to any article, device, product, material, fixture, form, or type of construction by name, make or catalog number, such references shall be interpreted as establishing a standard of quality and shall not be construed as limiting competition; and the Contractor, in such cases, may at his option use any article, device, product, material, fixture, or type of construction which, in the judgment of the Engineer, expressed in writing, is equal to that specified.
- B. Requests for written approval to substitute materials or equipment considered by the Contractor as equal to those specified, shall be submitted for approval to the Engineer ten (10) days prior to bid date. Requests shall be accompanied by samples, descriptive literature and engineering information as necessary to fully identify and evaluate the product. No increase in the contract sum will be considered when requests are not approved.
- C. The Contractor shall bear the burden and cost of coordinating with all trades any changes in work required by substitutions, including but not limited to electrical connections, additional components required, service clearance, etc.

# 1.14 AS-BUILT DRAWINGS:

- A. The Contractor shall keep a record set of drawings on the job; and as construction progresses shall show the actual installed location of all items, material, and equipment on these job drawings. Indicate approved changes in red ink.
- B. At the time of final completion, a corrected set of As-Built drawings shall be delivered to the Engineer. A final set of reproducible drawings with job information that reflects the actual installation shall be prepared by the Engineer and given to the Owner.

## 1.15 WARRANTY:

A. The Contractor for each section of the work under this division will furnish to the Owner a written warranty for the installation as installed, including controls and all other equipment covered under each section of the specifications, to perform in a quiet, efficient, and satisfactory manner with no more than normal service.

Issue Date: 06/05/2014

B. Each warranty shall extend for a period of one year following substantial completion and acceptance of construction. They shall be endorsed by the Contractor. Refrigeration compressors shall have a five (5) year warranty.

#### 1.16 MANUFACTURERS:

- A. In order to define requirements for quality and function of manufactured products, and requirements such as size, gauges, grade selection, color selections and like specifications requirements, the specifications as written hereinafter are based upon products of those manufacturers who are named hereinafter under various specifications for materials.
- B. In addition to products of manufacturers named hereinafter in the specifications, equivalent products of the following named manufacturers will be acceptable under the base bid:
  - 1. Ductless Split Heat Pumps:
    - a) Mitsubishi, Daikin, Toshiba/Carrier
  - 2. Air Distribution:
    - a) Metal Industries, Price Company, Titus Manufacturing Company, Nailor Industries, Anemostat Products Division, Krueger, J & J Register Co., Carnes Company, Tuttle and Bailey, AirGuide Manufacturing
  - 3. Fans:
    - a) Greenheck Fan Corporation, Loren Cook Company, Breidert/Jenn Fans, Carnes Company, ACME, PennBarry, Twin City Blower
  - 4. Dampers:
    - a) Ruskin Manufacturing Company, NCA Manufacturing, Safe Air/Dowco, Inc., Cesco Products, Inc., Leader Industries, Pottorff, Arrow United, Young Regulator, Nailor
  - 5. Louvers:
    - a) Ruskin Manufacturing Company, NCA Manufacturing, Safe Air/Dowco, Inc., Cesco Products, Inc., Leader Industries, Pottorff, Arrow United
  - 6. Insulation:
    - a) Owens Corning, Johns Manville, CertainTeed Corporation, Knauf Insulation

## 7. Identification Items:

a) Seton Name Plate Company, W.H. Brady Company, Handley Industries, Inc.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### PART 2 - PRODUCTS

## 2.1 PAINTING:

- A. Furnish touch up paint supplied by equipment manufacturer.
- B. Coat ferrous metal surfaces that do not have factory painting or galvanizing with one coat of Sherwin Williams high heat aluminum paint.

# 2.2 CONCRETE EQUIPMENT FOUNDATIONS:

A. Use 3000-psi "batch plant" concrete or approved "precast" reinforced concrete foundations.

#### 2.3 NAME PLATES:

A. All equipment provided under this division shall be labeled with a Bakelite nameplate 1" x 3" minimum with 3/8" minimum height lettering as manufactured by Seton Name Plate Company. See filter nameplate requirement below.

## 2.4 FILTERS:

A. Provide one new set of MERV 8 pleated filters in each unit at final completion. Provide the Owner one replacement set of filters with a complete filter list indicating unit tag and size and quantity of filters needed. At each filter door provide a Bakelite nameplate 1" x 3" minimum with 1/8" minimum height lettering as manufactured by Seton Name Plate Company, that indicates the size and quantity of each filter required in that particular unit.

## 2.5 SLEEVES AND OPENINGS:

A. Provide UL certified fire stop sleeving system for all pipe penetrations through fire rated walls, floors, partitions, ceilings, floor-ceiling assemblies and roofs as tested under ASTM E814-02 "Standard Method of Fire Tests of Through Penetration Fire Stops".

# PART 3 - EXECUTION

## 3.1 CONCRETE EQUIPMENT FOUNDATIONS:

A. Consult ASHRAE: A Practical Guide to Seismic Restraint, Chapter 6 for specific reinforcement and anchoring details, with respect to pad size and seismic forces. Unless otherwise noted, set all floor mounted and "on-grade" mounted equipment on 6" high

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

concrete foundation pads. Concrete foundations shall be reinforced with #4 bars - 12" o.c. both ways, or as directed by A Practical Guide to Seismic Restraint. Pads shall be approximately 6" larger than equipment base, and have 1" x 1" chamfer on all edges. Pads shall have carborundum brick rubbed finish. Surface finish shall be uniformly smooth. Concrete floor shall be rough and foundation doweled to floor per A Practical Guide to Seismic Restraint.

#### 3.2 PIPE FITTINGS:

- A. General: Provide complete systems of piping and fittings for all services as indicated. All pipe, valves, and fittings shall comply with American National Standards Institute, Inc. Code and/or local codes and ordinances. All fittings shall be domestically produced from domestic forgings. Cut pipe accurately to measurements established at building or site, and work into place without springing or forcing, properly clearing all windows, doors, and other openings or obstructions.
- B. Excessive cutting or other weakening of building to facilitate piping installation will not be permitted. Piping shall line up flanges and fittings freely and shall have adequate unions and flanges so that all equipment can be disassembled for repairs. Test all piping prior to insulation or concealing.

#### 3.3 PIPE:

- A. All piping material shall be as specified in other sections of this division.
- B. Fittings and Connections: All turns and connections shall be made with long radius fittings as scheduled hereinafter. No miter connections will be permitted in welded work.
- C. Pipe joints shall be made in accordance with the following applicable specifications:
- D. Make up flanged joints with ring-type gaskets, 1/16 inch thick.
- E. Make all solder joints with non-corrosive type flux 95 Percent tin and 5 percent antimony alloy solder.

## 3.4 SLEEVES:

A. Provide all sleeves in floors, beams, wall, roof, etc. as required for installing work of this division unless otherwise specified hereinafter. Size sleeves for insulated pipe to accommodate both pipe and insulation. Construct vertical sleeves in connection with concealed piping of 22 gauge galvanized iron. Sleeves thru fire-rated assemblies shall be firestopped as specified herein and insulation shall not pass thru sleeve unless material complies with firestopping specified.

# 3.5 PIPE HANGERS, SUPPORTS AND INSERTS:

A. Pipe hangers, supports and inserts shall comply with Table 305.4 of the 2006 International Mechanical Code and be provided as follows:

Issue Date: 06/05/2014

B. All piping shall be supported by forged steel hangers or brackets suitably fastened to structural portion. Wall brackets shall be Fee & Mason Fig. No. 151. Provide lock nuts on all adjustable hanger assemblies.

## PIPE SIZE - INCHES

	1/2 - 2	2-1/2-4	6 – Up	Wall Plate Hanger
Grinnel	104	260	171	139
Fee & Mason	199	239	170	302
Elcen	92	12	15	

- C. Hanger or Support Spacing (unless specified different hereinafter):
  - 1. Copper Pipe:

Nominal Pipe Size – Inches	Maximum Span - Feet
1-1/4" and under	6'
1-1/2" and above	10'

- D. Size hangers on insulated piping to permit insulation and saddles to pass full size through hanger.
- E. Trapeze Hangers:
  - 1. May be used for groups of pipes close together and parallel. Trapeze hangers may be constructed from structural channel or angle irons or from pre-formed channel shapes. All pipe lines must be held on specific centers by U bolts, clips or clamps.
  - 2. When supported with uni-strut an insulation sleeve under the clamp equal to Armacell Armafix is required.

#### F. Inserts:

1. For each hanger on horizontal pipes, installed before concrete is poured. Inserts shall permit horizontal adjustment of the nut.

# G. Special and Additional Supports:

1. Special supports will be required where hangers cannot be used. Horizontal pipes shall be secured to prevent vibration or excessive sway. Where pipes must be laid on fill, they shall be supported at each joint by brick or concrete supports carried down into solid, natural earth. Where required, provide additional hangers to secure required level, slope or drainage, and also to prevent sagging. Provide a hanger within one foot of each elbow. Provide all miscellaneous steel required for pipe supports, anchors, etc.

Construction Documents Issue Date: 06/05/2014

Architect's Project #: 12.130.09

## 3.6 DIELECTRIC CONNECTIONS:

A. Wherever any connection is made between dissimilar metals, provide dielectric pipe couplings or unions.

## 3.7 ELECTRIC WORK:

- A. All motors, and motor starters shall be furnished for items installed under this division of the specifications. All starters shall be magnetic type. All electrically operated equipment shall have readily accessible nameplates summarizing electrical information (i.e., voltage, phase, horsepower, watts, or amperes). Starters shall be as manufactured by General Electric Company, Westinghouse Electric Company, Cutler-Hammer Inc., or Square D Company. A.C. magnetic starters shall be across-the-line type. Starters shall provide overload protection in each phase and shall otherwise conform to all applicable requirements of these specifications. All magnetic starters shall be combination type, Motor Circuit Protector (MCP) type having interrupting rating equal to or greater than the available short circuit current, with "HAND-OFF-AUTO" selector switch, auxiliary contact, and pilot light in cover. Provide laminated plastic nameplates with white center core for each starter.
- B. For motors controlled by variable frequency drives, provide shaft grounding on the motor equal to Aegis bearing protection ring.
- C. All control conduit and wires and control devices shall be furnished and installed under this division. All contactors shall be of the mechanically held type. All control wiring within starters shall be installed in a workmanlike manner and neatly laced. All control wiring shall be color coded.
- D. All work shall conform with the applicable requirements of the National Electrical Codes. All electrical power characteristics shall be as indicated. All devices, which make and/or break electrical circuits, shall be rated for at least 125 percent of the load.
- E. Relays, contactors, and control devices shall open all ungrounded conductors. All fuses shall be current limiting time delay type equal to Bussman "LPN", 250 volt or "LPS", 600 volt.
- F. Control voltage shall not exceed 120 volts. Control power shall be taken from line terminals of controllers. Where necessary, control transformers shall be provided and shall conform to NEMA Standards, properly sized, and shall be properly fused. Where control voltage is 120 volts, control conductors shall be color-coded.
- G. Electrical power service and connections to all equipment in this division will be made under electrical division of the work.
- H. Manual motor starters with overload protection shall be flush mounted type with pilot light. Square D Catalog No. 2510-FS-1P or General Electric, or Westinghouse equivalent.

Construction Documents Issue Date: 06/05/2014

I. Duct smoke detectors shall be provided under electrical division and installed under this division. This division shall provide interlock wiring required for fan shutdown and smoke damper control. Power wiring and fire alarm communication wiring shall be provided under the electrical division.

Architect's Project #: 12.130.09

# 3.8 ITEMS OF MECHANICAL EQUIPMENT:

- A. All items of mechanical equipment electrically operated shall be in complete accordance with paragraph in this division entitled "Electrical Work". Mechanical equipment, other than individually mounted motors, shall be factory pre-wired to a single-set of line terminals and to a single load terminal strip to match load terminals on equipment. Each step shall have properly sized contactor and overcurrent protection.
- B. Mechanical equipment electrical components shall all be bonded together and connected to electrical system ground.

#### 3.9 CLEANING:

- A. All surfaces on metal, pipe, insulation covered surfaces, and other equipment furnished and installed under this division of the specifications shall be thoroughly cleaned of grease, scale, dirt and other foreign material.
- B. Upon complete installation of ducts, clean entire system of rubbish, plaster, dirt, etc., before installing any outlets. After installation of outlets and connections to fans are made, blow out entire system with all control devices wide open.

## 3.10 SYSTEM BALANCING:

- A. The HVAC Contractor is responsible for the entire Test & Balance process. The contractor shall employ an independent balancing firm specializing in total system air balancing as approved by the engineer and certified by the AABC or NEBB. The balancing firm shall be employed prior to installation of any ductwork. Provide all labor, engineering and test equipment required to test, adjust, and balance all heating, ventilating, air conditioning, and exhaust systems.
- B. The Contractor is responsible to have a functioning system prior to Testing and Balancing, to provide a joint and cooperative effort to coordinate the test and balance, and to solve any problems in balancing and controls in order to establish proper system performance before leaving the job. The Contractor is responsible for providing the Test and Balance Agency (TAB) with a complete set of project drawings, specifications, and submittals, and for providing and installing new sheave or sheaves, new belts, as required, if a change in fan speed is necessary which cannot be made by adjusting the sheave originally installed. When requested by the Engineer, the TAB Agency will review plans and specifications of the systems prior to installation and submit a report of any deficiencies, which could preclude proper adjusting, balancing and testing of the system. The TAB agency shall submit copies of deficiency reports along with a preliminary report to the Engineer for review prior to final submittal.

Issue Date: 06/05/2014

- C. Instruments used will be those that meet the instrument requirements for Agency Qualifications of the AABC as published in the NEBB "Procedural Standards for Testing Adjusting and Balancing of Environmental Systems" or the AABC "National Standards for Total System Balance".
- D. Fan air volume shall be adjusted to within 5% of design, and diffuser air volumes to within 10% of design.
- E. Reporting (Submit five copies of final Test Report)
  - 1. Complete nameplate data and equipment schedule number for all rotating equipment.
  - 2. Design and actual operating data for all rotating equipment including inlet and outlet data, flow rates, amps, voltage and rpm.
  - 3. Design and actual duct and diffuser volumes. Prepare a diagram showing flow measurement points.
  - 4. Record coil air pressure drop, filter pressure drop, external static pressure, and fan static pressure.
  - 5. Record flow rates, temperatures and pressures across each water coil, condenser and other heat exchangers.
  - 6. Heating equipment nameplate data, equipment schedule number design data, and operating data at maximum achievable load conditions.

## 3.11 TESTING (PIPING):

- A. Upon completion of each system of work under this division, and at a designated time, all piping shall be pressure tested for leaks in the presence of the owner. Owner shall be notified five days before testing is to be conducted and all tests shall be conducted in the presence of the owner. All equipment required for test shall be furnished by contractor at his expense. All tests shall be performed as specified hereinafter. If inspection or tests show defects, such defective work or material shall be replaced and inspection and tests repeated at no additional cost to owner. Make tight any leaks. Repeat tests until system is proven tight. Caulking of leaks will not be permitted. All equipment not capable of withstanding the test pressure shall be valved off during the test.
- B. All refrigerant piping and apparatus shall be tested with dry carbon dioxide or nitrogen plus a small amount of refrigerant. All refrigerating equipment shall be tested under vacuum and shall show no evidence of leakage with an absolute pressure of .20 inch mercury gauge, sustained for a period of one hour without pumping. Leaks shall be corrected by remaking the joint. Test pressures shall be as follows:

High Side Low Side

Refrigerant 410A - 400 psi Refrigerant 410A - 350 psi

C. Install a card conspicuously and as near as practicable to the refrigerant condensing unit giving instructions for the operation of the system, including precautions to be observed in case of a breakdown or leak.

Issue Date: 06/05/2014

D. Each refrigerating system shall be provided with an easily legible metal sign permanently attached and easily accessible, indicating thereon the name and address of the manufacturer or installer, the kind and total number of pounds of refrigerant contained in the system and the field test pressure applied.

# 3.12 IDENTIFICATION OF EQUIPMENT IN MECHANICAL AREAS:

A. All items of mechanical equipment shall be identified with a black bakelite label with engraved white lettering 1/2" tall. Labels shall be mechanically attached to the equipment with rivets or stainless steel screws. Thermostats and control devices shall be identified with a black bakelite label with engraved white lettering 1/4" tall. Lettering shall correspond with the tags shown in the drawings.

## 3.13 ADJUSTMENT AND TRIAL RUNS:

- A. Upon completion of all work, the contractor shall operate the system in the presence of the owner for the purpose of demonstrating quiet and satisfactory operation, the proper setting of controls, safety and relief valves, and cleanliness of system. Heating and cooling shall be tested separately during periods approaching design conditions and shall fully demonstrate fulfillment of capacity requirements. Test procedures shall be in accordance with applicable portions of ASME, ASHRAE, and other generally recognized test codes as far as field conditions will permit. Any changes or adjustment required shall be made by the contractor without additional expense to owner.
- B. Document and submit all operating conditions (startup report) of equipment during trial runs and after test and balance is complete. Include in the report:
  - 1. Ambient air temperature
  - 2. Design operating temperatures and flow rates
  - 3. Entering and leaving air temperatures across each coil or heating device
  - 4. Amp draw of all motors and nameplate amps
  - 5. Voltage at each piece of equipment
  - 6. Refrigerant pressures and temperatures

## 3.14 OPERATION AND MAINTENANCE INSTRUCTIONS, AND MAINTENANCE MANUAL:

- A. Upon completion of work, and at a time designated by the engineer, a competent employee of the contractor shall be provided to instruct a representative of the owner in the operation and maintenance of the system.
- B. Minimum instruction period shall be:
  - 1. Air Conditioning System 1 day
- C. Maintenance Manuals: The contractor shall compile and bind five (5) sets of all manufacturer's instructions and descriptive literature on all items of equipment furnished under this work. These instructions shall be delivered through the general contractor to the engineer for approval prior to final inspection.

# D. Instructions shall include:

- 1. Warranty letter signed by the Mechanical Contractor.
- 2. Index for each section with each section properly identified.
- 3. Complete equipment list with model and serial numbers.
- 4. Complete equipment list with filter sizes and quantities.
- 5. Copy of one complete, approved submittal for each equipment section.
- 6. Description of each system, including manufacturer's literature for all items.
- 7. Start-up and shut-down description for each system.
- 8. Suggested operating and maintenance instructions with frequency of maintenance indicated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 9. Parts list for all items of equipment.
- 10. Name, address, and telephone number of nearest sales and service organization for all items of equipment.
- 11. Startup reports.
- 12. Test and Balance Reports
- E. Manuals shall be 8-1/2 x 11 inch text pages bound in three ring expansion binders with a hard durable cover with clear plastic pocket on front for title page. Prepare binder covers with printed subject title of manual, title of project, date, and volume number when multiple binders are required. Printing shall be on face and spine. Provide a table of contents for each volume. Internally subdivide the binder contents with divider sheets with typed tab titles under reinforced plastic tabs. Provide directory listing as appropriate with names addresses, and telephone numbers of design consultant, Contractor, subcontractors, equipment suppliers, and nearest service representatives.

End of Section 230010

# SECTION 230500 – HEATING, VENTILATION and AIR CONDITIONING

## PART 1 - GENERAL

# 1.1 General Requirements:

A. This Section of the Specifications and related drawings describe requirements pertaining to Air Conditioning, Heating and Ventilation work, including applicable HVAC Insulation in separate Section 230700. All work shall comply with Section 230010 - General Provisions - HVAC.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. Construct rectangular ductwork to meet all functional criteria defined in Section VII, of the SMACNA "HVAC Duct Construction Standards Metal and Flexible" 2005 Edition. All ductwork must comply with all local, state and federal code requirements.

#### PART 2 - PRODUCTS

## 2.1 SUBMITTALS:

A. Ductwork shop drawings must be submitted for approval by Engineer. Any ductwork installed without prior approval by the Engineer shall be replaced at the expense of the contractor.

## 2.2 QUALITY ASSURANCE:

A. The contractor must comply with this specification in its entirety. At the discretion of the Engineer, sheet metal gauges, and reinforcing may be checked at various times to verify all duct construction is in compliance.

## 2.3 DUCTS, PLENUM, ETC.:

- A. As indicated on drawings, provide a system of metal ducts for supply, return and exhaust air.
- B. All sheet metal, ducts, casing, plenums, etc., of sizes indicated, shall be constructed from prime galvanized sheet steel.

## 2.4 DUCTS THRU WALLS:

- A. Where ducts pass through masonry walls, protect duct from contact with wall by 1/2 inch thick filler of fire rated felt or sponge rubber.
- B. Provide sheet metal flashing around all duct penetrations.
- C. Ducts shall be properly sealed per the fire rating and UL assembly.

## 2.5 INSTRUMENT TEST HOLES:

A. Install for air handling units instrument test holes in supply, return and outside air duct. Instrument test connections shall be Ventlock Model 699-2, or equal, and shall be located in accessible locations.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 2.6 AIR DISTRIBUTION:

- A. Devices shall quietly and draftlessly deliver and/or remove air quantities required to attain conditions indicated. Devices shall have sponge rubber gaskets for sealing devices to walls and ceilings. Exposed surfaces shall have baked enamel finish of manufacturer's standard colors noted.
- B. All air distribution equipment and accessories shall be as scheduled on drawings.

## 2.7 METAL DUCTWALL:

- A. All interior ducts shall be constructed of G-60 or better galvanized steel (ASTM A653) LFQ, chem treat. Exterior ductwork or duct exposed to high humidity conditions shall be constructed of G-90 or better galvanized steel LFQ, chem treat. Galvanized metal ducts shall be a minimum thickness of 24 gage.
- B. Support, access doors not part of ducts, bar or angle reinforcing damper rods and items made of uncoated mild steel shall be painted with two coats of primer or provide galvanized equivalent.
- C. Low Pressure Supply, Return, and Exhaust Duct:
  - 1. Ductwork downstream from the VAV box, ductwork on low pressure supply and return systems and restroom exhaust duct shall be fabricated to meet minimum 2" w.g. pressure class in accordance with SMACNA Duct Construction Standard.

## 2.8 LONGITUDINAL SEAMS:

A. Pittsburgh lock shall be used on all longitudinal seams. All longitudinal seams will be sealed with mastic sealant. Snaplock is not acceptable.

## 2.9 DUCT JOINTS:

- A. Ductmate or W.D.C.I. proprietary duct connection systems will be accepted as an alternative to SMACNA duct construction standards. Duct constructed using these systems will refer to the manufacturers guidelines for sheet gauge, intermediate reinforcement size and spacing, and joint reinforcements.
- B. Ductmate 440 or a Butyl Rubber Gasket which meets Mil-C 18969B, Type II Class B, TT-C-1796A, Type II Class B, and TTS-S-001657 must also pass UL-723. This material, in addition to the above, shall not contain vegetable oils, fish oils, or any other type vehicle that will support fungal and/or bacterial growth associated with dark, damp areas

of ductwork. The recommended test procedure for bacterial and fungal growth is found in

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 2.10 ACCESS DOORS IN DUCTWORK:

A. Provide access doors at all apparatus requiring service and inspection, including fire dampers and fire smoke dampers, and where indicated. Access doors for 2" pressure class duct shall be hinged or Ductmate Sandwich Access Doors as manufactured by Ductmate Industries, Inc., or equal. Access doors for 4" pressure class duct shall be Ductmate Sandwich Access Doors as manufactured by Ductmate Industries, Inc., or equal. Access doors shall be double wall construction with high density fiberglass insulation with R value equal to or greater than the duct insulation. Doors shall be of adequate size (12" x 12" minimum) as required to allow easy access to hardware which needs to be maintained. In accordance with the requirements of the International Building Code, contractor shall permanently mark any access doors or other openings that serve as a means of access to fire, smoke and fire/smoke dampers with ½" letters reading "Fire Damper", "Smoke Damper", or "Fire/Smoke Damper". Label shall be permanently and securely attached.

21CFR 177, 1210 closures with sealing gaskets for food containers.

## 2.11 FLEXIBLE DUCT:

- A. Flexible duct to meet criteria as defined in SMACNA's 2005 Manual, HVAC Duct Construction Standards, Metal and Flexible, or as defined within. Flexible air ducts and flexible air connectors shall be tested in accordance with UL 181, and listed and labeled as Class 0 or Class 1.
- B. Flexible duct shall be constructed with a polyethylene core with foil faced insulation.
- C. Flexible duct is not allowed in lengths greater than 8', unless otherwise noted. Bends, turns, or sagging, is not accepted.

## 2.12 SEALERS:

A. Duct sealer shall be flexible, water-based, adhesive sealant designed for use in all pressure duct systems. After curing, it shall be resistant to ultraviolet light and shall seal out water, air, and moisture. Sealer shall be UL listed and conform to NFPA 90A & 90B. Sealer shall be Childers CP-145A, or equal.

## 2.13 DUCTWORK HANGER/SUPPORT:

A. Hang and support ductwork as defined by SMACNA, Chapter 5 2005 Manual, First Edition, or as defined within. Hanger spacing not to exceed 8'.

## 2.14 TURNING VANES:

A. Turning vanes shall be double wall turning vanes fabricated from the same material as the duct. Tab spacing shall be SMACNA Standard. Rail systems with non-standard tab spacings shall not be accepted. All tabs shall be used, do not skip tabs. Mounting rails shall have friction insert tabs which align the vanes automatically. Vanes shall be

subjected to tensile loading and be capable of supporting 250 lbs. when fastened per the manufacturers instructions.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## 2.15 APPARATUS CONNECTIONS:

A. Flexible connections: For low velocity ductwork (less than 2,400 FPM), provide flexible connections at inlet and outlet of each fan connected to ductwork and elsewhere as indicated. Flexible connections shall be 6 inches wide, waterproof and fireproof, and shall be equal to "Hardcast Connector Plus Neoprene" flexible connectors. Provide at least one inch slack.

## 2.16 MANUAL OPPOSED BLADE DAMPERS:

A. Provide at locations shown on plans, or in accordance with details, schedules or specifications Ruskin Model CD35 manual opposed blade balancing dampers, or approved equal. Frame shall be 16 gage galvanized structural steel hat channel with tabbed corners for reinforcement. The blades shall be single skin, 16 gage galvanized steel with three longitudinal grooves for reinforcement. Bearings shall be corrosion resistant, molded synthetic sleeve type turning in an extruded hole in the damper frame. Axles shall be square or hexagonal positively locked into the damper blade. Linkage shall be concealed out of the airstream, within the damper frame to reduce pressure drop and noise. Submittal must include leakage, pressure drop, maximum velocity and maximum pressure data based on AMCA Publication 500.

## 2.17 PIPE AND FITTINGS:

- A. Schedule of pipe and fittings: Piping and fittings shall conform to requirements as indicated herein.
- B. All pipe shall be domestically produced from domestic forgings.

## 2.18 SCHEDULE OF PIPING

SERVICE	ITEM	PIPING	FITTINGS	FLANGES OR UNIONS
Unitary Condensate	2" and smaller	Type L, Hard drawn copper	Solder type wrought	Wrought solder copper
Drain			copper	to copper

## 2.19 REFRIGERANT PIPING:

- A. General: Execute all refrigerant piping with stamped type "ACR" hard copper and long radius, wrought copper, sweat fittings with tolerance not to exceed 3/1000 of an inch. All joints shall be made with silver solder. Submit equipment manufacturer's suggested piping diagram for approval.
- B. After refrigerant piping has been installed and tested, each system shall be evacuated and charged with proper refrigerant of quantity as recommended by manufacturer.

## 2.20 VENTILATING FANS:

A. See Schedule for characteristics and accessories. Units shall be AMCA or PFMA certified. Use shaded pole, single phase motors under 1/4 HP and split capacitor or polyphase motors 1/4 HP and larger.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. Fans shall be complete with all accessories required for installation including integral overload protection or motor starter.

## 2.21 VRV SPLIT SYSTEM HEAT PUMP UNITS:

- A. Provide Daikin variable refrigerant volume split system heat pump unit(s) or approved equal (see Section 230010) of the type, arrangement, size, and indicated capacities and characteristics. The outdoor unit is a direct expansion (DX), air-cooled heat pump, multizone air-conditioning system with variable speed inverter driven compressors using R-410A refrigerant. Operation of the system shall permit either cooling or heating of all of the indoor units.
- B. The units shall be tested by a Nationally Recognized Testing Laboratory (NRTL), in accordance with ANSI/UL 1995 Heating and Cooling Equipment and bear the Listed Mark. The outdoor unit will be factory charged with R410A.
- C. The outdoor unit shall be factory assembled and pre-wired with all necessary electronic and refrigerant controls. The refrigeration circuit of the condensing unit shall consist of Daikin scroll compressors, motors, fans, condenser coil, electronic expansion valves, solenoid valves, 4-way valve, distribution headers, capillaries, filters, shut off valves, oil separators, service ports and refrigerant regulator. The system will automatically restart operation after a power failure and will not cause any settings to be lost, thus eliminating the need for reprogramming. The unit shall incorporate an auto-charging feature and a refrigerant charge check function.
- D. The following safety devices shall be included on the condensing unit; high pressure switch, control circuit fuses, crankcase heaters, fusible plug, high pressure switch, overload relay, inverter overload protector, thermal protectors for compressor and fan motors, over current protection for the inverter and anti-recycling timers. To ensure the liquid refrigerant does not flash when supplying to the various indoor units, the circuit shall be provided with a sub-cooling feature. Oil recovery cycle shall be automatic occurring 2 hours after start of operation and then every 8 hours of operation. The outdoor unit shall be capable of heating operation at 0°F dry bulb ambient temperature without additional low ambient controls. The system shall continue to provide heat to the indoor units while in the defrost mode.
- E. The outdoor unit shall be completely weatherproof and corrosion resistant. The unit shall be constructed from rust-proofed mild steel panels coated with a baked enamel finish.
- F. The condensing unit shall consist of one or more propeller type, direct-drive 750 W fan motors that have multiple speed operation via a DC (digitally commutating) inverter.

Issue Date: 06/05/2014

The fan motor shall have inherent protection and permanently lubricated bearings and be mounted.

- G. The condenser coil shall be manufactured from copper tubes expanded into aluminum fins to form a mechanical bond. The heat exchanger coil shall be of a waffle louver fin and rifled bore tube design to ensure high efficiency performance. The fins are to be covered with an anti-corrosion acrylic resin and hydrophilic film type E1. The pipe plates shall be treated with powdered polyester resin for corrosion prevention. The thickness of the coating must be between 2.0 to 3.0 microns.
- H. The Daikin inverter scroll compressors shall be variable speed (PAM inverter) controlled which is capable of changing the speed to follow the variations in total cooling and heating load as determined by the suction gas pressure as measured in the condensing unit. In addition, samplings of evaporator and condenser temperatures shall be made so that the high/low pressures detected are read every 20 seconds and calculated. With each reading, the compressor capacity (INV frequency or STD ON/OFF) shall be controlled to eliminate deviation from target value. The capacity control range shall be as low as 6% to 100%. Each compressor shall be equipped with a crankcase heater, high pressure safety switch, and internal thermal overload protector. The compressor shall be spring mounted to avoid the transmission of vibration.
- I. Each indoor unit or group of indoor units shall be able to provide set temperature independently via a local wired controller. The wired remote controller shall have the following features:

OPERATION	Start/Stop	
	Operation Mode	
	Temperature Setting	
	60°F – 90°F Set Point Range	
	Fan Speed	
	Airflow Direction	
	Status	
	Malfunction Flashing	
	Malfunction Content	
	Filter Sign	
MONITORING	Operation Mode	
	Temperature Setting	
	Permit/Prohibit Selection	
	Fan Speed	
	Airflow Direction	
SCHEDULING	ON/OFF Timer	
CONTROL MANAGEMENT	Field Setting Mode	
	Group Setting	
	Auto Re-Start	

J. Provide complete system of air conditioning units and accessories as scheduled on the drawings. All units shall carry a one (1) year parts and labor warranty and a six (6) year compressor warranty.

# 2.22 AIR CONDITIONING UNITS:

A. Provide complete system of air conditioning units and accessories as scheduled on the drawings. All units shall carry a five (5) year compressor warranty.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## PART 3 - EXECUTION

## 3.1 DUCTWORK, GENERAL:

- A. Drawings show general arrangement of duct. Provide all ductwork required to complete installation and avoid interferences. Installation shall conform with applicable portions of Section 230010, General Provisions, HVAC. Fabricate ducts as job progresses, using actual job measurements and referring to architectural, structural, electrical, plumbing and equipment drawings in order to avoid conflicts. Where space limitations preclude use of ducts and fittings as shown, consult Engineer for instructions. All ductwork, offsets, fittings, etc. required to make a complete and efficiently operating installation are included in this contract and shall be fabricated and installed in accordance with SMACNA Standards for the application unless noted otherwise herein.
- B. All duct dimensions shown on drawings are "inside clear". The sizes of acoustically lined ducts and dampers in ducts shall be increased accordingly. Ducts shall be smooth on inside.
- C. Provide flexible duct connectors at all ductwork connections to equipment with fans, motors or rotating components.
- D. Install double thickness turning vanes in duct fittings having centerline radius less than 1-1/2 times width of duct.
- E. Support ducts from building structure with 1 inch wide galvanized steel bands per SMACNA recommendations. Wire hangers and nylon straps will not be acceptable.
- F. Do not install runout drops to ceiling diffusers until ceiling grids have been installed. Center ceiling diffusers between grids.
- G. Seal all joints in supply, return and exhaust ducts with Childers CP-145 Veloseal, or McGill Airseal, DuroDyne or equal water based synthetic duct sealant, or equal.
- H. Upon complete installation of ducts, clean entire system of rubbish, plaster, dirt, etc. before installing any outlets. After installation of outlets and connections to fans are made, blow out entire system with all control devices wide open.

## 3.2 PIPING, GENERAL:

A. All piping shall conform with Section 230010 - General Provisions - HVAC.

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- B. Run pipes parallel to walls and ceilings. Wherever pipes change size, use eccentric fittings. Run piping so as not to obstruct walking or service areas.
- C. Pipe and equipment locations shown are approximate. Exact location of equipment, pipes, and chases to be as approved and determined in field to avoid other pipes and maintain structural clearances. Use actual job dimensions and equipment shop drawings for roughing.
- D. Piping to comply with best trade practice. Provide clearance between pipe and building structure so pipes can expand without damage to building structure.
- E. When soldering refrigerant pipe joints, a dry nitrogen purge shall be required through the inside of the pipe to prevent oxidation.

#### 3.3 EQUIPMENT, GENERAL:

A. All equipment specified herein shall be installed in accordance with manufacturer's published installation instructions and these specifications. All items shall have adequate clearances for access and maintenance. Each item of equipment shall be performance tested to verify compliance with specifications. Certified data sheets of successful performance tests shall be included in operating manuals.

#### 3.4 AUTOMATIC TEMPERATURE CONTROL:

- A. General: Provide a complete system of temperature controls as described herein. The system shall be installed complete by competent mechanics in the employment of the control manufacturer. All control wiring shall be installed in EMT conduit with control and power wiring in separate conduits.
- B. Wiring for low voltage circuits (24 volts or less) may be No. 16 up to 50 feet, and above 50 feet shall be of size to limit voltage drop to 5 percent. Interlock wiring shall be as recommended by equipment manufacturer.
- C. Provide automatic changeover 7 day programmable thermostat per the equipment schedule.
- D. Motorized outdoor air dampers shall open to the ventilation position when in the occupied condition and close when system is in the unoccupied condition.

#### 3.5 SUBMITTALS:

A. Provide submittals as required in Section 230010. At completion of work, submit checkout report of automatic control system. Submit start up reports per Section 230010. Submit test and balance report per 230010. Submit manufacturer's installation, operation, and maintenance instructions.

End of Section 230500

onstruction Documents Issue Date: 06/05/2014

Architect's Project #: 12.130.09

#### SECTION 230700 - HVAC INSULATION

#### PART 1 - GENERAL

#### 1.1 WORK INCLUDED:

- A. General Requirements: This section shall include all insulation as required for installation on all items as specified hereinafter and/or as indicated. All insulations shall be installed in a workmanlike manner by qualified workers in the employment of an independent insulation contractor. Costs of insulation shall be included as part of work by contractor as applicable to his section of work. No separate bid is to be included for insulation work.
- B. Fire hazard classification for all material shall not exceed flame spread of 25 and smoke development of 50 as classified by Underwriters Laboratories under Test Method ASTM E-84 and acceptable under NFPA Standards. This is to apply to the complete system and be a composite rating of insulation material with jacket or facings, vapor barrier, joint sealing tapes, mastic and fittings.
- C. Prior to commencing any work, submit data sheets for engineer's approval of all material proposed to be used on this project.

#### PART 2 - PRODUCTS

#### 2.1 ABOVE GROUND INDOOR PIPING:

#### A. Refrigerant Pipe Insulation:

- 1. Insulation material shall be a flexible, closed-cell elastomeric insulation in tubular form equal to APArmaflex, APArmaflex W, APArmaflex SS, or APArmaflex SA. This product meets the requirements as defined in ASTM C 534, "Specification for preformed elastomeric cellular thermal insulation in tubular form." Insulation materials shall have a closed-cell structure to prevent moisture from wicking which makes it an efficient insulation. Insulation material shall be manufactured without the use of CFC's, HFC's or HCFC's. It is also formaldehyde free, low VOC's, fiber free, dust free and resists mold and mildew.
- 2. Materials shall have a flame spread index of less than 25 and a smoke-developed index of less than 50 when tested in accordance with ASTM E 84, latest revision. In addition, the product, when tested, shall not melt or drip flaming particles, the flame shall not be progressive and all materials shall pass simulated end-use fire tests.
- 3. Materials shall have a maximum thermal conductivity of 0.27 Btu-in./h-ft2- °F at a 75°F mean temperature when tested in accordance with ASTM C 177 or ASTM C 518, latest revisions. Materials shall have a maximum water vapor transmission of 0.08 perm-inches when tested in accordance with ASTM E 96, Procedure A, latest revision.

4. When supported with uni-strut an insulation sleeve under the clamp equal to Armacell Armafix is required.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 2.2 JACKET FOR OUTDOOR PIPING:

- A. All insulation outside (including insulation options) shall be protected with aluminum jacketing with factory applied moisture barrier. The aluminum jacketing shall be 0.016 thickness and be of 3003 alloy and H-14 temper. Jacketing shall be applied with 2-inch circumferential and 1-1/2 inch longitudinal lap and secured with 3/8 inch wide aluminum bands, 8 inches on center.
- B. All elbows shall be covered with 2 piece aluminum insulation covers, manufactured from 110 aluminum alloy in .024" thickness, Childers Aluminum E11-Jacs or equal.
- C. On hot service, aluminum elbows may be attached using self-tapping screws. On chilled water service, aluminum elbows shall be glued on pipe insulation.

#### 2.3 PIPE INSULATION THICKNESS:

A. Piping for the following systems shall be insulated to the thickness listed:

<u>Item</u> <u>Insulation Thickness (Inches)</u>

Armaflex K = 0.25

Cold Pipes:

Condensate Drain Piping 3/4"

Refrigerant Suction 1-1/2"

#### 2.4 DUCTWORK INSULATION:

- A. Supply, Return, and Fresh Air Return Ducts in Equipment Rooms:
  - 1. Insulation shall be 1-1/2 inch thick board equal to Owens Corning 705 (FRK) (ASJ).
- B. Supply And Return Ducts 5 Feet From Air Handling Equipment:
  - 1. Line all metal ducts with 1-1/2 pound density, 1 inch thick duct liner equal to Owens Corning Aeroflex PLUS. Liner shall meet requirements of ASTM C1338, G21 and G22 with respect to resistance to microbial growth.

- C. Supply, Return, and Fresh Air Return Ducts in Unconditioned Plenums:
  - 1. Insulate all, including lined and double wall spiral, metal ducts with 2" thick, 3/4 pound density duct wrap with FRK vapor barrier equal to Owens Corning Fiberglas All Service Duct Wrap.

Issue Date: 06/05/2014

#### 2.5 OUTDOOR DUCT INSULATION:

A. Insulate all sheet metal duct work outdoors exposed to the weather with 2 inch thick Owens-Corning 705 insulation board or equal with FSK factory applied facing. Seal all joints of metal duct with Childers CP-145A prior to installing insulation.

#### PART 3 - EXECUTION

## 3.1 PIPE INSULATION:

- A. All insulation shall be applied to clean, dry surfaces butting all sections firmly together and finishing as specified hereinafter.
- B. All vapor barriers shall be sealed, and shall be continuous throughout. No staples shall be used on any vapor barrier jacket unless sealed with vapor barrier coating or vapor barrier tape.
- C. Insulation of all insulated lines shall be interpreted as including all pipe, valves, fittings and specialties comprising the lines, except flanged unions and screwed unions on hot piping.
- D. Refrigerant Pipe Insulation: Armaflex insulation shall be slip fit over all tubing. Under no circumstances shall insulation be slit to fit over pipe already in place. Sufficient length shall be provided at all bends or turns to prevent the insulation from being pulled too tight and cracking. All seams and butt joints shall be adhered and sealed using Armaflex 520 or 520 BLVAdhesive or equal. Direct contact between pipe and hangers shall be avoided. Hanger shall pass outside of a sheet metal protection saddle which shall cover a section of high density insulation (cellular glass or calcium silicate), of sufficient length to support the weight of the pipe without crushing the insulation. The vapor barrier shall be continuous behind the saddle or shall be lapped over the saddle and securely cemented thereto.

#### 3.2 ALUMINUM JACKET:

A. Jacketing shall be applied with 2-inch circumferential and 1-1/2 inch longitudinal lap and secured with 3/8 inch wide aluminum bands, 8 inches on center and at joints.

#### 3.3 DUCTWORK INSULATION:

#### A. Board Insulation (External):

1. Board shall be applied by means of resistance welded mechanical fasteners or equal. Pins shall not be less than 3 inches in from each edge or corner of board and no more than 12 inches on center. Cut side pieces of insulation to lap top and bottom and scribe board to fit irregular surfaces. Apply a three inch wide bank of Childers CP-30 LO or CP-35 Vapor Barrier Coating or equal on all joints of insulation. While tack coat is still wet, embed 3-inch wide White 10 x 10 Fiberglass reinforcing mesh and recoat fully covering the mesh. Pins shall not protrude excessively above fastening washers. Spot all washers with Childers CP-30 LO or equal and cover with material to match jacket.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### B. Flexible Insulation (External):

1. Application: Insulation shall be wrapped tightly on the ductwork with all circumferential joints butted and longitudinal joints overlapped to the bottom of the rectangular duct. On ductwork over 24 inches wide, secure insulation with suitable resistance welded mechanical fasteners at not more than 18 inches on center. The 2-inch flange on the facing shall be stapled with 9/16 inch flare door stainless steel staples on 6 inch centers. Apply a three inch wide bank of Childers CP-30 LO or CP-35 or equal Vapor Barrier Coating on all joints of insulation. While tack coat is still wet, embed 3-inch wide White 10 x 10 Fiberglass reinforcing mesh and recoat fully covering the mesh. Spot all pin penetrations or punctures in the insulation with a full coat of CP-30 LO or CP-35 or equal.

## C. Flexible Insulation (Internal):

- 1. Applications: Duct Liner shall be applied to the interior of metal ducts using Childers CP-121 HV Duct Liner Adhesive or an equal product having a flame spread of less than 25 and a smoke development of less than 50 and classified such by Underwriters Laboratories. Exposed edges of insulation shall be coated with a heavy layer of Childers CP-135 CHIL-SPRED or equal to eliminate erosion of fibers.
- 2. When duct height or plenum walls exceed 24 inches and when duct widths exceed 12 inches, resistance welded mechanical fasteners will be used in addition to duct liner adhesive. Fasteners shall start within 3 inches of the upstream transverse edges of the liner and 3 inches from the longitudinal joints. Fasteners should be spaced a maximum of 6 inches on center around the perimeter of the duct, except that they may be a maximum of 6 inches from a corner break. Elsewhere they shall be a maximum of 18 inches on center.
- 3. Insulation shall extend the full length of each duct section to permit butting firmly at the duct joints. All joints shall be tightly sealed with CP-135 or equal.

#### 3.4 OUTDOOR DUCT INSULATION:

A. Insulation board shall be applied by means of resistance welded mechanical fasteners 12 inches on center and secured with a full coat of Childers CP-85 CHIL-STIX Clear UL Classified Adhesive or equal. Pins shall not be less than 3 inches in from each edge or corner of board. Cut side pieces of insulation to lap top and bottom, and scribe board to fit irregular surfaces. Pins shall protrude 1/8 to 3/16 inch above insulation. Apply Childers CP-76 Sealant (about the size of a pea) under the washer before pressing it down.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. Apply a tack coat of Childers CP-10/11 or equal to the outside of the duct at a rate of 2 gallons to 100 S.F. While the coating is still wet, embed into it a layer of CHIL-GLAS 5 (5 x 5 weave) or equal. Apply a finish coat at a rate of 4 gallons per 100S.F. fully covering the fiberglass reinforcing mesh., so that the minimum dry film thickness is 1/16 inch. Follow manufacturer's "Suggested Application Procedures" on data sheet.

End of Section 230700

#### SECTION 260500 - BASIC ELECTRICAL MATERIALS AND METHODS

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Electrical equipment coordination and installation.
  - 2. Common electrical installation requirements.
  - 3. Electrical demolition.

#### 1.3 COORDINATION

- A. Coordinate arrangement, mounting, and support of electrical equipment:
  - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.
  - 2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
  - 3. To allow right of way for piping and conduit installed at required slope.
  - 4. So connecting raceways and all other equipment will be clear of obstructions and of the working and access space of other equipment.
- B. Provide access panels and doors for electrical items that are behind finished surfaces or otherwise concealed.
- C. Coordinate all power outages in existing buildings with owner giving a written 7-day notice.
- D. Coordinate all connections/conduits to existing buildings with owner's representatives.
- E. Remove all material indicated to be demolished from construction site. Material indicated to be reused shall be store properly and re-installed in good condition. Clean and relamp lighting fixtures to be reused.
- F. Protect existing walls, ceiling, equipment, and furniture indicated to remain during construction. Repair and/or replace any damaged items after renovation.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Issue Date: 06/05/2014

Architect's Project #: 12.130.09

PART 2 - PRODUCTS (N/A)

#### PART 3 - EXECUTION

#### 3.1 COMMON REQUIREMENTS FOR ELECTRICAL INSTALLATION

- A. Comply with NECA 1.
- B. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- C. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- Equipment: Install to facilitate service, maintenance, and repair or replacement of components D. of both electrical equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.
- E. Right of Way: Give to raceways and piping systems installed at a required slope.
- Expansion Fittings: Provide conduit expansion fittings for all conduits between existing section F. and new addition.

#### 3.2 **ELECTRICAL DEMOLITION**

- Remove all electrical materials indicated to be demolished from construction site and dispose of A. it per local ordinances and laws.
- Turn over any material indicated to be maintain by the owner. Deliver the material to the B. owner's dedicated storage location.
- Remove all associated conductors, conduits, and boxes of devices/fixtures indicated to be C. demolished. Maintain continuity of existing circuits. Existing conduits in slab may be abandoned in place.
- Existing fire alarm system shall remain in operation. Provide protective material (i.e. bags, D. plastic covers, etc.) for existing devices or panels. Re-install devices in new ceiling indicated to remain. Provide retesting of fire alarm system and give a copy of the report to the Owner, Architect, and Engineer.
- E. The Contractor shall replace any damaged devices, fixtures, or any electrical materials indicated to remain. Replacements shall be new and not previously used.
- F. Replace any damaged wiring devices (receptacles and switches) and associated plates indicated to remain. Match desired color of Architect's selection.

# 3.3 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

B. Seal all penetrations (fire rated or not) with approved assemblies.

END OF SECTION 260500

# SECTION 260519 - CONDUCTORS AND CABLES

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Building wires and cables rated 600 V and less.
  - 2. Connectors, splices, and terminations rated 600 V and less.

#### 1.3 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70 2011, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NFPA 70 2011.

#### PART 2 - PRODUCTS

#### 2.1 CONDUCTORS AND CABLES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following or equal:
  - 1. American Insulated Wire Corp.; a Leviton Company.
  - 2. General Cable Corporation.
  - 3. Senator Wire & Cable Company.
  - 4. Southwire Company.
- B. Copper Conductors: Comply with NEMA WC 70.
- C. Conductor Insulation: Comply with NEMA WC 70 for Types THHN-THWN.

#### 2.2 CONNECTORS AND SPLICES

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Issue Date: 06/05/2014

- 1. AFC Cable Systems, Inc.
- 2. Hubbell Power Systems, Inc.
- 3. O-Z/Gedney; EGS Electrical Group LLC.
- 4. 3M; Electrical Products Division.
- 5. Tyco Electronics Corp.
- B. Description: Factory-fabricated connectors and splices of size, ampacity rating, material, type, and class for application and service indicated.

#### PART 3 - EXECUTION

#### 3.1 CONDUCTOR MATERIAL APPLICATIONS

A. Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.

# 3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

A. Class 1 Control Circuits: Type THHN-THWN, in raceway.

#### 3.3 INSTALLATION OF CONDUCTORS AND CABLES

- A. Conceal cables in finished walls, ceilings, and floors, unless otherwise indicated.
- B. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- C. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.
- D. Support cables according to Division 26 Section "Electrical Supports and Seismic Restraints."
- E. Identify and color-code conductors and cables according to Division 26 Section "Electrical Identification."

#### 3.4 CONNECTIONS

- A. Tighten electrical connectors and terminals according to manufacturer's published torquetightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- B. Make splices and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.
- C. Wiring at Outlets: Install conductor at each outlet, with at least 6 inches (150 mm).

## 3.5 FIELD QUALITY CONTROL

- A. Perform tests and inspections and prepare test reports.
- B. Tests and Inspections:
  - 1. After installing conductors and cables and before electrical circuitry has been energized, test service entrance and feeder conductors, and conductors feeding the following critical equipment and services for compliance with requirements.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

END OF SECTION 260519

Issue Date: 06/05/2014

#### SECTION 260526 - GROUNDING AND BONDING

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70 2011, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with UL 467 for grounding and bonding materials and equipment.

## PART 2 - PRODUCTS

#### 2.1 CONDUCTORS

A. Insulated Conductors: Copper wire or cable insulated for 600 V unless otherwise required by applicable Code or authorities having jurisdiction.

#### 2.2 CONNECTORS

- A. Listed and labeled by a nationally recognized testing laboratory acceptable to authorities having jurisdiction for applications in which used, and for specific types, sizes, and combinations of conductors and other items connected.
- B. Bolted Connectors for Conductors and Pipes: Copper or copper alloy, bolted pressure-type, with at least two bolts.
  - 1. Pipe Connectors: Clamp type, sized for pipe.

## 2.3 GROUNDING ELECTRODES

A. Ground Rods: Copper-clad steel; 3/4 inch by 10 feet (19mm by 3m).

Issue Date: 06/05/2014

#### **PART 3 - EXECUTION**

#### 3.1 APPLICATIONS

- A. Conductors: Install solid conductor for No. 10 AWG and smaller, and stranded conductors for No. 8 AWG and larger, unless otherwise indicated.
- B. Conductor Terminations and Connections:
  - 1. Pipe and Equipment Grounding Conductor Terminations: Bolted connectors.
  - 2. Underground Connections: Welded connectors, except at test wells and as otherwise indicated.
  - 3. Connections to Structural Steel: Welded connectors.

#### 3.2 EQUIPMENT GROUNDING

A. Install insulated equipment grounding conductors with all feeders and branch circuits.

#### 3.3 INSTALLATION

- A. Existing Grounding: Confirm existing grounding system of building. Incorporate new addition grounding and bonding requirements with existing system.
- B. Grounding Conductors: Route along shortest and straightest paths possible, unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.
- C. Ground Rods: Drive rods until tops are 2 inches below finished floor or final grade, unless otherwise indicated. Interconnect ground rods with grounding electrode conductor below grade and as otherwise indicated. Make connections without exposing steel or damaging coating, if any. For grounding electrode system, install at least 3 rods spaced at least 20 feet from each other and located at least the same distance from other grounding electrodes, and connect to the service grounding electrode conductor.
- D. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance, except where routed through short lengths of conduit.
  - 1. Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate any adjacent parts.
  - 2. Use exothermic-welded connectors for outdoor locations, but if a disconnect-type connection is required, use a bolted clamp.

END OF SECTION 260526

#### SECTION 260529 - ELECTRICAL SUPPORTS AND SEISMIC RESTRAINTS

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Hangers and supports for electrical equipment and systems.
  - 2. Seismic restraints for electrical equipment and systems.

#### 1.3 DEFINITIONS

- A. EMT: Electrical metallic tubing.
- B. IBC: International Building Code.
- C. IMC: Intermediate metal conduit.
- D. RMC: Rigid metal conduit.
- E. Seismic Restraint: A structural support element such as a metal framing member, a cable, an anchor bolt or stud, a fastening device, or an assembly of these items used to transmit seismic forces from an item of equipment or system to building structure and to limit movement of item during a seismic event.

#### 1.4 QUALITY ASSURANCE

- A. Comply with seismic-restraint requirements in the IBC unless requirements in this Section are more stringent.
- B. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code Steel."
- C. Comply with NFPA 70 2011.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

## PART 2 - PRODUCTS

#### 2.1 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

A. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed under this Project, with a minimum structural safety factor of five times the applied force.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Steel Slotted Support Systems: Comply with MFMA-3, factory-fabricated components for field assembly.
  - 1. Channel Dimensions: Selected for structural loading.
- C. Raceway and Cable Supports: As described in NECA 1.
- D. Conduit and Cable Support Devices: Steel and malleable-iron hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- E. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- F. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
  - 1. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
  - 2. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.
  - 3. Concrete Inserts: Steel or malleable-iron slotted-support-system units similar to MSS Type 18; complying with MFMA-3 or MSS SP-58.
  - 4. Clamps for Attachment to Steel Structural Elements: MSS SP-58, type suitable for attached structural element.
  - 5. Through Bolts: Structural type, hex head, high strength. Comply with ASTM A 325.
  - 6. Toggle Bolts: All-steel springhead type.
  - 7. Hanger Rods: Threaded steel.

#### 2.2 SEISMIC-RESTRAINT COMPONENTS

- A. Angle and Channel-Type Brace Assemblies: Steel angles or steel slotted-support-system components; with accessories for attachment to braced component at one end and to building structure at the other end.
- B. Cable Restraints: ASTM A 603, zinc-coated, steel wire rope attached to steel or stainless-steel thimbles, brackets, swivels, and bolts designed for restraining cable service.

-Bid Set Issue Date: 06/05/2014

1. Seismic Mountings, Anchors, and Attachments: Devices as specified in Part 2 "Support, Anchorage, and Attachment Components" Article, selected to resist seismic forces.

Architect's Project #: 12.130.09

## 2.3 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

A. Description: Welded or bolted, structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.

## PART 3 - EXECUTION

#### 3.1 APPLICATION

- A. Comply with NECA 1 for application of hangers and supports for electrical equipment and systems, except if requirements in this Section are stricter.
- B. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
  - 1. Secure raceways and cables to these supports with two-bolt conduit clamps using spring friction action for retention in support channel.
- C. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1-1/2-inch (38-mm) and smaller raceways serving branch circuits and communication systems above suspended ceilings and for fastening raceways to trapeze supports.

#### 3.2 SUPPORT AND SEISMIC-RESTRAINT INSTALLATION

- A. Comply with NECA 1 for installation requirements, except as specified in this Article.
- B. Raceway Support Methods: In addition to methods described in NECA 1, EMT may be supported by openings through structure members, as permitted in NFPA 70.
- C. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
  - 1. To Wood: Fasten with lag screws or through bolts.
  - 2. To New Concrete: Bolt to concrete inserts.
  - 3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
  - 4. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inches (100 mm) thick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inches (100 mm) thick.
  - 5. To Light Steel: Sheet metal screws.

Issue Date: 06/05/2014

- 6. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate by means that meet seismic-restraint strength and anchorage requirements.
- D. Drill holes for expansion anchors in concrete at locations and to depths that avoid reinforcing bars.

#### 3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
- B. Field Welding: Comply with AWS D1.1/D1.1M.

#### 3.4 INSTALLATION OF SEISMIC-RESTRAINT COMPONENTS

- A. Restraint Cables: Provide #12 slack steel cables on all recessed light fixtures. Provide two cables on all 2'x4' recessed fixtures attached from structure to diagonally opposite corners of fixtures. Provide one cable on each smaller fixture.
- B. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, upper truss chords of bar joists, or at concrete members.

END OF SECTION 260529

Issue Date: 06/05/2014

#### SECTION 260533 - RACEWAYS AND BOXES

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes raceways, fittings, boxes, enclosures, and cabinets for electrical wiring.
- B. Related Sections include the following:

#### 1.3 DEFINITIONS

- A. EMT: Electrical metallic tubing.
- B. FMC: Flexible metal conduit.
- C. IMC: Intermediate metal conduit.
- D. LFMC: Liquidtight flexible metal conduit.
- E. RNC: Rigid nonmetallic conduit.

#### 1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70 2011, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NFPA 70 2011.

#### PART 2 - PRODUCTS

#### 2.1 METAL CONDUIT AND TUBING

- A. Rigid Steel Conduit: ANSI C80.1.
- B. IMC: ANSI C80.6.

Issue Date: 06/05/2014

- C. EMT: ANSI C80.3.
- D. FMC: Zinc-coated steel.
- E. LFMC: Flexible steel conduit with PVC jacket.
- F. Fittings for Conduit (Including all Types and Flexible and Liquidtight), EMT, and Cable: NEMA FB 1; listed for type and size raceway with which used, and for application and environment in which installed.
  - 1. Fittings for EMT: Steel, set-screw (indoors), weatherproof compression (outdoors).

#### 2.2 BOXES, ENCLOSURES, AND CABINETS

- A. Metal Floor Boxes: Cast metal semi-adjustable, rectangular.
- B. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- C. Hinged-Cover Enclosures: NEMA 250, Type 1, with continuous-hinge cover with flush latch, unless otherwise indicated.
  - 1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.

#### PART 3 - EXECUTION

#### 3.1 RACEWAY APPLICATION

- A. Comply with the following indoor applications, unless otherwise indicated:
  - 1. Exposed, Not Subject to Physical Damage: EMT.
  - 2. Exposed and Subject to Severe Physical Damage: IMC.
  - 3. Concealed in Ceilings and Interior Walls and Partitions: EMT.
  - 4. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): FMC, except use LFMC in damp or wet locations.
  - 5. Damp or Wet Locations: IMC.
  - 6. Raceways for Optical Fiber or Communications Cable in Spaces Used for Environmental Air: EMT.
  - 7. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4, nonmetallic in damp or wet locations.
- B. Minimum Raceway Size: 3/4-inch (21-mm) trade size.
- C. Raceway Fittings: Compatible with raceways and suitable for use and location.
  - 1. Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings, unless otherwise indicated.

#### 3.2 INSTALLATION

A. Comply with NECA 1 for installation requirements applicable to products specified in Part 2 except where requirements on Drawings or in this Article are stricter.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Keep raceways at least 6 inches (150 mm) away from parallel runs of flues and steam or hotwater pipes. Install horizontal raceway runs above water and steam piping.
- C. Complete raceway installation before starting conductor installation.
- D. Support raceways as specified in Division 26 Section "Electrical Supports and Seismic Restraints."
- E. Install no more than the equivalent of three 90-degree bends in any conduit run except for communications conduits, for which fewer bends are allowed.
- F. Conceal conduit and EMT within finished walls, ceilings, and floors, unless otherwise indicated. If surface raceway is required on existing block walls, confirm routing with Architect before rough-in.
- G. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.
- H. Raceway Terminations at Locations Subject to Moisture or Vibration: Use insulating bushings to protect conductors, including conductors smaller than No. 4 AWG.
- I. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb (90-kg) tensile strength. Leave at least 12 inches (300 mm) of slack at each end of pull wire.
- J. Flexible Conduit Connections: Use maximum of 72 inches (1830 mm) of flexible conduit for recessed and semi-recessed lighting fixtures, equipment subject to vibration, noise transmission, or movement; and for transformers and motors.
  - 1. Use LFMC in damp or wet locations.
- K. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall.
- L. Coordinate all boxes in casework with furniture supplier. Coordinate all work in casework with Architect before roughing in.
- M. Floor boxes shall be exactly flush with floor surface. Boxes shall not be a tripping hazard.

Issue Date: 06/05/2014

#### 3.3 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 7 Section "Through-Penetration Firestop Systems."

#### 3.4 PROTECTION

- A. Provide final protection and maintain conditions that ensure coatings, finishes, and cabinets are without damage or deterioration at time of Substantial Completion.
  - 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.

END OF SECTION 260533

#### SECTION 260553 - ELECTRICAL IDENTIFICATION

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Identification for conductors and control cable.
  - 2. Equipment identification labels.

#### 1.3 QUALITY ASSURANCE

A. Comply with NFPA 70 - 2011.

#### 1.4 COORDINATION

- A. Coordinate identification names, abbreviations, colors, and other features with requirements in the Contract Documents, Shop Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual, and with those required by codes, standards, and 29 CFR 1910.145. Use consistent designations throughout Project.
- B. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- C. Coordinate installation of identifying devices with location of access panels and doors.
- D. Install identifying devices before installing acoustical ceilings and similar concealment.

#### PART 2 - PRODUCTS

## 2.1 CONDUCTOR AND CONTROL CABLE IDENTIFICATION MATERIALS

- A. Color-Coding Conductor Tape: Colored, self-adhesive vinyl tape not less than 3 mils (0.08 mm) thick by 1 to 2 inches (25 to 50 mm) wide.
- B. Marker Tapes: Vinyl or vinyl-cloth, self-adhesive wraparound type, with circuit identification legend machine printed by thermal transfer or equivalent process.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 2.2 INSTRUCTION SIGNS

A. Engraved, laminated acrylic or melamine plastic, minimum 1/16 inch (1.6 mm) thick for signs up to 20 sq. in. (129 sq. cm) and 1/8 inch (3.2 mm) thick for larger sizes.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Engraved legend with black letters on white face.
- 2. Punched or drilled for mechanical fasteners.

## 2.3 EQUIPMENT IDENTIFICATION LABELS

- A. Adhesive Film Label: Machine printed, in black, by thermal transfer or equivalent process. Minimum letter height shall be 3/8 inch (10 mm).
- B. Self-Adhesive, Engraved, Laminated Acrylic or Melamine Label: Adhesive backed, with black letters on a white background. Minimum letter height shall be 3/8 inch (10 mm).

#### 2.4 MISCELLANEOUS IDENTIFICATION PRODUCTS

A. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

#### PART 3 - EXECUTION

#### 3.1 APPLICATION

- A. Power-Circuit Conductor Identification: For secondary conductors in pull and junction boxes use color-coded tape.
- B. Branch-Circuit Conductor Identification: Where there are conductors for more than three branch circuits in same junction or pull box, use color-coding conductor tape.
- C. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and Operation and Maintenance Manual. Apply labels to disconnect switches and protection equipment, central or master units, control panels, control stations, terminal cabinets, and racks of each system. Systems include power, lighting, control, communication, signal, monitoring, and alarm systems unless equipment is provided with its own identification.

#### 1. Labeling Instructions:

a. Laminated acrylic or melamine label. Unless otherwise indicated, provide a single line of text with 1/2-inch- (13-mm-) high letters on 1-1/2-inch- (38-mm-) high label; where 2 lines of text are required, use labels 2 inches (50 mm) high.

#### 2. Equipment to Be Labeled:

a. Panelboards, electrical cabinets, and enclosures.

- Access doors and panels for concealed electrical items. b.
- Disconnect switches. c.
- Enclosed circuit breakers. d.
- e. Fire-alarm control panel and annunciators.
- f. Monitoring and control equipment.

#### 3.2 **INSTALLATION**

- Verify identity of each item before installing identification products. A.
- Location: Install identification materials and devices at locations for most convenient viewing В. without interference with operation and maintenance of equipment.
- C. Apply identification devices to surfaces that require finish after completing finish work.
- Self-Adhesive Identification Products: Clean surfaces before application, using materials and D. methods recommended by manufacturer of identification device.
- Color-Coding for Phase and Voltage Level Identification, 600 V and Less: Use the colors listed E. below for conductors.
  - Color shall be factory applied or, for sizes larger than No. 10 AWG if authorities having 1. jurisdiction permit, field applied.
  - Colors for 120/208-V Circuits: 2.
    - Phase A: Black. a.
    - Phase B: Red.
    - Phase C: Blue. c.
    - Neutral: White. d.
    - Ground: Green.
  - Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns for a minimum 3. distance of 6 inches (150 mm) from terminal points and in boxes where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding. Locate bands to avoid obscuring factory cable markings.

END OF SECTION 260553

Issue Date: 06/05/2014

#### SECTION 262200 - DRY-TYPE TRANSFORMERS

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following types of dry-type transformers rated 600 V and less:
  - 1. Distribution transformers.

#### 1.3 SUBMITTALS

A. Product Data Include rated nameplate data, capacities, weights, dimensions, minimum clearances, installed devices and features, and performance for each type and size of transformer indicated.

#### 1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with IEEE C 57.12.91.

#### 1.5 DELIVERY, STORAGE, AND HANDLING

A. Temporary Heating: Apply temporary heat according to manufacturer's written instructions within the enclosure of each ventilated-type unit, throughout periods during which equipment is not energized and when transformer is not in a space that is continuously under normal control of temperature and humidity.

#### PART 2 - PRODUCTS

## 2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Issue Date: 06/05/2014

- 1. Cutler-Hammer.
- 2. GE Electrical Distribution & Control.
- 3. Siemens Energy & Automation, Inc.
- 4. Square D/Groupe Schneider NA.

#### 2.2 MATERIALS

- A. Description: Factory-assembled and -tested, air-cooled units for 60-Hz service.
- B. Cores: Grain-oriented, non-aging silicon steel.
- C. Coils: Continuous windings without splices, except for taps.
  - 1. Internal Coil Connections: Brazed or pressure type.
  - 2. Coil Material: Copper.

#### 2.3 DISTRIBUTION TRANSFORMERS

- A. Comply with NEMA ST 20, and list and label as complying with UL 1561.
- B. Provide transformers that are internally braced to withstand seismic forces specified in Division 16 Section "Electrical Supports and Seismic Restraints."
- C. Cores: One leg per phase.
- D. Enclosure: Ventilated, NEMA 250, Type 2.
- E. Indoor Transformer Enclosure Finish: Comply with NEMA 250 for "Indoor Corrosion Protection."
  - 1. Finish Color: Gray.
- F. Insulation Class: 220 deg C, UL-component-recognized insulation system with a maximum of 150 deg C rise above 40 deg C ambient temperature.
- G. Taps for Transformers 25 kVA and Larger: Two 2.5 percent taps above and two 2.5 percent taps below normal full capacity.
- H. K-Factor Rating: Transformers shall be K-factor rated (K-13) and comply with UL 1561 requirements for nonsinusoidal load current-handling capability to the degree defined by designated K-factor.
  - 1. Unit shall not overheat when carrying full-load current with harmonic distortion corresponding to designated K-factor.
  - 2. Indicate value of K-factor on transformer nameplate.
- I. Low-Sound-Level Requirements: Minimum of 3 dBA less than NEMA ST 20 standard sound levels when factory tested according to IEEE C57.12.91.

Issue Date: 06/05/2014

#### **PART 3 - EXECUTION**

#### 3.1 EXAMINATION

- A. Examine conditions for compliance with enclosure- and ambient-temperature requirements for each transformer.
- B. Verify that field measurements are as needed to maintain working clearances required by NFPA 70 and manufacturer's written instructions.
- C. Examine walls and floors for suitable mounting conditions where transformers will be installed. Provide reinforcement of walls as required for proper mounting.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 INSTALLATION

- A. Install floor-mounting transformers level on concrete pad.
  - 1. Anchor transformers to concrete bases according to manufacturer's written instructions, seismic codes at Project, and requirements in Division 26 Section "Electrical Supports and Seismic Restraints."
  - 2. Maintain clearances as listed on transformer per NEC.

#### 3.3 CONNECTIONS

- A. Ground equipment according to Division 26 Section "Grounding and Bonding."
- B. Tighten electrical connectors and terminals according to manufacturer's published torquetightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B. Land each conductor under a separate lug barrel.

END OF SECTION 262200

#### SECTION 262416 - PANELBOARDS

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Lighting and appliance branch-circuit panelboards.

#### 1.3 SUBMITTALS

- A. Product Data: For each type of panelboard, overcurrent protective device, accessory, and component indicated. Include dimensions and manufacturers' technical data on features, performance, electrical characteristics, ratings, and finishes.
- B. Shop Drawings: For each panelboard and related equipment.
  - 1. Dimensioned plans, elevations, sections, and details. Show tabulations of installed devices, equipment features, and ratings. Include the following:
    - a. Enclosure types and details for types other than NEMA 250, Type 1.
    - b. current, and voltage ratings.
    - c. Short-circuit current rating of panelboards and overcurrent protective devices.
    - d. UL listing for series rating of installed devices.
    - e. Features, characteristics, ratings, and factory settings of individual overcurrent protective devices and auxiliary components.
- C. Manufacturer Seismic Qualification Certification: Submit certification that panelboards, overcurrent protective devices, accessories, and components will withstand seismic forces defined in Division 26 Section "Electrical Supports and Seismic Restraints." Include the following:
  - 1. Basis of Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
    - a. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."
- D. Panelboard Schedules: For installation in panelboards, typed.

## 1.4 QUALITY ASSURANCE

A. Source Limitations: Obtain panelboards, overcurrent protective devices, components, and accessories through one source from a single manufacturer.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Product Options: Drawings indicate size, profiles, and dimensional requirements of panelboards and are based on the specific system indicated. Refer to Division 1 Section "Product Requirements."
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70-2011, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- D. Comply with NEMA PB 1.
- E. Comply with NFPA 70 2011.

#### 1.5 COORDINATION

A. Coordinate layout and installation of panelboards and components with other construction that penetrates walls or is supported by them, including electrical and other types of equipment, raceways, piping, and encumbrances to workspace clearance requirements.

#### 1.6 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Keys: Six spares for each type of panelboard cabinet lock.

## PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following or equal:
  - 1. Panelboards, Overcurrent Protective Devices, and Accessories:
    - a. Eaton Corporation; Cutler-Hammer Products.
    - b. General Electric Co.; Electrical Distribution & Protection Div.
    - c. Siemens Energy & Automation, Inc.
    - d. Square D.

#### 2.2 MANUFACTURED UNITS

- A. Enclosures: Surface-mounted cabinets. NEMA PB 1, Type 1.
  - 1. Rated for environmental conditions at installed location.
  - 2. Front: Secured to box with concealed trim clamps. For surface-mounted fronts, match box dimensions.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 3. Hinged Front Cover: Entire front trim hinged to box and with standard door within hinged trim cover.
- 4. Finish: Manufacturer's standard enamel finish over corrosion-resistant treatment or primer coat.
- 5. Directory Card: With transparent protective cover, mounted in metal frame, inside panelboard door.

#### B. Phase and Ground Buses:

- 1. Material: Tin-plated Copper.
- 2. Equipment Ground Bus: Adequate for feeder and branch-circuit equipment ground conductors; bonded to box.
- C. Conductor Connectors: Suitable for use with conductor material.
  - 1. Main and Neutral Lugs: Mechanical type.
  - 2. Ground Lugs and Bus Configured Terminators: Mechanical type.
- D. Future Devices: Mounting brackets, bus connections, and necessary appurtenances required for future installation of devices.

#### 2.3 PANELBOARD SHORT-CIRCUIT RATING

A. UL label indicating series-connected rating with integral or remote upstream overcurrent protective devices. Include size and type of upstream device allowable, branch devices allowable, and UL series-connected short-circuit rating.

## 2.4 LIGHTING AND APPLIANCE BRANCH-CIRCUIT PANELBOARDS

- A. Branch Overcurrent Protective Devices: Bolt-on circuit breakers, replaceable without disturbing adjacent units.
- B. Doors: Concealed hinges; secured with flush latch with tumbler lock; keyed alike.

#### 2.5 OVERCURRENT PROTECTIVE DEVICES

A. Molded-Case Circuit Breaker: UL 489, with series-connected rating to meet available fault currents.

1. Thermal-Magnetic Circuit Breakers: Inverse time-current element for low-level overloads, and instantaneous magnetic trip element for short circuits. Adjustable

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
- 2. GFCI Circuit Breakers: Single- and two-pole configurations with 30-mA trip sensitivity.
- B. Molded-Case Circuit-Breaker Features and Accessories: Standard frame sizes, trip ratings, and number of poles.
  - 1. Lugs: Mechanical style, suitable for number, size, trip ratings, and conductor materials.
  - 2. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HACR for heating, air-conditioning, and refrigerating equipment.

#### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install panelboards and accessories according to NEMA PB 1.1.
- B. Comply with mounting and anchoring requirements specified in Division 16 Section "Electrical Supports and Seismic Restraints."
- C. Mount top of trim 74 inches (1880 mm) above finished floor, unless otherwise indicated.
- D. Mount plumb and rigid without distortion of box. Mount recessed panelboards with fronts uniformly flush with wall finish.
- E. Install overcurrent protective devices and controllers.
- F. Install filler plates in unused spaces.
- G. Arrange conductors in gutters into groups and bundle and wrap with wire ties.
- H. Provide an electrician to open panels for substantial completion observation by Engineer.

#### 3.2 IDENTIFICATION

- A. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs as specified in Division 26 Section "Electrical Identification."
- B. Create a directory to indicate installed circuit loads. Obtain approval before installing. Use a computer or typewriter to create directory; handwritten directories are not acceptable.
- C. Panelboard Nameplates: Label each panelboard with engraved metal or laminated-plastic nameplate mounted with corrosion-resistant screws.

## 3.3 CONNECTIONS

- A. Ground equipment according to Division 26 Section "Grounding and Bonding."
- B. Connect wiring according to Division 26 Section "Conductors and Cables."

#### 3.4 CLEANING

A. On completion of installation, inspect interior and exterior of panelboards. Remove paint splatters and other spots. Vacuum dirt and debris; do not use compressed air to assist in cleaning. Repair exposed surfaces to match original finish.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

END OF SECTION 262416

#### SECTION 262726 - WIRING DEVICES

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Receptacles, receptacles with integral GFCI, and associated device plates.
  - 2. Snap switches.

#### 1.3 DEFINITIONS

- A. GFCI: Ground-fault circuit interrupter.
- B. Pigtail: Short lead used to connect a device to a branch-circuit conductor.

## 1.4 QUALITY ASSURANCE

- A. Source Limitations: Obtain each type of wiring device and associated wall plate through one source from a single manufacturer. Insofar as they are available, obtain all wiring devices and associated wall plates from a single manufacturer and one source.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70 2011, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Comply with NFPA 70 2011.

#### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Manufacturers' Names: Shortened versions (shown in parentheses) of the following manufacturers' names are used in other Part 2 articles (Provide the following or equal):
  - 1. Cooper Wiring Devices; a division of Cooper Industries, Inc. (Cooper).
  - 2. Hubbell Incorporated; Wiring Device-Kellems (Hubbell).

WIRING DEVICES 262726 - 1

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

- 3. Leviton Mfg. Company Inc. (Leviton).
- 4. Pass & Seymour/Legrand; Wiring Devices & Accessories (Pass & Seymour).

#### 2.2 STRAIGHT BLADE RECEPTACLES

- A. Convenience Receptacles, 125 V, 20 A: Comply with NEMA WD 1, NEMA WD 6 configuration 5-20R, and UL 498.
  - 1. Products: Subject to compliance with requirements, provide one of the following or equal:
    - a. Cooper; 5351 (single), 5352 (duplex).
    - b. Hubbell; HBL5351 (single), CR5352 (duplex).
    - c. Leviton; 5891 (single), 5352 (duplex).
    - d. Pass & Seymour; 5381 (single), 5352 (duplex).

#### 2.3 GFCI RECEPTACLES

- A. General Description: Straight blade, feed-through type. Comply with NEMA WD 1, NEMA WD 6, UL 498, and UL 943, Class A, and include indicator light that is lighted when device is tripped.
- B. Duplex GFCI Convenience Receptacles, 125 V, 20 A:
  - 1. Products: Subject to compliance with requirements, provide one of the following or equal:
    - a. Cooper; GF20.
    - b. Hubbell; GF5262.
    - c. Leviton; 6899.
    - d. Pass & Seymour; 2084.

#### 2.4 SNAP SWITCHES

- A. Comply with NEMA WD 1 and UL 20.
- B. Switches, 120/277 V, 20 A:
  - 1. Products: Subject to compliance with requirements, provide one of the following or equal:
    - a. Cooper; 2221 (single pole), 2222 (two pole), 2223 (three way), 2224 (four way).
    - b. Hubbell; CS1221 (single pole), CS1222 (two pole), CS1223 (three way), CS1224 (four way).
    - c. Leviton; 1221-2 (single pole), 1222-2 (two pole), 1223-2 (three way), 1224-2 (four way).
    - d. Pass & Seymour; 20AC1 (single pole), 20AC2 (two pole), 20AC3 (three way), 20AC4 (four way).

WIRING DEVICES 262726 - 2

#### 2.5 WALL PLATES

- A. Single and combination types to match corresponding wiring devices.
  - 1. Plate-Securing Screws: Metal with head color to match plate finish.
  - 2. Material: Smooth stainless steel or unbreakable nylon (confirm with Architect).
  - 3. Material for Damp Locations: Cast aluminum with spring-loaded lift cover, and listed and labeled for use in "wet locations" and "while-in-use" rated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

#### 2.6 FINISHES

- A. Color: Wiring device catalog numbers in Section Text do not designate device color.
  - 1. Wiring Devices Connected to Normal Power System: Match existing as approved by Architect, unless otherwise indicated or required by NFPA 70 or device listing.

#### PART 3 - EXECUTION

#### 3.1 INSTALLATION

A. Comply with NECA 1, including the mounting heights listed in that standard, unless otherwise noted.

#### B. Coordination with Other Trades:

- 1. Take steps to insure that devices and their boxes are protected. Do not place wall finish materials over device boxes and do not cut holes for boxes with routers that are guided by riding against outside of the boxes.
- 2. Keep outlet boxes free of plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other material that may contaminate the raceway system, conductors, and cables.
- 3. Install device boxes in brick or block walls so that the cover plate does not cross a joint unless the joint is troweled flush with the face of the wall.
- 4. Install wiring devices after all wall preparation, including painting, is complete.

#### C. Conductors:

- 1. Do not strip insulation from conductors until just before they are spliced or terminated on devices.
- 2. Strip insulation evenly around the conductor using tools designed for the purpose. Avoid scoring or nicking of solid wire or cutting strands from stranded wire.
- 3. The length of free conductors at outlets for devices shall meet provisions of NFPA 70, Article 300, without pigtails.

#### D. Device Installation:

WIRING DEVICES 262726 - 3

Sid Set Issue Date: 06/05/2014

1. Replace all devices that have been in temporary use during construction or that show signs that they were installed before building finishing operations were complete.

Architect's Project #: 12.130.09

- 2. Keep each wiring device in its package or otherwise protected until it is time to connect conductors.
- 3. Do not remove surface protection, such as plastic film and smudge covers, until the last possible moment.
- 4. Connect devices to branch circuits using pigtails that are not less than 6 inches (152 mm) in length.
- 5. When there is a choice, use side wiring with binding-head screw terminals. Wrap solid conductor tightly clockwise, 2/3 to 3/4 of the way around terminal screw.
- 6. When conductors larger than No. 12 AWG are installed on 15- or 20-A circuits, splice No. 12 AWG pigtails for device connections.

# E. Receptacle Orientation:

- 1. Install ground pin of vertically mounted receptacles down. Horizontally mounted receptacles, ground pin to the right.
- F. Device Plates: Do not use oversized or extra-deep plates. Repair wall finishes and remount outlet boxes when standard device plates do not fit flush or do not cover rough wall opening.
- G. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical and with grounding terminal of receptacles on bottom. Group adjacent switches under single, multigang wall plates.
- H. All devices shall be ADA-compliant in mounting height. Toggle of switches shall not exceed 48" aff. In block wall construction, mount top of box at 48" aff (coordinate with block mason and bond beam). Match switches in gyp wall construction at common height.

# 3.2 FIELD QUALITY CONTROL

# A. Tests for Convenience Receptacles:

- 1. Line Voltage: Acceptable range is 105 to 132 V.
- 2. GFCI Trip: Test for tripping values specified in UL 1436 and UL 943.
- 3. Using the test plug, verify that the device and its outlet box are securely mounted.
- 4. The tests shall be diagnostic, indicating damaged conductors, poor connections, inadequate fault current path, defective devices, or similar problems. Correct circuit conditions, remove malfunctioning units and replace with new ones, and retest as specified above.

END OF SECTION 262726

WIRING DEVICES 262726 - 4

# SECTION 262816 - ENCLOSED SWITCHES AND CIRCUIT BREAKERS

# PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. This Section includes the following individually mounted, enclosed switches and circuit breakers:
  - 1. Fusible switches.
  - 2. Non-fusible switches.
  - 3. Enclosures.

### 1.3 DEFINITIONS

A. GD: General duty.

# 1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70-2011, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NFPA 70 2011.
- C. Product Selection for Restricted Space: Drawings indicate maximum dimensions for enclosed switches and circuit breakers, including clearances between enclosures, and adjacent surfaces and other items. Comply with indicated maximum dimensions.

# 1.5 PROJECT CONDITIONS

- A. Environmental Limitations: Rate equipment for continuous operation under the following conditions, unless otherwise indicated:
  - 1. Ambient Temperature: Not less than minus 22 deg F (minus 30 deg C) and not exceeding 104 deg F (40 deg C).

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

Issue Date: 06/05/2014

### 1.6 COORDINATION

A. Coordinate layout and installation of switches, circuit breakers, and components with other construction, including conduit, piping, equipment, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

### PART 2 - PRODUCTS

# 2.1 FUSIBLE AND NONFUSIBLE SWITCHES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following or equal:
  - 1. Eaton Corporation; Cutler-Hammer Products.
  - 2. General Electric Co.; Electrical Distribution & Control Division.
  - 3. Siemens Energy & Automation, Inc.
  - 4. Square D/Group Schneider.
- B. Fusible Switch, NEMA KS 1, Type GD, with clips or bolt pads to accommodate specified fuses, lockable handle with capability to accept two padlocks, and door interlocked with cover in closed position.
- C. Nonfusible Switch: NEMA KS 1, Type, lockable handle with capability to accept two padlocks, and interlocked with cover in closed position.

# 2.2 ENCLOSURES

- A. NEMA AB 1 and NEMA KS 1 to meet environmental conditions of installed location.
  - 1. Outdoor Locations: NEMA 250, Type 3R.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine elements and surfaces to receive enclosed switches and circuit breakers for compliance with installation tolerances and other conditions affecting performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 INSTALLATION

A. Comply with applicable portions of NECA 1, NEMA PB 1.1, and NEMA PB 2.1 for installation of enclosed switches and circuit breakers.

Issue Date: 06/05/2014

- B. Mount individual wall-mounting switches and circuit breakers with tops at uniform height, unless otherwise indicated.
- C. Comply with mounting and anchoring requirements specified in Division 16 Section "Electrical Supports and Seismic Restraints."
- D. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from enclosures and components.

### 3.3 IDENTIFICATION

- A. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs as specified in Division 26 Section "Electrical Identification."
- B. Enclosure Nameplates: Label each enclosure with engraved laminated-plastic nameplate as specified in Division 26 Section "Electrical Identification."

# 3.4 FIELD QUALITY CONTROL

- A. Prepare for acceptance testing as follows:
  - 1. Inspect mechanical and electrical connections.
  - 2. Verify switch and labeling.
  - 3. Verify rating of installed fuses.
  - 4. Inspect proper installation of type, size, quantity, and arrangement of mounting or anchorage devices complying with manufacturer's certification.

# 3.5 CLEANING

A. On completion of installation, vacuum dirt and debris from interiors; do not use compressed air to assist in cleaning. Inspect exposed surfaces and repair damaged finishes.

END OF SECTION 262816

# SECTION 265100 - INTERIOR LIGHTING

# PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Lighting fixtures, lamps, and ballasts (interior and exterior building mounted).
  - 2. Emergency lighting units.
  - 3. Exit signs.
  - 4. Lighting fixture supports.

### 1.3 DEFINITIONS

- A. BF: Ballast factor.
- B. CRI: Color-rendering index.
- C. CU: Coefficient of utilization.
- D. HID: High-intensity discharge.
- E. LER: Luminaire efficacy rating.
- F. Luminaire: Complete lighting fixture, including ballast housing if provided.
- G. RCR: Room cavity ratio.

### 1.4 SUBMITTALS

- A. Product Data: For each type of lighting fixture, arranged in order of fixture designation. Include data on features, accessories, finishes, and the following:
  - 1. Physical description of lighting fixture including dimensions.
  - 2. Emergency lighting units including battery and charger.
  - 3. Ballast.
  - 4. Energy-efficiency data.
  - 5. Lighting Fixtures.
  - 6. Suspended ceiling components.

Issue Date: 06/05/2014

7. Structural members to which suspension systems for lighting fixtures will be attached.

Architect's Project #: 12.130.09

- Operation and Maintenance Data: For lighting equipment and fixtures to include in emergency, B. operation, and maintenance manuals.
- C. Warranties: Special warranties specified in this Section.

#### 1.5 **QUALITY ASSURANCE**

- Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70 -A. 2011, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NFPA 70 - 2011.

#### 1.6 **COORDINATION**

Coordinate layout and installation of lighting fixtures and suspension system with other A. construction that penetrates ceilings or is supported by them, including HVAC equipment, firesuppression system, and partition assemblies.

### PART 2 - PRODUCTS

#### 2.1 **MANUFACTURERS**

A. Provide products listed in Lighting Fixture Schedule on the drawings or prior approved equals.

#### LIGHTING FIXTURES AND COMPONENTS, GENERAL REQUIREMENTS 2.2

- Recessed Fixtures: Comply with NEMA LE 4 for ceiling compatibility for recessed fixtures. A.
- B. Comply with UL 1598.
- C. Metal Parts: Free of burrs and sharp corners and edges.
- Sheet Metal Components: Steel, unless otherwise indicated. Form and support to prevent D. warping and sagging.
- E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.
- Reflecting surfaces shall have minimum reflectance as follows, unless otherwise indicated: F.

White Surfaces: 85 percent. 1.

Re-Bid Set

Issue Date: 06/05/2014

- 2. Specular Surfaces: 83 percent.
- 3. Diffusing Specular Surfaces: 75 percent.
- 4. Laminated Silver Metallized Film: 90 percent.

# G. Plastic Diffusers, Covers, and Globes:

- 1. Acrylic Lighting Diffusers: 100 percent virgin acrylic plastic. High resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
  - a. Lens Thickness: At least 0.125 inch (3.175 mm) minimum unless different thickness is indicated.

Architect's Project #: 12.130.09

b. UV stabilized.

### 2.3 BALLASTS FOR LINEAR FLUORESCENT LAMPS

- A. Electronic Ballasts: Comply with ANSI C82.11; instant-start type, unless otherwise indicated, and designed for type and quantity of lamps served. Ballasts shall be designed for full light output unless dimmer or bi-level control is indicated.
  - 1. Sound Rating: A.
  - 2. Total Harmonic Distortion Rating: Less than 20 percent.
  - 3. BF: 0.85 or higher.
  - 4. Parallel Lamp Circuits: Multiple lamp ballasts shall comply with ANSI C 82.11 and shall be connected to maintain full light output on surviving lamps if one or more lamps fail.

### 2.4 EMERGENCY FLUORESCENT POWER UNIT

- A. Internal Type: Self-contained, modular, battery-inverter unit, factory mounted within lighting fixture body and compatible with ballast. Comply with UL 924.
  - 1. Emergency Connection: Operate 2 fluorescent lamp(s) continuously at an output of 1400 lumens each. Connect unswitched circuit to battery-inverter unit and switched circuit to fixture ballast.
  - 2. Test Push Button and Indicator Light: Visible and accessible without opening fixture or entering ceiling space.
    - a. Push Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
    - b. Indicator Light: LED indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.
  - 3. Battery: Sealed, maintenance-free, nickel-cadmium type.
  - 4. Charger: Fully automatic, solid-state, constant-current type with sealed power transfer relay.

### 2.5 EXIT SIGNS

A. Description: Comply with UL 924; for sign colors, visibility, luminance, and lettering size, comply with authorities having jurisdiction.

# B. Internally Lighted Signs:

- 1. Lamps for AC Operation: LEDs, 70,000 hours minimum rated lamp life.
- 2. Self-Powered Exit Signs (Battery Type): Integral automatic charger in a self-contained power pack.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- a. Battery: Sealed, maintenance-free, nickel-cadmium type.
- b. Charger: Fully automatic, solid-state type with sealed transfer relay.
- c. Operation: Relay automatically energizes lamp from battery when circuit voltage drops to 80 percent of nominal voltage or below. When normal voltage is restored, relay disconnects lamps from battery, and battery is automatically recharged and floated on charger.
- d. Test Push Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
- e. LED Indicator Light: Indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.

# 2.6 FLUORESCENT LAMPS

- A. Low-Mercury Lamps: Comply with EPA's toxicity characteristic leaching procedure test; shall yield less than 0.2 mg of mercury per liter when tested according to NEMA LL 1.
- B. T8 rapid-start low-mercury lamps, rated 32 W maximum, nominal length of 48 inches (1220 mm), 2800 initial lumens (minimum), CRI 75 (minimum), color temperature as indicated on drawings, and average rated life 20,000 hours, unless otherwise indicated.

### 2.7 LIGHTING FIXTURE SUPPORT COMPONENTS

- A. Comply with Division 26 Section "Electrical Supports and Seismic Restraints" for channel- and angle-iron supports and nonmetallic channel and angle supports.
- B. Wires: ASTM A 641/A 641M, Class 3, soft temper, zinc-coated steel, 12 gage (2.68 mm).

# PART 3 - EXECUTION

# 3.1 INSTALLATION

- A. Lighting fixtures: Set level, plumb, and square with ceilings and walls. Install lamps in each fixture.
- B. Support for Lighting Fixtures in or on Grid-Type Suspended Ceilings: Use grid as a support element.

- 1. Support Clips: Fasten to lighting fixtures and to ceiling grid members at or near each
  - 2. Fixtures of Sizes Less Than Ceiling Grid: Install as indicated on reflected ceiling plans or center in acoustical panel, and support fixtures independently with at least two 3/4-inch (20-mm) metal channels spanning and secured to ceiling tees.

Issue Date: 06/05/2014

C. Connect wiring according to Division 26 Section "Conductors and Cables."

fixture corner with clips that are UL listed for the application.

# 3.2 FIELD QUALITY CONTROL

A. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery and retransfer to normal.

END OF SECTION 265100

# SECTION 311000 - SITE CLEARING

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 SUMMARY

### A. Section Includes:

- 1. Protecting existing vegetation to remain.
- 2. Removing existing vegetation.
- 3. Clearing and grubbing.
- 4. Stripping and stockpiling topsoil.
- 5. Removing above- and below-grade site improvements.
- 6. Disconnecting, capping or sealing, and removing site utilities.
- 7. Retain subparagraph below if erosion- and sedimentation-control measures are not included in Division 01 Section "Temporary Facilities and Controls."
- 8. Temporary erosion- and sedimentation-control measures.

### B. Related Sections:

- 1. Division 01 Section "Temporary Facilities and Controls" for temporary utility services, construction and support facilities, security and protection facilities, and temporary erosion- and sedimentation-control measures.
- 2. Division 01 Section "Execution" for field engineering and surveying.

### 1.3 DEFINITIONS

- A. Subsoil: All soil beneath the topsoil layer of the soil profile, and typified by the lack of organic matter and soil organisms.
- B. Surface Soil: Soil that is present at the top layer of the existing soil profile at the Project site. In undisturbed areas, the surface soil is typically topsoil; but in disturbed areas such as urban environments, the surface soil can be subsoil.
- C. Topsoil: Top layer of the soil profile consisting of existing native surface topsoil or existing inplace surface soil and is the zone where plant roots grow. Its appearance is generally friable, pervious, and black or a darker shade of brown, gray, or red than underlying subsoil; reasonably

Re-Bid Set

Issue Date: 06/05/2014

free of subsoil, clay lumps, gravel, and other objects more than 2 inches (50 mm) in diameter; and free of subsoil and weeds, roots, toxic materials, or other nonsoil materials.

Architect's Project #: 12.130.09

- D. Tree-Protection Zone: Area surrounding individual trees or groups of trees to be protected during construction, and indicated on Drawings.
- E. Vegetation: Trees, shrubs, groundcovers, grass, and other plants.

### 1.4 MATERIAL OWNERSHIP

A. Except for stripped topsoil and other materials indicated to be stockpiled or otherwise remain Owner's property, cleared materials shall become Contractor's property and shall be removed from Project site.

### 1.5 SUBMITTALS

- A. Existing Conditions: Documentation of existing trees and plantings, adjoining construction, and site improvements that establishes preconstruction conditions that might be misconstrued as damage caused by site clearing.
  - 1. Use sufficiently detailed photographs or videotape.
  - 2. Include plans and notations to indicate specific wounds and damage conditions of each tree or other plants designated to remain.
- B. Record Drawings: Identifying and accurately showing locations of capped utilities and other subsurface structural, electrical, and mechanical conditions.

# 1.6 QUALITY ASSURANCE

A. Preinstallation Conference: Conduct conference at Project site.

# 1.7 PROJECT CONDITIONS

- A. Traffic: Minimize interference with adjoining roads, streets, walks, and other adjacent occupied or used facilities during site-clearing operations.
  - 1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction.
  - 2. Provide alternate routes around closed or obstructed traffic ways if required by Owner or authorities having jurisdiction.
- B. Salvable Improvements: Carefully remove items indicated to be salvaged and store on Owner's premises where indicated.
- C. Utility Locator Service: Notify utility locator service for area where Project is located before site clearing.

D. Do not commence site clearing operations until temporary erosion- and sedimentation-control measures are in place.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- E. The following practices are prohibited within protection zones:
  - 1. Storage of construction materials, debris, or excavated material.
  - 2. Parking vehicles or equipment.
  - 3. Foot traffic.
  - 4. Erection of sheds or structures.
  - 5. Impoundment of water.
  - 6. Excavation or other digging unless otherwise indicated.
  - 7. Attachment of signs to or wrapping materials around trees or plants unless otherwise indicated.
- F. Do not direct vehicle or equipment exhaust towards protection zones.
- G. Prohibit heat sources, flames, ignition sources, and smoking within or near protection zones.
- H. Soil Stripping, Handling, and Stockpiling: Perform only when the topsoil is dry or slightly moist.

### PART 2 - PRODUCTS

# 2.1 MATERIALS

- A. Satisfactory Soil Material: Requirements for satisfactory soil material are specified in Division 31 Section "Earth Moving."
  - 1. Obtain approved borrow soil material off-site when satisfactory soil material is not available on-site.

### PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Protect and maintain benchmarks and survey control points from disturbance during construction.
- B. Locate and clearly identify trees, shrubs, and other vegetation to remain.
- C. Protect existing site improvements to remain from damage during construction.
  - 1. Restore damaged improvements to their original condition, as acceptable to Owner.

# 3.2 TEMPORARY EROSION AND SEDIMENTATION CONTROL

A. Provide temporary erosion- and sedimentation-control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to erosion- and sedimentation-control Drawings and requirements of authorities having jurisdiction.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Verify that flows of water redirected from construction areas or generated by construction activity do not enter or cross protection zones.
- C. Inspect, maintain, and repair erosion- and sedimentation-control measures during construction until permanent vegetation has been established.
- D. Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.

### 3.3 TREE AND PLANT PROTECTION

- A. General: Protect trees and plants remaining on-site.
- B. Repair or replace trees, shrubs, and other vegetation indicated to remain or be relocated that are damaged by construction operations, in a manner approved by Architect.
- C. Locate, identify, disconnect, and seal or cap utilities indicated to be removed.
  - 1. Arrange with utility companies to shut off indicated utilities.
  - 2. Owner will arrange to shut off indicated utilities when requested by Contractor.
- D. Locate, identify, and disconnect utilities indicated to be abandoned in place.
- E. Interrupting Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
  - 1. Notify Architect not less than two days in advance of proposed utility interruptions.
  - 2. Do not proceed with utility interruptions without Architect's written permission.
- F. Excavate for and remove underground utilities indicated to be removed.

### 3.4 EXISTING UTILITIES

- A. Owner will arrange for disconnecting and sealing indicated utilities that serve existing structures before site clearing, when requested by Contractor.
  - 1. Verify that utilities have been disconnected and capped before proceeding with site clearing.
- B. Locate, identify, disconnect, and seal or cap utilities indicated to be removed.

- 1. Arrange with utility companies to shut off indicated utilities.
- 2. Owner will arrange to shut off indicated utilities when requested by Contractor.

Issue Date: 06/05/2014

- C. Locate, identify, and disconnect utilities indicated to be abandoned in place.
- D. Interrupting Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
  - 1. Notify Architect not less than two days in advance of proposed utility interruptions.
  - 2. Do not proceed with utility interruptions without Architect's written permission.
- E. Excavate for and remove underground utilities indicated to be removed.

### 3.5 CLEARING AND GRUBBING

- A. Remove obstructions, trees, shrubs, and other vegetation to permit installation of new construction.
  - 1. Do not remove trees, shrubs, and other vegetation indicated to remain or to be relocated.
  - 2. Grind down stumps and remove roots, obstructions, and debris to a depth of 18 inches (450 mm) below exposed subgrade.
  - 3. Use only hand methods for grubbing within protection zones.
  - 4. Chip removed tree branches and dispose of off-site.
- B. Fill depressions caused by clearing and grubbing operations with satisfactory soil material unless further excavation or earthwork is indicated.
  - 1. Place fill material in horizontal layers not exceeding a loose depth of 8 inches (200 mm), and compact each layer to a density equal to adjacent original ground.

### 3.6 TOPSOIL STRIPPING

- A. Remove sod and grass before stripping topsoil.
- B. Strip topsoil to depth of 6 inches (150 mm) in a manner to prevent intermingling with underlying subsoil or other waste materials.
  - 1. Remove subsoil and nonsoil materials from topsoil, including clay lumps, gravel, and other objects more than 2 inches (50 mm) in diameter; trash, debris, weeds, roots, and other waste materials.
- C. Stockpile topsoil away from edge of excavations without intermixing with subsoil. Grade and shape stockpiles to drain surface water. Cover to prevent windblown dust and erosion by water.
  - 1. Limit height of topsoil stockpiles to 72 inches (1800 mm).
  - 2. Do not stockpile topsoil within protection zones.

Re-Bid Set Issue Date: 06/05/2014

3. Dispose of surplus topsoil. Surplus topsoil is that which exceeds quantity indicated to be stockpiled or reused.

Architect's Project #: 12.130.09

4. Stockpile surplus topsoil to allow for respreading deeper topsoil.

# 3.7 SITE IMPROVEMENTS

- A. Remove existing above- and below-grade improvements as indicated and necessary to facilitate new construction.
- B. Remove slabs, paving, curbs, gutters, and aggregate base as indicated.
  - 1. Unless existing full-depth joints coincide with line of demolition, neatly saw-cut along line of existing pavement to remain before removing adjacent existing pavement. Saw-cut faces vertically.
  - 2. Paint cut ends of steel reinforcement in concrete to remain with two coats of antirust coating, following coating manufacturer's written instructions. Keep paint off surfaces that will remain exposed.

### 3.8 DISPOSAL OF SURPLUS AND WASTE MATERIALS

- A. Remove surplus soil material, unsuitable topsoil, obstructions, demolished materials, and waste materials including trash and debris, and legally dispose of them off Owner's property.
- B. Separate recyclable materials produced during site clearing from other nonrecyclable materials. Store or stockpile without intermixing with other materials and transport them to recycling facilities. Do not interfere with other Project work.

END OF SECTION 311000

# SECTION 312000 - EARTH MOVING

### PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 SUMMARY

#### A. Section Includes:

- 1. Preparing subgrades for slabs-on-grade, walks, pavements, turf and grasses, and plants.
- 2. Excavating and backfilling for buildings and structures.
- 3. Drainage course for concrete slabs-on-grade.
- 4. Subbase course and base course for asphalt paving.
- 5. Excavating and backfilling trenches for utilities and pits for buried utility structures.

### B. Related Sections:

- 1. Division 01 Section "Temporary Facilities and Controls" for temporary controls, utilities, and support facilities; also for temporary site fencing if not in another Section.
- 2. Divisions 21, 22, 23, and 26 Sections for installing underground mechanical and electrical utilities and buried mechanical and electrical structures.

# 1.3 DEFINITIONS

- A. Backfill: Soil material or controlled low-strength material used to fill an excavation.
  - 1. Initial Backfill: Backfill placed beside and over pipe in a trench, including haunches to support sides of pipe.
  - 2. Final Backfill: Backfill placed over initial backfill to fill a trench.
- B. Base Course: Aggregate layer placed between the subbase course and hot-mix asphalt paving.
- C. Bedding Course: Aggregate layer placed over the excavated subgrade in a trench before laying pipe.
- D. Borrow Soil: Satisfactory soil imported from off-site for use as fill or backfill.
- E. Drainage Course: Aggregate layer supporting the slab-on-grade that also minimizes upward capillary flow of pore water.
- F. Excavation: Removal of material encountered above subgrade elevations and to lines and dimensions indicated.

1. Authorized Additional Excavation: Excavation below subgrade elevations or beyond indicated lines and dimensions as directed by Architect. Authorized additional excavation and replacement material will be paid for according to Contract provisions for

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Bulk Excavation: Excavation more than 10 feet (3 m) in width and more than 30 feet (9 m) in length.
- 3. Unauthorized Excavation: Excavation below subgrade elevations or beyond indicated lines and dimensions without direction by Architect. Unauthorized excavation, as well as remedial work directed by Architect, shall be without additional compensation.
- G. Fill: Soil materials used to raise existing grades.

changes in the Work.

- H. Rock: Rock material in beds, ledges, unstratified masses, conglomerate deposits, and boulders of rock material that exceed 1 cu. yd. (0.76 cu. m) for bulk excavation or 3/4 cu. yd. (0.57 cu. m) for footing, trench, and pit excavation that cannot be removed by rock excavating equipment equivalent to the following in size and performance ratings, without systematic drilling, ram hammering, ripping, or blasting, when permitted:
  - 1. Excavation of Footings, Trenches, and Pits: Late-model, track-mounted hydraulic excavator; equipped with a 42-inch- (1065-mm-) wide, maximum, short-tip-radius rock bucket; rated at not less than 138-hp (103-kW) flywheel power with bucket-curling force of not less than 28,700 lbf (128 kN) and stick-crowd force of not less than 18,400 lbf (82 kN) with extra-long reach boom; measured according to SAE J-1179.
  - 2. Bulk Excavation: Late-model, track-mounted loader; rated at not less than 230-hp (172-kW) flywheel power and developing a minimum of 47,992-lbf (213.3-kN) breakout force with a general-purpose bare bucket; measured according to SAE J-732.
- I. Structures: Buildings, footings, foundations, retaining walls, slabs, tanks, curbs, mechanical and electrical appurtenances, or other man-made stationary features constructed above or below the ground surface.
- J. Subbase Course: Aggregate layer placed between the subgrade and base course for hot-mix asphalt pavement, or aggregate layer placed between the subgrade and a cement concrete pavement or a cement concrete or hot-mix asphalt walk.
- K. Subgrade: Uppermost surface of an excavation or the top surface of a fill or backfill immediately below subbase, drainage fill, drainage course, or topsoil materials.
- L. Utilities: On-site underground pipes, conduits, ducts, and cables, as well as underground services within buildings.

### 1.4 SUBMITTALS

- A. Product Data: For each type of the following manufactured products required:
  - 1. Geotextiles.
  - 2. Controlled low-strength material, including design mixture.
  - 3. Warning tapes.

- B. Samples for Verification: For the following products, in sizes indicated below:
  - 1. Geotextile: 12 by 12 inches (300 by 300 mm).
  - 2. Warning Tape: 12 inches (300 mm) long; of each color.
- C. Qualification Data: For qualified testing agency.
- D. Material Test Reports: For each on-site and borrow soil material proposed for fill and backfill as follows:

Issue Date: 06/05/2014

- 1. Classification according to ASTM D 2487.
- 2. Laboratory compaction curve according to ASTM D 698.
- E. Seismic survey report from seismic survey agency.
- F. Preexcavation Photographs or Videotape: Show existing conditions of adjoining construction and site improvements, including finish surfaces, that might be misconstrued as damage caused by earth moving operations. Submit before earth moving begins.
- G. Co-Permittee Agreement for Storm Water Management: This submittal shall be submitted prior to beginning work.
- H. Permits: Contractor shall review the City of Columbia / DHEC Storm Water Management and Sediment Control Permit issued for the project and shall comply fully with all requirements.

# 1.5 QUALITY ASSURANCE

- A. Blasting: Not allowed
- B. Seismic Survey Agency: An independent testing agency, acceptable to authorities having jurisdiction, experienced in seismic surveys and blasting procedures to perform the following services:
  - 1. Seismographic monitoring during blasting operations.
- C. Geotechnical Testing Agency Qualifications: Qualified according to ASTM E 329 and ASTM D 3740 for testing indicated.
- D. Preexcavation Conference: Conduct conference at Project site.

# 1.6 PROJECT CONDITIONS

- A. Traffic: Minimize interference with adjoining roads, streets, walks, and other adjacent occupied or used facilities during earth moving operations.
  - 1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction.
  - 2. Provide alternate routes around closed or obstructed traffic ways if required by Owner or authorities having jurisdiction.

B. Utility Locator Service: Notify utility locator service for area where Project is located before beginning earth moving operations.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- C. Do not commence earth moving operations until temporary erosion- and sedimentation-control measures, specified in Division 31 Section "Site Clearing," are in place.
- D. Do not commence earth moving operations until plant-protection measures specified in Division 01 Section "Temporary Tree and Plant Protection" are in place.
- E. The following practices are prohibited within protection zones:
  - 1. Storage of construction materials, debris, or excavated material.
  - 2. Parking vehicles or equipment.
  - 3. Foot traffic.
  - 4. Erection of sheds or structures.
  - 5. Impoundment of water.
  - 6. Excavation or other digging unless otherwise indicated.
  - 7. Attachment of signs to or wrapping materials around trees or plants unless otherwise indicated.
- F. Do not direct vehicle or equipment exhaust towards protection zones.
- G. Prohibit heat sources, flames, ignition sources, and smoking within or near protection zones.

# PART 2 - PRODUCTS

# 2.1 SOIL MATERIALS

- A. General: Provide borrow soil materials when sufficient satisfactory soil materials are not available from excavations.
- B. Satisfactory Soils: Soil Classification Groups GW, GP, GM, SC, SW, SP, and SM according to ASTM D 2487, or a combination of these groups; free of rock or gravel larger than 3 inches (75 mm) in any dimension, debris, waste, frozen materials, vegetation, and other deleterious matter.
  - 1. Liquid Limit: <35
  - 2. Plasticity Index: <20
- C. Unsatisfactory Soils: Soil Classification Groups GC, CL, ML, OL, CH, MH, OH, and PT according to ASTM D 2487 or a combination of these groups.
  - 1. Unsatisfactory soils also include satisfactory soils not maintained within 2 percent of optimum moisture content at time of compaction.
- D. Subbase Material: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 90 percent passing a 1-1/2-inch (37.5-mm) sieve and not more than 12 percent passing a No. 200 (0.075-mm) sieve.

E. Base Course: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 95 percent passing a 1-1/2-inch (37.5-mm) sieve and not more than 8 percent passing a No. 200 (0.075-mm) sieve.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- F. Engineered Fill: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 90 percent passing a 1-1/2-inch (37.5-mm) sieve and not more than 12 percent passing a No. 200 (0.075-mm) sieve.
- G. Bedding Course: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; except with 100 percent passing a 1-inch (25-mm) sieve and not more than 8 percent passing a No. 200 (0.075-mm) sieve.
- H. Drainage Course: Narrowly graded mixture of washed crushed stone, or crushed or uncrushed gravel; ASTM D 448; coarse-aggregate grading Size 57; with 100 percent passing a 1-1/2-inch (37.5-mm) sieve and 0 to 5 percent passing a No. 8 (2.36-mm) sieve.
- I. Filter Material: Narrowly graded mixture of natural or crushed gravel, or crushed stone and natural sand; ASTM D 448; coarse-aggregate grading Size 67; with 100 percent passing a 1-inch (25-mm) sieve and 0 to 5 percent passing a No. 4 (4.75-mm) sieve.
- J. Sand: ASTM C 33; fine aggregate.
- K. Impervious Fill: Clayey gravel and sand mixture capable of compacting to a dense state.

# 2.2 GEOTEXTILES

- A. Subsurface Drainage Geotextile: Nonwoven needle-punched geotextile, manufactured for subsurface drainage applications, made from polyolefins or polyesters; with elongation greater than 50 percent; complying with AASHTO M 288 and the following, measured per test methods referenced:
  - 1. Survivability: Class 2; AASHTO M 288.
  - 2. Grab Tensile Strength: 157 lbf (700 N); ASTM D 4632.
  - 3. Sewn Seam Strength: 142 lbf (630 N); ASTM D 4632.
  - 4. Tear Strength: 56 lbf (250 N); ASTM D 4533.
  - 5. Puncture Strength: 56 lbf (250 N); ASTM D 4833.
  - 6. Apparent Opening Size: No. 40 (0.425-mm) sieve, maximum; ASTM D 4751.
  - 7. Permittivity: 0.5 per second, minimum; ASTM D 4491.
  - 8. UV Stability: 50 percent after 500 hours' exposure; ASTM D 4355.
- B. Separation Geotextile: Woven geotextile fabric, manufactured for separation applications, made from polyolefins or polyesters; with elongation less than 50 percent; complying with AASHTO M 288 and the following, measured per test methods referenced:
  - 1. Survivability: Class 2; AASHTO M 288.
  - 2. Grab Tensile Strength: 247 lbf (1100 N); ASTM D 4632.
  - 3. Sewn Seam Strength: 222 lbf (990 N); ASTM D 4632.
  - 4. Tear Strength: 90 lbf (400 N); ASTM D 4533.

e Tennis Complex Addition

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 5. Puncture Strength: 90 lbf (400 N); ASTM D 4833.
- 6. Apparent Opening Size: No. 60 (0.250-mm) sieve, maximum; ASTM D 4751.
- 7. Permittivity: 0.02 per second, minimum; ASTM D 4491.
- 8. UV Stability: 50 percent after 500 hours' exposure; ASTM D 4355.

# 2.3 CONTROLLED LOW-STRENGTH MATERIAL

- A. Controlled Low-Strength Material: Self-compacting flowable concrete material produced from the following:
  - 1. Portland Cement: ASTM C 150, Type I.
  - 2. Fly Ash: ASTM C 618, Class C or F.
  - 3. Normal-Weight Aggregate: ASTM C 33, 3/4-inch (19-mm) nominal maximum aggregate size.
  - 4. Foaming Agent: ASTM C 869.
  - 5. Water: ASTM C 94/C 94M.
  - 6. Air-Entraining Admixture: ASTM C 260.
- B. Produce low-density, controlled low-strength material with the following physical properties:
  - 1. As-Cast Unit Weight: 30 to 36 lb/cu. ft. (480 to 576 kg/cu. m) at point of placement, when tested according to ASTM C 138/C 138M.
  - 2. Compressive Strength: 80 psi (550 kPa), when tested according to ASTM C 495.
- C. Produce conventional-weight, controlled low-strength material with 80-psi (550-kPa) compressive strength when tested according to ASTM C 495.

# 2.4 ACCESSORIES

- A. Detectable Warning Tape: Acid- and alkali-resistant, polyethylene film warning tape manufactured for marking and identifying underground utilities, a minimum of 6 inches (150 mm) wide and 4 mils (0.1 mm) thick, continuously inscribed with a description of the utility, with metallic core encased in a protective jacket for corrosion protection, detectable by metal detector when tape is buried up to 30 inches (750 mm) deep; colored as follows:
  - 1. Red: Electric.
  - 2. Yellow: Gas, oil, steam, and dangerous materials.
  - 3. Orange: Telephone and other communications.
  - 4. Blue: Water systems.
  - 5. Green: Sewer systems.

### PART 3 - EXECUTION

### 3.1 PREPARATION

A. Protect structures, utilities, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout, and other hazards created by earth moving operations.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Protect and maintain erosion and sedimentation controls during earth moving operations.
- C. Protect subgrades and foundation soils from freezing temperatures and frost. Remove temporary protection before placing subsequent materials.

### 3.2 DEWATERING

- A. Prevent surface water and ground water from entering excavations, from ponding on prepared subgrades, and from flooding Project site and surrounding area.
- B. Protect subgrades from softening, undermining, washout, and damage by rain or water accumulation.
  - 1. Reroute surface water runoff away from excavated areas. Do not allow water to accumulate in excavations. Do not use excavated trenches as temporary drainage ditches.

### 3.3 EXPLOSIVES

A. Explosives: Do not use explosives.

# 3.4 EXCAVATION, GENERAL

- A. Unclassified Excavation: Excavate to subgrade elevations regardless of the character of surface and subsurface conditions encountered. Unclassified excavated materials may include rock, soil materials, and obstructions. No changes in the Contract Sum or the Contract Time will be authorized for rock excavation or removal of obstructions.
  - 1. If excavated materials intended for fill and backfill include unsatisfactory soil materials and rock, replace with satisfactory soil materials.
  - 2. Remove rock to lines and grades indicated to permit installation of permanent construction without exceeding the following dimensions:
    - a. 24 inches (600 mm) outside of concrete forms other than at footings.
    - b. 12 inches (300 mm) outside of concrete forms at footings.
    - c. 6 inches (150 mm) outside of minimum required dimensions of concrete cast against grade.
    - d. Outside dimensions of concrete walls indicated to be cast against rock without forms or exterior waterproofing treatments.

- e. 6 inches (150 mm) beneath bottom of concrete slabs-on-grade.
- f. 6 inches (150 mm) beneath pipe in trenches, and the greater of 24 inches (600 mm) wider than pipe or 42 inches (1065 mm) wide.

Issue Date: 06/05/2014

# 3.5 EXCAVATION FOR STRUCTURES

- A. Excavate to indicated elevations and dimensions within a tolerance of plus or minus 1 inch (25 mm). If applicable, extend excavations a sufficient distance from structures for placing and removing concrete formwork, for installing services and other construction, and for inspections.
  - 1. Excavations for Footings and Foundations: Do not disturb bottom of excavation. Excavate by hand to final grade just before placing concrete reinforcement. Trim bottoms to required lines and grades to leave solid base to receive other work.
  - 2. Excavation for Underground Tanks, Basins, and Mechanical or Electrical Utility Structures: Excavate to elevations and dimensions indicated within a tolerance of plus or minus 1 inch (25 mm). Do not disturb bottom of excavations intended as bearing surfaces.
- B. Excavations at Edges of Tree- and Plant-Protection Zones:
  - 1. Excavate by hand to indicated lines, cross sections, elevations, and subgrades. Use narrow-tine spading forks to comb soil and expose roots. Do not break, tear, or chop exposed roots. Do not use mechanical equipment that rips, tears, or pulls roots.
  - 2. Cut and protect roots according to requirements in Division 01 Section "Temporary Tree and Plant Protection."

# 3.6 EXCAVATION FOR WALKS AND PAVEMENTS

A. Excavate surfaces under walks and pavements to indicated lines, cross sections, elevations, and subgrades.

# 3.7 EXCAVATION FOR UTILITY TRENCHES

- A. Excavate trenches to indicated gradients, lines, depths, and elevations.
  - 1. Beyond building perimeter, excavate trenches to allow installation of top of pipe below frost line.
- B. Excavate trenches to uniform widths to provide the following clearance on each side of pipe or conduit. Excavate trench walls vertically from trench bottom to 12 inches (300 mm) higher than top of pipe or conduit unless otherwise indicated.
  - 1. Clearance: 12 inches (300 mm) each side of pipe or conduit.
- C. Trench Bottoms: Excavate and shape trench bottoms to provide uniform bearing and support of pipes and conduit. Shape subgrade to provide continuous support for bells, joints, and barrels of

pipes and for joints, fittings, and bodies of conduits. Remove projecting stones and sharp objects along trench subgrade.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. For pipes and conduit less than 6 inches (150 mm) in nominal diameter, hand-excavate trench bottoms and support pipe and conduit on an undisturbed subgrade.
- 2. For pipes and conduit 6 inches (150 mm) or larger in nominal diameter, shape bottom of trench to support bottom 90 degrees of pipe or conduit circumference. Fill depressions with tamped sand backfill.
- 3. For flat-bottomed, multiple-duct conduit units, hand-excavate trench bottoms and support conduit on an undisturbed subgrade.
- 4. Excavate trenches 6 inches (150 mm) deeper than elevation required in rock or other unyielding bearing material to allow for bedding course.
- D. Trench Bottoms: Excavate trenches 4 inches (100 mm) deeper than bottom of pipe and conduit elevations to allow for bedding course if necessary. Hand-excavate deeper for bells of pipe.
  - 1. Excavate trenches 6 inches (150 mm) deeper than elevation required in rock or other unyielding bearing material to allow for bedding course.
- E. Trenches in Tree- and Plant-Protection Zones:
  - 1. Hand-excavate to indicated lines, cross sections, elevations, and subgrades. Use narrowtine spading forks to comb soil and expose roots. Do not break, tear, or chop exposed roots. Do not use mechanical equipment that rips, tears, or pulls roots.
  - 2. Do not cut main lateral roots or taproots; cut only smaller roots that interfere with installation of utilities.
  - 3. Cut and protect roots according to requirements in Division 01 Section "Temporary Tree and Plant Protection."

### 3.8 SUBGRADE INSPECTION

- A. Notify Architect when excavations have reached required subgrade.
- B. If Architect determines that unsatisfactory soil is present, continue excavation and replace with compacted backfill or fill material as directed.
- C. Proof-roll subgrade below the building slabs and pavements with a pneumatic-tired and loaded 10-wheel, tandem-axle dump truck weighing not less than 15 tons (13.6 tonnes) to identify soft pockets and areas of excess yielding. Do not proof-roll wet or saturated subgrades.
  - 1. Completely proof-roll subgrade in one direction, repeating proof-rolling in direction perpendicular to first direction. Limit vehicle speed to 3 mph (5 km/h).
  - 2. Excavate soft spots, unsatisfactory soils, and areas of excessive pumping or rutting, as determined by Architect, and replace with compacted backfill or fill as directed.
- D. Authorized additional excavation and replacement material will be paid for according to Contract provisions for changes in the Work.

Re-Bid Set Issue Date: 06/05/2014

Architect's Project #: 12.130.09

E. Reconstruct subgrades damaged by freezing temperatures, frost, rain, accumulated water, or construction activities, as directed by Architect, without additional compensation.

### 3.9 UNAUTHORIZED EXCAVATION

- A. Fill unauthorized excavation under foundations or wall footings by extending bottom elevation of concrete foundation or footing to excavation bottom, without altering top elevation. Lean concrete fill, with 28-day compressive strength of 2500 psi (17.2 MPa), may be used when approved by Architect.
  - 1. Fill unauthorized excavations under other construction, pipe, or conduit as directed by Architect.

### 3.10 STORAGE OF SOIL MATERIALS

- A. Stockpile borrow soil materials and excavated satisfactory soil materials without intermixing. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
  - 1. Stockpile soil materials away from edge of excavations. Do not store within drip line of remaining trees.

### 3.11 BACKFILL

- A. Place and compact backfill in excavations promptly, but not before completing the following:
  - 1. Construction below finish grade including, where applicable, subdrainage, dampproofing, waterproofing, and perimeter insulation.
  - 2. Surveying locations of underground utilities for Record Documents.
  - 3. Testing and inspecting underground utilities.
  - 4. Removing concrete formwork.
  - 5. Removing trash and debris.
  - 6. Removing temporary shoring and bracing, and sheeting.
  - 7. Installing permanent or temporary horizontal bracing on horizontally supported walls.
- B. Place backfill on subgrades free of mud, frost, snow, or ice.

# 3.12 UTILITY TRENCH BACKFILL

- A. Place backfill on subgrades free of mud, frost, snow, or ice.
- B. Place and compact bedding course on trench bottoms and where indicated. Shape bedding course to provide continuous support for bells, joints, and barrels of pipes and for joints, fittings, and bodies of conduits.

C. Trenches under Footings: Backfill trenches excavated under footings and within 18 inches (450 mm) of bottom of footings with satisfactory soil; fill with concrete to elevation of bottom of footings. Concrete is specified in Division 03 Section "Cast-in-Place Concrete."

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- D. Backfill voids with satisfactory soil while removing shoring and bracing.
- E. Place and compact initial backfill of satisfactory soil, free of particles larger than 1 inch (25 mm) in any dimension, to a height of 12 inches (300 mm) over the pipe or conduit.
  - 1. Carefully compact initial backfill under pipe haunches and compact evenly up on both sides and along the full length of piping or conduit to avoid damage or displacement of piping or conduit. Coordinate backfilling with utilities testing.
- F. Controlled Low-Strength Material: Place initial backfill of controlled low-strength material to a height of 12 inches (300 mm) over the pipe or conduit. Coordinate backfilling with utilities testing.
- G. Place and compact final backfill of satisfactory soil to final subgrade elevation.
- H. Controlled Low-Strength Material: Place final backfill of controlled low-strength material to final subgrade elevation.
- I. Install warning tape directly above utilities, 12 inches (300 mm) below finished grade, except 6 inches (150 mm) below subgrade under pavements and slabs.

# 3.13 SOIL FILL

- A. Plow, scarify, bench, or break up sloped surfaces steeper than 1 vertical to 4 horizontal so fill material will bond with existing material.
- B. Place and compact fill material in layers to required elevations as follows:
  - 1. Under grass and planted areas, use satisfactory soil material.
  - 2. Under walks and pavements, use satisfactory soil material.
  - 3. Under steps and ramps, use satisfactory soil material.
  - 4. Under building slabs, use satisfactory soil material.
  - 5. Under footings and foundations, use satisfactory soil material.
- C. Place soil fill on subgrades free of mud, frost, snow, or ice.

# 3.14 SOIL MOISTURE CONTROL

- A. Uniformly moisten or aerate subgrade and each subsequent fill or backfill soil layer before compaction to within 2 percent of optimum moisture content.
  - 1. Do not place backfill or fill soil material on surfaces that are muddy, frozen, or contain frost or ice.

2. Remove and replace, or scarify and air dry, otherwise satisfactory soil material that exceeds optimum moisture content by 2 percent and is too wet to compact to specified dry unit weight.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# 3.15 COMPACTION OF SOIL BACKFILLS AND FILLS

- A. Refer to geotechnical report included in the specifications. Recommendations in geotechnical report shall govern over section 312000.
- B. Place backfill and fill soil materials in layers not more than 8 inches (200 mm) in loose depth for material compacted by heavy compaction equipment, and not more than 4 inches (100 mm) in loose depth for material compacted by hand-operated tampers
- C. Place backfill and fill soil materials evenly on all sides of structures to required elevations, and uniformly along the full length of each structure.
- D. Compact soil materials to not less than the following percentages of maximum dry unit weight according to ASTM D 698:
  - 1. Under structures, building slabs, steps, and pavements, scarify and recompact top 12 inches (300 mm) of existing subgrade and each layer of backfill or fill soil material at 98 percent and the upper one (1) foot of floor slab and footing area compacted to 100 percent of its maximum dry density.
  - 2. Under walkways, scarify and recompact top 6 inches (150 mm) below subgrade and compact each layer of backfill or fill soil material at 95 percent.
  - 3. Under turf or unpaved areas, scarify and recompact top 6 inches (150 mm) below subgrade and compact each layer of backfill or fill soil material at 85 percent.
  - 4. For utility trenches, compact each layer of initial and final backfill soil material at 90 percent in lawn areas and 95 percent under paved areas.

### 3.16 GRADING

- A. General: Uniformly grade areas to a smooth surface, free of irregular surface changes. Comply with compaction requirements and grade to cross sections, lines, and elevations indicated.
  - 1. Provide a smooth transition between adjacent existing grades and new grades.
  - 2. Cut out soft spots, fill low spots, and trim high spots to comply with required surface tolerances.
- B. Site Rough Grading: Slope grades to direct water away from buildings and to prevent ponding. Finish subgrades to required elevations within the following tolerances:
  - 1. Turf or Unpaved Areas: Plus or minus 1 inch (25 mm).
  - 2. Walks: Plus or minus 1/2 inch (13 mm).
  - 3. Pavements: Plus or minus 1/2 inch (13 mm).

C. Grading inside Building Lines: Finish subgrade to a tolerance of 1/2 inch (13 mm) when tested with a 10-foot (3-m) straightedge.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# 3.17 SUBBASE AND BASE COURSES UNDER PAVEMENTS AND WALKS

- A. Place subbase course and base course on subgrades free of mud, frost, snow, or ice.
- B. On prepared subgrade, place subbase course and base course under pavements and walks as follows:
  - 1. Install separation geotextile, if required, on prepared subgrade according to manufacturer's written instructions, overlapping sides and ends.
  - 2. Shape subbase course and base course to required crown elevations and cross-slope grades.
  - 3. Place subbase course and base course 6 inches (150 mm) or less in compacted thickness in a single layer.
  - 4. Place subbase course and base course that exceeds 6 inches (150 mm) in compacted thickness in layers of equal thickness, with no compacted layer more than 6 inches (150 mm) thick or less than 3 inches (75 mm) thick.
  - 5. Compact subbase course and base course at optimum moisture content to required grades, lines, cross sections, and thickness to not less than 95 percent of maximum dry unit weight according to ASTM D 698.
- C. Pavement Shoulders: Place shoulders along edges of subbase course and base course to prevent lateral movement. Construct shoulders, at least 12 inches (300 mm) wide, of satisfactory soil materials and compact simultaneously with each subbase and base layer to not less than 95 percent of maximum dry unit weight according to ASTM D 698.

### 3.18 DRAINAGE COURSE UNDER CONCRETE SLABS-ON-GRADE

- A. Place drainage course on subgrades free of mud, frost, snow, or ice.
- B. On prepared subgrade, place and compact drainage course under cast-in-place concrete slabs-on-grade as follows:
  - 1. Install subdrainage geotextile on prepared subgrade according to manufacturer's written instructions, overlapping sides and ends.
  - 2. Place drainage course 6 inches (150 mm) or less in compacted thickness in a single layer.
  - 3. Place drainage course that exceeds 6 inches (150 mm) in compacted thickness in layers of equal thickness, with no compacted layer more than 6 inches (150 mm) thick or less than 3 inches (75 mm) thick.
  - 4. Compact each layer of drainage course to required cross sections and thicknesses to not less than 95 percent of maximum dry unit weight according to ASTM D 698.

# 3.19 FIELD QUALITY CONTROL

- A. Special Inspections: Owner will engage a qualified special inspector to perform the following special inspections:
  - 1. Determine prior to placement of fill that site has been prepared in compliance with requirements.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Determine that fill material and maximum lift thickness comply with requirements.
- 3. Determine, at the required frequency, that in-place density of compacted fill complies with requirements.
- B. Testing Agency: Owner will engage a qualified geotechnical engineering testing agency to perform tests and inspections.
- C. Allow testing agency to inspect and test subgrades and each fill or backfill layer. Proceed with subsequent earth moving only after test results for previously completed work comply with requirements.
- D. Footing Subgrade: At footing subgrades, at least one test of each soil stratum will be performed to verify design bearing capacities. Subsequent verification and approval of other footing subgrades may be based on a visual comparison of subgrade with tested subgrade when approved by Architect.
- E. Testing agency will test compaction of soils in place according to ASTM D 698, ASTM D 1556, ASTM D 2167, ASTM D 2922, and ASTM D 2937 as applicable. Tests will be performed at the following locations and frequencies:
  - 1. Paved and Building Slab Areas: At subgrade and at each compacted fill and backfill layer, at least one test for every 2000 sq. ft. (186 sq. m) or less of paved area or building slab, but in no case fewer than three tests.
  - 2. Foundation Wall Backfill: At each compacted backfill layer, at least one test for every 100 feet (30 m) or less of wall length, but no fewer than two tests.
  - 3. Trench Backfill: At each compacted initial and final backfill layer, at least one test for every 150 feet (46 m) or less of trench length, but no fewer than two tests.
- F. When testing agency reports that subgrades, fills, or backfills have not achieved degree of compaction specified, scarify and moisten or aerate, or remove and replace soil materials to depth required; recompact and retest until specified compaction is obtained.

### 3.20 PROTECTION

- A. Protecting Graded Areas: Protect newly graded areas from traffic, freezing, and erosion. Keep free of trash and debris.
- B. Repair and reestablish grades to specified tolerances where completed or partially completed surfaces become eroded, rutted, settled, or where they lose compaction due to subsequent construction operations or weather conditions.

- e-Bid Set Issue Date: 06/05/2014
  - 1. Scarify or remove and replace soil material to depth as directed by Architect; reshape and recompact.

- C. Where settling occurs before Project correction period elapses, remove finished surfacing, backfill with additional soil material, compact, and reconstruct surfacing.
  - 1. Restore appearance, quality, and condition of finished surfacing to match adjacent work, and eliminate evidence of restoration to greatest extent possible.

# 3.21 DISPOSAL OF SURPLUS AND WASTE MATERIALS

A. Remove surplus satisfactory soil and waste materials, including unsatisfactory soil, trash, and debris, and legally dispose of them off Owner's property.

END OF SECTION 312000

### SECTION 313116 - TERMITE CONTROL

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

# 1.2 SUMMARY

- A. Section Includes:
  - 1. Soil treatment with termiticide.

### 1.3 SUBMITTALS

- A. Product Data: For each type of termite control product.
  - 1. Include the EPA-Registered Label for termiticide products.
  - 2. Include the Certificate of Product Registration with the South Carolina Department of Pesticide Regulation.
- B. Qualification Data: For qualified Installer, include a copy of the current Business License in Category 7A along with the Commercial Applicator License issued by the South Carolina Department of Pesticide Regulation.
- C. Product Certificates: For termite control products, from manufacturer.
- D. Soil Treatment Application Report: After application of termiticide is completed, submit report for Owner's records and include the following:
  - 1. Date and time of application.
  - 2. Moisture content of soil before application.
  - 3. Termiticide brand name and manufacturer.
  - 4. Quantity of undiluted termiticide used.
  - 5. Dilutions, methods, volumes used, and rates of application.
  - 6. Areas of application.
  - 7. Water source for application.
- E. Warranties: Sample of special warranties.

# 1.4 OUALITY ASSURANCE

A. Installer Qualifications: A specialist who is licensed according to regulations of authorities having jurisdiction to apply termite control treatment and products in jurisdiction where Project is located.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Regulatory Requirements: Formulate and apply termiticides and termiticide devices according to the EPA-Registered Label.
- C. Source Limitations: Obtain termite control products from single source from single manufacturer.

### 1.5 PROJECT CONDITIONS

- A. Environmental Limitations: To ensure penetration, do not treat soil that is water saturated or frozen. Do not treat soil while precipitation is occurring. Comply with requirements of the EPA-Registered Label and requirements of authorities having jurisdiction.
- B. Coordinate soil treatment application with excavating, filling, grading, and concreting operations. Treat soil under footings, grade beams, and ground-supported slabs before construction.

# 1.6 WARRANTY

- A. Soil Treatment Special Warranty: Manufacturer's standard form, signed by Applicator and Contractor, certifying that termite control work, consisting of applied soil termiticide treatment, will prevent infestation of subterranean termites. If subterranean termite activity or damage is discovered during warranty period, re-treat soil and repair or replace damage caused by termite infestation.
  - 1. Warranty Period: Five years from date of Substantial Completion.

# 1.7 MAINTENANCE SERVICE

A. Continuing Service: Beginning at Substantial Completion, provide 12 months' continuing service including monitoring, inspection, and re-treatment for occurrences of termite activity. Provide a standard continuing service agreement. State services, obligations, conditions, terms for agreement period, and terms for future renewal options.

### PART 2 - PRODUCTS

# 2.1 SOIL TREATMENT

A. Termiticide: Provide termiticide products registered by the EPA and South Carolina Department of Pesticide Regulation complying with requirements of authorities having

jurisdiction, in an aqueous solution formulated to prevent termite infestation. Provide quantity required for application at the label volume and rate for the maximum termiticide concentration

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Products: Subject to compliance with requirements, provide one of the following:
  - a. BASF Corporation, Agricultural Products; Termidor.

allowed for each specific use, according to product's EPA-Registered Label.

- b. <u>Bayer Environmental Science</u>; Premise 75.
- c. FMC Corporation, Agricultural Products Group; Talstar, Prevail.
- d. Syngenta; Demon TC, Prelude, Probuild TC.
- 2. Service Life of Treatment: Soil treatment termiticide that is effective for not less than five years against infestation of subterranean termites.

### PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Applicator present, for compliance with requirements for moisture content of soil per termiticide label requirements, interfaces with earthwork, slab and foundation work, landscaping, utility installation, and other conditions affecting performance of termite control.
- B. Proceed with application only after unsatisfactory conditions have been corrected.

# 3.2 PREPARATION

- A. General: Comply with the most stringent requirements of authorities having jurisdiction and with manufacturer's written instructions for preparation before beginning application of termite control treatment. Remove all extraneous sources of wood cellulose and other edible materials such as wood debris, tree stumps and roots, stakes, formwork, and construction waste wood from soil within and around foundations.
- B. Soil Treatment Preparation: Remove foreign matter and impermeable soil materials that could decrease treatment effectiveness on areas to be treated. Loosen, rake, and level soil to be treated except previously compacted areas under slabs and footings. Termiticides may be applied before placing compacted fill under slabs if recommended in writing by termiticide manufacturer.
  - 1. Fit filling hose connected to water source at the site with a backflow preventer, complying with requirements of authorities having jurisdiction.

# 3.3 APPLICATION, GENERAL

A. General: Comply with the most stringent requirements of authorities having jurisdiction and with manufacturer's EPA-Registered Label for products.

# 3.4 APPLYING SOIL TREATMENT

- A. Application: Mix soil treatment termiticide solution to a uniform consistency. Provide quantity required for application at the label volume and rate for the maximum specified concentration of termiticide, according to manufacturer's EPA-Registered Label, to the following so that a continuous horizontal and vertical termiticidal barrier or treated zone is established around and under building construction. Distribute treatment evenly.
  - 1. Slabs-on-Grade: Under ground-supported slab construction, including footings, building slabs, and attached slabs as an overall treatment. Treat soil materials before concrete footings and slabs are placed.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Foundations: Adjacent soil, including soil along the entire inside perimeter of foundation walls; along both sides of interior partition walls; around plumbing pipes and electric conduit penetrating the slab; around interior column footers, piers, and chimney bases; and along the entire outside perimeter, from grade to bottom of footing. Avoid soil washout around footings.
- 3. Masonry: Treat voids.
- 4. Penetrations: At expansion joints, control joints, and areas where slabs will be penetrated.
- B. Avoid disturbance of treated soil after application. Keep off treated areas until completely dry.
- C. Protect termiticide solution, dispersed in treated soils and fills, from being diluted until ground-supported slabs are installed. Use waterproof barrier according to EPA-Registered Label instructions.
- D. Post warning signs in areas of application.
- E. Reapply soil treatment solution to areas disturbed by subsequent excavation, grading, landscaping, or other construction activities following application.

END OF SECTION 313116

# SECTION 321313 - CONCRETE PAVING

# PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### 1.2 SUMMARY

- A. This Section includes exterior cement concrete pavement for the following:
  - 1. Pads
  - 2. Walkways.
- B. Related Sections include the following:
  - 1. Division 03 Section "Cast-in-Place Concrete" for general building applications of concrete.
  - 2. Division 31 Section "Earth Moving" for subgrade preparation, grading, and subbase course.

### 1.3 DEFINITIONS

A. Cementitious Materials: Portland cement alone or in combination with one or more of blended hydraulic cement, fly ash and other pozzolans, and ground granulated blast-furnace slag.

### 1.4 SUBMITTALS

- A. Product Data: For each type of manufactured material and product indicated.
- B. Design Mixtures: For each concrete pavement mixture. Include alternate mixture designs when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.
- C. Qualification Data: For manufacturer.
- D. Material Test Reports: From a qualified testing agency indicating and interpreting test results for compliance of the following with requirements indicated, based on comprehensive testing of current materials:
  - 1. Aggregates. Include service record data indicating absence of deleterious expansion of concrete due to alkali-aggregate reactivity.

E. Material Certificates: Signed by manufacturers certifying that each of the following materials complies with requirements:

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 1. Cementitious materials.
- 2. Admixtures.
- 3. Curing compounds.
- 4. Bonding agent or epoxy adhesive.
- 5. Joint fillers.
- F. Field quality-control test reports.
- G. Minutes of preinstallation conference.

# 1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Manufacturer of ready-mixed concrete products who complies with ASTM C 94/C 94M requirements for production facilities and equipment.
  - 1. Manufacturer certified according to NRMCA's "Certification of Ready Mixed Concrete Production Facilities."
- B. Testing Agency Qualifications: An independent agency qualified according to ASTM C 1077 and ASTM E 329 for testing indicated, as documented according to ASTM E 548.
  - 1. Personnel conducting field tests shall be qualified as ACI Concrete Field Testing Technician, Grade 1, according to ACI CP-01 or an equivalent certification program.
- C. ACI Publications: Comply with ACI 301, "Specification for Structural Concrete," unless modified by requirements in the Contract Documents.
- D. Concrete Testing Service: Engage a qualified independent testing agency to perform material evaluation tests and to design concrete mixtures.
- E. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01 Section "Project Management and Coordination."
  - 1. Before submitting design mixtures, review concrete pavement mixture design and examine procedures for ensuring quality of concrete materials and concrete pavement construction practices. Require representatives, including the following, of each entity directly concerned with concrete pavement, to attend conference:
    - a. Contractor's superintendent.
    - b. Independent testing agency responsible for concrete design mixtures.
    - c. Ready-mix concrete producer.
    - d. Concrete pavement subcontractor.

### 1.6 PROJECT CONDITIONS

A. Traffic Control: Maintain access for vehicular and pedestrian traffic as required for other construction activities.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

### PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
  - 1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, products specified.
  - 2. Products: Subject to compliance with requirements, provide one of the products specified.
  - 3. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, manufacturers specified.
  - 4. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

### 2.2 FORMS

- A. Form Materials: Plywood, metal, metal-framed plywood, or other approved panel-type materials to provide full-depth, continuous, straight, smooth exposed surfaces.
  - 1. Use flexible or curved forms for curves with a radius 100 feet (30.5 m) or less.
- B. Form-Release Agent: Commercially formulated form-release agent that will not bond with, stain, or adversely affect concrete surfaces and will not impair subsequent treatments of concrete surfaces.

### 2.3 CONCRETE MATERIALS

- A. Cementitious Material: Use one of the following cementitious materials, of the same type, brand, and source throughout the Project:
  - 1. Portland Cement: ASTM C 150, Type I/II
    - a. Fly Ash: ASTM C 618, Class F.
    - b. Ground Granulated Blast-Furnace Slag: ASTM C 989, Grade 100 or 120.
- B. Normal-Weight Aggregates: ASTM C 33, Class 4M, 4S, 1N coarse aggregate, uniformly graded. Provide aggregates from a single source with documented service record data of at least

Issue Date: 06/05/2014

10 years' satisfactory service in similar pavement applications and service conditions using similar aggregates and cementitious materials.

- 1. Maximum Coarse-Aggregate Size: 1 inch (25 mm) nominal.
- 2. Fine Aggregate: Free of materials with deleterious reactivity to alkali in cement.
- C. Water: ASTM C 94/C 94M.
- D. Air-Entraining Admixture: ASTM C 260.
- E. Chemical Admixtures: Provide admixtures certified by manufacturer to be compatible with other admixtures and to contain not more than 0.1 percent water-soluble chloride ions by mass of cementitious material.
  - 1. Water-Reducing Admixture: ASTM C 494/C 494M, Type A.
  - 2. Retarding Admixture: ASTM C 494/C 494M, Type B.
  - 3. Water-Reducing and Retarding Admixture: ASTM C 494/C 494M, Type D.
  - 4. High-Range, Water-Reducing Admixture: ASTM C 494/C 494M, Type F.
  - 5. High-Range, Water-Reducing and Retarding Admixture: ASTM C 494/C 494M, Type G.
  - 6. Plasticizing and Retarding Admixture: ASTM C 1017/C 1017M, Type II.

# 2.4 CURING MATERIALS

- A. Absorptive Cover: AASHTO M 182, Class 2, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd. (305 g/sq. m) dry.
- B. Moisture-Retaining Cover: ASTM C 171, polyethylene film or white burlap-polyethylene sheet.
- C. Water: Potable.
- D. Evaporation Retarder: Waterborne, monomolecular film forming; manufactured for application to fresh concrete.
  - 1. Available products equal to but not limited to the following:
    - a. Axim Concrete Technologies; Cimfilm.
    - b. Burke by Edeco; BurkeFilm.
    - c. ChemMasters; Spray-Film.
    - d. Conspec Marketing & Manufacturing Co., Inc.; Aquafilm.
    - e. Dayton Superior Corporation; Sure Film.
    - f. Euclid Chemical Company (The); Eucobar.
    - g. Kaufman Products, Inc.; Vapor Aid.
    - h. Lambert Corporation; Lambco Skin.
    - i. L&M Construction Chemicals, Inc.; E-Con.
    - j. MBT Protection and Repair, ChemRex Inc.; Confilm.
    - k. Meadows, W. R., Inc.; Sealtight Evapre.
    - 1. Metalcrete Industries; Waterhold.

m. Nox-Crete Products Group, Kinsman Corporation; Monofilm.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- n. Sika Corporation, Inc.; SikaFilm.
- o. Symons Corporation; Finishing Aid.
- p. Vexcon Chemicals, Inc.; Certi-Vex EnvioAssist.
- E. Clear Waterborne Membrane-Forming Curing Compound: ASTM C 309, Type 1, Class B.
  - 1. Available products equal to but not limited to the following:
    - a. Anti-Hydro International, Inc.; AH Curing Compound #2 DR WB.
    - b. Burke by Edoko; Aqua Resin Cure.
    - c. ChemMasters; Safe-Cure Clear.
    - d. Conspec Marketing & Manufacturing Co., Inc.; W.B. Resin Cure.
    - e. Dayton Superior Corporation; Day Chem Rez Cure (J-11-W).
    - f. Euclid Chemical Company (The); Kurez DR VOX.
    - g. Kaufman Products, Inc.; Thinfilm 420.
    - h. Lambert Corporation; Aqua Kure-Clear.
    - i. L&M Construction Chemicals, Inc.; L&M Cure R.
    - j. Meadows, W. R., Inc.; 1100 Clear.
    - k. Nox-Crete Products Group, Kinsman Corporation; Resin Cure E.
    - 1. Symons Corporation; Resi-Chem Clear.
    - m. Tamms Industries Inc.; Horncure WB 30.
    - n. Unitex; Hydro Cure 309.
    - o. Vexcon Chemicals, Inc.; Certi-Vex Enviocure 100.

# 2.5 RELATED MATERIALS

- A. Expansion- and Isolation-Joint-Filler Strips: ASTM D 1751, asphalt-saturated cellulosic fiber.
- B. Bonding Agent: ASTM C 1059, Type II, non-redispersible, acrylic emulsion or styrene butadiene.
- C. Epoxy Bonding Adhesive: ASTM C 881, two-component epoxy resin, capable of humid curing and bonding to damp surfaces, of class suitable for application temperature and of grade to requirements, and as follows:
  - 1. Types I and II, non-load bearing, for bonding hardened or freshly mixed concrete to hardened concrete.
- D. Chemical Surface Retarder: Water-soluble, liquid-set retarder with color dye, for horizontal concrete surface application, capable of temporarily delaying final hardening of concrete to a depth of 1/8 to 1/4 inch (3 to 6 mm).
  - 1. Available products equal to but not limited to the following:
    - a. Burke by Edeco; True Etch Surface Retarder.
    - b. ChemMasters; Exposee.
    - c. Conspec Marketing & Manufacturing Co., Inc.; Delay S.
    - d. Euclid Chemical Company (The); Surface Retarder S.

- e. Kaufman Products, Inc.; Expose.
- f. Metalcrete Industries; Surftard.
- g. Nox-Crete Products Group, Kinsman Corporation; Crete-Nox TA.

Issue Date: 06/05/2014

- h. Scofield, L. M. Company; Lithotex.
- i. Sika Corporation, Inc.; Rugasol-S.
- j. Vexcon Chemicals, Inc.; Certi-Vex Envioset.

### 2.6 CONCRETE MIXTURES

- A. Prepare design mixtures, proportioned according to ACI 301, for each type and strength of normal-weight concrete determined by either laboratory trial mixes or field experience.
  - 1. Use a qualified independent testing agency for preparing and reporting proposed concrete mixture designs for the trial batch method.
- B. Add air-entraining admixture at manufacturer's prescribed rate to result in normal-weight concrete at point of placement having an air content as follows:
  - 1. Air Content: 6 percent plus or minus 1.5 percent for 1-inch (25-mm) nominal maximum aggregate size.
- C. Limit water-soluble, chloride-ion content in hardened concrete to 0.15 percent by weight of cement.
- D. Chemical Admixtures: Use admixtures according to manufacturer's written instructions.
  - 1. Use water-reducing admixture, high-range, water-reducing admixture, high-range, water-reducing and retarding mixture, plasticizing and retarding mixture in concrete, as required, for placement and workability.
  - 2. Use water-reducing and retarding admixture when required by high temperatures, low humidity, or other adverse placement conditions.
- E. Cementitious Materials: Limit percentage, by weight, of cementitious materials other than portland cement according to ACI 301 requirements as follows:
  - 1. Fly Ash or Pozzolan: 25 percent.
  - 2. Ground Granulated Blast-Furnace Slag: 50 percent.
  - 3. Combined Fly Ash or Pozzolan, and Ground Granulated Blast-Furnace Slag: 50 percent, with fly ash or pozzolan not exceeding 25 percent.

# 2.7 CONCRETE MIXING

- A. Project-Site Mixing: Measure, batch, and mix concrete materials and concrete according to ASTM C 94/C 94M. Mix concrete materials in appropriate drum-type batch machine mixer.
  - 1. For concrete mixes of 1 cu. yd. (0.76 cu. m) or smaller, continue mixing at least 1-1/2 minutes, but not more than 5 minutes after ingredients are in mixer, before any part of batch is released.

Re-Bid Set Issue Date: 06/05/2014

2. For concrete mixes larger than 1 cu. yd. (0.76 cu. m), increase mixing time by 15 seconds for each additional 1 cu. yd. (0.76 cu. m).

Architect's Project #: 12.130.09

3. Provide batch ticket for each batch discharged and used in the Work, indicating Project identification name and number, date, mixture type, mixing time, quantity, and amount of water added.

### PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine exposed subgrades and subbase surfaces for compliance with requirements for dimensional, grading, and elevation tolerances.
- B. Proof-roll prepared subbase surface below concrete pavements with heavy pneumatic-tired equipment to identify soft pockets and areas of excess yielding.
  - 1. Completely proof-roll subbase in one direction and repeat in perpendicular direction. Limit vehicle speed to 3 mph (5 km/h).
  - 2. Proof-roll with a loaded 10-wheel tandem-axle dump truck weighing not less than 15 tons (13.6 tonnes).
  - 3. Subbase with soft spots and areas of pumping or rutting exceeding depth of 1/2 inch (13 mm) require correction according to requirements in Division 31 Section "Earth Moving."
- C. Proceed with concrete pavement operations only after nonconforming conditions have been corrected and subgrade is ready to receive pavement.

### 3.2 PREPARATION

A. Remove loose material from compacted subbase surface immediately before placing concrete.

### 3.3 EDGE FORMS AND SCREED CONSTRUCTION

- A. Set, brace, and secure edge forms, bulkheads, and intermediate screed guides for pavement to required lines, grades, and elevations. Install forms to allow continuous progress of work and so forms can remain in place at least 24 hours after concrete placement.
- B. Clean forms after each use and coat with form-release agent to ensure separation from concrete without damage.

### 3.4 JOINTS

A. General: Form construction, isolation, and contraction joints and tool edgings true to line with faces perpendicular to surface plane of concrete. Construct transverse joints at right angles to centerline, unless otherwise indicated.

1. When joining existing pavement, place transverse joints to align with previously placed joints, unless otherwise indicated.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- B. Construction Joints: Set construction joints at side and end terminations of pavement and at locations where pavement operations are stopped for more than one-half hour unless pavement terminates at isolation joints.
  - 1. Butt Joints: Use bonding agent at joint locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
  - 2. Keyed Joints: Provide preformed keyway-section forms or bulkhead forms with keys, unless otherwise indicated. Embed keys at least 1-1/2 inches (38 mm) into concrete.
- C. Isolation Joints: Form isolation joints of preformed joint-filler strips abutting concrete curbs, catch basins, manholes, inlets, structures, walks, other fixed objects, and where indicated.
  - 1. Locate expansion joints at intervals of 50 feet (15.25 m), unless otherwise indicated.
  - 2. Extend joint fillers full width and depth of joint.
  - 3. Terminate joint filler not less than 1/2 inch (13 mm) or more than 1 inch (25 mm) below finished surface if joint sealant is indicated.
  - 4. Place top of joint filler flush with finished concrete surface if joint sealant is not indicated.
  - 5. Furnish joint fillers in one-piece lengths. Where more than one length is required, lace or clip joint-filler sections together.
  - 6. Protect top edge of joint filler during concrete placement with metal, plastic, or other temporary preformed cap. Remove protective cap after concrete has been placed on both sides of joint.
- D. Contraction Joints: Form weakened-plane contraction joints, sectioning concrete into areas as indicated. Construct contraction joints for a depth equal to at least one-fourth of the concrete thickness, as follows:
  - 1. Sawed Joints: Form contraction joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch- (3-mm-) wide joints into concrete when cutting action will not tear, abrade, or otherwise damage surface and before developing random contraction cracks.
  - 2. Scored Joints: On sidewalk score joints at 10' o/c unless otherwise indicated on drawings. On sidewalks wider than 10' provide a center line scoring. On curb and gutters and concrete flumes score joints shall be at 10' o/c.
- E. Edging: Tool edges of pavement, gutters, curbs, and joints in concrete after initial floating with an edging tool to a 1/4-inch (6-mm) radius. Repeat tooling of edges after applying surface finishes. Eliminate tool marks on concrete surfaces.

# 3.5 CONCRETE PLACEMENT

A. Inspection: Before placing concrete, inspect and complete formwork installation, steel reinforcement, and items to be embedded or cast in. Notify other trades to permit installation of their work.

B. Remove snow, ice, or frost from subbase surface and reinforcement before placing concrete. Do not place concrete on frozen surfaces.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- C. Moisten subbase to provide a uniform dampened condition at time concrete is placed. Do not place concrete around manholes or other structures until they are at required finish elevation and alignment.
- D. Comply with ACI 301 requirements for measuring, mixing, transporting, and placing concrete.
- E. Do not add water to concrete during delivery or at Project site.
- F. Do not add water to fresh concrete after testing.
- G. Deposit and spread concrete in a continuous operation between transverse joints. Do not push or drag concrete into place or use vibrators to move concrete into place.
- H. Consolidate concrete according to ACI 301 by mechanical vibrating equipment supplemented by hand spading, rodding, or tamping.
  - 1. Consolidate concrete along face of forms and adjacent to transverse joints with an internal vibrator. Keep vibrator away from joint assemblies, or side forms. Use only square-faced shovels for hand spreading and consolidation. Consolidate with care to prevent dislocating joint devices.
- I. Place concrete in one operation.
- J. Screed pavement surfaces with a straightedge and strike off.
- K. Commence initial floating using bull floats or darbies to impart an open textured and uniform surface plane before excess moisture or bleed water appears on the surface. Do not further disturb concrete surfaces before beginning finishing operations or spreading surface treatments.
- L. Cold-Weather Placement: Comply with ACI 306.1 and as follows. Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.
  - 1. When air temperature has fallen to or is expected to fall below 40 deg F (4.4 deg C), uniformly heat water and aggregates before mixing to obtain a concrete mixture temperature of not less than 50 deg F (10 deg C) and not more than 80 deg F (27 deg C) at point of placement.
  - 2. Do not use frozen materials or materials containing ice or snow.
  - 3. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators unless otherwise specified and approved in mix designs.
- M. Hot-Weather Placement: Comply with ACI 301 and as follows when hot-weather conditions exist:
  - 1. Cool ingredients before mixing to maintain concrete temperature below 90 deg F (32 deg C) at time of placement. Chilled mixing water or chopped ice may be used to control

temperature, provided water equivalent of ice is calculated to total amount of mixing water. Using liquid nitrogen to cool concrete is Contractor's option.

Architect's Project #: 12.130.09

Issue Date: 06/05/2014

- 2. Cover steel reinforcement with water-soaked burlap so steel temperature will not exceed ambient air temperature immediately before embedding in concrete.
- 3. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade moisture uniform without standing water, soft spots, or dry areas.

### 3.6 FLOAT FINISHING

- A. General: Do not add water to concrete surfaces during finishing operations.
- B. Float Finish: Begin the second floating operation when bleed-water sheen has disappeared and concrete surface has stiffened sufficiently to permit operations. Float surface with power-driven floats, or by hand floating if area is small or inaccessible to power units. Finish surfaces to true planes. Cut down high spots and fill low spots. Refloat surface immediately to uniform granular texture.

Sidewalks: Medium-to-Fine-Textured Broom Finish: Draw a soft bristle broom across float-finished concrete surface perpendicular to line of traffic to provide a uniform, fine-line texture.

Concourse: Match adjoining finish on existing concourse pavement areas.

# 3.7 CONCRETE PROTECTION AND CURING

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.
- B. Comply with ACI 306.1 for cold-weather protection.
- C. Evaporation Retarder: Apply evaporation retarder to concrete surfaces if hot, dry, or windy conditions cause moisture loss approaching 0.2 lb/sq. ft. x h (1 kg/sq. m x h) before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding, and bull floating or darbying concrete, but before float finishing.
- D. Begin curing after finishing concrete but not before free water has disappeared from concrete surface.
- E. Curing Methods: Cure concrete by moisture curing, moisture-retaining-cover curing, curing compound, or a combination of these as follows:
  - 1. Moist Curing: Keep surfaces continuously moist for not less than seven days with the following materials:
    - a. Water.
    - b. Continuous water-fog spray.
    - c. Absorptive cover, water saturated and kept continuously wet. Cover concrete surfaces and edges with 12-inch (300-mm) lap over adjacent absorptive covers.

Re-Bid Set Issue Date: 06/05/2014

2. Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches (300 mm), and sealed by waterproof tape or adhesive. Immediately repair any holes or tears during curing period using cover material and waterproof tape.

Architect's Project #: 12.130.09

3. Curing Compound: Apply uniformly in continuous operation by power spray or roller according to manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Maintain continuity of coating and repair damage during curing period.

### 3.8 PAVEMENT TOLERANCES

- A. Comply with tolerances of ACI 117 and as follows:
  - 1. Elevation: 1/4 inch (6 mm).
  - 2. Thickness: Plus 3/8 inch (10 mm), minus 1/4 inch (6 mm).
  - 3. Surface: Gap below 10-foot- (3-m-) long, unleveled straightedge not to exceed 1/4 inch (6 mm).
  - 4. Contraction Joint Depth: Plus 1/4 inch (6 mm), no minus.
  - 5. Joint Width: Plus 1/8 inch (3 mm), no minus.

# 3.9 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports.
- B. Testing Services: Testing of composite samples of fresh concrete obtained according to ASTM C 172 shall be performed according to the following requirements:
  - 1. Testing Frequency: Obtain at least 1 composite sample for each 100 cu. yd. (76 cu. m) 5000 sq. ft. (465 sq. m) or fraction thereof of each concrete mix placed each day.
    - a. When frequency of testing will provide fewer than five compressive-strength tests for each concrete mixture, testing shall be conducted from at least five randomly selected batches or from each batch if fewer than five are used.
  - 2. Slump: ASTM C 143/C 143M; one test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mix. Perform additional tests when concrete consistency appears to change.
  - 3. Air Content: ASTM C 231, pressure method; one test for each composite sample, but not less than one test for each day's pour of each concrete mix.
  - 4. Concrete Temperature: ASTM C 1064; one test hourly when air temperature is 40 deg F (4.4 deg C) and below and when 80 deg F (27 deg C) and above, and one test for each composite sample.
  - 5. Compression Test Specimens: ASTM C 31/C 31M; cast and laboratory cure one set of three standard cylinder specimens for each composite sample.
  - 6. Compressive-Strength Tests: ASTM C 39/C 39M; test 1 specimen at 7 days and 2 specimens at 28 days.

- Bid Set Issue Date: 06/05/2014
  - a. A compressive-strength test shall be the average compressive strength from 2 specimens obtained from same composite sample and tested at 28 days.

- C. Strength of each concrete mix will be satisfactory if average of any 3 consecutive compressive-strength tests equals or exceeds specified compressive strength and no compressive-strength test value falls below specified compressive strength by more than 500 psi (3.4 MPa).
- D. Test results shall be reported in writing to Architect, concrete manufacturer, and Contractor within 48 hours of testing. Reports of compressive-strength tests shall contain Project identification name and number, date of concrete placement, name of concrete testing and inspecting agency, location of concrete batch in Work, design compressive strength at 28 days, concrete mixture proportions and materials, compressive breaking strength, and type of break for both 7- and 28-day tests.
- E. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.
- F. Additional Tests: Testing and inspecting agency shall make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Architect.
- G. Remove and replace concrete pavement where test results indicate that it does not comply with specified requirements.
- H. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

# 3.10 REPAIRS AND PROTECTION

- A. Remove and replace concrete pavement that is broken, damaged, or defective or that does not comply with requirements in this Section.
- B. Drill test cores, where directed by Architect, when necessary to determine magnitude of cracks or defective areas. Fill drilled core holes in satisfactory pavement areas with portland cement concrete bonded to pavement with epoxy adhesive.
- C. Protect concrete from damage. Exclude traffic from pavement for at least 14 days after placement. When construction traffic is permitted, maintain pavement as clean as possible by removing surface stains and spillage of materials as they occur.
- D. Maintain concrete pavement free of stains, discoloration, dirt, and other foreign material. Sweep concrete pavement not more than two days before date scheduled for Substantial Completion inspections.

END OF SECTION 321313