

University of South Carolina  
Jones PSC 210 Renovations

State Project No. H27-I905  
Architect's Project No. 11.126.00  
Addendum No. 2

Quackenbush Architects + Planners  
1217 Hampton Street  
Columbia, South Carolina 29201

February 29, 2012

**ADDENDUM NO.2**

The following items shall take precedence over the drawings and specifications for the above named project and shall become a part of the contract documents. Where any item called for in the specifications, or indicated on the drawings, is not supplemented hereby, the original requirements shall remain in effect. Where any original item is amended, voided or superseded hereby, the provisions of such item not specifically amended, voided or superseded shall remain in effect.

**ATTACHMENTS**

None

**SPECIFICATIONS**

- | <b><u>Item No.</u></b> | <b><u>Description</u></b>  |
|------------------------|--|
| 1.                     | Refer to Specification Section 126100, FIXED AUDIENCE SEATING, 2.3, A, 2.a and replace with the following:<br><br>a. <i>American Seating Company: "Spirit HQ", "Stellar" system frame and seat with "Spirit" Back.</i>   |
| 2.                     | Refer to Specification Section 126100, FIXED AUDIENCE SEATING, 2.3, B and add the following:<br><br>2. <i>Cast Iron: One-piece castings with integral mounting points and attachment anchoring points for seat pivots, backs, and armrests.</i>  |
| 3.                     | Refer to Specification Section 126100, FIXED AUDIENCE SEATING, 3.2, A and add the following:<br><br>4. <i>Install standards with epoxy anchors as required for attachment to existing concrete substrate.</i><br>5. <i>Provide and install larger steel mounting plates as required for riser chair mounting where existing chair anchor holes interfere with required clearances for attachment to concrete substrate in order to maintain a secure installation.</i> |

## DRAWINGS

- | <u>Item No.</u> | <u>Description</u>  |
|-----------------|---|
| 1.              | <p>Reference sheet E0.0, Partial First Floor Renovation Plan -1: Add "general note GN1, GN2 &amp; PN29".</p> <p><i>GN1. ALL NEW CONDUIT RUNS SHALL HAVE PULL STRINGS. COORDINATE.</i></p> <p><i>GN2. ALL JUNCTION BOXES LOCATED ABOVE THE SOFFIT FOR THE PROJECTOR SCREENS AND THE MOTORIZED MARKER BOARD SHALL BE ACCESSIBLE FROM THE REMOVABLE PANELS OR THE ACOUSTICAL CEILING. COORDINATE.</i></p> <p><i>PN29. EC SHALL FURNISH AND INSTALL J-BOX UNDER FUME HOOD TO PROVIDE POWER FOR THE FUMEHOOD LIGHTBOX. CONNECT J-BOX TO NEAREST 120V CIRCUIT IN SPACE. A SWITCH SHALL BE INSTALLED ON THE FACE OF THE CABINET THAT HOUSES THE FUMEHOOD TO CONTROL THE LIGHTBOX. EC SHALL MAKE ALL REQUIRED CONNECTIONS AND COORDINATE WITH FUMEHOOD INSTALLATION INSTRUCTIONS AND CASEWORK MANUFACTURER AND INSTALLER.</i></p> |
| 2.              | <p>Reference sheet E0.0, Partial Demolition Plan: Delete note "DN4." and replace with the following:</p> <p><i>DN4. EC SHALL DISCONNECT AND REMOVE EXISTING LAMP. EC SHALL FURNISH AND INSTALL A NEW DIMMABLE 120V L.E.D. PAR 30 LAMP COORDINATE.</i></p>   |
| 3.              | <p>Reference sheet E0.0, Partial First Floor Demolition Plan: Delete note "DN9 &amp; DN11." and replace with the following:</p> <p><i>DN9. EC SHALL DISCONNECT AND REMOVE EXISTING FIXTURE LENS. EC SHALL FURNISH AND INSTALL A NEW EGG CRATE LOUVER LENS. RE-LAMP BROKEN OR BLOWN LAMPS AS REQUIRED FOR EACH FIXTURE. COORDINATE.</i></p> <p><i>DN11. EC SHALL DISCONNECT AND REMOVE EXISTING LAMP. EC SHALL FURNISH AND INSTALL A NEW DIMMABLE 120V L.E.D. PAR 30 LAMP COORDINATE.</i></p>  |
| 4.              | <p>Reference sheet E0.0, Partial First Floor Demolition Plan &amp; Partial Demolition Plan: Delete "DN1 &amp; DN13" for exit signs &amp; Add general note GN1.:</p> <p><i>GN1. EC SHALL FURNISH AND INSTALL NEW EXIT SIGNS FOR ALL EXITS IN PSC 210 AUDITORIUM. FIXTURE SHALL BE DUAL LITE CV3RW. 120V INPUT. LED</i></p>   |
| 5.              | <p>Reference sheet E0.0, Partial First Floor Renovation Plan -2: Add note PN5.</p> <p><i>PN5. EC SHALL FURNISH AND INSTALL A CEILING MOUNTED DUPLEX 20A 120V RECEPTACLE IN THE REAR OF THE ROOM TO PROVIDE POWER FOR A OWNER FURNISHED HD CAMERA. COORDINATE EXACT LOCATION WITH USC PERSONNAL PRIOR TO ROUGH-IN.</i></p>   |

END OF ADDENDUM NO.2