

CEILING DEMOLITION NOTES

1. THE DEMOLITION INDICATED ON DRAWINGS D-4.1 AND D-4.2 ARE THE FIRST PHASE OF A LARGER CONSTRUCTION PROJECT. THE SCOPE OF WORK IN THIS PHASE IS LIMITED TO PRIMARILY DEMOLITION, DEBRIS REMOVAL AND ONE NEW PARTITION. A FUTURE PHASE WILL REPAIR AND UPFIT THE AREA BEING DEMOLISHED IN THIS SCOPE OF WORK.

2. THE GENERAL CONTRACTOR SHALL NOTIFY THE USC PROJECT MANAGER IF EXISTING CONDITIONS DO NOT MATCH THESE PLANS PRIOR TO CONDUCTING DEMOLITION IN THE AREA OF THE DISCREPANCY. CONTACT USC PROJECT MANAGER CHRIS MERGNER AT (803) 777-4569.

3. REFER TO DETAIL 2 D-5.1 FOR DETAIL AT WOOD CASEWORK REMOVAL DETAIL. EXISTING STEEL ANGLE SUPPORT ABOVE CEILING MAY REMAIN. WOOD NAILER ATTACHED TO STEEL ANGLES SHALL BE REMOVED.

4. EXISTING CEILING FIXTURES WHERE INDICATED TO REMAIN SHALL BE WIRED IN PLACE FOR SUSPENSION AFTER CEILING GRID IS REMOVED AS NOTED IN DEMOLITION SYMBOL NOTES.

5. INCLUDE REMOVAL OF CEILING EDGE ANGLE AT WALLS WITH REMOVAL OF CEILING GRID.-TYPICAL.

6. EXISTING DUCTS, HVAC GRILLES, LIGHTS (ONLY WHERE INDICATED), SMOKE DETECTORS AND EXIT SIGNS TO REMAIN. WIRE SUPPORT ITEMS AS REQUIRED ONCE CEILING IS REMOVED.

7.REMOVE EXISTING 2X2 LIGHTS. SALVAGE 10 FIXTURES AND PROVIDE TO OWNER. PROVIDE TEMPORARY SUPPORT TO A FEW EXISTING LIGHTS TO REMAIN FOR TEMPORARY LIGHTING WHERE NDICATED AND MAINTAIN CIRCUITS HOT. SEE SYMBOLS LEGEND AND PLAN FOR LOCATIONS. OWNER WILL WORK WITH CONTRACTOR TO SELECT BEST FIXTURES TO REMAIN BASED ON EXISTING CIRCUITING BUT THE LIGHTS TO REMAIN ACTIVE MUST BE

DEMOLITION LEGEND

EXISTING GYPSUM WALLBOARD AND METAL STUD FRAMED WALL ASSEMBLY TO BE REMOVED.

EXISTING GYPSUM WALLBOARD AND METAL STUD FRAMED WALL ASSEMBLY TO REMAIN.

EXISTING 2X2 FLORESCENT LIGHT TO BE REMOVED. EXISTING CIRCUIT TO REMAIN INCLUDING WHIP. CIRCUIT WILL BE REUSED IN FUTURE PHASE FOR NEW LIGHTING. LINE OF DUST BARRIER. BARRIER MAY BE HEAVY POLY TAPED TO FLOOR AND CEILING.


EXISTING 2X2 FLORESCENT LIGHT TO REMAIN TO PROVIDE MINIMAL LIGHTING FOR FUTURE CONSTRUCTION. SUPPORT LIGHTS WITH NEW WIRES FROM STRUCTURE ABOVE.

EXISTING UNDER-SHELF LIGHTING TO BE REMOVED. DEMOLITION SYMBOLS

- REMOVE EXISTING CEILING TILES AND SUSPENDED GRID SYSTEM INCLUDING SUPPORT WIRES. GWB SOFFITS TO REMAIN.
- REMOVE EXISTING WOOD HEADER TRIM BELOW CEILING AND REMOVE WOOD NAILER ABOVE CEILING. EXISTING STEEL SUPPORT FRAMING ABOVE CEILING MAY REMAIN.

<u>®</u>

 \bigcirc



 $\subseteq \mathcal{R}$

 \bigcirc

EILING

DE

MOLITION

PL

 $\stackrel{|\Sigma}{\sim}$

2 OF 3	SHEET	SHEET:	PROJECT TITLE: LEVEL 4 RCP DEMOLITION THOMAS COOPER LIBRARY	BUILDING: 103 REV.	DRAWING: SFL4	DATE: 02JULY12 DESCRIPTION	DRAWN BY	DSG	CHECKED	BY: ——— DRAWN BY	CAMPUS PLANNING AND CONSTRUCTION COLUMBIA, SC 29208
	IN SET:	-4.2	University of South Carolina							DSG	