

**University of South Carolina
WBS Women's Restroom Construction (SE)**

State Project No. H27-Z054
Architect's Project No. 12.130.06
Addendum No. 3

Quackenbush Architects + Planners
1217 Hampton Street
Columbia, South Carolina 29201

April 05, 2013

ADDENDUM NO.3

The following items shall take precedence over the drawings and specifications for the above named project and shall become a part of the contract documents. Where any item called for in the specifications, or indicated on the drawings, is not supplemented hereby, the original requirements shall remain in effect. Where any original item is amended, voided or superseded hereby, the provisions of such item not specifically amended, voided or superseded shall remain in effect.

ATTACHMENTS

Documents: None

SPECIFICATIONS

Item No. Description

1. Refer to Section 075419 – POLYVINYL-CHLORIDE (PVC) ROOFING

Add the following approved manufacturer to 2.3.A:

4. GAF - EverGuard

DRAWINGS

Item No. Description

1. Reference S1.0, Concrete, and add the following note:

The weight of the existing concrete double tee beam including the existing topping slab that is to be removed is estimated to be approximately 60,000 lbs.

END OF ADDENDUM NO.3