

**University of South Carolina-Minor Construction  
DLES Evidence Intake & Storage Building  
Project Number: H27-Z177  
Project Manager: Chris Mergner**

**Addendum Number One (1)**

DATE: July 24, 2014

FROM: Aimee B. Rish, Procurement Specialist

TO: All Bidders

The following items add to, modify, clarify, or otherwise alter the Drawings and/or specifications and will become a part of the Contract Documents. Where a portion of the Drawings and/or specifications is added to, modified, clarified, or otherwise altered, the portion not so affected shall remain. Bidder shall include all effects that these items may have on his proposal.

Modifications:

1. 24' wide x 51' long x 12' high pre-fab metal structure. A-frame. Vertical Roof. Additional Leg Height. 2-closed sides. Closed ends with certified 12-gauge metal roof and wall panels. Includes: (2) 10'x10' roll-up doors; (1) walk-in passage door 3'x7'; and (1) one window 30"x30" standard. Standard color to be selected by Owner. No electrical. No Plumbing. Owner to provide any permits, if required. Includes: Material, Labor, Equipment, Delivery and Installation.
2. The construction cost range is now approximately \$10,000.00-\$14,000.

**END OF ADDENDUM Number One (1)**