



A ELECTRICAL DEMOLITION PLAN - 1st FLOOR
 ED1.1 SCALE: 1/8" = 1'-0"

- ELECTRICAL DEMOLITION NOTES:**
- ED1. DISCONNECT AND REMOVE ALL LIGHT FIXTURES IN THE AREAS OF WORK BUT MAINTAIN EXISTING WIRING FOR CIRCUITING OF NEW FIXTURES. EXISTING CEILING ARE TO BE REMOVED IN THESE AREAS. DISPOSE OF LIGHT FIXTURES IN A SUITABLE MANNER.
 - ED2. FOR AREAS WITH ACOUSTICAL TILE CEILINGS, TEMPORARILY SUPPORT ALL EMERGENCY LIGHTING UNITS, EXIT SIGNS, SMOKE DETECTORS, AND HORN STROBES AT A HIGHER ELEVATION THAN THE CEILING TO ALLOW FOR CEILING REMOVAL. REINSTALL ALL OF THESE ITEMS AFTER THE NEW CEILING AND NEW LIGHT FIXTURES ARE IN PLACE AND RELOCATE AS REQUIRED FOR THE NEW LIGHTING LAYOUTS.
 - ED3. REMOVE EXISTING JUNCTION BOXES THAT NO LONGER SERVE A PURPOSE. FOR JUNCTION BOXES STILL IN USE, RAISE ABOVE THE ACOUSTICAL TILE CEILING SO THAT BOXES ARE CONCEALED BY THE NEW CEILING. JUNCTION BOXES IN GYP BOARD CEILINGS SHALL REMAIN AS IS.
- GENERAL NOTES:**
- G1. CONTRACTOR SHALL TAKE CARE TO COMPLETELY COVER ALL BOOK STACKS WITH PLASTIC WHEN WORKING IN THOSE AREAS.
 - G2. CROSSHATCHED AREAS INDICATE NO WORK TO BE DONE IN THIS AREA.

REVISION	DATE	BY
A	ISSUED FOR REVIEW	1/29/13 LCM/LJK
B	FINAL ISSUE FOR REVIEW	2/8/13 LCM/LJK

PROJECT NO.	DATE	DATE	DATE
ED1.1	1/29/13	2/8/13	

PROJECT NO.	DATE	DATE	DATE
ED1.1	1/29/13	2/8/13	

PROJECT NO.	DATE	DATE	DATE
ED1.1	1/29/13	2/8/13	