

URS

101 Research Drive Columbia, SC 29203 Phone: (803) 254-4400

Fax: (803) 771-6676

### Posted to USC Website

RE: USC Upstate Ditch Section Maintenance and Repairs RE-BID For the University of South Carolina State Project No. H34-9544-JM-E URS Project No. 46423272 - Ditch

# **ADDENDUM NO. 1 – July 2, 2014**

### TO: ALL HOLDERS OF RECORD OF CONTRACT DOCUMENTS

Acknowledge receipt of this addendum by inserting its number and date in the Bid Form. Failure to do so may subject bidder to disqualification. This addendum forms a part of the Contract Documents. It modifies them as follows:

# **GENERAL / CLARIFICATIONS**

- 1. **Bid Location/Hand Delivery/Mail Address:** Bids are due to USC (Columbia) Campus Planning and Construction, 743 Greene Street, Columbia, SC 29208, Attn: Juaquana Brookins.
- 2. **Bid Closing Date/Time:** Bids are due on 7/8/14 at 2:00 PM at the above location and will be publicly opened in Conference Room 53.
- 3. A non-mandatory pre-bid meeting was held on June 24, 2014. A list of attendees is attached.
- 4. Please ensure the following information is placed on the exterior of the bid envelope: <u>Bid for USC Upstate Ditch Section Maintenance and Repairs RE-BID, Project No. H34-9544-JM-E.</u>
- 5. Excess top soil shall remain the property of USC Upstate and shall be placed onsite as directed by the owner.
- 6. The "berms" downstream of each inlet shall be mowable berms.
- 7. USC Upstate will require the use of Grassing Schedule Rate B.

### **GENERAL QUESTIONS**

1. **Question:** Are brick-built drainage structures allowed?

**Answer:** Yard Inlet A4 (YI-A4) can be a brick-built structure, so long as it is constructed according to SCDOT standard drawings and specifications. All other structures shall be pre-cast units.

2. **Question:** Clarification: All excess dirt can stay and be stockpiled on-site in an approved area? Then unsuitables will have to be hauled off site?

**Answer:** Any encountered unsuitable material must be removed from the site.

3. **Question:** Are any asbuilts required?

**Answer:** To clarify Note 12 of the Construction Sequence on sheet 4, as-builts will be required for newly installed and modified storm drainage only.

4. **Question:** The specs mention construction schedules. Is a schedule going to be a requirement for this project?

**Answer:** At the pre-construction conference the owner would like a project schedule indicating major work components with milestones and durations and it shall be updated periodically throughout the project as conditions dictate.

5. **Question:** Is the owner or contractor responsible for testing?

**Answer:** Please reference Specification 01410 – Testing Lab Services.

6. **Question:** Please clarify the type of turf reinforcement mat / erosion control blanket to be used.

**Answer:** For all noted areas of turf reinforcement mat and/or erosion control blanket, the product shall be North American Green BioNET C125BN Double Net Coconut Blanket, installed with North American Green Bio-STAKES biodegradable blanket pins.

# **ATTACHMENTS**

1. Pre-bid sign-in attendance sheet.

**END OF ADDENDUM NO. 1** 

# University of South Carolina -Upstate

Spartanburg, South Carolina

Project Name:
Project Number:
Pre Bid Date & Time:

Pre Bid Meeting Sign In Sheets
USC Upstate Ditch Section Maintenance & Repairs

H34-9544-JM-E

June 24, 2014 @ 9:30 am

Name	Company Name	Address	Phone #	Email
RICK PUNCKE	USC UPSTATE		2025-505	Princke @ uscrpstate, edu
BRYAN THOMAS	URS		803-254-4400	BRYAN. THOUSS OURS, com
Jon Houston	Houston Grading		864-884-7703	Coll-488-498 Too Yourstand Lock-488-498
BEN COONPOD		3	55.0E5.608	807.530.5382 beconvod @
Sheile Edmondson Mactin Cont. Inc		Spaceanburg 29306 264-303-3623	864-303-3623	awaynamaetin 62@ yahoo.esm
DENO WAITE	CAPITOL COLD		949-1407	164949-1407 DENO & CAPITOL CONSTRUCTIO