

# **URS Corporation**

P.O. Box 1116

Columbia, SC 29202-1116

101 Research Drive (29203) (Shipping)

Phone: (803) 254-4400 Fax: (803) 771-6676

**USC Upstate Parking Lot Resurface & Repair** 

State Project # H34-I352 URS Project No. 46422372

# **ADDENDUM NO. 1 – MAY 11, 2012**

# TO: ALL HOLDERS OF RECORD OF CONTRACT DOCUMENTS

Acknowledge receipt of this addendum by inserting its number and date in the Bid Form. Failure to do so may subject bidder to disqualification. This addendum forms a part of the Contract Documents. It modifies them as follows:

# **GENERAL**

RE:

- 1. Sign-in attendance sheets from the non-mandatory pre-bid conference are included in this addendum.
- 2. The successful bidder will be required to provide Builders Risk Insurance covering the interest of all parties.

# **SPECIFICATIONS**

## 1. SECTION SE-310 – REQUEST FOR ADVERTISEMENT

<u>Bid Delivery Addresses, Mail Service</u> – Delete Mail Service address and replace with the following:

Attn: Fred Scott USC Upstate – Facilities Management 800 University Way Spartanburg, SC 29303

# 2. SECTION 01060 – REGULATORY REQUIREMENTS

H. <u>Inspection by Agencies</u> – Delete the paragraph in its entirety and replace with the following:

Inspection by Agencies: The representatives of the South Carolina Department of Health and Environmental Control, Spartanburg County, Environmental Protection Agency, the University of South Carolina, and USC Upstate shall have access to the work wherever it is, in preparation or in progress, and the Contractor shall provide proper facilities for such access and inspection.

# 3. SECTION 01700 - CONTRACT CLOSEOUT

- 1.5. <u>Completion by Contractor</u> Add the following to Paragraph B:
  - 8. Digital copy in .pdf format of all closeout documents.

## 4. SECTION 02260 – EROSION AND SEDIMENT CONTROL

 General – Delete Paragraph A in its entirety and replace with the following:

Exercise every reasonable precaution, throughout the life of the project, to prevent the eroding of soil and the silting of rivers, streams, lakes, reservoirs, other water impoundments, ground or roadway surfaces, or other property. Erosion control practices to be used for this project are shown on the drawings and are to conform to Spartanburg County and South Carolina Department of Health and Environmental Control regulations.

# 5. SECTION 02510 - STONE BASE COURSE

- 3.3 Rolling and Compacting Delete Paragraph E in its entirety and replace with the following:
  - E. Compact stone base course to provide not less than 98% Standard Proctor Maximum Dry Density.
- 3.5 Placing Prime Coat Delete this section in its entirety.

#### 6. SECTION 02577 – PAVEMENT MARKING AND SIGNAGE

1.1. <u>Description</u> – Delete Paragraph A in its entirety and replace with the following:

- A. Work included: Prepare and paint the asphaltic concrete and/or concrete traffic or parking surfaces as indicated in the drawings, as specified, and as needed for a complete and proper installation. This shall include the following:
  - 1. 24" wide, white stop lines at all stop signs and as otherwise indicated in the drawings.
  - 2. Parking space markings.
  - 3. Median markings.
  - 4. ADA markings.
  - 5. Turn arrow markings.
- 2.1. <u>Paint Materials</u> Delete Paragraphs A and B in their entirety and replace with the following:
  - A. Provide temporary paint materials conforming to Section 609 of the SCDOT's "Standard Specifications for Highway Construction" and latest revisions and supplements.
  - B. Provide permanent pavement marking materials conforming to Section 625 of the SCDOT's "Standard Specifications for Highway Construction" and latest revisions and supplements.
- 2.2. <u>Reflective Glass Beads</u> Delete Paragraph A in its entirety and replace with the following:
  - A. Reflective glass spheres shall be properly graded and conform to Section 625 of SCDOT's "Standard Specifications for Highway Construction" and latest revisions and supplements.

#### **DRAWINGS**

The following drawing revisions are reflected in the attached 8 ½ x 11 plan revision exhibits 1 thru 6:

- Sheet 2 Existing Conditions & Demolition Plan: Demolish approximately 10 LF of damaged concrete curb and gutter in the North Lot and the approximate 4ft x 5-ft asphalt ramp in the South Lot.
- 2. **Sheet 3 Site Improvement Plan:** Install approximately 10 LF of hand-formed concrete curb and gutter in the North Lot and approximately 4-ft x 5-ft of full depth asphalt pavement patching at the former asphalt ramp location in the South Lot.
- 3. **Sheet 4 Paving & Site Details:** Detail 3 allows for either asphalt aggregate base course or 6-in graded aggregate base course at 98% Standard Proctor. Detail 11 clarifies that a manhole ring and cover is part of the modified yard inlet.

# **GENERAL QUESTIONS**

1. **Question:** Can you please clarify the type of ADA truncated dome detectable warning mat required at new ADA ramps?

**Answer:** Provide a surface-applied mat with adhesive and mechanical fasteners.

2. **Question:** What contractor classifications are required to bid on the project?

**Answer:** A prime bidder shall be properly licensed in accordance with the South Carolina Contractors' Licensing Laws and shall be licensed to perform a minimum of 40% of the licensed work of the project. Bidders should contact SCLLR directly if they have questions regarding their licensing coverage for the work required for the project.

3. **Question:** Will tree protection fencing be required, since we are only working in the parking lot?

**Answer:** Tree protection fencing is not required. However, all existing trees are to be protected by the contractor during construction and the contractor will be responsible for any damage to any trees as a result of the work.

4. **Question:** It was mentioned in the pre bid that these lots would be closed. Is perimeter fencing to barricade off the parking lot required for this project?

**Answer:** USC Upstate will notify the campus faculty, staff, and students that the lots are closed. The contractor is responsible for barricading of the lots to prevent vehicles from entering, but perimeter fencing is not required.

5. **Question:** Can we get a copy of the cad file for take-off purposes?

**Answer:** The AutoCAD file for the project will be made available to the successful bidder upon execution of the construction contract.

6. **Question:** Is fiber reinforcing going to be required in concrete for the handicap ramps?

**Answer:** The drawings do not require the use of fiber reinforcing in the concrete sidewalks or ramps.

7. **Question:** It was mentioned in the pre bid about cracks reflecting back through the new asphalt. We are required to give a one year warranty. What is going to be required on the warranty, since these cracks will reflect back through in a short amount of time?

**Answer:** After the pre-construction conference, but before construction begins, the contractor is required to photograph each lot in detail and provide a copy of those photos to the owner and engineer for their record. This documentation will be referenced and compared to previous surface cracks in the asphalt should a warranty item arise. The owner acknowledges the exposed tree roots in the 2-3 space area in the northern lot may re-surface in the overlay shortly after construction.

# **ATTACHMENTS**

- 1. Pre-bid sign-in attendance sheets 1 thru 3.
- 2. 8 ½ x 11 plan revision exhibits 1 thru 6, referencing plan sheets 2, 3, and 4.

**END OF ADDENDUM NO. 1** 

# USC Upstate

USC Upstate Parking Lot Resurface and Repair

State Project Number: H34-I352 Non-Mandatory Pre-Bid Conference

May 3, 2012 @ 10:00 AM @ USC Upstate, 155 American Way, Spartanburg, Facilities Conf. Rm.

ATTENDEE'S NAME		COMPANY NAME & MAILING ADDRESS
Relph Smith		Biro Paring P.O. Box 27
		Grom Blog J.C. 29348
		PHONE# 864~ 472 - 3969
	EMAIL B	FAX# James Ex Paring & Wind otherm, net
SRYAN THOMAS		URS COPT.
		101 RESERRAL DR.
		Counget 6C 29203
		PHONE# 803 - 254 - 4400
	ENGAIT	FAX#
	EMAIL	BRYAN. THOMAS @ URS. COM
Scott DOMINOUEZ	_ /	ASHMORE BROS. INC
	•	1000 S. HWY 14 GREEZ SC 29651
		PHONE# 864 - 879 - 7311
		FAX# 864 - 879 - 7315
	EMAIL	SPOMINQUEZ & ASLIMORE BROS. Com
Reedfagers	_	Panagakos Asphalt Paving Inc
· ·		PO Cox 25187
		Green ville, SC 29616
		PHONE# 864-277-7860 FAX# 864-422-8749
	EMAII rea	
	EMAIL : 66	depanagakospaving.com

Make sure to include your company name on this form and list it the same as if you were submitting a bid to USC. Please print clearly.

# USC upstate

USC Upstate Parking Lot Resurface and Repair State Project Number: H34-I352

**Non-Mandatory Pre-Bid Conference** 

May 3, 2012 @ 10:00 AM @ USC Upstate, 155 American Way, Spartanburg, Facilities Conf. Rm.

ATTENDEE'S NAME		COMPANY NAME & MAILING ADDRESS
CHAIT GILMORE		BENNETT PAVING  P.O. BOX SENTISO33  SPARMINUTY SC 29304  PHONE# 9364.5743100  FAX# 5767001  TO BENNETT PAVING. COM
-	_	DENOLITE  CAPITOL CONST. & GRADING  DOY RANSGALE DE SOART. SE 2930/ PHÓNE# 864 809-810/
	EMAIL	GRADING . COM
Nich Roe	_	Venesky Asphalt Paving & Grading 111 Venesky Way Easley, Sc 29642
	EMAIL hich	PHONE# (864) 859-8594  FAX# (864) 855-1533  Ovenesky asphalt, com
	_	
		PHONE# FAX#
	<u>EMAIL</u>	

Make sure to include your company name on this form and list it the same as if you were submitting a bid to USC. Please print clearly.

# USC Upstate


USC Upstate Parking Lot Resurface and Repair State Project Number: H34-I352

**Non-Mandatory Pre-Bid Conference** 


May 3, 2012 @ 10:00 AM @ USC Upstate, 155 American Way, Spartanburg, Facilities Conf. Rm.

ATTENDEE'S NAME		COMPANY NAME & MAILING ADDRESS
FRED SCOTT	_	BOO INTERSITY WAY SPARTANBURY, SC 29303 PHONE# BLA - 503-5538 FAX#
	<b>EMAIL</b>	
RICK PUNCKE	_	VSC JPSTATE
	EMAIL	PHONE# 864-503-5500 FAX# - 5542
Kay Keisler	_	USC. Columbia. TH3 Overes Street Columbia, Sc 29208 PHONE# 803-777-5812
	<u>EMAIL</u>	FAX# 803-777-8739 KKeîslev@fmc.sc.edu
	_	
		PHONE#
		<u>FAX#</u>
	EMAIL_	

Make sure to include your company name on this form and list it the same as if you were submitting a bid to USC. Please print clearly.



CURB & GUTTER.



101 Research Drive Columbia, South Carolina 29203

Telephone (803) 254-4400 : Fax (803) 771-6676 www.URSCorp.com

# ADDENDUM #1 - SHT. C2

NORTH PARKING LOT

# SITE IMPROVEMENTS


USC UPSTATE PARKING LOT RESURFACE & REPAIR

SPARTANBURG COUNTY

SOUTH CAROLINA


DATE: MAY 10, 2012

SHEET: 1 OF 6



# **DEMOLITION KEY**

2 SAWCUT AND DEMOLISH EXISTING CONCRETE PAD, SIDEWALK, CURBING AND/OR RAMP.





101 Research Drive Columbia, South Carolina 29203

Telephone (803) 254-4400 : Fax (803) 771-6676 www.URSCorp.com

# ADDENDUM #1 - SHT. C2

SOUTH PARKING LOT


# SITE IMPROVEMENTS


USC UPSTATE PARKING LOT RESURFACE & REPAIR

SPARTANBURG COUNTY SOUTH CAROLINA

DATE: MAY 10, 2012 SHEET: 2 OF 6

N:\PROJECTS\46422372\DWG\SHEETS\46422372\_S2-EXDM.DWG 5/10/2012 1:44:







101 Research Drive Columbia, South Carolina 29203

Telephone (803) 254-4400 : Fax (803) 771-6676 www.URSCorp.com

NORTH PARKING LOT

# SITE IMPROVEMENTS


USC UPSTATE PARKING LOT RESURFACE & REPAIR

SPARTANBURG COUNTY

SOUTH CAROLINA

DATE: MAY 10, 2012

SHEET: 3 OF 6





O' 30' 60'

GRAPHIC SCALE: 1"=30'

( IN FEET )



101 Research Drive Columbia, South Carolina 29203

Telephone (803) 254-4400 : Fax (803) 771-6676 www.URSCorp.com

# ADDENDUM #1 - SHT. C3

SOUTH PARKING LOT

# SITE IMPROVEMENTS


USC UPSTATE PARKING LOT RESURFACE & REPAIR

SPARTANBURG COUNTY

SOUTH CAROLINA

DATE: MAY 10, 2012

SHEET: 4 OF 6



REFERENCE: SCDOT STD. DWG: 719-009-01 FOR TOP SLAB (COVER) & THROAT LEGS.

# MODIFIED YARD INLET





101 Research Drive Columbia, South Carolina 29203

Telephone (803) 254-4400 : Fax (803) 771-6676 www.URSCorp.com ADDENDUM #1 - SHT. C4

# SITE IMPROVEMENTS

USC UPSTATE PARKING LOT RESURFACE & REPAIR

SPARTANBURG COUNTY SOUTH CAROLINA

DATE: MAY 10, 2012 SHEET: 5 OF 6

# DEPTH ASPHALT PAVEMENT SECTION

95% STD. PROCTOR



NOTE: ASPHALT THICKNESS NOTED SHALL BE THE FINAL COMPACTED MATERIAL THICKNESS.



101 Research Drive Columbia, South Carolina 29203

Telephone (803) 254-4400 : Fax (803) 771-6676 www.URSCorp.com

ADDENDUM #1 - SHT. C4

# SITE IMPROVEMENTS

USC UPSTATE PARKING LOT RESURFACE & REPAIR

SPARTANBURG COUNTY

DATE: MAY 10, 2012

SOUTH CAROLINA SHEET: 6 OF 6