

ADDENDUM NUMBER 1

Thursday, May 15, 2014

**PROJECT: USC UPSTATE RENOVATIONS TO CAMPUS RESTROOMS AND BUILDINGS
UNIVERSITY OF SOUTH CAROLINA UPSTATE
STATE PROJECT NO. H34-I365
GMC PROJECT NO. AGRE140006**

This addendum forms a part of the Construction Documents and modifies the original Bidding Documents dated 04.16.2014 as noted below. Acknowledge receipt of this addendum in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

GENERAL:

- A1G1 Non-Mandatory Pre-Bid sign in sheet, dated May 6, 2014 is attached.
- A1G2 USC Upstate Fall Classes will begin on August 21st. The Contractor shall coordinate their efforts with the knowledge that the buildings will be occupied after this date.
- A1G3 All existing restrooms in Hodge, HPAC and Tukey that are not in this scope of work shall remain operational during the entirety of this project.
- A1G4 The Contractor shall schedule all outages with the University three (3) business days in advance.
- A1G5 Any outages that require a building wide water outage shall be done after normal business hours. Normal business hours are Monday – Friday, 8:00am – 5:00pm.

SPECIFICATIONS:

- A1S1 Section 09250, The Contractor shall assume that all wall tile will require tile backing panels specified in this section.
- A1S2 Section 09310, add the following Tile Finish Schedule information:
- Hodge- Wall Tile: 12"x12" Daltile, Continental Slate, Persian Gold CS54.
Floor Tile: 12"x12" Daltile, Continental Slate, Persian Gold CS54.
- HPAC- Wall Tile: 12"x12" Daltile, City Scape, Full Color Range.
Wall Tile Accent: Daltile, City Scape, Linear Brick Joint 9"x18" (to be banded around entire bathroom).
Floor Tile: 12"x12" Daltile, City Scape, Full Color Range.
- Tukey- Wall Tile: 6"x12" Daltile, Colour Scheme, Group 1 Colors.
Floor Tile: 12"x 12" Daltile, Colour Scheme, Group 1 Colors.
- A1S3 Section 09310, The Contractor shall assume that the stone thresholds specified in this section shall be installed at each entry to each restroom in the scope of work.

A1S4 Section 10155, Toilet Partitions, Guardian Toilet Compartments, manufactured by Alan Lewis, Inc has been approved.

DRAWINGS:

A1D1 Sheet A-101, Hodge Demolition and New Floor Plan, the Contractor shall assume that the new door shown on the men's restroom shall be a 3'-0" x 7'-0" solid core wood veneer door with a 3'-0" x 1'-6" solid core wood veneer transom panel in a welded hollow metal frame.

END OF ADDENDUM NUMBER 1

University of South Carolina - Upstate
Spartanburg, South Carolina

Project Name: USC Upstate Renovations to Campus Restrooms & Buildings
 Project Number: H34-1365
 Pre Bid Date & Time: May 6, 2014 @ 10 am

Name	Company Name	Address	Phone #	Email
Chris Wheeler	LYNNER CONSTRUCTION	531 S. DORIS DR Columbia, SC 29220	(803) 352-9948	Host @ Bellsouth.net
Scott Wilson	JONES & JONES GENERAL CONTRACTORS	201 B Pelham Doris Cir Greenville PO Box 2998 Spartanburg, SC 29304	864 284-9402	sdj@jonesjones.com
The Fine	Clayton Construction Company, INC.	55 Commerce Blvd Greenville	864 576-1901	fine@claytonconstruction.net
Paul Brubaker	MARLOW BRYNER	800 UNIVER. WAY SPARTANBURG, SC 704 KAYSATLORD SPLOT. SC.	803- 530-5386	paul.brubaker@marlowbrubaker.com
BEN CONRAD	USC	800 UNIVER. WAY SPARTANBURG, SC	803- 530-5386	benconrad@usc.edu
Drew White	CAPITOL Const.	2914 Union Avenue Spartanburg SC	949-1407	Drew @ CAPITOLCONSTRUCTION.US
Bruce Brown	Highlands Construction	800 S. WASHINGTON AVE. GREENVILLE, SC 29611	(803)580-3122	ben@hglc.com
KYLE MURPHY	CELY CONSTRUCTION		864-269-8915	KMURPHY@CELYCONSTRUCTION.COM
TRIP SCOTT	USC UPSTATE		864-5035334	TRIP@USCUPSTATE.EDU

