



USC SUMTER NORTH END MAIN PARKING LOT IMPROVEMENTS

PREPARED FOR UNIVERSITY OF SOUTH CAROLINA SUMTER, SOUTH CAROLINA










STATE PROJECT NO. H39-9518

BID DOCUMENTS

THESE DOCUMENTS ARE FOR THE PURPOSE OF SOLICITATION OF BIDS AND ARE NOT FOR USE FOR CONSTRUCTION









APRIL 9, 2015

PROJECT NO. 46423713

FILE NO. 36,395-B91




DETAIL REFERENCES




MATERIALS

	ASPHALT PAVEMENT RESURFACING
	FULL DEPTH ASPHALT PAVEMENT
Δ	CONCRETE
	EXISTING GRADE
	FINISHED GRADE
	GRANULAR FILL (ROCK/GRAVEL)
	RIP RAP

STRUCTURE



PIPING



<u>IDENTIFIER</u>	DESCRIPTION	
DB	DUCT BANK	
DRN	DRAIN	
FM	FORCEMAIN	
G	GAS	
SD	STORM DRAIN	
S	SANITARY SEWER	
W	WATER	

GENERAL NOTES

- REFERENCE IS MADE TO THE FOLLOWING: A. BOUNDARY AND TOPOGRAPHICAL SURVEY PREPARED FOR USC SUMTER BY
- URS CORPORATION, DATED MAY 20, 2013. SOILS DATA REPORT PREPARED BY S&ME, INC., DATED FEBRUARY 14, 2013 (S&ME FILE NO. 1611-13-055).
- AERIAL MAPPING TO DETERMINE BUILDING LOCATIONS. CONSTRUCTION PLANS FOR USC SUMTER PARKING LOT STORM DRAINAGE AND GRAVITY SEWER REPAIR PREPARED BY URS CORPORATION, DATED AUGUST 2, 2013, WITH REVISIONS (URS PROJECT NUMBER
- CONSTRUCTION PLANS FOR USC SUMTER PARKING LOT IMPROVEMENTS (PHASE 1) PREPARED BY URS
- CORPORATION, DATED AUGUST 29, 2014 (URS PROJECT NUMBER 46423239). 2. ALL ELEVATIONS SHOWN ARE BASED ON:
- HORIZONTAL: SOUTH CAROLINA STATE PLANE COORDINATE NAD 83 VERTICAL: NAVD 88
- VERIFY ALL FIELD CONDITIONS AND THE EXACT LOCATIONS OF ALL UNDERGROUND UTILITIES PRIOR TO BEGINNING DEMOLITION AND CONSTRUCTION. IF CONDITIONS ARE DIFFERENT FROM THAT SHOWN ON THE PLANS, STOP WORK AND NOTIFY THE ENGINEER.
- 4. ALL WORK FOR THE PROJECT SHALL CONFORM TO THE PROJECT SPECIFICATIONS FOUND IN THE PROJECT MANUAL (CONTRACT DOCUMENTS AND SPECIFICATIONS).
- PROMPTLY INFORM THE ENGINEER OF ANY ERROR OR DISCREPANCY DISCOVERED IN THESE DRAWINGS OR SPECIFICATIONS OR CONFLICT BETWEEN THE DRAWINGS OR SPECIFICATIONS.
- THESE CIVIL/SITE PLANS ARE PART OF THE OVERALL PROJECT PLAN SET. REVIEW PLANS OF ALL TRADES FOR CONSTRUCTION COORDINATION AND NOTIFY THE ENGINEER OF ANY CONFLICTS PRIOR TO BEGINNING CONSTRUCTION.

LEGEND


	<u>LEGEND</u>	
	EXISTING	<u>NEW</u>
CONTOURS (1' & 2')		174
CONTOURS (5' & 10')	 175	 175
EDGE OF PAVEMENT		
CURB & GUTTER		
CENTERLINE OF ROADWAY		
PROPERTY LINE		
RIGHT-OF-WAY		
LIMITS OF WORK		
ITEMS TO BE DEMOLISHED		
INLET PROTECTION	a79.00	
TREE		—
SILT FENCE		— — — SF — — —
WETLANDS	अपेर अपेर और और और और और और	
WETLANDS BUFFER		
FENCE LINE	— X — X — X — X —	—xx—xx—xx—
GUARD RAIL	0 0 0 0	• • •
TREE LINE		$\sim\sim\sim\sim$
SURFACE DRAINAGE FLOW		-(/)
STORM DRAINAGE	□ = = = 18" RCP □ = = = = = = = = = = = = = = = = = = =	N18SD
CATCH BASIN	СВ	■ CB
DROP INLET	□ DI	■ DI
YARD INLET	☐ YI	■ YI
JUNCTION BOX	☐ JB	● JB
SANITARY SEWER	— — 8S — — —	N8S
SEWER FORCE MAIN	8FM	N8FM
SEWER MANHOLE		
SEWER VALVE	\bowtie	×
AIR RELEASE MANHOLE	ARV	
SEWER CLEANOUT	O CO	O CO
WATER LINE	12W	N12W
FIRE HYDRANT	- <mark>◇</mark> FH	→ FH
WATER METER	, www	•
WATER VALVE	₩V	Ä
GAS LINE	2G	N2G
GAS VALVE	⊠ GV	.,
UNDERGROUND ELECTRIC	— — UE — — —	
OVERHEAD POWER	— — OHP — — —	
SIGN	- 0 -	- 0
POWER POLE	Ø PP	
GUY WIRE	>	
GUY POLE	-Ø GP	
LAMP POLE	▶ Ø LMP	
SERVICE POLE	Ø SP	
LIGHT POLE	-X-LP	
ELECTRIC MANHOLE	Œ	
ELECTRIC TRANSFORMER	TRN	
ELECTRIC BOX	☐ EBOX	
UNDERGROUND TELEPHONE	— — UT — — —	
TELEPHONE PEDESTAL	☐ TPED	STATE PROJECT NO.
TELEPHONE MANHOLE	▼ TMH	H39-9518
UNDERGRD. CABLE TV	— — CTV — — —	BID DOCUMENTS
CABLE TV PEDESTAL	☐ CTV PED	THESE DOCUMENTS ARE FOR THE
MAIL DOV	MR MR	


⊠ мв


———U-FOC———

UNDERGRD. FIBER OPTIC LINE

MAIL BOX







29203

Colum Telephon

GENERAL NOTES, LEGEND, SYMBOLS, & ABBREVIATIONS

USC SUMTER END MAIN PARKING IMPROVEMENTS THE UNIVERSITY OF SOUTH CAROLINA


DWG NAME S1-46423713<u></u>(


N.B. NO. OF PROJECT NO. 46423713


FILE NO. 36,395-B91

THESE DOCUMENTS ARE FOR THE PURPOSE OF SOLICITATION OF BIDS AND

ARE NOT FOR USE FOR CONSTRUCTION







SEDIMENT AND **EROSION CONTROL NOTES**

- ALL ELEVATIONS ARE BASED ON MEAN SEA LEVEL DATUM. CONTRACTOR SHALL, FOR ALL GRASSED AREAS, BE RESPONSIBLE FOR REPLACING ERODED SOIL AND GRASS SEED UNTIL AN APPROVED STAND OF GRASS IS ESTABLISHED.
- CONTRACTOR SHALL, BEFORE BEGINNING GRADING WORK ON SITE, STAKE SILT FENCE AND INSTALL ALL PERIMETER CONTROLS AS SHOWN ON THIS PLAN. CONTRACTOR SHALL BE AWARE OF EXISTING UTILITY LINES DURING PIPE LINE INSTALLATION. CONTRACTOR SHALL NOTIFY UTILITY COMPANIES SUCH AS THE LOCAL ELECTRIC COMPANY, AT&T, ETC. FOR LOCATION OF OTHER UTILITIES NOT SHOWN ON PLAN. CALL PALMETTO UTILITIES PROTECTION SERVICES (888-721-7877) FOR UNDERGROUND UTILITY LINES LOCATION. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES
- PROMPTLY INFORM THE ENGINEER OF ANY ERROR OR DISCREPANCIES DISCOVERED IN THE DRAWINGS OR SPECIFICATIONS OR CONFLICTS BETWEEN THE DRAWING AND SPECIFICATIONS IN ORDER FOR CORRECTIONS TO BE MADE.
- ALL WORK AND MATERIALS MUST CONFIRM WITH CITY OF SUMTER REGULATIONS AND SPECIFICATIONS, LATEST REVISIONS AT THE BEGINNING OF CONSTRUCTION.
- ALL NEWLY CONSTRUCTED SLOPES WHICH ARE STEEPER THAN 2.5 TO 1 MUST BE STABILIZED BY INSTALLATION OF EROSION CONTROL MATTING. OTHER AREAS SUCH AS CHANNEL BOTTOMS, CHANNEL SIDESLOPES, AND SLOPES NEAR SENSITIVE WETLAND AREAS MAY ALSO REQUIRE EROSION CONTROL MATTING WHERE SHOWN ON PLANS. USE NORTH AMERICAN GREEN S150 OR APPROVED EQUAL. EQUAL PRODUCTS MUST BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.
- PROVIDE A TEMPORARY STONE SPLASH PAD AT ALL FIRE HYDRANTS OR OTHER POINTS OF DISCHARGE DURING TESTING OF THE WATER DISTRIBUTION SYSTEM. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES AS MAY BE REQUIRED TO CONTROL SOIL EROSION DURING OFF SITE UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY
- INSTALLATION. 10. ALL AREAS WHICH ARE DISTURBED BY CONSTRUCTION ACTIVITIES SHALL BE SEEDED AT NO
- ADDITIONAL EXPENSE TO THE OWNER. INSTALL PERMANENT VEGETATIVE COVER AND THE LONG-TERM EROSION PROTECTION MEASURES OR STRUCTURES AS SOON AS PRACTICAL IN THE DEVELOPMENT PROCESS
- 12. PROVIDE FOR HANDLING OF THE INCREASED RUNOFF CAUSED BY CHANGED SOIL AND SURFACE CONDITIONS. USE EFFECTIVE MEANS TO CONSERVE EXISTING ON-SITE SOIL INCLUDING THE USE OF DIVERSION DITCHES, GRASSED WATERWAYS AND STORM SEWERS
- . PLACE SILT FENCE BARRIERS AT LOCATIONS SHOWN ON THE EROSION CONTROL PLAN. SILT BARRIERS SHALL BE MAINTAINED IN PLACE AND IN GOOD CONDITION UNTIL GROUND COVER IS ESTABLISHED. SILT FENCE SHALL BE CLEANED OR REPLACED WHEN SILT ACCUMULATION REACHES 1/3 THE HEIGHT OF THE FENCE. SEDIMENT SHALL BE RESPREAD ONSITE ALL DISTURBED AREAS NOT PAVED SHALL BE GRASSED OR LANDSCAPED. USE TEMPORARY PLANT COVER, MULCHING, AND/OR STRUCTURES TO CONTROL RUNOFF AND PROTECT AREA SUBJECT TO EROSION DURING CONSTRUCTION.
- . ALL SEDIMENT AND EROSION CONTROLS ARE TO BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. MAINTENANCE OF SEDIMENT TRAPPING SHALL BE PERFORMED AS NECESSARY PER THESE INSPECTIONS. DAMAGED OR INEFFECTIVE DEVICES SHALL BE REPAIRED OR REPLACED, AS NECESSARY.
- ADDITIONAL EROSION CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION TO CONTROL EROSION AND/OR OFF SITE SEDIMENTATION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING THE STABILITY OF ALL GRADED AND/OR CLEARED AREAS UNTIL PERMANENT GROUND COVER IS ESTABLISHED. ANY AREAS DAMAGED BY EROSION SHALL BE REPAIRED TO ITS ORIGINAL CONDITION AND PROTECTED FROM FURTHER EROSION AT NO ADDITIONAL
- 17. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETED AND THE SITE STABILIZED

GRASSING NOTES

GRASSING NOTES

- SEED THESE AREAS IMMEDIATELY UPON COMPLETION OF GRADING OR CONSTRUCTION AND CLEAN-UP OPERATIONS.
- A. SLOPES GREATER THAN FOUR HORIZONTAL TO ONE VERTICAL B. UTILITY RIGHTS-OF-WAY ADJACENT TO STREAM BANKS.
- AREAS READY FOR PLANTING BETWEEN AUGUST 16 AND FEBRUARY 28 SHALL BE PLANTED WITH A TEMPORARY COVER OF SCHEDULE NO. 2. AT THE ACCEPTABLE SEASONS FOR PLANTING SCHEDULE NO. 1, THE TURF SHALL BE DESTROYED BY REWORKING THE SOIL, AND SCHEDULE NO. 1 SEEDING
- ESTABLISHED AS SPECIFIED HEREIN. USE RATE A LBS. PER 1000 SQ. FT. ON SLOPES OVER 5' HORIZONTAL TO 1' VERTICAL IN HEIGHT AND USE RATE B LBS. PER 1000 SQ. FT. ON SLOPES LESS THAN 5' HORIZONTAL TO 1' VERTICAL.
- SEE GRASSING SPECIFICATIONS (SECTION 02930) FOR ADDITIONAL REQUIREMENTS.

GRASSING SCHEDULES:

GRASSING SCHEDULE NO. 1 - PLANTING DATES MARCH 1 TO AUGUST 15:

COMMON NAME OF SEED	RATE A	RATE B
RYE GRAIN	1	1
COMMON BERMUDA (HULLED)	0	1.5
SERICEA LESPEDEZA (CLAY SOILS)	1	0
WEEPING LOVE GRASS (SANDY SOILS)	1	0
CENTIPEDE	0.5	0.5
FERTILIZER	18-25	18-25

GRASSING SCHEDULE NO. 2 - PLANTING DATES AUGUST 16 - FEBRUARY 28:

COMMON NAME OF SEED	RATE A	RATE B
RYE GRAIN	0	1
COMMON BERMUDA (HULLED)	0	1.5
BROWN TOP MILLET	5	0
COMMON BERMUDA (UNHULLED)	0	2.0
FERTILIZER	18-25	18-25

14 DAY STABILIZATION **CLAUSE**

ALL DISTURBED AREAS WHICH ARE TO BE LEFT IDLE FOR A PERIOD OF 14 DAYS OR LONGER ARE TO RECEIVE TEMPORARY VEGETATION OR MULCH.

EROSION CONTROL MAINTENANCE SCHEDULE


ALL SEDIMENT AND EROSION CONTROLS ARE TO BE INSPECTED AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS. CONTRACTOR TO DOCUMENT WITH SCDHEC APPROVED INSPECTION REPORTS AND LOGGED IN THE PROJECT SWPPP.

SCDHEC STANDARD NOTES:

- 1. IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
- 2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW.
 - A. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.
 - B. WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, & EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- ALL SEDIMENT & EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.
- PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING. THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES & ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS & THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
- RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 ET. SEQ. AND SCR100000
- TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
- 9. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.
- 10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, & BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) & CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 11. A COPY OF THE SWPPP, INSPECTION RECORDS & RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 12. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, & WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS
- 13. MINIMIZE SOIL COMPACTION &, UNLESS INFEASIBLE, PRESERVE TOPSOIL 14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT & VEHICLE WASHING, WHEEL WASH WATER & OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR
- BETTER TREATMENT PRIOR TO DISCHARGE. 15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES & EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG, ETC.)
- 16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED: A. WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY
 - APPROPRIATE CONTROL;
 - B. WASTEWATER FROM WASHOUT/CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS & OTHER CONSTRUCTION MATERIALS;
 - C. FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE & EQUIPMENT OPERATION & MAINTENANCE;
- D. SOAPS OR SOLVENTS USED IN VEHICLE & EQUIPMENT WASHING 17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK & MUST BE CONDUCTED UNTIL
- FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE. 18. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE
- IMPLEMENTED AS SOON AS REASONABLY POSSIBLE. 19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.

CONSTRUCTION AND EROSION AND SEDIMENT CONTROL SEQUENCE


- 1. RECEIVE NOTIFICATION OF NPDES COVERAGE FROM SCDHEC, COORDINATE PRE-CONSTRUCTION MEETING ON-SITE, AND NOTIFY SCDHEC EQC OFFICE AT LEAST 48 HOURS IN ADVANCE OF LAND DISTURBING ACTIVITIES.
- 2. INSTALL EROSION CONTROL MEASURES AND BEGIN PERFORMING WEEKLY SCDHEC SWPPP INSPECTIONS UNTIL SITE IS PERMANENTLY STABILIZED.
- COMPLETE DEMOLITION ACTIVITIES AS SHOWN ON THE PLANS.
- STOCKPILE UNUSED MATERIALS AND STABILIZE AS NOTED ON THE PLANS. 5. INITIATE PERMANENT VEGETATIVE STABILIZATION MEASURES AS FINAL GRADE IS REACHED IN AREAS TO REMAIN UNDEVELOPED. APPLY TEMPORARY VEGETATIVE STABILIZATION MEASURES TO AREAS TO BE DEVELOPED LATER.
- 6. INSPECT AND MAINTAIN ALL STORMWATER CONTROLS AND SEDIMENT TRAPPING DEVICES UNTIL SITE IS STABILIZED
- 7. CONSTRUCT REMAINDER OF SITE IMPROVEMENTS AND INSTALL PERMANENT SITE STABILIZATION STRUCTURES.
- 8. MAINTAIN ALL TEMPORARY EROSION CONTROL MEASURES UNTIL SITE STABILIZATION IS ACHIEVED. 9. UPON COMPLETE STABILIZATION OF THE SITE, REMOVE ALL TEMPORARY EROSION CONTROL
- MEASURES AND REMOVE SEDIMENT BUILD-UP FROM THE STORMWATER SYSTEM.
- 10. SUBMIT NOTICE OF TERMINATION (NOT) TO DHEC AS APPROPRIATE (BY ENGINEER).




- 18" COMPACTED SUBGRADE <u>ASPHALT PAVEMENT</u>


DETAI

1. ASPHALT THICKNESS NOTED SHALL BE THE FINAL COMPACTED MATERIAL THICKNESS.




SPEED BUMP






ASPHALT PAVEMENT RESURFACE **DETAIL**

1. ASPHALT THICKNESS NOTED SHALL BE THE FINAL COMPACTED MATERIAL THICKNESS.



CONCRETE FLUME



BARRIER CURB AND GUTTER




ALL TRAFFIC SIGNS AND PAVEMENT MARKINGS SHALL MEET ALL REQUIREMENTS OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES

- 2. APPLY ALL ROADWAY STRIPING AND MARKINGS AS TEMPORARY PAINT IMMEDIATELY AFTER APPLICATION OF FINAL SURFACE.
- APPLY ALL ROADWAY STRIPING AND MARKINGS AS PERMANENT THERMOPLASTIC WITH REFLECTIVE GLASS SPHERES NOT LESS THAN TWO WEEKS, AND NOT GREATER THAN FOUR WEEKS AFTER APPLICATION OF FINAL
- 4. PARKING LOT STRIPING MAY BE NON-REFLECTIVE ACRYLIC PAINT 5. SEE SCDOT STANDARD DRAWING NO. 625-410-00 AND LATEST REVISIONS AND SUPPLEMENTS FOR "DIRECTIONAL ARROWS" DETAILS.

SEE SCDOT STANDARD DRAWING NO. 625-410-00 AND LATEST REVISIONS AND SUPPLEMENTS FOR "ARROWS" DETAILS.

PAVEMENT STRIPING & MARKING STANDARDS



SIGNAGE LOCATION NOTES:

- 1. ALL SIGNAGE SHALL BE INSTALLED A MINIMUM OF 6 FEET FROM EDGE OF PAVEMENT IN RURAL LOCATIONS AND A MINIMUM OF 2 FEET FROM EDGE OF
- PAVEMENT IN URBAN LOCATIONS.
- FACE ALL SIGNS IN APPROPRIATE DIRECTION. ALL TRAFFIC SIGNS AND PAVEMENT MARKINGS SHALL MEET ALL REQUIREMENTS OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
- ROAD SIGNAGE SHALL BE MOUNTED ON GALVANIZED STEEL 2"x2" SQUARE BASE POST. ADA SIGNAGE SHALL BE MOUNTED ON U-POST.
- REFER TO MUTCD REQUIREMENTS FOR MOUNTING HEIGHT.

TRAFFIC SIGN




-MINIMUM 12" OVERLAP

1. PLACE AN ADEQUATE NUMBER OF SEDIMENT TUBES AROUND AN INLET TO PROVIDE COMPLETE PROTECTION. LEAVE APPROXIMATELY 3"-6" BETWEEN THE SEDIMENT TUBE AND THE INLET OR GRATE.

2. ENDS SHOULD OVERLAP 12-18 INCHES. SIDES SHOULD BE PRESSED TIGHTLY TO CURB. 3. USE SMALL ROCK BAGS TO HOLD TUBES IN PLACE IN PAVED AREAS. USE WOOD STAKES

- TO SECURE TUBES IN PLACE IN UNPAVED AREAS. 4. INSPECT INLET PROTECTION DEVICE BEFORE AND AFTER RAIN EVENTS, AND WEEKLY THROUGHOUT THE RAINY SEASON. DURING EXTENDED RAIN EVENTS, INSPECT AT LEAST
- ONCE EVERY 24 HOURS. 5. REMOVE AND PROPERLY DISPOSE OF ACCUMULATED SILT AND DEBRIS TO ALLOW FOR
- PROPER FUNCTION OF DEVICE. 6. COMPLY WITH ALL MANUFACTURERS SPECIFICATIONS AND INSTRUCTIONS.

TEMPORARY INLET PROTECTION — SEDIMENT TUBE



STATE PROJECT NO. H39-9518

BID DOCUMENTS THESE DOCUMENTS ARE FOR THE

PURPOSE OF SOLICITATION OF BIDS AND ARE NOT FOR USE FOR CONSTRUCTION

S1-46423713<u></u>(N.B. NO. OF PROJECT NO. 46423713

SITE

29203

| FILE NO. **36,395—B91**

