

Addendum Number 2

April 9, 2015

USC Sumter - Administration Building Roof Repairs

Owner Project Number: H39-9519

Prepared by:

ADC Engineering, Inc.
1226 Yeamans Hall Road
Hanahan, South Carolina 29410

To Bidders:

This Addendum forms a part of the Contract Documents and modifies the original Procurement Documents dated February 27, 2015 as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of 1 page and the attachments listed.

Changes to Prior Addenda:

1. Addendum Number 1 was issued on April 7, 2015.

Changes to Procurement Requirements:

2. Bid date, time and location changed to April 21, 2015, 3 PM, 743 Greene Street, Conference Room 53.

Changes to Contracting Requirements:

3. Add the attached Answers / Clarifications to Questions Raised.

Changes to Specifications:

4. None.

Changes to Drawings:

5. None.

End of Addendum Number 2

Answers / Clarifications to Questions Raised

1. **Are dumpsters needed for this project?**
 - a. Contractor is responsible for removal of all construction debris from the jobsite. Contractor can either provide a dumpster at the jobsite or remove debris via trucks on a daily basis. **Contractor is not to use the standard dumpster that is in use by campus personnel.**
2. **What is the anticipated start date?**
 - a. As soon as everything is in order. The ideal window for work is May – June 2015.
3. **Are there any work hour restrictions?**
 - a. No. However, no interior access will be permitted on the weekends.
4. **Are port-o-lets required to be provided?**
 - a. Yes. Contractor is to provide their own facilities.
5. **Is existing lead removal required for the roof drains to be repaired?**
 - a. Yes. Clamping rings are to be removed, spudding existing aggregate, cut the existing membrane and lead flashings away from the drain bowls, install a new lead sheet and new modified bitumen target sheet, reinstall clamping rings and reinstall aggregate to the outside edge of the modified bitumen target sheet. Also, see Section 07 50 01, 3.07 and Sheet R201, Detail 2.
6. **Is water provided on site?**
 - a. Yes. There are hose bibs around the facility that can be used by the Contractor.