



U N I V E R S I T Y O F  
**SOUTH CAROLINA**

AMENDMENT NO.1 TO SOLICITATION

TO: ALL VENDORS  
FROM: Kevin Sanders, Procurement Manager  
SUBJECT: SOLICITATION NUMBER: **USC-IFB-2469-KS**

Furnish, deliver and install "Custom Modular, Mobile" kitchen appliances and equipment

DATE: June 20<sup>th</sup>, 2013

This Amendment **No.1** modifies the Invitation for Bids only in the manner and to the extent as stated herein.

**Addition to Section II-B of the solicitation**

SITE VISIT (JAN 2006): A site visit will be held at the following date, time and location. Your failure to attend will not relieve the Contractor from responsibility for estimating properly the difficulty and cost of successfully performing the work, or for proceeding to successfully perform the work without additional expense to the State. The State assumes no responsibility for any conclusions or interpretations made by the Contractor based on the information made available at the conference. Nor does the State assume responsibility for any understanding reached or representation made concerning conditions which can affect the work by any of its officers or agents before the execution of this contract, unless that understanding or representation is expressly stated in this contract.

Date & Start Time: **July 2<sup>nd</sup>, 2013 10:00AM**

Location: Sodexo Dining /University of South Carolina  
1313 Blossom St. McBryde C  
Columbia, SC 29208

**Site Visit in Non-Mandantory**

**Addition to Section III of the solicitation (See page 2 of amendment)**

BIDDER SHALL ACKNOWLEDGE RECEIPT OF AMENDMENT **NO. 1** IN THE SPACE PROVIDED BELOW AND RETURN IT WITH THEIR BID RESPONSE. FAILURE TO DO SO MAY SUBJECT BID TO REJECTION.

\_\_\_\_\_  
Authorized Signature

\_\_\_\_\_  
Name of Offeror

## Date

The drawings presented are taken from a larger set intended for General Construction and as such sometimes display items that are not in this contract. For instance, this contract does not include the electrical and plumbing items shown on Sheet A5.7. This sheet was included to show the millwork provider locations of electrical and plumbing items that are provided by others. These items must be field verified and accommodations must be provided in the millwork to allow installation of millwork to these items and allow extension of these utilities through the millwork.

The following items are in the contract:

**Salad Bar** referred to on A5.4 as item 28 – this item is to include in this contract the millwork indicated and the purchase and installation of cold wells and sneezeguards as indicated on the drawings. Plumbing items internal to the salad bar are the responsibility of this contract. Plumbing identified as floor drain and beyond is by others. Electrical items internal to the salad bar are the responsibility of this contract. Electrical connections at points indicated are by others. Equipment indicated is the basis of design. Any substitutions must be equal or superior to that indicated.

**Base Cabinetry** referred to on A5.4 as item 29- this item is to include in this contract the fabrication and installation of the overpanels as indicated in elevation on sheet A5.4 as well as the basic base cabinets and countertops indicated. Equipment indicated on the base cabinetry is purchased and installed by others. The drop in sink being provided is an Eagle SR10-14-5-1 – prepare the countertop accordingly. All plumbing this section of millwork is by others. All electrical for this section of millwork is by others.

**Point of sale millwork** referred to on A5.4 as item 30 – this consists of two pieces, a front counter for accommodation of two points of sale and a back display piece. There is no plumbing in either of these pieces. Electrical items internal to the millwork are the responsibility of this contract. Electrical connections at points indicated are by others. Data raceways to and from points indicated are the responsibility of this contract. Data wiring is by others.

The millwork indicated was for shop built, permanently installed millwork. This contract as previously indicated is for modular mobile millwork. The drawings are to be followed for overall sizes and design intent. The millwork provider is to adapt this design to accomplish the mobile and modular requirements previously discussed.

In all cases, the final installed product must meet or exceed the requirements of the SC DHEC regulations.