



UNIVERSITY OF
SOUTH CAROLINA

Ch
[Signature]

AMENDMENT NO. 1

TO: ALL VENDORS
FROM: Damon Hightower
SUBJECT: USC-RFQ-1528-DH - Demolition and Removal of a covered Walkway at USC-Salkehatchie (Walterboro)
Opening Date/Time: Changed and Modifications to Job
DATE: July 20, 2009

This Amendment No. 1 modifies the Request for Quotes in the manner and to the extent as stated herein.

Item One: Opening TIME: Has been extended to July 30, 2009 at 10:00 AM

Item Two: Contractors Requirement: (Change/Replace) Page 3

(4) The contractor is responsible for the removal and appropriate disposal of the entire covered walkway to include all metal I-beams, steel and wood truss work, roofing material, vertical supports, roof flashing and truss bolts, any and all tar material that is affixed to the brick veneer surface of buildings where the covered walkway is attached, and all electrical wiring and lighting fixtures.

(5) Cut all 3" vertical pole supports at the pedestrian surface level, fill with concrete, and grind smooth to prevent trip hazards. In cases where handrail systems exist, cut the 3" vertical pole supports to the top of handrail systems and weld on handrail caps.

(6) Cut all steel I-beams, roof truss supports, and bolts in a manner that allows the existing wall cavities to be re-bricked and blended to closely match existing brickwork of buildings.

(7) The contractor is responsible for providing protection materials that will prevent the damage to green space by heavy equipment (i.e.; plywood matting for tracked vehicles, etc.).

BIDDER SHALL ACKNOWLEDGE RECEIPT OF AMENDMENT NO. 1 IN THE SPACE PROVIDED BELOW AND RETURN IT **WITH THEIR QUOTE**. FAILURE TO DO SO MAY SUBJECT QUOTE TO REJECTION.

Authorized Signature

Name of Offeror

Date