USCA Pedestrian Bridge

Project No.: H29-9545-PG In Aiken County, SC



Prepared For

University of South Carolina Aiken

by:

Chao & Associates, Inc.

Consulting Engineers

C & A #: 391402F-15

August 10, 2015

DRAWING INDEX

CIVIL DRAWINGS

C1.0 - EXISTING CONDITIONS

C2.0 - OVERALL BRIDGE PLAN AND PROFILE

C3.0 - LAYOUT PLAN - NORTH RAMP

C3.1 - GRADING DETAIL - NORTH RAMP

C3.2 - SEDIMENT AND EROSION CONTROL - NORTH RAMP

C3.3 - CENTERLINE STAIR SECTION - NORTH RAMP

C3.4 - RAMP SECTIONS - NORTH RAMP

C4.0 - LAYOUT PLAN - SOUTH RAMP

C4.1 - GRADING DETAIL - SOUTH RAMP

C4.2 - SEDIMENT AND EROSION CONTROL - SOUTH RAMP

C5.0 - MSE WALL ELEVATIONS

C5.1 - MSE RIB WALL AND DETAILS

C6.0 - MISCELLANEOUS DETAILS

C6.1 - MISCELLANEOUS DETAILS

C7.0 - PEDESTRIAN SIGNAGE PLAN

C7.1 - TRAFFIC CONTROL/DETOUR PLAN

STRUCTURAL DRAWINGS

S0.0 - GENERAL NOTES & DETAILS

S1.0 - BRIDGE PLAN AND ELEVATION

S2.0 - ABUTMENT SECTIONS & DETAILS

S3.0 - ABUTMENT SECTIONS & DETAILS

S4.0 - MISCELLANEOUS DETAILS

ARCHITECTURAL DRAWINGS

A1.0 - PEDESTRIAN BRIDGE RAILINGS AND FENCING

ELECTRICAL DRAWINGS

E001- ELECTRICAL SYMBOLS, SCHEDULES AND DETAILS

E002- ELECTRICAL DETAILS

E101- ELECTRICAL SITE PLAN

E102- ELECTRICAL SITE PLAN

OWNER

UNIVERSITY OF SOUTH CAROLINA AIKEN FACILITIES MANAGEMENT 471 UNIVERSITY PARKWAY AIKEN, SC 29801

PROJECT MANAGER

CIVIL, SURVEYING, AND STRUCTURAL ENGINEER:

CHAO & ASSOCIATES, INC

7 CLUSTERS COURT

COLUMBIA, SC 29210

TEL: 803-772-8420

ARCHITECT:

McCREARY/SNOW ARCHITECTS, PA

PO BOX 11143

COLUMBIA, SC 29211

TEL: 803-771-6267

ELECTRICAL ENGINEER:

GWA, INC

168 LAURELHURST AVENUE

COLUMBIA, SC 29210

TEL: 803-252-6919

GEOTECHNICAL ENGINEER:

GEOSTELLAR ENGINEERING, LLC


1077 RODNEY DRIVE


BATON ROUGE, LA 70808

TEL: 803-997-0554










ASSOCIATES No. C00357

dge 5-P(arol conditions lestrian Bric H29-9545

 $\mathbf{H} \supset \mathbf{H} \supset$


Sheet Number August 10, 2015 Date



Sheet Number August 10, 2015 Date

CHAO & ASSOCIATES

THESE DOCUMENTS AND THE INFORMATION CONTAINED HEREIN ARE THE PROPERTY OF CHAO & ASSOCIATES, INC. AND MAY NOT BE USED FOR ANY PURPOSE WITHOUT THE WRITTEN PERMISSION OF CHAO & ASSOCIATES, INC.




CHAO & ASSOCIATES No. C00357

strian Bridge H29-9545-PC South Caroli y, SC

Sheet Number

Date




Sheet Number
August 10, 2015

CHAO & ASSOCIATES

THESE DOCUMENTS AND THE INFORMATION CONTAINED HEREIN ARE THE PROPERTY OF CHAO & ASSOCIATES, INC. AND MAY NOT BE USED FOR ANY PURPOSE WITHOUT THE WRITTEN PERMISSION OF CHAO & ASSOCIATES, INC.


SOUTH CAROLINA 811 (SC811) WWW.SC811.COM ALL UTILITIES MAY NOT BE A MEMBER OF SC811 12. Aiken County shall not maintain Stormwater Detention or Retention Ponds. The Property Owner shall maintain all Stormwater Detention Facilities shown



∞

Sheet Number August 10, 2015

WWW.SC811.COM ALL UTILITIES MAY NOT BE A MEMBER OF SC811




AND ASSOCIATES INC.
CONSULTING ENGINEERS
& LAND SURVEYORS

vil - Structural - Survey
7 Clusters Court
Columbia, SC 29210
/oice: (803) 772-8420

Civil - Structur
7 Clusters
Columbia, S
Voice: (803)

PROFESS ON A STATE OF THE PROPERTY OF THE PROP




ilon - North Ramporate Manager Services and Park Manager Services and

Centerline Stair Section - N USCA Pedestrian Bridge Project No.: H29-9545-PG University of South Carolina Aiken County, SC

awn: TKS Checked: LEE
evised:
p. 301402E.C.dwa

C3.3
Sheet Number
August 10, 2015
Date








Ramp Sections - North Ram USCA Pedestrian Bridge Project No.: H29-9545-PG University of South Carolina Aiken County, SC

Sheet Number August 10, 2015 Date






CHAO & ASSOCIATES

dge 5-P(

Sheet Number August 10, 2015

Date


REFER TO EACH UTILITY'S APPROVED ENCROACHMENT PERMIT FOR ADDITIONAL RESTRICTIONS AND REQUIREMENTS





Civil - Structural - Survey
7 Clusters Court
Columbia, SC 29210
Voice: (803) 772-8420







Grading Detail - South RampUSCA Pedestrian Bridge
Project No.: H29-9545-PG
University of South Carolina

Checked: LEE


Drawn: TKS Che

C4.1
Sheet Number
August 10, 2015
Date





Sheet Number August 10, 2015





જ ≅

CHAO & ASSOCIATES No. C00357

MSE Wall Elevations
USCA Pedestrian Bridge
Project No.: H29-9545-PG
University of South Carolina
Aiken County, SC

Sheet Number August 10, 2015 Typical Section N.T.S.

- (1) Construct 1'-0" x 1'-0" aggregate drain using 6" dia. perforated pipe. Provide aggregate, other than Macadam, that meets the requirements for stone backfill in Supplemental Technical Specification SC-M-713. Wrap geotextile for drainage filtration (see Supplemental Technical Specification SC-M-713) completely around aggregate drain and overlap 1'-0". Design MSE wall drainage system to drain the aggregate drain.
- 2 Extend top two layers of soil reinforcement 5 feet beyond the end of the lower layers of soil reinforcement.
- 3 Slope 2% min. Provide unperforated pipe connecting aggregate drain to drain at wall facing.
- 4) Maximum vertical spacing of soil reinforcement is 36".
- (5) Provide rodent screen manufactured from T304 stainless steel or galvanized steel with a minimum wire diameter of 0.050". Provide rodent screen with minimum of 2 openings per inch and a maximum of 4 openings per inch.
- 6 Limit step height for panel facing to 1/2 of the full panel height. Separate adjacent steps in leveling pad by a minimum of 2 full panels.
- 7 Angle to be determined by the Contractor based on site conditions and the method of construction used. Excavation and/or shoring of retained backfill to permit construction of the MSE wall is considered incidental to the MSE wall construction and is not paid for as a separate item.
- 8 Provide aggregate, other than Macadam, that meets the requirements for stone backfill in the Supplemental Technical Specification SC-M-713.

Added notes

MSE Wall Notes: This drawing is conceptual.

Contractor to provide design and construction in accordance with SCDOT standard drawings 713-01 and the SCDOT Supplemental Technical Specification for Mechanically Stabilized Earth (MSE) Walls. Design must be signed and sealed by a South Carolina Registered Engineer.

Design Methodology: LRFD Design

— See Detail 6 below for formliner

dimensions


Design Life:

Permanent structures = 100 years. Temporary structures in service for 5 years or longer = 100 years. Temporary structures in service for less than 5 year = 5 years.


Associates, I - Structural - Survey

જ :≣

Chao



Sheet Number August 10, 2015 Date



N.T.S.

Section C5.1 Outside of Detail 6 N.T.S.

<u>∕</u>9 Clarification

3 DAYS BEFORE DIGGING IN SOUTH CAROLINA **CALL 811** SOUTH CAROLINA 811 (SC811) WWW.SC811.COM ALL UTILITIES MAY NOT BE A MEMBER OF SC811 Front face of wall

- 2. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than fourteen (14) days after work has ceased, except as stated below.
 - > Where stabilization by the 14th day is precluded by snow cover or frozen ground conditions
 - stabilization measures must be initiated as soon as practicable.
 - > Where construction activity on a portion of the Site is temporarily ceased, and earth-disturbing activities will be resumed within 14 days, temporary stabilization measures do not have to be initiated on that portion of the Site.
- 3. All sediment and erosion control devices shall be inspected every seven (7) days. If site inspections identify BMPs that are damaged or are not operating effectively, maintenance must be performed as soon as practical or as reasonably possible and before the next storm event whenever practicable.
- 4. Provide silt fence and/or other control devices, as may be required, to control soil erosion during utility construction. All disturbed areas shall be cleaned, graded, and stabilized with grassing immediately after the utility installation. Fill, cover, and temporary seeding at the end of each day are recommended. If water is encountered while trenching, the water should be filtered to remove any sediments before being pumped back into any waters of the State.
- 5. All erosion control devices shall be properly maintained during all phases of construction until the completion of all construction activities and all disturbed areas have been stabilized. Additional control devices may be required during construction in order to control erosion and/or offsite sedimentation. All temporary control devices shall be removed once construction is complete and the site is stabilized.
- 6. The contractor must take necessary action to minimize the tracking of mud onto paved roadway(s) from construction areas and the generation of dust. The contractor shall daily remove mud/soil from pavement, as may be required.
- 7. Residential subdivisions require erosion control features for infrastructure as well as for individual lot construction. Individual property owners shall follow these plans during construction or obtain approval of an individual plan in accordance with S.C Reg. 72-300 et seq. and SCR100000.
- 8. Temporary diversion berms and/or ditches will be provided as needed during construction to protect work areas from upslope runoff and/or to divert sediment-laden water to appropriate traps or stable outlets.
- 9. All waters of the State (WoS), including wetlands, are to be flagged or otherwise clearly marked in the field. A double row of silt fence is to be installed in all areas where a 50-foot buffer can't be maintained between the disturbed area and all WoS. A 10-foot buffer should be maintained between the last row of silt fence and all WoS.
- 10. Litter, construction debris, oils, fuels, and building products with significant potential for impact (such as stockpiles of freshly treated lumber) and construction chemicals that could be exposed to storm water must be prevented from becoming a pollutant source in storm water discharges.

2 Pounds Annual Rye Grass

1.5 Pounds Unhulled Bermuda

25 Pounds 10-10-10 Fertilizer

0.5 Pound Hulled Bermuda

Seeding Schedule:

Actual types and application rates may vary depending on soil type. Contractor should consult with the local conservation district office for specific recommendations.

The following rates are per 1000 S.F. SEPT. 1 - APR. 30

MAY 1. - AUG. 31 1 Pound Browntopmillet 2 Pounds Hulled Bermuda 25 Pounds10-10-10 Fertilizer

75 Pounds Limestone

1 Pound Hulled Bermuda *2 Pounds Bahia Grass 25 Pounds 10-10-10 Fertilizer 75 Pounds Limestone

Or **DEEP SANDY SOILS** 2 Pounds Browntopmillet *3 Pounds Bahia Grass 25 Pounds 10-10-10 Fertilizer

75 Pounds Limestone Or 2 Pounds Annual Rve Grass 1 Pound Browntopmillet 0.5 Pound Hulled Bermuda 1 Pound Unhulled Bermuda *2 Pounds Bahia Grass 25 Pounds 10-10-10 Fertilizer 75 Pounds Limestone 1 Pound Annual Rye Grass

**3 Pounds Fescue Grass 25 Pounds 10-10-10 Fertilizer 75 Pounds Limestone 75 Pounds Limestone DEEP SANDY SOILS 1 Pound Unhulled Bermuda


2 Pounds Rye Grass or 2 lbs Grain Rye *2 Pounds Bahai Grass 25 Pounds 10-10-10 Fertilizer 75 Pounds Limestone

* Bahia grass is a good erosion control grass; however, it produces many seed heads which scatter to other areas. Bahia Grass is hard to mow, but it does not require the care that many other grasses require. Around office buildings and within subdivisions, use 4 to 6 ounces of Centipede Grass on lieu of Bahia Grass or in combination with Bermuda Grass.


** For soils with clay subsoil. Do not plant in sandy soils.


- On all vegetated swales or ditches with side slopes (cut or fill) steeper than 2:1, add 4 to 6 ounces per 1,000 square feet of Weeping Love Grass Seed to any of the above mixtures.

- Swale and ditch bottoms should be double seeded.
- All slopes steeper than 2:1 shall be hydroseeded.
- Growth of Rye Grass in the early spring must be supressed to prevent Rye from choking out perement grass such as Bermuda, Bahia or Fescue.



1. SET POST AT 6' SPACING AND EXCAVATE A 4" X 4" TRENCH UPSLOPE OF THE LINE OF POSTS.





3. ATTACH THE FILTER FABRIC TO WIRES FABRIC AND EXTEND IT INTO THE TRENCH.


4. BACKFILL AND COMPACT THE EXCAVATED SOIL.

MAINTENANCE NOTES:

1. INSPECT SILT FENCE WEEKLY AND AFTER EACH RAINFALL. 2. REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES 1/2 THE HEIGHT OF THE SILT FENCE


3. REPAIR OR REPLACE FABRIC WHEN TORN OR WEATHERED.


SILT FENCE CONSTRUCTION NOT TO SCALE



GRAVEL MAT SHALL BE INSTALLED AT ALL CONSTRUCTION TRAFFIC ACCESS POINTS

TEMPORARY GRAVEL CONSTRUCTION ENTRANCE/EXIT NOT TO SCALE





NOTE:

MANUFACTUREE'S INSTALLATION:


- 1. FORMWORK MATERIALS ARE PERMITTED TO BE OF WOOD OR STEEL AND SHALL BE THE FULL DEPTH OF THE PAVEMENT.
- 2. PERVIOUS CONCRETE SHALL BE MANUFACTURED AND DELIVERED IN
- ACCORDANCE WITH ASTM C 94. 3. THE BASE SHALL BE IN A DAMP OR SEMI-FLOODED CONDITION AT TIME OF
- PLACEMENT. 4. PLACING, FINISHING, AND TOOLED JOINTING MUST BE COMPLETED WITHIN 20 MINUTES FROM THE TIME THE PERVIOUS CONCRETE IS DISCHARGED FROM THE TRUCK.
- 5. THE PERVIOUS CONCRETE PAVEMENT SHALL BE COMPACTED TO THE REQUIRED CROSS-SECTION.
- 6. CURING PROCEDURES SHALL BEGIN IMMEDIATELY BUT NO LATER THAN 20 MINUTES FROM THE TIME THE PERVIOUS CONCRETE IS DISCHARGED FROM THE TRUCK.

MAINTENANCE SPECIFICATIONS

- 1. THE PAVEMENT SURFACE SHOULD BE VACUUMED BIANNUALLY WITH A
- COMMERCIAL CLEANING UNIT.
- 2. PLANTED AREAS ADJACENT TO POROUS PAVEMENT SHALL BE WELL MAINTAINED TO PREVENT SOIL WASHOUT ONTO THE PAVEMENT AND SHALL BE INSPECTED ON A SEMI-ANNUAL BASIS.
- 3. ALL TRASH AND OTHER LITTER THAT IS OBSERVED DURING THESE INSPECTIONS SHOULD BE REMOVED.
- 4. ALL CONSTRUCTION OR HAZARDOUS MATERIALS CARRIERS SHOULD BE PROHIBITED FROM ENTERING A POROUS PAVEMENT LOT IN ORDER TO PREVENT FROM TRACKING OR SPILLING DIRT ONTO THE PAVEMENT.

TYPICAL PERVIOUS CONCRETE PAVEMENT SECTION NOT TO SCALE

SEDIMENT LOGS SHALL BE USED IN LIEU OF SILT FENCE IN VICINITY OF EXISTING GAS MAINS. STAKES TO KEEP LOGS IN PLACE SHALL BE WOOD AND DRIVEN NO DEEPER THAN 12". NO STAKE SHALL BE DRIVEN DIRECTLY OVER CENTERLINE OF PIPELINE.



TOP VIEW


- SEDIMENT TUBE MAY BE TEMPORARILY MOVED DURING CONSTRUCTION AS
- DIAMETER OF SEDIMENT TUBE SHALL BE 20 INCHES FOR DITCH APPLICATIONS.
- SEDIMENT TUBES SHALL BE TIED TOGETHER WITH PLASTIC TIES.


SEDIMENT LOG DETAIL NOT TO SCALE

> 3 DAYS BEFORE DIGGING IN SOUTH CAROLINA **CALL 811** SOUTH CAROLINA 811 (SC811) WWW.SC811.COM ALL UTILITIES MAY NOT BE A MEMBER OF SC811




∞






ous Details strian Bridge H29-9545-PC South Caroli

Sheet Number August 10, 2015 Date





TYPICAL CONCRETE SIDEWALK SECTION NOT TO SCALE

GENERAL NOTE: CONCRETE TESTING WILL BE PERFORMED BY USC AIKEN 3rd PARTY CONTRACTOR

CHAO & ASSOCIATES No. C00357


∞





ous Details estrian Bridge H29-9545-PC f South Caroli

Sheet Number August 10, 2015


Date








Sheet Number August 10, 2015 Date







Detour Detour Detour Bridge -9545-PC Ith Caroli

Sheet Number August 10, 2015

PAYMENT

This project is a lump sum bid including the installation of the piles. Bidder shall include all anticipated costs in his/her bid.

COORDINATION OF PLANS, SPECIFICATIONS, AND SPECIAL PROVISIONS

Generally, in case of discrepancy, this General Notes sheet governs over the Standard Specifications but the remainder of the plans govern over notes on this sheet and Special Provisions govern over all. See Subsection 105.4 of the Standard Specifications.

REINFORCING STEEL

Fabricate reinforcing bars in accordance with the current C.R.S.I. Manual of Standard Practice except for ties, stirrups, and welded hoops.

Provide all ties and stirrups with 135° hooks that have extensions no less than the larger of ten bar diameters or six inches. This 135° hook requirement does not apply to stirrups extending from prestressed concrete beams.

The fabrication tolerance for out-to-out dimension of welded hoop diameter is ±1/2 inch.

Do not use lap splices in column and shaft reinforcing steel.

CONCRETE

Provide the class of concrete as noted in the contract documents. For cast-in-place structural elements, use Class 4000 concrete where the class of concrete is not specified in the contract documents.

When holes are cast in beams to accommodate falsework, fill the holes with a non-shrink structural grout suitable for overhead repairs after falsework is removed.

Chamfer all exposed edges 3/4" unless otherwise noted.

The minimum acceptable concrete cover for reinforcing steel is 1/2" less than the plan dimensions when required by reinforcing bar fabrication tolerances.

DRIVEN PILE FOUNDATIONS

Where piles occur in fill, place fill before driving piles.

STRUCTURAL AND MISCELLANEOUS STEEL

All structural and miscellaneous steel shall conform to the Thirteenth Edition of the AISC "Specification for the Design, Fabrication & Erection of Structural steel for Buildings" and all its supplements, and to the AISC "Code of Standard Practice for Steel Buildings and Bridges".

All structural steel shall conform to ASTM A-36, FY=36,000 PSI unless otherwise

Steel W-Shapes shall conform to ASTM A992, FY=50,000 PSI. All rectangular or square steel HSS-Shapes shall conform to ASTM A500 grade B, FY=46,000 PSI. All round steel HSS-Shapes shall conform to ATSM A500 grade B, FY=42,000 PSI.

All steel pipes shall conform to A-53 grade B, FY=35,000 PSI. All welded connections shall be done with E70XX electrodes with 1/4" min. material, unless otherwise noted.

All bolts shall be A325 bolts, unless otherwise noted. Fabrication and assembly of bolted connections shall comply with applicable sections of AISC "Specification for Structural Joints using ASTM A325 or A490

No openings in beams shall be permitted without the written permission of the engineer.

The use of a gas-cutting torch in the field for cutting holes or for correcting fabrication errors will not be permitted on structural framing members except w/ the written approval of the Engineer for each specification.

An independent inspection agency shall be employed by the contractor and approved by the engineer to inspect the structural steel in the field and verify that it conforms to the requirements of the contract documents.

All anchor bolts shall be ASTM F1554 Grade 36, unless noted otherwise.

All steel plates in moment connection shall be ASTM A572 Grade 50. All bolts in moment connection shall be fully tensioned A325-X bearing bolts.

All moment connected members shall be fabricated, erected, inspected and approved in compliance with FEMA-353, "Recommended Specifications and Quality Assurance Guidelines for Steel Moment Frame Construction for Seismic Applications."

Generally, holes for 3/4" dia. bolts shall be 13/16" dia. However, oversize holes, 3/16" larger than bolt dia., may be used in diaphragms and/or crossframes and their connection plates provided hardened washers are installed over oversize holes in the outer ply of the material gripped. Hardened washers are required under DTIs on oversized holes. In every case install a hardened washer under the element turned for each bolt of a bolted connection. Indicate on the Shop Plans which holes are to be oversize and where hardened washers are required. No additional payment is made for the costs associated with the use of oversize holes and furnishing additional hardened washers as necessary.

PAINT FOR STRUCTURAL STEEL

Paint System shall be in accordance with 710.2.7.2 Paint System NS2. And the contractor shall submit finish coat color to the owner for approval before proceeding. Ensure that the intermediate coat of Acrylic paint is of a different color than the finish coat of Acrylic paint.

Surface preparation shall be in accordance with 710.4.1.1.1 Surface Preparation.

See SECTION 710 "PAINT FOR STRUCTURAL STEEL" for all other requirements


BEARING AND ANCHOR BOLT ASSEMBLIES

Galvanize bearing and anchor bolt assemblies in accordance with AASHTO M 111, AASHTO M 232, or ASTM F 2329 as applicable.

After the required field welding of galvanized bearing assemblies, field repair the weld areas and/or damaged areas of the galvanized coating in accordance with

ORIENTATION IN RELATION TO STATIONING

Left and right sides, where referred to in these plans, are in relation to direction of stationing.



Before making subsequent pour, wait either a minimum of 96 hours after placement of the initial pour or until the initial pour concrete has attained a minimum of 75% of the specified 28-day compressive strength as verified by testing extra cylinders.

Construction Joint Detail

SPECIFICATIONS

AASHTO 2010 LRFD Bridge Design Specifications, 5th Edition, with Interim Revisions through 2010.

AASHTO LRFD Guide Specifications for the Design of Pedestrian Bridges

ANSI/AASHTO/AWS D1.5 Bridge Welding Code (Latest Edition) with additions and revisions as stated in the Standard Specifications.

DESIGN DATA

1: Dead Loads: The weight of all materials of construction

2: Uniform live loads: Pedestrian: 90 psf 3: Truck Load: H-5

Seismic design is in accordance with the 2008 SCDOT "Seismic Design Specifications for Highway Bridges", Version 2.0 with the following

Seismic Design Category: B Analysis method: No detailed analysis

Operational Classification: II Site Class: D

Design Acceleration Coefficients:

PGA (FFE): 0.15g Sds (FFE): 0.26g Sd1 (FFE): 0.13g PGA (SEE): 0.33g

Sds

(SEE): 0.60g (SEE): 0.33g Sd1

Values determined from the Three-Point Method


Where notes specify "Department", this refers to the project owner being the University of South Carolina Aiken.

Where notes specify "RCE", this refers to the project Engineer being Chao & Associates, Inc.



≪ ≕








Details Bridge 3ridge 29-95

Sheet Number August 10, 2015

Date



∞ర




Bridge Plan and Elevatio USCA Pedestrian Bridge State Project No. H29.954 University of South Carolir Aiken County, SC

Sheet Number August 10, 2015

Date

Sheet Number August 10, 2015 Date



- Finished grade not

shown, see Civil

EL. 409.74

─ Detail S4.0

@ beg. and end of bridge

Abutment wall

Do not backfill to full height around new structures that causes unbalanced earth pressure until the Abutment has cured for at least 14 days. Place and compact fill around Abutment Wall in accordance with Section 205 of SCDOT Standard Specifications and the Geotechnical Report.

Do not erect the pre-manufactured bridge superstructure until the abutment has cured for at least 14 days or has attained at least 75% percent of the specified 28-day compressive strength as verified by testing extra cylinders.

Geotechnical Notes

The installation of the driven piles shall be conducted in accordance with Section 7II Driven Pile Foundations section of the SCDOT Standard Specifications for Highway Construction, 2007 edition.

Method of controlling Installation of piles and verifying their capacity: Capacity will be verified by Pile Driving Analyzer (PDA) and CAPWAP analysis on Index piles. A pile Installation chart developed from the analysis will be used to verify the capacity of production piles.

The following parameters should be used for performing drivabillity analysis for the

Pile Bearing (one pile)					
	Abutments				
Factored Design Load	100 tons				
Geotechnical Resistance Factor	0.6500				
Nominal Resistance	154 tons				
Est. Loss Due to Scour	0 tons				
Est. Loss Due to Downdrag	0 tons ⁽¹⁾				
Required Driving Resistance	154 tons				
Estimated Pile Tip Elevation (ft, MSL)	340.0 ft				
Minimum Pile Tip Elevation for Lateral Stability (ft, MSL)	363.0 ft ⁽²⁾				
(1) Consolidation downdrag (2) Minimum that	at must be achieved				

Perform pile driving analyzer (PDA) testing on the index piles. Index piles should be lengthened an additional 5 feet in order to accommodate the PDA testing. Drive index pile to grade or practical refusal, whichever occurs first. If a CAPWAP analysis determines that capacity has not been achieved, restrike the index pile. Perform PDA testing during the restrike. Contact the bridge construction office to determine the time between initial driving and restrike.

Each pile is to be installed in one continuous operation. Include details of any anticipated temporary driving discontinuities including anticipated time intervals during the pile installation plan.


A pile hammer having the rated energy indicated is considered suitable for driven pile installation. However final hammer acceptance is based on a wave equation analysis that accurately reflects the contractor's proposed driving

This project is a lump sum bid including the installation of the piles. Bidder shall include all anticipated costs in his/her bid.


Drivabillity Analysis					
	End Bents				
Pile Type	HP 14 x 73 Steel Pile				
Skin Quake	0.10				
Toe Quake	0.10				
Skin Damping	0.05				
Toe Damping	0.15				
% Skin Friction	N/A				
% End Bearing	N/A				
Distribution Shape No.	Variable Resistance Distribution (1)				
Pile Penetration	100%				
Hammer Rated Energy Range	20 to 40 ft-kips (3)				

1. Variable Unit Skin Distribution: at 5 feet depth = 0; at 27 feet depth = 1.9 ksf; and at 40 feet depth = 2.4 ksf. Variable Unit toe Resistance: at 5 feet depth = 0; at 23 feet depth = 22.0 ksf; at 40 feet depth = 22.0 ksf.

2. Hammer rated energy is based on GRLWEAP maximum rated energy database for diesel hammers



G Bridge & Abutment



- Begin Bridge

Sta. 2+96.42

- EL. = 409.74

– 5'-10 1/2" –

Handrail not shown, see

right side of Abutment 1, and

see Vent Hole Detail on S4.0

left side of Abutment 2

Arch. for details

Abutment slab, -

Vent hole

elevation varies

Prefabricated Bridge


not shown

Abutment slab -

Guard rail not shown

for clairty, see Arch.


EL. 409.68 —



Abutment 1 shown, Abutment 2 similar

Scale: 3/8" = 1'-0"

Scale: 3/8" = 1'-0"






CHAO & ASSOCIATES No. C00357


etails t Sections & Dedestrian Bridge ect No. H29-95 of South Caroli

Sheet Number August 10, 2015 Date






≪ ై Chao



Miscellaneous Details
USCA Pedestrian Bridge
State Project No. H29-954
University of South Carolir
Aiken County, SC

August 10, 2015 Date



Fencing

Pedestrian Bridge - Railings & USCA Pedestrian Bridge State Project No. H29-9545-PG University of South Carolina Aiken County, SC

Sheet Number 8/28/2015

Date

/-MAX. 4" GAP TO CHAIN LINK

• •

- FEEDER

UTILITY

• SERVICE

SERVICE

DIMENSIONS

1" CHAMFER ALL AROUND.

ANCHOR BOLTS AS-RECOMMENDED BY POLE

10 INCHES.

MANUFACTURER. BOLTS SHALL NOT BE SHORTER THAN "B" DIMENSION LESS!

#6 BARE COPPER GRD.

POLE & ANCHOR BOLTS.

3/4" X 10' COPPERCLAD STEEL GROUND ROD. DRIVE 11' DEEP.-

REINFORCING STEEL
#3 TIES AT 12" O.C. MAX. #6 BARS EACH CORNER.—

WIRE: BOND TO ROD,


24 54

DISCONNECT

DUPLEX

RECEPTACLE

BRANCH CIRCUIT



GROUNDING OF METER POINT Copyright © 1999 Guy White & Associates, In NO SCALE

NOT TO SCALE Copyright © 1999 Guy White & Associates, Inc.

12'0"±||12'0"±||------3/4" X 10' DRIVEN GROUND RODS

THE FOLLOWING STANDARD ABBREVIATIONS ARE USED IN THESE PLANS AND SPECIFICATIONS. CONTRACTOR IS CAUTIONED THAT ALL ABBREVIATIONS LISTED MAY NOT BE USED; CONSULT PLANS AND SPECIFICATIONS FOR ABBREVIATIONS APPLICABLE TO THIS PROJECT.

ABOVE FINISHED FLOOR B.F.F. BELOW FINISHED FLOOR A.F.G. ABOVE FINISHED GRADE BELOW FINISHED GRADE B.F.G. UNLESS NOTED OTHERWISE U.N.O. CKT. CIRCUIT CONDUIT E.C. EMPTY CONDUIT

FLX. FLEXIBLE CONDUIT WEATHERPROOF FLEXIBLE CONDUIT

BRANCH CIRCUIT WIRING -

HASHMARK CODE

pyright @ 1999 Guy White & Associates, NO SCALE

BRANCH CIRCUITS SHOWN ON THESE DRAWINGS MAY INCLUDE HASHMARKS WHICH INDICATE THE NUMBER OF WIRES TO BE PROVIDED IN A CONDUIT RUN BETWEEN OUTLETS OR JUNCTION BOXES. WIRE SIZES SHALL BE AS TABULATED IN PANELBOARD SCHEDULES UNLESS OTHERWISE INDICATED ON PLAN. SEE SYMBOL SCHEDULE FOR CONDUIT ROUTING NOTATION. HASHMARK CODE IS AS FOLLOWS:

EACH PHASE AND NEUTRAL WIRE IN A CONDUIT RUN IS REPRESENTED BY A HASHMARK. FOR EXAMPLE -

TWO WIRES (NO HASHMARKS) ——/// ► THREE WIRES (3 HASHMARKS) — ///// ➤ FIVE WIRES (5 HASHMARKS) . . . AND SO FORTH.

NOTE: GROUND WIRES ARE NOT GENERALLY SHOWN. EXAMINE SPECIFICATIONS AND GENERAL NOTES TO DETERMINE REQUIREMENTS FOR GROUND WIRES AND WHERE SPECIFIED, PROVIDE IN ADDITION TO THE NUMBER OF WIRES INDICATED BY HASHMARK CODE.

NOTE: CONTRACTOR IS CAUTIONED THAT MULTIWIRE (LINE-TO-NEUTRAL) BRANCH CIRCUITS DO NOT INDICATE ALL REQUIRED NEUTRAL CONDUCTORS PROVIDE SEPARATE NEUTRAL CONDUCTORS (WITH COLORED STRIPE TO MATCH PHASE CONDUCTOR) FOR EACH PHASE CONDUCTOR.

EMPTY CONDUITS ARE NOTED BY "EC" WITH TRADE SIZE.

- 1. DO NOT SCALE DRAWINGS UNLESS DIMENSIONS ARE SHOWN. LOCATE LIGHTING FIXTURES AND EQUIPMENT AS OBVIOUSLY INDICATED AND COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS. SEE CIVIL PLANS.
- 2. MINIMUM SIZE CONDUCTOR FOR POWER SHALL BE NO. 12 AWG. ALL CONDUCTORS SHALL BE COPPER.
- 3. ALL FUSES SHALL BE DUAL-ELEMENT TYPE, "FUSETRON" BY BUSSMAN, OR "ECON" BY ECONOMY.
- 4. BRANCH CIRCUIT SIZES ARE AWG 12-3/4" C. UNLESS OTHERWISE NOTED IN PANELBOARD SCHEDULES.
- 5. ALL BRANCH CIRCUIT LOADS SHALL BE BALANCED ACROSS PANELBOARD BUSSES TO OBTAIN MINIMUM NEUTRAL CURRENT.
- 6. ALL FLEXIBLE CONDUIT SHALL CONTAIN A GREEN WIRE BONDED TO RIGID RACEWAY, BOX OR FIXTURE AT EACH END OF FLEX. SIZE GROUND WIRE PER N.E.C. TABLE 250-122.
- 7. CONTRACTOR IS CAUTIONED THAT WORK SHALL BE COMPLETED IN PHASES AS REQUIRED TO MAINTAIN USE OF STREETS, SIDEWALKS, BUSINESSES AND THE LIKE. REFER TO LANDSCAPE ARCHITECT AND CIVIL PLANS FOR PHASING OF WORK.
- 8. ALL WORK SHALL COMPLY WITH NFPA, ADA, AASHTO, SCDOT, CITY OF COLUMBIA AND ALL OTHER APPLICABLE CODES AND STANDARDS.
- 9. SEE CIVIL AND UTILITY PLANS FOR EXISTING AND NEW UTILITIES. VERIFY EXACT LOCATIONS OF HANDHOLES, RISER POLES, PEDASTALS AND THE LIKE WITH UTILITIES.
- 10. CONDUIT ROUTING SHOWN DOES NOT INDICATE PATH OF ROUTING-SHOWN FOR CLARITY ONLY. ROUTE CONDUITS IN R.O.W. SEE CIVIL PLANS. 11. COORDINATE ALL NEW METER POINT LOCATIONS AND SERVICE LOCATIONS
- WITH UTILITY PRIOR TO BIDDING. 12. ALL CONDUIT ELBOWS BELOW GRADE SHALL BE BITUMINOUS COATED GRS.
- 13. IF REQUIRED TO SUIT LUGS, PROVIDE HYDRAULIC CRIMP TYPE WIRE
- CONDUCTORS TO CONTACTOR/CIRCUIT BREAKERS. 14. MINIMUM COVER FOR LIGHTING, TRAFFIC CONTROL AND IRRIGATION POWER

CIRCUITS SHALL BE 30".

REDUCERS IN METER CENTER AS REQUIRED TO CONNECT FEEDER

15. CONTRACTOR IS CAUTIONED THAT THESE PLANS ARE DIAGRAMMATIC ONLY AND THAT EXACT LOCATIONS AND ROUTINGS FOR NEW WORK SHALL BE AS OBVIOUSLY INDICATED AND AS DIRECTED BY OWNER, WITH MODIFICATIONS AS REQUIRED TO AVOID CONFLICTS IN THE FIELD. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS AND

ELECTRICAL SYMBOLS

- CONDUIT STUB JTDOOR LIGHTING STANDARD & FIXTURE
 - PHOTOCELL, 1800VA U.N.O., AIM NORTH.
 - TIME SWITCH

MOTION SENSOR SWITCH

- CAM SECURITY CAMERA ECS EMERGENCY CALL STATION
- BRANCH CIRCUIT RACEWAY CONCEALED IN WALL OR CEILING
- BRANCH CIRCUIT RACEWAY CONCEALED IN FLOOR OR UNDERGROUND BRANCH CIRCUIT RACEWAY - EXPOSED

OTE: ALL DEVICES SHOWN ON THIS SCHEDULE ARE SYMBOLIC ONLY. SEE ELECTRICAL SPECIFICATIONS FOR

XACT DEVICE REQUIREMENTS AND PERFORMACE CHARACTERISTICS.

DWNLIGHT FIXTURE

FLUSH JUNCTION BOX CEILING ()- WALL)

PULL BOX OR JUNCTION BOX IN FLOOR

DUPLEX RECEPTACLE (
HIGH MOUNT)

¬WP | WEATHERPROOF DUPLEX RECEPTACLE. 16" UP

ФGFI GROUND FAULT INTERRUPTER RECEPTACLE

TRANSFORMER

PANELBOARD

opyright © 1999 Guy White & Associate

SPECIAL NOTE: CONTRACTOR IS CAUTIONED THAT THESE PLANS ARE DIAGRAMMATIC ONLY AND THAT EXACT LOCATIONS OF LIGHTING FIXTURES, METER POINTS, RACEWAY (INCLUDING ROUTING) AND THE LIKE FOR NEW WORK SHALL BE AS OBVIOUSLY INDICATED AND AS DIRECTED BY THE CIVIL ENGINEER. PRIOR TO BIDDING, CONTRACTOR SHALL REVIEW ALL PLANS AND SPECIFICATIONS (ALL TRADES). FIELD VERIFY EXISTING CONDITIONS

AND COORDINATE WITH NEW WORK, TO INCLUDE FIELD MODIFICATIONS AS REQUIRED FOR A COMPLETE PROJECT.

NOTES TO ELECTRICAL WORK


- PRIOR TO BIDDING, CONTRACTOR SHALL REVIEW PLANS FOR ALL TRADES AND INCLUDE IN BID ALL WORK AS REQUIRED FOR A COMPLETE AND OPERABLE ELECTRICAL AND LIGHTING SYSTEM AS INDICATED.
- 2. CONTRACTOR IS CAUTIONED THAT SOME BRIDGE AND RAMP/STAIR COMPONENTS MAY BE REMANUFACTURED / PRECAST AND FIELD ASSEMBLED. COORDINATE CLOSELY WITH GC FOR MOUNTING OF ALL EQUIPMENT, FIXTURES, RACEWAY AND OTHER COMPONENTS.
- 3. COORDINATE WITH LANDSCAPE CONTRACTOR FOR LOCATION OF IRRIGATION CONTROLLER AND PROVIDE 120V POWER AS REQUIRED TO CONTROLLER LOCATION.
- 4. LOCATION FOR METER POINT IS PROPOSED AND MAY BE ADJUSTED AS REQUIRED TO SUIT FINAL SITE LAYOUT AND CONSTRUCTION SEQUENCE. COORDINATE WITH OWNER, GC AND ELECTRIC UTILITY FOR FINAL LOCATION. MAINTAIN NEC 110 CLEARANCES AND WORKSPACE.
- ALL LIGHTING SHALL BE AIMED, ADJUSTED AND SECURED TO PREVENT GLARE AND DISTRACTION TO DRIVERS ALONG ROADWAY.

LIGHTING FIXTURE SCHEDULE

SYMBOL	DESCRIPTION	MANUFACTURER	CATALOG NUMBER	VOLTAGE	LAMPS*	BALLASTS*	FIXTURE WATTAGE	NOTES
S1	LED LINEAR FIXTURE WITH 45° BEAM SPREAD. WET LOCATION.	INSIGHT	MVW-6W/FT-40K-45°- D-48"	120V	LED	N/A	30W	LED ILLUMINATED LINEAR LIGHTING FIXTURE MOUNTED TO CENTER OF BRIDGE CAGE FENCE AT APPROXIMATELY 9'-0" ABOVE WALKWAY. PROVIDE ALL HARDWARE REQUIRED FOR MOUNTING. CONNECT COMPLETE.
SC	CAMPUS STANDARD LED POST TOP	STERNBERG	1970LED-S-BTSR-FG- ONPT-6ARC45T5-PEC 1-OD-DBA-BK(FIXTURE) 4212-FP5(POLE)		LED	N/A	110W	MOUNT TO CONCRETE BASE. PROVIDE POLE EPA RATED 90MPH (1.3 GUST FACTOR). PROVIDE FINISH TO MATCH EXISTING CAMPUS STANDARD. INTEGRAL PHOTOCELL.


NOTES TO LIGHTING FIXTURE SCHEDULE


L1. LOCATE ALL FIXTURES IN STRICT ACCORDANCE WITH ARCHITECTURAL AND LANDSCAPE PLANS.



POLE ASSEMBLY SC

NO SCALE





5. EXTEND BONDING JUMPER TO EACH PANEL INCLUDING

TWO-SECTION PANELS WITH FEED-THRU NIPPLES. GROUNDING OF CONDUITS 1" C.

AND LARGER





Midlands Office - Main 168 Laurelhurst Avenue Columbia, SC 29210 (803)252-6919 Fax (803)799-5494 gwa@gwainc.net http://www.gwainc.net

August 10, 2015 Date

THESE DOCUMENTS AND THE INFORMATION CONTAINED HEREIN ARE THE PROPERTY OF CHAO & ASSOCIATES, INC. AND MAY NOT BE USED FOR ANY PURPOSE WITHOUT THE WRITTEN PERMISSION OF CHAO & ASSOCIATES, INC.

S Associate

∞ $\overline{\mathcal{O}}$

etail

dul

7

-ELECTRICAL

WARNING TAPE

-UNDERGROUND CONDUIT(S)

Sheet Number August 10, 2015

Date

SIDE VIEW FRONT VIEW - FINISHED GRADE — UNDISTURBED METER BY UTILITY. PROVIDE \ METER SOCKET AS REQUIRED. FLOWABLE FILL OR 180 DEGREES HINGED ELECTRICAL FLOWABLE SECTION COMPACTED BACKFILL METER/TEST SECTION WARNING TAPE FILL AS SPECIFIED. HINGED DEMAND METER COVER WITH HANDLE 12" BELOW GRADE RESET COVER WITH PADLOCKABLE. -UNDERGROUND CONDUIT(S) 2"X4" (51mm X 102mm) r F WINDOW. LIFT OFF SERVICE 4-1/2" X 6" (114mm X COVER WITH HANDLE 152mm) ACCESS PADLOCKABLE. < PHOTOCELL COMPARTMENT OPENING. PADLOCKABLE. WITH PHOTOCELL CONCRETE OR PAVED AREA NON-PAVED AREA PADLOCK BRACKET PANEL UTILITY TERMINATION **CONDUIT NOT IN AN UNDERGROUND** LANDING. < INDICATED PADLOCK BRACKET **DUCTBANK** EXTENDS THROUGH DOOR FOR SECURITY. NO SCALE ←GFCI, WP RECEPTACLE WITH FLUSH MOUNTED, - HINGED DEADFRONT. LOCKABLE, METAL, IN-USE NOTES TO SPD (SURGE PROTECTION DEVICES): SECTION ||SERVICE| - HINGED EXTERIOR DOOR. TERM. MEANS PROVIDED TO HOLD SECTION DOOR IN OPEN POSITION. SYMBOL **APPLICATION** - ANCHOR BOLTS PADLOCK -CIRCUITS. CONDUCTOR SIZES PER BRACKET~ MT'D ON A BASE PLANS, IN CONDUITS AS INDICATED. DISTRIBUTION PANEL MINIMUM 1° SLOPE 6" THICK CONC. SLAB REINF. WITH 1. PROVIDE SPD AT PANELBOARD(S) AND OUTLETS AS INDICATED. 6x6, 10-10 W.W.M. MINIMUM

DIMENSIONS = ENCLOSURE

一CONDUITS AS INDICATED ON

GRD. AS INDICATED ON POWER RISER DIAGRAM.

BRASS MARKER.)

POWER RISER DIAGRAMS. STUB

┙(MIN. 2' BEYOND TRANSCLOSURE BASE. MARK AT GRADE WITH

u OUT AND CAP FOR FUTURE USE

— FOOTPRINT PLUS 6" ALL—AROUND.

DIAGRAMS. PAD MOUNTED METER POINT DETAIL

NOTES TO METER POINT ASSEMBLY

NO SCALE

CONTROL CABINET SHALL BE U/L LISTED "INDUSTRIAL CONTROL PANEL" PER UL 508.

SERVICE —

ENTRANCE AS

INDICATED ON

POWER RISER

- 2. CONSTRUCTION SHALL BE NEMA 3R, MIN. 12 GA A60 STEEL POWDER COATED, FINISH PER
- 3. VOLTAGE RATINGS OF SERVICE EQUIPMENT SHALL CONFORM TO THE SERVICE VOLTAGES INDICATED ON THE PLANS.
- I. SERVICE EQUIPMENT ENCLOSURE AND METERING EQUIPMENT SHALL MEET THE REQUIREMENTS OF THE SERVING UTILITY. THE METER AREA SHALL HAVE A SEALABLE, LOCKABLE, RAINTIGHT COVER THAT CAN BE REMOVED WITHOUT THE USE OF TOOLS.
- 5. SERVICE EQUIPMENT SHALL BE FACTORY WIRED AND CONFORM TO NEMA STANDARDS.
- 6. THE EXTERIOR DOOR SHALL HAVE PROVISIONS FOR PADLOCKING. THE PADLOCK HOLE SHALL BE A MINIMUM DIAMETER OF 11mm.
- ALL TERMINALS FOR INCOMING SERVICE CONDUCTORS SHALL BE COMPATIBLE WITH EITHER COPPER OR ALUMINUM CONDUCTORS SIZED TO SUIT THE CONDUCTORS SHOWN ON THE PLAN. TERMINAL LUGS SHALL BE COPPER OR TIN-PLATED ALUMINUM. SOLID NEUTRAL TERMINAL STRIP SHALL BE RATED 125A UNLESS OTHERWISE SPECIFIED AND FOR USE WITH COPPER OR ALUMINUM CONDUCTORS. THE TERMINAL SHOULD INCLUDE BUT NOT BE LIMITED TO: INCOMING TERMINALS (LANDING LUGS), NEUTRAL LUGS, SOLID NEUTRAL TERMINAL STRIP, TERMINAL STRIPS FOR CONDUCTORS WITHIN THE ENCLOSURE.
- FASTENERS ON THE EXTERIOR OF THE ENCLOSURE SHALL BE VANDAL RESISTANT AND SHALL NOT BE REMOVABLE FROM THE EXTERIOR. ALL NUTS, BOLTS, SCREWS, WASHERS, AND HINGES SHALL BE STAINLESS STEEL.
- 9. PHENOLIC NAME PLATES SHALL BE PROVIDED AS SPECIFIED.
- 10. A PLASTIC COVERED WIRING DIAGRAM SHALL BE ATTACHED TO THE INSIDE OF THE FRONT DOOR.
- 11. ASSEMBLY SHALL BE BY MILBANK MFG CO. (816)483-5314 COMMERCIAL PEDESTAL OR EQUAL BY MYERS POWER PRODUCTS (866)696-9377 OR PACIFIC UTILITY PRODUCTS (800)860-6157.
- 12. OBTAIN APPROVAL OF UTILITY PRIOR TO ORDERING. ASSEMBLY AND METERING SHALL MEET ALL REQUIREMENTS OF UTILITY.

NUMBER OF POLES PER MANUFACTURER'S INSTRUCTIONS. 3. LOCATE SPD UNITS AS NEAR TO PROTECTED GEAR AS PHYSICALLY POSSIBLE IN ORDER TO MINIMIZE LEAD LENGTH. 4. VOLTAGE RATING SHALL SUIT GEAR/DEVICES SERVED. -UTILITY DIP POLE 5. SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION. UTILITY: AIKEN ELECTRIC COOP. 2790 WAGENER RD. AIKEN, SC 29803 TEL. (803) 649-6245 - PROVIDE SLACK FOR DRIP LOOP AS DIRECTED BY UTILITY. - PROVIDE METER SOCKET AS DIRECTED BY PROVIDE PHOTOCONTROLLER NEW METER POINT ELECTRIC UTILITY. (RECEPTACLE TYPE)-RIPLEY "MP-A" OR EQUAL. CONNECT CONTRACTOR SHALL COORDINATE WITH COMPLETE TO CONTROL ELECTRIC UTILITY AND COMPLY WITH ALL CONTACTOR. REQUIREMENTS FOR SERVICE AND #8 GRD.-1"C.-METERING. SEE SPEC. PROVIDE 6 (SIX) POLE, 30A - ELECTRICALLY HELD LIGHTING #8 GRD. - 1 1/4"C. PANEL CONTACTOR "CA" WITH 120V COIL. "BLA" CONNECT COMPLETE TO CONTROL - METER PEDESTAL. LIGHTING. SEE DETAIL. 120/240V 2 - 2" CONDUITS FOR 7 FUTURE USE. 3#3 - 2"C.(SCH. 40 ----PVC). MIN. 42"B.F.G. IRRIG. CONTROLLER → BRIDGE LIGHTING CIRCUITS AS INDICATED. GRS ELBOW AND RISER WALKWAY LIGHTING CIRCUITS AS INDICATED.


2. INSTALL STRICTLY IN ACCORDANCE WITH MANUFACTURER'S

RECOMMENDATIONS AND NEC ARTICLE 285 REQUIREMENTS. LEAD LENGTHS

LENGTHS. PROVIDE OVERCURRENT PROTECTION IN CURRENT RATINGS AND

SHALL BE EQUAL TO OR LESS THAN MANUFACTURER'S RECOMMENDED


POWER RISER DIAGRAM - MP-A NO SCALE






Midlands Office - Main 168 Laurelhurst Avenue Columbia, SC 29210 (803)252-6919 Fax (803)799-5494 gwa@gwainc.net http://www.gwainc.net

GWA, INC. ELECTRICAL ENGINEERS



Electrical Site Plan
USCA Pedestrian Bridge
State Project No. H29-954
University of South Carolir
Aiken County, SC

Sheet Number August 10, 2015



Sheet Number August 10, 2015

Date