

## ADDENDUM NUMBER 2

**Date:** February 18, 2021  
**Project:** **USC Union – Central Building  
HVAC Upgrades**  
University of South Carolina



**USC Proj No.** **H40-9512 / 50003140-4**  
**MDI Proj. No.:** 213688

**Submitted By:** Justin Varco, PE, CPD  
Mechanical Design, Inc.  
4403 Broad River Road  
Columbia, S.C. 29210  
(803)731-9834 Fax: (803)731-9837  
[justin@mdi9834.com](mailto:justin@mdi9834.com)

The following items take precedence over referenced portions of the Contract Documents for the referenced project dated 02/04/21, and, in executing a contract, shall become a part thereof.

Where any item called for in the documents is supplemented hereby, the original requirements shall remain in effect. All supplemental conditions shall be considered as added thereto.

Where any original item is amended, voided, or superseded hereby, the provision of such items not so specifically amended, voided, or superseded shall remain in effect.

---

### **DRAWINGS**

Drawing E103, 1st Floor Electrical Renovation Plan: There is a note above Room 110 that directs the contractor to route raceways and conductors that serve outdoor HVAC units HPD-2-48 and HP-2-144 through the crawl space to panel "LB". Change this note to require the raceways and conductors to be routed up the exterior wall of the building and penetrate the wall at a height at some point above the installed level of the new drop ceiling in Corridor H102. Raceways and conductors shall then be routed concealed above new and existing drop ceilings to panel "LB".

Drawing E105, Lighting Fixture Schedule - The following are prior-approved equals to the lighting fixtures specified in the schedule:

|           |               |  |
|-----------|---------------|--|
| Type "A"  | H.E. Williams | LT-24-L40/840-AF-(4) EQ CLIPS-DIM-UNV                            |
| Type "AE" | H.E. Williams | LT-24-L40/840-AF-(4) EQ CLIPS-DIM-UNV-<br>with BODINE BSL310LPST |

Drawing E105, General Note 2 – Delete the existing Note 2 and replace it with the following:

2. Fire Alarm Devices: The new fire alarm system will be under warranty with MSS Fire & Security, LLC in Greer, South Carolina. The contractor shall procure the services of MSS Fire & Security to perform the following:
  - A) Before ceiling demolition begins, remove existing detectors, notification appliances, and associated backboxes from ceiling tiles. Provide a dust bag over all fire alarm system detectors and notification appliances and support detectors and notification appliances from structural ceiling.

- B) When new ceilings are installed, disconnect existing detectors and notification appliances from their backbox and wiring as required to install them centered in a new ceiling tile, and then reattach the detectors and notification appliances to their wiring and backbox.
- C) Retest and recertify the fire alarm system in accordance with NFPA 72 at project completion and provide a certification letter and a test log.

Drawing E105, General Note 3: Add the following General Note 3 to the drawing:

- 3. Coordinate any required fire alarm system outages with Ducky Lawson of USC Union, phone number (864) 466-2607. Provide 7 days' notice to Owner prior to any required fire alarm system outages.

**END OF ADDENDUM ITEMS**