

May 26, 2016

Garvin Design Group
1209 Lincoln St.
Columbia, SC 29201

ADDENDUM NO. 3

The following items shall take precedence over the drawings and specifications for the above named project and shall become a part of the contract documents. Where any item called for in the specifications, or indicated on the drawings, is not supplemented hereby, the original requirements shall remain in effect. Where any original item is amended, voided, or superseded hereby, the provisions of such item not specifically amended, voided or superseded shall remain in effect.

General

1. Reference the attached Addendum No. 3 memorandum from Belka Engineering Associates.

END OF ADDENDUM NO. 3

Attachments:

1. Belka Engineering Associates – Addendum No. 3



**BELKA
ENGINEERING
ASSOCIATES, INC.**

May 26, 2016

Mr. Terry Buchmann
Garvin Design Group
1209 Lincoln Street
Columbia, SC 29202

Re: **Strom Thurmond Signage – Electrical Package – Addendum No. 3**
BEA Project No. GA21602

Dear Terry:

Please add to the final addendum the following:

On Sheet E2-1; Replace note 5 in Key Notes to read, "PROVIDE THREE (3) 20 AMP 1-POLE BREAKERS IN NEW SUB PANEL FED FROM EXISTING PANEL "1LB" (SEE SHEET E1-1 FOR LOCATION) FOR DIGITAL RIBBON SIGNAGE. PROVIDE 2#12, 1#12 GND. PER BRANCH CIRCUIT IN 3/4" C. TO JUNCTION BOX AT THIS LOCATION FOR DIGITAL RIBBON SIGNAGE. ROUTE CONDUIT/CONDUCTORS ABOVE ACCESSIBLE CEILING WHERE POSSIBLE. CONDUIT/CONDUCTORS SHALL BE ROUTED IN EXISTING CHASE AND BELOW RUNNING TRACK ABOVE LEVEL 2 AS SHOWN ON PLAN. COORDINATE ACCESS PANEL LOCATION WITH ARCHITECT IF ACCESS PANEL IS NECESSARY."

If you have any questions, please give us a call or email.

Sincerely,

Zack

Zack Stringfield, E.I.T., LEED GA
Electrical Designer
ZSTRINGFIELD@BEA-Consulting.com