

## **ADDENDUM NO. TWO**



**REBID – USC Upstate Baseball Field  
Drainage System Improvements  
State Project No. H34-I376  
WKD Project No. 20170043.00.CA**

**May 3, 2017**

---

### **TO ALL BIDDERS:**

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents.

Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may disqualify the Bidder.

Bidders and other interested parties are informed that the above referenced plans, specifications and contract documents are hereby revised, changed, clarified and supplemented as set forth below:

### **GENERAL / CLARIFICATIONS**

1. The owner has chosen to revise Bid Alternate 1, to allow the Cambridge Drainage System. The details and requirements of the system are found on the revised plans sheets, 3 and 4. In lieu of the Base Bid required 20-foot spaced 4-inch underdrains, this bid alternate shall be to install a 50mm perforated “Cambridge Drainage System” with 10-foot lateral spacing of the underdrain lines. The installation shall be per the notes and details indicated on sheets 3 and 4 of the revised plans under the Bid Alternate # 1 designation. All remaining portions of the project including header pipe installation, outfalls, cleanouts, etc. shall be the same as the Base Bid.
2. The attached revised SE-330 – Lump Sum Bid Form shall be used by all contractors bidding on the project. Each bidder must include a Base Bid.

### **PLANS:**

1. Replace plan sheets 3 and 4 in their entirety with the attached revised plan sheets.

### **CONTRACT DOCUMENTS / SPECIFICATIONS:**

2. Replace SE-330 – Lump Sum Bid Form in its entirety with the attached revised SE-330 – Lump Sum Bid Form.

### **ATTACHMENTS:**

1. Plan Sheet 3 of 5 (Revised)
2. Plan Sheet 4 of 5 (Revised)
3. SE-330 – Lump Sum Bid Form (Revised)

**END OF ADDENDUM NO. 2**

**SE-330  
LUMP SUM BID FORM**

*Bidders shall submit bids on only Bid Form SE-330.*

**BID SUBMITTED BY:** \_\_\_\_\_  
*(Bidder's Name)*

**BID SUBMITTED TO:** University of South Carolina  
*(Owner's Name)*

**FOR: PROJECT NAME:** REBID - USC Upstate Baseball Field Drainage System Installation  
**PROJECT NUMBER:** H34-I376

**OFFER**

§ 1. In response to the Invitation for Construction Services and in compliance with the Instructions to Bidders for the above-named Project, the undersigned Bidder proposes and agrees, if this Bid is accepted, to enter into a Contract with the Owner on the terms included in the Bidding Documents, and to perform all Work as specified or indicated in the Bidding Documents, for the prices and within the time frames indicated in this Bid and in accordance with the other terms and conditions of the Bidding Documents.

§ 2. Pursuant to Section 11-35-3030(1) of the SC Code of Laws, as amended, Bidder has submitted Bid Security as follows in the amount and form required by the Bidding Documents:

- Bid Bond with Power of Attorney
  - Electronic Bid Bond
  - Cashier's Check
- (Bidder check one)*

§ 3. Bidder acknowledges the receipt of the following Addenda to the Bidding Documents and has incorporated the effects of said Addenda into this Bid:

*(Bidder, check all that apply. Note, there may be more boxes than actual addenda. Do not check boxes that do not apply.)*

- ADDENDA:**             #1             #2             #3             #4             #5

§ 4. Bidder accepts all terms and conditions of the Invitation for Bids, including, without limitation, those dealing with the disposition of Bid Security. Bidder agrees that this Bid, including all Bid Alternates, if any, may not be revoked or withdrawn after the opening of bids, and shall remain open for acceptance for a period of **60** Days following the Bid Date, or for such longer period of time that Bidder may agree to in writing upon request of the Owner.

§ 5. Bidder herewith offers to provide all labor, materials, equipment, tools of trades and labor, accessories, appliances, warranties and guarantees, and to pay all royalties, fees, permits, licenses and applicable taxes necessary to complete the following items of construction work:

§ 6.1 **BASE BID WORK** *(as indicated in the Bidding Documents and generally described as follows):* Provide labor and materials as required to perform underdrain system installation including surveying, demolition, trenching, subgrade preparation, storm drainage installation, and other field improvements for the varsity baseball field, per the plans and specifications.

**\$** \_\_\_\_\_, which sum is hereafter called the Base Bid.

*(Bidder to insert Base Bid Amount on line above)*

**SE-330  
LUMP SUM BID FORM**

§ 6.2 **BID ALTERNATES** as indicated in the Bidding Documents and generally described as follows:

**ALTERNATE # 1** (*Brief Description*): Provide same final product per plans and specifications, but in lieu of 4-inch, 20-foot spaced underdrains, install a 50mm Cambridge Drainage System as detailed and specified with a 10-foot lateral spacing of underdrains.

**ADD TO** or  **DEDUCT FROM BASE BID:** \$ \_\_\_\_\_

*(Bidder to mark appropriate box to clearly indicate the price adjustment offered for each Alternate)*

**ALTERNATE # 2** (*Brief Description*): N/A

**ADD TO** or  **DEDUCT FROM BASE BID:** \$ \_\_\_\_\_

*(Bidder to mark appropriate box to clearly indicate the price adjustment offered for each Alternate)*

**ALTERNATE # 3** (*Brief Description*): N/A

**ADD TO** or  **DEDUCT FROM BASE BID:** \$ \_\_\_\_\_

*(Bidder to mark appropriate box to clearly indicate the price adjustment offered for each Alternate)*

§ 6.3 **UNIT PRICES:**

**BIDDER** offers for the Agency’s consideration and use, the following **UNIT PRICES**. The **UNIT PRICES** offered by **BIDDER** indicate the amount to be added to or deducted from the **CONTRACT SUM** for each item-unit combination. **UNIT PRICES** include all costs to the Agency, including those for materials, labor, equipment, tools of trades and labor, fees, taxes, insurance, bonding, overhead, profit, etc. The Agency reserves the right to include or not to include any of the following **UNIT PRICES** in the Contract and to negotiate the **UNIT PRICES** with **BIDDER**.

<u>No.</u>	<u>ITEM</u>	<u>UNIT OF MEASURE</u>	<u>ADD</u>	<u>DEDUCT</u>
<u>1.</u>	<u>Remove Warning Track Material (2")</u>	<u>CY</u>	<u>\$</u>	<u>\$</u>
<u>2.</u>	<u>New Crushed Brick Warning Track Mat. (2")</u>	<u>TON</u>	<u>\$</u>	<u>\$</u>
<u>3.</u>	<u>Cert. Bermuda 419 Sprigging (700 Bus/AC)</u>	<u>AC</u>	<u>\$</u>	<u>\$</u>
<u>4.</u>	<u>Tarp Drain / Cleanout</u>	<u>EA</u>	<u>\$</u>	<u>\$</u>
<u>5.</u>	<u>4" HDPE Underdrain (with req. backfill)</u>	<u>LF</u>	<u>\$</u>	<u>\$</u>
<u>6.</u>	<u>12" HDPE Header (with req. backfill)</u>	<u>LF</u>	<u>\$</u>	<u>\$</u>

**SE-330  
LUMP SUM BID FORM**

**§ 7. LISTING OF PROPOSED SUBCONTRACTORS PURSUANT TO SECTION 3020(b)(i), CHAPTER 35, TITLE 11 OF THE SOUTH CAROLINA CODE OF LAWS, AS AMENDED**  
*(See Instructions on the following page BF-2A)*

Bidder shall use the below-listed Subcontractors in the performance of the Subcontractor Classification work listed:

<b>SUBCONTRACTOR CLASSIFICATION</b> <b>By License Classification and/or Subclassification</b> <i>(Completed by Owner)</i>	<b>SUBCONTRACTOR'S PRIME CONTRACTOR'S NAME</b> <i>(Must be completed by Bidder)</i>	<b>SUBCONTRACTOR'S PRIME CONTRACTOR'S SC LICENSE NUMBER</b> <i>(Requested, but not Required)</i>
<b>BASE BID</b>		
N/A		
<b>ALTERNATE #1</b>		
N/A		
<b>ALTERNATE #2</b>		
<b>ALTERNATE #3</b>		

If a Bid Alternate is accepted, Subcontractors listed for the Bid Alternate shall be used for the work of both the Alternate and the Base Bid work.

SE-330

## LUMP SUM BID FORM

**INSTRUCTIONS FOR  
SUBCONTRACTOR LISTING**

1. Section 7 of the Bid Form sets forth an Owner developed list of contractor/subcontractor specialties by contractor license category and/or subcategory for which bidder is required to identify the entity (subcontractor(s) and/or himself) Bidder will use to perform the work of each listed specialty..
  - a. **Column A:** The Owner fills out this column, which identifies the contractor/subcontractor specialties for which the bidder must list either a subcontractor or himself as the entity that will perform this work. Subcontractor specialties are identified by contractor license categories or subcategories listed in Title 40 of the South Carolina Code of laws. Abbreviations of classifications to be listed after the specialty can be found at: <http://www.llr.state.sc.us/POL/Contractors/PDFFiles/CLBCClassificationAbbreviations.pdf> . If the owner has not identified a specialty, the bidder does not list a subcontractor.
  - b. **Columns B and C:** In these columns, the Bidder identifies the subcontractors it will use for the work of each specialty listed by the Owner in Column A. Bidder must identify only the subcontractor(s) who will perform the work and no others. Bidders should make sure that their identification of each subcontractor is clear and unambiguous. A listing that could be any number of different entities may be cause for rejection of the bid as non-responsive. For example, a listing of M&M without more may be problematic if there are multiple different licensed contractors in South Carolina whose names start with M&M.
2. **Subcontractor Defined:** For purposes of subcontractor listing, a subcontractor is an entity who will perform work or render service to the prime contractor to or about the construction site pursuant to a contract with the prime contractor. Bidder should not identify sub-subcontractors in the spaces provided on the bid form but only those entities with which bidder will contract directly. Likewise, do not identify material suppliers, manufacturers, and fabricators that will not perform physical work at the site of the project but will only supply materials or equipment to the bidder or proposed subcontractor(s).
3. **Subcontractor Qualifications:** Bidder must only list subcontractors who possess a South Carolina Contractor's license with the license classification and/or subclassification identified by the Owner in the first column on the left. The subcontractor license must also be within the appropriate license group for the work of the specialty. If Bidder lists a subcontractor who is not qualified to perform the work, the Bidder will be rejected as non-responsive.
4. **Use of Own forces:** If under the terms of the Bidding Documents, Bidder is qualified to perform the work of a listed specialty and Bidder does not intend to subcontract such work but to use Bidder's own employees to perform such work, the Bidder must insert its own name in the space provided for that specialty.
5. **Use of Multiple Subcontractors:**
  - a. If Bidder intends to use multiple subcontractors to perform the work of a single specialty listing, Bidder must insert the name of each subcontractor Bidder will use, preferably separating the name of each by the word "**and**". If Bidder intends to use both his own employees to perform a part of the work of a single specialty listing and to use one or more subcontractors to perform the remaining work for that specialty listing, bidder must insert his own name and the name of each subcontractor, preferably separating the name of each with the word "**and**". Bidder must use each entity listed for the work of a single specialty listing in the performance of that work.
  - b. **Optional Listing Prohibited:** Bidder may not list multiple subcontractors for a specialty listing, in a form that provides the Bidder the option, after bid opening or award, to choose to use one or more but not all the listed subcontractors to perform the work for which they are listed. A listing, which on its face requires subsequent explanation to determine whether it is an optional listing, is non-responsive. If bidder intends to use multiple entities to perform the work for a single specialty listing, bidder must clearly set forth on the bid form such intent. Bidder may accomplish this by simply inserting the word "**and**" between the names of each entity listed for that specialty. Agency will reject as non-responsive a listing that contains the names of multiple subcontractors separated by a blank space, the word "or", a virgule (that is a /), or any separator that the Agency may reasonably interpret as an optional listing.
6. If Bidder is awarded the contract, bidder must, except with the approval of the Agency for good cause shown, use the listed entities to perform the work for which they are listed.
7. If bidder is awarded the contract, bidder will not be allowed to substitute another entity as subcontractor in place of a subcontractor listed in Section 7 of the Bid except for one or more of the reasons allowed by the SC Code of Laws.
8. Bidder's failure to identify an entity (subcontractor or himself) to perform the work of a subcontractor specialty listed in the first column on the left will render the Bid non-responsive.

**SE-330**  
**LUMP SUM BID FORM**

**§ 8. LIST OF MANUFACTURERS, MATERIAL SUPPLIERS, AND SUBCONTRACTORS OTHER THAN SUBCONTRACTORS LISTED IN SECTION 7 ABOVE (FOR INFORMATION ONLY):**

Pursuant to instructions in the Invitation for Construction Services, if any, Bidder will provide to Owner upon the Owner's request and within 24 hours of such request, a listing of manufacturers, material suppliers, and subcontractors, other than those listed in Section 7 above, that Bidder intends to use on the project. Bidder acknowledges and agrees that this list is provided for purposes of determining responsibility and not pursuant to the subcontractor listing requirements of SC Code Ann § 11-35-3020(b)(i).

**§ 9. TIME OF CONTRACT PERFORMANCE AND LIQUIDATED DAMAGES**

**a) CONTRACT TIME**

Bidder agrees that the Date of Commencement of the Work shall be established in a Notice to Proceed to be issued by the Owner. Bidder agrees to substantially complete the Work within 65 Calendar Days from the Date of Commencement, subject to adjustments as provided in the Contract Documents.

**b) LIQUIDATED DAMAGES**

Bidder further agrees that from the compensation to be paid, the Owner shall retain as Liquidated Damages the amount of \$ 250.00 for each Calendar Day the actual construction time required to achieve Substantial Completion exceeds the specified or adjusted time for Substantial Completion as provided in the Contract Documents. This amount is intended by the parties as the predetermined measure of compensation for actual damages, not as a penalty for nonperformance.

**§ 10. AGREEMENTS**

- a) Bidder agrees that this bid is subject to the requirements of the laws of the State of South Carolina.
- b) Bidder agrees that at any time prior to the issuance of the Notice to Proceed for this Project, this Project may be canceled for the convenience of, and without cost to, the State.
- c) Bidder agrees that neither the State of South Carolina nor any of its agencies, employees or agents shall be responsible for any bid preparation costs, or any costs or charges of any type, should all bids be rejected or the Project canceled for any reason prior to the issuance of the Notice to Proceed.

**§ 11. ELECTRONIC BID BOND**

By signing below, the Principal is affirming that the identified electronic bid bond has been executed and that the Principal and Surety are firmly bound unto the State of South Carolina under the terms and conditions of the AIA Document A310, Bid Bond, included in the Bidding Documents.

**ELECTRONIC BID BOND NUMBER:** \_\_\_\_\_

**SIGNATURE AND TITLE:** \_\_\_\_\_

**SE-330  
LUMP SUM BID FORM**

**CONTRACTOR'S CLASSIFICATIONS AND SUBCLASSIFICATIONS WITH LIMITATION**

**SC Contractor's License Number(s):** \_\_\_\_\_

**Classification(s) & Limits:** \_\_\_\_\_

**Subclassification(s) & Limits:** \_\_\_\_\_

**By signing this Bid, the person signing reaffirms all representation and certification made by both the person signing and the Bidder, including without limitation, those appearing in Article 2 of the Instructions to Bidders, is expressly incorporated by reference.**

**BIDDER'S LEGAL NAME:** \_\_\_\_\_

**ADDRESS:** \_\_\_\_\_  
\_\_\_\_\_

**TELEPHONE:** \_\_\_\_\_


**EMAIL:** \_\_\_\_\_

**SIGNATURE:** \_\_\_\_\_ **DATE:** \_\_\_\_\_

**PRINT NAME:** \_\_\_\_\_

**TITLE:** \_\_\_\_\_


CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL, STATE, AND FEDERAL AGENCIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL, STATE, AND FEDERAL AGENCIES.



**BID ALTERNATE #1:**

THE BID SHALL BE THE LABOR, MATERIALS, AND INCIDENTALS NECESSARY TO MEET ALL OTHER SPECIFICATIONS, DIMENSIONS, PRODUCTS, DETAILS AND REQUIREMENTS FOR THE PROJECT. IN LIEU OF THE BASE BID REQUIRED 20-FOOT SPACED 4-INCH UNDERDRAINS, THIS BID ALTERNATE SHALL BE TO INSTALL A 50MM PERFORATED "CAMBRIDGE DRAINAGE SYSTEM" WITH 10-FOOT LATERAL SPACING OF THE UNDERDRAIN LINES. THE INSTALLATION SHALL BE PER THE NOTES AND DETAILS INDICATED ON SHEET 4 OF THE PLANS UNDER THE BID ALTERNATE # 1 HEADER. ALL REMAINING PORTIONS OF THE PROJECT INCLUDING HEADER PIPE INSTALLATION, OUTFALLS, CLEANOUTS, ETC. SHALL BE THE SAME AS THE BASE BID.

**WK DICKSON**  
 community infrastructure consultants  
 1320 MAIN STREET  
 SUITE 400  
 COLUMBIA, SC 29201  
 (803) 786-4261  
 (803) 786-4263  
 WWW.WKDICKSON.COM



NO.	DATE	DESCRIPTION	BY
1.	05-02-2017	ADDENDUM NO 2 BID ALTERNATE REVISION	MDJ


- NOTES:**
- REFER TO GENERAL NOTES, SHEET 2 FOR ADDITIONAL NOTES.
  - UNDERDRAIN INVERT ELEVATIONS ARE SHOWN AT A DEPTH BASED OFF OF THE CURRENT FIELD SURFACE ELEVATIONS.
  - FIELD IRRIGATION TO BE REPAIRED AS REQUIRED DURING INSTALLATION OF UNDERDRAIN SYSTEM.
  - SITE IMPROVEMENT PLAN ABBREVIATIONS:  
 HP: HEADER PIPE  
 UD: UNDERDRAIN  
 INV: PIPE/STRUCTURE INVERT
  - CONTRACTOR SHALL LIMIT FIELD DISTURBANCE TO WORKABLE AREAS, TO MINIMIZE OPEN TRENCHES AND SOIL EROSION. AREAS ADJACENT TO THE TRENCHES SHALL REMAIN NEAT AND TIDY AND THE CONTRACTOR SHALL TAKE SPECIAL CARE TO MINIMIZE MIXING AND SPREADING OF MATERIALS.
  - CONTRACTOR SHALL USE PROPER EQUIPMENT AND TECHNIQUES REQUIRED FOR THE INSTALLATION OF THE FIELD DRAINAGE SYSTEM, IN ACCORDANCE WITH REQUIREMENTS AND RECOMMENDATIONS SET FOR PER THE AMERICAN SPORTS BUILDERS ASSOCIATION (ASBA).
  - CONTRACTOR SHALL BE A MEMBER IN GOOD STANDING OF THE ASBA.
  - FOR ALL PIPES INSTALLED IN THE INFIELD AREAS, THE BASE BID SHALL INCLUDE PLACEMENT OF COVER MATERIAL MATCHING THE EXISTING MATERIAL TO A DEPTH OF 3 INCHES OVER THE SAND ROOT ZONE MIX. FOR PIPES INSTALLED IN THE GRASSED AREAS, THE BASE BID SHALL INCLUDE CERTIFIED 419 BERMUDA SPRIGGING OF THE TRENCH AT A RATE OF 700 BUSHELS PER ACRE.
  - THIRTY DAYS AFTER OWNER ACCEPTANCE OF PROJECT, CONTRACTOR SHALL TOP DRESS ALL SETTLED TRENCHES.
  - DUMP DRAIN LOCATIONS SHOWN ARE FOR REFERENCE ONLY. CONTRACTOR TO FIELD-LOCATE THE FINAL DRAINS IN COORDINATION WITH THE OWNER.
  - INFIELD SKIN AREAS SHALL BE LASER GRADED AFTER CONSTRUCTION OF UNDER DRAIN SYSTEM.
  - CONTRACTOR SHALL ENSURE THE FIELD IS RETURNED TO ITS ORIGINAL CONDITION, OR BETTER, AFTER CONSTRUCTION IS COMPLETE.

**The Palmetto Utility Protection Service, Inc.**  
 810 Duck Square Blvd, Suite 130, Columbia, South Carolina 29210 (803) 939-1117

**South Carolina 811**  
 Call 811 Before you Dig

3 DAYS BEFORE DIGGING IN SOUTH CAROLINA  
**CALL 811**

CONTRACTOR SHALL CONTACT THE UNDERGROUND LOCATORS EVERY 10 DAYS FOR AN UPDATE TO UTILITY LOCATIONS.



**BID DOCUMENTS - DO NOT USE FOR CONSTRUCTION**

PROJECT NAME: REBID USC UP STATE BASEBALL FIELD DRAINAGE SYSTEM IMPROVEMENTS FOR THE UNIVERSITY OF SOUTH CAROLINA SPARTANBURG COUNTY, SOUTH CAROLINA

DRAWING TITLE: SITE IMPROVEMENT PLAN

PROJ. MGR.: BET  
 DESIGN BY: MDJ  
 DRAWN BY: MDJ  
 PROJ. DATE: MAY 2, 2017  
 DRAWING NUMBER:  
**3 OF 5**  
 WKD PROJ. NO.: 20170043.00.CA



