

Project Name: USC Gateway Column Reconstruction
Project Number: FY18000712
University of South Carolina

Addendum Number One

Date: June 22, 2018

From: Aimee Rish, Procurement Specialist

To: All Bidders

The following items add to, modify, clarify, or otherwise later the Drawings and/or specifications and will become a part of the Contract Documents. Where a portion of the Drawings and/or specifications is added to, modified, clarified, or otherwise altered, the portion shall not so affected shall remain. Bidder shall include all effects that these items may have on his proposal.

Acknowledgement receipt of this addendum in the space provided on the Bid Form. Failure to do so may subject a Bidder to disqualification.

General

1. The Sign-in Sheet for attendance at the pre-bid meeting is attached.
2. Fencing & Laydown Area: No laydown space will be provided. Three parking spaces along Pendleton St will be provided for parking and storage; contractor will need to deliver and remove large materials on a daily basis, or provide an enclosed trailer or container at the parking zone. No fencing will be required around the project site, but the contractor will provide suitable barricades/barrels/traffic control to protect the work and vehicles and pedestrians. No materials should be left out in the project area overnight.
3. The existing 18" x 5'-6" concrete footing will be used. The contractor will be responsible for removing any column materials remaining above the footing and exposing the full area of the footing. Bidders shall core-drill into the existing footing and set (5) 54" x #4 rebar into the existing footing. Rebar shall be set with epoxy grout to a depth of 12" and the upper sections of the bars shall be tied in horizontally every 12" to the exposed height of 42". Embedded rebar shall be securely fastened to the #5 vertical rebar.
4. Metal corner guards will be provided and installed by Owner.
5. A minor amount of asphalt patching will be required at the edge of the driveway.
6. Pre-cast concrete pieces are available from:
Bassco Cast Stone
Elkmont, AL. 256-732-2228
www.basscocaststone.com

END OF ADDENDUM (page 1 of 2)

University of South Carolina
Non Mandatory Pre Bid Sign In Sheet
 Columbia, South Carolina

Project Name: USC Gateway Column Reconstruction
 Project Number: FY18000712
 Pre Bid Date & Time: June 21, 2018 10AM 1300 Pickens St Conf Rm 100C

SWMBE Contractor Indicate Below	Name	Company Name	Address	Phone #	Email
S W M B E	Jo Rodgers	Contract Bids Systems, LLC	114 Bunker Dr West Columbia, SC 29172	803-315-4848	wdavis43@sc.rr.com
S W M B E	Kenneth Boyles	KTD Masonry & Concrete	2727 Wellwood Columbia, SC 29166	803-862-7789	Kendaltdmasonryconcrete.com
S W M B E	MIKE SWEAT	AOS SPECIALTY CONTRACTORS	1224 TWO NOTCH RD LEX, SC 29063	803-798-6931	MIKE@AOSSC.ORG
S W M B E	Emily Jones	USC			efjones@fmc.sc.edu
S W M B E	Aimee Fish	USC	1300 pickens 29208	7-2261	arisha@fmc.sc.edu
S W M B E	Rickie Pendergrass	GORP CONSULT, LLC	1735 MT. HOLLY RD Rock Hill, SC 29730	704-519-9870	endergrass@yahoo.com
S W M B E					
S W M B E					
S W M B E					

***By signing this sheet you agree to receive information electronically.