

ADDENDUM NUMBER TWO

for

**USC Taylor House Phase II Renovations
Project No.: U-858-17-2
State Project Number: H27-Z366**

COLUMBIA, SOUTH CAROLINA

PREPARED BY:

The Boudreaux Group 1519 Sumter Street, Columbia, South Carolina 29201

DATE OF ISSUE: July 24, 2018

TO: ALL BIDDERS OF RECORD, CONSULTANTS, OWNER:

The following items shall take precedence over the drawings and specifications for the above named project and shall become a part of the contract documents. Where any item called for in the specifications, or indicated on the drawings, is not supplemented hereby, the original requirements shall remain in effect. Where any original item is amended, voided or superseded hereby, the provisions of such item not specifically amended, voided or superseded shall remain in effect.

CONTRACTOR SHALL ACKNOWLEDGE RECEIPT OF ADDENDUM.

This addendum consists of 2 pages and the following attachments: none

I. GENERAL CLARIFICATIONS:

1. **Temporary facilities:** add the following clarifications to the Specification Section 015000 "Temporary Facilities and Controls":
 - A. Contractor is to provide a temporary construction fence at the rear side of the Taylor House to separate construction work from day to day operational and pedestrian traffic at the adjacent USC School of Law. Provide approximately 200 linear feet of 6' tall galvanized steel with 2" posts, chain link fabric fencing with gate access for equipment and materials to enter. Provide privacy fence fabric screen on construction fence (knitted HDPE with edge reinforcement and grommets for attachment every 24", with minimum 75% blockage, green in color).
 - B. Contractor is to pay for all parking needs on the project. Contractor can coordinate with the city of Columbia for bagging meters if desired. No parking is provided at the Law School building for contractor use.

USC Taylor House Phase II Renovations
Addendum Number Two

II. Civil Drawings:

1. Add the following general note to C1.0 and C2.0:
“The existing water service that serves Taylor House is believed to be a 2” service supplied from Bull Street. Contractor is to locate existing service and cap existing service to abandon at water meter. Coordinate with City of Columbia on removal of existing water meter.”

END OF ADDENDUM