1206 FLORA STREET MILL

FIRE ALARM BID PACKAGE

USC # H27-I851 50001658-25 GMC # ACOL180003

PROJECT MANUAL

March 20,2020



1219 Wayne Street Columbia, SC 29201 803.766.1235

TABLE OF CONTENTS

PROJECT NAME:	USC - 1206 Flora Street Mill Renovation - Fire Alarm Bid Package	
· · · · · · · · · · · · · · · · · · ·	•	

PROJECT NUMBER: <u>H27-I851 50001658-25</u>

SECTION	NUMBER OF PAGES
Table of Contents	2
SE-310, Invitation for Design-Bid-Build Construction Services	1
AIA Document A701 Instructions to Bidders South Carolina Division of Procurement Services, Office of State Engineer Version	13
Bid Bond (AIA A310 or reference)	1
SE-330, Lump Sum Bid Form	6
AIA Document A101 Standard Form of Agreement between Owner and Contractor South Carolina Division of Procurement Services, Office of State Engineer Version	9
AIA Document A201 General Conditions of the Contract for Construction South Carolina Division of Procurement Services, Office of State Engineer Version	49
USC Supplemental General Conditions for Construction Projects	5
Contractor's One Year Guarantee	1
SE-355, Performance Bond	2
SE-357, Labor & Material Payment Bond	2
SE-380. Change Order to Construction Contract	1

TECHNICAL SPECIFICATIONS

END OF TABLE OF CONTENTS

DIVISIO	N 1 - GENERAL REQUIREMENTS	
00 01 26	Existing Hazardous Material Information	1
01 10 00	Summary	3
	Contract Modification Procedures	
	Payment Procedures	
	Project Management and Coordination	
	Construction Progress Documentation	
	Submittal Procedures	
	Quality Requirements	
	Special Inspections and Testing	
	References	
01 50 00	Temporary Facilities and Controls	4
01 60 00	Product Requirements	5
01 73 00	Execution	8
01 73 10	Cutting and Patching.	3
01 73 20	Selective Demolition	5
	Closeout Procedures.	
01 78 20	Operation and Maintenance Data	5
01 78 39	Project Record Documents	3
DIVISIO	N 07 – THERMAL AND MOISTURE PROTECTION	
07 84 13	Penetration Firestopping	8
DIVISIO	N 26 – ELECTRICAL	
26 05 00	Common Work Results for Electrical	6
26 05 19	Low-Voltage Electrical Power Conductors and Cables	5
26 05 26	Grounding and Bonding for Electrical Systems	5
	Hangers and Supports for Electrical Systems	
26 05 33	Raceway and Boxes for Electrical Systems	6
	Identification for Electrical Systems	
26 05 83	Equipment Wiring Connections	3
26 43 00	Surge Protective Devices	4
DIVISIO	N 28 – ELECTRONIC SAFETY AND SECURITY	
28 31 00	Fire Detection and Alarm	15

SE-310

INVITATION FOR DESIGN-BID-BUILD CONSTRUCTION SERVICES

AGENCY/OWNER: University of South Carolina	
PROJECT NAME: 1206 Flora Street Mill Renovation - Fire Al	larm Bid Package
PROJECT NUMBER: H27-I851 50001658-25 CONSTRUCT	ION COST RANGE: \$ <u>125,000</u> to \$ <u>150,000</u> N/A □
PROJECT LOCATION: 1206 Flora Street, Columbia, SC 2920	08
DESCRIPTION OF PROJECT/SERVICES: Installation of a n	new Fire Alarm System throughout the existing building. Small
and Minority Business participation is highly encouraged.	
BID/SUBMITTAL DUE DATE: 6/4/2020 TIM	IE: 10:00 am NUMBER OF COPIES: 1
PROJECT DELIVERY METHOD: Design-Bid-Build	
AGENCY PROJECT COORDINATOR: Kristen Moss	
EMAIL: kbmoss@mailbox.sc.edu	TELEPHONE: 803-777-5253 / 803-528-0250
DOCUMENTS MAY BE OBTAINED FROM: http://purchasi	ng.sc.edu - Solicitations and Awards
BID SECURITY IS REQUIRED IN AN AMOUNT NOT LES	SS THAN 5% OF THE BASE BID.
PERFORMANCE BOND REQUIRED? Yes ⊠ No □	PAYMENT BOND REQUIRED? Yes ⊠ No □
DOCUMENT DEPOSIT AMOUNT: \$ 0.00 IS	DEPOSIT REFUNDABLE Yes □ No □ N/A ⊠
Bidders must obtain Bidding Documents/Plans from the above listed source(s) to any other source do so at their own risk. All written communications with official	
Agency WILL NOT accept Bids send via email.	
All questions & correspondence concerning this Invitation shall be addressed to t	he A/E.
A/E NAME: Goodwyn, Mills & Cawood (GMC)	
A/E CONTACT: Marc Warren, AIA	
EMAIL: marc.warren@gmcnetwork.com	TELEPHONE: 803-766-1235
PRE-BID CONFERENCE: Yes No	MANDATORY ATTENDANCE: Yes ☐ No 🏻
PRE-BID DATE: _ 5/18/2020	TIME: 10:00 am
PRE-BID PLACE: Conference Call (800) 753-1965 /	
. ,	t in 20 min. increments - Call Chris Geary at (803)331-6761 to
	ed to 1 person per appointment. Use of attendee provided face
	distance rules apply fully. Site Visit Meeting location is at the
Front Entracne of 1206 Flora Street, Columbia, SC.	
BID OPENING PLACE: Bid openings will be limited to teleco	nference only: Telephone 800-753-1965/Access code 7777162
BID DELIVERY ADDRESSES:	
HAND-DELIVERY:	MAIL SERVICE:
Attn: Kristen Moss (Bid Enclsoed #H27-I851 50001658-25)	Attn: Kristen Moss (Bid Enclsoed #H27-I851 50001658-25)
University of South Carolina - Consolidated Services	University of South Carolina - Consolidated Service
925 Gadsden Street Columbia, SC 29208	925 Gadsden Street Columbia, SC 29208
IS PROJECT WITHIN AGENCY CONSTRUCTION CERTIFICATION	TION? (Agency MUST check one) Yes 🖂 No 🗌
APPROVED BY: (OSE Project Manager)	DATE:
(OSE Project Manager)	

South Carolina Division of Procurement Services, Office of the State Engineer Version of $\mathbf{AIA}^{\hat{n}}$ Document A701TM – 1997

Instructions to Bidders

This version of AIA Document A701[™]–1997 is modified by the South Carolina Division of Procurement Services, Office of the State Engineer ("SCOSE"). Publication of this version of AIA Document A701–1997 does not imply the American Institute of Architects' endorsement of any modification by SCOSE. A comparative version of AIA Document A701–1997 showing additions and deletions by SCOSE is available for review on the SCOSE Web site.

Cite this document as "AIA Document A701™— 1997, Instructions to Bidders — SCOSE Version," or "AIA Document A701™—1997 — SCOSE Version."

South Carolina Division of Procurement Services, Office of the State Engineer Version of \PAIA Document A701 $^{\text{TM}}$ – 1997

Instructions to Bidders

for the following PROJECT:
(Name and location or address)
1206 Flora Street Mill Renovation
Fire Alarm Bid Package
Columbia, SC 29208

THE OWNER:

(Name, legal status and address)
University of South Carolina
1300 Pickens Street
Columbia, SC 29208

The Owner is a Governmental Body of the State of South Carolina as defined by Title 11, Chapter 35 of the South Carolina Code of Laws, as amended.

THE ARCHITECT:

(Name, legal status and address)
Goodwyn Mills & Cawood
1219 Wayne Street
Columbia, SC 29201

TABLE OF ARTICLES

- 1 DEFINITIONS
- 2 BIDDER'S REPRESENTATIONS
- 3 BIDDING DOCUMENTS
- 4 BIDDING PROCEDURES
- 5 CONSIDERATION OF BIDS
- 6 POST-BID INFORMATION
- 7 PERFORMANCE BOND AND PAYMENT BOND
- 8 FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

This version of AIA Document A701-1997 is modified by the South Carolina Division of Procurement Services. Office of the State Engineer. Publication of this version of AIA Document A701 does not imply the American Institute of Architects' endorsement of any modification by South Carolina Division of Procurement Services, Office of the State Engineer. A comparative version of AIA Document A701-1997 showing additions and deletions by the South Carolina Division of Procurement Services. Office of the State Engineer is available for review on South Carolina state Web site.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

ARTICLE 1 DEFINITIONS

- § 1.1 Bidding Documents, collectively referred to as the **Invitation for Bids**, include the Bidding Requirements and the proposed Contract Documents. The Bidding Requirements consist of the Advertisement, Instructions to Bidders, Supplementary Instructions to Bidders, the Bid Form, the Notice of Intent to Award, and other sample bidding and contract forms. The proposed Contract Documents consist of the form of Agreement between the Owner and Contractor, Conditions of the Contract (General, Supplementary and other Conditions), Drawings, Specifications and all Addenda issued prior to execution of the Contract, and other documents set forth in the Bidding Documents. Any reference in this document to the Agreement between the Owner and Contractor, AIA Document A101, or some abbreviated reference thereof, shall mean AIA Document A101TM—2007 Standard Form of Agreement Between Owner and Contractor, SCOSE edition. Any reference in this document to the General Conditions of the Contract for Construction, AIA Document A201, or some abbreviated reference thereof, shall mean AIA Document A201TM—2007 General Conditions of the Contract for Construction, SCOSE edition.
- § 1.2 Definitions set forth in the General Conditions of the Contract for Construction, AIA Document A201, or in other Contract Documents are applicable to the Bidding Documents.
- § 1.3 Addenda are written or graphic instruments issued by the Architect prior to the execution of the Contract which modify or interpret the Bidding Documents by additions, deletions, clarifications or corrections.
- § 1.4 A Bid is a complete and properly executed proposal to do the Work for the sums stipulated therein, submitted in accordance with the Bidding Documents.
- § 1.5 The Base Bid is the sum stated in the Bid for which the Bidder offers to perform the Work described in the Bidding Documents as the base, to which Work may be added or from which Work may be deleted for sums stated in Alternate Bids.
- § 1.6 An Alternate Bid (or Alternate) is an amount stated in the Bid to be added to or deducted from the amount of the Base Bid if the corresponding change in the Work, as described in the Bidding Documents, is accepted.
- § 1.7 A Unit Price is an amount stated in the Bid as a price per unit of measurement for materials, equipment or services or a portion of the Work as described in the Bidding Documents.
- § 1.8 A Bidder is a person or entity who submits a Bid.
- § 1.9 A Sub-bidder is a person or entity who submits a bid to a Bidder for materials, equipment or labor for a portion of the Work.

ARTICLE 2 BIDDER'S REPRESENTATIONS

- § 2.1 The Bidder by submitting a Bid represents that:
- § 2.1.1 The Bidder has read and understands the Bidding Documents and Contract Documents, to the extent that such documentation relates to the Work for which the Bid is submitted, and for other portions of the Project, if any, being bid concurrently or presently under construction. Bidders are expected to examine the Bidding Documents and Contract Documents thoroughly and should request an explanation of any ambiguities, discrepancies, errors, omissions, or conflicting statements. Failure to do so will be at the Bidder's risk. Bidder assumes responsibility for any patent ambiguity that Bidder does not bring to the Owner's attention prior to bid opening.
- § 2.1.2 The Bid is made in compliance with the Bidding Documents.
- § 2.1.3 The Bidder has visited the site, become familiar with local conditions under which the Work is to be performed and has correlated the Bidder's personal observations with the requirements of the proposed Contract Documents and accepts full responsibility for any pre-bid existing conditions that would affect the Bid that could have been ascertained by a site visit. As provided in Regulation 19-445.2042(B), a bidder's failure to attend an advertised pre-bid conference will not excuse its responsibility for estimating properly the difficulty and cost of successfully performing the work, or for proceeding to successfully perform the work without additional expense to the State.

§ 2.1.4 The Bid is based upon the materials, equipment and systems required by the Bidding Documents without exception.

§ 2.1.5 CERTIFICATION OF INDEPENDENT PRICE DETERMINATION

GIVING FALSE, MISLEADING, OR INCOMPLETE INFORMATION ON THIS CERTIFICATION MAY RENDER YOU SUBJECT TO PROSECUTION UNDER SECTION 16-9-10 OF THE SOUTH CAROLINA CODE OF LAWS AND OTHER APPLICABLE LAWS.

§ 2.1.5.1 By submitting a bid, the bidder certifies that:

- .1 The prices in this bid have been arrived at independently, without, for the purpose of restricting competition, any consultation, communication, or agreement with any other bidder or competitor relating to:
 - .1 those prices;
 - .2 the intention to submit a bid; or
 - .3 the methods or factors used to calculate the prices offered.
- .2 The prices in this bid have not been and will not be knowingly disclosed by the bidder, directly or indirectly, to any other bidder or competitor before bid opening (in the case of a sealed bid solicitation) or contract award (in the case of a negotiated solicitation) unless otherwise required by law; and
- .3 No attempt has been made or will be made by the bidder to induce any other concern to submit or not to submit a bid for the purpose of restricting competition.
- § 2.1.5.2 Each signature on the bid is considered to be a certification by the signatory that the signatory:
 - .1 Is the person in the bidder's organization responsible for determining the prices being offered in this bid, and that the signatory has not participated and will not participate in any action contrary to Section 2.1.5.1 of this certification; or
 - .2 Has been authorized, in writing, to act as agent for the bidder's principals in certifying that those principals have not participated, and will not participate in any action contrary to Section 2.1.5.1 of this certification [As used in this subdivision, the term "principals" means the person(s) in the bidder's organization responsible for determining the prices offered in this bid];
 - .3 As an authorized agent, does certify that the principals referenced in Section 2.1.5.2.2 of this certification have not participated, and will not participate, in any action contrary to Section 2.1.5.1 of this certification; and
 - .4 As an agent, has not personally participated, and will not participate, in any action contrary to Section 2.1.5.1 of this certification.

§ 2.1.5.3 If the bidder deletes or modifies Section 2.1.5.1.2 of this certification, the bidder must furnish with its offer a signed statement setting forth in detail the circumstances of the disclosure.

§ 2.1.6 DRUG FREE WORKPLACE

By submitting a bid, the Bidder certifies that Bidder will maintain a drug free workplace in accordance with the requirements of Title 44, Chapter 107 of South Carolina Code of Laws, as amended.

§ 2.1.7 CERTIFICATION REGARDING DEBARMENT AND OTHER RESPONSIBILITY MATTERS

§ 2.1.7.1 By submitting a Bid, Bidder certifies, to the best of its knowledge and belief, that:

- .1 Bidder and/or any of its Principals-
 - .1 Are not presently debarred, suspended, proposed for debarment, or declared ineligible for the award of contracts by any state or federal agency;
 - .2 Have not, within a three-year period preceding this bid, been convicted of or had a civil judgment rendered against them for: commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, state, or local) contract or subcontract; violation of Federal or state antitrust statutes relating to the submission of bids; or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, tax evasion, or receiving stolen property; and
 - Are not presently indicted for, or otherwise criminally or civilly charged by a governmental entity with, commission of any of the offenses enumerated in Section 2.1.7.1.1.2 of this provision.
- .2 Bidder has not, within a three-year period preceding this bid, had one or more contracts terminated for default by any public (Federal, state, or local) entity.

- .3 "Principals," for the purposes of this certification, means officers; directors; owners; partners; and, persons having primary management or supervisory responsibilities within a business entity (e.g., general manager; plant manager; head of a subsidiary, division, or business segment, and similar positions).
- § 2.1.7.2 Bidder shall provide immediate written notice to the Procurement Officer if, at any time prior to contract award, Bidder learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- § 2.1.7.3 If Bidder is unable to certify the representations stated in Section 2.1.7.1, Bidder must submit a written explanation regarding its inability to make the certification. The certification will be considered in connection with a review of the Bidder's responsibility. Failure of the Bidder to furnish additional information as requested by the Procurement Officer may render the Bidder nonresponsible.
- § 2.1.7.4 Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render, in good faith, the certification required by Section 2.1.7.1 of this provision. The knowledge and information of a Bidder is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- § 2.1.7.5 The certification in Section 2.1.7.1 of this provision is a material representation of fact upon which reliance was placed when making award. If it is later determined that the Bidder knowingly or in bad faith rendered an erroneous certification, in addition to other remedies available to the State, the Procurement Officer may terminate the contract resulting from this solicitation for default.

§ 2.1.8 ETHICS CERTIFICATE

By submitting a bid, the bidder certifies that the bidder has and will comply with, and has not, and will not, induce a person to violate Title 8, Chapter 13 of the South Carolina Code of Laws, as amended (Ethics Act). The following statutes require special attention: Section 8-13-700, regarding use of official position for financial gain; Section 8-13-705, regarding gifts to influence action of public official; Section 8-13-720, regarding offering money for advice or assistance of public official; Sections 8-13-755 and 8-13-760, regarding restrictions on employment by former public official; Section 8-13-775, prohibiting public official with economic interests from acting on contracts; Section 8-13-790, regarding recovery of kickbacks; Section 8-13-1150, regarding statements to be filed by consultants; and Section 8-13-1342, regarding restrictions on contributions by contractor to candidate who participated in awarding of contract. The state may rescind any contract and recover all amounts expended as a result of any action taken in violation of this provision. If the contractor participates, directly or indirectly, in the evaluation or award of public contracts, including without limitation, change orders or task orders regarding a public contract, the contractor shall, if required by law to file such a statement, provide the statement required by Section 8-13-1150 to the procurement officer at the same time the law requires the statement to be filed.

§ 2.1.9 RESTRICTIONS APPLICABLE TO BIDDERS & GIFTS

Violation of these restrictions may result in disqualification of your bid, suspension or debarment, and may constitute a violation of the state Ethics Act.

- § 2.1.9.1 After issuance of the solicitation, bidder agrees not to discuss this procurement activity in any way with the Owner or its employees, agents or officials. All communications must be solely with the Procurement Officer. This restriction may be lifted by express written permission from the Procurement Officer. This restriction expires once a contract has been formed.
- § 2.1.9.2 Unless otherwise approved in writing by the Procurement Officer, bidder agrees not to give anything to the Owner, any affiliated organizations, or the employees, agents or officials of either, prior to award.
- § 2.1.9.3 Bidder acknowledges that the policy of the State is that a governmental body should not accept or solicit a gift, directly or indirectly, from a donor if the governmental body has reason to believe the donor has or is seeking to obtain contractual or other business or financial relationships with the governmental body. Regulation 19-445.2165(C) broadly defines the term donor.

§ 2.1.10 IRAN DIVESTMENT ACT CERTIFICATION

§ 2.1.10.1 The Iran Divestment Act List is a list published by the State Fiscal Accountability Authority pursuant to Section 11-57-310 that identifies persons engaged in investment activities in Iran. Currently, the list is available at the

following URL: http://procurement.sc.gov/PS/PS-iran-divestment.phtm(.) Section 11-57-310 requires the government to provide a person ninety days written notice before he is included on the list. The following representation, which is required by Section 11-57-330(A), is a material inducement for the State to award a contract to you.

- § 2.1.10.2 By signing your Offer, you certify that, as of the date you sign, you are not on the then-current version of the Iran Divestment Act List.
- § 2.1.10.3 You must notify the Procurement Officer immediately if, at any time before posting of a final statement of award, you are added to the Iran Divestment Act List.

§ 2.1.11 OPEN TRADE REPRESENTATION (JUN 2015)

By submitting an Offer, the Offeror represents that Offeror is not currently engaged in the boycott of a person or an entity based in or doing business with a jurisdiction with whom South Carolina can enjoy open trade, as defined in SC Code Section 11-35-5300. [02-2A083-1]

ARTICLE 3 BIDDING DOCUMENTS

§ 3.1 COPIES

- § 3.1.1 Bidders may obtain complete sets of the Bidding Documents from the issuing office designated in the Advertisement in the number and for the deposit sum, if any, stated therein. If so provided in the Advertisement, the deposit will be refunded to all plan holders who return the Bidding Documents in good condition within ten (10) days after receipt of Bids. The cost of replacement of missing or damaged documents will be deducted from the deposit. A Bidder receiving a Contract award may retain the Bidding Documents and the Bidder's deposit will be refunded.
- § 3.1.2 Bidders shall use complete sets of Bidding Documents in preparing Bids; neither the Owner nor Architect assumes responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bidding Documents.
- § 3.1.3 The Owner has made copies of the Bidding Documents available on the above terms for the purpose of obtaining Bids on the Work. No license or grant of use is conferred by issuance of copies of the Bidding Documents.
- § 3.1.4 All persons obtaining Bidding Documents from the issuing office designated in the Advertisement shall provide that office with Bidder's contact information to include the Bidder's name, telephone number, mailing address, and email address.

§ 3.2 INTERPRETATION OR CORRECTION OF BIDDING DOCUMENTS

- § 3.2.1 The Bidder shall carefully study and compare the Bidding Documents with each other, and with other work being bid concurrently or presently under construction to the extent that it relates to the Work for which the Bid is submitted, shall examine the site and local conditions, and shall at once report to the Architect errors, inconsistencies or ambiguities discovered.
- § 3.2.2 Bidders requiring clarification or interpretation of the Bidding Documents shall make a written request which shall reach the Architect at least ten (10) days prior to the date for receipt of Bids.
- § 3.2.3 Interpretations, corrections and changes of the Bidding Documents will be made by written Addendum. Interpretations, corrections and changes of the Bidding Documents made in any other manner will not be binding, and Bidders shall not rely upon them. As provided in Regulation 19-445.2042(B), nothing stated at the pre-bid conference shall change the Bidding Documents unless a change is made by written Addendum.

§ 3.3 SUBSTITUTIONS

- § 3.3.1 The materials, products and equipment described in the Bidding Documents establish a standard of required function, dimension, appearance and quality to be met by any proposed substitution. Reference in the Bidding Documents to a designated material, product, thing, or service by specific brand or trade name followed by the words "or equal" and "or approved equal" shall be interpreted as establishing a standard of quality and shall not be construed as limiting competition.
- § 3.3.2 No request to substitute materials, products, or equipment for materials, products, or equipment described in the Bidding Documents and no request for addition of a manufacturer or supplier to a list of approved manufacturers or suppliers in the Bidding Documents will be considered prior to receipt of Bids unless written request for approval has been received by the Architect at least ten (10) days prior to the date for receipt of Bids established in the Invitation for

Bids. Any subsequent extension of the date for receipt of Bids by addendum shall not extend the date for receipt of such requests unless the addendum so specifies. Such requests shall include the name of the material or equipment for which it is to be substituted and a complete description of the proposed substitution including drawings, performance and test data, and other information necessary for an evaluation. A statement setting forth changes in other materials, equipment or other portions of the Work, including changes in the work of other contracts that incorporation of the proposed substitution would require, shall be included. The burden of proof of the merit of the proposed substitution is upon the proposer. The Architect's decision of approval or disapproval of a proposed substitution shall be final.

- § 3.3.3 If the Architect approves a proposed substitution prior to receipt of Bids, such approval will be set forth in an Addendum. Bidders shall not rely upon approvals made in any other manner.
- § 3.3.4 No substitutions will be considered after the Contract award unless specifically provided for in the Contract Documents.

§ 3.4 ADDENDA

- § 3.4.1 Addenda will be transmitted to all who are known by the issuing office to have received a complete set of Bidding Documents.
- § 3.4.2 Copies of Addenda will be made available for inspection wherever Bidding Documents are on file for that purpose.
- § 3.4.3 Addenda will be issued no later than 120 hours prior to the time for receipt of Bids except an Addendum withdrawing the request for Bids or one which includes postponement of the date for receipt of Bids.
- § 3.4.4 Each Bidder shall ascertain prior to submitting a Bid that the Bidder has received all Addenda issued, and the Bidder shall acknowledge their receipt in the Bid.
- § 3.4.5 When the date for receipt of Bids is to be postponed and there is insufficient time to issue a written Addendum prior to the original Bid Date, the Owner will notify prospective Bidders by telephone or other appropriate means with immediate follow up with a written Addendum. This Addendum will verify the postponement of the original Bid Date and establish a new Bid Date. The new Bid Date will be no earlier than the fifth (5th) calendar day after the date of issuance of the Addendum postponing the original Bid Date.
- § 3.4.6 If an emergency or unanticipated event interrupts normal government processes so that bids cannot be received at the government office designated for receipt of bids by the exact time specified in the solicitation, the time specified for receipt of bids will be deemed to be extended to the same time of day specified in the solicitation on the first work day on which normal government processes resume. In lieu of an automatic extension, an Addendum may be issued to reschedule bid opening. If state offices are closed at the time a pre-bid or pre-proposal conference is scheduled, an Addendum will be issued to reschedule the conference.

ARTICLE 4 BIDDING PROCEDURES

§ 4.1 PREPARATION OF BIDS

- § 4.1.1 Bids shall be submitted on the SE-330 Bid Form included with the Bidding Documents.
- § 4.1.2 Any blanks on the bid form to be filled in by the Bidder shall be legibly executed in a non-erasable medium. Bids shall be signed in ink or other indelible media.
- § 4.1.3 Sums shall be expressed in figures.
- § 4.1.4 Interlineations, alterations and erasures must be initialed by the signer of the Bid. Bidder shall not make stipulations or qualify his bid in any manner not permitted on the bid form. An incomplete Bid or information not requested that is written on or attached to the Bid Form that could be considered a qualification of the Bid, may be cause for rejection of the Bid.
- § 4.1.5 All requested Alternates shall be bid. The failure of the bidder to indicate a price for an Alternate shall render the Bid non-responsive. Indicate the change to the Base Bid by entering the dollar amount and marking, as appropriate, the box for "ADD TO" or "DEDUCT FROM". If no change in the Base Bid is required, enter "ZERO" or "No Change."

For add alternates to the base bid, Subcontractor(s) listed on page BF-2 of the Bid Form to perform Alternate Work shall be used for both Alternates and Base Bid Work if Alternates are accepted.

- § 4.1.6 Pursuant to Title 11, Chapter 35, Section 3020(b)(i) of the South Carolina Code of Laws, as amended, Section 7 of the Bid Form sets forth a list of subcontractor specialties for which Bidder is required to identify only those subcontractors Bidder will use to perform the work of each listed specialty. Bidder must follow the Instructions in the Bid Form for filling out this section of the Bid Form. Failure to properly fill out Section 7 may result in rejection of Bidder's bid as non-responsive.
- § 4.1.7 Each copy of the Bid shall state the legal name of the Bidder and the nature of legal form of the Bidder. Each copy shall be signed by the person or persons legally authorized to bind the Bidder to a contract. A Bid submitted by an agent shall have a current power of attorney attached certifying the agent's authority to bind the Bidder.

§ 4.2 BID SECURITY

- § 4.2.1 If required by the Invitation for Bids, each Bid shall be accompanied by a bid security in an amount of not less than five percent of the Base Bid. The bid security shall be a bid bond or a certified cashier's check. The Bidder pledges to enter into a Contract with the Owner on the terms stated in the Bid and will, if required, furnish bonds covering the faithful performance of the Contract and payment of all obligations arising thereunder. Should the Bidder refuse to enter into such Contract or fail to furnish such bonds if required, the amount of the bid security shall be forfeited to the Owner as liquidated damages, not as a penalty.
- § 4.2.2 If a surety bond is required, it shall be written on AIA Document A310, Bid Bond, and the attorney-in-fact who executes the bond on behalf of the surety shall affix to the bond a certified and current copy of the power of attorney. The bid bond shall:
 - .1 be issued by a surety company licensed to do business in South Carolina;
 - .2 be issued by a surety company having, at a minimum, a "Best Rating" of "A" as stated in the most current publication of "Best's Key Rating Guide, Property-Casualty", which company shows a financial strength rating of at least five (5) times the contract price.
 - .3 be enclosed in the bid envelope at the time of Bid Opening, either in paper copy or as an electronic bid bond authorization number provided on the Bid Form and issued by a firm or organization authorized by the surety to receive, authenticate and issue binding electronic bid bonds on behalf the surety.
- § 4.2.3 By submitting a bid bond via an electronic bid bond authorization number on the Bid Form and signing the Bid Form, the Bidder certifies that an electronic bid bond has been executed by a Surety meeting the standards required by the Bidding Documents and the Bidder and Surety are firmly bound unto the State of South Carolina under the conditions provided in this Section 4.2.
- § 4.2.4 The Owner will have the right to retain the bid security of Bidders to whom an award is being considered until either (a) the Contract has been executed and performance and payment bonds, if required, have been furnished, or (b) the specified time has elapsed so that Bids may be withdrawn or (c) all Bids have been rejected.

§ 4.3 SUBMISSION OF BIDS

- § 4.3.1 All copies of the Bid, the bid security, if any, and any other documents required to be submitted with the Bid shall be enclosed in a sealed opaque envelope. The envelope shall, unless hand delivered by the Bidder, be addressed to the Owner's designated purchasing office as shown in the Invitation for Bids. The envelope shall be identified with the Project name, the Bidder's name and address and, if applicable, the designated portion of the Work for which the Bid is submitted. If the Bid is sent by mail or special delivery service (UPS, Federal Express, etc.), the envelope should be labeled "BID ENCLOSED" on the face thereof. Bidders hand delivering their Bids shall deliver Bids to the place of the Bid Opening as shown in the Invitation for Bids. Whether or not Bidders attend the Bid Opening, they shall give their Bids to the Owner's procurement officer or his/her designee as shown in the Invitation for Bids prior to the time of the Bid Opening.
- § 4.3.2 Bids shall be deposited at the designated location prior to the time and date for receipt of Bids. Bids received after the time and date for receipt of Bids will be returned unopened.
- § 4.3.3 The Bidder shall assume full responsibility for timely delivery at the location designated for receipt of Bids.

- § 4.3.4 Oral, telephonic, telegraphic, facsimile or other electronically transmitted bids will not be considered.
- § 4.3.5 The official time for receipt of Bids will be determined by reference to the clock designated by the Owner's procurement officer or his/her designee. The procurement officer conducting the Bid Opening will determine and announce that the deadline has arrived and no further Bids or bid modifications will be accepted. All Bids and bid modifications in the possession of the procurement officer at the time the announcement is completed will be timely, whether or not the bid envelope has been date/time stamped or otherwise marked by the procurement officer.

§ 4.4 MODIFICATION OR WITHDRAWAL OF BID

- § 4.4.1 A Bid may not be modified, withdrawn or canceled by the Bidder during the stipulated time period following the time and date designated for the receipt of Bids, and each Bidder so agrees in submitting a Bid.
- § 4.4.2 Prior to the time and date designated for receipt of Bids, a Bid submitted may be withdrawn in person or by written notice to the party receiving Bids at the place designated for receipt of Bids. Withdrawal by written notice shall be in writing over the signature of the Bidder.
- § 4.4.3 Withdrawn Bids may be resubmitted up to the date and time designated for the receipt of Bids provided that they are then fully in conformance with these Instructions to Bidders.
- § 4.4.4 Bid security, if required, shall be in an amount sufficient for the Bid as resubmitted.

ARTICLE 5 CONSIDERATION OF BIDS

§ 5.1 OPENING OF BIDS

- § 5.1.1 Bids received on time will be publicly opened and will be read aloud. The Owner will not read aloud Bids that the Owner determines, at the time of opening, to be non-responsive.
- § 5.1.2 At bid opening, the Owner will announce the date and location of the posting of the Notice of Intended Award.
- § 5.1.3 The Owner will send a copy of the final Bid Tabulation to all Bidders within ten (10) working days of the Bid Opening.
- § 5.1.4 If the Owner determines to award the Project, the Owner will, after posting a Notice of Intended Award, send a copy of the Notice to all Bidders.
- § 5.1.5 If only one Bid is received, the Owner will open and consider the Bid.

§ 5.2 REJECTION OF BIDS

- § 5.2.1 The Owner shall have the right to reject any or all Bids. A Bid not accompanied by a required bid security or by other data required by the Bidding Documents, or a Bid which is in any way incomplete or irregular is subject to rejection.
- § 5.2.2 The reasons for which the Owner will reject Bids include, but are not limited to:
 - .1 Failure by a Bidder to be represented at a Mandatory Pre-Bid Conference or site visit;
 - .2 Failure to deliver the Bid on time;
 - .3 Failure to comply with Bid Security requirements, except as expressly allowed by law;
 - .4 Listing an invalid electronic Bid Bond authorization number on the bid form;
 - .5 Failure to Bid an Alternate, except as expressly allowed by law;
 - .6 Failure to list qualified Subcontractors as required by law;
 - .7 Showing any material modification(s) or exception(s) qualifying the Bid;
 - .8 Faxing a Bid directly to the Owner or their representative; or
 - .9 Failure to include a properly executed Power-of-Attorney with the bid bond.
- § 5.2.3 The Owner may reject a Bid as nonresponsive if the prices bid are materially unbalanced between line items or sub-line items. A bid is materially unbalanced when it is based on prices significantly less than cost for some work and prices which are significantly overstated in relation to cost for other work, and if there is a reasonable doubt that the bid

will result in the lowest overall cost to the Owner even though it may be the low evaluated bid, or if it is so unbalanced as to be tantamount to allowing an advance payment.

§ 5.3 ACCEPTANCE OF BID (AWARD)

§ 5.3.1 It is the intent of the Owner to award a Contract to the lowest qualified Bidder provided the Bid has been submitted in accordance with the requirements of the Bidding Documents and does not exceed the funds available. The Owner shall have the right to waive informalities and irregularities in a Bid received and to accept the Bid which, in the Owner's judgment, is in the Owner's own best interests.

§ 5.3.2 The Owner shall have the right to accept Alternates in any order or combination, unless otherwise specifically provided in the Bidding Documents, and to determine the low Bidder on the basis of the sum of the Base Bid and Alternates accepted.

ARTICLE 6 POST-BID INFORMATION § 6.1 CONTRACTOR'S RESPONSIBILITY

Owner will make a determination of Bidder's responsibility before awarding a contract. Bidder shall provide all information and documentation requested by the Owner to support the Owner's evaluation of responsibility. Failure of Bidder to provide requested information is cause for the Owner, at its option, to determine the Bidder to be non-responsible.

§ 6.2 CLARIFICATION

Pursuant to Section 11-35-1520(8), the Procurement Officer may elect to communicate with a Bidder after opening for the purpose of clarifying either the Bid or the requirements of the Invitation for Bids. Such communications may be conducted only with Bidders who have submitted a Bid which obviously conforms in all material aspects to the Invitation for Bids and only in accordance with Appendix E (Paragraph A(6)) to the Manual for Planning and Execution of State Permanent Improvement, Part II. Clarification of a Bid must be documented in writing and included with the Bid. Clarifications may not be used to revise a Bid or the Invitation for Bids. [Section 11-35-1520(8); R.19-445.2080].

§ 6.3 SUBMITTALS

§ 6.3.1 The Bidder shall, as soon as practicable or as stipulated in the Bidding Documents, after notification of selection for the award of a Contract, furnish to the Owner through the Architect in writing:

- .1 a designation of the Work to be performed with the Bidder's own forces;
- .2 names of the manufacturers, products, and the suppliers of principal items or systems of materials and equipment proposed for the Work; and
- .3 names of persons or entities (including those who are to furnish materials or equipment fabricated to a special design) proposed for the principal portions of the Work.

ARTICLE 7 PERFORMANCE BOND AND PAYMENT BOND § 7.1 BOND REQUIREMENTS

§ 7.1.1 If stipulated in the Bidding Documents, the Bidder shall furnish bonds covering the faithful performance of the Contract and payment of all obligations arising thereunder. Bonds may be secured through the Bidder's usual sources.

§ 7.1.2 The performance and payment bonds shall conform to the requirements of Section 11.4 of the General Conditions of the Contract. If the furnishing of such bonds is stipulated in the Bidding Documents, the cost shall be included in the Bid.

§ 7.2 TIME OF DELIVERY CONTRACT, CERTIFICATES OF INSURANCE AND FORM OF BONDS

§ 7.2.1 After expiration of the protest period, the Owner will tender a signed Contract for Construction to the Bidder and the Bidder shall return the fully executed Contract for Construction to the Owner within seven (7) days thereafter. The Bidder shall deliver the required bonds and certificate of insurance to the Owner not later than three (3) days following the date of execution of the Contract. Failure to deliver these documents as required shall entitle the Owner to consider the Bidder's failure as a refusal to enter into a contract in accordance with the terms and conditions of the Bidder's Bid and to make claim on the Bid Security for re-procurement cost.

§ 7.2.2 The bonds shall be dated on or after the date of the Contract.

§ 7.2.3 The Bidder shall require the attorney-in-fact who executes the required bonds on behalf of the surety to affix thereto a certified and current copy of the power of attorney.

ARTICLE 8 FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

Unless otherwise required in the Bidding Documents, the Agreement for the Work will be written on AIA Document A101-2007, Standard Form of Agreement Between Owner and Contractor, SCOSE edition.

ARTICLE 9 MISCELLANEOUS

\S 9.1 Nonresident taxpayer registration affidavit income tax withholding important tax notice - nonresidents only

§ 9.1.1 Withholding Requirements for Payments to Nonresidents: Section 12-8-550 of the South Carolina Code of Laws requires persons hiring or contracting with a nonresident conducting a business or performing personal services of a temporary nature within South Carolina to withhold 2% of each payment made to the nonresident. The withholding requirement does not apply to (1) payments on purchase orders for tangible personal property when the payments are not accompanied by services to be performed in South Carolina, (2) nonresidents who are not conducting business in South Carolina, (3) nonresidents for contracts that do not exceed \$10,000 in a calendar year, or (4) payments to a nonresident who (a) registers with either the S.C. Department of Revenue or the S.C. Secretary of State and (b) submits a Nonresident Taxpayer Registration Affidavit - Income Tax Withholding, Form I-312 to the person letting the contract.

§ 9.1.2 For information about other withholding requirements (e.g., employee withholding), contact the Withholding Section at the South Carolina Department of Revenue at 803-898-5383 or visit the Department's website at: www.sctax.org

§ 9.1.3 This notice is for informational purposes only. This Owner does not administer and has no authority over tax issues. All registration questions should be directed to the License and Registration Section at 803-898-5872 or to the South Carolina Department of Revenue, Registration Unit, Columbia, S.C. 29214-0140. All withholding questions should be directed to the Withholding Section at 803-898-5383.

PLEASE SEE THE "NONRESIDENT TAXPAYER REGISTRATION AFFIDAVIT INCOME TAX WITHHOLDING" FORM (Available through SC Department of Revenue).

§ 9.2 CONTRACTOR LICENSING

Contractors and Subcontractors listed in Section 7 of the Bid Form who are required by the South Carolina Code of Laws to be licensed, must be licensed at the time of bidding.

§ 9.3 SUBMITTING CONFIDENTIAL INFORMATION

- § 9.3.1 For every document the Bidder submits in response to or with regard to this solicitation or request, the Bidder must separately mark with the word "CONFIDENTIAL" every page, or portion thereof, that the Bidder contends contains information that is exempt from public disclosure because it is either (a) a trade secret as defined in Section 30-4-40(a)(1), or (b) privileged & confidential, as that phrase is used in Section 11-35-410.
- § 9.3.2 For every document the Bidder submits in response to or with regard to this solicitation or request, the Bidder must separately mark with the words "TRADE SECRET" every page, or portion thereof, that the Bidder contends contains a trade secret as that term is defined by Section 39-8-20 of the Trade Secrets Act.
- § 9.3.3 For every document the Bidder submits in response to or with regard to this solicitation or request, the Bidder must separately mark with the word "PROTECTED" every page, or portion thereof, that the Bidder contends is protected by Section 11-35-1810.
- § 9.3.4 All markings must be conspicuous; use color, bold, underlining, or some other method in order to conspicuously distinguish the mark from the other text. Do not mark your entire bid as confidential, trade secret, or protected! If your bid, or any part thereof, is improperly marked as confidential or trade secret or protected, the State may, in its sole discretion, determine it nonresponsive. If only portions of a page are subject to some protection, do not mark the entire page.
- § 9.3.5 By submitting a response to this solicitation, Bidder (1) agrees to the public disclosure of every page of every document regarding this solicitation or request that was submitted at any time prior to entering into a contract

(including, but not limited to, documents contained in a response, documents submitted to clarify a response, & documents submitted during negotiations), unless the page is conspicuously marked "TRADE SECRET" or "CONFIDENTIAL" or "PROTECTED", (2) agrees that any information not marked, as required by these bidding instructions, as a "Trade Secret" is not a trade secret as defined by the Trade Secrets Act, & (3) agrees that, notwithstanding any claims or markings otherwise, any prices, commissions, discounts, or other financial figures used to determine the award, as well as the final contract amount, are subject to public disclosure.

§ 9.3.6 In determining whether to release documents, the State will detrimentally rely on the Bidders' marking of documents, as required by these bidding instructions, as being either "Confidential" or "Trade Secret" or "PROTECTED".

§ 9.3.7 By submitting a response, the Bidder agrees to defend, indemnify & hold harmless the State of South Carolina, its officers & employees, from every claim, demand, loss, expense, cost, damage or injury, including attorney's fees, arising out of or resulting from the State withholding information that Bidder marked as "confidential" or "trade secret" or "PROTECTED".

§ 9.4 POSTING OF INTENT TO AWARD

The SE-370, Notice of Intent to Award, will be posted at the following location:

Room or Area of Posting: Main Entrance / Lobby **Building Where Posted:** Procurement Office

Address of Building: 1300 Pickens Street, Columbia, SC 29208 WEB site address (if applicable): http://www.purchasing.sc.edu

Posting date will be announced at bid opening. In addition to posting the notice, the Owner will promptly send all responsive bidders a copy of the notice of intent to award and the final bid tabulation

§ 9.5 PROTEST OF SOLICITATION OR AWARD

§ 9.5.1 Any prospective bidder, offeror, contractor, or subcontractor who is aggrieved in connection with the solicitation of a contract shall protest within fifteen (15) days of the date of issuance of the applicable solicitation document at issue. Any actual bidder, offeror, contractor, or subcontractor who is aggrieved in connection with the intended award or award of a contract shall protest within ten (10) days of the date notification of intent to award is posted in accordance with Title 11, Chapter 35, Section 4210 of the South Carolina Code of Laws, as amended. A protest shall be in writing, shall set forth the grounds of the protest and the relief requested with enough particularity to give notice of the issues to be decided, and must be received by the State Engineer within the time provided.

§ 9.5.2 Any protest must be addressed to the CPO, Office of State Engineer, and submitted in writing:

- .1 by email to protest-ose@mmo.sc.gov,
- .2 by facsimile at 803-737-0639, or
- .3 by post or delivery to 1201 Main Street, Suite 600, Columbia, SC 29201.

By submitting a protest to the foregoing email address, you (and any person acting on your behalf) consent to receive communications regarding your protest (and any related protests) at the e-mail address from which you sent your protest.

§ 9.6 SOLICITATION INFORMATION FROM SOURCES OTHER THAN OFFICIAL SOURCE

South Carolina Business Opportunities (SCBO) is the official state government publication for State of South Carolina solicitations. Any information on State agency solicitations obtained from any other source is unofficial and any reliance placed on such information is at the bidder's sole risk and is without recourse under the South Carolina Consolidated Procurement Code.

§ 9.7 BUILDER'S RISK INSURANCE

Bidders are directed to Article 11.3 of the South Carolina Modified AIA Document A201, 2007 Edition, which, unless provided otherwise in the bid documents, requires the contractor to provide builder's risk insurance on the project.

§ 9.8 TAX CREDIT FOR SUBCONTRACTING WITH MINORITY FIRMS

§ 9.8.1 Pursuant to Section 12-6-3350, taxpayers, who utilize certified minority subcontractors, may take a tax credit equal to 4% of the payments they make to said subcontractors. The payments claimed must be based on work performed directly for a South Carolina state contract. The credit is limited to a maximum of fifty thousand dollars annually. The

taxpayer is eligible to claim the credit for 10 consecutive taxable years beginning with the taxable year in which the first payment is made to the subcontractor that qualifies for the credit. After the above ten consecutive taxable years, the taxpayer is no longer eligible for the credit. The credit may be claimed on Form TC-2, "Minority Business Credit." A copy of the subcontractor's certificate from the Governor's Office of Small and Minority Business (OSMBA) is to be attached to the contractor's income tax return.

§ 9.8.2 Taxpayers must maintain evidence of work performed for a State contract by the minority subcontractor. Questions regarding the tax credit and how to file are to be referred to: SC Department of Revenue, Research and Review, Phone: (803) 898-5786, Fax: (803) 898-5888.

§ 9.8.3 The subcontractor must be certified as to the criteria of a "Minority Firm" by the Governor's Office of Small and Minority Business Assistance (OSMBA). Certificates are issued to subcontractors upon successful completion of the certification process. Questions regarding subcontractor certification are to be referred to: Governor's Office of Small and Minority Business Assistance, Phone: (803) 734-0657, Fax: (803) 734-2498. Reference: SC §11-35-5010 – Definition for Minority Subcontractor & SC §11-35-5230 (B) – Regulations for Negotiating with State Minority Firms.

§ 9.9 OTHER SPECIAL CONDITIONS OF THE WORK

Bid Bond

CONTRACTOR:

(Name, legal status and address)

SURETY:

(Name, legal status and principal place of business)

OWNER:

(Name, legal status and address)

BOND AMOUNT: \$

PROJECT:

(Name, location or address, and Project number, if any) Blank

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and gives such bond or bonds as may be specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof; or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waives any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An Additions and Deletions Report that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences, Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

	(Contractor as Principal)	(Seal)
(Witness)	(Title)	
	(Surety)	(Seal)

Bidders shall submit bids on only Bid Form SE-330.

RID	SUBMITTED BY:
DID	(Bidder's Name)
BID	SUBMITTED TO: University of South Carolina
	(Owner's Name)
FOR	R: PROJECT NAME: USC - 1206 Flora Street Mill Renovation - Fire Alarm Bid Package
	PROJECT NUMBER: <u>H27-I851 50001658-25</u>
OFF	<u>ER</u>
§ 1.	In response to the Invitation for Construction Services and in compliance with the Instructions to Bidders for the above-named Project, the undersigned Bidder proposes and agrees, if this Bid is accepted, to enter into a Contract with the Owner on the terms included in the Bidding Documents, and to perform all Work as specified or indicated in the Bidding Documents, for the prices and within the time frames indicated in this Bid and in accordance with the other terms and conditions of the Bidding Documents.
§ 2.	Pursuant to SC Code § 11-35-3030(1), Bidder has submitted Bid Security as follows in the amount and form required by the Bidding Documents:
	☐ Bid Bond with Power of Attorney ☐ Electronic Bid Bond ☐ Cashier's Check
	(Bidder check one)
§ 3.	Bidder acknowledges the receipt of the following Addenda to the Bidding Documents and has incorporated the effects of said Addenda into this Bid: (Bidder, check all that apply. Note, there may be more boxes than actual addenda. Do not check boxes that do not apply)
	ADDENDA: \square #1 \square #2 \square #3 \square #4 \square #5
§ 4.	Bidder accepts all terms and conditions of the Invitation for Bids, including, without limitation, those dealing with the disposition of Bid Security. Bidder agrees that this Bid, including all Bid Alternates, if any, may not be revoked or withdrawn after the opening of bids, and shall remain open for acceptance for a period of <u>60</u> Days following the Bid Date, or for such longer period of time that Bidder may agree to in writing upon request of the Owner.
§ 5.	Bidder herewith offers to provide all labor, materials, equipment, tools of trades and labor, accessories, appliances, warranties and guarantees, and to pay all royalties, fees, permits, licenses and applicable taxes necessary to complete the following items of construction work:
§ 6.1	BASE BID WORK (as indicated in the Bidding Documents and generally described as follows): The project work consists of
	install a new Fire Sprinkler System throughout the existing building.
	\$, which sum is hereafter called the Base Bid. (Bidder to insert Base Bid Amount on line above)

BF – 1 SE-330

§ 7. LISTING OF PROPOSED SUBCONTRACTORS PURSUANT TO SECTION 3020(b)(i), CHAPTER 35, TITLE 11 OF THE SOUTH CAROLINA CODE OF LAWS, AS AMENDED

(See Instructions on the following page BF-2A)

Bidder shall use the below-listed Subcontractors in the performance of the Subcontractor Classification work listed:

(A) SUBCONTRACTOR LICENSE CLASSIFICATION or SUBCLASSIFICATION NAME (Completed by Owner)	(B) LICENSE CLASSIFICATION or SUBCLASSIFICATION ABBREVIATION (Completed by Owner)	(C) SUBCONTRACTOR and/or PRIME CONTRACTOR (Required - must be completed by Bidder)	(D) SUBCONTRACTOR'S and/or PRIME CONTRACTOR'S SC LICENSE NUMBER (Requested, but not Required)		
		ASE BID			
	ALTI	ERNATE #1			
	ALTI	ERNATE #2			
	ALTERNATE #3				

If a Bid Alternate is accepted, Subcontractors listed for the Bid Alternate shall be used for the work of both the Alternate and the Base Bid work.

BF – 2 SE-330

§ 8. LIST OF MANUFACTURERS, MATERIAL SUPPLIERS, AND SUBCONTRACTORS OTHER THAN SUBCONTRACTORS LISTED IN SECTION 7 ABOVE (FOR INFORMATION ONLY):

Pursuant to instructions in the Invitation for Construction Services, if any, Bidder will provide to Owner upon the Owner's request and within 24 hours of such request, a listing of manufacturers, material suppliers, and subcontractors, other than those listed in Section 7 above, that Bidder intends to use on the project. Bidder acknowledges and agrees that this list is provided for purposes of determining responsibility and not pursuant to the subcontractor listing requirements of SC Code

§ 9.

	•	1-35-3020(b)(i).
§ 9.	TI	ME OF CONTRACT PERFORMANCE AND LIQUIDATED DAMAGES
	a)	CONTRACT TIME
		Bidder agrees that the Date of Commencement of the Work shall be established in a Notice to Proceed to be issued by the Owner. Bidder agrees to substantially complete the Work within Calendar Days
		from the Date of Commencement, subject to adjustments as provided in the Contract Documents.
	b)	LIQUIDATED DAMAGES
		Bidder further agrees that from the compensation to be paid, the Owner shall retain as Liquidated Damages the amount of \$_250.00\$ for each Calendar Day the actual construction time required to achieve Substantial Completion exceeds the specified or adjusted time for Substantial Completion as provided in the Contract Documents. This amount is intended by the parties as the predetermined measure of compensation for actual damages, not as a penalty for nonperformance.
§ 10.	A(GREEMENTS
	a)	Bidder agrees that this bid is subject to the requirements of the laws of the State of South Carolina.
	b)	Bidder agrees that at any time prior to the issuance of the Notice to Proceed for this Project, this Project may be canceled for the convenience of, and without cost to, the State.
	c)	Bidder agrees that neither the State of South Carolina nor any of its agencies, employees or agents shall be responsible for any bid preparation costs, or any costs or charges of any type, should all bids be rejected or the Project canceled for any reason prior to the issuance of the Notice to Proceed.
§ 11.	EL	ECTRONIC BID BOND
	and	signing below, the Principal is affirming that the identified electronic bid bond has been executed and that the Principal Surety are firmly bound unto the State of South Carolina under the terms and conditions of the AIA Document A310, I Bond, included in the Bidding Documents.
	EL	ECTRONIC BID BOND NUMBER:
	SIC	GNATURE AND TITLE:

BF 3 SE-330

CONTRACTOR'S CLASSIFICATIONS AND SUBCLASSIFICATIONS WITH LIMITATION SC Contractor's License Number(s): Classification(s) & Limits: Subclassification(s) & Limits: By signing this Bid, the person signing reaffirms all representation and certification made by both the person signing and the Bidder, including without limitation, those appearing in Article 2 of the SCOSE Version of the AIA Document A701, Instructions to Bidders, is expressly incorporated by reference. BIDDER'S LEGAL NAME:____ ADDRESS:_____ TELEPHONE: EMAIL: SIGNATURE:_____ DATE:____ PRINT NAME:___ TITLE:____

BF 4 SE-330

South Carolina Division of Procurement Services, Office of the State Engineer Version of \mathbf{AIA}° Document $\mathbf{A}101^{\text{TM}}$ – 2007

Standard Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum

This version of AIA Document A101[™]–2007 is modified by the South Carolina Division of Procurement Services, Office of the State Engineer ("SCOSE"). Publication of this version of AIA Document A101–2007 does not imply the American Institute of Architects' endorsement of any modification by SCOSE. A comparative version of AIA Document A101–2007 showing additions and deletions by SCOSE is available for review on the SCOSE Web site.

Cite this document as "AIA Document A101™–2007, Standard Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum — SCOSE Version," or "AIA Document A101™–2007 — SCOSE Version."

South Carolina Division of Procurement Services, Office of the State Engineer Version of ${}^{\blacksquare}AIA^{\hat{}}$ Document A101 ${}^{\blacksquare}$ – 2007

Standard Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum

AGREEMENT made as of as of the day of in the year (In words, indicate day, month and year.)

BETWEEN the Owner:

(Name, legal status, address and other information)

The Owner is a Governmental Body of the State of South Carolina as defined by Title 11, Chapter 35 of the South Carolina Code of Laws, as amended.

and the Contractor: (Name, legal status, address and other information)

for the following Project: (Name, location and detailed description)

The Architect: (Name, legal status, address and other information)

This version of AIA Document A101-2007 is modified by the South Carolina Division of Procurement Services. Office of the State Engineer. Publication of this version of AIA Document A101 does not imply the American Institute of Architects' endorsement of any modification by South Carolina Division of Procurement Services, Office of the State Engineer. A comparative version of AIA Document A101-2007 showing additions and deletions by the South Carolina Division of Procurement Services. Office of the State Engineer is available for review on South Carolina state Web site.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

The Owner and Contractor agree as follows.

TABLE OF ARTICLES

- 1 THE CONTRACT DOCUMENTS
- 2 THE WORK OF THIS CONTRACT
- 3 DATE OF COMMENCEMENT AND SUBSTANTIAL COMPLETION
- 4 CONTRACT SUM
- 5 PAYMENTS
- 6 DISPUTE RESOLUTION
- 7 TERMINATION OR SUSPENSION
- 8 MISCELLANEOUS PROVISIONS
- 9 ENUMERATION OF CONTRACT DOCUMENTS
- 10 INSURANCE AND BONDS

ARTICLE 1 THE CONTRACT DOCUMENTS

§ 1.1 The Contract Documents consist of this Agreement, Conditions of the Contract (General, Supplementary and other Conditions), Drawings, Specifications, Addenda issued prior to execution of this Agreement, other documents listed in this Agreement and Modifications issued after execution of this Agreement, all of which form the Contract, and are as fully a part of the Contract as if attached to this Agreement or repeated herein. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior negotiations, representations or agreements, either written or oral. An enumeration of the Contract Documents, other than a Modification, appears in Article 9.

§ 1.2 Any reference in this document to the Agreement between the Owner and Contractor, AIA Document A101, or some abbreviated reference thereof, shall mean AIA Document A101TM-2007 Standard Form of Agreement Between Owner and Contractor, SCOSE edition. Any reference in this document to the General Conditions of the Contract for Construction, AIA Document A201, or some abbreviated reference thereof, shall mean AIA Document A201TM-2007 General Conditions of the Contract for Construction, SCOSE edition.

ARTICLE 2 THE WORK OF THIS CONTRACT

The Contractor shall fully execute the Work described in the Contract Documents, except as specifically indicated in the Contract Documents to be the responsibility of others.

ARTICLE 3 DATE OF COMMENCEMENT AND SUBSTANTIAL COMPLETION

§ 3.1 The Date of Commencement of the Work shall be the date fixed in a Notice to Proceed issued by the Owner. The Owner shall issue the Notice to Proceed to the Contractor in writing, no less than seven (7) days prior to the Date of Commencement. Unless otherwise provided elsewhere in the contract documents, and provided the contractor has secured all required insurance and surety bonds, the Contractor may commence work immediately after receipt of the Notice to Proceed.

§ 3.2 The Contract Time as provided in Section 9(a) of the Bid Form for this Project shall be measured from the Date of Commencement. The Contractor agrees that if the Contractor fails to achieve Substantial Completion of the Work within the Contract Time, the Owner shall be entitled to withhold or recover from the Contractor Liquidated Damages in the amounts set forth in Section 9(b) of the Bid Form, subject to adjustments of this Contract Time as provided in the Contract Documents.

§ 3.3 The Contractor shall achieve Substantial Completion of the entire Work not later than

) days from the date of commencement, or as follows:

not be reproduced prior to its completion.

(Insert number of calendar days. Alternatively, a calendar date may be used when coordinated with the date of commencement. If appropriate, insert requirements for earlier Substantial Completion of certain portions of the Work.)

, subject to adjustments of this Contract Time as provided in the Contract Documents. (Insert provisions, if any, for liquidated damages relating to failure to achieve Substantial Completion on time or for bonus payments for early completion of the Work.)

ARTICLE 4 CONTRACT SUM

§ 4.1 The Owner shall pay the Contractor the Contract Sum in current funds for the Contractor's performance of the Contract. The Contract Sum shall be (\$), subject to additions and deductions as provided in the Contract Documents.

§ 4.2 The Contract Sum is based upon the following alternates, if any, which are described in the Contract Documents and are hereby accepted by the Owner:

(State the numbers or other identification of accepted alternates. If the bidding or proposal documents permit the Owner to accept other alternates subsequent to the execution of this Agreement, attach a schedule of such other alternates showing the amount for each and the date when that amount expires.)

§ 4.3 Unit prices, if any:

(Identify and state the unit price; state quantity limitations, if any, to which the unit price will be applicable.)

Item Units and Limitations Price per Unit (\$0.00)

§ 4.4 Allowances included in the Contract Sum, if any: (*Identify allowance and state exclusions, if any, from the allowance price.*)

ltem Price

and is not for resale. This document is licensed by The American Institute of Architects for one-time use only, and may

under license number

ARTICLE 5 PAYMENTS

§ 5.1 PROGRESS PAYMENTS

- § 5.1.1 Based upon Applications for Payment submitted to the Architect and Owner by the Contractor and Certificates for Payment issued by the Architect, the Owner shall make progress payments on account of the Contract Sum to the Contractor as provided below and elsewhere in the Contract Documents.
- § 5.1.2 The period covered by each Application for Payment shall be one calendar month ending on the last day of the month, or as follows:
- § 5.1.3 The Owner shall make payment of the certified amount to the Contractor not later than twenty-one (21) days after receipt of the Application for Payment.
- § 5.1.4 Each Application for Payment shall be based on the most recent schedule of values submitted by the Contractor in accordance with the Contract Documents. The schedule of values shall allocate the entire Contract Sum among the various portions of the Work. The schedule of values shall be prepared in such form and supported by such data to substantiate its accuracy as the Architect may require. This schedule, unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's Applications for Payment.
- § 5.1.5 Applications for Payment shall show the percentage of completion of each portion of the Work as of the end of the period covered by the Application for Payment.
- § 5.1.6 Subject to other provisions of the Contract Documents and subject to Title 12, Chapter 8, Section 550 of the South Carolina Code of Laws, as amended (Withholding Requirements for Payments to Non-Residents), the amount of each progress payment shall be computed as follows:
 - Take that portion of the Contract Sum properly allocable to completed Work as determined by multiplying the percentage completion of each portion of the Work by the share of the Contract Sum allocated to that portion of the Work in the schedule of values, less retainage of three and one-half percent (3.5%). Pending final determination of cost to the Owner of changes in the Work, amounts not in dispute shall be included as provided in Section 7.3.9 of AIA Document A201TM–2007, General Conditions of the Contract for Construction;
 - Add that portion of the Contract Sum properly allocable to materials and equipment delivered and suitably stored at the site for subsequent incorporation in the completed construction (or, if approved in advance by the Owner, suitably stored off the site at a location agreed upon in writing), less retainage of three and one-half percent (3.5%);
 - .3 Subtract the aggregate of previous payments made by the Owner; and
 - Subtract amounts, if any, for which the Architect has withheld or nullified a Certificate for Payment as provided in Section 9.5 of AIA Document A201–2007.
- § 5.1.7 The progress payment amount determined in accordance with Section 5.1.6 shall be further modified under the following circumstances:
 - Add, upon Substantial Completion of the Work, a sum sufficient to increase the total payments to the full amount of the Contract Sum, less such amounts as the Architect shall determine for incomplete Work, retainage applicable to such work and unsettled claims; and (Section 9.8.5 of AIA Document A201–2007 requires release of applicable retainage upon Substantial Completion of Work with consent of surety, if any.)
 - Add, if final completion of the Work is thereafter materially delayed through no fault of the Contractor, any additional amounts payable in accordance with Section 9.10.3 of AIA Document A201–2007.
- § 5.1.8 Reduction or limitation of retainage, if any, shall be as set forth in S.C. Code Ann. § 11-35-3030(4). (If it is intended, prior to Substantial Completion of the entire Work, to reduce or limit the retainage resulting from the percentages inserted in Sections 5.1.6.1 and 5.1.6.2 above, and this is not explained elsewhere in the Contract Documents, insert here provisions for such reduction or limitation.)

§ 5.1.9 The Contractor shall not make advance payments to suppliers for materials or equipment which have not been delivered and stored at the site.

§ 5.2 FINAL PAYMENT

§ 5.2.1 Final payment, constituting the entire unpaid balance of the Contract Sum, shall be made by the Owner to the Contractor when

- .1 the Contractor has fully performed the Contract except for the Contractor's responsibility to correct Work as provided in Section 12.2.2 of AIA Document A201–2007, and to satisfy other requirements, if any, which extend beyond final payment; and
- .2 a final Certificate for Payment has been issued by the Architect.

§ 5.2.2 The Owner's final payment to the Contractor shall be made no later than twenty-one (21) days after the issuance of the Architect's final Certificate for Payment.

ARTICLE 6 DISPUTE RESOLUTION

§ 6.1 Reserved

ARTICLE 7 TERMINATION OR SUSPENSION

§ 7.1 The Contract may be terminated by the Owner or the Contractor as provided in Article 14 of AIA Document A201–2007.

§ 7.2 The Work may be suspended by the Owner as provided in Article 14 of AIA Document A201–2007.

ARTICLE 8 MISCELLANEOUS PROVISIONS

§ 8.1 Where reference is made in this Agreement to a provision of AIA Document A201–2007 or another Contract Document, the reference refers to that provision as amended or supplemented by other provisions of the Contract Documents.

§ 8.2 Reserved

§ 8.3 The Owner's representatives:

(Name, address and other information)

§ 8.3.1 The Owner designates the individual listed below as its Senior Representative ("Owner's Senior Representative"), which individual has the responsibility for and, subject to Section 7.2.1 of the General Conditions, the authority to resolve disputes under Section 15.6 of the General Conditions:

Name:	
Title:	
Address:	
Telephone:	FAX:
Email:	

§ 8.3.2 The Owner designates the individual listed below as its Owner's Representative, which individual has the authority and responsibility set forth in Section 2.1.1 of the General Conditions:

Name:	
Title:	
Address:	
Telephone:	FAX:
Email	

Init.

and is not for resale. This document is licensed by The American Institute of Architects for one-time use only, and may

under license number

§ 8.4 The Contractor's representation (Name, address and other inform			
	s the individual listed below as its Se all has the responsibility for and auth		
Name:			
Title:			
Address:			
Telephone:		FAX:	
Email:			
	s the individual listed below as its Coorth in Section 3.1.1 of the General G		ative, which individual has the
Name:			
Title:			
Address:			
Telephone:		FAX:	
Email:			
§ 8.5 Neither the Owner's nor the other party.	e Contractor's representative shall be	changed without ter	n days written notice to the
§ 8.6 Other provisions:			
§ 8.6.1 The Architect's representa	ative:		
Name:			
Title:			
Address:			
Telephone:		FAX:	
Email:			
ARTICLE 9 ENUMERATION OF C § 9.1 The Contract Documents, e sections below.	CONTRACT DOCUMENTS except for Modifications issued after	execution of this Ag	reement, are enumerated in the
§ 9.1.1 The Agreement is this exercise Contractor.	ecuted AIA Document A101–2007, S	Standard Form of Ag	reement Between Owner and
§ 9.1.2 The General Conditions a	re AIA Document A201–2007, Gene	eral Conditions of the	e Contract for Construction.
§ 9.1.3 The Supplementary and o	ther Conditions of the Contract:		
Document	Title	Date	Pages

(Either li	st the Specifications h	ere or refer to an exhibit at	tached to this A	greement.)	
:	Section	Title		Date	Pages
	e Drawings: st the Drawings here	or refer to an exhibit attach	ed to this Agree	ement.)	
1	Number	Title		Date	
§ 9.1.6 Th	e Addenda, if any:				

Portions of Addenda relating to bidding requirements are not part of the Contract Documents unless the bidding requirements are also enumerated in this Article 9.

§ 9.1.7 Additional documents, if any, forming part of the Contract Documents:

Title

AIA Document E201TM–2007, Digital Data Protocol Exhibit, if completed by the parties, or the following:

Date

§ 9.1.4 The Specifications:

Number

.2 Other documents, if any, listed below:

(List here any additional documents that are intended to form part of the Contract Documents. AIA Document A201–2007 provides that bidding requirements such as advertisement or invitation to bid, Instructions to Bidders, sample forms and the Contractor's bid are not part of the Contract Documents unless enumerated in this Agreement. They should be listed here only if intended to be part of the Contract Documents.)

SE-310, Invitation for Construction Services

Instructions to Bidders (AIA Document A701-1997)

Contractor's Bid (Completed Bid Form)

SE-370, Notice of Intent to Award

Certificate of Procurement Authority issued by the State Fiscal Accountability Authority

ARTICLE 10 INSURANCE AND BONDS

The Contractor shall purchase and maintain insurance and provide bonds as set forth in Article 11 of AIA Document A201–2007.

This Agreement entered into as of the day and year first written	
OWNER (Signature)	CONTRACTOR (Signature)
(Printed name and title)	(Printed name and title)

South Carolina Division of Procurement Services, Office of the State Engineer Version of $\mathbf{AIA}^{\hat{n}}$ Document A201TM – 2007

General Conditions of the Contract for Construction

This version of AIA Document A201[™]–2007 is modified by the South Carolina Division of Procurement Services, Office of the State Engineer ("SCOSE"). Publication of this version of AIA Document A201–2007 does not imply the American Institute of Architects' endorsement of any modification by SCOSE. A comparative version of AIA Document A201–2007 showing additions and deletions by SCOSE is available for review on the SCOSE Web site.

Cite this document as "AIA Document A201 $^{\text{TM}}$ -2007, General Conditions of the Contract for Construction—SCOSE Version," or "AIA Document A201 $^{\text{TM}}$ -2007 — SCOSE Version."

South Carolina Division of Procurement Services, Office of the State Engineer Version of $\mathbb{Z}AIA$ Document A201TM – 2007

General Conditions of the Contract for Construction

for the following PROJECT:

(Name and location or address)
1206 Flora Street Mill Renovation
Fire Alarm Bid Package
Columbia, SC 29208
THE OWNER:

(Name, legal status and address)

University of South Carolina 1300 Pickens Street Columbia, SC 29208

The Owner is a Governmental Body of the State of South Carolina as defined by Title 11, Chapter 35 of the South Carolina Code of Laws, as amended.

THE ARCHITECT:

(Name, legal status and address)
Goodwyn Mills & Cawood
1219 Wayne Street
Columbia. SC 29201

TABLE OF ARTICLES

- 1 GENERAL PROVISIONS
- 2 OWNER
- 3 CONTRACTOR
- 4 ARCHITECT
- 5 SUBCONTRACTORS
- 6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS
- 7 CHANGES IN THE WORK
- 8 TIME
- 9 PAYMENTS AND COMPLETION
- 10 PROTECTION OF PERSONS AND PROPERTY
- 11 INSURANCE AND BONDS
- 12 UNCOVERING AND CORRECTION OF WORK
- 13 MISCELLANEOUS PROVISIONS
- 14 TERMINATION OR SUSPENSION OF THE CONTRACT
- 15 CLAIMS AND DISPUTES

This version of AIA Document A201-2007 is modified by the South Carolina Division of Procurement. Office of the State Engineer. Publication of this version of AIA Document A201 does not imply the American Institute of Architects' endorsement of any modification by South Carolina Division of Procurement, Office of the State Engineer. A comparative version of AIA Document A201-2007 showing additions and deletions by the South Carolina Division of Procurement, Office of the State Engineer is available for review on the State of South Carolina Web site.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

INDEX

(Topics and numbers in bold are section headings.)

Acceptance of Nonconforming Work

9.6.6, 9.9.3, **12.3** Acceptance of Work

9.6.6, 9.8.2, 9.9.3, 9.10.1, 9.10.3, 12.3

Access to Work

3.16, 6.2.1, 12.1

Accident Prevention

10

Acts and Omissions

3.2, 3.3.2, 3.12.8, 3.18, 4.2.3, 8.3.1, 9.5.1, 10.2.5,

10.2.8, 13.4.2, 13.7, 14.1, 15.2

Addenda

1.1.1, 3.11

Additional Costs, Claims for

3.7.4, 3.7.5, 6.1.1, 7.3.7.5, 10.3, 15.1.4

Additional Inspections and Testing

9.4.2, 9.8.3, 12.2.1, **13.5**

Additional Insured

11.1.4

Additional Time, Claims for

3.2.4, 3.7.4, 3.7.5, 3.10.2, 8.3.2, **15.1.5**

Administration of the Contract

3.1.3, **4.2**, 9.4, 9.5

Advertisement or Invitation to Bid

1.1.1

Aesthetic Effect

4.2.13

Allowances

3.8, 7.3.8

All-risk Insurance

11.3.1, 11.3.1.1

Applications for Payment

4.2.5, 7.3.9, 9.2, **9.3**, 9.4, 9.5.1, 9.6.3, 9.7, 9.10,

11.1.3

Approvals

2.1.1, 2.2.2, 2.4, 3.1.3, 3.10.2, 3.12.8, 3.12.9, 3.12.10,

4.2.7, 9.3.2, 13.5.1

Arbitration

8.3.1, 11.3.10, 13.1, 15.3.2, **15.4**

ARCHITECT

Architect, Definition of

4.1.1

Architect, Extent of Authority

2.4, 3.12.7, 4.1, 4.2, 5.2, 6.3, 7.1.2, 7.3.7, 7.4, 9.2, 9.3.1, 9.4, 9.5, 9.6.3, 9.8, 9.10.1, 9.10.3, 12.1, 12.2.1,

13.5.1, 13.5.2, 14.2.2, 14.2.4, 15.1.3, 15.2.1

Architect, Limitations of Authority and

Responsibility

2.1.1, 3.12.4, 3.12.8, 3.12.10, 4.1.2, 4.2.1, 4.2.2,

4.2.3, 4.2.6, 4.2.7, 4.2.10, 4.2.12, 4.2.13, 5.2.1, 7.4,

9.4.2, 9.5.3, 9.6.4, 15.1.3, 15.2

Architect's Additional Services and Expenses 2.4, 11.3.1.1, 12.2.1, 13.5.2, 13.5.3, 14.2.4

Architect's Administration of the Contract

3.1.3, 4.2, 3.7.4, 15.2, 9.4.1, 9.5

Architect's Approvals

2.4, 3.1.3, 3.5, 3.10.2, 4.2.7

Architect's Authority to Reject Work

3.5, 4.2.6, 12.1.2, 12.2.1

Architect's Copyright

1.1.7, 1.5

Architect's Decisions

3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 4.2.14, 6.3,

7.3.7, 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4.1, 9.5, 9.8.4, 9.9.1,

13.5.2, 15.2, 15.3

Architect's Inspections

3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 13.5

Architect's Instructions

3.2.4, 3.3.1, 4.2.6, 4.2.7, 13.5.2

Architect's Interpretations

4.2.11, 4.2.12

Architect's Project Representative

4.2.10

Architect's Relationship with Contractor

1.1.2, 1.5, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2, 3.5,

3.7.4, 3.7.5, 3.9.2, 3.9.3, 3.10, 3.11, 3.12, 3.16, 3.18,

4.1.2, 4.1.3, 4.2, 5.2, 6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5,

9.7, 9.8, 9.9, 10.2.6, 10.3, 11.3.7, 12, 13.4.2, 13.5,

Architect's Relationship with Subcontractors

1.1.2, 4.2.3, 4.2.4, 4.2.6, 9.6.3, 9.6.4, 11.3.7

Architect's Representations

9.4.2, 9.5.1, 9.10.1

Architect's Site Visits

3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.5

Asbestos

10.3.1

Attorneys' Fees

3.18.1, 9.10.2, 10.3.3

Award of Separate Contracts

6.1.1.6.1.2

Award of Subcontracts and Other Contracts for **Portions of the Work**

5.2

Basic Definitions

1.1

Bidding Requirements

1.1.1, 5.2.1, 11.4.1

Binding Dispute Resolution

9.7, 11.3.9, 11.3.10, 13.1, 15.2.5, 15.2.6.1, 15.3.1,

15.3.2, 15.4.1

Boiler and Machinery Insurance

11.3.2

Bonds, Lien

7.3.7.4, 9.10.2, 9.10.3

Bonds, Performance, and Payment

7.3.7.4, 9.6.7, 9.10.3, 11.3.9, **11.4**

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

Building Permit

3.7.1

Capitalization

1.3

Certificate of Substantial Completion

9.8.3, 9.8.4, 9.8.5

Certificates for Payment

4.2.1, 4.2.5, 4.2.9, 9.3.3, **9.4**, 9.5, 9.6.1, 9.6.6, 9.7, 9.10.1, 9.10.3, 14.1.1.3, 14.2.4, 15.1.3

Certificates of Inspection, Testing or Approval 13.5.4

Certificates of Insurance

9.10.2, 11.1.3

Change Orders

1.1.1, 2.4, 3.4.2, 3.7.4, 3.8.2.3, 3.11, 3.12.8, 4.2.8, 5.2.3, 7.1.2, 7.1.3, **7.2**, 7.3.2, 7.3.6, 7.3.9, 7.3.10, 8.3.1, 9.3.1.1, 9.10.3, 10.3.2, 11.3.1.2, 11.3.4, 11.3.9, 12.1.2, 15.1.3

Change Orders, Definition of

7.2.1

CHANGES IN THE WORK

2.2.1, 3.11, 4.2.8, **7**, 7.2.1, 7.3.1, 7.4, 8.3.1, 9.3.1.1, 11.3.9

Claims, Definition of

15.1.1

CLAIMS AND DISPUTES

3.2.4, 6.1.1, 6.3, 7.3.9, 9.3.3, 9.10.4, 10.3.3, **15**, 15.4 Claims and Timely Assertion of Claims 15.4.1

Claims for Additional Cost

3.2.4, 3.7.4, 6.1.1, 7.3.9, 10.3.2, **15.1.4**

Claims for Additional Time

3.2.4, 3.7.4, 6.1.1, 8.3.2, 10.3.2, **15.1.5**

Concealed or Unknown Conditions, Claims for

Claims for Damages

3.2.4, 3.18, 6.1.1, 8.3.3, 9.5.1, 9.6.7, 10.3.3, 11.1.1, 11.3.5, 11.3.7, 14.1.3, 14.2.4, 15.1.6

Claims Subject to Arbitration

15.3.1, 15.4.1

Cleaning Up

3.15, 6.3

Commencement of the Work, Conditions Relating to 2.2.1, 3.2.2, 3.4.1, 3.7.1, 3.10.1, 3.12.6, 5.2.1, 5.2.3, 6.2.2, 8.1.2, 8.2.2, 8.3.1, 11.1, 11.3.1, 11.3.6, 11.4.1,

Commencement of the Work, Definition of

Communications Facilitating Contract Administration

3.9.1, 4.2.4

Completion, Conditions Relating to 3.4.1, 3.11, 3.15, 4.2.2, 4.2.9, 8.2, 9.4.2, 9.8, 9.9.1, 9.10, 12.2, 13.7, 14.1.2

COMPLETION, PAYMENTS AND

Completion, Substantial

4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, 9.8, 9.9.1, 9.10.3, 12.2, 13.7

Compliance with Laws

1.6, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 4.1.1, 9.6.4, 10.2.2, 11.1, 11.3, 13.1, 13.4, 13.5.1, 13.5.2, 13.6, 14.1.1,

14.2.1.3, 15.2.8, 15.4.2, 15.4.3

Concealed or Unknown Conditions

3.7.4, 4.2.8, 8.3.1, 10.3

Conditions of the Contract

1.1.1, 6.1.1, 6.1.4

Consent, Written

3.4.2, 3.7.4, 3.12.8, 3.14.2, 4.1.2, 9.3.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3, 11.3.1, 13.2, 13.4.2, 15.4.4.2

Consolidation or Joinder

15.4.4

CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

1.1.4.6

Construction Change Directive, Definition of

Construction Change Directives

1.1.1, 3.4.2, 3.12.8, 4.2.8, 7.1.1, 7.1.2, 7.1.3, **7.3**,

Construction Schedules, Contractor's 3.10, 3.12.1, 3.12.2, 6.1.3, 15.1.5.2

Contingent Assignment of Subcontracts

5.4. 14.2.2.2

Continuing Contract Performance

15.1.3

Contract, Definition of

1.1.2

CONTRACT, TERMINATION OR

SUSPENSION OF THE

5.4.1.1, 11.3.9, **14**

Contract Administration

3.1.3, 4, 9.4, 9.5

Contract Award and Execution, Conditions Relating

3.7.1, 3.10, 5.2, 6.1, 11.1.3, 11.3.6, 11.4.1

Contract Documents, Copies Furnished and Use of 1.5.2, 2.2.5, 5.3

Contract Documents, Definition of

1.1.1

Contract Sum

3.7.4, 3.8, 5.2.3, 7.2, 7.3, 7.4, **9.1**, 9.4.2, 9.5.1.4, 9.6.7, 9.7, 10.3.2, 11.3.1, 14.2.4, 14.3.2, 15.1.4, 15.2.5

Contract Sum, Definition of

9.1

Contract Time

3.7.4, 3.7.5, 3.10.2, 5.2.3, 7.2.1.3, 7.3.1, 7.3.5, 7.4, 8.1.1, 8.2.1, 8.3.1, 9.5.1, 9.7, 10.3.2, 12.1.1, 14.3.2, 15.1.5.1, 15.2.5

Contract Time, Definition of

8.1.1

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

CONTRACTOR

3

Contractor, Definition of

3.1, 6.1.2

Contractor's Construction Schedules

3.10, 3.12.1, 3.12.2, 6.1.3, 15.1.5.2

Contractor's Employees

3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, 10.2, 10.3,

11.1.1, 11.3.7, 14.1, 14.2.1.1

Contractor's Liability Insurance

11.1

Contractor's Relationship with Separate Contractors and Owner's Forces

3.12.5, 3.14.2, 4.2.4, 6, 11.3.7, 12.1.2, 12.2.4

Contractor's Relationship with Subcontractors

1.2.2, 3.3.2, 3.18.1, 3.18.2, 5, 9.6.2, 9.6.7, 9.10.2,

11.3.1.2, 11.3.7, 11.3.8

Contractor's Relationship with the Architect

1.1.2, 1.5, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2, 3.5, 3.7.4, 3.10, 3.11, 3.12, 3.16, 3.18, 4.1.3, 4.2, 5.2,

6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5, 9.7, 9.8, 9.9, 10.2.6, 10.3, 11.3.7, 12, 13.5, 15.1.2, 15.2.1

Contractor's Representations

3.2.1, 3.2.2, 3.5, 3.12.6, 6.2.2, 8.2.1, 9.3.3, 9.8.2

Contractor's Responsibility for Those Performing the Work

3.3.2, 3.18, 5.3, 6.1.3, 6.2, 9.5.1, 10.2.8

Contractor's Review of Contract Documents 3 2

Contractor's Right to Stop the Work

Contractor's Right to Terminate the Contract 14.1, 15.1.6

Contractor's Submittals

3.10, 3.11, 3.12.4, 4.2.7, 5.2.1, 5.2.3, 9.2, 9.3, 9.8.2, 9.8.3, 9.9.1, 9.10.2, 9.10.3, 11.1.3, 11.4.2

Contractor's Superintendent

3.9, 10.2.6

Contractor's Supervision and Construction

Procedures

1.2.2, 3.3, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4,

7.1.3, 7.3.5, 7.3.7, 8.2, 10, 12, 14, 15.1.3

Contractual Liability Insurance

11.1.1.8, 11.2

Coordination and Correlation

1.2, 3.2.1, 3.3.1, 3.10, 3.12.6, 6.1.3, 6.2.1

Copies Furnished of Drawings and Specifications

1.5, 2.2.5, 3.11

Copyrights

1.5, 3.17

Correction of Work

2.3, 2.4, 3.7.3, 9.4.2, 9.8.2, 9.8.3, 9.9.1, 12.1.2, 12.2

Correlation and Intent of the Contract Documents

1.2

Cost, Definition of

7.3.7

Costs

2.4, 3.2.4, 3.7.3, 3.8.2, 3.15.2, 5.4.2, 6.1.1, 6.2.3, 7.3.3.3, 7.3.7, 7.3.8, 7.3.9, 9.10.2, 10.3.2, 10.3.6, 11.3, 12.1.2, 12.2.1, 12.2.4, 13.5, 14

Cutting and Patching

3.14, 6.2.5

Damage to Construction of Owner or Separate

Contractors

3.14.2, 6.2.4, 10.2.1.2, 10.2.5, 10.4, 11.1.1, 11.3, 12.2.4

Damage to the Work

3.14.2, 9.9.1, 10.2.1.2, 10.2.5, 10.4, 11.3.1, 12.2.4

Damages, Claims for

 $3.2.4,\, 3.18,\, 6.1.1,\, 8.3.3,\, 9.5.1,\, 9.6.7,\, 10.3.3,\, 11.1.1,\,$

11.3.5, 11.3.7, 14.1.3, 14.2.4, 15.1.6

Damages for Delay

6.1.1, 8.3.3, 9.5.1.6, 9.7, 10.3.2

Date of Commencement of the Work, Definition of **8.1.2**

Date of Substantial Completion, Definition of

8.1.3

Day, Definition of

8.1.4

Decisions of the Architect

3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 15.2, 6.3, 7.3.7, 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4, 9.5.1, 9.8.4, 9.9.1,

13.5.2, 14.2.2, 14.2.4, 15.1, 15.2

Decisions to Withhold Certification

9.4.1, **9.5**, 9.7, 14.1.1.3

Defective or Nonconforming Work, Acceptance,

Rejection and Correction of

2.3, 2.4, 3.5, 4.2.6, 6.2.5, 9.5.1, 9.5.2, 9.6.6, 9.8.2,

9.9.3, 9.10.4, 12.2.1

Definitions

1.1, 2.1.1, 3.1.1, 3.5, 3.12.1, 3.12.2, 3.12.3, 4.1.1,

15.1.1, 5.1, 6.1.2, 7.2.1, 7.3.1, 8.1, 9.1, 9.8.1

Delays and Extensions of Time

3.2, 3.7.4, 5.2.3, 7.2.1, 7.3.1, 7.4, **8.3**, 9.5.1, 9.7,

10.3.2, 10.4, 14.3.2, 15.1.5, 15.2.5

Disputes

6.3, 7.3.9, 15.1, 15.2

Documents and Samples at the Site

3.11

Drawings, Definition of

1.1.5

Drawings and Specifications, Use and Ownership of 3.11

Effective Date of Insurance

8.2.2, 11.1.2

Emergencies

10.4, 14.1.1.2, 15.1.4

Employees, Contractor's

3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, 10.2,

10.3.3, 11.1.1, 11.3.7, 14.1, 14.2.1.1

Init.

Equipment, Labor, Materials or Insurance 1.1.3, 1.1.6, 3.4, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 3.18.1, 6.1.1, 7.3.7, 9.3.2, 9.8.4, 9.9.1, 9.10.2, **11** 4.2.6, 4.2.7, 5.2.1, 6.2.1, 7.3.7, 9.3.2, 9.3.3, 9.5.1.3, **Insurance, Boiler and Machinery** 9.10.2, 10.2.1, 10.2.4, 14.2.1.1, 14.2.1.2 Execution and Progress of the Work **Insurance, Contractor's Liability** 1.1.3, 1.2.1, 1.2.2, 2.2.3, 2.2.5, 3.1, 3.3.1, 3.4.1, 3.5, 11.1 3.7.1, 3.10.1, 3.12, 3.14, 4.2, 6.2.2, 7.1.3, 7.3.5, 8.2, Insurance. Effective Date of 9.5.1, 9.9.1, 10.2, 10.3, 12.2, 14.2, 14.3.1, 15.1.3 8.2.2, 11.1.2 Extensions of Time Insurance, Loss of Use 3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3, 7.4, 9.5.1, 9.7, 10.3.2, 11.3.3 10.4, 14.3, 15.1.5, 15.2.5 Insurance, Owner's Liability **Failure of Payment** 11.2 9.5.1.3, **9.7**, 9.10.2, 13.6, 14.1.1.3, 14.2.1.2 **Insurance, Property** Faulty Work 10.2.5, **11.3** Insurance, Stored Materials (See Defective or Nonconforming Work) **Final Completion and Final Payment** 9.3.2 4.2.1, 4.2.9, 9.8.2, **9.10**, 11.1.2, 11.1.3, 11.3.1, 11.3.5, INSURANCE AND BONDS 12.3, 14.2.4, 14.4.3 Financial Arrangements, Owner's Insurance Companies, Consent to Partial Occupancy 2.2.1, 13.2.2, 14.1.1.4 Fire and Extended Coverage Insurance Intent of the Contract Documents 11.3.1.1 1.2.1, 4.2.7, 4.2.12, 4.2.13, 7.4 **GENERAL PROVISIONS Interest** 13.6 **Governing Law** Interpretation 1.2.3, **1.4**, 4.1.1, 5.1, 6.1.2, 15.1.1 13.1 Guarantees (See Warranty) Interpretations, Written **Hazardous Materials** 4.2.11, 4.2.12, 15.1.4 10.2.4. **10.3** Judgment on Final Award Identification of Subcontractors and Suppliers 15.4.2 Labor and Materials, Equipment Indemnification 1.1.3, 1.1.6, **3.4**, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 3.17, **3.18**, 9.10.2, 10.3.3, 10.3.5, 10.3.6, 11.3.1.2, 4.2.6, 4.2.7, 5.2.1, 6.2.1, 7.3.7, 9.3.2, 9.3.3, 9.5.1.3, 11.3.7 9.10.2, 10.2.1, 10.2.4, 14.2.1.1, 14.2.1.2 Information and Services Required of the Owner Labor Disputes 2.1.2, **2.2**, 3.2.2, 3.12.4, 3.12.10, 6.1.3, 6.1.4, 6.2.5, 8.3.1 9.6.1, 9.6.4, 9.9.2, 9.10.3, 10.3.3, 11.2, 11.4, 13.5.1, Laws and Regulations 13.5.2, 14.1.1.4, 14.1.4, 15.1.3 1.5, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 4.1.1, 9.6.4, 9.9.1, **Initial Decision** 10.2.2, 11.1.1, 11.3, 13.1, 13.4, 13.5.1, 13.5.2, 13.6, 15.2 14, 15.2.8, 15.4 Liens Initial Decision Maker, Decisions 2.1.2, 9.3.3, 9.10.2, 9.10.4, 15.2.8 Limitations, Statutes of 14.2.2, 14.2.4, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5 Initial Decision Maker, Extent of Authority 12.2.5, 13.7, 15.4.1.1 14.2.2, 14.2.4, 15.1.3, 15.2.1, 15.2.2, 15.2.3, 15.2.4, Limitations of Liability 2.3, 3.2.2, 3.5, 3.12.10, 3.17, 3.18.1, 4.2.6, 4.2.7, **Injury or Damage to Person or Property** 4.2.12, 6.2.2, 9.4.2, 9.6.4, 9.6.7, 10.2.5, 10.3.3, **10.2.8**, 10.4 11.1.2, 11.2, 11.3.7, 12.2.5, 13.4.2 Inspections Limitations of Time 3.1.3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3, 2.1.2, 2.2, 2.4, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2.7, 9.9.2, 9.10.1, 12.2.1, 13.5 5.2, 5.3, 5.4.1, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3, Instructions to Bidders 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 11.1.3, 11.3.1.5, 1 1 1 11.3.6, 11.3.10, 12.2, 13.5, 13.7, 14, 15 Instructions to the Contractor **Loss of Use Insurance** 3.2.4, 3.3.1, 3.8.1, 5.2.1, 7, 8.2.2, 12, 13.5.2 11.3.3 Instruments of Service, Definition of Material Suppliers 1.5, 3.12.1, 4.2.4, 4.2.6, 5.2.1, 9.3, 9.4.2, 9.6, 9.10.5

Init.

Materials, Hazardous

10.2.4, **10.3**

Materials, Labor, Equipment and

1.1.3, 1.1.6, 1.5.1, 3.4.1, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 4.2.6, 4.2.7, 5.2.1, 6.2.1, 7.3.7, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1.2, 10.2.4, 14.2.1.1, 14.2.1.2

Means, Methods, Techniques, Sequences and

Procedures of Construction

3.3.1, 3.12.10, 4.2.2, 4.2.7, 9.4.2

Mechanic's Lien

2.1.2, 15.2.8

Mediation

8.3.1, 10.3.5, 10.3.6, 15.2.1, 15.2.5, 15.2.6, **15.3**, 15.4.1

Minor Changes in the Work

1.1.1, 3.12.8, 4.2.8, 7.1, 7.4

MISCELLANEOUS PROVISIONS

13

Modifications, Definition of

1.1.1

Modifications to the Contract

1.1.1, 1.1.2, 3.11, 4.1.2, 4.2.1, 5.2.3, 7, 8.3.1, 9.7, 10.3.2, 11.3.1

Mutual Responsibility

6.2

Nonconforming Work, Acceptance of

9.6.6, 9.9.3, 12.3

Nonconforming Work, Rejection and Correction of 2.3, 2.4, 3.5, 4.2.6, 6.2.4, 9.5.1, 9.8.2, 9.9.3, 9.10.4, 12.2.1

Notice

2.2.1, 2.3, 2.4, 3.2.4, 3.3.1, 3.7.2, 3.12.9, 5.2.1, 9.7, 9.10, 10.2.2, 11.1.3, 12.2.2.1, 13.3, 13.5.1, 13.5.2, 14.1, 14.2, 15.2.8, 15.4.1

Notice, Written

2.3, 2.4, 3.3.1, 3.9.2, 3.12.9, 3.12.10, 5.2.1, 9.7, 9.10, 10.2.2, 10.3, 11.1.3, 11.3.6, 12.2.2.1, **13.3**, 14, 15.2.8, 15.4.1

Notice of Claims

3.7.4, 10.2.8, **15.1.2**, 15.4

Notice of Testing and Inspections

13.5.1, 13.5.2

Observations, Contractor's

3.2, 3.7.4

Occupancy

2.2.2, 9.6.6, 9.8, 11.3.1.5

Orders, Written

1.1.1, 2.3, 3.9.2, 7, 8.2.2, 11.3.9, 12.1, 12.2.2.1, 13.5.2, 14.3.1

OWNER

2

Owner, Definition of

2.1.1

Owner, Information and Services Required of the

2.1.2, **2.2**, 3.2.2, 3.12.10, 6.1.3, 6.1.4, 6.2.5, 9.3.2, 9.6.1, 9.6.4, 9.9.2, 9.10.3, 10.3.3, 11.2, 11.3, 13.5.1, 13.5.2, 14.1.1.4, 14.1.4, 15.1.3

Owner's Authority

1.5, 2.1.1, 2.3, 2.4, 3.4.2, 3.8.1, 3.12.10, 3.14.2, 4.1.2, 4.1.3, 4.2.4, 4.2.9, 5.2.1, 5.2.4, 5.4.1, 6.1, 6.3, 7.2.1, 7.3.1, 8.2.2, 8.3.1, 9.3.1, 9.3.2, 9.5.1, 9.6.4, 9.9.1, 9.10.2, 10.3, 11.1.3, 11.3.3, 11.3.10, 12.2.2, 12.3,

13.2.2, 14.3, 14.4, 15.2.7 Owner's Financial Capability

2.2.1, 13.2.2, 14.1.1.4

Owner's Liability Insurance

11.2

Owner's Relationship with Subcontractors 1.1.2, 5.2, 5.3, 5.4, 9.6.4, 9.10.2, 14.2.2

Owner's Right to Carry Out the Work 2.4, 14.2.2

Owner's Right to Clean Up

6.3

Owner's Right to Perform Construction and to

Award Separate Contracts

6.1

Owner's Right to Stop the Work

2.3

Owner's Right to Suspend the Work 14.3

Owner's Right to Terminate the Contract

14.2

Ownership and Use of Drawings, Specifications and Other Instruments of Service

1.1.1, 1.1.6, 1.1.7, **1.5**, 2.2.5, 3.2.2, 3.11, 3.17, 4.2.12, 5.3

Partial Occupancy or Use

9.6.6, **9.9**, 11.3.1.5

Patching, Cutting and

3.14, 6.2.5

Patents

3.17

Payment, Applications for

4.2.5, 7.3.9, 9.2, **9.3**, 9.4, 9.5, 9.6.3, 9.7, 9.8.5, 9.10.1, 14.2.3, 14.2.4, 14.4.3

Payment, Certificates for

4.2.5, 4.2.9, 9.3.3, **9.4**, 9.5, 9.6.1, 9.6.6, 9.7, 9.10.1, 9.10.3, 13.7, 14.1.1.3, 14.2.4

Payment, Failure of

9.5.1.3, **9.7**, 9.10.2, 13.6, 14.1.1.3, 14.2.1.2

Payment, Final

4.2.1, 4.2.9, 9.8.2, 9.10, 11.1.2, 11.1.3, 11.4.1, 12.3,

13.7, 14.2.4, 14.4.3

Payment Bond, Performance Bond and

7.3.7.4, 9.6.7, 9.10.3, **11.4**

Payments, Progress

9.3, **9.6**, 9.8.5, 9.10.3, 13.6, 14.2.3, 15.1.3

PAYMENTS AND COMPLETION

9

Payments to Subcontractors

5.4.2, 9.5.1.3, 9.6.2, 9.6.3, 9.6.4, 9.6.7, 14.2.1.2

PCB 10.3.1

Performance Bond and Payment Bond

7.3.7.4, 9.6.7, 9.10.3, **11.4**

Permits, Fees, Notices and Compliance with Laws

2.2.2, **3.7**, 3.13, 7.3.7.4, 10.2.2

PERSONS AND PROPERTY, PROTECTION OF

10

Polychlorinated Biphenyl

10.3.1

Product Data, Definition of

3.12.2

Product Data and Samples, Shop Drawings

3.11, **3.12**, 4.2.7

Progress and Completion

4.2.2, **8.2**, 9.8, 9.9.1, 14.1.4, 15.1.3

Progress Payments

9.3, **9.6**, 9.8.5, 9.10.3, 13.6, 14.2.3, 15.1.3

Project, Definition of

1.1.4

Project Representatives

4.2.10

Property Insurance

10.2.5, **11.3**

PROTECTION OF PERSONS AND PROPERTY

10

Regulations and Laws

1.5, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 4.1.1, 9.6.4, 9.9.1, 10.2.2, 11.1, 11.4, 13.1, 13.4, 13.5.1, 13.5.2, 13.6, 14,

15.2.8, 15.4

Rejection of Work

3.5, 4.2.6, 12.2.1

Releases and Waivers of Liens

9.10.2

Representations

3.2.1, 3.5, 3.12.6, 6.2.2, 8.2.1, 9.3.3, 9.4.2, 9.5.1,

9.8.2, 9.10.1

Representatives

2.1.1, 3.1.1, 3.9, 4.1.1, 4.2.1, 4.2.2, 4.2.10, 5.1.1,

5.1.2, 13.2.1

Responsibility for Those Performing the Work 3.3.2, 3.18, 4.2.3, 5.3, 6.1.3, 6.2, 6.3, 9.5.1, 10

Retainage

9.3.1, 9.6.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3

Review of Contract Documents and Field

Conditions by Contractor

3.2, 3.12.7, 6.1.3

Review of Contractor's Submittals by Owner and

Architect

3.10.1, 3.10.2, 3.11, 3.12, 4.2, 5.2, 6.1.3, 9.2, 9.8.2

Review of Shop Drawings, Product Data and

Samples by Contractor

3.12

Rights and Remedies

1.1.2, 2.3, 2.4, 3.5, 3.7.4, 3.15.2, 4.2.6, 5.3, 5.4, 6.1, 6.3, 7.3.1, 8.3, 9.5.1, 9.7, 10.2.5, 10.3, 12.2.2, 12.2.4,

13.4, 14, 15.4

Royalties, Patents and Copyrights

3.17

Rules and Notices for Arbitration

15.4.1

Safety of Persons and Property

10.2, 10.4

Safety Precautions and Programs

3.3.1, 4.2.2, 4.2.7, 5.3, **10.1**, 10.2, 10.4

Samples, Definition of

3.12.3

Samples, Shop Drawings, Product Data and

3.11, **3.12**, 4.2.7

Samples at the Site, Documents and

3.11

Schedule of Values

9.2, 9.3.1

Schedules, Construction

3.10, 3.12.1, 3.12.2, 6.1.3, 15.1.5.2

Separate Contracts and Contractors

1.1.4, 3.12.5, 3.14.2, 4.2.4, 4.2.7, 6, 8.3.1, 12.1.2

Shop Drawings, Definition of

3.12.1

Shop Drawings, Product Data and Samples

3.11, **3.12**, 4.2.7

Site, Use of

3.13, 6.1.1, 6.2.1

Site Inspections

3.2.2, 3.3.3, 3.7.1, 3.7.4, 4.2, 9.4.2, 9.10.1, 13.5

Site Visits, Architect's

3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.5

Special Inspections and Testing

4.2.6, 12.2.1, 13.5

Specifications, Definition of

1.1.6

Specifications

1.1.1, **1.1.6**, 1.2.2, 1.5, 3.11, 3.12.10, 3.17, 4.2.14

Statute of Limitations

13.7, 15.4.1.1

Stopping the Work

2.3, 9.7, 10.3, 14.1

Stored Materials

6.2.1, 9.3.2, 10.2.1.2, 10.2.4

Subcontractor, Definition of

5.1.1

SUBCONTRACTORS

5

Subcontractors, Work by

1.2.2, 3.3.2, 3.12.1, 4.2.3, 5.2.3, 5.3, 5.4, 9.3.1.2, 9.6.7

Subcontractual Relations

5.3, 5.4, 9.3.1.2, 9.6, 9.10, 10.2.1, 14.1, 14.2.1

Submittals

3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 7.3.7, 9.2, 9.3,

9.8, 9.9.1, 9.10.2, 9.10.3, 11.1.3

Submittal Schedule

3.10.2, 3.12.5, 4.2.7

Init.

American Institute of Architects. All rights reserved. South Carolina Division of Procurement Services, Office of the State Engineer Version of AIA Document A201™–2007.Copyright © 2016 by The American Institute of Architects. All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was created on 11/21/2016 12:24:14 under license number 2009500317 , and is not for resale. This document is licensed by The American Institute of Architects for one-time use only, and may not be reproduced prior to its completion.

Subrogation, Waivers of

6.1.1, 11.3.7

Substantial Completion

4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, **9.8**, 9.9.1, 9.10.3, 12.2, 13.7

Substantial Completion, Definition of

Substitution of Subcontractors

5.2.3, 5.2.4

Substitution of Architect

4.1.3

Substitutions of Materials

3.4.2, 3.5, 7.3.8

Sub-subcontractor, Definition of

5.1.2

Subsurface Conditions

3.7.4

Successors and Assigns

13.2

Superintendent

3.9, 10.2.6

Supervision and Construction Procedures

1.2.2, **3.3**, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4, 7.1.3, 7.3.7, 8.2, 8.3.1, 9.4.2, 10, 12, 14, 15.1.3

Surety

5.4.1.2, 9.8.5, 9.10.2, 9.10.3, 14.2.2, 15.2.7

Surety, Consent of 9.10.2, 9.10.3 Surveys

Suspension by the Owner for Convenience

Suspension of the Work

5.4.2, 14.3

Suspension or Termination of the Contract

5.4.1.1, 14

Taxes

3.6, 3.8.2.1, 7.3.7.4

Termination by the Contractor

14.1. 15.1.6

Termination by the Owner for Cause

5.4.1.1, **14.2,** 15.1.6

Termination by the Owner for Convenience

14.4

Termination of the Architect

4.1.3

Termination of the Contractor

14.2.2

TERMINATION OR SUSPENSION OF THE

CONTRACT

14

Tests and Inspections

3.1.3, 3.3.3, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3, 9.9.2,

9.10.1, 10.3.2, 11.4.1, 12.2.1, **13.5**

TIME

8

Time, Delays and Extensions of

3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3.1, 7.4, **8.3**, 9.5.1, 9.7,

10.3.2, 10.4, 14.3.2, 15.1.5, 15.2.5

Time Limits

2.1.2, 2.2, 2.4, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2,

5.2, 5.3, 5.4, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3, 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 11.1.3, 12.2, 13.5,

13.7, 14, 15.1.2, 15.4

Time Limits on Claims

3.7.4, 10.2.8, **13.7**, 15.1.2

Title to Work

9.3.2, 9.3.3

Transmission of Data in Digital Form

UNCOVERING AND CORRECTION OF

WORK

12

Uncovering of Work

12.1

Unforeseen Conditions, Concealed or Unknown

3.7.4, 8.3.1, 10.3

Unit Prices

7.3.3.2, 7.3.4

Use of Documents

1.1.1, 1.5, 2.2.5, 3.12.6, 5.3

Use of Site

3.13, 6.1.1, 6.2.1

Values, Schedule of

9.2, 9.3.1

Waiver of Claims by the Architect

13.4.2

Waiver of Claims by the Contractor

9.10.5, 13.4.2, 15.1.6

Waiver of Claims by the Owner

9.9.3, 9.10.3, 9.10.4, 12.2.2.1, 13.4.2, 14.2.4, 15.1.6

Waiver of Consequential Damages

14.2.4, 15.1.6

Waiver of Liens

9.10.2, 9.10.4

Waivers of Subrogation

6.1.1, **11.3.7**

Warranty

3.5, 4.2.9, 9.3.3, 9.8.4, 9.9.1, 9.10.4, 12.2.2, 13.7

Weather Delays

15.1.5.2

Work, Definition of

1.1.3

Written Consent

1.5.2, 3.4.2, 3.7.4, 3.12.8, 3.14.2, 4.1.2, 9.3.2, 9.8.5,

9.9.1, 9.10.2, 9.10.3, 11.4.1, 13.2, 13.4.2, 15.4.4.2

Written Interpretations

4.2.11, 4.2.12

Written Notice

2.3, 2.4, 3.3.1, 3.9, 3.12.9, 3.12.10, 5.2.1, 8.2.2, 9.7,

9.10, 10.2.2, 10.3, 11.1.3, 12.2.2, 12.2.4, **13.3**, 14,

15.4.1

ARTICLE 1 GENERAL PROVISIONS

§ 1.1 BASIC DEFINITIONS

§ 1.1.1 THE CONTRACT DOCUMENTS

The Contract Documents are enumerated in the Agreement between the Owner and Contractor (hereinafter the Agreement) and consist of the Agreement, Conditions of the Contract (General, Supplementary and other Conditions), Drawings, Specifications, Addenda issued prior to execution of the Contract, other documents listed in the Agreement and Modifications issued after execution of the Contract. A Modification is (1) a written amendment to the Contract signed by both parties, (2) a Change Order, (3) a Construction Change Directive or (4) a written order for a minor change in the Work issued by the Architect. Unless specifically enumerated in the Agreement, the Contract Documents do not include the advertisement or invitation to bid, Instructions to Bidders, sample forms, other information furnished by the Owner in anticipation of receiving bids or proposals, the Contractor's bid or proposal, or portions of Addenda relating to bidding requirements.

Any reference in this document to the Agreement between the Owner and Contractor, AIA Document A101, or some abbreviated reference thereof, shall mean AIA Document A101TM–2007 Standard Form of Agreement Between Owner and Contractor, SCOSE edition. Any reference in this document to the General Conditions of the Contract for Construction, AIA Document A201, or some abbreviated reference thereof, shall mean AIA Document A201TM–2007 General Conditions of the Contract for Construction, SCOSE edition.

§ 1.1.2 THE CONTRACT

The Contract Documents form the Contract for Construction. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior negotiations, representations or agreements, either written or oral. The Contract may be amended or modified only by a Modification. The Contract Documents shall not be construed to create a contractual relationship of any kind (1) between the Contractor and the Architect or the Architect's consultants, (2) between the Owner and a Subcontractor or a Sub-subcontractor, (3) between the Owner and the Architect or the Architect's consultants or (4) between any persons or entities other than the Owner and the Contractor.

§ 1.1.3 THE WORK

The term "Work" means the construction and services required by the Contract Documents, whether completed or partially completed, and includes all other labor, materials, equipment and services provided or to be provided by the Contractor to fulfill the Contractor's obligations. The Work may constitute the whole or a part of the Project.

§ 1.1.4 THE PROJECT

The Project is the total construction of which the Work performed under the Contract Documents may be the whole or a part and which may include construction by the Owner and by separate contractors.

§ 1.1.5 THE DRAWINGS

The Drawings are the graphic and pictorial portions of the Contract Documents showing the design, location and dimensions of the Work, generally including plans, elevations, sections, details, schedules and diagrams.

§ 1.1.6 THE SPECIFICATIONS

The Specifications are that portion of the Contract Documents consisting of the written requirements for materials, equipment, systems, standards and workmanship for the Work, and performance of related services.

§ 1.1.7 INSTRUMENTS OF SERVICE

Instruments of Service are representations, in any medium of expression now known or later developed, of the tangible and intangible creative work performed by the Architect and the Architect's consultants under their respective professional services agreements. Instruments of Service may include, without limitation, studies, surveys, models, sketches, drawings, specifications, and other similar materials.

§ 1.1.8 NOTICE TO PROCEED

The Notice to Proceed is a document issued by the Owner to the Contractor, with a copy to the Architect, directing the Contractor to begin prosecution of the Work in accordance with the requirements of the Contract Documents. The Notice to Proceed shall fix the date on which the Contract Time will commence.

§ 1.2 CORRELATION AND INTENT OF THE CONTRACT DOCUMENTS

§ 1.2.1 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary, and what is required by one shall be as binding as if required by all; performance by the Contractor shall be required only to the extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the indicated results. In the event of patent ambiguities within or between parts of the Contract Documents, the Contractor shall 1) provide the better quality or greater quantity of Work, or 2) comply with the more stringent requirement, either or both in accordance with the Architect's interpretation.

- § 1.2.2 Organization of the Specifications into divisions, sections and articles, and arrangement of Drawings shall not control the Contractor in dividing the Work among Subcontractors or in establishing the extent of Work to be performed by any trade.
- § 1.2.3 Unless otherwise stated in the Contract Documents, words that have well-known technical or construction industry meanings are used in the Contract Documents in accordance with such recognized meanings.

§ 1.3 CAPITALIZATION

Terms capitalized in these General Conditions include those that are (1) specifically defined, (2) the titles of numbered articles or (3) the titles of other documents published by the American Institute of Architects.

§ 1.4 INTERPRETATION

In the interest of brevity the Contract Documents frequently omit modifying words such as "all" and "any" and articles such as "the" and "an," but the fact that a modifier or an article is absent from one statement and appears in another is not intended to affect the interpretation of either statement.

§ 1.5 OWNERSHIP AND USE OF DRAWINGS, SPECIFICATIONS AND OTHER INSTRUMENTS OF SERVICE

§ 1.5.1 The Architect and the Architect's consultants shall be deemed the authors and owners of their respective Instruments of Service and will retain all common law, statutory and other reserved rights, including copyrights. The Contractor, Subcontractors, Sub-subcontractors, and material or equipment suppliers shall not own or claim a copyright in the Instruments of Service. Submittal or distribution to meet official regulatory requirements or for other purposes in connection with this Project is not to be construed as a violation of the Architect's or Architect's consultants' reserved rights.

§ 1.5.2 The Contractor, Subcontractors, Sub-subcontractors and material or equipment suppliers are authorized to use and reproduce the Instruments of Service provided to them solely and exclusively for execution of the Work. All copies made under this authorization shall bear the copyright notice, if any, shown on the Instruments of Service. The Contractor, Subcontractors, Sub-subcontractors, and material or equipment suppliers may not use the Instruments of Service on other projects or for additions to this Project outside the scope of the Work without the specific written consent of the Owner, Architect and the Architect's consultants.

§ 1.6 TRANSMISSION OF DATA IN DIGITAL FORM

If the parties intend to transmit Instruments of Service or any other information or documentation in digital form, they shall endeavor to establish necessary protocols governing such transmissions, unless otherwise already provided in the Agreement or the Contract Documents.

ARTICLE 2 OWNER § 2.1 GENERAL

§ 2.1.1 The Owner is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Owner shall designate in writing a representative who shall have express authority to bind the Owner with respect to all matters requiring the Owner's approval or authorization, except as provided in Section 7.1.2. Except as otherwise provided in Section 4.2.1, the Architect does not have such

authority. The term "Owner" means the Owner or the Owner's Representative. [Reference § 8.3 of the Agreement.]

§ 2.1.2 The Owner shall furnish to the Contractor within fifteen (15) days after receipt of a written request, information necessary and relevant for the Contractor to post Notice of Project Commencement pursuant to Title 29, Chapter 5, Section 23 of the South Carolina Code of Laws, as amended.

§ 2.2 INFORMATION AND SERVICES REQUIRED OF THE OWNER

§ 2.2.1 Prior to commencement of the Work, the Contractor may request in writing that the Owner provide reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract. Thereafter, the Contractor may only request such evidence if (1) the Owner fails to make payments to the Contractor as the Contract Documents require; (2) a change in the Work materially changes the Contract Sum; or (3) the Contractor identifies in writing a reasonable concern regarding the Owner's ability to make payment when due. The Owner shall furnish such evidence as a condition precedent to commencement or continuation of the Work or the portion of the Work affected by a material change. After the Owner furnishes the evidence, the Owner shall not materially vary such financial arrangements without prior notice to the Contractor.

- § 2.2.2 Except for permits and fees that are the responsibility of the Contractor under the Contract Documents, including those required under Section 3.7.1, the Owner shall secure and pay for necessary approvals, easements, assessments and charges required for construction, use or occupancy of permanent structures or for permanent changes in existing facilities.
- § 2.2.3 The Owner shall furnish surveys describing physical characteristics, legal limitations and utility locations for the site of the Project, and a legal description of the site. Subject to the Contractor's obligations, including those in Section 3.2, the Contractor shall be entitled to rely on the accuracy of information furnished by the Owner pursuant to this Section but shall exercise proper precautions relating to the safe performance of the Work.
- § 2.2.4 The Owner shall furnish information or services required of the Owner by the Contract Documents with reasonable promptness. The Owner shall also furnish any other information or services under the Owner's control and relevant to the Contractor's performance of the Work with reasonable promptness after receiving the Contractor's written request for such information or services; however, the Owner does not warrant the accuracy of any such information requested by the Contractor that is not otherwise required of the Owner by the Contract Documents. Neither the Owner nor the Architect shall be required to conduct investigations or to furnish the Contractor with any information concerning subsurface characteristics or other conditions of the area where the Work is to be performed beyond that which is provide in the Contract Documents.
- § 2.2.5 Unless otherwise provided in the Contract Documents, the Owner shall furnish to the Contractor one electronic copy (.pdf format) of the Contract Documents. The Contractor may make reproductions of the Contract Documents pursuant to Section 1.5.2.
- § 2.2.6 The Owner assumes no responsibility for any conclusions or interpretation made by the Contractor based on information made available by the Owner.
- § 2.2.7 The Owner shall obtain, at its own cost, general building and specialty inspection services as required by the Contract Documents. The Contractor shall be responsible for payment of any charges imposed for reinspections.

§ 2.3 OWNER'S RIGHT TO STOP THE WORK

If the Contractor fails to correct Work that is not in accordance with the requirements of the Contract Documents as required by Section 12.2 or repeatedly fails to carry out Work in accordance with the Contract Documents, the Owner may issue a written order to the Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, the right of the Owner to stop the Work shall not give rise to a duty on the part of the Owner to exercise this right for the benefit of the Contractor or any other person or entity, except to the extent required by Section 6.1.3.

§ 2.4 OWNER'S RIGHT TO CARRY OUT THE WORK

not be reproduced prior to its completion.

If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents and fails within a ten-day period after receipt of written notice from the Owner to commence and continue correction of such default or neglect, including but not limited to providing necessary resources, with diligence and promptness, the Owner may, without prejudice to other remedies the Owner may have, correct such deficiencies. In such case an appropriate Change Directive shall be issued deducting from payments then or thereafter due the Contractor the reasonable cost of correcting such deficiencies, including Owner's expenses and compensation for the Architect's additional services made necessary by such default, neglect or failure. If payments then or thereafter due the Contractor are not sufficient to cover such amounts, the Contractor shall pay the difference to the Owner.

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

under license number 2009500317 , and is not for resale. This document is licensed by The American Institute of Architects for one-time use only, and may

ARTICLE 3 CONTRACTOR

§ 3.1 GENERAL

§ 3.1.1 The Contractor is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Contractor shall be lawfully licensed, if required in the jurisdiction where the Project is located. The Contractor shall designate in writing a representative who shall have express authority to bind the Contractor with respect to all matters under this Contract. The term "Contractor" means the Contractor or the Contractor's authorized representative.

- § 3.1.2 The Contractor shall perform the Work in accordance with the Contract Documents.
- § 3.1.3 The Contractor shall not be relieved of obligations to perform the Work in accordance with the Contract Documents either by activities or duties of the Architect in the Architect's administration of the Contract, or by tests, inspections or approvals required or performed by persons or entities other than the Contractor.

§ 3.2 REVIEW OF CONTRACT DOCUMENTS AND FIELD CONDITIONS BY CONTRACTOR

§ 3.2.1 Execution of the Contract by the Contractor is a representation that the Contractor has visited the site, become generally familiar with local conditions under which the Work is to be performed and correlated personal observations with requirements of the Contract Documents. The Contractor acknowledges that it has investigated and satisfied itself as to the general and local conditions which can affect the work or its cost, including but not limited to (1) conditions bearing upon transportation, disposal, handling, and storage of materials; (2) the availability of labor, water, electric power, and roads; (3) uncertainties of weather, river stages, tides, or similar physical conditions at the site; (4) the conformation and conditions of the ground; and (5) the character of equipment and facilities needed preliminary to and during work performance. The Contractor also acknowledges that it has satisfied itself as to the character, quality, and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information is reasonably ascertainable from an inspection of the site, including all exploratory work done by the Owner, as well as from the drawings and specifications made a part of this contract. Any failure of the Contractor to take the actions described and acknowledged in this paragraph will not relieve the Contractor from responsibility for estimating properly the difficulty and cost of successfully performing the work, or for proceeding to successfully perform the work without additional expense to the Owner.

§ 3.2.2 Because the Contract Documents are complementary, the Contractor shall, before starting each portion of the Work, carefully study and compare the various Contract Documents relative to that portion of the Work, as well as the information furnished by the Owner pursuant to Section 2.2.3, shall take field measurements of any existing conditions related to that portion of the Work, and shall observe any conditions at the site affecting it. These obligations are for the purpose of facilitating coordination and construction by the Contractor and are not for the purpose of discovering errors, omissions, or inconsistencies in the Contract Documents; however, the Contractor shall promptly report to the Architect any errors, inconsistencies or omissions discovered by or made known to the Contractor as a request for information in such form as the Architect may require. It is recognized that the Contractor's review is made in the Contractor's capacity as a contractor and not as a licensed design professional, unless otherwise specifically provided in the Contract Documents.

§ 3.2.3 The Contractor is not required to ascertain that the Contract Documents are in accordance with applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, but the Contractor shall promptly report to the Architect any nonconformity discovered by or made known to the Contractor as a request for information in such form as the Architect may require.

§ 3.2.4 If the Contractor believes that additional cost or time is involved because of clarifications or instructions the Architect issues in response to the Contractor's notices or requests for information pursuant to Sections 3.2.2 or 3.2.3, the Contractor shall make Claims as provided in Article 15. If the Contractor fails to perform the obligations of Sections 3.2.2 or 3.2.3, the Contractor shall pay such costs and damages to the Owner as would have been avoided if the Contractor had performed such obligations. If the Contractor performs those obligations, the Contractor shall not be liable to the Owner or Architect for damages resulting from latent errors, inconsistencies or omissions in the Contract Documents, for differences between field measurements or conditions and the Contract Documents, or for nonconformities of the Contract Documents to applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities.

not be reproduced prior to its completion.

§ 3.3 SUPERVISION AND CONSTRUCTION PROCEDURES

§ 3.3.1 The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for, and have control over, construction means, methods, techniques, sequences and procedures and for coordinating all portions of the Work under the Contract, unless the Contract Documents give other specific instructions concerning these matters. If the Contract Documents give specific instructions concerning construction means, methods, techniques, sequences or procedures, the Contractor shall evaluate the jobsite safety thereof and, except as stated below, shall be fully and solely responsible for the jobsite safety of such means, methods, techniques, sequences or procedures. If the Contractor determines that such means, methods, techniques, sequences or procedures may not be safe, the Contractor shall give timely written notice to the Owner and Architect and shall not proceed with that portion of the Work without further written instructions from the Architect. If the Contractor is then instructed by the Owner in writing to proceed with the required means, methods, techniques, sequences or procedures without acceptance of changes proposed by the Contractor, the Owner shall be solely responsible for any loss or damage arising solely from those Owner-required means, methods, techniques, sequences or procedures.

- § 3.3.2 The Contractor shall be responsible to the Owner for acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons or entities performing portions of the Work for, or on behalf of, the Contractor or any of its Subcontractors.
- § 3.3.3 The Contractor shall be responsible for inspection of portions of Work already performed to determine that such portions are in proper condition to receive subsequent Work.

§ 3.4 LABOR AND MATERIALS

- § 3.4.1 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for proper execution and completion of the Work, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work.
- § 3.4.2 Except in the case of minor changes in the Work authorized by the Architect in accordance with Sections 3.12.8 or 7.4, the Contractor may make substitutions only with the consent of the Owner, after evaluation by the Architect and in accordance with a Change Order or Construction Change Directive.
- § 3.4.3 The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Work. The Contractor shall not permit employment of unfit persons or persons not properly skilled in tasks assigned to them.

§ 3.5 WARRANTY

The Contractor warrants to the Owner and Architect that materials and equipment furnished under the Contract will be of good quality and new unless the Contract Documents require or permit otherwise. The Contractor further warrants that the Work will conform to the requirements of the Contract Documents and will be free from defects, except for those inherent in the quality of the Work the Contract Documents require or permit. Work, materials, or equipment not conforming to these requirements shall be considered defective. Unless caused by the Contractor or a subcontractor at any tier, the Contractor's warranty excludes remedy for damage or defect caused by abuse, alterations to the Work not executed by the Contractor, improper or insufficient maintenance, improper operation, or normal wear and tear and normal usage. If required by the Architect, the Contractor shall furnish satisfactory evidence as to the kind and quality of materials and equipment.

§ 3.6 TAXES

The Contractor shall pay sales, consumer, use and similar taxes for the Work provided by the Contractor that are legally enacted when bids are received or negotiations concluded, whether or not yet effective or merely scheduled to go into effect. The Contractor shall comply with the requirements of Title 12, Chapter 8 of the South Carolina Code of Laws, as amended, regarding withholding tax for nonresidents, employees, contractors and subcontractors.

§ 3.7 PERMITS, FEES, NOTICES AND COMPLIANCE WITH LAWS

§ 3.7.1 Unless otherwise provided in the Contract Documents, the Contractor shall secure and pay for permits, fees, licenses, and inspections by government agencies necessary for proper execution and completion of the Work that are customarily secured after execution of the Contract and legally required at the time bids are received or

negotiations concluded. Pursuant to Title 10, Chapter 1, Section 180 of the South Carolina Code of Laws, as amended, no local general or specialty building permits are required for state buildings.

- § 3.7.2 The Contractor shall comply with and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities applicable to performance of the Work.
- § 3.7.3 If the Contractor performs Work knowing it to be contrary to applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, the Contractor shall assume appropriate responsibility for such Work and shall bear the costs attributable to correction.
- § 3.7.4 Concealed or Unknown Conditions. If the Contractor encounters conditions at the site that are (1) subsurface or otherwise concealed physical conditions that differ materially from those indicated in the Contract Documents or (2) unknown physical conditions of an unusual nature, that differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in the Contract Documents, the Contractor shall promptly provide notice to the Owner and the Architect before conditions are disturbed and in no event later than 21 days after first observance of the conditions. The Architect will promptly investigate such conditions and, if the Architect determines that they differ materially and cause an increase or decrease in the Contractor's cost of, or time required for, performance of any part of the Work, will recommend an equitable adjustment in the Contract Sum or Contract Time, or both. If the Architect determines that the conditions at the site are not materially different from those indicated in the Contract Documents and that no change in the terms of the Contract is justified, the Architect shall promptly notify the Owner and Contractor in writing, stating the reasons. If either party disputes the Architect's determination or recommendation, that party may proceed as provided in Article 15.
- § 3.7.5 If, in the course of the Work, the Contractor encounters human remains or recognizes the existence of burial markers, archaeological sites or wetlands not indicated in the Contract Documents, the Contractor shall immediately suspend any operations that would affect them and shall notify the Owner and Architect. Upon receipt of such notice, the Owner shall promptly take any action necessary to obtain governmental authorization required to resume the operations. The Contractor shall continue to suspend such operations until otherwise instructed by the Owner but shall continue with all other operations that do not affect those remains or features. Adjustments in the Contract Sum and Contract Time arising from the existence of such remains or features may be made as provided in Article 7.3.3.

§ 3.8 ALLOWANCES

§ 3.8.1 The Contractor shall include in the Contract Sum all allowances stated in the Contract Documents. Items covered by allowances shall be supplied for such amounts and by such persons or entities as the Owner may direct, but the Contractor shall not be required to employ persons or entities to whom the Contractor has reasonable objection.

- § 3.8.2 Unless otherwise provided in the Contract Documents,
 - Allowances shall cover the cost to the Contractor of materials and equipment delivered at the site and all required taxes, less applicable trade discounts;
 - .2 Contractor's costs for unloading and handling at the site, labor, installation costs, overhead, profit and other expenses contemplated for stated allowance amounts shall be included in the Contract Sum but not in the allowances; and
 - .3 Whenever costs are more than or less than allowances, the Contract Sum shall be adjusted accordingly by Change Order. The amount of the Change Order shall reflect the difference between actual costs, as documented by invoices, and the allowances under Section 3.8.2.1.
- § 3.8.3 Materials and equipment under an allowance shall be selected by the Owner with reasonable promptness.

§ 3.9 SUPERINTENDENT

not be reproduced prior to its completion.

§ 3.9.1 The Contractor shall employ a competent superintendent, acceptable to the Owner, and necessary assistants who shall be in attendance at the Project site during performance of the Work. The superintendent shall represent the Contractor, and communications given to the superintendent shall be as binding as if given to the Contractor.

§ 3.9.2 The Contractor, as soon as practicable after award of the Contract, shall furnish in writing to the Owner the name and qualifications of a proposed superintendent. The Owner may reply within 14 days to the Contractor in

writing stating whether the Owner has reasonable objection to the proposed superintendent. Failure of the Owner to reply within the 14 day period shall constitute notice of no reasonable objection.

§ 3.9.3 The Contractor shall not employ a proposed superintendent to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall notify the Owner, in writing, of any proposed change in the superintendent, including the reason therefore, prior to making such change. The Contractor shall not change the superintendent without the Owner's consent, which shall not unreasonably be withheld or delayed.

§ 3.10 CONTRACTOR'S CONSTRUCTION SCHEDULES

§ 3.10.1 The Contractor, promptly after being awarded the Contract, shall prepare and submit for the Owner's and Architect's information a Contractor's construction schedule for the Work. The schedule shall not exceed time limits current under the Contract Documents, shall be revised at appropriate intervals as required by the conditions of the Work and Project, shall be related to the entire Project to the extent required by the Contract Documents, and shall provide for expeditious and practicable execution of the Work.

§ 3.10.2 The Contractor shall prepare a submittal schedule, promptly after being awarded the Contract and thereafter as necessary to maintain a current submittal schedule, and shall submit the schedule(s) for the Architect's approval. The Architect's approval shall not unreasonably be delayed or withheld. The submittal schedule shall (1) be coordinated with the Contractor's construction schedule, and (2) allow the Architect reasonable time to review submittals. If the Contractor fails to submit a submittal schedule, the Contractor shall not be entitled to any increase in Contract Sum or extension of Contract Time based on the time required for review of submittals.

§ 3.10.3 Additional requirements, if any, for the constructions schedule are as follows: (*Check box if applicable to this Contract*))

The construction schedule shall be in a detailed precedence-style critical path management (CPM) or primaveratype format satisfactory to the Owner and the Architect that shall also (1) provide a graphic representation of all activities and events that will occur during performance of the work; (2) identify each phase of construction and occupancy; and (3) set forth dates that are critical in ensuring the timely and orderly completion of the Work in accordance with the requirements of the Contract Documents (hereinafter referred to as "Milestone Dates"). Upon review and acceptance by the Owner and the Architect of the Milestone Dates, the construction schedule shall be deemed part of the Contract Documents and attached to the Agreement as Exhibit "A." If not accepted, the construction schedule shall be promptly revised by the Contractor in accordance with the recommendations of the Owner and the Architect and resubmitted for acceptance. The Contactor shall monitor the progress of the Work for conformance with the requirements of the construction schedule and shall promptly advise the Owner of any delays or potential delays. Whenever the approved construction schedule no longer reflects actual conditions and progress of the work or the Contract Time is modified in accordance with the terms of the Contract Documents, the Contractor shall update the accepted construction schedule to reflect such conditions. In the event any progress report indicates any delays, the Contractor shall propose an affirmative plan to correct the delay, including overtime and/or additional labor, if necessary. In no event shall any progress report constitute an adjustment in the Contract Time, any Milestone Date, or the Contract Sum unless any such adjustment is agreed to by the Owner and authorized pursuant to Change Order.

§ 3.10.4 The Owner's review and acceptance of the Contractor's schedule is not conducted for the purpose of either determining its accuracy and completeness or approving the construction means, methods, techniques, sequences or procedures. The Owner's approval shall not relieve the Contractor of any obligations. Unless expressly addressed in a Modification, the Owner's approval of a schedule shall not change the Contract Time.

§ 3.11 DOCUMENTS AND SAMPLES AT THE SITE

not be reproduced prior to its completion.

The Contractor shall maintain at the site for the Owner one copy of the Drawings, Specifications, Addenda, Change Orders and other Modifications, in good order and marked currently to indicate field changes and selections made during construction, and one copy of approved Shop Drawings, Product Data, Samples and similar required submittals. These shall be available to the Architect and shall be delivered to the Architect for submittal to the Owner upon completion of the Work as a record of the Work as constructed.

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

under license number 2009500317 , and is not for resale. This document is licensed by The American Institute of Architects for one-time use only, and may

§ 3.12 SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

- § 3.12.1 Shop Drawings are drawings, diagrams, schedules and other data specially prepared for the Work by the Contractor or a Subcontractor, Sub-subcontractor, manufacturer, supplier or distributor to illustrate some portion of the Work.
- § 3.12.2 Product Data are illustrations, standard schedules, performance charts, instructions, brochures, diagrams and other information furnished by the Contractor to illustrate materials or equipment for some portion of the Work.
- § 3.12.3 Samples are physical examples that illustrate materials, equipment or workmanship and establish standards by which the Work will be judged.
- § 3.12.4 Shop Drawings, Product Data, Samples and similar submittals are not Contract Documents. Their purpose is to demonstrate the way by which the Contractor proposes to conform to the information given and the design concept expressed in the Contract Documents for those portions of the Work for which the Contract Documents require submittals. Review by the Architect is subject to the limitations of Section 4.2.7. Informational submittals upon which the Architect is not expected to take responsive action may be so identified in the Contract Documents. Submittals that are not required by the Contract Documents may be returned by the Architect without action.
- § 3.12.5 The Contractor shall review for compliance with the Contract Documents, approve and submit to the Architect Shop Drawings, Product Data, Samples and similar submittals required by the Contract Documents in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness and in such sequence as to cause no delay in the Work or in the activities of the Owner or of separate contractors.
- § 3.12.5.1 The fire sprinkler shop drawings shall be prepared by a licensed fire sprinkler contractor and shall accurately reflect actual conditions affecting the required layout of the fire sprinkler system. The fire sprinkler contractor shall certify the accuracy of his shop drawings prior to submitting them for review and approval. The fire sprinkler shop drawings shall be reviewed and approved by the Architect's engineer of record who, upon approving the sprinkler shop drawings will submit them to the State Fire Marshal for review and approval. A copy of the shop drawings will also be sent to OSE for information. The Architect's engineer of record will submit a copy of the State Fire Marshal's approval letter to the Contractor, Architect, and OSE. Unless authorized in writing by OSE, neither the Contractor nor subcontractor at any tier shall submit the fire sprinkler shop drawings directly to the State Fire Marshal for approval.
- § 3.12.6 By submitting Shop Drawings, Product Data, Samples and similar submittals, the Contractor represents to the Owner and Architect that the Contractor has (1) reviewed and approved them, (2) determined and verified materials, field measurements and field construction criteria related thereto, or will do so and (3) checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.
- § 3.12.7 The Contractor shall perform no portion of the Work for which the Contract Documents require submittal and review of Shop Drawings, Product Data, Samples or similar submittals until the respective submittal has been approved by the Architect.
- § 3.12.8 The Work shall be in accordance with approved submittals except that the Contractor shall not be relieved of responsibility for deviations from requirements of the Contract Documents by the Architect's approval of Shop Drawings, Product Data, Samples or similar submittals unless the Contractor has specifically informed the Architect in writing of such deviation at the time of submittal and (1) the Architect has given written approval to the specific deviation as a minor change in the Work, or (2) a Change Order or Construction Change Directive has been issued authorizing the deviation. The Contractor shall not be relieved of responsibility for errors or omissions in Shop Drawings, Product Data, Samples or similar submittals by the Architect's approval thereof.
- § 3.12.9 The Contractor shall direct specific attention, in writing or on resubmitted Shop Drawings, Product Data, Samples or similar submittals, to revisions other than those requested by the Architect on previous submittals. In the absence of such written notice, the Architect's approval of a resubmission shall not apply to such revisions.

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

under license number 2009500317 , and is not for resale. This document is licensed by The American Institute of Architects for one-time use only, and may

not be reproduced prior to its completion.

§ 3.12.10 The Contractor shall not be required to provide professional services that constitute the practice of architecture or engineering unless such services are specifically required by the Contract Documents for a portion of the Work or unless the Contractor needs to provide such services in order to carry out the Contractor's responsibilities for construction means, methods, techniques, sequences and procedures. The Contractor shall not be required to provide professional services in violation of applicable law. If professional design services or certifications by a design professional related to systems, materials or equipment are specifically required of the Contractor by the Contract Documents, the Owner and the Architect will specify all performance and design criteria that such services must satisfy. The Contractor shall cause such services or certifications to be provided by a properly licensed design professional, who shall comply with reasonable requirements of the Owner regarding qualifications and insurance and whose signature and seal shall appear on all drawings, calculations, specifications, certifications, Shop Drawings and other submittals prepared by such professional. Shop Drawings and other submittals related to the Work designed or certified by such professional, if prepared by others, shall bear such professional's written approval when submitted to the Architect. The Owner and the Architect shall be entitled to rely upon the adequacy, accuracy and completeness of the services, certifications and approvals performed or provided by such design professionals, provided the Owner and Architect have specified to the Contractor all performance and design criteria that such services must satisfy. Pursuant to this Section 3.12.10, the Architect will review, approve or take other appropriate action on submittals only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents. The Contractor shall not be responsible for the adequacy of the performance and design criteria specified in the Contract Documents.

§ 3.13 USE OF SITE

§ 3.13.1 The Contractor shall confine operations at the site to areas permitted by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities and the Contract Documents and shall not unreasonably encumber the site with materials or equipment.

§ 3.13.2 Protection of construction materials and equipment stored at the Project site from weather, theft, vandalism, damage, and all other adversity is solely the responsibility of the Contractor. The Contractor shall perform the work in a manner that affords reasonable access, both vehicular and pedestrian, to the site of the Work and all adjacent areas. The Work shall be performed, to the fullest extent reasonably possible, in such a manner that public areas adjacent to the site of the Work shall be free from all debris, building materials, and equipment likely to cause hazardous conditions.

§ 3.13.3 The Contractor and any entity for which the Contractor is responsible shall not erect any sign on the Project site without the prior written consent of the Owner.

§ 3.14 CUTTING AND PATCHING

§ 3.14.1 The Contractor shall be responsible for cutting, fitting or patching required to complete the Work or to make its parts fit together properly. All areas requiring cutting, fitting and patching shall be restored to the condition existing prior to the cutting, fitting and patching, unless otherwise required by the Contract Documents.

§ 3.14.2 The Contractor shall not damage or endanger a portion of the Work or fully or partially completed construction of the Owner or separate contractors by cutting, patching or otherwise altering such construction, or by excavation. The Contractor shall not cut or otherwise alter such construction by the Owner or a separate contractor except with written consent of the Owner and of such separate contractor; such consent shall not be unreasonably withheld. The Contractor shall not unreasonably withhold from the Owner or a separate contractor the Contractor's consent to cutting or otherwise altering the Work.

§ 3.15 CLEANING UP

not be reproduced prior to its completion.

§ 3.15.1 The Contractor shall keep the premises and surrounding area free from accumulation of waste materials or rubbish caused by operations under the Contract. At completion of the Work, the Contractor shall remove waste materials, rubbish, the Contractor's tools, construction equipment, machinery and surplus materials from and about the Project.

§ 3.15.2 If the Contractor fails to clean up as provided in the Contract Documents, the Owner may do so and Owner shall be entitled to reimbursement from the Contractor.

§ 3.16 ACCESS TO WORK

The Contractor shall provide the Owner and Architect access to the Work in preparation and progress wherever located.

§ 3.17 ROYALTIES, PATENTS AND COPYRIGHTS

The Contractor shall pay all royalties and license fees. The Contractor shall defend suits or claims for infringement of copyrights and patent rights and shall hold the Owner and Architect harmless from loss on account thereof, but shall not be responsible for such defense or loss when a particular design, process or product of a particular manufacturer or manufacturers is required by the Contract Documents, or where the copyright violations are contained in Drawings, Specifications or other documents prepared by the Owner or Architect. However, if the Contractor has reason to believe that the required design, process or product is an infringement of a copyright or a patent, the Contractor shall be responsible for such loss unless such information is promptly furnished to the Architect.

§ 3.18 INDEMNIFICATION

§ 3.18.1 To the fullest extent permitted by law the Contractor shall indemnify and hold harmless the Owner, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work, provided that such claim, damage, loss or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself) including loss of use resulting therefrom, but only to the extent caused by the negligent acts or omissions of the Contractor, a Subcontractor, anyone directly or indirectly employed by them or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss or expense is caused in part by a party indemnified hereunder. Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity that would otherwise exist as to a party or person described in this Section 3.18.

§ 3.18.2 In claims against any person or entity indemnified under this Section 3.18 by an employee of the Contractor, a Subcontractor, anyone directly or indirectly employed by them or anyone for whose acts they may be liable, the indemnification obligation under Section 3.18.1 shall not be limited by a limitation on amount or type of damages, compensation or benefits payable by or for the Contractor or a Subcontractor under workers' compensation acts, disability benefit acts or other employee benefit acts.

ARTICLE 4 ARCHITECT

§ 4.1 GENERAL

§ 4.1.1 The Architect is that person or entity identified as the Architect in the Agreement and is referred to throughout the Contract Documents as if singular in number.

§ 4.1.2 Duties, responsibilities and limitations of authority of the Architect as set forth in the Contract Documents shall not be restricted, modified or extended without written consent of the Owner, Contractor and Architect. Consent shall not be unreasonably withheld.

§ 4.1.3 If the employment of the Architect is terminated, the Owner shall employ a successor architect as to whom the Contractor has no reasonable objection and whose status under the Contract Documents shall be that of the Architect.

§ 4.2 ADMINISTRATION OF THE CONTRACT

§ 4.2.1 The Architect will provide administration of the Contract as described in the Contract Documents and will be an Owner's representative during construction until the date the Architect issues the final Certificate for Payment. The Architect will have authority to act on behalf of the Owner only to the extent provided in the Contract Documents. Any reference in the Contract Documents to the Architect taking action or rendering a decision with a "reasonable time" is understood to mean no more than fourteen days, unless otherwise specified in the Contract Documents or otherwise agreed to by the parties.

§ 4.2.2 The Architect will visit the site as necessary to fulfill its obligation to the Owner for inspection services, if any, and, at a minimum, to assure conformance with the Architect's design as shown in the Contract Documents and to observe the progress and quality of the various components of the Contractor's Work, and to determine if the Work observed is being performed in a manner indicating that the Work, when fully completed, will be in accordance with the Contract Documents. However, the Architect will not be required to make exhaustive or

continuous on-site inspections to check the quality or quantity of the Work. The Architect will not have control over, charge of, or responsibility for, the construction means, methods, techniques, sequences or procedures, or for the safety precautions and programs in connection with the Work, since these are solely the Contractor's rights and responsibilities under the Contract Documents, except as provided in Section 3.3.1.

§ 4.2.3 On the basis of the site visits, the Architect will keep the Owner informed about the progress and quality of the portion of the Work completed, and report to the Owner (1) deviations from the Contract Documents and from the most recent construction schedule submitted by the Contractor, and (2) defects and deficiencies observed in the Work. The Architect will not be responsible for the Contractor's failure to perform the Work in accordance with the requirements of the Contract Documents. The Architect will not have control over or charge of and will not be responsible for acts or omissions of the Contractor, Subcontractors, or their agents or employees, or any other persons or entities performing portions of the Work.

§ 4.2.4 COMMUNICATIONS FACILITATING CONTRACT ADMINISTRATION

Except as otherwise provided in the Contract Documents or when direct communications have been specially authorized, the Owner and Contractor shall endeavor to communicate with each other through the Architect about matters arising out of or relating to the Contract. Communications by and with the Architect's consultants shall be through the Architect. Communications by and with Subcontractors and material suppliers shall be through the Contractor. Communications by and with separate contractors shall be through the Owner.

§ 4.2.5 Based on the Architect's evaluations of the Work completed and correlated with the Contractor's Applications for Payment, the Architect will review and certify the amounts due the Contractor and will issue Certificates for Payment in such amounts.

§ 4.2.6 The Architect has authority to reject Work that does not conform to the Contract Documents. Whenever the Architect considers it necessary or advisable, the Architect will have authority to require inspection or testing of the Work in accordance with Sections 13.5.2 and 13.5.3, whether or not such Work is fabricated, installed or completed. However, neither this authority of the Architect nor a decision made in good faith either to exercise or not to exercise such authority shall give rise to a duty or responsibility of the Architect to the Contractor, Subcontractors, material and equipment suppliers, their agents or employees, or other persons or entities performing portions of the Work.

§ 4.2.7 The Architect will review and approve, or take other appropriate action upon, the Contractor's submittals such as Shop Drawings, Product Data and Samples, but only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents. The Architect's action will be taken in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness while allowing sufficient time in the Architect's professional judgment to permit adequate review. Review of such submittals is not conducted for the purpose of determining the accuracy and completeness of other details such as dimensions and quantities, or for substantiating instructions for installation or performance of equipment or systems, all of which remain the responsibility of the Contractor as required by the Contract Documents. The Architect's review of the Contractor's submittals shall not relieve the Contractor of the obligations under Sections 3.3, 3.5 and 3.12. The Architect's review shall not constitute approval of safety precautions or, unless otherwise specifically stated by the Architect, of any construction means, methods, techniques, sequences or procedures. The Architect's approval of a specific item shall not indicate approval of an assembly of which the item is a component.

§ 4.2.8 The Architect will prepare Change Orders and Construction Change Directives, and may authorize minor changes in the Work as provided in Section 7.4. The Architect will investigate and make determinations and recommendations regarding concealed and unknown conditions as provided in Section 3.7.4.

§ 4.2.9 The Architect will conduct inspections to determine the date or dates of Substantial Completion and the date of final completion; issue Certificates of Substantial Completion pursuant to Section 9.8; receive and forward to the Owner, for the Owner's review and records, written warranties and related documents required by the Contract and assembled by the Contractor pursuant to Section 9.10; and issue a final Certificate for Payment pursuant to Section 9.10.

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

American Institute of Architects. All rights reserved. South Carolina Division of Procurement Services, Office of the State Engineer Version of AIA

- § 4.2.10 If the Owner and Architect agree, the Architect will provide one or more project representatives to assist in carrying out the Architect's responsibilities at the site. The duties, responsibilities and limitations of authority of such project representatives shall be as set forth in an exhibit to be incorporated in the Contract Documents.
- § 4.2.11 The Architect will, in the first instance, interpret and decide matters concerning performance under, and requirements of, the Contract Documents on written request of either the Owner or Contractor. Upon receipt of such request, the Architect will promptly provide the non-requesting party with a copy of the request. The Architect's response to such requests will be made in writing with reasonable promptness.
- § 4.2.12 Interpretations and decisions of the Architect will be consistent with the intent of, and reasonably inferable from, the Contract Documents and will be in writing or in the form of drawings. When making such interpretations and decisions, the Architect will endeavor to secure faithful performance by both Owner and Contractor, and will not show partiality to either. Except in the case of interpretations resulting in omissions, defects, or errors in the Instruments of Service or perpetuating omissions, defects, or errors in the Instruments of Service, the Architect will not be liable for results of interpretations or decisions rendered in good faith. If either party disputes the Architects interpretation or decision, that party may proceed as provided in Article 15. The Architect's interpretations and decisions may be, but need not be, accorded any deference in any review conducted pursuant to law or the Contract Documents.
- § 4.2.13 The Architect's decisions on matters relating to aesthetic effect will be final if consistent with the intent expressed in the Contract Documents.
- § 4.2.14 The Architect will review and respond to requests for information about the Contract Documents so as to avoid delay to the construction of the Project. The Architect's response to such requests will be made in writing with reasonable promptness. If appropriate, the Architect will prepare and issue supplemental Drawings and Specifications in response to the requests for information. Any response to a request for information must be consistent with the intent of, and reasonably inferable from, the Contract Documents and will be in writing or in the form of drawings. Unless issued pursuant to a Modification, supplemental Drawings or Specifications will not involve an adjustment to the Contract Sum or Contract Time.

ARTICLE 5 SUBCONTRACTORS

not be reproduced prior to its completion.

§ 5.1 DEFINITIONS

- § 5.1.1 A Subcontractor is a person or entity who has a direct contract with the Contractor to perform a portion of the Work at the site. The term "Subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Subcontractor or an authorized representative of the Subcontractor. The term "Subcontractor" does not include a separate contractor or subcontractors of a separate contractor.
- § 5.1.2 A Sub-subcontractor is a person or entity who has a direct or indirect contract with a Subcontractor to perform a portion of the Work at the site. The term "Sub-subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Sub-subcontractor or an authorized representative of the Sub-subcontractor.

§ 5.2 AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK

- § 5.2.1 Unless otherwise stated in the Contract Documents or the bidding requirements, the Contractor, within fourteen days after posting of the Notice of Intent to Award the Contract, shall furnish in writing to the Owner through the Architect the names of persons or entities (excluding Listed Subcontractors but including those who are to furnish materials or equipment fabricated to a special design) proposed for each principal portion of the Work. The Owner may reply within 14 days to the Contractor in writing stating whether the Owner has reasonable objection to any such proposed person or entity. Failure of the Owner to reply within the 14-day period shall constitute notice of no reasonable objection.
- § 5.2.2 The Contractor shall not contract with a proposed person or entity to whom the Owner has made reasonable and timely objection. The Owner shall not direct the Contractor to contract with any specific individual or entity for supplies or services unless such supplies and services are necessary for completion of the Work and the specified individual or entity is the only source of such supply or services.
- § 5.2.3 If the Owner has reasonable objection to a person or entity proposed by the Contractor, the Contractor shall propose another to whom the Owner has no reasonable objection. If the proposed but rejected Subcontractor was

reasonably capable of performing the Work, the Contract Sum and Contract Time shall be increased or decreased by the difference, if any, occasioned by such change, and an appropriate Change Order shall be issued before commencement of the substitute Subcontractor's Work. However, no increase in the Contract Sum or Contract Time shall be allowed for such change unless the Contractor has acted promptly and responsively in submitting names as required.

- § 5.2.4 The Contractor shall not substitute a Subcontractor, person or entity previously selected if the Owner makes reasonable objection to such substitution. The Contractor's request for substitution must be made to the Owner in writing accompanied by supporting information.
- § 5.2.5 A Subcontractor identified in the Contractor's Bid in response the specialty subcontractor listing requirements of Section 7 of the Bid Form (SE-330) may only be substituted in accordance with and as permitted by the provisions of Title 11, Chapter 35, Section 3021 of the South Carolina Code of Laws, as amended. A proposed substitute for a Listed Subcontractor shall be subject to the Owner's approval as set forth is Section 5.2.3.
- § 5.2.6 The Iran Divestment Act List is a list published by the State Fiscal Accountability Authority pursuant to Section 11-57-310 that identifies persons engaged in investment activities in Iran. Currently, the list is available at the following URL: http://procurement.sc.gov/PS/PS-iran-divestment.phtm(.) Consistent with Section 11-57-330(B), the Contractor shall not contract with any person to perform a part of the Work, if, at the time you enter into the subcontract, that person is on the then-current version of the Iran Divestment Act List.

§ 5.3 SUBCONTRACTUAL RELATIONS

- § 5.3.1 By appropriate written agreement, the Contractor shall require each Subcontractor, to the extent of the Work to be performed by the Subcontractor, to be bound to the Contractor by terms of the Contract Documents, and to assume toward the Contractor all the obligations and responsibilities, including the responsibility for safety of the Subcontractor's Work, which the Contractor, by these Documents, assumes toward the Owner and Architect. Each subcontract agreement shall preserve and protect the rights of the Owner and Architect under the Contract Documents with respect to the Work to be performed by the Subcontractor so that subcontracting thereof will not prejudice such rights, and shall allow to the Subcontractor, unless specifically provided otherwise herein or in the subcontract agreement, the benefit of all rights, remedies and redress against the Contractor that the Contractor, by the Contract Documents, has against the Owner. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with Sub-subcontractors. The Contractor shall make available to each proposed Subcontractor, prior to the execution of the subcontract agreement, copies of the Contract Documents to which the Subcontractor will be bound, and, upon written request of the Subcontractor, identify to the Subcontractor terms and conditions of the proposed subcontract agreement that may be at variance with the Contract Documents. Subcontractors will similarly make copies of applicable portions of such documents available to their respective proposed Sub-subcontractors.
- § 5.3.2 Without limitation on the generality of Section 5.3.1, each Subcontract agreement and each Sub-subcontract agreement shall include, and shall be deemed to include, the following Sections of these General Conditions: 3.2, 3.5, 3.18, 5.3, 5.4, 6.2.2, 7.3.3, 7.5, 7.6, 13.1, 13.12, 14.3, 14.4, and 15.1.6.
- § 5.3.3 Each Subcontract Agreement and each Sub-subcontract agreement shall exclude, and shall be deemed to exclude, Sections 13.2 and 13.6 and all of Article 15, except Section 15.1.6, of these General Conditions. In the place of these excluded sections of the General Conditions, each Subcontract Agreement and each Sub-subcontract may include Sections 13.2.1 and 13.6 and all of Article 15, except Section 15.1.6, of AIA Document A201-2007, Conditions of the Contract, as originally issued by the American Institute of Architects.
- § 5.3.4 The Contractor shall assure the Owner that all agreements between the Contractor and its Subcontractor incorporate the provisions of Subparagraph 5.3.1 as necessary to preserve and protect the rights of the Owner and the Architect under the Contract Documents with respect to the work to be performed by Subcontractors so that the subcontracting thereof will not prejudice such rights. The Contractor's assurance shall be in the form of an affidavit or in such other form as the Owner may approve. Upon request, the Contractor shall provide the Owner or Architect with copies of any or all subcontracts or purchase orders.

§ 5.4 CONTINGENT ASSIGNMENT OF SUBCONTRACTS

§ 5.4.1 Each subcontract agreement for a portion of the Work is assigned by the Contractor to the Owner, provided that

- assignment is effective only after termination of the Contract by the Owner for cause pursuant to Section 14.2 and only for those subcontract agreements that the Owner accepts by notifying the Subcontractor and Contractor in writing; and
- .2 assignment is subject to the prior rights of the surety, if any, obligated under bond relating to the Contract.
- § 5.4.2 Upon such assignment, if the Work has been suspended for more than 30 days, the Subcontractor's compensation shall be equitably adjusted for increases in cost resulting from the suspension.
- § 5.4.3 Upon such assignment to the Owner under this Section 5.4, the Owner may further assign the subcontract to a successor contractor or other entity. If the Owner assigns the subcontract to a successor contractor or other entity, the Owner shall nevertheless remain legally responsible for all of the successor contractor's obligations under the subcontract.
- § 5.4.4 Each subcontract shall specifically provide that the Owner shall only be responsible to the subcontractor for those obligations of the Contractor that accrue subsequent to the Owner's exercise of any rights under this conditional assignment.
- § 5.4.5 Each subcontract shall specifically provide that the Subcontractor agrees to perform portions of the Work assigned to the Owner in accordance with the Contract Documents.
- § 5.4.6 Nothing in this Section 5.4 shall act to reduce or discharge the Contractor's payment bond surety's obligations to claims arising prior to the Owner's exercise of any rights under this conditional assignment.

ARTICLE 6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS § 6.1 OWNER'S RIGHT TO PERFORM CONSTRUCTION AND TO AWARD SEPARATE CONTRACTS

- § 6.1.1 The Owner reserves the right to perform construction or operations related to the Project with the Owner's own forces, and to award separate contracts in connection with other portions of the Project or other construction or operations on the site under Conditions of the Contract identical or substantially similar to these including those portions related to insurance and waiver of subrogation. If the Contractor claims that delay or additional cost is involved because of such action by the Owner, the Contractor shall make such Claim as provided in Article 15.
- § 6.1.2 When separate contracts are awarded for different portions of the Project or other construction or operations on the site, the term "Contractor" in the Contract Documents in each case shall mean the Contractor who executes each separate Owner-Contractor Agreement.
- § 6.1.3 The Owner shall provide for coordination of the activities of the Owner's own forces and of each separate contractor with the Work of the Contractor, who shall cooperate with them. The Contractor shall participate with other separate contractors and the Owner in reviewing their construction schedules. The Contractor shall make any revisions to the construction schedule deemed necessary after a joint review and mutual agreement. The construction schedules shall then constitute the schedules to be used by the Contractor, separate contractors and the Owner until subsequently revised.
- § 6.1.4 Reserved.

§ 6.2 MUTUAL RESPONSIBILITY

- § 6.2.1 The Contractor shall afford the Owner and separate contractors reasonable opportunity for introduction and storage of their materials and equipment and performance of their activities, and shall connect and coordinate the Contractor's construction and operations with theirs as required by the Contract Documents.
- § 6.2.2 If part of the Contractor's Work depends for proper execution or results upon construction or operations by the Owner or a separate contractor, the Contractor shall, prior to proceeding with that portion of the Work, promptly report to the Architect apparent discrepancies or defects in such other construction that would render it unsuitable

for such proper execution and results. Failure of the Contractor so to report shall constitute an acknowledgment that the Owner's or separate contractor's completed or partially completed construction is fit and proper to receive the Contractor's Work, except as to defects not then reasonably discoverable.

- § 6.2.3 The Contractor shall reimburse the Owner for costs the Owner incurs that are payable to a separate contractor because of the Contractor's delays, improperly timed activities or defective construction. The Owner shall be responsible to the Contractor for costs the Contractor incurs because of a separate contractor's delays, improperly timed activities, damage to the Work or defective construction.
- § 6.2.4 The Contractor shall promptly remedy damage the Contractor wrongfully causes to completed or partially completed construction or to property of the Owner or separate contractors as provided in Section 10.2.5.
- § 6.2.5 The Owner and each separate contractor shall have the same responsibilities for cutting and patching as are described for the Contractor in Section 3.14.

§ 6.3 OWNER'S RIGHT TO CLEAN UP

If a dispute arises among the Contractor, separate contractors and the Owner as to the responsibility under their respective contracts for maintaining the premises and surrounding area free from waste materials and rubbish, the Owner may clean up and the Architect will allocate the cost among those responsible.

ARTICLE 7 CHANGES IN THE WORK § 7.1 GENERAL

- § 7.1.1 Changes in the Work may be accomplished after execution of the Contract, and without invalidating the Contract, by Change Order, Construction Change Directive or order for a minor change in the Work, subject to the limitations stated in this Article 7 and elsewhere in the Contract Documents.
- § 7.1.2 A Change Order shall be based upon agreement among the Owner, Contractor and Architect; a Construction Change Directive requires agreement by the Owner and Architect and may or may not be agreed to by the Contractor; an order for a minor change in the Work may be issued by the Architect alone. If the amount of a Modification exceeds the limits of the Owner's Construction Change Order Certification (reference Section 9.1.7.2 of the Agreement), then the Owner's agreement is not effective, and Work may not proceed, until approved in writing by the Office of State Engineer.
- § 7.1.3 Changes in the Work shall be performed under applicable provisions of the Contract Documents, and the Contractor shall proceed promptly, unless otherwise provided in the Change Order, Construction Change Directive or order for a minor change in the Work.

§ 7.2 CHANGE ORDERS

not be reproduced prior to its completion.

- § 7.2.1 A Change Order is a written instrument prepared by the Architect (using Form SE-380 "Construction Change Order") and signed by the Owner, Contractor and Architect stating their agreement upon all of the following:
 - .1 The change in the Work;
 - .2 The amount of the adjustment, if any, in the Contract Sum; and
 - .3 The extent of the adjustment, if any, in the Contract Time.
- § 7.2.2 If a Change Order provides for an adjustment to the Contract Sum, the adjustment must be calculated in accordance with Section 7.3.3.
- § 7.2.3 At the Owner's request, the Contractor shall prepare a proposal to perform the work of a proposed Change Order setting forth the amount of the proposed adjustment, if any, in the Contract Sum; and the extent of the proposed adjustment, if any, in the Contract Time. Any proposed adjustment in the Contract sum shall be prepared in accordance with Section 7.2.2. The Owner's request shall include any revisions to the Drawings or Specifications necessary to define any changes in the Work. Within fifteen days of receiving the request, the Contractor shall submit the proposal to the Owner and Architect along with all documentation required by Section 7.6.
- § 7.2.4 If the Contractor requests a Change Order, the request shall set forth the proposed change in the Work and shall be prepared in accordance with Section 7.2.3. If the Contractor requests a change to the Work that involves a revision to either the Drawings or Specifications, the Contractor shall reimburse the Owner for any expenditure associated with the Architects' review of the proposed revisions, except to the extent the revisions are accepted by

execution of a Change Order.

§ 7.2.5 Agreement on any Change Order shall constitute a final settlement of all matters relating to the change in the Work that is the subject of the Change Order, including, but not limited to, any adjustments to the Contract Sum or the Contract Time.

§ 7.3 CONSTRUCTION CHANGE DIRECTIVES

§ 7.3.1 A Construction Change Directive is a written order prepared by the Architect and signed by the Owner and Architect, directing a change in the Work prior to agreement on adjustment, if any, in the Contract Sum or Contract Time, or both. The Owner may by Construction Change Directive, without invalidating the Contract, order changes in the Work within the general scope of the Contract consisting of additions, deletions or other revisions, the Contract Sum and Contract Time being adjusted accordingly.

§ 7.3.2 A Construction Change Directive shall be used in the absence of total agreement on the terms of a Change Order.

§ 7.3.3 PRICE ADJUSTMENTS

§ 7.3.3.1 If any Modification, including a Construction Change Directive, provides for an adjustment to the Contract Sum, the adjustment shall be based on whichever of the following methods is the most valid approximation of the actual cost to the contractor, with overhead and profit as allowed by Section 7.5:

- .1 Mutual acceptance of a lump sum;
- .2 Unit prices stated in the Contract Documents, except as provided in Section 7.3.4, or subsequently agreed upon;
- .3 Cost attributable to the events or situations under applicable clauses with adjustment of profits or fee, all as specified in the contract, or subsequently agreed upon by the parties, or by some other method as the parties may agree; or
- .4 As provided in Section 7.3.7.
- § 7.3.3.2 Consistent with Section 7.6, costs must be properly itemized and supported by substantiating data sufficient to permit evaluation before commencement of the pertinent performance or as soon after that as practicable. All costs incurred by the Contractor must be justifiably compared with prevailing industry standards. Except as provided in Section 7.5, all adjustments to the Contract Price shall be limited to job specific costs and shall not include indirect costs, overhead, home office overhead, or profit.
- § 7.3.4 If unit prices are stated in the Contract Documents or subsequently agreed upon, and if quantities originally contemplated are materially changed in a proposed Change Order or Construction Change Directive so that application of such unit prices to quantities of Work proposed will cause substantial inequity to the Owner or Contractor, the applicable unit prices shall be equitably adjusted.
- § 7.3.5 Upon receipt of a Construction Change Directive, the Contractor shall promptly proceed with the change in the Work involved and advise the Architect of the Contractor's agreement or disagreement with the method, if any, provided in the Construction Change Directive for determining the proposed adjustment in the Contract Sum or Contract Time.
- § 7.3.6 A Construction Change Directive signed by the Contractor indicates the Contractor's agreement therewith, including adjustment in Contract Sum and Contract Time or the method for determining them. Such agreement shall be effective immediately and shall be recorded as a Change Order.
- § 7.3.7 If the Contractor does not respond promptly or disagrees with the method for adjustment in the Contract Sum, the Architect shall make an initial determination, consistent with Section 7.3.3, of the method and the adjustment on the basis of reasonable expenditures and savings of those performing the Work attributable to the change, including, in case of an increase in the Contract Sum, an amount for overhead and profit as set forth in Section 7.5. In such case, and also under Section 7.3.3.1.3, the Contractor shall keep and present, in such form as the Architect may prescribe, an itemized accounting together with appropriate supporting data. Unless otherwise provided in the Contract Documents, costs for the purposes of this Section 7.3.7 shall be limited to the following:
 - .1 Costs of labor, including social security, old age and unemployment insurance, fringe benefits required by agreement or custom, and workers' compensation insurance;

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

under license number 2009500317 , and is not for resale. This document is licensed by The American Institute of Architects for one-time use only, and may

not be reproduced prior to its completion.

- .2 Costs of materials, supplies and equipment, including cost of transportation, whether incorporated or consumed:
- .3 Rental costs of machinery and equipment, exclusive of hand tools, whether rented from the Contractor or others;
- .4 Costs of premiums for all bonds and insurance, permit fees, and sales, use or similar taxes related to the Work.

§ 7.3.8 Using the percentages stated in Section 7.5, any adjustment to the Contract Sum for deleted work shall include any overhead and profit attributable to the cost for the deleted Work.

§ 7.3.9 Pending final determination of the total cost of a Construction Change Directive to the Owner, the Contractor may request payment for Work completed under the Construction Change Directive in Applications for Payment. The Architect will make an interim determination for purposes of monthly certification for payment for those costs and certify for payment the amount that the Architect determines, in the Architect's professional judgment, to be reasonably justified. The Architect's interim determination of cost shall adjust the Contract Sum on the same basis as a Change Order, subject to the right of either party to disagree and assert a Claim in accordance with Article 15.

§ 7.3.10 When the Owner and Contractor agree with a determination made by the Architect concerning the adjustments in the Contract Sum and Contract Time, or otherwise reach agreement upon the adjustments, such agreement shall be effective immediately and the Architect will prepare a Change Order. Change Orders may be issued for all or any part of a Construction Change Directive.

§ 7.4 MINOR CHANGES IN THE WORK

The Architect has authority to order minor changes in the Work not involving adjustment in the Contract Sum or extension of the Contract Time and not inconsistent with the intent of the Contract Documents. Such changes will be effected by written order signed by the Architect and shall be binding on the Owner and Contractor.

§ 7.5 AGREED OVERHEAD AND PROFIT RATES

§ 7.5.1 For any adjustment to the Contract Sum for which overhead and profit may be recovered, other than those made pursuant to Unit Prices stated in the Contract Documents, the Contractor agrees to charge and accept, as full payment for overhead and profit, the following percentages of costs attributable to the change in the Work. The percentages cited below shall be considered to include all indirect costs including, but not limited to: field and office managers, supervisors and assistants, incidental job burdens, small tools, and general overhead allocations. The allowable percentages for overhead and profit are as follows:

- .1 To the Contractor for work performed by the Contractor's own forces, 17% of the Contractor's actual
- .2 To each Subcontractor for work performed by the Subcontractor's own forces, 17% of the subcontractor's actual costs.
- .3 To the Contractor for work performed by a subcontractor, 10% of the subcontractor's actual costs (not including the subcontractor's overhead and profit).

§ 7.6 PRICING DATA AND AUDIT

not be reproduced prior to its completion.

§ 7.6.1 Cost or Pricing Data

Upon request of the Owner or Architect, Contractor shall submit cost or pricing data prior to execution of a Modification which exceeds \$500,000. Contractor shall certify that, to the best of its knowledge and belief, the cost or pricing data submitted is accurate, complete, and current as of a mutually determined specified date prior to the date of pricing the Modification. Contractor's price, including profit, shall be adjusted to exclude any significant sums by which such price was increased because Contractor furnished cost or pricing data that was inaccurate, incomplete, or not current as of the date specified by the parties. Notwithstanding Subparagraph 9.10.4, such adjustments may be made after final payment to the Contractor.

§ 7.6.2 Cost or pricing data means all facts that, as of the date specified by the parties, prudent buyers and sellers would reasonably expect to affect price negotiations significantly. Cost or pricing data are factual, not judgmental; and are verifiable. While they do not indicate the accuracy of the prospective contractor's judgment about estimated future costs or projections, they do include the data forming the basis for that judgment. Cost or pricing data are

more than historical accounting data; they are all the facts that can be reasonably expected to contribute to the soundness of estimates of future costs and to the validity of determinations of costs already incurred.

§ 7.6.3 Records Retention

As used in Section 7.6, the term "records" means any books or records that relate to cost or pricing data that Contractor is required to submit pursuant to Section 7.6.1. Contractor shall maintain records for three years from the date of final payment, or longer if requested by the chief procurement officer. The Owner may audit Contractor's records at reasonable times and places.

ARTICLE 8 TIME

§ 8.1 DEFINITIONS

- § 8.1.1 Unless otherwise provided, Contract Time is the period of time, including authorized adjustments, allotted in the Contract Documents for Substantial Completion of the Work.
- § 8.1.2 The date of commencement of the Work is the date established in the Agreement.
- § 8.1.3 The date of Substantial Completion is the date certified by the Architect in accordance with Section 9.8.
- § 8.1.4 The term "day" as used in the Contract Documents shall mean calendar day unless otherwise specifically defined.

§ 8.2 PROGRESS AND COMPLETION

- § 8.2.1 Time limits stated in the Contract Documents are of the essence of the Contract. By executing the Agreement the Contractor confirms that the Contract Time is a reasonable period for performing the Work.
- § 8.2.2 The Contractor shall not knowingly commence operations on the site or elsewhere prior to the effective date of surety bonds and insurance required by Article 11 to be furnished by the Contractor and Owner. The date of commencement of the Work shall not be changed by the effective date of such surety bonds or insurance.
- § 8.2.3 The Contractor shall proceed expeditiously with adequate forces and shall achieve Substantial Completion within the Contract Time.

§ 8.3 DELAYS AND EXTENSIONS OF TIME

§ 8.3.1 If the Contractor is delayed at any time in the commencement or progress of the Work by an act or neglect of the Owner or Architect, or of an employee of either, or of a separate contractor employed by the Owner; or by changes ordered in the Work; or by labor disputes, fire, unusual delay in deliveries, unavoidable casualties or other causes beyond the control of the Contractor and any subcontractor at any tier; or by delay authorized by the Owner pending dispute resolution; or by other causes that the Architect determines may justify delay, then to the extent such delay will prevent the Contractor from achieving Substantial Completion within the Contract Time and provided the delay (1) is not caused by the fault or negligence of the Contractor or a subcontractor at any tier and (2) is not due to unusual delay in the delivery of supplies, machinery, equipment, or services when such supplies, machinery, equipment, or services were obtainable from other sources in sufficient time for the Contractor to meet the required delivery, the Contract Time shall be extended by Change Order for such reasonable time as the Architect may determine.

- § 8.3.2 Claims relating to time shall be made in accordance with applicable provisions of Article 15.
- § 8.3.3 This Section 8.3 does not preclude recovery of damages for delay by either party under other provisions of the Contract Documents.

ARTICLE 9 PAYMENTS AND COMPLETION § 9.1 CONTRACT SUM

The Contract Sum is stated in the Agreement and, including authorized adjustments, is the total amount payable by the Owner to the Contractor for performance of the Work under the Contract Documents. All changes to the Contract Sum shall be adjusted in accordance with Section 7.3.3.

§ 9.2 SCHEDULE OF VALUES

§ 9.2.1 The Contractor shall submit to the Architect, within ten days of full execution of the Agreement, a schedule of values allocating the entire Contract Sum to the various portions of the Work and prepared in such form and supported by such data to substantiate its accuracy as the Architect may require. This schedule, unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's Applications for Payment. As requested by the Architect, the Contractor and each Subcontractor shall prepare a trade payment breakdown for the Work for which each is responsible, such breakdown being submitted on a uniform standardized format approved by the Architect and Owner. The breakdown shall be divided in detail, using convenient units, sufficient to accurately determine the value of completed Work during the course of the Project. The Contractor shall update the schedule of values as required by either the Architect or Owner as necessary to reflect:

- .1 the description of Work (listing labor and material separately);
- .2 the total value:
- .3 the percent and value of the Work completed to date;
- .4 the percent and value of previous amounts billed; and
- .5 the current percent completed and amount billed.

§ 9.2.2 Any schedule of values or trade breakdown that fails to include sufficient detail, is unbalanced, or exhibits "front-loading" of the value of the Work shall be rejected. If a schedule of values or trade breakdown is used as the basis for payment and later determined to be inaccurate, sufficient funds shall be withheld from future Applications for Payment to ensure an adequate reserve (exclusive of normal retainage) to complete the Work.

§ 9.3 APPLICATIONS FOR PAYMENT

not be reproduced prior to its completion.

§ 9.3.1 Monthly, the Contractor shall submit to the Architect an itemized Application for Payment prepared in accordance with the schedule of values, if required under Section 9.2, for completed portions of the Work. Such application shall be notarized, if required, and supported by such data substantiating the Contractor's right to payment as the Owner or Architect may require (such as copies of requisitions from Subcontractors and material suppliers) and shall reflect retainage and any other adjustments provided in Section 5 of the Agreement. If required by the Owner or Architect, the Application for Payment shall be accompanied by a current construction schedule.

§ 9.3.1.1 As provided in Section 7.3.9, such applications may include requests for payment on account of changes in the Work that have been properly authorized by Construction Change Directives, or by interim determinations of the Architect, but not yet included in Change Orders.

§ 9.3.1.2 Applications for Payment shall not include requests for payment for portions of the Work for which the Contractor does not intend to pay a Subcontractor or material supplier, unless such Work has been performed by others whom the Contractor intends to pay.

§ 9.3.2 Unless otherwise provided in the Contract Documents, payments shall be made on account of materials and equipment delivered and suitably stored at the site for subsequent incorporation in the Work. If approved in advance by the Owner, payment may similarly be made for materials and equipment suitably stored off the site at a location agreed upon in writing provided such materials or equipment will be subsequently incorporated in the Work. Payment for materials and equipment stored on or off the site shall be conditioned upon compliance by the Contractor with procedures satisfactory to the Owner to establish the Owner's title to such materials and equipment or otherwise protect the Owner's interest, and shall include the costs of applicable insurance, storage and transportation to the site for such materials and equipment stored off the site. The Contractor shall 1) protect such materials from diversion, vandalism, theft, destruction, and damage, 2) mark such materials specifically for use on the Project, and 3) segregate such materials from other materials at the storage facility. The Architect and the Owner shall have the right to make inspections of the storage areas at any time.

§ 9.3.3 The Contractor warrants that title to all Work covered by an Application for Payment will pass to the Owner no later than the time of payment. The Contractor further warrants that upon submittal of an Application for Payment all Work for which Certificates for Payment have been previously issued and payments received from the Owner shall, to the best of the Contractor's knowledge, information and belief, be free and clear of liens, claims, security interests or encumbrances in favor of the Contractor, Subcontractors, material suppliers, or other persons or entities making a claim by reason of having provided labor, materials and equipment relating to the Work.

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

under license number 2009500317 , and is not for resale. This document is licensed by The American Institute of Architects for one-time use only, and may

§ 9.4 CERTIFICATES FOR PAYMENT

§ 9.4.1 The Architect will, within seven days after receipt of the Contractor's Application for Payment, either issue to the Owner a Certificate for Payment, with a copy to the Contractor, for such amount as the Architect determines is properly due, or notify the Contractor and Owner in writing of the Architect's reasons for withholding certification in whole or in part as provided in Section 9.5.1.

§ 9.4.2 The issuance of a Certificate for Payment will constitute a representation by the Architect to the Owner, based on the Architect's evaluation of the Work and the data comprising the Application for Payment, that, to the best of the Architect's knowledge, information and belief, the Work has progressed to the point indicated in both the Application for Payment and, if required to be submitted by the Contractor, the accompanying current construction schedule and that the quality of the Work is in accordance with the Contract Documents. The foregoing representations are subject to an evaluation of the Work for conformance with the Contract Documents upon Substantial Completion, to results of subsequent tests and inspections, to correction of minor deviations from the Contract Documents prior to completion and to specific qualifications expressed by the Architect. The issuance of a Certificate for Payment will further constitute a representation that the Contractor is entitled to payment in the amount certified. However, the issuance of a Certificate for Payment will not be a representation that the Architect has (1) made exhaustive or continuous on-site inspections to check the quality or quantity of the Work, (2) reviewed construction means, methods, techniques, sequences or procedures, or (3) made examination to ascertain how or for what purpose the Contractor has used money previously paid on account of the Contract Sum.

§ 9.5 DECISIONS TO WITHHOLD CERTIFICATION

§ 9.5.1 The Architect shall withhold a Certificate for Payment in whole or in part, to the extent reasonably necessary to protect the Owner, if in the Architect's opinion the representations to the Owner required by Section 9.4.2 cannot be made. The Architect shall withhold a Certificate of Payment if the Application for Payment is not accompanied by the current construction schedule required by Section 3.10.1. If the Architect is unable to certify payment in the amount of the Application, the Architect will notify the Contractor and Owner as provided in Section 9.4.1. If the Contractor and Architect cannot agree on a revised amount, the Architect will promptly issue a Certificate for Payment for the amount for which the Architect is able to make such representations to the Owner. The Architect may also withhold a Certificate for Payment or, because of subsequently discovered evidence, may nullify the whole or a part of a Certificate for Payment previously issued, to such extent as may be necessary in the Architect's opinion to protect the Owner from loss for which the Contractor is responsible, including loss resulting from acts and omissions described in Section 3.3.2, because of

- .1 defective Work not remedied;
- .2 third party claims filed or reasonable evidence indicating probable filing of such claims unless security acceptable to the Owner is provided by the Contractor;
- .3 failure of the Contractor to make payments properly to Subcontractors or for labor, materials or equipment;
- .4 reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Sum;
- .5 damage to the Owner or a separate contractor;
- reasonable evidence that the Work will not be completed within the Contract Time, and that the unpaid balance would not be adequate to cover actual or liquidated damages for the anticipated delay; or
- .7 repeated failure to carry out the Work in accordance with the Contract Documents.

§ 9.5.2 When the above reasons for withholding certification are removed, certification will be made for amounts previously withheld.

§ 9.5.3 If the Architect withholds certification for payment under Section 9.5.1.3, the Owner may, at its sole option, issue joint checks to the Contractor and to any Subcontractor or material or equipment suppliers to whom the Contractor failed to make payment for Work properly performed or material or equipment suitably delivered. If the Owner makes payments by joint check, the Owner shall notify the Architect and the Architect will reflect such payment on the next Certificate for Payment.

§ 9.6 PROGRESS PAYMENTS

not be reproduced prior to its completion.

§ 9.6.1 After the Architect has issued a Certificate for Payment, the Owner shall make payment in the manner and within the time provided in the Contract Documents, and shall so notify the Architect.

§ 9.6.2 Pursuant to Chapter 6 of Title 29 of the South Carolina Code of Laws, as amended, the Contractor shall pay each Subcontractor no later than seven days after receipt of payment from the Owner the amount to which the Subcontractor is entitled, reflecting percentages actually retained from payments to the Contractor on account of the Subcontractor's portion of the Work. The Contractor shall, by appropriate agreement with each Subcontractor, require each Subcontractor to make payments to Sub-subcontractors in a similar manner.

§ 9.6.3 The Architect will, on request, furnish to a Subcontractor, if practicable, information regarding percentages of completion or amounts applied for by the Contractor and action taken thereon by the Architect and Owner on account of portions of the Work done by such Subcontractor.

§ 9.6.4 The Owner has the right to request written evidence from the Contractor that the Contractor has properly paid Subcontractors and material and equipment suppliers amounts paid by the Owner to the Contractor for subcontracted Work. If the Contractor fails to furnish such evidence within seven days, the Owner shall have the right to contact Subcontractors to ascertain whether they have been properly paid. Neither the Owner nor Architect shall have an obligation to pay or to see to the payment of money to a Subcontractor, except as may otherwise be required by law.

§ 9.6.5 Contractor payments to material and equipment suppliers shall be treated in a manner similar to that provided in Sections 9.6.2, 9.6.3 and 9.6.4.

§ 9.6.6 A Certificate for Payment, a progress payment, or partial or entire use or occupancy of the Project by the Owner shall not constitute acceptance of Work not in accordance with the Contract Documents.

§ 9.6.7 Unless the Contractor provides the Owner with a payment bond in the full penal sum of the Contract Sum, payments received by the Contractor for Work properly performed by Subcontractors and suppliers shall be held by the Contractor for those Subcontractors or suppliers who performed Work or furnished materials, or both, under contract with the Contractor for which payment was made by the Owner. Nothing contained herein shall require money to be placed in a separate account and not commingled with money of the Contractor, shall create any fiduciary liability or tort liability on the part of the Contractor for breach of trust or shall entitle any person or entity to an award of punitive damages against the Contractor for breach of the requirements of this provision.

§ 9.7 FAILURE OF PAYMENT

If the Architect does not issue a Certificate for Payment to the Owner, through no fault of the Contractor, within seven days after receipt of the Contractor's Application for Payment, or if the Owner does not pay the Contractor within seven days after the time established in the Contract Documents the amount certified by the Architect or awarded by final dispute resolution order, then the Contractor may, upon seven additional days' written notice to the Owner and Architect, stop the Work until payment of the amount owing has been received. The Contract Time shall be extended appropriately and the Contract Sum shall be increased, in accordance with the provisions of Section 7.3.3, by the amount of the Contractor's reasonable costs of shut-down, delay and start-up, plus interest as provided for in the Contract Documents.

§ 9.8 SUBSTANTIAL COMPLETION

§ 9.8.1 Substantial Completion is the stage in the progress of the Work when the Work or designated portion thereof is sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use and when all required occupancy permits, if any, have been issued and copies have been delivered to the Owner.

§ 9.8.2 When the Contractor considers that the Work, or a portion thereof which the Owner agrees to accept separately, is substantially complete, the Contractor shall prepare and submit to the Architect a comprehensive written list of items to be completed or corrected prior to final payment. Failure to include an item on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents.

§ 9.8.3 Upon receipt of the Contractor's list, the Architect, with the Owner and any other person the Architect or the Owner choose, will make an inspection on a date and at a time mutually agreeable to the Architect, Owner, and Contractor, to determine whether the Work or designated portion thereof is substantially complete. The Contractor shall furnish access for the inspection and testing as provided in this Contract. The inspection shall include a demonstration by the Contractor that all equipment, systems and operable components of the Work function properly and in accordance with the Contract Documents. If the Architect's inspection discloses any item, whether

or not included on the Contractor's list, which is not sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work or designated portion thereof for its intended use, the Contractor shall, before issuance of the Certificate of Substantial Completion, complete or correct such item upon notification by the Architect. In such case, the Contractor shall then submit a request for another inspection by the Architect to determine Substantial Completion. If more than one Substantial Completion inspection is required, the Contractor shall reimburse the Owner for all costs of re-inspections or, at the Owner's option, the costs may be deducted from payments due to the Contractor.

§ 9.8.3.1 If the Architect and Owner concur in the Contractor's assessment that the Work or a portion of the Work is safe to occupy, the Owner and Contractor may arrange for a Certificate of Occupancy Inspection by OSE. The Owner, Architect, and Contractor shall be present at OSE's inspection. Upon verifying that the Work or a portion of the Work is substantially complete and safe to occupy, OSE will issue, as appropriate, a Full or Partial Certificate of Occupancy.

§ 9.8.4 When the Work or designated portion thereof is substantially complete, the Architect will prepare a Certificate of Substantial Completion that shall establish the date of Substantial Completion, shall establish responsibilities of the Owner and Contractor for security, maintenance, heat, utilities, damage to the Work and insurance, and shall fix the time within which the Contractor shall finish all items on the list accompanying the Certificate. Warranties required by the Contract Documents shall commence on the date of Substantial Completion of the Work or designated portion thereof unless otherwise provided in the Certificate of Substantial Completion.

§ 9.8.5 The Certificate of Substantial Completion shall be submitted to the Owner and Contractor for their written acceptance of responsibilities assigned to them in such Certificate. Upon such acceptance, the Owner shall make payment of retainage applying to such Work or designated portion thereof. Such payment shall be adjusted for Work that is incomplete or not in accordance with the requirements of the Contract Documents.

§ 9.9 PARTIAL OCCUPANCY OR USE

§ 9.9.1 The Owner may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with the Contractor, provided such occupancy or use is consented to by the insurer as required under Section 11.3.1.5 and authorized by public authorities having jurisdiction over the Project. Such partial occupancy or use may commence whether or not the portion is substantially complete, provided the Owner and Contractor have accepted in writing the responsibilities assigned to each of them for payments, retainage, if any, security, maintenance, heat, utilities, damage to the Work and insurance, and have agreed in writing concerning the period for correction of the Work and commencement of warranties required by the Contract Documents. When the Contractor considers a portion substantially complete, the Contractor shall prepare and submit a list to the Architect as provided under Section 9.8.2. Consent of the Contractor to partial occupancy or use shall not be unreasonably withheld. The stage of the progress of the Work shall be determined by written agreement between the Owner and Contractor or, if no agreement is reached, by decision of the Architect.

§ 9.9.2 Immediately prior to such partial occupancy or use, the Owner, Contractor and Architect shall jointly inspect the area to be occupied or portion of the Work to be used in order to determine and record the condition of the Work.

§ 9.9.3 Unless otherwise agreed upon, partial occupancy or use of a portion or portions of the Work shall not constitute acceptance of Work not complying with the requirements of the Contract Documents.

§ 9.10 FINAL COMPLETION AND FINAL PAYMENT

§ 9.10.1 Unless the parties agree otherwise in the Certificate of Substantial Completion, the Contractor shall achieve Final Completion no later than thirty days after Substantial Completion. Upon receipt of the Contractor's written notice that the Work is ready for final inspection and acceptance and upon receipt of a final Application for Payment, the Architect, with the Owner and any other person the Architect or the Owner choose, will make an inspection on a date and at a time mutually agreeable to the Architect, Owner, and Contractor, and, when the Architect finds the Work acceptable under the Contract Documents and the Contract fully performed, the Architect will promptly issue a final Certificate for Payment stating that to the best of the Architect's knowledge, information and belief, and on the basis of the Architect's on-site visits and inspections, the Work has been completed in accordance with terms and conditions of the Contract Documents and that the entire balance found to be due the Contractor and noted in the final Certificate is due and payable. The Architect's final Certificate for Payment will

constitute a further representation that conditions listed in Section 9.10.2 as precedent to the Contractor's being entitled to final payment have been fulfilled. If more than one Final Completion inspection is required, the Contractor shall reimburse the Owner for all costs of re-inspections or, at the Owner's option, the costs may be deducted from payments due to the Contractor. If the Contractor does not achieve final completion within thirty days after Substantial Completion or the timeframe agreed to by the parties in the Certificate of Substantial Completion, whichever is greater, the Contractor shall be responsible for any additional Architectural fees resulting from the delay.

§ 9.10.2 Neither final payment nor any remaining retained percentage shall become due until the Contractor submits to the Architect (1) an affidavit that payrolls, bills for materials and equipment, and other indebtedness connected with the Work for which the Owner or the Owner's property might be responsible or encumbered (less amounts withheld by Owner) have been paid or otherwise satisfied, (2) a certificate evidencing that insurance required by the Contract Documents to remain in force after final payment is currently in effect and will not be canceled or allowed to expire until at least 30 days' prior written notice has been given to the Owner, (3) a written statement that the Contractor knows of no substantial reason that the insurance will not be renewable to cover the period required by the Contract Documents, (4) consent of surety, if any, to final payment (5), if required by the Owner, other data establishing payment or satisfaction of obligations, such as receipts, releases and waivers of liens, claims, security interests or encumbrances arising out of the Contract, to the extent and in such form as may be designated by the Owner, (6) required Training Manuals, (7) equipment Operations and Maintenance Manuals, (8) any certificates of testing, inspection or approval required by the Contract Documents and not previously provided (9) all warranties and guarantees required under or pursuant to the Contract Documents, and (10) one copy of the Documents required by Section 3.11.

§ 9.10.3 If, after Substantial Completion of the Work, final completion thereof is delayed 60 days through no fault of the Contractor or by issuance of Change Orders affecting final completion, and the Architect so confirms, the Owner shall, upon application by the Contractor and certification by the Architect, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed and accepted. If the remaining balance for Work not fully completed or corrected is less than retainage stipulated in the Contract Documents, and if bonds have been furnished, the written consent of surety to payment of the balance due for that portion of the Work fully completed and accepted shall be submitted by the Contractor to the Architect prior to certification of such payment. Such payment shall be made under terms and conditions governing final payment, except that it shall not constitute a waiver of claims.

§ 9.10.4 The making of final payment shall constitute a waiver of Claims by the Owner except those arising from

- .1 liens, Claims, security interests or encumbrances arising out of the Contract and unsettled;
- .2 failure of the Work to comply with the requirements of the Contract Documents; or
- .3 terms of special warranties required by the Contract Documents.

§ 9.10.5 Acceptance of final payment by the Contractor, a Subcontractor or material supplier shall constitute a waiver of claims by that payee except those specific claims in stated amounts that have been previously made in writing and identified by that payee as unsettled at the time of final Application for Payment.

§ 9.10.6 If OSE has not previously issued a Certificate of Occupancy for the entire Project, the Parties shall arrange for a representative of OSE to participate in the Final Completion Inspection. Representatives of the State Fire Marshal's Office and other authorities having jurisdiction may be present at the Final Completion Inspection or otherwise inspect the completed Work and advise the Owner whether the Work meets their respective requirements for the Project.

ARTICLE 10 PROTECTION OF PERSONS AND PROPERTY § 10.1 SAFETY PRECAUTIONS AND PROGRAMS

The Contractor shall be responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the performance of the Contract.

§ 10.2 SAFETY OF PERSONS AND PROPERTY

§ 10.2.1 The Contractor shall take reasonable precautions for safety of, and shall provide reasonable protection to prevent damage, injury or loss to

.1 employees on the Work and other persons who may be affected thereby;

- .2 the Work and materials and equipment to be incorporated therein, whether in storage on or off the site, under care, custody or control of the Contractor or the Contractor's Subcontractors or Subsubcontractors; and
- other property at the site or adjacent thereto, such as trees, shrubs, lawns, walks, pavements, roadways, structures and utilities not designated for removal, relocation or replacement in the course of construction.
- § 10.2.2 The Contractor shall comply with and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities bearing on safety of persons or property or their protection from damage, injury or loss.
- § 10.2.3 The Contractor shall erect and maintain, as required by existing conditions and performance of the Contract, reasonable safeguards for safety and protection, including posting danger signs and other warnings against hazards, promulgating safety regulations and notifying owners and users of adjacent sites and utilities.
- § 10.2.4 When use or storage of explosives or other hazardous materials or equipment or unusual methods are necessary for execution of the Work, the Contractor shall exercise utmost care and carry on such activities under supervision of properly qualified personnel.
- § 10.2.5 The Contractor shall promptly remedy damage and loss (other than damage or loss insured under property insurance required by the Contract Documents) to property referred to in Sections 10.2.1.2 and 10.2.1.3 caused in whole or in part by the Contractor, a Subcontractor, a Sub-subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable and for which the Contractor is responsible under Sections 10.2.1.2 and 10.2.1.3, except damage or loss attributable to acts or omissions of the Owner or Architect or anyone directly or indirectly employed by either of them, or by anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Contractor. The foregoing obligations of the Contractor are in addition to the Contractor's obligations under Section 3.18.
- § 10.2.6 The Contractor shall designate a responsible member of the Contractor's organization at the site whose duty shall be the prevention of accidents. This person shall be the Contractor's superintendent unless otherwise designated by the Contractor in writing to the Owner and Architect.
- § 10.2.7 The Contractor shall not permit any part of the construction or site to be loaded so as to cause damage or create an unsafe condition.

§ 10.2.8 INJURY OR DAMAGE TO PERSON OR PROPERTY

If either party suffers injury or damage to person or property because of an act or omission of the other party, or of others for whose acts such party is legally responsible, written notice of such injury or damage, whether or not insured, shall be given to the other party within a reasonable time not exceeding 21 days after discovery. The notice shall provide sufficient detail to enable the other party to investigate the matter.

§ 10.3 HAZARDOUS MATERIALS

§ 10.3.1 If the Contractor encounters a hazardous material or substance which was not discoverable as provided in Section 3.2.1 and not required by the Contract Documents, and if reasonable precautions will be inadequate to prevent foreseeable bodily injury or death to persons or serious loss to real or personal property resulting from such material or substance encountered on the site by the Contractor, the Contractor shall, upon recognizing the condition, immediately stop Work in the affected area and report the condition to the Owner and Architect in writing. Hazardous materials or substances are those hazardous, toxic, or radioactive materials or substances subject to regulations by applicable governmental authorities having jurisdiction, such as, but not limited to, the S.C. Department of Health and Environmental Control, the U.S. Environmental Protection Agency, and the U.S. Nuclear Regulatory Commission.

§ 10.3.2 Upon receipt of the Contractor's written notice, the Owner shall obtain the services of a licensed laboratory to verify the presence or absence of the material or substance reported by the Contractor and, in the event such material or substance is found to be present, to cause it to be rendered harmless. Unless otherwise required by the Contract Documents, the Owner shall furnish in writing to the Contractor and Architect the names and qualifications of persons or entities who are to perform tests verifying the presence or absence of such material or substance or

who are to perform the task of removal or safe containment of such material or substance. The Contractor and the Architect will promptly reply to the Owner in writing stating whether or not either has reasonable objection to the persons or entities proposed by the Owner. If either the Contractor or Architect has an objection to a person or entity proposed by the Owner, the Owner shall propose another to whom the Contractor and the Architect have no reasonable objection. When the material or substance has been rendered harmless, Work in the affected area shall resume upon written agreement of the Owner and Contractor. By Change Order, the Contract Time shall be extended appropriately and the Contract Sum shall be increased in the amount of the Contractor's reasonable additional costs of shut-down, delay and start-up. In the absence of agreement, the Architect will make an interim determination regarding any delay or impact on the Contractor's additional costs. The Architect's interim determination of cost shall adjust the Contract Sum on the same basis as a Change Order, subject to the right of either party to disagree and assert a Claim in accordance with Article 15. Any adjustment in the Contract Sum shall be determined in accordance with Section 7.3.3.

§ 10.3.3 The Work in the affected area shall be resumed immediately following the occurrence of any one of the following events: (a) the Owner causes remedial work to be performed that results in the absence of hazardous materials or substances; (b) the Owner and the Contractor, by written agreement, decide to resume performance of the Work; or (c) the Work may safely and lawfully proceed, as determined by an appropriate governmental authority or as evidenced by a written report to both the Owner and the Contractor, which is prepared by an environmental engineer reasonably satisfactory to both the Owner and the Contractor.

§ 10.3.4 The Owner shall not be responsible under this Section 10.3 for materials or substances the Contractor brings to the site unless such materials or substances are required by the Contract Documents. The Owner shall be responsible for materials or substances required by the Contract Documents, except to the extent of the Contractor's fault or negligence in the use and handling of such materials or substances.

§ 10.3.5 In addition to its obligations under Section 3.18, the Contractor shall indemnify the Owner for the cost and expense the Owner incurs (1) for remediation of a material or substance the Contractor brings to the site and negligently handles, or (2) where the Contractor fails to perform its obligations under Section 10.3.1, except to the extent that the cost and expense are due to the Owner's fault or negligence.

§ 10.3.6 Reserved.

§ 10.4 EMERGENCIES

In an emergency affecting safety of persons or property, the Contractor shall act, at the Contractor's discretion, to prevent threatened damage, injury or loss. Additional compensation or extension of time claimed by the Contractor on account of an emergency shall be determined as provided in Article 15 and Article 7. The Contractor shall immediately give the Architect notice of the emergency. This initial notice may be oral followed within five days by a written notice setting forth the nature and scope of the emergency. Within fourteen days of the start of the emergency, the Contractor shall give the Architect a written estimate of the cost and probable effect of delay on the progress of the Work.

ARTICLE 11 INSURANCE AND BONDS § 11.1 CONTRACTOR'S LIABILITY INSURANCE

not be reproduced prior to its completion.

§ 11.1.1 The Contractor shall purchase from and maintain in a company or companies lawfully authorized to do business in the jurisdiction in which the Project is located such insurance as will protect the Contractor from claims set forth below which may arise out of or result from the Contractor's operations and completed operations under the Contract and for which the Contractor may be legally liable, whether such operations be by the Contractor or by a Subcontractor or by anyone directly or indirectly employed by any of them, or by anyone for whose acts any of them may be liable:

- .1 Claims under workers' compensation, disability benefit and other similar employee benefit acts that are applicable to the Work to be performed;
- .2 Claims for damages because of bodily injury, occupational sickness or disease, or death of the Contractor's employees;

- .3 Claims for damages because of bodily injury, sickness or disease, or death of any person other than the Contractor's employees;
- .4 Claims for damages insured by usual personal injury liability coverage;

- .5 Claims for damages, other than to the Work itself, because of injury to or destruction of tangible property, including loss of use resulting therefrom;
- .6 Claims for damages because of bodily injury, death of a person or property damage arising out of ownership, maintenance or use of a motor vehicle;
- .7 Claims for bodily injury or property damage arising out of completed operations; and
- .8 Claims involving contractual liability insurance applicable to the Contractor's obligations under Section 3.18.

§ 11.1.2 The insurance required by Section 11.1.1 shall be written for not less than limits of liability specified below or required by law, whichever coverage is greater. Coverages, shall be written on an occurrence basis and shall be maintained without interruption from the date of commencement of the Work until the date of final payment and termination of any coverage required to be maintained after final payment, and, with respect to the Contractor's completed operations coverage, until the expiration of the period for correction of Work or for such other period for maintenance of completed operations coverage as specified in the Contract Documents.

.1 COMMERCIAL GENERAL LIABILITY:

(a)	General Aggregate (per project)	\$1,000,000
(b)	Products/Completed Operations	\$1,000,000
(c)	Personal and Advertising Injury	\$1,000,000
(d)	Each Occurrence	\$1,000,000
(e)	Damage to Rented Premises (ea occurrence)	\$50,000
(f)	Medical Expense (Any one person)	\$5,000

- .2 BUSINESS AUTO LIABILITY (including All Owned, Non-owned, and Hired Vehicles):
 - (a) Combined Single Limit \$1,000,000
- .3 WORKER'S COMPENSATION:
 - (a) State Statutory

(b)	Employers Liability	\$100,000 per Acc.
		\$500,000 Disease, Policy Limit
		\$100,000 Disease, Each Employee

In lieu of separate insurance policies for Commercial General Liability, Business Auto Liability, and Employers Liability, the Contractor may provide an umbrella policy meeting or exceeding all coverage requirements set forth in this Section 11.1.2. The umbrella policy limits shall not be less than \$3,000,000.

§ 11.1.3 Prior to commencement of the Work, and thereafter upon replacement of each required policy of insurance, the Contractor shall provide to the Owner a written endorsement to the Contractor's general liability insurance policy that:

- .1 names the Owner as an additional insureds for claims caused in whole or in part by the Contractor's negligent acts or omissions during the Contractor's operations;
- .2 provides that no material alteration, cancellation, non-renewal, or expiration of the coverage contained in such policy shall have effect unless all additional insureds have been given at least ten (10) days prior written notice of cancellation for non-payment of premiums and thirty (30) days prior written notice of cancellation for any other reason; and
- provides that the Contractor's liability insurance policy shall be primary, with any liability insurance of the Owner as secondary and noncontributory.

Prior to commencement of the Work, and thereafter upon renewal or replacement of each required policy of insurance, the Contractor shall provide to the Owner a signed, original certificate of liability insurance (ACORD 25). Consistent with this Section 11.1, the certificate shall identify the types of insurance, state the limits of liability for each type of coverage, name the Owner a Consultants as Certificate Holder, provide that the general aggregate limit applies per project, and provide that coverage is written on an occurrence basis. Both the certificates and the endorsements must be received directly from either the Contractor's insurance agent or the insurance company. An additional certificate evidencing continuation of liability coverage, including coverage for completed operations, naming the Owner as an additional insured for claims made under the Contractor's completed operations, and otherwise meeting the above requirements, shall be submitted with the final Application for Payment as required by Section 9.10.2 and thereafter upon renewal or replacement of such coverage until the expiration of the time required

by Section 11.1.2. Information concerning reduction of coverage on account of revised limits or claims paid under the General Aggregate, or both, shall be furnished by the Contractor with reasonable promptness.

§ 11.1.4 A failure by the Owner to either (i) demand a certificate of insurance or written endorsement required by Section 11.1, or (ii) reject a certificate or endorsement on the grounds that it fails to comply with Section 11.1, shall not be considered a waiver of Contractor's obligations to obtain the required insurance.

§ 11.2 OWNER'S LIABILITY INSURANCE

The Owner shall be responsible for purchasing and maintaining the Owner's usual liability insurance.

§ 11.3 PROPERTY INSURANCE

§ 11.3.1 Unless otherwise provided in the Contract Documents, the Contractor shall purchase and maintain, in a company or companies lawfully authorized to do business in the jurisdiction in which the Project is located, property insurance written on a builder's risk "all-risk" or equivalent policy form in the amount of the initial Contract Sum, plus value of subsequent Contract Modifications and cost of materials supplied or installed by others, comprising total value for the entire Project at the site on a replacement cost basis. Such property insurance shall be maintained, unless otherwise provided in the Contract Documents or otherwise agreed in writing by all persons and entities who are beneficiaries of such insurance, until final payment has been made as provided in Section 9.10 or until no person or entity other than the Owner has an insurable interest in the property required by this Section 11.3 to be covered, whichever is later. This insurance shall include interests of the Owner, the Contractor, Subcontractors and Subsubcontractors in the Project.

§ 11.3.1.1 Property insurance shall be on an "all-risk" or equivalent policy form and shall include, without limitation, insurance against the perils of fire (with extended coverage) and physical loss or damage including, without duplication of coverage, theft, vandalism, malicious mischief, collapse, earthquake, flood, windstorm, falsework, testing and startup, temporary buildings and debris removal including demolition occasioned by enforcement of any applicable legal requirements, and shall cover reasonable compensation for Architect's and Contractor's services and expenses required as a result of such insured loss.

§ 11.3.1.2 Reserved.

§ 11.3.1.3 Reserved.

§ 11.3.1.4 This property insurance shall cover portions of the Work stored off the site, and also portions of the Work in transit.

§ 11.3.1.5 Partial occupancy or use in accordance with Section 9.9 shall not commence until the insurance company or companies providing property insurance have consented to such partial occupancy or use by endorsement or otherwise. The Owner and the Contractor shall take reasonable steps to obtain consent of the insurance company or companies and shall, without mutual written consent, take no action with respect to partial occupancy or use that would cause cancellation, lapse or reduction of insurance.

§ 11.3.2 BOILER AND MACHINERY INSURANCE

The Contractor shall purchase and maintain boiler and machinery insurance required by the Contract Documents or by law, which shall specifically cover such insured objects during installation and until final acceptance by the Owner; this insurance shall include interests of the Owner, Contractor, Subcontractors and Sub-subcontractors in the Work, and the Owner and Contractor shall be named insureds.

§ 11.3.3 LOSS OF USE INSURANCE

The Owner, at the Owner's option, may purchase and maintain such insurance as will insure the Owner against loss of use of the Owner's property due to fire or other hazards, however caused. To the extent any losses are covered and paid for by such insurance, the Owner waives all rights of action against the Contractor for loss of use of the Owner's property, including consequential losses due to fire or other hazards however caused.

§ 11.3.4 If the Owner requests in writing that insurance for risks other than those described herein or other special causes of loss be included in the property insurance policy, the Contractor shall, if possible, include such insurance, and the cost thereof shall be charged to the Owner by appropriate Change Order.

§ 11.3.5 Reserved.

§ 11.3.6 Before an exposure to loss may occur, the Contractor shall file with the Owner a copy of each policy that includes insurance coverages required by this Section 11.3. Each policy shall contain all generally applicable conditions, definitions, exclusions and endorsements related to this Project. Each policy shall contain a provision that the policy will not be canceled or allowed to expire, and that its limits will not be reduced, until at least 30 days' prior written notice has been given to the Owner.

§ 11.3.7 WAIVERS OF SUBROGATION

The Owner and Contractor waive all rights against (1) each other and any of their subcontractors, subsubcontractors, agents and employees, each of the other, and (2) the Architect, Architect's consultants, separate contractors described in Article 6, if any, and any of their subcontractors, sub-subcontractors, agents and employees, for damages caused by fire or other causes of loss to the extent the property insurance provided by the Contractor pursuant to this Section 11.3 covers and pays for the damage, except such rights as they have to proceeds of such insurance held by the Contractor as fiduciary. The Owner or Contractor, as appropriate, shall require of the Architect, Architect's consultants, separate contractors described in Article 6, if any, and the subcontractors, subsubcontractors, agents and employees of any of them, by appropriate agreements, written where legally required for validity, similar waivers each in favor of other parties enumerated herein. The policies shall provide such waivers of subrogation by endorsement or otherwise. A waiver of subrogation shall be effective as to a person or entity even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, did not pay the insurance premium directly or indirectly, and whether or not the person or entity had an insurable interest in the property damaged.

§ 11.3.8 A loss insured under the Contractor's property insurance shall be adjusted by the Contractor as fiduciary and made payable to the Contractor as fiduciary for the insureds, as their interests may appear, subject to requirements of any applicable mortgagee clause and of Section 11.3.10. The Contractor shall pay Subcontractors their just shares of insurance proceeds received by the Contractor, and by appropriate agreements, written where legally required for validity, shall require Subcontractors to make payments to their Sub-subcontractors in similar manner.

§ 11.3.9 If required in writing by a party in interest, the Contractor as fiduciary shall, upon occurrence of an insured loss, give bond for proper performance of the Contractor's duties. The cost of required bonds shall be charged against proceeds received as fiduciary. The Contractor shall deposit in a separate account proceeds so received, which the Contractor shall distribute in accordance with such agreement as the parties in interest may reach. If after such loss no other special agreement is made and unless the Owner terminates the Contract for convenience, replacement of damaged property shall be performed by the Contractor.

§ 11.3.10 The Contractor as fiduciary shall have power to adjust and settle a loss with insurers unless one of the parties in interest shall object in writing within five days after occurrence of loss to the Contractor's exercise of this power; if such objection is made, the dispute shall be resolved in the manner provided in the contract between the parties in dispute as the method of binding dispute resolution. The Contractor as fiduciary shall make settlement with insurers or, in the case of a dispute over distribution of insurance proceeds, in accordance with a final order or determination issued by the appropriate authority having jurisdiction over the dispute.

§ 11.4 PERFORMANCE BOND AND PAYMENT BOND

not be reproduced prior to its completion.

§ 11.4.1 Before commencing any services hereunder, the Contractor shall provide the Owner with Performance and Payment Bonds, each in an amount not less than the Contract Price set forth in Article 4 of the Agreement. The Surety shall have, at a minimum, a "Best Rating" of "A" as stated in the most current publication of "Best's Key Rating Guide, Property-Casualty". In addition, the Surety shall have a minimum "Best Financial Strength Category" of "Class V", and in no case less than five (5) times the contract amount. The Performance Bond shall be written on Form SE-355, "Performance Bond" and the Payment Bond shall written on Form SE-357, "Labor and Material Payment Bond", and both shall be made payable to the Owner.

- § 11.4.2 The Performance and Labor and Material Payment Bonds shall:
 - .1 be issued by a surety company licensed to do business in South Carolina;
 - .2 be accompanied by a current power of attorney and certified by the attorney-in-fact who executes the bond on the behalf of the surety company; and

- .3 remain in effect for a period not less than one (1) year following the date of Substantial Completion or the time required to resolve any items of incomplete Work and the payment of any disputed amounts, whichever time period is longer.
- § 11.4.3 Any bonds required by this Contract shall meet the requirements of the South Carolina Code of Laws and Regulations, as amended.
- § 11.4.4 Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a copy of the bonds or shall authorize a copy to be furnished.

ARTICLE 12 UNCOVERING AND CORRECTION OF WORK

§ 12.1 UNCOVERING OF WORK

§ 12.1.1 If a portion of the Work is covered contrary to the requirements specifically expressed in the Contract Documents, including inspections of work-in-progress required by all authorities having jurisdiction over the Project, it must, upon demand of the Architect or authority having jurisdiction, be uncovered for observation and be replaced at the Contractor's expense without change in the Contract Time.

§ 12.1.2 If a portion of the Work has been covered that the Architect has not specifically requested to examine prior to its being covered, the Architect may request to see such Work and it shall be uncovered by the Contractor. If such Work is in accordance with the Contract Documents, costs of uncovering and replacement shall, by appropriate Change Order, be at the Owner's expense. If such Work is not in accordance with the Contract Documents, such costs and the cost of correction shall be at the Contractor's expense unless the condition was caused by the Owner or a separate contractor in which event the Owner shall be responsible for payment of such costs.

§ 12.2 CORRECTION OF WORK

not be reproduced prior to its completion.

§ 12.2.1 BEFORE OR AFTER SUBSTANTIAL COMPLETION

The Contractor shall promptly correct Work rejected by the Architect or failing to conform to the requirements of the Contract Documents, whether discovered before or after Substantial Completion and whether or not fabricated, installed or completed. Costs of correcting such rejected Work, including additional testing and inspections, the cost of uncovering and replacement, and compensation for the Architect's services and expenses made necessary thereby, shall be at the Contractor's expense.

§ 12.2.2 AFTER SUBSTANTIAL COMPLETION

§ 12.2.2.1 In addition to the Contractor's obligations under Section 3.5, if, within one year after the date of Substantial Completion of the Work or designated portion thereof or after the date for commencement of warranties established under Section 9.9.1, or by terms of an applicable special warranty required by the Contract Documents, any of the Work is found to be not in accordance with the requirements of the Contract Documents, the Contractor shall correct it promptly after receipt of written notice from the Owner to do so unless the Owner has previously given the Contractor a written acceptance of such condition. The Owner shall give such notice promptly after discovery of the condition. During the one-year period for correction of Work, if the Owner fails to notify the Contractor and give the Contractor an opportunity to make the correction, the Owner waives the rights to require correction by the Contractor. If the Contractor fails to correct nonconforming Work within a reasonable time during that period after receipt of notice from the Owner or Architect, the Owner may correct it in accordance with Section 2.4.

- § 12.2.2.2 The one-year period for correction of Work shall be extended with respect to portions of Work first performed after Substantial Completion by the period of time between Substantial Completion and the actual completion of that portion of the Work.
- § 12.2.2.3 The one-year period for correction of Work shall not be extended by corrective Work performed by the Contractor pursuant to this Section 12.2 unless otherwise provided in the Contract Documents.
- § 12.2.3 The Contractor shall remove from the site portions of the Work that are not in accordance with the requirements of the Contract Documents and are neither corrected by the Contractor nor accepted by the Owner.

§ 12.2.4 The Contractor shall bear the cost of correcting destroyed or damaged construction, whether completed or partially completed, of the Owner or separate contractors caused by the Contractor's correction or removal of Work that is not in accordance with the requirements of the Contract Documents. If, prior to the date of Substantial Completion, the Contractor, a Subcontractor, or anyone for whom either is responsible, uses or damages any portion of the Work, including, without limitation, mechanical, electrical, plumbing, and other building systems, machinery, equipment, or other mechanical device, the Contractor shall cause such item to be restored to "like new" condition at no expense to the Owner.

§ 12.2.5 Nothing contained in this Section 12.2 shall be construed to establish a period of limitation with respect to other obligations the Contractor has under the Contract Documents. Establishment of the one-year period for correction of Work as described in Section 12.2.2 relates only to the specific obligation of the Contractor to correct the Work, and has no relationship to the time within which the obligation to comply with the Contract Documents may be sought to be enforced, nor to the time within which proceedings may be commenced to establish the Contractor's liability with respect to the Contractor's obligations other than specifically to correct the Work.

§ 12.3 ACCEPTANCE OF NONCONFORMING WORK

If the Owner prefers to accept Work that is not in accordance with the requirements of the Contract Documents, the Owner may do so instead of requiring its removal and correction, in which case the Contract Sum will be reduced as appropriate and equitable. Such adjustment shall be effected whether or not final payment has been made.

ARTICLE 13 MISCELLANEOUS PROVISIONS § 13.1 GOVERNING LAW

The Contract, any dispute, claim, or controversy relating to the Contract, and all the rights and obligations of the parties shall, in all respects, be interpreted, construed, enforced and governed by and under the laws of the State of South Carolina, except its choice of law rules.

§ 13.2 SUCCESSORS AND ASSIGNS

The Owner and Contractor respectively bind themselves, their partners, successors, assigns and legal representatives to covenants, agreements and obligations contained in the Contract Documents. Neither party to the Contract shall assign the Contract as a whole, or in part, without written consent of the other and then only in accordance with and as permitted by Regulation 19-445.2180 of the South Carolina Code of Regulations, as amended. If either party attempts to make such an assignment without such consent, that party shall nevertheless remain legally responsible for all obligations under the Contract.

§ 13.3 WRITTEN NOTICE

Unless otherwise permitted herein, all notices contemplated by the Contract Documents shall be in writing and shall be deemed given:

- .1 upon actual delivery, if delivery is by hand;
- .2 upon receipt by the transmitting party of confirmation or reply, if delivery is by electronic mail, facsimile, telex or telegram;
- .3 upon receipt, if delivery is by the United States mail.

Notice to Contractor shall be to the address provided in Section 8.4.2 of the Agreement. Notice to Owner shall be to the address provided in Section 8.3.2 of the Agreement. Either party may designate a different address for notice by giving notice in accordance with this paragraph.

§ 13.4 RIGHTS AND REMEDIES

not be reproduced prior to its completion.

§ 13.4.1 Unless expressly provided otherwise, duties and obligations imposed by the Contract Documents and rights and remedies available thereunder shall be in addition to and not a limitation of duties, obligations, rights and remedies otherwise imposed or available by law.

§ 13.4.2 No action or failure to act by the Owner, Architect or Contractor shall constitute a waiver of a right or duty afforded them under the Contract, nor shall such action or failure to act constitute approval of or acquiescence in a breach there under, except as may be specifically agreed in writing.

- § 13.4.3 Notwithstanding Section 9.10.4, the rights and obligations which, by their nature, would continue beyond the termination, cancellation, rejection, or expiration of this contract shall survive such termination, cancellation, rejection, or expiration, including, but not limited to, the rights and obligations created by the following clauses:
 - 1.5 Ownership and Use of Drawings, Specifications and Other Instruments of Service;
 - 3.5 Warranty
 - 3.17 Royalties, Patents and Copyrights
 - 3.18 Indemnification
 - 7.6 Cost or Pricing Data
 - 11.1 Contractor's Liability Insurance
 - 11.4 Performance and Payment Bond
 - 15.1.6 Claims for Listed Damages
 - 15.1.7 Waiver of Claims Against the Architect
 - 15.6 Dispute Resolution
 - 15.6.5 Service of Process

§ 13.5 TESTS AND INSPECTIONS

- § 13.5.1 Tests, inspections and approvals of portions of the Work shall be made as required by the Contract Documents and by applicable laws, statutes, ordinances, codes, rules and regulations or lawful orders of public authorities. Unless otherwise provided, the Contractor shall make arrangements for such tests, inspections and approvals with an independent testing laboratory or entity acceptable to the Owner, or with the appropriate public authority, and shall bear all related costs of tests, inspections and approvals. The Contractor shall give the Architect timely notice of when and where tests and inspections are to be made so that the Architect may be present for such procedures. The Owner shall bear costs of (1) tests, inspections or approvals that do not become requirements until after bids are received or negotiations concluded, and (2) tests, inspections or approvals where building codes or applicable laws or regulations prohibit the Owner from delegating their cost to the Contractor.
- § 13.5.2 If the Architect, Owner or public authorities having jurisdiction determine that portions of the Work require additional testing, inspection or approval not included under Section 13.5.1, the Architect will, upon written authorization from the Owner, instruct the Contractor to make arrangements for such additional testing, inspection or approval by an entity acceptable to the Owner, and the Contractor shall give timely notice to the Architect of when and where tests and inspections are to be made so that the Architect may be present for such procedures. Such costs, except as provided in Section 13.5.3, shall be at the Owner's expense.
- § 13.5.3 If such procedures for testing, inspection or approval under Sections 13.5.1 and 13.5.2 reveal failure of the portions of the Work to comply with requirements established by the Contract Documents, all costs made necessary by such failure including those of repeated procedures and compensation for the Architect's services and expenses shall be at the Contractor's expense.
- § 13.5.4 Required certificates of testing, inspection or approval shall, unless otherwise required by the Contract Documents, be secured by the Contractor and promptly delivered to the Architect.
- § 13.5.5 If the Architect is to observe tests, inspections or approvals required by the Contract Documents, the Architect will do so promptly and, where practicable, at the normal place of testing.
- § 13.5.6 Tests or inspections conducted pursuant to the Contract Documents shall be made promptly to avoid unreasonable delay in the Work.

§ 13.6 INTEREST

Payments due to the Contractor and unpaid under the Contract Documents shall bear interest only if and to the extent allowed by Title 29, Chapter 6, Article 1 of the South Carolina Code of Laws. Amounts due to the Owner shall bear interest at the rate of one percent a month or a pro rata fraction thereof on the unpaid balance as may be due.

§ 13.7 Reserved

٠

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

§ 13.8 PROCUREMENT OF MATERIALS BY OWNER

The Contractor accepts assignment of all purchase orders and other agreements for procurement of materials and equipment by the Owner that are identified as part of the Contract Documents. The Contractor shall, upon delivery, be responsible for the storage, protection, proper installation, and preservation of such Owner purchased items, if any, as if the Contractor were the original purchaser. The Contract Sum includes, without limitation, all costs and expenses in connection with delivery, storage, insurance, installation, and testing of items covered in any assigned purchase orders or agreements. Unless the Contract Documents specifically provide otherwise, all Contractor warranty of workmanship and correction of the Work obligations under the Contract Documents shall apply to the Contractor's installation of and modifications to any Owner purchased items,

§ 13.9 INTERPRETATION OF BUILDING CODES

As required by Title 10, Chapter 1, Section 180 of the South Caroline Code of Laws, as amended, OSE shall determine the enforcement and interpretation of all building codes and referenced standards on state buildings. The Contractor shall refer any questions, comments, or directives from local officials to the Owner and OSE for resolution.

§ 13.10 MINORITY BUSINESS ENTERPRISES

Contractor shall notify Owner of each Minority Business Enterprise (MBE) providing labor, materials, equipment, or supplies to the Project under a contract with the Contractor. Contractor's notification shall be via the first monthly status report submitted to the Owner after execution of the contract with the MBE. For each such MBE, the Contractor shall provide the MBE's name, address, and telephone number, the nature of the work to be performed or materials or equipment to be supplied by the MBE, whether the MBE is certified by the South Carolina Office of Small and Minority Business Assistance, and the value of the contract.

§ 13.11 SEVERABILITY

If any provision or any part of a provision of the Contract Documents shall be finally determined to be superseded, invalid, illegal, or otherwise unenforceable pursuant to any applicable Legal Requirements, such determination shall not impair or otherwise affect the validity, legality, or enforceability of the remaining provision or parts of the provision of the Contract Documents, which shall remain in full force and effect as if the unenforceable provision or part were deleted.

§ 13.12 ILLEGAL IMMIGRATION

Contractor certifies and agrees that it will comply with the applicable requirements of Title 8, Chapter 14 of the South Carolina Code of Laws and agrees to provide to the State upon request any documentation required to establish either: (a) that Title 8, Chapter 14 is inapplicable both to Contractor and its subcontractors or subsubcontractors; or (b) that Contractor and its subcontractors or subsubcontractors are in compliance with Title 8, Chapter 14. Pursuant to Section 8-14-60, "A person who knowingly makes or files any false, fictitious, or fraudulent document, statement, or report pursuant to this chapter is guilty of a felony and, upon conviction, must be fined within the discretion of the court or imprisoned for not more than five years, or both." Contractor agrees to include in any contracts with its subcontractors language requiring its subcontractors to (a) comply with the applicable requirements of Title 8, Chapter 14, and (b) include in their contracts with the sub-subcontractors language requiring the sub-subcontractors to comply with the applicable requirements of Title 8, Chapter 14. (An overview is available at www.procurement.sc.gov)

§ 13.13 SETOFF

The Owner shall have all of its common law, equitable, and statutory rights of set-off.

§ 13.14 DRUG-FREE WORKPLACE

The Contractor certifies to the Owner that Contractor will provide a Drug-Free Workplace, as required by Title 44, Chapter 107 of the South Carolina Code of Laws, as amended.

§ 13.15 FALSE CLAIMS

According to the S.C. Code of Laws § 16-13-240, "a person who by false pretense or representation obtains the signature of a person to a written instrument or obtains from another person any chattel, money, valuable security, or other property, real or personal, with intent to cheat and defraud a person of that property is guilty" of a crime.

§ 13.16 NON-INDEMNIFICATION

Any term or condition is void to the extent it requires the State to indemnify anyone. It is unlawful for a person charged with disbursements of state funds appropriated by the General Assembly to exceed the amounts and purposes stated in the appropriations. (§ 11-9-20) It is unlawful for an authorized public officer to enter into a contract for a purpose in which the sum is in excess of the amount appropriated for that purpose. It is unlawful for an authorized public officer to divert or appropriate the funds arising from any tax levied and collected for any one fiscal year to the payment of an indebtedness contracted or incurred for a previous year. (§ 11-1-40)

§ 13.17 OPEN TRADE (JUN 2015)

During the contract term, including any renewals or extensions, Contractor will not engage in the boycott of a person or an entity based in or doing business with a jurisdiction with whom South Carolina can enjoy open trade, as defined in SC Code Section 11-35-5300. [07-7A053-1]

ARTICLE 14 TERMINATION OR SUSPENSION OF THE CONTRACT § 14.1 TERMINATION BY THE CONTRACTOR

§ 14.1.1 The Contractor may terminate the Contract if the Work is stopped for a period of 45 consecutive days through no act or fault of the Contractor or a Subcontractor, Sub-subcontractor or their agents or employees or any other persons or entities performing portions of the Work under direct or indirect contract with the Contractor, for any of the following reasons:

- .1 Issuance of an order of a court or other public authority having jurisdiction that requires substantially all Work to be stopped; or
- .2 An act of government, such as a declaration of national emergency that requires substantially all Work to be stopped;
- .3 Because the Architect has not issued a Certificate for Payment and has not notified the Contractor of the reason for withholding certification as provided in Section 9.4.1, or because the Owner has not made payment on a Certificate for Payment within the time stated in the Contract Documents and the Contractor has stopped work in accordance with Section 9.7
- § 14.1.2 The Contractor may terminate the Contract if, through no act or fault of the Contractor or a Subcontractor, Sub-subcontractor or their agents or employees or any other persons or entities performing portions of the Work under direct or indirect contract with the Contractor, repeated suspensions, delays or interruptions of the entire Work by the Owner as described in Section 14.3 constitute in the aggregate more than 100 percent of the total number of days scheduled for completion, or 120 days in any 365-day period, whichever is less.
- § 14.1.3 If one of the reasons described in Section 14.1.1 or 14.1.2 exists, the Contractor may, upon seven days' written notice to the Owner and Architect, terminate the Contract and recover from the Owner payment for Work executed, including reasonable overhead and profit, costs incurred by reason of such termination, and damages. Any adjustment to the Contract Sum pursuant to this Section shall be made in accordance with the requirements of Article 7.
- § 14.1.4 If the Work is stopped for a period of 60 consecutive days through no act or fault of the Contractor or a Subcontractor or their agents or employees or any other persons performing portions of the Work under contract with the Contractor because the Owner has persistently failed to fulfill the Owner's obligations under the Contract Documents with respect to matters important to the progress of the Work, the Contractor may, upon seven additional days' written notice to the Owner and the Architect, terminate the Contract and recover from the Owner as provided in Section 14.1.3.

§ 14.2 TERMINATION BY THE OWNER FOR CAUSE

not be reproduced prior to its completion.

§ 14.2.1 The Owner may terminate the Contract if the Contractor

- 11 repeatedly refuses or fails to supply enough properly skilled workers or proper materials, or otherwise fails to prosecute the Work, or any separable part of the Work, with the diligence, resources and skill that will ensure its completion within the time specified in the Contract Documents, including any authorized adjustments;
- .2 fails to make payment to Subcontractors for materials or labor in accordance with the Contract Documents and the respective agreements between the Contractor and the Subcontractors;

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

- .3 repeatedly disregards applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of a public authority; or
- .4 otherwise is guilty of substantial breach of a provision of the Contract Documents.

- § 14.2.2 When any of the above reasons exist, the Owner may without prejudice to any other rights or remedies of the Owner and after giving the Contractor and the Contractor's surety, if any, seven days' written notice, terminate employment of the Contractor and may, subject to any prior rights of the surety:
 - 1 Exclude the Contractor from the site and take possession of all materials, equipment, tools, and construction equipment and machinery thereon owned by the Contractor;
 - .2 Accept assignment of subcontracts pursuant to Section 5.4; and
 - Finish the Work by whatever reasonable method the Owner may deem expedient. Upon written request of the Contractor, the Owner shall furnish to the Contractor a detailed accounting of the costs incurred by the Owner in finishing the Work.
- § 14.2.3 When the Owner terminates the Contract for one of the reasons stated in Section 14.2.1, the Contractor shall not be entitled to receive further payment until the Work is finished.
- § 14.2.4 If the unpaid balance of the Contract Sum exceeds costs of finishing the Work, including compensation for the Architect's services and expenses made necessary thereby, and other damages incurred by the Owner and not expressly waived, such excess shall be paid to the Contractor. If such costs and damages exceed the unpaid balance, the Contractor shall pay the difference to the Owner. The amount to be paid to the Contractor or Owner, as the case may be, shall be certified by the Architect, upon application, and this obligation for payment shall survive termination of the Contract.
- § 14.2.5 If, after termination for cause, it is determined that the Owner lacked justification to terminate under Section 14.2.1, or that the Contractor's default was excusable, the rights and obligations of the parties shall be the same as if the termination had been issued for the convenience of the Owner under Section 14.4.

§ 14.3 SUSPENSION BY THE OWNER FOR CONVENIENCE

- § 14.3.1 The Owner may, without cause, order the Contractor in writing to suspend, delay or interrupt the Work in whole or in part for such period of time as the Owner may determine.
- § 14.3.2 The Contract Sum and Contract Time shall be adjusted for increases in the cost and time caused by suspension, delay or interruption as described in Section 14.3.1. Any adjustment to the Contract Sum made pursuant to this section shall be made in accordance with the requirements of Article 7.3.3. No adjustment shall be made to the extent
 - .1 that performance is, was or would have been so suspended, delayed or interrupted by another cause for which the Contractor is responsible; or
 - .2 that an equitable adjustment is made or denied under another provision of the Contract.

§ 14.4 TERMINATION BY THE OWNER FOR CONVENIENCE

- § 14.4.1 The Owner may, at any time, terminate the Contract in whole or in part for the Owner's convenience and without cause. The Owner shall give written notice of the termination to the Contractor specifying the part of the Contract terminated and when termination becomes effective.
- § 14.4.2 Upon receipt of written notice from the Owner of such termination for the Owner's convenience, the Contractor shall
 - .1 cease operations as directed by the Owner in the notice;
 - .2 take actions necessary, or that the Owner may direct, for the protection and preservation of the Work;
 - .3 except for Work directed to be performed prior to the effective date of termination stated in the notice, terminate all existing subcontracts and purchase orders and enter into no further subcontracts and purchase orders; and
 - .4 complete the performance of the Work not terminated, if any.
- § 14.4.3 In case of such termination for the Owner's convenience, the Contractor shall be entitled to receive payment for Work executed, and costs incurred by reason of such termination, and any other adjustments otherwise allowed by the Contract. Any adjustment to the Contract Sum made pursuant to this Section 14.4 shall be made in accordance with the requirements of Article 7.3.3.

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

under license number 2009500317 , and is not for resale. This document is licensed by The American Institute of Architects for one-time use only, and may

not be reproduced prior to its completion.

§ 14.4.4 Contractor's failure to include an appropriate termination for convenience clause in any subcontract shall not (i) affect the Owner's right to require the termination of a subcontract, or (ii) increase the obligation of the Owner beyond what it would have been if the subcontract had contained an appropriate clause.

§ 14.4.5 Upon written consent of the Contractor, the Owner may reinstate the terminated portion of this Contract in whole or in part by amending the notice of termination if it has been determined that:

- the termination was due to withdrawal of funding by the General Assembly, Governor, or State Fiscal Accountability Authority or the need to divert project funds to respond to an emergency as defined by Regulation 19-445.2110(B) of the South Carolina Code of Regulations, as amended;
- .2 funding for the reinstated portion of the work has been restored;
- .3 circumstances clearly indicate a requirement for the terminated work; and
- .4 reinstatement of the terminated work is advantageous to the Owner.

§ 14.5 CANCELLATION AFTER AWARD BUT PRIOR TO PERFORMANCE

Pursuant to Title 11, Chapter 35 and Regulation 19-445.2085 of the South Carolina Code of Laws and Regulations, as amended, this contract may be canceled after award but prior to performance.

ARTICLE 15 CLAIMS AND DISPUTES § 15.1 CLAIMS § 15.1.1 DEFINITION

A Claim is a demand or assertion by one of the parties seeking, as a matter of right, payment of money, or other relief with respect to the terms of the Contract. The term "Claim" also includes other disputes and matters in question between the Owner and Contractor arising out of or relating to the Contract. A voucher, invoice, payment application or other routine request for payment that is not in dispute when submitted is not a Claim under this definition. The responsibility to substantiate Claims shall rest with the party making the Claim.

§ 15.1.2 NOTICE OF CLAIMS

Claims by either the Owner or Contractor must be initiated by written notice to the other party and to the Architect Such notice shall include sufficient information to advise the Architect and other party of the circumstances giving rise to the claim, the specific contractual adjustment or relief requested and the basis of such request. Claims by either party arising prior to the date final payment is due must be initiated within 21 days after occurrence of the event giving rise to such Claim or within 21 days after the claimant first recognizes the condition giving rise to the Claim, whichever is later except as stated for adverse weather days in Section 15.1.5.2. By failing to give written notice of a Claim within the time required by this Section, a party expressly waives its claim.

§ 15.1.3 CONTINUING CONTRACT PERFORMANCE

Pending final resolution of a Claim, including any administrative review allowed under Section 15.6, except as otherwise agreed in writing or as provided in Section 9.7 and Article 14, the Contractor shall proceed diligently with performance of the Contract and the Owner shall continue to make payments in accordance with the Contract Documents. The Architect will issue Certificates for Payment in accordance with the initial decisions and determinations of the Architect.

§ 15.1.4 CLAIMS FOR ADDITIONAL COST

If the Contractor wishes to make a Claim for an increase in the Contract Sum, written notice as provided herein shall be given before proceeding to execute the Work. Prior notice is not required for Claims relating to an emergency endangering life or property arising under Section 10.4.

§ 15.1.5 CLAIMS FOR ADDITIONAL TIME

not be reproduced prior to its completion.

§ 15.1.5.1 If the Contractor wishes to make a Claim for an increase in the Contract Time, written notice as provided herein shall be given. The Contractor's Claim shall include an estimate of cost and of probable effect of delay on progress of the Work. In the case of a continuing delay, only one Claim is necessary. Claims for an increase in the Contract Time shall be based on one additional calendar day for each full calendar day that the Contractor is prevented from working.

§ 15.1.5.2 If adverse weather conditions are the basis for a Claim for additional time, such Claim shall be documented by data substantiating that weather conditions were abnormal for the period of time, could not have been reasonably anticipated and had an adverse effect on the scheduled construction.

- 1 Claims for adverse weather shall be based on actual weather conditions at the job site or other place of performance of the Work, as documented in the Contractor's job site log.
- .2 For the purpose of this Contract, a total of five (5) days per calendar month (non-cumulative) shall be anticipated as "adverse weather" at the job site, and such time will not be considered justification for an extension of time. If, in any month, adverse weather develops beyond the five (5) days, the Contractor shall be allowed to claim additional days to compensate for the excess weather delays only to the extent of the impact on the approved construction schedule and days the contractor was already scheduled to work. The remedy for this condition is for an extension of time only and is exclusive of all other rights and remedies available under the Contract Documents or imposed or available by law.
- 3 The Contractor shall submit monthly with their pay application all claims for adverse weather conditions that occurred during the previous month. The Architect shall review each monthly submittal in accordance with Section 15.5 and inform the Contractor and the Owner promptly of its evaluation. Approved days shall be included in the next Change Order issued by the Architect. Adverse weather conditions not claimed within the time limits of this Subparagraph shall be considered to be waived by the Contractor. Claims will not be allowed for adverse weather days that occur after the scheduled (original or adjusted) date of Substantial Completion.

§ 15.1.6 CLAIMS FOR LISTED DAMAGES

Notwithstanding any other provision of the Contract Documents, including Section 1.2.1, but subject to a duty of good faith and fair dealing, the Contractor and Owner waive Claims against each other for listed damages arising out of or relating to this Contract.

§ 15.1.6.1 For the Owner, listed damages are (i) lost revenue and profit, (ii) losses resulting from injury to business or reputation, (iii) additional or escalated overhead and administration expenses, (iv) additional financing costs, (v) costs suffered by a third party unable to commence work, (vi) attorney's fees, (vii) any interest, except to the extent allowed by Section 13.6 (Interest), (viii) lost revenue and profit for lost use of the property, (ix) costs resulting from lost productivity or efficiency.

§ 15.1.6.2 For the Contractor, listed damages are (i) lost revenue and profit, (ii) losses resulting from injury to business or reputation, (iii) additional or escalated overhead and administration expenses, (iv) additional financing costs, (v) attorney's fees, (vi) any interest, except to the extent allowed by Section 13.6 (Interest); (vii) unamortized equipment costs; and, (viii) losses incurred by subcontractors for the types of damages the Contractor has waive as against the Owner. Without limitation, this mutual waiver is applicable to all damages due to either party's termination in accordance with Article 14.

§ 15.1.6.3 Nothing contained in this Section shall be deemed to preclude an award of liquidated damages, when applicable, in accordance with the requirements of the Contract Documents. This mutual waiver is not applicable to amounts due or obligations under Section 3.18 (Indemnification).

§ 15.1.7 WAIVER OF CLAIMS AGAINST THE ARCHITECT

Notwithstanding any other provision of the Contract Documents, including Section 1.2.1, but subject to a duty of good faith and fair dealing, the Contractor waives all claims against the Architect and any other design professionals who provide design and/or project management services to the Owner, either directly or as independent contractors or subcontractors to the Architect, for listed damages arising out of or relating to this Contract. The listed damages are (i) lost revenue and profit, (ii) losses resulting from injury to business or reputation, (iii) additional or escalated overhead and administration expenses, (iv) additional financing costs, (v) attorney's fees, (vi) any interest; (vii) unamortized equipment costs; and, (viii) losses incurred by subcontractors for the types of damages the Contractor has waive as against the Owner. This mutual waiver is not applicable to amounts due or obligations under Section 3.18 (Indemnification).

§ 15.2 Reserved.

§ 15.3 Reserved.

not be reproduced prior to its completion.

§ 15.5 CLAIM AND DISPUTES - DUTY OF COOPERATION, NOTICE, AND ARCHITECTS INITIAL DECISION

§ 15.5.1 Contractor and Owner are fully committed to working with each other throughout the Project to avoid or minimize claims. To further this goal, Contractor and Owner agree to communicate regularly with each other and the Architect at all times notifying one another as soon as reasonably possible of any issue that if not addressed may cause loss, delay, and/or disruption of the Work. If claims do arise, Contractor and Owner each commit to resolving such claims in an amicable, professional, and expeditious manner to avoid unnecessary losses, delays, and disruptions to the Work.

- § 15.5.2 Claims shall first be referred to the Architect for initial decision. An initial decision shall be required as a condition precedent to resolution pursuant to Section 15.6 of any Claim arising prior to the date of final payment, unless 30 days have passed after the Claim has been referred to the Architect with no decision having been rendered, or after all the Architect's requests for additional supporting data have been answered, whichever is later. The Architect will not address claims between the Contractor and persons or entities other than the Owner.
- § 15.5.3 The Architect will review Claims and within ten days of the receipt of a Claim (1) request additional supporting data from the claimant or a response with supporting data from the other party or (2) render an initial decision in accordance with Section 15.5.5.
- § 15.5.4 If the Architect requests a party to provide a response to a Claim or to furnish additional supporting data, such party shall respond, within ten days after receipt of such request, and shall either (1) provide a response on the requested supporting data, (2) advise the Architect when the response or supporting data will be furnished or (3) advise the Architect that all supporting data has already been provided. Upon receipt of the response or supporting data, the Architect will render an initial decision in accordance with Section 15.5.5.
- § 15.5.5 The Architect will render an initial decision in writing; (1) stating the reasons therefor; and (2) notifying the parties of any change in the Contract Sum or Contract Time or both. The Architect will deliver the initial decision to the parties within two weeks of receipt of any response or supporting data requested pursuant to Section 16.4 or within such longer period as may be mutually agreeable to the parties. If the parties accept the initial decision, the Architect shall prepare a Change Order with appropriate supporting documentation for the review and approval of the parties and the Office of State Engineer. If either the Contractor, Owner, or both, disagree with the initial decision, the Contractor and Owner shall proceed with dispute resolution in accordance with the provisions of Section 15.6.
- § 15.5.6 In the event of a Claim against the Contractor, the Owner may, but is not obligated to, notify the surety, if any, of the nature and amount of the Claim. If the Claim relates to a possibility of a Contractor's default, the Owner may, but is not obligated to, notify the surety and request the surety's assistance in resolving the controversy.

§ 15.6 DISPUTE RESOLUTION

not be reproduced prior to its completion.

- § 15.6.1 If a claim is not resolved pursuant to Section 15.5 to the satisfaction of either party, both parties shall attempt to resolve the dispute at the field level through discussions between Contractor's Representative and Owner's Representative. If a dispute cannot be resolved through Contractor's Representative and Owner's Representative, then the Contractor's Senior Representative and the Owner's Senior Representative, upon the request of either party, shall meet as soon as conveniently possible, but in no case later than twenty-one days after such a request is made, to attempt to resolve such dispute. Prior to any meetings between the Senior Representatives, the parties will exchange relevant information that will assist the parties in resolving their dispute. The meetings required by this Section are a condition precedent to resolution pursuant to Section 15.6.2.
- § 15.6.2 If after meeting in accordance with the provisions of Section 15.6.1, the Senior Representatives determine that the dispute cannot be resolved on terms satisfactory to both the Contractor and the Owner, then either party may submit the dispute by written request to South Carolina's Chief Procurement Officer for Construction (CPOC). Except as otherwise provided in Article 15, all claims, claims, or controversies relating to the Contract shall be resolved exclusively by the appropriate Chief Procurement Officer in accordance with Title 11, Chapter 35, Article 17 of the South Carolina Code of Laws, or in the absence of jurisdiction, only in the Court of Common Pleas for, or in the absence of jurisdiction a federal court located in, Richland County, State of South Carolina. Contractor agrees

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

under license number 2009500317 , and is not for resale. This document is licensed by The American Institute of Architects for one-time use only, and may

that any act by the State regarding the Contract is not a waiver of either the State's sovereign immunity or the State's immunity under the Eleventh Amendment of the United State's Constitution.

§ 15.6.3 If any party seeks resolution to a dispute pursuant to Section 15.6.2, the parties shall participate in non-binding mediation to resolve the claim. If the claim is governed by Title 11, Chapter 35, Article 17 of the South Carolina Code of Laws as amended and the amount in controversy is \$100,000.00 or less, the CPOC shall appoint a mediator, otherwise, the mediation shall be conducted by an impartial mediator selected by mutual agreement of the parties, or if the parties cannot so agree, a mediator designated by the American Arbitration Association ("AAA") pursuant to its Construction Industry Mediation Rules. The mediation will be governed by and conducted pursuant to a mediation agreement negotiated by the parties or, if the parties cannot so agree, by procedures established by the mediator.

§ 15.6.4 Without relieving any party from the other requirements of Sections 15.5 and 15.6, either party may initiate proceedings in the appropriate forum prior to initiating or completing the procedures required by Sections 15.5 and 15.6 if such action is necessary to preserve a claim by avoiding the application of any applicable statutory period of limitation or repose.

§ 15.6.5 SERVICE OF PROCESS

Contractor consents that any papers, notices, or process necessary or proper for the initiation or continuation of any claims, claims, or controversies relating to the Contract; for any court action in connection therewith; or for the entry of judgment on any award made, may be served on Contractor by certified mail (return receipt requested) addressed to Contractor at the address provided for the Contractor's Senior Representative or by personal service or by any other manner that is permitted by law, in or outside South Carolina. Notice by certified mail is deemed duly given upon deposit in the United States mail.

	PROJECT-SPECIFIC REQUIREMENTS AND INFORMATION TION REQUIREMENTS (Indicate the inspection services required by the Contract)
V	Special Inspections are required and are not part of the Contract Sum. (see section 01400) Building Inspections are required and are not part of the Contract Sum. (see section 01400)
The	inspections required for this Work are:
(Indi	icate which services are required and the provider)
	Civil:
\Box s	tructural:
	Mechanical:
$\overline{\sqcap}_{P}$	lumbing:
— ✓ E	Electrical:
	Gas:
	Other (list):

§ 16.1.1 Contractor shall schedule and request inspections in an orderly and efficient manner and shall notify the Owner whenever the Contractor schedules an inspection in accordance with the requirements of Section 16.1. Contractor shall be responsible for the cost of inspections scheduled and conducted without the Owner's knowledge and for any increase in the cost of inspections resulting from the inefficient scheduling of inspections.

§ 16.2 List Cash Allowances, if any. (Refer to attachments as needed, or enter NONE)

None

Remarks: Refer to Specification Section 01 40 00 for inspection requirements

AIA Document A201™-2007. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997 and 2007 by The

§ 16.3 Requirements for Record Drawings, if any. (Refer to attachments as needed, or enter NONE)
Refer to Scetion 01 78 10 for Project Record Document Requirements

§ 16.4 Requirements for Shop Drawings and other submittals, if any, including number, procedure for submission, list of materials to be submitted, etc. (Refer to attachments as needed, or enter NONE)

Refer to Section 01 33 00 for Submittal Procedures as well as individual specifications for submittal requirements.

§ 16.5 Requirements for signage, on-site office or trailer, utilities, restrooms, etc., in addition to the Contract, if any. (Refer to attachments as needed, or enter NONE)

Refer to 01 50 00 for Temporary Facilities and Controls

§ 16.6 Requirements for Project Cleanup in addition to the Contract, if any. (Refer to attachments as needed, or enter NONE)

Refer to Section 01 77 00 for final cleaning as part of Closeout Procedures.

§ 16.7 List all attachments that modify these General Conditions. (If none, enter NONE)

NONE

USC SUPPLEMENTAL GENERAL CONDITIONS FOR CONSTRUCTION PROJECTS

WORK AREAS

- 1. The Contractor shall maintain the job site in a safe manner at all times. This includes (but is not limited to) the provision and/or maintenance of lighting, fencing, barricades around obstructions, and safety and directional signage.
- 2. Contractor's employees shall take all reasonable means not to interrupt the flow of student traffic in building corridors, lobbies, stairs and exterior walks. All necessary and reasonable safety precautions shall be taken to prevent injury to building occupants while transporting materials and equipment through the work area. Providing safe, accessible, plywood-shielded pedestrian ways around construction may be required if a suitable alternative route is not available.
- 3. At the beginning of the project, the USC Project Manager will establish the Contractor's lay-down area. This area will also be used for the Contractor's work vehicles. The lay-down area will be clearly identified to the contractor by the Project Manager, with a sketch or drawing provided to USC Parking Services. In turn, Parking Services will mark off this area with a sign containing the project name, Project Manager's name, Contractor name and contact number, and end date. Where this area is subject to foot traffic, protective barriers will be provided as specified by the Project Manager. The area will be maintained in a neat and orderly fashion.
- 4. Work vehicles parked in the lay down area (or designated parking areas) will be clearly marked and display a USC-furnished placard for identification. No personal vehicles will be allowed in this area, or in any areas surrounding the construction site. Personal vehicles must be parked in the perimeter parking lots or garages. Temporary parking permits can be obtained at the Contractor's expense at the USC Parking Office located in the Pendleton Street parking garage. Refer to the CAMPUS VEHICLE EXPECTATIONS (below) for additional information.
- 5. Contractor is responsible for removal of all debris from the site, and is required to provide the necessary dumpsters which will be emptied on a regular basis. Construction waste must not be placed in University dumpsters. The construction site must be thoroughly cleaned with all trash picked up and properly disposed of on a daily basis and the site must be left in a safe and sanitary condition each day. The University will inspect job sites regularly and will fine any contractor found to be in violation of this requirement an amount of up to \$1,000 per violation.
- 6. Where it is necessary to jump curbs, dimensional lumber and plywood must be built up to appropriate curb elevation to protect curbs from damage. Contractor will be responsible for any project related damage.
- 7. The Contractor shall be responsible for erosion and sediment control measures where ground disturbances are made.

PROJECT FENCING

- 8. All construction projects with exterior impacts shall have construction fencing at the perimeter. Fencing shall be 6' chain link with black or green privacy fabric (80-90% blockage). For fence panels with footed stands, sandbag weights shall be placed on the inside of the fence. Ripped sandbags shall be replaced immediately.
- 9. For projects with long fencing runs and/or high profile locations, decorative USC banners shall be used on top of privacy fabric; banners should be used at a ratio of one banner for every five fence

M:\Facilities Resources\Procurement\Memos & Form Letters\USC Suppl Conditions Updated 04-2015.doc

- panels. USC Project Manager will make arrangements for banner delivery for Contractor to hang.
- 10. The use of plastic safety fencing is discouraged and shall only be used on a temporary basis (less than four weeks) where absolutely necessary. Safety fencing shall be a neon yellow-green, high-visibility fencing equal to 'Kryptonight' by Tenax. Safety fencing shall be erected and maintained in a neat and orderly fashion throughout the project.
- 11. Vehicles and all other equipment shall be contained within a fenced area if they are on site for more than 3 consecutive calendar days.

BEHAVIOR

- 12. Fraternization between Contractor's employees and USC students, faculty or staff is strictly prohibited.
- 13. USC will not tolerate rude, abusive or degrading behavior on the job site. Heckling and cat-calling directed toward students, faculty or staff or any other person on USC property is strictly prohibited. Any contractor whose employees violate this requirement will be assessed a fine of up to \$500 per violation.
- 14. Contractor's employees must adhere to the University's policy of maintaining a drug-free and tobacco-free campus. Tobacco product trash that is found on the jobsite may result in a \$25/piece fee.

HAZARDOUS MATERIALS & SAFETY COMPLIANCE

- 15. A USC Permit to Work must be signed prior to any work being performed by the general contractor or sub-contractor(s).
- 16. The contractor will comply with all regulations set forth by OSHA, EPA and SCDHEC. Contractor must also adhere to USC's internal policies and procedures (available by request). Upon request, the contractor will submit all Safety Programs and Certificates of Insurance to the University for review.
- 17. Contractor must notify the University immediately upon the discovery of suspect material which may contain asbestos or other such hazardous materials. These materials must not be disturbed until approved by the USC Project Manager.
- 18. In the event of an OSHA inspection, the Contractor shall immediately call the Facilities Call Center, 803-777-4217, and report that an OSHA inspector is on site. An employee from USC's Safety Unit will arrive to assist in the inspection.

LANDSCAPE & TREE PROTECTION

- 19. In conjunction with the construction documents, the USC Arborist shall direct methods to minimize damage to campus trees. Tree protection fencing is required to protect existing trees and other landscape features to be affected by a construction project. The location of this fence will be evaluated for each situation with the USC Arborist, Landscape Architect and Project Manager. Tree protection fencing may be required along access routes as well as within the project area itself. Fence locations may have to be reset throughout the course of the project.
- 20. The tree protection fence shall be 6' high chain link fence with 80-90% privacy screening unless otherwise approved by USC Arborist and/or Landscape Architect. If the tree protection fence is completely within a screened jobsite fence perimeter, privacy fabric is not required. In-ground

M:\Facilities Resources\Procurement\Memos & Form Letters\USC Suppl Conditions Updated 04-2015.doc

fence posts are preferred in most situations for greater protection. If utility or pavement conflicts are present, fence panels in footed stands are acceptable. See attached detail for typical tree protection fencing.

- 21. No entry, vehicle parking, or materials storage will be allowed inside the tree protection zone. A 4" layer of mulch shall be placed over the tree protection area to maintain moisture in the root zone.
- Where it is necessary to cross walks, tree root zones (i.e., under canopy) or lawns the following protective measures shall be taken:
 - a. For single loads up to 9,000 lbs., a 3/4" minimum plywood base shall be placed over 4" of mulch.
 - b. For single loads over 9,000 lbs., two layers of 3/4" plywood shall be placed over 4" of mulch.
 - c. Plywood sheets shall be replaced as they deteriorate or delaminate with exposure.
 - d. For projects requiring heavier loads, a construction entry road consisting of 10' X 16' oak logging mats on 12" coarse, chipped, hardwood base. Mulch and logging mats shall be supplemented throughout the project to keep matting structurally functional.
- 23. Damage to any trees during construction shall be assessed by the USC Arborist, who will stipulate what action will be taken for remediation of damage. The cost of any and all remediation will be assumed by the contractor at no additional cost to the project. Compensation for damages may be assessed up to \$500 per caliper inch of tree (up to 8") and \$500 per inch of diameter at breast height (for trees over 8").
- 24. Damage to trunks and limbs, as well as disturbance of the root zone under the dripline of tree, including compaction of soil, cutting or filling, or storage of materials, shall qualify as damage and subject to remediation.
- 25. Any damage to existing pavements or landscaping (including lawn areas and irrigation) will be remediated before final payment is made.

TEMPORARY FACILITIES

- 26. Contractor will be responsible for providing its own temporary toilet facilities, unless prior arrangements are made with the USC Project Manager.
- 27. Contractor must provide its own electrical power supply. Water may be available to the extent of existing sources. Any needed or desired taps, connections, or metering devices, shall be at the sole expense of the contractor.
- 28. Use of USC communications facilities (telephones, computers, etc.) by the Contractor is prohibited, unless prior arrangements are made with the USC Project Manager.

CAMPUS KEYS

29. Contractor must sign a Contractor Key Receipt/Return form before any keys are issued. Keys must be returned immediately upon the completion of the work. The Contractor will bear the cost of any re-keying necessary due to the loss of or failure to return keys.

WELDING

30. A welding (hot work) permit must be issued by the University Fire Marshall before any welding can begin inside a building. The USC Project Manager will coordinate.


M:\Facilities Resources\Procurement\Memos & Form Letters\USC Suppl Conditions Updated 04-2015.doc

PROJECT EVALUATION & CLOSE-OUT

- 31. For all projects over \$100,000, including IDCs, a Contractor Performance Evaluation (SE 397) will be reviewed with the GC at the beginning of the project and a copy given to the GC. At the end of the project the form will be completed by the USC Project Manager and a Construction Performance rating will be established.
- 32. Contractor must provide all O&M manuals, as-built drawings, and training of USC personnel on new equipment, controls, etc. prior to Substantial Completion. Final payment will not be made until this is completed.

CAMPUS VEHICLE EXPECTATIONS

- 33. Personal vehicles must be parked in the perimeter parking lots or garages. Temporary parking permits can be obtained at the Contractor's expense at the USC Parking Office located in the Pendleton Street parking garage.
- 34. All motorized vehicle traffic on USC walkways and landscape areas must be approved by the USC Project Manager and Parking Division, have a USC parking placard, and be parked within the approved laydown area. Violators may be subject to ticketing, towing and fines.
- 35. All motorized vehicles that leak or drip liquids are prohibited from traveling or parking on walks or landscaped areas.
- 36. Drivers of equipment or motor vehicles that damage university hardscape or landscape will be held responsible for damages and restoration expense.
- 37. All vehicles parked on landscape, hardscape, or in the process of service delivery, must display adequate safety devices, i.e. flashing lights, cones, signage, etc.
- 38. All drivers of equipment and vehicles shall be respectful of University landscape, equipment, structures, fixtures and signage.
- 39. All incidents of property damage shall be reported to Parking Services or the Work Management Center.



NOTES:

- PROVIDE PROTECTION FENCING FOR ALL TREES WITHIN AREA OF DISTURBANCE AND CONSTRUCTION ACCESS.
- 2. PROTECTION FENCING SHALL BE IN PLACE PRIOR TO BEGINNING CONSTRUCTION.
- 3. PROTECTION FENCING TO BE PLACED AT THE OUTSIDE OF THE CANOPY DRIPLINE, OR AT A DISTANCE OF ONE FOOT PER ONE INCH OF TREE DIAMETER, MEASURED AT BREAST HEIGHT, WHICHEVER IS LARGER, UNLESS OTHERWISE INDICATED ON LANDSCAPE PLAN OR APPROVED BY UNIVERSITY ARBORIST.
- 4. IN—GROUND POSTS ARE STANDARD. IF EXISTING ROOTS, UTILITIES OR PAVEMENT PRECLUDE USE OF IN—GROUND POSTS, FOOTED STANDS ARE ACCEPTABLE. SAND BAGS SHALL BE PLACED ON THE INSIDE OF FENCE.
- 5. DAMAGE TO ANY TREES DURING CONSTRUCTION SHALL BE ASSESSED BY UNIVERSITY ARBORIST AND THE UNIVERSITY ARBORIST SHALL STIPULATE WHAT ACTION WILL BE TAKEN FOR REMEDIATION OF DAMAGE. THE COST OF ANY AND ALL REMEDIATION WILL BE ASSUMED BY CONTRACTOR AT NO ADDITONAL COST TO THE PROJECT.
- 6. DISTURBANCE OF ROOT ZONE UNDER DRIPLINE OF TREE, INCLUDING COMPACTION OF SOIL, CUTTING OR FILLING OR STORAGE OF MATERIALS SHALL QUALIFY AS DAMAGE AND SUBJECT TO REMEDIATION.

 $\frac{\text{USC-1206 Flora Street Mill Renovation - Fire Alarm Bid Package}}{\text{H27-I851 50001658-25}}$ Project Name:

Project Number:

CONTRACTOR'S ONE YEAR GUARANTEE

STATE OF
COUNTY OF
WE
as General Contractor on the above-named project, do hereby guarantee that all work executed under the requirements of the Contract Documents shall be free from defects due to faulty materials and /or workmanship for a period of one (1) year from date of acceptance of the work by the Owner and/or Architect/Engineer; and hereby agree to remedy defects due to faulty materials and/or workmanship, and pay for any damage resulting wherefrom, at no cost to the Owner, provided; however, that the following are excluded from this guarantee;
Defects or failures resulting from abuse by Owner.
Damage caused by fire, tornado, hail, hurricane, acts of God, wars, riots, or civil commotion.
[Name of Contracting Firm]
*By
Title
*Must be executed by an office of the Contracting Firm.
SWORN TO before me this day of, 2 (seal)
State
My commission expires

SE-355

PERFORMANCE BOND

KNOW ALL Name: Address:			
hereinafter ref Name: Address:	Perred to as "Contractor", and (Insert full name and		
Name:	University of South Carolina 1300 Pickens St	and firmly bound unto (Insert full name and address of A	
of the Bond to	Perred to as "Agency", or its successors or assig	ns, the sum of(\$) he Contractor and Surety bind themselves, their firmly by these presents.	
State Proj State Proj Brief Des in accordance Name: Address: which agreem IN WITNESS each cause thi	ect Name: 1206 Flora Street Mill Renovation - ect Number: H27-I851 50001658-25 cription of Awarded Work: Installation of a ne with Drawings and Specifications prepared by Goodwyn, Mills & Cawood (GMC) / Marc V 1219 Wayne Street Columbia, SC 29201 ent is by reference made a part hereof, and is h	Varren, AIA	stated herein, do
CONTRAC By:	TOR (Seal)	SURETY By:	(Seal)
Print Name	:	Print Name:	
Print Title:		Print Title:(Attach Power of Attorney)	
Witness:		Witness:	

(Additional Signatures, if any, appear on attached page)

PERFORMANCE BOND

NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION IS SUCH THAT:

- 1. The Contractor and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Agency for the full and faithful performance of the contract, which is incorporated herein by reference.
- 2. If the Contractor performs the contract, the Surety and the Contractor have no obligation under this Bond, except to participate in conferences as provided in paragraph 3.1.
- **3.** The Surety's obligation under this Bond shall arise after:
- 3.1 The Agency has notified the Contractor and the Surety at the address described in paragraph 10 below, that the Agency is considering declaring a Contractor Default and has requested and attempted to arrange a conference with the Contractor and the Surety to be held not later than 15 days after receipt of such notice to discuss methods of performing the Contract. If the Agency, the Contractor and the Surety agree, the Contractor shall be allowed a reasonable time to perform the Contract, but such an agreement shall not waive the Agency's right, if any, subsequently to declare a Contractor Default; or
- **3.2** The Agency has declared a Contractor Default and formally terminated the Contractor's right to complete the Contract.
- **4.** The Surety shall, within 15 days after receipt of notice of the Agency's declaration of a Contractor Default, and at the Surety's sole expense, take one of the following actions:
- **4.1** Arrange for the Contractor, with consent of the Agency, to perform and complete the Contract; or
- 4.2 Undertake to perform and complete the Contract itself, through its agents or through independent contractors; or
- 4.3 Obtain bids or negotiated proposals from qualified contractors acceptable to the Agency for a contract for performance and completion of the Contract, arrange for a contract to be prepared for execution by the Agency and the contractor selected with the Agency's concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the Bonds issued on the Contract, and pay to the Agency the amount of damages as described in paragraph 7 in excess of the Balance of the Contract Sum incurred by the Agency resulting from the Contractor Default; or
- **4.4** Waive its right to perform and complete, arrange for completion, or obtain a new contractor, and:
 - **4.4.1** After investigation, determine the amount for which it may be liable to the Agency and, within 60 days of waiving its rights under this paragraph, tender payment thereof to the Agency: or
 - **4.4.2** Deny liability in whole or in part and notify the Agency, citing the reasons therefore.
- 5. Provided Surety has proceeded under paragraphs 4.1, 4.2, or
- 4.3, the Agency shall pay the Balance of the Contract Sum to either:
- 5.1 Surety in accordance with the terms of the Contract; or
- **5.2** Another contractor selected pursuant to paragraph 4.3 to perform the Contract.
- 5.3 The balance of the Contract Sum due either the Surety or another contractor shall be reduced by the amount of damages as described in paragraph 7.
- 6. If the Surety does not proceed as provided in paragraph 4 with reasonable promptness, the Surety shall be deemed to be in default on this Bond 15 days after receipt of written notice from the Agency to the Surety demanding that the Surety perform its obligations under this Bond, and the Agency shall be entitled to enforce any remedy available to the Agency.

- **6.1** If the Surety proceeds as provided in paragraph 4.4 and the Agency refuses the payment tendered or the Surety has denied liability, in whole or in part, then without further notice the Agency shall be entitled to enforce any remedy available to the Agency.
- 6.2 Any dispute, suit, action or proceeding arising out of or relating to this Bond shall be governed by the Dispute Resolution process defined in the Contract Documents and the laws of the State of South Carolina.
- 7. After the Agency has terminated the Contractor's right to complete the Contract, and if the Surety elects to act under paragraph 4.1, 4.2, or 4.3 above, then the responsibilities of the Surety to the Agency shall be those of the Contractor under the Contract, and the responsibilities of the Agency to the Surety shall those of the Agency under the Contract. To a limit of the amount of this Bond, but subject to commitment by the Agency of the Balance of the Contract Sum to mitigation of costs and damages on the Contract, the Surety is obligated to the Agency without duplication for:
- 7.1 The responsibilities of the Contractor for correction of defective Work and completion of the Contract; and
- 7.2 Additional legal, design professional and delay costs resulting from the Contractor's Default, and resulting from the actions or failure to act of the Surety under paragraph 4; and
- 7.3 Damages awarded pursuant to the Dispute Resolution Provisions of the Contract. Surety may join in any Dispute Resolution proceeding brought under the Contract and shall be bound by the results thereof; and
- 7.4 Liquidated Damages, or if no Liquidated Damages are specified in the Contract, actual damages caused by delayed performance or non-performance of the Contractor.
- **8.** The Surety shall not be liable to the Agency or others for obligations of the Contractor that are unrelated to the Contract, and the Balance of the Contract Sum shall not be reduced or set-off on account of any such unrelated obligations. No right of action shall accrue on this Bond to any person or entity other than the Agency or its heirs, executors, administrators, or successors.
- **9.** The Surety hereby waives notice of any change, including changes of time, to the contract or to related subcontracts, purchase orders and other obligations.
- **10.** Notice to the Surety, the Agency or the Contractor shall be mailed or delivered to the address shown on the signature page.
- 11. Definitions
- 11.1 Balance of the Contract Sum: The total amount payable by the Agency to the Contractor under the Contract after all proper adjustments have been made, including allowance to the Contractor of any amounts to be received by the Agency in settlement of insurance or other Claims for damages to which the Contractor si entitled, reduced by all valid and proper payments made to or on behalf of the Contractor under the Contract.
- 11.2 Contractor Default: Failure of the Contractor, which has neither been remedied nor waived, to perform the Contract or otherwise to comply with the terms of the Contract.

SE-357

LABOR & MATERIAL PAYMENT BOND

KNOW ALL	MEN BY THESE PRESENTS, that (Insert full	l name or legal title and address of Contractor)
Name:		
Address:		
hereinafter refe	erred to as "Contractor", and (Insert full name and	address of principal place of business of Surety)
Name:		
Address:		
hereinafter cal	led the "surety", are jointly and severally held	and firmly bound unto (Insert full name and address of Agency)
Name:		
Address:		
	Columbia, SC 29208	
of the Bond to	erred to as "Agency", or its successors or assign which payment to be well and truly made, successors and assigns, jointly and severally,	gns, the sum of(\$), being the sum the Contractor and Surety bind themselves, their heirs, executors, firmly by these presents.
WHEREAS,	Contractor has by written agreement dated	entered into a contract with Agency to construct
State Proj	ect Name: 1206 Flora Street Mill Renovation -	Fire Alarm Bid Package
State Proj	ect Number: <u>H27-I851 50001658-25</u>	
Brief Desc	cription of Awarded Work: Installation of a ne	w Fire Alarm System throughout the existing building.
in accordance	with Drawings and Specifications prepared by	(Insert full name and address of A/E)
Name:	Goodwyn, Mills & Cawood (GMC) / Marc V	Varren, AIA
Address:	1219 Wayne Street	
	Columbia, SC 29201	
which agreeme	ent is by reference made a part hereof, and is h	ereinafter referred to as the Contract.
		ng to be legally bound hereby, subject to the terms stated herein, do ecuted on its behalf by its authorized officer, agent or representative.
DATED 41.5.	Jan of 2	DOND NUMBED
(sh	day of , 2 , all be no earlier than Date of Contract)	BOND NUMBER
CONTRAC	TOR	SURETY
By:		Ву:
·	(Seal)	(Seal)
Print Name:		Print Name:
Print Title:		Print Title:
		(Attach Power of Attorney)
Witness:		Witness:

(Additional Signatures, if any, appear on attached page)

LABOR & MATERIAL PAYMENT BOND

NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION IS SUCH THAT:

- 1. The Contractor and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Agency to pay for all labor, materials and equipment required for use in the performance of the Contract, which is incorporated herein by reference.
- 2. With respect to the Agency, this obligation shall be null and void if the Contractor:
- 2.1 Promptly makes payment, directly or indirectly, for all sums due Claimants; and
- 2.2 Defends, indemnifies and holds harmless the Agency from all claims, demands, liens or suits by any person or entity who furnished labor, materials or equipment for use in the performance of the Contract.
- 3. With respect to Claimants, this obligation shall be null and void if the Contractor promptly makes payment, directly or indirectly, for all sums due.
- 4. With respect to Claimants, and subject to the provisions of Title 29, Chapter 5 and the provisions of §11-35-3030(2)(c) of the SC Code of Laws, as amended, the Surety's obligation under this Bond shall arise as follows:
- 4.1 Every person who has furnished labor, material or rental equipment to the Contractor or its subcontractors for the work specified in the Contract, and who has not been paid in full therefore before the expiration of a period of ninety (90) days after the date on which the last of the labor was done or performed by him or material or rental equipment was furnished or supplied by him for which such claim is made, shall have the right to sue on the payment bond for the amount, or the balance thereof, unpaid at the time of institution of such suit and to prosecute such action for the sum or sums justly due him.
- 4.2 A remote claimant shall have a right of action on the payment bond upon giving written notice by certified or registered mail to the Contractor within ninety (90) days from the date on which such person did or performed the last of the labor or furnished or supplied the last of the material or rental equipment upon which such claim is made.
- 4.3 Every suit instituted upon a payment bond shall be brought in a court of competent jurisdiction for the county or circuit in which the construction contract was to be performed, but no such suit shall be commenced after the expiration of o ne year after the day on which the last of the labor was performed or material or rental equipment was supplied by the person bringing suit.
- **5.** When the Claimant has satisfied the conditions of paragraph 4, the Surety shall promptly and at the Surety's expense take the following actions:
- 5.1 Send an answer to the Claimant, with a copy to the Agency, within sixty (60) days after receipt of the claim, stating the amounts that are undisputed and the basis for challenging any amounts that are disputed.
- **5.2** Pay or arrange for payment of any undisputed amounts.
- 5.3 The Surety's failure to discharge its obligations under this paragraph 5 shall not be deemed to constitute a waiver of defenses the Surety or Contractor may have or acquire as to a claim. However, if the Surety fails to discharge its obligations under this paragraph 5, the Surety shall indemnify the Claimant for the reasonable attorney's fees the Claimant incurs to recover any sums found to be due and owing to the Claimant.

- **6.** Amounts owed by the Agency to the Contractor under the Contract shall be used for the performance of the Contract and to satisfy claims, if any, under any Performance Bond. By the Contractor furnishing and the Agency accepting this Bond, they agree that all funds earned by the contractor in the performance of the Contract are dedicated to satisfy obligations of the Contractor and the Surety under this Bond, subject to the Agency's prior right to use the funds for the completion of the Work.
- 7. The Surety shall not be liable to the Agency, Claimants or others for obligations of the Contractor that are unrelated to the Contract. The Agency shall not be liable for payment of any costs or expenses of any claimant under this bond, and shall have under this Bond no obligations to make payments to, give notices on behalf of, or otherwise have obligations to Claimants under this Bond.
- **8.** The Surety hereby waives notice of any change, including changes of time, to the Contract or to related Subcontracts, purchase orders and other obligations.
- 9. Notice to the Surety, the Agency or the Contractor shall be mailed or delivered to the addresses shown on the signature page. Actual receipt of notice by Surety, the Agency or the contractor, however accomplished, shall be sufficient compliance as of the date received at the address shown on the signature page.
- 10. By the Contractor furnishing and the Agency accepting this Bond, they agree that this Bond has been furnished to comply with the statutory requirements of the South Carolina Code of Laws, as amended, and further, that any provision in this Bond conflicting with said statutory requirements shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. The intent is that this Bond shall be construed as a statutory Bond and not as a common law bond.
- 11. Upon request of any person or entity appearing to be a potential beneficiary of this bond, the Contractor shall promptly furnish a copy of this Bond or shall permit a copy to be made.
- 12. Any dispute, suit, action or proceeding arising out of or relating to this Bond shall be governed by the laws of the State of South Carolina.

13. DEFINITIONS

- 13.1 Claimant: An individual or entity having a direct contract with the Contractor or with a Subcontractor of the Contractor to furnish labor, materials, or equipment for use in the performance of the Contract. The intent of this Bond shall be to include without limitation in the terms "labor, materials or equipment" that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental equipment used in the Contract, architectural and engineering services required for performance of the Work of the Contractor and the Contractor's Subcontractors, and all other items for which a mechanic's lien might otherwise be asserted.
- **13.2** Remote Claimant: A person having a direct contractual relationship with a subcontractor of the Contractor or subcontractor, but no contractual relationship expressed or implied with the Contractor.
- 13.3 Contract: The agreement between the Agency and the Contractor identified on the signature page, including all Contract Documents and changes thereto.

SE-380

CHANGE ORDER NO	١.	

CHANGE ORDER TO DESIGN-BID-BUILD CONSTRUCTION CONTRACT				
	ENCY: <u>University of South Carolina</u> DJECT NAME: 1206 Flora Street Mill Renovation - Fire Alarm l	Did Dookogo		
	NECENTIADED 1125 1051 50001650 25			
CONTRACTOR:		CONTRACT DATE:		
This (Contract is changed as follows: (Insert description of change in space provided below)			
AD.	JUSTMENTS IN THE CONTRACT SUM:			
1.	Original Contract Sum:		\$	
2.	Change in Contract Sum by previously approved Change Orders:			
3.	Contract Sum prior to this Change Order		\$ 0.00	
4.	Amount of this Change Order:			
5.	New Contract Sum, including this Change Order:		\$ 0.00	
AD.	JUSTMENTS IN THE CONTRACT TIME:			
1.	Original Substantial Completion Date:			
2.	Sum of previously approved increases and decreases in Days:		Days	
3.	Change in Days for this Change Order		Days	
4.	Total Number of Days added to this Contract including this Change Order		0 Days	
5.	New Substantial Completion Date:			
CON'	TRACTOR ACCEPTANCE:			
BY	:	Date:		
	:			
<u>A/E F</u>	RECOMMENDATION FOR ACCEPTANCE:			
BY	•	Date:		
21	(Signature of Representative)			
Pri	nt Name or Representative:		_	
	NCY ACCEPTANCE AND CERTIFICATION: cify that the Agency has authorized, unencumbered funds available for obligation to this contract.			
BY	:(Signature of Representative)	Date:		
Pri	(Signature of Representative) nt Name of Representative:			
Chang	ge is within Agency Construction Contract Change Order Certification of:		Yes □ No □	
APPI	ROVED BY:	DATE:		
	(OSE Project Manager)			

SUBMIT THE FOLLOWING TO OSE

- SE-380, fully completed and signed by the Contractor, A/E and Agency;
 Detailed back-up information, with OH&P shown, from the Contractor/Subcontractor(s) that justifies the costs and schedule changes shown.
 If any item exceeds Agency certification, OSE will approved the SE-380 and return to Agency.

DOCUMENT 003126 - EXISTING HAZARDOUS MATERIAL INFORMATION

1.1 EXISTING HAZARDOUS MATERIAL INFORMATION

- A. This Document with its referenced attachments is part of the Procurement and Contracting Requirements for Project. They provide Owner's information for Bidders' convenience and are intended to supplement rather than serve in lieu of Bidders' own investigations. They are made available for Bidders' convenience and information, but are not a warranty of existing conditions. This Document and its attachments are not part of the Contract Documents.
- B. An existing Asbestos Containing Material Report (dated March 19, 2018) and a Lead-Based Paint Report (dated April 4, 2018) have been prepared for the existing facility, prepared by F&ME Consultants. Each report is hereby attached.

C. Hazardous Material Abatement:

- 1. All associated abatement shall be done by the University of South Carolina prior to the commence of construction associated with the scope of work described herein.
- 2. The contractor has a responsibility to notify the Owner and the Architect if any existing materials encountered as part of work associated with this project are suspected to be hazardous prior to disturbing any existing conditions.

D. Related Requirements:

- 1. AIA Document A701 "Instructions to Bidders" for the Bidder's responsibilities for examination of Project site and existing conditions.
- 2. Section 017320 "Selective Demolition" for notification requirements if materials suspected of containing hazardous materials are encountered.

END OF DOCUMENT 003126



ASBESTOS CONTAINING MATERIAL INVESTIGATION REPORT

UNIVERSITY OF SOUTH CAROLINA FORMER SCE&G COMPOUND MAIN 2-STORY BUILDING (BUILDING 1) 1206 FLORA STREET COLUMBIA, SOUTH CAROLINA

PREPARED FOR:



Mr. Christopher Geary University of South Carolina 1300 Pickens Street Columbia, South Carolina 29201

PREPARED BY:

F&ME Consultants 1825 Blanding Street Columbia, South Carolina 29201

March 29, 2018

F&ME Project No.: E5700.190

TABLE OF CONTENTS

1.	Executive Summary	1
2.	Introduction	3
3.	Existing building Structure	3
4.	Field assessment	
	4.1 Suspect Materials Encountered During Investigation	4
5.	Assessment Results	6
	5.1 Homogeneous Area Locations Where ACM Was Identified	7
6.	Recommendations	9
APP	PENDICES	12
	Appendix A – Site Vicinity Map	
	Appendix B – General Building Plans	
	Appendix C – Sample Location Plans	
	Appendix D – Homogeneous Area Plans	
	Appendix E – Summary of Samples	
	Appendix F – Summary of Asbestos Containing Materials	
	Appendix G – Summary of Inspection	
	Appendix H – Physical Assessment Data Sheets	
	Appendix I – Laboratory Analysis Reports	
	Appendix J – Chain of Custody Forms	
	Appendix K – Personnel Certifications	
	Appendix L – Regulatory Summary	
	Appendix M – Abatement Project Forms	

1. EXECUTIVE SUMMARY

This executive summary is intended as an overview for the convenience of the reader. This report should be reviewed in its entirety prior to making any decisions regarding this project.

F&ME Consultants Inc. (F&ME) has completed an Asbestos Containing Material (ACM) Investigation of multiple structures associated with the former SCE&G Compound (Site) located at 1206 Flora Street in Columbia, SC for the University of South Carolina (USC). This report is for the investigation of the main 2-story former mill structure (Building 1) found on the compound that fronts Flora Street. The investigation was performed in anticipation of planned renovations to both the interior and exterior of the building and was conducted in accordance with South Carolina Department of Health and Environmental Control (SCDHEC), United States Environmental Protection Agency (USEPA), National Emission Standards for Hazardous Air Pollutants (NESHAP), and Occupational Safety and Health Administration (OSHA) regulations requiring an ACM investigation prior to any demolition and/or renovation activities.

Per an agreed upon scope of work, F&ME performed this Investigation to identify ACM that may be encountered during the planned renovations, and to make recommendations regarding proper handling and disposal of any ACM found. The scope of work included a complete investigation of both the interior and exterior portions of the building, as well as sampling of the existing roof system. The initial field investigation was performed on March 13th through March 15th, 2018. A follow-up visit made for the purposes of delineating the locations of ACM materials was performed on March 26, 2018.

The ACM investigation uncovered multiple suspect materials within the interior and exterior of the building that may be impacted by the planned renovations. Of the suspect materials sampled and analyzed, laboratory results indicate that the following materials were found to be positive for asbestos content: black mastic under various flooring materials (i.e. floor tile; carpeting etc.); black mastic on fiberglass HVAC duct wrap; TSI pipe insulation; TSI mudded elbows; residual TSI pipe insulation in floor penetrations (underside of second floor); felt at base of timber column and black and gray flashing mastics.

We sincerely appreciate the opportunity to assist you with this project. Should you have any questions or require additional information concerning this Investigation, please do not hesitate to contact our office at (803) 254-4540.

Sincerely,

F&ME CONSULTANTS

Michael S. Mincey

Environmental Professional

Mile Muay

Asbestos Consultant/ Management Planner

SCDHEC License No: MP-00161

Expiration Date 01/29/2019

Glynn M. Ellen

Environmental Manager

Asbestos Consultant/ Management Planner

SCDHEC License No: MP-20979

Expiration Date 1/29/2019

2. INTRODUCTION

It is F&ME's understanding that renovations are in the planning stages for Building 1, and currently the scope of the renovations is undefined. It is also our understanding that the renovations will likely impact the entire structure, will impact both the interior and exterior of the building, and will potentially include the replacement of the existing roof system. Therefore, the scope of this ACM Investigation was to identify, assess and sample materials suspected of containing asbestos within the interior and exterior of the building, to include the roof. The initial field investigation was performed from March 13th through to March 15th, 2018, and a follow-up visit for the purpose of delineating ACM materials was performed on March 26, 2018.

The results, conclusions and recommendations from this investigation are representative of the conditions observed at the site on the dates of the field inspection. F&ME does not assume responsibility for any changes in conditions or circumstances that occur after the inspection. This report has been prepared exclusively for USC and shall not be disseminated in whole or part to other parties without prior consent from USC or F&ME Consultants, Inc. No other environmental issues were addressed as part of this report.

3. EXISTING BUILDING STRUCTURE

Building 1 is an approximate 65,000 square foot, two-story structure located at 1206 Flora Street, in Columbia SC. The structure was originally the location for the Capital City Mills and in recent years was owned and operated by SCE&G. USC took possession of the property in March of 2018. The original building construction is believed to have occurred near the turn of the century. A historic document found online indicated Capital City Mills being incorporated in 1900.

The original 2-story building is a masonry brick and concrete structure with wood



Photo 1. University of South Carolina, former SCE&G Compound, Main Building (Building 1) located at 1206 Flora Street, Columbia SC.

columns and beams throughout. There have been alterations or renovations made to the structure over its history that include more current construction. Two (2) all metal additions were noted during the investigation on northwest and southwest corners of the building. It appeared that an earlier renovation was performed to add the stairwells at the front entrance and northwest corner of the building. The stairwells were added before the metal addition on the northwest corner of the building. It also appears that the entire second floor was renovated and all new finished were installed at some point in time. Based on the condition of the building materials, the two (2) areas

with offices found on the first-floor level were likely renovated earlier than the renovations on the second floor of the building. The roof system for the main structure consists of a commercial TPO membrane roof and flashing. The additions at the northwest and southwest corners have metal roof systems.

The interior spaces of the building consisted of drywall, plaster, wood, masonry block and brick walls, carpet and various 12" x 12" floor tiles over concrete and/or wood flooring, and suspended drop ceiling system. The main warehouse area (Room 100) on the first floor is opened to the underside of the floor of the second-floor level. See Appendix A – Site Vicinity Map, for the location of the structure. See Appendix B –General Building Plans, for a layout of the building.

4. FIELD ASSESSMENT

The purpose of this Investigation was to locate, sample and record the physical characteristics of suspect ACM associated with the interior and exterior areas of the subject building, and the roof in anticipation of planned renovation activities. During the field assessment, all interior and exterior building components were visually inspected for suspect ACM and consisted of a review of wall and ceiling systems, HVAC mechanical systems, stairwells, thermal systems insulation (TSI) utilized on mechanical systems piping, pipe fittings and ductwork, floor and wall finishes, windows and glass store fronts as well as the roofing system. Once reviewed, the quantities and physical condition of suspect materials were assessed, and bulk samples of these materials were submitted for laboratory analysis.

F&ME's approach to the investigation considered the varying construction dates and the evidence of past renovation activities over the years. Common or homogeneous suspect materials were sampled independently of each other and materials in each of these areas of the building were sampled independently. Based on the age of the subject structure, some building materials such as elevator doors and brake shoes, etc., could contain asbestos. Due to the inaccessibility of these types of materials, the destructive nature of bulk sampling, and/ or the potential for voiding product warrantees and/ or fire ratings, these suspect materials were not sampled during this investigation. It is important to note that additional investigations of these building systems may be required if they are to be impacted by planned renovation activities.

During the investigation, a single run of TSI pipe insulation was found at the top of a wall in the back area toward the southwest corner of the building. In addition, two (2) mudded fittings were found in the northwest corner of Room 100. No other actual pipe insulation or mudded fittings of this type were found during the field investigation. All other TSI on piping and ductwork identified during the field investigation was non-suspect fiberglass with various suspect mastics on the seams. Approximately 40 floor penetrations from an older mechanical system in the building were noted when looking at the underside of the second floor from Room 100. These floor penetrations had a thin sheet metal cap over most of the openings. A review of these penetrations found residual TSI on the metal covers and inside the penetrations that tested positive. Should the renovations to

the building impact these penetrations they will require cleaning to remove the residual TSI by a licensed abatement contractor.

It should be noted, due to the age of the structure, with the TSI pipe insulation and mudded elbows found in the building, as well as the residual TSI found in multiple wall and floor penetrations, that remnants of older mechanical systems may be uncovered during the planned renovations. Special consideration should be given during the design development phase of the project to investigate closed wall, floor and ceiling cavities, as well as closed chases that may be uncovered. In addition, there is an indication that there may be a crawl space under a portion of the original building. No means of accessing this crawl space was found during the field investigation. Should an access point be found during the planned renovations, or if one is made to gain access to this space, it should be investigated prior to accessing, to verify whether suspect materials are present and to determine of it is safe for access.

4.1 Suspect Materials

The purpose of this investigation was to locate, sample and record the physical characteristics of suspect ACM associated with the interior and exterior portions of the subject structure. Therefore, the quantities and physical condition of suspect materials were assessed, and bulk samples of these materials were submitted for laboratory analysis. The following suspect materials and approximate amounts were identified during this ACM Investigation:

- Drywall and joint compound (>5,000 ft²)
- 2' x 2' and 2' x 4' ceiling tiles (~32,600 ft²)
- Multiple 12" x 12" vinyl floor tiles and associated mastic (~2,000 ft²)
- Multiple baseboard adhesives (~3,000 LF)
- Carpet adhesive (~30,000 ft²)
- White floor leveling compound (~600 ft²)
- Tan sink undercoating (2 sinks)
- Mastics on HVAC duct wrap (~400 ft²)
- Plaster ($\sim 3,000 \text{ ft}^2$)
- Brown window caulk (~200 LF)
- TSI pipe insulation (15 LF)
- Textured wall surfacing material (<1,000 ft²)
- Red fire stop (100 ft²)
- Mudded elbows (2 elbows)
- Various floor underfelts (88,000 ft²)
- Old floor and wall penetration TSI residue (~25 ft²)
- Timber column felt (~5 ft²)
- Expansion joint material (~1,000 LF)
- Expansion joint felts (~2,000 LF)

- Fire door material (5 Doors)
- Stucco wall fill (~100 ft²)
- Stair tread adhesive (~200 ft²)
- Interior door caulk (~10 ft²)
- Exterior door/window caulk (~25 ft²)
- White window caulk (~5 LF)
- Textured Stucco (Exterior) (~1,500 ft²)
- Built-up roofing materials (~29,000 ft²)
- Flashing ($\sim 300 \text{ ft}^2$)
- White roof caulk (~100 ft²)
- Gray roof surface coating (~1,500 ft²)
- Gray flashing mastic (~90 LF)
- Black roof patch (~10 ft²)
- Red roof patch (~5 ft²)
- Black flashing mastic (~50 ft²)
- White flashing mastic (~10 LF)
- Elevator doors (3 Doors)
- Elevator brake shoes (Unknown)

Random samples of the suspect materials were collected for laboratory analysis, and their physical characteristics were recorded. Building materials such as concrete, metal, wood, brick, carpet, etc., were not considered suspect ACM. Bulk samples of suspect materials were analyzed by Polarized Light Microscopy (PLM) in accordance with EPA 600/R-93/116. Confirmation Transmission Electron Microscopy (TEM) was also performed on any non-friable organically bound materials that tested negative for asbestos content as per SCDHEC regulations effective May 27, 2011. See Appendix E – Summary of Samples, for complete list of all samples taken. See Appendix L–SCDHEC Regulation Summary. Proper sampling and chain-of-custody protocols were followed to ensure appropriate handling and delivery of samples to the analytical laboratory. Refer to Appendix K –Personnel Certifications, for SCDHEC qualifications of Investigation personnel, and Appendix J – Chain of Custody Forms, for documentation of proper handling and delivery of samples.

5. ASSESSMENT RESULTS

A total of two hundred twenty-three (223) samples were collected from the subject building. A "first positive stop" protocol was implemented for this sampling. This protocol establishes that if the first sample of a material tested positive for asbestos content, subsequent samples were not to be analyzed, and would be considered positive as well. Therefore, due to multiple layers of some materials sampled, and the implementation of a "first positive stop" protocol, two hundred forty-two (242) samples were analyzed by PLM and sixty-one (61) were TEM-confirmed. Based on the sample results, thirty-seven (37) samples returned positive results for asbestos content. See

Appendix C –Sample Location Plan, for the various sample locations and Appendix F –Summary of Asbestos Containing Materials, for the materials determined to be ACM.

Appropriate sampling and chain-of-custody protocols were followed to ensure proper handling and delivery of samples to the analytical laboratory. Appendix I – Bulk Asbestos Analytical Report and Appendix J – Laboratory Chain of Custody were provided to show laboratory documentation of the analytical results. Appendix K – Personnel Certification, provides the qualifications for the F&ME Asbestos Inspectors.

5.1 Homogeneous Area Locations Where ACM Was Identified

The following are photographs, descriptions, and approximate quantities of the ACM identified during the Investigation. Guidance is also provided for the proper handling and disposition if the materials in these areas are to be removed. See Appendix D – Homogeneous Area Plans, for homogeneous sampling areas for the various ACM identified below.

HA-1 – Black mastic under various floor finishes (~3,600 ft²). ACM black mastic is noted under multiple flooring finishes (i.e. non-ACM floor tiles; white leveling compound; residual under carpet) in various areas throughout the 1st and 2nd floors of the building. Overall, this material is in a non-friable and intact condition. This material will must be removed and disposed of as ACM by a licensed abatement contractor prior to the beginning of renovation activities.



HA-2 - Black mastic on HVAC duct wrap (~250 ft²). Asbestos-containing black mastic on HVAC duct wrap was found above the drop ceiling in multiple areas on the 1st and 2nd floors. Overall this material was found to be in a good, intact non-friable condition with no damage being noted during the investigation. This material will must be removed and disposed of as ACM by a licensed abatement contractor prior to the beginning of renovation activities.



HA-3 – TSI pipe insulation (15 LF piping/40 SF penetrations). One (1) run of asbestos-containing TSI pipe insulation was found in the corner of H102 on the first floor of the building. No other suspect pipe insulation was found during the field investigation. Residual TSI was noted on several penetrations in the walls and ceiling of Room 100. The TSI pipe insulation was in an intact but friable condition with some localized damage being noted. Some TSI debris was noted on the floor in the area below the damage area. This material must be removed and disposed of as ACM by a licensed abatement contractor prior to the beginning of renovation activities.



HA-4 – Mudded elbows (2 elbows) The two mudded elbows were found in the north west corner of Room 100 on the 1st floor. No other mudded elbows were identified during the field investigation. This material is in an intact but friable condition with only minor localized damage. This material must be removed and disposed of as ACM by a licensed abatement contractor prior to the beginning of renovation activities.

HA-5 – Timber column felt (5 ft²) Asbestos-containing timber column felt was found on the two timber support columns in Room 111 on the 1st floor. Review of other columns throughout the build showed this condition was localized in this area and metal pedestals were the interface of the columns with the concrete slab. Overall, this material was in an intact and non-friable condition. If it is anticipated that the renovations will impact this material, it must be removed, handled and disposed of as ACM by a licensed abatement contractor prior to the beginning of renovation activities that will impact it.






HA-6 – Gray flashing mastic (90 SF) Asbestos-containing gray mastic was found on flashing at the interface of the exterior wall of the original structure and the metal roof of the all metal addition (Room 110) found on the northwest corner of the building on the metal roof. This material was found in good, intact non-friable condition with no damage being noted. If the planned renovation activities will impact this material it must be removed and disposed of as ACM by a licensed abatement contractor prior to the beginning of renovation activities.



HA-7 – Black flashing mastic (50 SF) Asbestos-containing black mastic was found on flashing at the interface of the exterior wall of the original structure and the metal roof above the rear-loading dock. This material is in good, intact non-friable condition. This material must be removed and disposed of as ACM by a licensed abatement contractor prior to the beginning of renovation activities.



HA-8 – Elevator doors/Brake pads (1 elevator, 3 doors) Asbestos-containing insulation can be found in the interior cavity of elevator doors, and pads associated with the braking systems for elevators have been known to contain asbestos in older elevators. Due to the destructive methods necessary to collect samples of these types of building components, these materials were not sampled as part of this investigation and they are assumed positive until samples can be collected and the materials proven negative by laboratory analysis. These materials, if found to be ACM must be removed and disposed of by a licensed abatement contractor prior to the beginning of renovation activities.



6. RECOMMENDATIONS

The results, conclusions, and recommendations of this Investigation are representative of the conditions observed at the site on the date of the field inspection. F&ME does not assume

responsibility for any changes in conditions or circumstances that may have occurred after this inspection.

It is our understanding that this investigation was conducted in anticipation of planned renovations to the structure. For this reason, ACM identified during this investigation must be abated prior to the commencement of renovation activities that will impact them. In addition, TSI may be found in closed wall and floor cavities as well as closed chases. If renovation activities should uncover any hidden TSI, the contractor is to stop work immediately, cordon off the area and notify USC Hazmat or F&ME Consultants.

All ACM identified during this Investigation must be abated prior to the commencement of renovation activities, where ACM will, or may potentially, be impacted. Due to the age of the building, along with the renovations and additions added over the years, there is an increase in the probability that suspect ACM may be found hidden in wall cavities. If any concealed and/or inaccessible ACM are encountered during abatement and/ or demolition activities, the affected contractor(s) must stop work, take appropriate actions, and notify the Owner or the Owner's Environmental consultant for an appropriate response action. The SCDHEC must be notified in the event any additional ACM is discovered, as well as changes in the condition of identified ACM. Appendix M – Abatement Project Forms, are provided for more information. See Appendix G – Summary of Inspection and Appendix H –Physical Assessment Data Sheets, for description and condition of ACM materials.

All abatement work must be performed by an AHERA-certified and SCDHEC-licensed Abatement Contractor. This work must be performed in accordance with all applicable regulations and guidelines, such as notification and air monitoring requirements. All asbestos waste, including contaminated building materials (i.e. original window frames etc.), must be deposited in a landfill permitted by the SCDHEC for receiving ACM.

The SCDHEC's Standards of Performance for Asbestos Projects (R 61-86.1) includes requirements for abatement projects regarding notifications, project design, air sampling and analysis, etc. For informational purposes, some of these requirements are summarized below:

Notifications. Written notification (SCDHEC Form 3430) must be submitted to SCDHEC at least two (2) calendar weeks prior to initiation of abatement activities for renovation/demolition projects. A copy of this inspection report and applicable fee payment must be attached to the notification. Additional fees may be required. Copies of all notifications and documents pertinent to the abatement operations must be posted on the job site during abatement work. The Owner/Operators must notify all parties involved with this project of the nature of the work as well as the locations and quantities of asbestos materials to be disturbed or those located near demolition/removal work areas. This notification requirement is also extended to any persons/employees who work near the demolition/removal work areas.

Project Design. Furthermore, abatement projects that will remove more than 3,000 square feet, 1,500 linear feet, or 656 cubic feet of regulated asbestos-containing materials are required to have a licensed and certified Abatement Project Designer develop a project design prior to the commencement of any abatement activities. The Abatement Contractor is required to adhere to the design, which must address all information as directed by the regulations.

Air Monitoring. The Abatement Contractor is responsible for daily personal air sampling for Abatement Workers in compliance with current OSHA standard 29 CFR 1926.1101. All remaining air monitoring services required for a renovation project (i.e. backgrounds, areas, and clearances) will be provided by the Owner or the Owner's Representative, as required by SCDHEC.

We sincerely appreciate the opportunity to be of service to USC, in this matter. If you have any questions regarding the information presented herein, please contact our office at (803) 254-4540.

APPENDICES

Appendix A – Site Vicinity Map

Appendix B – General Building Plans

Appendix C – Sample Location Plans

Appendix D – Homogeneous Area Plans

Appendix E – Summary of Samples

Appendix F – Summary of Asbestos Containing Materials

Appendix G – Summary of Inspection

Appendix H – Physical Assessment Data Sheets

Appendix I – Laboratory Analysis Reports

Appendix J – Chain of Custody Forms

Appendix K – Personnel Certifications

Appendix L – Regulatory Summary

Appendix M – Abatement Project Forms

Appendix A

Site Vicinity Map






FIGURE NUMBER:

1

F&ME CONSULTANTS PROJECT NUMBER:

E5700.190

Asbestos Containing Materials Investigation Former SCE&G Complex 1206 Flora Street, Columbia, SC 29201

Appendix A - Site Location Plan
Prepared for:

Prepared for: Facilities Planning and Construction 743 Greene Street Columbia, SC 29208 F&ME CONSULTANTS


3112 Devine Street Columbia, SC 29205

ORIGINAL:	DRWN. BY: CTC
March 23, 2018	CHKD. BY: MSM
REVISIONS:	APPR. BY: GME
1	
2	NOTES:
3	
SCALE	
As Shown	
· · · · · · · · · · · · · · · · · · ·	

Appendix B

General Building Plans





FIRST FLOOR PLAN - 1"=16"

SCALE: 1/16" = 1'-0"


F&ME
CONSULTANTS
GEOTECHNICAL - ENVIRONMENTAL - M
3112 Devine Street
COLUMBIA, SC 29205

Asbestos Containing Materials Investigation
Former SCE&G Complex - Main 2-Story Structure
1206 Flora Street, Columbia, SC 29201
Appendix B - General Building Plan
Prepared for:

F&ME CONSULTANTS PROJECT NUMBER: E5700.190

FIGURE NUMBER:

2



Asbestos Containing Materials Investigation
Former SCE&G Complex - Main 2-Story Structure
1206 Flora Street, Columbia, SC 29201
Appendix B - General Building Plan
Prepared for:

F&ME
CONSULTANTS
GEOTECHNICAL - ENVIRONMENTAL - MATERIALS
3112 Devine Street
COLUMBIA, SC 29205

F&ME CONSULTANTS PROJECT NUMBER: E5700.190

FIGURE NUMBER:

3


SECOND FLOOR PLAN - 1"=16'


SCALE: 1/16" = 1'-0" 1 A2


Appendix C

Sample Location Plans










Appendix D


Homogeneous Area Plans





E5700.190

HA-1 - BLACK MASTIC UNDER MULTIPLE FLOORING COMPONENTS
(I.E. CARPET, NON-ACM FLOOR TILE, WHITE FLOOR





S Containing Materials investigation &&G Complex - Main 2-Story Structur Flora Street, Columbia, SC 29201 ndix D - Homogeneous Area Plan Prepared for:

1206 Flora Street, Colu

Appendix D - Homoge


Prepared f

Facilities Planning an

F&ME CONSULTANTS
PROJECT NUMBER:
E5700.190

FIGURE NUMBER:

8



Asbestos Containing Materials Investigation Former SCE&G Complex - Main 2-Story Structure 1206 Flora Street, Columbia, SC 29201 Appendix D - Homogeneous Area Plan Prepared for:

F&ME CONSULTANTS PROJECT NUMBER: E5700.190

FIGURE NUMBER:

9

Appendix E

Summary of Samples



Sample ID	Description
1206-1-1	Drywall/Joint Compound
1206-1-2	Drywall/Joint Compound
1206-1-3	Drywall/Joint Compound
1206-1-4	Drywall/Joint Compound
1206-1-5	Drywall/Joint Compound
1206-1-6	Drywall/Joint Compound
1206-1-7	Drywall/Joint Compound
1206-2-1	2' x 2' Heavy Textured Ceiling Tile
1206-2-2	2' x 2' Heavy Textured Ceiling Tile
1206-2-3	2' x 2' Heavy Textured Ceiling Tile
1206-3-1	2' x 4' Small Pinhole Ceiling Tile
1206-3-2	2' x 4' Small Pinhole Ceiling Tile
1206-3-3	2' x 4' Small Pinhole Ceiling Tile
1206-4-1	Cream Baseboard Adhesive
1206-4-2	Cream Baseboard Adhesive
1206-4-3	Cream Baseboard Adhesive
1206-5-1	Brown Baseboard Adhesive
1206-5-2	Brown Baseboard Adhesive
1206-5-3	Brown Baseboard Adhesive
1206-6-1	Carpet Adhesive



1206.6.2	Commet A II
1206-6-2	Carpet Adhesive
1206-6-3	Carpet Adhesive
1206-7-1	12" x 12" Gray Floor Tile/Mastic
1206-7-2	12" x 12" Gray Floor Tile/Mastic
1206-7-3	12" x 12" Gray Floor Tile/Mastic
1206-8-1	12" x 12" Blue Floor Tile/Mastic
1206-8-2	12" x 12" Blue Floor Tile/Mastic
1206-8-3	12" x 12" Blue Floor Tile/Mastic
1206-9-1	12" x 12" Red Floor Tile/Mastic
1206-9-2	12" x 12" Red Floor Tile/Mastic
1206-9-3	12" x 12" Red Floor Tile/Mastic
1206-10-1	12" x 12" Peach Floor Tile/Mastic
1206-10-2	12" x 12" Peach Floor Tile/Mastic
1206-10-3	12" x 12" Peach Floor Tile/Mastic
1206-11-1	White Leveling Compound
1206-11-2	White Leveling Compound
1206-11-3	White Leveling Compound
1206-12-1	12" x 12" Tan Floor Tile/Mastic
1206-12-2	12" x 12" Tan Floor Tile/Mastic
1206-12-3	12" x 12" Tan Floor Tile/Mastic
1206-13-1	Tan Sink Undercoating



T -	
1206-13-2	Tan Sink Undercoating
1206-13-3	Tan Sink Undercoating
1206-14-1	12" x 12" Light Brown Floor Tile/Mastic
1206-14-2	12" x 12" Light Brown Floor Tile/Mastic
1206-14-3	12" x 12" Light Brown Floor Tile/Mastic
1206-15-1	12" x 12" Tan Streaked Floor Tile/Mastic
1206-15-2	12" x 12" Tan Streaked Floor Tile/Mastic
1206-15-3	12" x 12" Tan Streaked Floor Tile/Mastic
1206-16-1	Tan Mastic on HVAC Duct Wrap
1206-16-2	Tan Mastic on HVAC Duct Wrap
1206-16-3	Tan Mastic on HVAC Duct Wrap
1206-17-1	Gray Mastic on HVAC Duct Wrap
1206-17-2	Gray Mastic on HVAC Duct Wrap
1206-17-3	Gray Mastic on HVAC Duct Wrap
1206-18-1	White Mastic on HVAC Duct Wrap
1206-18-2	White Mastic on HVAC Duct Wrap
1206-18-3	White Mastic on HVAC Duct Wrap
1206-19-1	Black Mastic on HVAC Duct Wrap
1206-19-2	Black Mastic on HVAC Duct Wrap
1206-19-3	Black Mastic on HVAC Duct Wrap
1206-20-1	Plaster



1206-20-2	Plaster
1206-20-3	Plaster
1206-20-4	Plaster
1206-20-5	Plaster
1206-21-1	Brown Window Caulk (Interior)
1206-21-2	Brown Window Caulk (Interior)
1206-21-3	Brown Window Caulk (Interior)
1206-22-1	TSI Pipe Insulation
1206-23-1	Drywall/Joint Compound
1206-23-2	Drywall/Joint Compound
1206-23-3	Drywall/Joint Compound
1206-23-4	Drywall/Joint Compound
1206-23-5	Drywall/Joint Compound
1206-24-1	2' x 2' Textured Ceiling Tiles
1206-24-2	2' x 2' Textured Ceiling Tiles
1206-24-3	2' x 2' Textured Ceiling Tiles
1206-25-1	12" x 12" Gray/Off-White Floor Tile/Mastic/Carpet Adhesive
1206-25-2	12" x 12" Gray/Off-White Floor Tile/Mastic/Carpet Adhesive
1206-25-3	12" x 12" Gray/Off-White Floor Tile/Mastic/Carpet Adhesive
1206-26-1	12" x 12" Blue Floor Tile/Mastic
1206-26-2	12" x 12" Blue Floor Tile/Mastic



1206-26-3	12" x 12" Blue Floor Tile/Mastic
1206-27-1	Baseboard Adhesive
1206-27-2	Baseboard Adhesive
1200-27-2	Baseboard Admestive
1206-27-3	Baseboard Adhesive
1206-28-1	2' x 2' Gypsum Ceiling Tiles
1206-28-2	2' x 2' Gypsum Ceiling Tiles
1206-28-3	2' x 2' Gypsum Ceiling Tiles
1206-29-1	12" x 12" Off-White Floor Tile/Mastic
1206-29-2	12" x 12" Off-White Floor Tile/Mastic
1206-29-3	12" x 12" Off-White Floor Tile/Mastic
1206-30-1	Gray Duct Mastic
1206-30-2	Gray Duct Mastic
1206-30-3	Gray Duct Mastic
1206-31-1	Textured Wall Surfacing Material
1206-31-2	Textured Wall Surfacing Material
1206-31-3	Textured Wall Surfacing Material
1206-32-1	Light Gray Duct Mastic
1206-32-2	Light Gray Duct Mastic
1206-32-3	Light Gray Duct Mastic
1206-33-1	Drywall/Joint Compound
1206-33-2	Drywall/Joint Compound



1206-33-3	Drywall/Joint Compound
1206-33-4	Drywall/Joint Compound
1206-33-5	Drywall/Joint Compound
1206-33-6	Drywall/Joint Compound
1206-33-7	Drywall/Joint Compound
1206-34-1	Carpet Adhesive
1206-34-2	Carpet Adhesive
1206-34-3	Carpet Adhesive
1206-35-1	Baseboard Adhesive
1206-35-2	Baseboard Adhesive
1206-35-3	Baseboard Adhesive
1206-36-1	2' x 4' Textured Ceiling Tiles
1206-36-2	2' x 4' Textured Ceiling Tiles
1206-36-3	2' x 4' Textured Ceiling Tiles
1206-37-1	2' x 2' Rough Textured Ceiling Tiles
1206-37-2	2' x 2' Rough Textured Ceiling Tiles
1206-37-3	2' x 2' Textured Ceiling Tiles
1206-38-1	2' x 4' Rough Textured Ceiling Tiles
1206-38-2	2' x 4' Rough Textured Ceiling Tiles
1206-38-3	2' x 4' Rough Textured Ceiling Tiles
1206-39-1	Black Duct Mastic



Black Duct Mastic
Black Duct Mastic
12" x 12' Light Gray on Brown Floor Tile/Mastic
12" x 12' Light Gray on Brown Floor Tile/Mastic
12" x 12' Light Gray on Brown Floor Tile/Mastic
12" x 12" Gray with White Floor Tile/Mastic
12" x 12" Gray with White Floor Tile/Mastic
12" x 12" Gray with White Floor Tile/Mastic
12" x 12" Beige with Tan Floor Tile/Mastic
12" x 12" Beige with Tan Floor Tile/Mastic
12" x 12" Beige with Tan Floor Tile/Mastic
12" x 12" White with Black Floor Tile/Mastic
12" x 12" White with Black Floor Tile/Mastic
12" x 12" White with Black Floor Tile/Mastic
Residual Black Mastic
Residual Black Mastic
Residual Black Mastic
Red Fire Stop
Red Fire Stop
Red Fire Stop
Mudded Elbow



1206-46-2	Mudded Elbow
1206-47-1	Old Floor Underfelt
1206-47-2	Old Floor Underfelt
1206-47-3	Old Floor Underfelt
1206-48-1	Newer Floor Underfelt
1206-48-2	Newer Floor Underfelt
1206-48-3	Newer Floor Underfelt
1206-49-1	Red Floor Underfelt
1206-49-2	Red Floor Underfelt
1206-49-3	Red Floor Underfelt
1206-50-1	Old Floor Penetration TSI
1206-51-1	Expansion Joint Material
1206-51-2	Expansion Joint Material
1206-51-3	Expansion Joint Material
1206-52-1	Timber Column Felt
1206-52-2	Timber Column Felt
1206-52-3	Timber Column Felt
1206-53-1	Black Expansion Joint Felt
1206-53-2	Black Expansion Joint Felt
1206-53-3	Black Expansion Joint Felt
1206-54-1	Red Expansion Joint Felt



The state of the s	
1206-54-2	Red Expansion Joint Felt
1206-54-3	Red Expansion Joint Felt
1206-55-1	Fire Door Material
1206-55-2	Fire Door Material
1206-55-3	Fire Door Material
1206-56-1	Stucco Wall Fill
1206-56-2	Stucco Wall Fill
1206-56-3	Stucco Wall Fill
1206-57-1	Stair Tread Adhesive
1206-57-2	Stair Tread Adhesive
1206-57-3	Stair Tread Adhesive
1206-58-1	12" x 12" Gray Floor Tile/Mastic (Entry)
1206-58-2	12" x 12" Gray Floor Tile/Mastic (Entry)
1206-58-3	12" x 12" Gray Floor Tile/Mastic (Entry)
1206-59-1	Interior Door Caulk
1206-59-2	Interior Door Caulk
1206-59-3	Interior Door Caulk
1206-60-1	Exterior Door/Window Caulk
1206-60-2	Exterior Door/Window Caulk
1206-60-3	Exterior Door/Window Caulk
1206-61-1	White Window Caulk



1206-61-2	White Window Caulk
1206-61-3	White Window Caulk
1206-62-1	Exterior Stucco
1206-62-2	Exterior Stucco
1206-62-3	Exterior Stucco
1206-62-4	Exterior Stucco
1206-62-5	Exterior Stucco
1206-63-1	Roof Core
1206-63-2	Roof Core
1206-63-3	Roof Core
1206-64-1	Flashing
1206-64-2	Flashing
1206-64-3	Flashing
1206-65-1	White Roof Caulk
1206-65-2	White Roof Caulk
1206-65-3	White Roof Caulk
1206-66-1	Gray Surface Coating
1206-66-2	Gray Surface Coating
1206-66-3	Gray Surface Coating
1206-67-1	Gray Flashing Mastic
1206-67-2	Gray Flashing Mastic
-	-



r-	
1206-67-3	Gray Flashing Mastic
1206-68-1	Black Roof Patch
1206-68-2	Black Roof Patch
1206-68-3	Black Roof Patch
1206-69-1	Red Roof Patch
1206-69-2	Red Roof Patch
1206-69-3	Red Roof Patch
1206-70-1	Black Flashing Mastic
1206-70-2	Black Flashing Mastic
1206-70-3	Black Flashing Mastic
1206-71-1	White Flashing Mastic
1206-71-2	White Flashing Mastic
1206-71-3	White Flashing Mastic



Appendix F

Summary of Asbestos Containing Materials



Appendix F: Summary of Asbestos Containing Materials

Sample ID	Sample Description	Layer	% Asbestos
1206-11-1	White Leveling Compound	White	None Detected
1200 11 1	White Devening Compound	Black	8% Chrysotile
1206-11-2	White Leveling Compound	White	None Detected
	white 20 compound	Black	First Stop Positive
1206-11-3	White Leveling Compound	White	None Detected
		Black	First Stop Positive
1206-12-1	12" x 12" Tan Floor Tile/Mastic	Floor Tile	None Detected
		Mastic	8% Chrysotile
1206-12-2	12" x 12" Tan Floor Tile/Mastic	Floor Tile Mastic	None Detected
		Floor Tile	First Stop Positive None Detected
1206-12-3	12" x 12" Tan Floor Tile/Mastic	Mastic	First Stop Positive
1206 10 1	Disala Markin and INVAC Deart Wise	- Iviastic	
1206-19-1	Black Mastic on HVAC Duct Wrap	_	10% Chrysotile
1206-19-2	Black Mastic on HVAC Duct Wrap	-	First Positive Stop
1206-19-3	Black Mastic on HVAC Duct Wrap	-	First Positive Stop
1206.22.1	mar pi		5% Amosite
1206-22-1	TSI Pipe Insulation	-	55% Chrysotile
1206-26-1	12" x 12" Blue Floor Tile/Mastic	Floor Tile	None Detected
1200-20-1	12 x 12 Blue 1 loof The/Wastic	Mastic	3% Chrysotile
1206-26-2	12" x 12" Blue Floor Tile/Mastic	Floor Tile	None Detected
1200 20 2	12 X 12 Blue 1 loof The Wastle	Mastic	First Positive Stop
1206-26-3	12" x 12" Blue Floor Tile/Mastic	Floor Tile	None Detected
1200 20 3	12 X 12 Blue 1 loof The Wastle	Mastic	First Positive Stop
1206-39-1	Black Mastic on HVAC Duct Wrap	-	8% Chrysotile
1206-39-2	Black Mastic on HVAC Duct Wrap	-	First Positive Stop
1206-39-3	Black Mastic on HVAC Duct Wrap	-	First Positive Stop
1206-40-1	12" x 12" Gray on Brown Floor	Floor Tile	None Detected
1200-40-1	Tile/Mastic	Mastic	8% Chrysotile
1206-40-2	12" x 12" Gray on Brown Floor	Floor Tile	None Detected
	Tile/Mastic	Mastic	First Positive Stop
1206-40-3	12" x 12" Gray on Brown Floor	Floor Tile	None Detected
	Tile/Mastic	Mastic	First Positive Stop
1206-42-1	12" x 12" Beige w/Tan Floor	Floor Tile	None Detected
	Tile/Mastic	Mastic	8% Chrysotile
1206-42-2	12" x 12" Beige w/Tan Floor	Floor Tile	None Detected
1200 12 2	Tile/Mastic	Mastic	First Stop Positive



Appendix F: Summary of Asbestos Containing Materials

Sample ID	Sample Description	Layer	% Asbestos
1206-42-3	12" x 12" Beige w/Tan Floor	Floor Tile	None Detected
1200-42-3	Tile/Mastic	Mastic	First Stop Positive
1206-44-1	Residual Black Mastic	-	8% Chrysotile
1206-44-2	Residual Black Mastic	-	First Stop Positive
1206-44-3	Residual Black Mastic	-	First Stop Positive
1206-46-1	Mudded Elbow	-	75% Chrysotile
1206-46-2	Mudded Elbow	-	First Stop Positive
1206-50-1	Residual Floor Penetration TSI	-	40% Chrysotile
1206-52-1	Timber Column Felt	-	60% Chrysotile
1206-52-2	Timber Column Felt	-	First Stop Positive
1206-52-3	Timber Column Felt	-	First Stop Positive
1206-67-1	Gray Flashing Mastic	-	5% Chrysotile
1206-67-2	Gray Flashing Mastic	-	First Stop Positive
1206-67-3	Gray Flashing Mastic	-	First Stop Positive
1206-70-1	Black Flashing Mastic	-	10% Chrysotile
1206-70-2	Black Flashing Mastic	-	First Stop Positive
1206-70-3	Black Flashing Mastic	-	First Stop Positive

Appendix G

Summary of Inspection



SUMMARY OF INSPECTION

SUMMARY OF INSPECTION

The following tables summarize the physical assessment data, sampling and assessment results.

As exhibited on these tables, coding is used to abbreviate the asbestos containing materials' (ACM) locations, characteristics and results. These codes are as follows:

TYPES OF ACM:

Misc. = Miscellaneous

Sur. = Surfacing

TSI = Thermal System Insulation

ACM LOCATIONS:

Homogeneous areas = Indicated by Roman Numerals, Room Number or Area Designation

Functional Space No.:	Function	onal Space Type:
1.	MR	Mechanical Room
2.	S	Suite
3.	С	Chase
4.	Н	Hallway
5.	Е	Elevator
6.	О	Office

ACM CHARACTERISTICS:

F = Friable

NF = Non-Friable

ASSESSMENT RESULTS:

(Refer to Physical Assessment Data)

POTENTIAL FOR DISTURBANCE:

(Refer to Physical Assessment Data)

SUMMARY OF INSPECTION

PHYSICAL ASSESSMENT CATAGORIES:

- 1. Damaged or significantly damaged friable thermal system insulation ACM.
- 2. Damaged friable surfacing ACM.
- 3. Significantly damaged friable surfacing ACM.
- 4. Damaged or significantly damaged friable miscellaneous ACM.
- 5. ACM with potential for significant damage.
- 6. ACM with potential for damage.
- 7. Any remaining friable ACM or friable suspect ACM.
- 8. Non-friable ACM.

CLASSIFICATION FOR HAZARD POTENTIAL:

(Tabular Display)

<u>Hazard</u> <u>Rank</u>	ACM Condition	ACM Disturbance Potential
7	Significantly Damaged	Any
6	Damaged	Potential for Significant Damage
5	Damaged	Potential for Damage
4	Damaged	Low
3	Good	Potential for Significant Damage
2	Good	Potential for Damage
1	Good	Low

Appendix H

Physical Assessment Data Sheets



Building:	Former S	SCE&G M	ain Bui	lding						
Functional S	pace No:	1, 3	3	Type:	O, H	<u>L</u>	ocation:	(See Ho	mogeneou	s Area Plan)
Type of Suspect M	<u> Iaterial</u> :			TSI _		S	urfacing	X	Misc.	
Description:		HA-1, B1	ack Ma	stic Under \	Various No	on-ACN	1 Flooring	Compon	ents	
Approximate Amo	unt of Material	(SF or LF)	:	~3,600 ft²						
Condition :										
Percent Damage:		X	>0%		<10%		>10%		<25%	>25%
Extent of Damage:				Localized	_		X	Distribut	ted	
Type of Damage:				Deteriorat						Physical
Description:										
		idual under	r carpet)) in various d intact con	areas throu					white leveling ding. Overall,
	Overall Condi	tion Rating				Dama	ged		Good	X
Potential for Distu	ırbance:									
				High	Mod	lerate	Low	7	Friable ACM	
	Frequency of Contact:	f Potential					X			_
	Influence of	Vibration					X			_
	Frequency of	f Air Erosi	on				X			_
	Potential of	Water Eros	sion				X			_
Overall Potential	Disturbance R	ating:								
				Potential Sig. Dam		Potenti Dam		Lor Potenti Dam	al for age	
Overall Hazard R	ank #:									
		_	Sig. Da	amaged	Pot. Si Damaş		Potenti Damaş		Low Pot. Damage	
<u>Comments</u> : Por	tential for Distu	rbance and	l Hazaro	d Ranking a	ssessed is	based o	on current	usage of	the facility	<i>7</i> .
Signed:	pril	le M	ma	ry	:	Date:	03/27/201	18		
Building:	Former S	SCE&G M	ain Bui	lding						

Functional Space No:		1, 3		<u>Type:</u> O, H		Locati	<u>ion</u> : ((See Homogeneous		s Area Plan)
Type of Suspect Material:			TSI _		Surfac	cing _	X	Misc.		
Description:		HA-2, I	Black M	astic on HV	AC Duct W	⁷ rap				
Approximate Amo	ount of Material	(SF or LI	F):	~250 ft²						
Condition:										
Percent Damage:		X	>0%		<10%	>10)%	<	25%	>25%
Extent of Damage:	:									
Type of Damage:		X		Deteriorati	on	W	V ater			Physical
Description:										
	Asbestos-contai 1 st and 2 nd floor being noted dur	s. Overal	l this ma	aterial was fo						
	Overall Conditi	on Rating	Sig. g: Dan	_]	Damaged			Good	X
Potential for Dist	urbance:									
				Uiah	Mode	mata	Low		Friable ACM	
	Frequency of	Dotontial		High	Mode	rate	Low		ACM	
	Contact:	rotentiai					X			_
	Influence of V	Vibration			<u></u>		X			_
	Frequency of	Air Eros	ion				X			_
	Potential of V	Vater Ero	sion				X			_
Overall Potential	Disturbance R	ating:								
				Potential Sig. Dama		Potential for Damage	r	Low Potentia Dama	l for	
Overell Hezend D	Pank #•				<u> </u>			0		
Overall Hazard F	<u>капк #</u> :		Sig. D	amaged	Pot. Sig Damage		otential Damage		Low Pot. Damage	
									1	

<u>Functional Space No:</u>	3	Type:	Н	<u>Locat</u>	<u>ion</u> : (S	See Homogeneor	us Area Plan)
Type of Suspect Material:	X	_ TSI		Surfa	cing	Misc.	•
Description:	HA-3, TSI Pip	e Insulation a	and Residua	l TSI on F	loor Pen	etrations	
Approximate Amount of Material	(SF or LF):	~15 LF/40	SF Penetrat	tions			
Condition:							
Percent Damage:	>0%	X	<10%	>1	0%	<25%	>25%
Extent of Damage:	X	Localized			D	istributed	
Type of Damage:	X		on				Physical
Description:		_					
One (1) run of asbestos- No other suspect pipe penetrations in the walls some localized damage	insulation was and ceiling of R	found during coom 100. The ne TSI debris v	the field in e TSI pipe in	nvestigation rsulation v	n. Resid vas in an	ual TSI was no intact but friable	oted on several e condition with
Overall Condit		maged]	Damaged	X	Good	
Potential for Disturbance:							
		High	Mode	rate	Low	Friable ACM	
Frequency of	f Potential		1.2000		20	120112	
Contact:	1 Otentiai				X	X	
Influence of	Vibration				X	X	<u></u>
Frequency of	f Air Erosion				X	X	<u>—</u>
Potential of V	Water Erosion				X	X	<u> </u>
Overall Potential Disturbance R	Rating:						
		Potential Sig. Dama		otential fo Damage	or l	Low Potential for Damage 7	
Overall Hazard Rank #:		_					
	Sig. l	Damaged	Pot. Sig.		Potential Damage	Low Pot Damage	
Comments: Potential for Districtions Signed:	urbance and Haz	_			current us	sage of the facil	ity.

Building: Form	ner SCE&G	Main B	uilding						
Functional Space No:		2		R	Location:	(See Homogeneo	(See Homogeneous Area Plan)		
Type of Suspect Material:		X			Surfacing	Misc.			
Description:	HA-4,	Mudded	Elbows						
Approximate Amount of Mater	rial (SF or L	F):	2 Elbows						
Condition :									
Percent Damage:	X	>0%		<10%	>10%	<25%	>25%		
Extent of Damage:		X	Localized			Distributed			
Type of Damage:		X	Deteriorati	ion	Water	X	_ Physical		
Description :									
elbows were		during th				0 on the 1 st floor. N an intact but friable			
Overall Cor	ndition Ratin	Sig. g: Dar	naged	I	Damaged	Good	X		
Potential for Disturbance:									
			High	Moder	rate Lov	Friable ACM			
Frequency Contact:	y of Potentia	.1			X	X	<u> </u>		
Influence	of Vibration	1			X	X			
Frequency	y of Air Eros	sion			X	X			
Potential	of Water Ero	osion			X	X			
Overall Potential Disturbance	e Rating:								
			Potential Sig. Dam		otential for Damage	Low Potential for Damage 7			
Overall Hazard Rank #:									
		Sig. D	amaged	Pot. Sig. Damage					
						1	<u>—</u>		
	disturbance a				oased on currer	nt usage of the facil	ity.		

Building:	Former	SCE&G	Main B	uilding					
Functional	Space No:	2		Type:	R	Location :	(See Homogeneou		ıs Area Plan)
Type of Suspect	Material:			TSI _		Surfacing	X	Misc.	
Description:		HA-5, 7	imber (Column Felt					
Approximate Am	ount of Materia	l (SF or LF	F):	~ 5 ft²					
Condition :									
Percent Damage:		X	>0%		<10%	>10%		<25%	>25%
Extent of Damage	e:		X	Localized			Distribut	ted	
Type of Damage:		X	-	_ Deteriorati	on	Water		X	Physical
Description:									
	floor. Review of	of other col the interfa	umns th	roughout the e columns w	build showe	d this condition	was locali	ized in this	n 111 on the 1 st area and metal n an intact and
	Overall Condi	tion Rating			Γ	Damaged		Good	X
Potential for Dis	turbance:								
				TT! al.	Mada	4. T		Friable	
	Frequency of	of Potential		High	Moder	rate Lo	W	ACM	
	Contact:	n i otentiai				X			<u> </u>
	Influence of	Vibration				X			<u> </u>
	Frequency of	of Air Erosi	ion			X			_
	Potential of	Water Ero	sion			X			<u> </u>
Overall Potentia	l Disturbance I	Rating:							
				Potential Sig. Dam		otential for Damage	Lor Potenti Dam	al for age	
O 11	D l - #.						8		
Overall Hazard	<u>Kank #</u> :		Sig. D	D amaged	Pot. Sig. Damage	Poten Dama		Low Pot. Damage	
Comments: P Signed:	otential for Dist	turbance a	nd Haza	ard Ranking	Damage assessed is b	Dama 	nt usage of	Damage 1	_

PHYSICAL ASSESSMENT DATA SHEET

Building:	Former	SCE&G	Main B	uilding						
Functional S	Space No:		4	Type:	R		Location :	(See Ho	nogeneou	s Area Plan)
Type of Suspect	Material:			TSI _			Surfacing	X	Misc.	
Description:		HA-6,	Gray Fla	shing Masti	c					
Approximate Am	ount of Material	l (SF or L	F):	~90 SF						
Condition :										
Percent Damage:		<u>X</u>	>0%		<10%		>10%	<	25%	>25%
Extent of Damage	e:			Localized			X	Distribute	ed	
Type of Damage:			X	Deteriorati	on	X	Water			Physical
Description:										
	Asbestos-conta structure and the on the metal ro	ne metal roof. This n	oof of the naterial w	all metal add vas found in g	dition (R good, int	oom 11 act non-	0) found on t	the northweition with	est corner	of the building
Potential for Dis		cion Rucin	15. Dui				<u></u>		Good	
1 Ottimus 101 Dis	tur bunce.			High	M	oderate	e Lov		Friable ACM	
	Frequency o Contact:	f Potentia	nl				X			_
	Influence of	Vibration	1				X			_
	Frequency o	f Air Ero	sion				X			_
	Potential of	Water Ero	osion				X			_
Overall Potentia	l Disturbance I	Rating:								
				Potential Sig. Dama			ntial for mage	Lov Potentia Dama	ıl for	
Overall Hazard	<u>Rank #</u> :									
			Sig. D	amaged	Pot. Dam		Potent Dama		Low Pot. Damage	
							-		1	_
Comments: Posigned:	otential for Dist				assessec	d is base Date:			the facilit	y.

PHYSICAL ASSESSMENT DATA SHEET

Building: Form	er SCE&G Main B	uilding					
Functional Space No:	4	Type:	R	Location:	(See Homog	geneou	s Area Plan)
Type of Suspect Material:		_ TSI		Surfacing	X	Misc.	
Description:	HA-7, Black F	lashing Masti	c				
Approximate Amount of Mater	ial (SF or LF):	~ 50 SF					
Condition :							
Percent Damage:	X >0%		<10%	>10%	<25	%	>25%
Extent of Damage:		Localized		X	Distributed		
Type of Damage:	X			Water			Physical
Description:							
structure and	ntaining black masti the metal roof abov Sig	e the rear-load	ling dock. Tl	nis material is in	n good, intact i	non-fri	able condition.
	dition Rating: Da	maged	Г	Damaged	Go	od	X
<u>Potential for Disturbance</u> :					T7		
		High	Moder	ate Lov		iable CM	
Frequency	of Potential						
Contact:				X			_
Influence of	of Vibration			X			_
Frequency	of Air Erosion			X			_
Potential o	of Water Erosion			X			_
Overall Potential Disturbance	e Rating:						
		Potential to Sig. Dama		otential for Damage	Low Potential fo Damage 8	or	
Overall Hazard Rank #:							
	Sig. I	Damaged	Pot. Sig. Damage	Potent Dama		w Pot. amage	_
	isturbance and Haz			pased on currer	•	facilit	ty.

PHYSICAL ASSESSMENT DATA SHEET

- 00	Space No:	5	Type:	Е	Location :	(See Homogene	ous Area Plan)
Type of Suspect	Material:	X	_ TSI _		_ Surfacing	X Mis	с.
Description:		HA-8, Elevato	r Doors and	Brake Shoes			
Approximate Am	ount of Material	(SF or LF):	1 Elevator	, 3 Doors			
Condition :							
Percent Damage:		X >0%		<10%	>10%	<25%	>25%
Extent of Damage	: :	X					
Type of Damage:		X			Water		Physical
Description:			_				
	methods necess as part of this	sary to collect san	nples of these they are assu	types of build	ing component	der elevators. Due s, these materials v can be collected a	were not sampled
	Overall Condit	Sig ion Rating: Da	g. maged	D	amaged	Good	X
Potential for Dist	turbance:						
			High	Modera	ate Lov	Friable v ACM	
	_		O				
	Frequency of Contact:	f Potential	J		X	X	
	Frequency of Contact: Influence of				X	X X	
	Contact: Influence of	Vibration			X	X	<u> </u>
	Contact: Influence of Frequency of	Vibration					
Overall Potentia	Contact: Influence of Frequency of Potential of V	Vibration f Air Erosion Water Erosion			X	X X	_
Overall Potentia	Contact: Influence of Frequency of Potential of V	Vibration f Air Erosion Water Erosion	Potential Sig. Dam		X	X X	
Overall Potentia	Contact: Influence of Frequency of Potential of V	Vibration f Air Erosion Water Erosion	Potential		X X X x tential for	X X X Low Potential for Damage	

Appendix I

Laboratory Analysis Reports





1825 Blanding Street

Columbia, SC 29201

EMSL Order: 021801945 Customer ID: FMEC62 Customer PO: E5700.19

Project ID:

Phone: (803) 254-4540

Fax: (803) 254-4542

Received Date: 03/19/2018 9:00 AM

Analysis Date: 03/21/2018 **Collected Date**: 03/16/2018

Project: ACM Investigation - Former SCE&G Building

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			<u>Asbestos</u>		
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1206-1-1-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous Heterogeneous	8% Cellulose	92% Non-fibrous (Other)	None Detected
1206-1-1-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
1206-1-2-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous Heterogeneous	8% Cellulose	92% Non-fibrous (Other)	None Detected
1206-1-2-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous	<1% Cellulose	30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
02/80/1945-0002A 1206-1-3-Drywall 02/80/1945-0003	Drywall/Joint Compound	Brown/Gray Fibrous Heterogeneous	8% Cellulose	92% Non-fibrous (Other)	None Detected
1206-1-3-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
1206-1-4-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous Heterogeneous	8% Cellulose	92% Non-fibrous (Other)	None Detected
1206-1-4-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
1206-1-5-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous Heterogeneous	8% Cellulose	92% Non-fibrous (Other)	None Detected
1206-1-5-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
021801945-0005A 1206-1-6-Drywall 021801945-0006	Drywall/Joint Compound	Brown/Gray Fibrous Heterogeneous	30% Cellulose 1% Glass	69% Non-fibrous (Other)	None Detected
1206-1-6-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous	1% Cellulose	30% Ca Carbonate 69% Non-fibrous (Other)	None Detected
021801945-0006A					
1206-1-6-Tape 021801945-0006B	Drywall/Joint Compound	Beige Fibrous Homogeneous	100% Cellulose		None Detected
1206-1-7-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous	15% Cellulose 1% Glass	84% Non-fibrous (Other)	None Detected

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample			Non-Asbes		Asbestos	
	Description	Appearance	% Fibrous	% Non-Fibrous	% Type	
1206-1-7-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous	1% Cellulose	30% Ca Carbonate 69% Non-fibrous (Other)	None Detected	
021801945-0007A		-				
1206-1-7-Tape	Drywall/Joint Compound	Beige Fibrous	100% Cellulose		None Detected	
021801945-0007B		Homogeneous				
1206-2-1	2x2 Heavy Textured Ceiling Tiles	Gray/White Fibrous	30% Cellulose 55% Min. Wool	5% Perlite 10% Non-fibrous (Other)	None Detected	
021801945-0008		Homogeneous				
1206-2-2	2x2 Heavy Textured Ceiling Tiles	Gray/White Fibrous	30% Cellulose 55% Min. Wool	5% Perlite 10% Non-fibrous (Other)	None Detected	
021801945-0009		Homogeneous				
1206-2-3	2x2 Heavy Textured Ceiling Tiles	Gray/White Non-Fibrous	30% Cellulose 55% Min. Wool	10% Perlite 5% Non-fibrous (Other)	None Detected	
021801945-0010		Homogeneous				
1206-3-1	2x4 Small Pinhole Ceiling Tiles	Brown/Gray Fibrous	40% Cellulose 20% Min. Wool	30% Perlite 10% Non-fibrous (Other)	None Detected	
021801945-0011		Homogeneous				
1206-3-2	2x4 Small Pinhole Ceiling Tiles	Gray/White Fibrous	40% Cellulose 20% Min. Wool	30% Perlite 10% Non-fibrous (Other)	None Detected	
021801945-0012	0.46	Homogeneous	100/ 5	200/ 5		
1206-3-3	2x4 Small Pinhole Ceiling Tiles	Gray/White/Beige Fibrous	40% Cellulose 20% Min. Wool	30% Perlite 10% Non-fibrous (Other)	None Detected	
		Homogeneous		(224)		
1206-4-1	Cream Baseboard Adhesive	Beige Non-Fibrous Homogeneous	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
	Croom Dooghoord	-	<10/ Collulado	1000/ Non fibrous (Other)	Nana Datastad	
1206-4-2 021801945-0015	Cream Baseboard Adhesive	Yellow Non-Fibrous Homogeneous	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
1206-5-1	Brown Baseboard	Brown	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
021801945-0016	Adhesive	Non-Fibrous Homogeneous	176 Cellulose	100% Non-librous (Other)	None Detected	
1206-5-2	Brown Baseboard	Brown	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
021801945-0017	Adhesive	Non-Fibrous Homogeneous	- 1 /0 Geliulose	100 /0 14011-1101003 (Ott161)	None Detected	
1206-6-1	Carpet Adhesive	Tan	1% Cellulose	99% Non-fibrous (Other)	None Detected	
021801945-0018	Carpot Adricoive	Non-Fibrous Homogeneous	<1% Synthetic	os /s (toll librous (Other)	None Detected	
1206-6-2	Carpet Adhesive	Tan/Yellow Non-Fibrous	<1% Cellulose 1% Synthetic	99% Non-fibrous (Other)	None Detected	
021801945-0019		Homogeneous				
1206-7-1-Floor Tile	12x12 Gray Floor Tile/Mastic	Gray/White/Blue Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected	
021801945-0020		Homogeneous		,		
1206-7-1-Mastic	12x12 Gray Floor Tile/Mastic	Tan Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
021801945-0020A		Homogeneous				
1206-7-1-Leveler	12x12 Gray Floor Tile/Mastic	Gray Non-Fibrous	1% Cellulose	99% Non-fibrous (Other)	None Detected	
021801945-0020B		Homogeneous				
1206-7-2-Floor Tile	12x12 Gray Floor Tile/Mastic	Gray/White/Blue Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected	
021801945-0021		Homogeneous				
1206-7-2-Mastic	12x12 Gray Floor Tile/Mastic	Yellow/Orange Non-Fibrous	<1% Cellulose <1% Synthetic	100% Non-fibrous (Other)	None Detected	
021801945-0021A		Homogeneous				

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample			<u>Asbestos</u>		
	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1206-8-1-Floor Tile	12x12 Blue Floor Tile/Mastic	Blue Non-Fibrous Homogeneous		25% Quartz 75% Non-fibrous (Other)	None Detected
1206-8-1-Mastic	12x12 Blue Floor	Tan	<1% Cellulose	100% Non-fibrous (Other)	None Detected
1200-8-1-Mastic 021801945-0022A	Tile/Mastic	Non-Fibrous Homogeneous	<1% Cellulose	100% Non-librous (Other)	None Detected
1206-8-2-Floor Tile	12x12 Blue Floor	Blue		25% Quartz	None Detected
021801945-0023	Tile/Mastic	Non-Fibrous Homogeneous		75% Non-fibrous (Other)	None Beledied
206-8-2-Mastic	12x12 Blue Floor	Tan/Yellow	<1% Cellulose	100% Non-fibrous (Other)	None Detected
121801945-0023A	Tile/Mastic	Non-Fibrous Homogeneous	1170 Gendidae	100 /0 NOT IIDTOUS (Ottlet)	None Beledieu
1206-9-1-Floor Tile	12x12 Red Floor	Red/Purple		25% Quartz	None Detected
1200 0 1 1 1001 1110	Tile/Mastic	Non-Fibrous		75% Non-fibrous (Other)	110.10 20.00.00
021801945-0024		Homogeneous			
1206-9-1-Mastic	12x12 Red Floor Tile/Mastic	Tan Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0024A		Homogeneous			
1206-9-2-Floor Tile	12x12 Red Floor Tile/Mastic	Purple/Rust Non-Fibrous Homogeneous		25% Quartz 75% Non-fibrous (Other)	None Detected
	10v10 Dod Floor	-	<1% Cellulose	1000/ Non fibrage (Other)	None Detected
1206-9-2-Mastic	12x12 Red Floor Tile/Mastic	Yellow/Orange Non-Fibrous Homogeneous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
1206-10-1-Floor Tile	12x12 Peach Floor	Various/Beige		25% Quartz	None Detected
021801945-0026	Tile/Mastic	Non-Fibrous Homogeneous		75% Non-fibrous (Other)	None Detected
1206-10-1-Mastic	12x12 Peach Floor	Tan	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0026A	Tile/Mastic	Non-Fibrous Homogeneous	17/0 00/10/1000	100 % Not instead (Gallet)	None Bollotta
1206-10-2-Floor Tile	12x12 Peach Floor	Various/Beige		25% Quartz	None Detected
021801945-0027	Tile/Mastic	Non-Fibrous Heterogeneous		75% Non-fibrous (Other)	
1206-10-2-Mastic	12x12 Peach Floor Tile/Mastic	Tan/Black/Orange Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	<1% Chrysotile
021801945-0027A		Heterogeneous			
1206-11-1-Tan Mastic	White Leveling Compound	Tan Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0028		Homogeneous			
1206-11-1-Leveler	White Leveling Compound	White Non-Fibrous		100% Non-fibrous (Other)	None Detected
021801945-0028A	140.11	Homogeneous	40/ 5 " /	000/ 11 - 71 - 11	
1206-11-1-Black Mastic	White Leveling Compound	Black Non-Fibrous Homogeneous	<1% Cellulose	92% Non-fibrous (Other)	8% Chrysotile
	White Leveling	Tan	<1% Cellulose	100% Non-fibrous (Other)	None Detected
1206-11-2-Tan Mastic	Compound	Non-Fibrous Homogeneous	<1% Cellulose	100% Non-librous (Other)	None Detected
1206-11-2-Leveler	White Leveling Compound	White Non-Fibrous		100% Non-fibrous (Other)	None Detected
021801945-0029A	Compound	Homogeneous			
1206-11-2-Black Mastic	White Leveling Compound	<u> </u>			Positive Stop (Not Analyzed)
021801945-0029B					
1206-11-3-Leveler	White Leveling Compound	Gray/White Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0030		Homogeneous			

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-Asbes		Asbestos	
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type	
1206-11-3-Black Mastic	White Leveling Compound				Positive Stop (Not Analyzed)	
1206-12-1-Floor Tile	12x12 Tan Floor Tile/Mastic	Gray/Tan/Green Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected	
021801945-0031		Homogeneous				
1206-12-1-Mastic	12x12 Tan Floor Tile/Mastic	Black Non-Fibrous Homogeneous	<1% Cellulose	92% Non-fibrous (Other)	8% Chrysotile	
206-12-2-Floor Tile	12x12 Tan Floor Tile/Mastic	Gray/Green/Beige Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected	
21801945-0032		Homogeneous		,		
206-12-2-Mastic	12x12 Tan Floor Tile/Mastic				Positive Stop (Not Analyzed)	
21801945-0032A						
1206-13-1	Tan Sink Undercoating	Beige Non-Fibrous Homogeneous	10% Cellulose	90% Non-fibrous (Other)	None Detected	
	Ton Cink		150/ Callulana	1% Mica	Nana Datastad	
1206-13-2 021801945-0034	Tan Sink Undercoating	Beige Fibrous Homogeneous	15% Cellulose	84% Non-fibrous (Other)	None Detected	
1206-14-1-Floor Tile	12x12 Light Brown	Tan/Beige		25% Quartz	None Detected	
221801945-0035	Floor Tile/Mastic	Non-Fibrous Homogeneous		75% Non-fibrous (Other)	None Detected	
206-14-1-Mastic	12x12 Light Brown Floor Tile/Mastic	Tan Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
021801945-0035A	. ioo. momada	Homogeneous				
1206-14-2-Floor Tile	12x12 Light Brown Floor Tile/Mastic	Tan/Beige Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected	
021801945-0036		Homogeneous				
206-14-2-Mastic	12x12 Light Brown Floor Tile/Mastic	White/Orange Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
	40.40 Tan Otropled	Homogeneous		050/ Overth	None Detected	
1206-15-1-Floor Tile	12x12 Tan Streaked Floor Tile/Mastic	Tan/Beige Non-Fibrous Homogeneous		25% Quartz 75% Non-fibrous (Other)	None Detected	
1206-15-1-Mastic	12x12 Tan Streaked Floor Tile/Mastic	Tan Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
021801945-0037A	1 loor The/Iwastic	Homogeneous				
1206-15-2-Floor Tile	12x12 Tan Streaked Floor Tile/Mastic	Tan/Beige Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected	
021801945-0038		Homogeneous				
206-15-2-Mastic	12x12 Tan Streaked Floor Tile/Mastic	Yellow/Orange Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
021801945-0038A		Homogeneous				
1206-16-1	Tan Mastic on HVAC Duct Wrap	Beige Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
021801945-0039	Top Marking of LD (A.C.	Homogeneous	40/ 04/1-1	OOM Nam Strang (Otto)	Name Detected	
1206-16-2	Tan Mastic on HVAC Duct Wrap	Beige Non-Fibrous Homogeneous	1% Cellulose	99% Non-fibrous (Other)	None Detected	
	Gray Mastic on HVAC	Gray/White	<1% Cellulose	80% Non-fibrous (Other)	None Detected	
1206-17-1 021801945-0041	Duct Wrap	Fibrous Homogeneous	20% Glass	ou 70 INUIT-IIDIUUS (OUTER)	None Detected	
1206-17-2	Gray Mastic on HVAC Duct Wrap	Gray Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
021801945-0042		Homogeneous	2.000			

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample			<u>Asbestos</u>		
	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1206-18-1	White Mastic on HVAC Duct Wrap	Gray Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0043		Homogeneous			
1206-18-2	White Mastic on HVAC Duct Wrap	Gray Non-Fibrous	1% Cellulose <1% Glass	99% Non-fibrous (Other)	None Detected
021801945-0044		Homogeneous			
1206-19-1	Black Mastic on HVAC Duct Wrap	Black Non-Fibrous	<1% Cellulose	90% Non-fibrous (Other)	10% Chrysotile
021801945-0045		Homogeneous			
206-19-2	Black Mastic on HVAC Duct Wrap				Positive Stop (Not Analyzed)
021801945-0046					
1206-20-1-Skim Coat	Plaster (Both Coates)	White Non-Fibrous		10% Ca Carbonate 90% Non-fibrous (Other)	None Detected
021801945-0047		Homogeneous			
1206-20-1-Rough Coat	Plaster (Both Coates)	Gray/Tan Non-Fibrous	<1% Cellulose	35% Quartz 65% Non-fibrous (Other)	None Detected
021801945-0047A	Diseases (Dath Coast)	Homogeneous		400/ 0- 0	Nama Data dad
1206-20-2-Skim Coat	Plaster (Both Coates)	White Non-Fibrous Homogeneous		10% Ca Carbonate 90% Non-fibrous (Other)	None Detected
	Plaster (Both Coates)	Gray/Tan	<1% Cellulose	35% Quartz	None Detected
1206-20-2-Rough Coat	Plaster (Both Coates)	Non-Fibrous Homogeneous	<1% Cellulose	65% Non-fibrous (Other)	None Detected
1206-20-3-Skim Coat	Plaster (Both Coates)	White		10% Ca Carbonate	None Detected
21801945-0049	Flaster (Butil Coates)	Non-Fibrous Homogeneous		90% Non-fibrous (Other)	None Detected
1206-20-3-Rough Coat	Plaster (Both Coates)	Gray/Tan	<1% Cellulose	35% Quartz	None Detected
021801945-0049A	Plaster (Butil Coates)	Non-Fibrous Homogeneous	1 /0 Cellulose	65% Non-fibrous (Other)	None Detected
1206-20-4-Skim Coat	Plaster (Both Coates)	White		10% Ca Carbonate	None Detected
221801945-0050	. 140101 (2011) 204100)	Non-Fibrous Homogeneous		90% Non-fibrous (Other)	2000000
1206-20-4-Rough Coat	Plaster (Both Coates)	Gray/Tan	<1% Cellulose	35% Quartz	None Detected
021801945-0050A	,	Non-Fibrous Homogeneous		65% Non-fibrous (Other)	
1206-20-5-Skim Coat	Plaster (Both Coates)	White		10% Ca Carbonate	None Detected
021801945-0051	,	Non-Fibrous Homogeneous		90% Non-fibrous (Other)	
1206-20-5-Rough Coat	Plaster (Both Coates)	Gray/Tan	<1% Cellulose	35% Quartz	None Detected
)21801945-0051A		Non-Fibrous Homogeneous		65% Non-fibrous (Other)	
206-20-6-Skim Coat	Plaster (Both Coates)	White Non-Fibrous		10% Ca Carbonate 90% Non-fibrous (Other)	None Detected
021801945-0052		Homogeneous		. ,	
206-20-6-Rough Coat	Plaster (Both Coates)	Gray/Tan Non-Fibrous	<1% Cellulose	30% Quartz 70% Non-fibrous (Other)	None Detected
021801945-0052A		Heterogeneous			
1206-20-7-Skim Coat	Plaster (Both Coates)	White Non-Fibrous		10% Ca Carbonate 90% Non-fibrous (Other)	None Detected
021801945-0053		Homogeneous			
1206-20-7-Rough Coat	Plaster (Both Coates)	Gray/Tan Non-Fibrous	<1% Cellulose	30% Quartz 70% Non-fibrous (Other)	None Detected
021801945-0053A		Heterogeneous			
1206-21-1	Brown Interior Window Caulk	Brown Non-Fibrous	<1% Cellulose	10% Ca Carbonate 90% Non-fibrous (Other)	None Detected
021801945-0054		Homogeneous			

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			<u>Asbestos</u>		
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1206-21-2 021801945-0055	Brown Interior Window Caulk	Brown Non-Fibrous Homogeneous	<1% Cellulose 1% Glass	99% Non-fibrous (Other)	None Detected
1206-22-1	TSI Pipe Insulation	Gray/White Fibrous	2% Cellulose	38% Non-fibrous (Other)	5% Amosite 55% Chrysotile
021801945-0056		Homogeneous			
1206-23-1-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous	15% Cellulose	85% Non-fibrous (Other)	None Detected
021801945-0057	B ##1:4	Heterogeneous		2007 0 0 1 1	
1206-23-1-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
021801945-0057A					
1206-23-1-Tape	Drywall/Joint Compound	Beige Fibrous	100% Cellulose		None Detected
021801945-0057B		Homogeneous			
1206-23-2-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous Heterogeneous	15% Cellulose	85% Non-fibrous (Other)	None Detected
1206-23-2-Joint	Drywall/Joint	White		30% Ca Carbonate	None Detected
Compound	Compound	Non-Fibrous Homogeneous		70% Non-fibrous (Other)	None Detected
021801945-0058A					
1206-23-2-Tape	Drywall/Joint Compound	Beige Fibrous	100% Cellulose		None Detected
021801945-0058B		Homogeneous			
1206-23-3-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous	15% Cellulose	85% Non-fibrous (Other)	None Detected
021801945-0059		Heterogeneous			
1206-23-3-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
021801945-0059A					
1206-23-3-Tape	Drywall/Joint Compound	Beige Fibrous	100% Cellulose		None Detected
021801945-0059B		Homogeneous			
1206-23-4-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous	10% Cellulose	90% Non-fibrous (Other)	None Detected
021801945-0060	December 11/1 1 1	Heterogeneous		000/ 0- 0- 1	Maria D. C. C. I
1206-23-4-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
021801945-0060A					
1206-23-5-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous	10% Cellulose	90% Non-fibrous (Other)	None Detected
021801945-0061		Heterogeneous			
1206-23-5-Joint Compound	Drywall/Joint Compound	White Non-Fibrous	1% Cellulose	30% Ca Carbonate 69% Non-fibrous (Other)	None Detected
021801945-0061A		Homogeneous			
1206-23-5-Tape	Drywall/Joint Compound	Beige Fibrous	100% Cellulose		None Detected
021801945-0061B		Homogeneous			
1206-24-1	2x2 Textured Ceiling Tiles	Gray/White Fibrous	45% Cellulose 1% Min. Wool	45% Perlite 9% Non-fibrous (Other)	None Detected
021801945-0062		Homogeneous			



Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample			Asbestos		
	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1206-24-2	2x2 Textured Ceiling	Gray/White	45% Cellulose	45% Perlite	None Detected
021801945-0063	Tiles	Fibrous Homogeneous	1% Min. Wool	9% Non-fibrous (Other)	
1206-24-3	2x2 Textured Ceiling	Gray/White	45% Cellulose	40% Perlite	None Detected
021801945-0064	Tiles	Fibrous	1% Glass	14% Non-fibrous (Other)	
	10.10.0 (05.11)	Homogeneous	10/ 0 !! !	1000(1) 51 (01)	
1206-25-1-Carpet Mastic	12x12 Gray/Off White Floor Tile/Mastic/	Clear Non-Fibrous	<1% Cellulose <1% Synthetic	100% Non-fibrous (Other)	None Detected
	Carpet Adhesive	Homogeneous	,		
021801945-0065					
1206-25-1-Floor Tile	12x12 Gray/Off White Floor Tile/Mastic/	Gray/Tan/Beige Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected
021801945-0065A	Carpet Adhesive	Homogeneous		70,011011 1101040 (04101)	
1206-25-1-Mastic	12x12 Gray/Off White	Tan	<1% Cellulose	100% Non-fibrous (Other)	None Detected
21801945-0065B	Floor Tile/Mastic/ Carpet Adhesive	Non-Fibrous Homogeneous			
1206-25-2-Carpet	12x12 Gray/Off White	Yellow/Clear	<1% Cellulose	100% Non-fibrous (Other)	None Detected
Mastic	Floor Tile/Mastic/	Non-Fibrous	170 Ochdiose	100 /0 NON-IIDIOGS (Other)	None Detected
	Carpet Adhesive	Homogeneous			
021801945-0066 1206-25-2-Floor Tile	12x12 Gray/Off White	Brown/Tan/Beige		25% Quartz	None Detected
1206-25-2-F1001 THE	Floor Tile/Mastic/	Non-Fibrous		75% Non-fibrous (Other)	None Detected
)21801945-0066A	Carpet Adhesive	Homogeneous		. ,	
1206-25-2-Mastic	12x12 Gray/Off White	Yellow/Clear/Orang	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0066B	Floor Tile/Mastic/ Carpet Adhesive	e Non-Fibrous			
27007340 00000	ourpet/ tunesive	Homogeneous			
1206-26-1-Floor Tile	12x12 Blue Floor	Blue		25% Quartz	None Detected
021801945-0067	Tile/Mastic	Non-Fibrous		75% Non-fibrous (Other)	
	40.40 Dhaa Flaan	Homogeneous	00/ 0-11-1	OFO(New Shares (Others)	00/ 01
1206-26-1-Mastic	12x12 Blue Floor Tile/Mastic	Black Non-Fibrous	2% Cellulose	95% Non-fibrous (Other)	3% Chrysotile
021801945-0067A		Homogeneous			
1206-26-2-Floor Tile	12x12 Blue Floor	Green		25% Quartz	None Detected
021801945-0068	Tile/Mastic	Non-Fibrous Homogeneous		75% Non-fibrous (Other)	
1206-26-2-Mastic	12x12 Blue Floor	Homogonoodo			Positive Stop (Not Analyzed)
.200 20 2	Tile/Mastic				· · · · · · · · · · · · · · · · · · ·
021801945-0068A					
1206-27-1	Baseboard Adhesive	Beige Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0069		Homogeneous			
1206-27-2	Baseboard Adhesive	Yellow	1% Cellulose	99% Non-fibrous (Other)	None Detected
021801945-0070		Non-Fibrous			
1206-28-1	Gypsum Ceiling Tiles	Homogeneous Brown/Gray/White	15% Cellulose	1% Mica	None Detected
021801945-0071	Cypsum Ceiling mes	Fibrous Heterogeneous	1% Glass	83% Non-fibrous (Other)	None Delected
1206-28-2	Gypsum Ceiling Tiles	Brown/Gray	10% Cellulose	1% Mica	None Detected
1200-20-2	Gypsum Celling mes	Fibrous	1% Glass	88% Non-fibrous (Other)	NOTIC DELECTED
021801945-0072		Heterogeneous			
1206-28-3	Gypsum Ceiling Tiles	Brown/Gray/White	10% Cellulose	1% Mica	None Detected
021801945-0073		Fibrous Heterogeneous	1% Glass	88% Non-fibrous (Other)	
1206-29-1-Floor Tile	12x12 Off-White Floor	Brown/Gray		25% Quartz	None Detected
	Tile/Mastic	Non-Fibrous		75% Non-fibrous (Other)	
21801945-0074		Homogeneous			

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample			<u>Asbestos</u>		
	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1206-29-1-Mastic	12x12 Off-White Floor Tile/Mastic	Tan Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0074A		Homogeneous			
1206-29-2-Floor Tile	12x12 Off-White Floor Tile/Mastic	Tan/Beige Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected
021801945-0075		Homogeneous			
1206-29-2-Mastic	12x12 Off-White Floor Tile/Mastic	Yellow/Gold Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0075A		Homogeneous			
1206-30-1	Gray Duct Mastic	Gray Non-Fibrous	<1% Cellulose 10% Glass	90% Non-fibrous (Other)	None Detected
021801945-0076		Homogeneous			
1206-30-2	Gray Duct Mastic	Gray Fibrous	<1% Cellulose 10% Glass	90% Non-fibrous (Other)	None Detected
021801945-0077		Homogeneous			
1206-31-1	Textured Wall Surfacing Material	Gray/White Non-Fibrous	<1% Cellulose	30% Quartz 70% Non-fibrous (Other)	None Detected
021801945-0078	T	Homogeneous	-10/ 0 " '	000/ Owert	None Data to 1
1206-31-2 021801945-0079	Textured Wall Surfacing Material	Gray/White Non-Fibrous Homogeneous	<1% Cellulose	30% Quartz 70% Non-fibrous (Other)	None Detected
	Textured Wall	-	440/ Oallulaaa	200/ 0	Nama Datastad
1206-31-3 021801945-0080	Surfacing Material	Gray/Tan/White Non-Fibrous	<1% Cellulose	30% Quartz 70% Non-fibrous (Other)	None Detected
	Link One Deat	Heterogeneous	40/ 0-11-1	400/ O- O-d	News Datastad
1206-32-1 021801945-0081	Light Gray Duct Mastic	Beige Non-Fibrous	1% Cellulose 5% Glass	10% Ca Carbonate 84% Non-fibrous (Other)	None Detected
	Liebt Over Don't	Homogeneous	40/ 0-11-1	OAN(New Shares (Others)	News Datastad
1206-32-2	Light Gray Duct Mastic	White/Beige Non-Fibrous Homogeneous	1% Cellulose 5% Glass	94% Non-fibrous (Other)	None Detected
	Drywall/Joint	-	15% Cellulose	84% Non-fibrous (Other)	None Detected
1206-33-1-Drywall	Compound	Brown/Gray Fibrous Heterogeneous	1% Glass	64% Non-librous (Other)	None Detected
1206-33-1-Joint	Drywall/Joint	White		30% Ca Carbonate	None Detected
Compound	Compound	Non-Fibrous Homogeneous		70% Non-fibrous (Other)	None Detected
021801945-0083A					
1206-33-2-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous	10% Cellulose 1% Glass	89% Non-fibrous (Other)	None Detected
021801945-0084		Heterogeneous			
1206-33-2-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
021801945-0084A					
1206-33-3-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous	15% Cellulose 1% Glass	84% Non-fibrous (Other)	None Detected
021801945-0085	· 	Heterogeneous			
1206-33-3-Joint Compound	Drywall/Joint Compound	White Non-Fibrous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
·		Homogeneous			
021801945-0085A					
1206-33-4-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous	10% Cellulose 1% Glass	89% Non-fibrous (Other)	None Detected
021801945-0086		Heterogeneous		2004 0 0 1 1	
1206-33-4-Joint Compound	Drywall/Joint Compound	White Non-Fibrous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
		Homogeneous			

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample			<u>Asbestos</u>		
	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1206-33-5-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous Heterogeneous	20% Cellulose 1% Glass	79% Non-fibrous (Other)	None Detected
1206-33-5-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous		30% Ca Carbonate 70% Non-fibrous (Other)	None Detected
021801945-0087A					
1206-33-6-Drywall	Drywall/Joint Compound	Brown/Gray Fibrous Heterogeneous	15% Cellulose 1% Glass	84% Non-fibrous (Other)	None Detected
1206-33-6-Joint	Drywall/Joint	White	1% Cellulose	30% Ca Carbonate	None Detected
Compound	Compound	Non-Fibrous Homogeneous	1 /6 Cellulose	69% Non-fibrous (Other)	None Detected
021801945-0088A					
1206-33-6-Tape	Drywall/Joint Compound	Beige Fibrous	100% Cellulose		None Detected
1206-33-7-Drywall	Drywall/Joint Compound	Homogeneous Brown/Gray Fibrous	15% Cellulose 1% Glass	84% Non-fibrous (Other)	None Detected
021801945-0089		Heterogeneous			
1206-33-7-Joint Compound	Drywall/Joint Compound	White Non-Fibrous Homogeneous	1% Cellulose	30% Ca Carbonate 69% Non-fibrous (Other)	None Detected
021801945-0089A					
1206-33-7-Tape	Drywall/Joint Compound	Beige Fibrous	100% Cellulose		None Detected
021801945-0089B		Homogeneous			
1206-34-1	Carpet Adhesive	Tan/Yellow Non-Fibrous	3% Cellulose 1% Synthetic	96% Non-fibrous (Other)	None Detected
021801945-0090		Homogeneous	00/ 0 # 1	000/ N 51 (011)	
1206-34-2	Carpet Adhesive	Tan/Yellow/Gold Non-Fibrous Heterogeneous	3% Cellulose 1% Synthetic	96% Non-fibrous (Other)	None Detected
1206-35-1	Baseboard Adhesive	Beige Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0092		Homogeneous			
1206-35-2	Baseboard Adhesive	Beige Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0093		Homogeneous			
1206-36-1	2x4 Textured Ceiling Tiles	Gray/White Fibrous Homogeneous	40% Cellulose 10% Min. Wool	40% Perlite 10% Non-fibrous (Other)	None Detected
1206-36-2	2x4 Textured Ceiling Tiles	Gray/White Fibrous	40% Cellulose 10% Min. Wool	40% Perlite 10% Non-fibrous (Other)	None Detected
021801945-0095		Homogeneous			
1206-36-3	2x4 Textured Ceiling Tiles	Gray/White Fibrous	45% Cellulose 10% Min. Wool	40% Perlite 5% Non-fibrous (Other)	None Detected
021801945-0096		Homogeneous			
1206-37-1	2x2 Textured Ceiling Tiles	Gray/White Fibrous	40% Cellulose 30% Min. Wool	20% Perlite 10% Non-fibrous (Other)	None Detected
021801945-0097		Homogeneous			
1206-37-2	2x2 Textured Ceiling Tiles	Gray/White Fibrous Homogeneous	40% Cellulose 30% Min. Wool	20% Perlite 10% Non-fibrous (Other)	None Detected
1206-37-3	2x2 Textured Ceiling Tiles	Gray/White Fibrous	45% Cellulose 30% Min. Wool	20% Perlite 5% Non-fibrous (Other)	None Detected
021801945-0099		Homogeneous			

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-Asbes	stos	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1206-38-1	2x2 Rough Textured Ceiling Tiles	Gray/White Fibrous	30% Cellulose 40% Min. Wool	20% Perlite 10% Non-fibrous (Other)	None Detected
021801945-0100		Homogeneous			
1206-38-2	2x2 Rough Textured Ceiling Tiles	Gray/White Fibrous	30% Cellulose 40% Min. Wool	20% Perlite 10% Non-fibrous (Other)	None Detected
21801945-0101		Homogeneous			
206-38-3	2x2 Rough Textured Ceiling Tiles	Gray/White Fibrous	30% Cellulose 40% Min. Wool	20% Perlite 10% Non-fibrous (Other)	None Detected
021801945-0102		Homogeneous			
206-39-1	Black Mastic on HVAC Duct Wrap	Black Non-Fibrous	2% Cellulose	90% Non-fibrous (Other)	8% Chrysotile
21801945-0103		Homogeneous			D ": 0: 41.14 1 1)
206-39-2	Black Mastic on HVAC Duct Wrap				Positive Stop (Not Analyzed)
21801945-0104	10.10.0	D (0 (D)		050/ 0	
1206-40-1-Floor Tile	12x12 Gray on Brown Floor Tile/Mastic	Brown/Gray/Beige Non-Fibrous Homogeneous		25% Quartz 75% Non-fibrous (Other)	None Detected
	12x12 Gray on Brown	Black	<1% Cellulose	92% Non fibrous (Other)	8% Chrysotile
1206-40-1-Mastic	Floor Tile/Mastic	Non-Fibrous Homogeneous	~176 Cellulose	92% Non-fibrous (Other)	6% Chrysothe
1206-40-2-Floor Tile	12x12 Gray on Brown	Brown/Tan/Beige		25% Quartz	None Detected
021801945-0106	Floor Tile/Mastic	Non-Fibrous Homogeneous		75% Non-fibrous (Other)	None Detected
206-40-2-Mastic	12x12 Gray on Brown Floor Tile/Mastic	Homogeneous			Positive Stop (Not Analyzed)
021801945-0106A	1 1001 THE/IVIASTIC				
1206-41-1-Floor Tile	12x12 Gray w/ White Floor Tile/Mastic	Gray/Tan Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected
021801945-0107		Homogeneous			
206-41-1-Mastic	12x12 Gray w/ White Floor Tile/Mastic	Tan Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0107A		Homogeneous			
1206-41-2-Floor Tile	12x12 Gray w/ White Floor Tile/Mastic	Gray/Tan Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected
021801945-0108		Homogeneous			
1206-41-2-Mastic	12x12 Gray w/ White Floor Tile/Mastic	Tan/Yellow Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0108A		Homogeneous			
1206-42-1-Floor Tile	12x12 Beige w/ Tan Floor Tile/Mastic	Tan/Beige Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected
021801945-0109		Homogeneous			
206-42-1-Mastic	12x12 Beige w/ Tan Floor Tile/Mastic	Black Non-Fibrous	<1% Cellulose	92% Non-fibrous (Other)	8% Chrysotile
021801945-0109A	40.40 Dain/ T	Homogeneous		25% Overt	Name Detected
206-42-2-Floor Tile	12x12 Beige w/ Tan Floor Tile/Mastic	Tan/Beige Non-Fibrous Homogeneous		25% Quartz 75% Non-fibrous (Other)	None Detected
	10v10 Poice w/ Tor	Homogeneous			Docitivo Ston (Not Analyses 4)
206-42-2-Mastic	12x12 Beige w/ Tan Floor Tile/Mastic				Positive Stop (Not Analyzed)
121801945-0110A	10v10 \Mbita/ Dla -1:	Vollow	z10/ Collisions	1009/ Non fibrous (Other)	None Detected
1206-43-1-Top Mastic	12x12 White w/ Black Floor Tile/Mastic	Yellow Non-Fibrous Homogeneous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
1206-43-1-Floor Tile	12x12 White w/ Black Floor Tile/Mastic	Gray/White Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected
021801945-0111A	. iooi Tiio/Mastic	Homogeneous		70% Non-Ilbrous (Otrici)	

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-Asbe	estos	<u>Asbestos</u>	
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type	
1206-43-1-Bottom Mastic	12x12 White w/ Black Floor Tile/Mastic	Tan/Black Non-Fibrous Homogeneous	<1% Cellulose	100% Non-fibrous (Other)	<1% Chrysotile	
21801945-0111B						
1206-43-2-Top Mastic	12x12 White w/ Black Floor Tile/Mastic	Yellow Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected	
021801945-0112	40: 40 M/E/F / Plant	Homogeneous		05% 0	News Detected	
1206-43-2-Floor Tile	12x12 White w/ Black Floor Tile/Mastic	Gray/White/Beige Non-Fibrous Homogeneous		25% Quartz 75% Non-fibrous (Other)	None Detected	
1206-43-2-Bottom Mastic	12x12 White w/ Black Floor Tile/Mastic	Black/Yellow Non-Fibrous Heterogeneous	<1% Cellulose	100% Non-fibrous (Other)	<1% Chrysotile	
021801945-0112B						
1206-44-1	Residual Black Floor Tile Mastic	Black Non-Fibrous	<1% Cellulose	92% Non-fibrous (Other)	8% Chrysotile	
021801945-0113		Homogeneous				
1206-44-2	Residual Black Floor Tile Mastic				Positive Stop (Not Analyzed)	
1206 45 1	Dod Fire Oter	Dod	410/ O-III.J	070/ Nan Share (Ollan)	Name Date of all	
1206-45-1	Red Fire Stop	Red Fibrous Homogeneous	<1% Cellulose 3% Glass	97% Non-fibrous (Other)	None Detected	
1206-45-2	Red Fire Stop	Red/Black	<1% Cellulose	99% Non-fibrous (Other)	None Detected	
021801945-0116	Red File Stop	Non-Fibrous Homogeneous	1% Glass	99% Non-librous (Other)	None Detected	
1206-46-1	Mudded Elbow	Gray	5% Cellulose	20% Non-fibrous (Other)	75% Chrysotile	
021801945-0117	Widded Libow	Fibrous Homogeneous	370 Genulose	20 % Non-ilbrous (Other)	73% Onlysome	
1206-46-2	Mudded Elbow				Positive Stop (Not Analyzed)	
21801945-0118						
1206-47-1	Floor Underfelt (Old)	Brown/Black Fibrous	60% Cellulose 5% Synthetic	35% Non-fibrous (Other)	None Detected	
021801945-0119		Homogeneous				
1206-47-2	Floor Underfelt (Old)	Brown/Black Fibrous	80% Cellulose 5% Synthetic	14% Non-fibrous (Other)	None Detected	
021801945-0120	Floral C. C.	Homogeneous	1% Hair	000/ 11 51 (20)	N 5	
1206-48-1	Floor Underfelt (Newer)	Black Fibrous Homogeneous	70% Cellulose 1% Synthetic	29% Non-fibrous (Other)	None Detected	
	Elear Underfelt		759/ Colledos	240/ Non Shrava (Other)	None Detected	
1206-48-2	Floor Underfelt (Newer)	Black Fibrous Homogeneous	75% Cellulose 1% Synthetic <1% Hair	24% Non-fibrous (Other)	None Detected	
1206-49-1	Floor Underfelt (Red)	Brown/White Fibrous	98% Cellulose	2% Non-fibrous (Other)	None Detected	
021801945-0123		Homogeneous				
1206-49-2	Floor Underfelt (Red)	Brown/Tan/Beige Fibrous	95% Cellulose <1% Glass	5% Non-fibrous (Other)	None Detected	
021801945-0124		Heterogeneous				
1206-50-1	Residual Floor Penetration TSI	Brown/Gray/Tan Fibrous	5% Cellulose	55% Non-fibrous (Other)	40% Chrysotile	
021801945-0125		Heterogeneous				
1206-51-1	Expansion Joint Material	Black Fibrous	10% Cellulose	90% Non-fibrous (Other)	None Detected	
021801945-0126		Homogeneous				

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			<u>Asbestos</u>		
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1206-51-2	Expansion Joint Material	Tan/Black Fibrous	5% Cellulose <1% Synthetic	95% Non-fibrous (Other)	None Detected
021801945-0127		Heterogeneous			
1206-52-1	Timber Column Felt	Brown/Black Fibrous	5% Cellulose 10% Glass	25% Non-fibrous (Other)	60% Chrysotile
021801945-0128		Homogeneous			
1206-52-2	Timber Column Felt				Positive Stop (Not Analyzed)
21801945-0129					
206-53-1	Expansion Joint Felt (Black)	Brown/Black Fibrous	70% Cellulose	30% Non-fibrous (Other)	None Detected
21801945-0130		Homogeneous			
206-53-2	Expansion Joint Felt (Black)	Brown/Black Fibrous	70% Cellulose	30% Non-fibrous (Other)	None Detected
21801945-0131		Homogeneous			
206-54-1	Expansion Joint Felt (Red)	Brown/Black Fibrous	70% Cellulose	30% Non-fibrous (Other)	None Detected
021801945-0132		Homogeneous	700/ O. H.:	000/ N	
1206-54-2	Expansion Joint Felt (Red)	Brown/Tan/Black Fibrous Homogeneous	70% Cellulose <1% Synthetic	30% Non-fibrous (Other)	None Detected
	Fire Deer Material		000/ 0-11-1	400/ New Shares (Others)	News Datastad
206-55-1	Fire Door Material	Tan Fibrous Homogeneous	60% Cellulose	40% Non-fibrous (Other)	None Detected
	Fire Deer Material	-	100% Callulana		None Detected
206-55-2	Fire Door Material	Tan Fibrous Homogeneous	100% Cellulose		None Detected
206-56-1	Stucco Window Fill	Gray/Tan/White	<1% Cellulose	30% Quartz	None Detected
21801945-0136	Stucco William Fill	Non-Fibrous Homogeneous	<1% Cellulose	70% Non-fibrous (Other)	None Detected
206-56-2	Stucco Window Fill	Gray/Tan/White	<1% Cellulose	30% Quartz	None Detected
21801945-0137	Staces William Fill	Non-Fibrous Homogeneous	170 Genulose	70% Non-fibrous (Other)	None Detected
206-56-3	Stucco Window Fill	Gray/White/Beige	<1% Cellulose	25% Quartz	None Detected
21801945-0138		Non-Fibrous Heterogeneous	. 70 Condidas	75% Non-fibrous (Other)	25.65.65
206-57-1	Stair Tread Adhesive	Gray/Tan/Beige	<1% Cellulose	1% Quartz	None Detected
21801945-0139		Non-Fibrous Homogeneous	<1% Fibrous (Other)	99% Non-fibrous (Other)	110110 2010000
206-57-2	Stair Tread Adhesive	Yellow/Orange Non-Fibrous	<1% Cellulose 1% Synthetic	99% Non-fibrous (Other)	None Detected
21801945-0140		Homogeneous			
206-58-1-Floor Tile	12x12 Gray Floor Tile	Tan/Beige Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected
21801945-0141		Homogeneous			
206-58-1-Mastic	12x12 Gray Floor Tile	Tan Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
21801945-0141A		Homogeneous			
206-58-2-Floor Tile	12x12 Gray Floor Tile	White/Beige Non-Fibrous		25% Quartz 75% Non-fibrous (Other)	None Detected
21801945-0142		Homogeneous		. ,	
1206-58-2-Mastic	12x12 Gray Floor Tile	Yellow/Orange Non-Fibrous	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0142A		Homogeneous			
1206-59-1	Interior Door Caulk	White/Black Non-Fibrous	<1% Cellulose	10% Ca Carbonate 90% Non-fibrous (Other)	None Detected
021801945-0143		Homogeneous		-	

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbe % Fibrous	stos % Non-Fibrous	<u>Asbestos</u> % Type
1206-59-2	Interior Door Caulk	Brown/Beige	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	10% Ca Carbonate	None Detected
021801945-0144		Non-Fibrous Homogeneous		90% Non-fibrous (Other)	
1206-60-1	Exterior Door/Window Caulk	White/Black Non-Fibrous	<1% Cellulose	10% Ca Carbonate 90% Non-fibrous (Other)	None Detected
021801945-0145		Homogeneous			
1206-60-2	Exterior Door/Window Caulk	Brown Non-Fibrous	<1% Cellulose	10% Ca Carbonate 90% Non-fibrous (Other)	None Detected
021801945-0146		Homogeneous			
1206-61-1 021801945-0147	Exterior White Window Caulk	Gray/White/Beige Non-Fibrous Homogeneous	<1% Cellulose	1% Quartz 10% Ca Carbonate 89% Non-fibrous (Other)	None Detected
1206-61-2	Exterior White	-		2% Quartz	None Detected
1200-01-2	Window Caulk	White/Beige/Orang e		2% Quartz 10% Ca Carbonate	None Detected
021801945-0148		Non-Fibrous Heterogeneous		88% Non-fibrous (Other)	
1206-62-1	Textured Exterior	Gray/Tan/Beige	<1% Cellulose	40% Quartz	None Detected
	Stucco	Non-Fibrous		5% Ca Carbonate	
021801945-0149		Homogeneous		55% Non-fibrous (Other)	
1206-62-2	Textured Exterior	Gray/Tan/Beige	<1% Cellulose	40% Quartz 5% Ca Carbonate	None Detected
021801945-0150	Stucco	Non-Fibrous Homogeneous		5% Ca Carbonate 55% Non-fibrous (Other)	
1206-62-3	Textured Exterior	Gray/Tan/Beige	<1% Cellulose	40% Quartz	None Detected
1200 02 0	Stucco	Non-Fibrous	170 Collabor	5% Ca Carbonate	THORE DOLECTED
021801945-0151		Homogeneous		55% Non-fibrous (Other)	
1206-62-4-Stucco 1	Textured Exterior	Gray/Tan/Beige	<1% Cellulose	40% Quartz	None Detected
004004045 0455	Stucco	Non-Fibrous		5% Ca Carbonate	
021801945-0152		Homogeneous		55% Non-fibrous (Other)	
1206-62-4-Texture	Textured Exterior	Gray/Tan/Yellow	2% Cellulose	10% Quartz	None Detected
021801945-0152A	Stucco	Non-Fibrous Homogeneous		88% Non-fibrous (Other)	
1206-62-4-Stucco 2	Textured Exterior	Gray/Tan		30% Quartz	None Detected
	Stucco	Non-Fibrous		1% Mica	20.00.00
021801945-0152B		Heterogeneous		69% Non-fibrous (Other)	
1206-62-5-Stucco 1	Textured Exterior	White/Yellow/Beige		40% Quartz	None Detected
021801945-0153	Stucco	Non-Fibrous		5% Ca Carbonate	
	Tanking d Findender	Heterogeneous	00/ Calledon	55% Non-fibrous (Other)	Nama Data da 1
1206-62-5-Texture	Textured Exterior Stucco	Gray/Tan/Yellow Non-Fibrous	2% Cellulose	10% Quartz 88% Non-fibrous (Other)	None Detected
021801945-0153A		Heterogeneous			
1206-62-5-Stucco 2	Textured Exterior	Gray/Tan		30% Quartz	None Detected
	Stucco	Non-Fibrous		1% Mica	
021801945-0153B		Heterogeneous		69% Non-fibrous (Other)	
1206-63-1-Roofing	Roof Core	Black	<1% Cellulose	85% Non-fibrous (Other)	None Detected
021801945-0154		Non-Fibrous Homogeneous	15% Glass		
1206-63-1-Backing	Roof Core	Brown/Gray	10% Cellulose	88% Non-fibrous (Other)	None Detected
Board		Fibrous Homogeneous	2% Glass	•	
021801945-0154A					
1206-63-2-Roofing	Roof Core	Black	15% Cellulose	84% Non-fibrous (Other)	None Detected
021801945-0155		Fibrous Heterogeneous	1% Synthetic <1% Glass		
	Poof Core			900/ Non fibratio (Other)	None Detected
1206-63-2-Backing Board	Roof Core	Brown/Gray/Green Fibrous	10% Cellulose 1% Glass	89% Non-fibrous (Other)	None Detected
Doald		Heterogeneous	170 01000		
021801945-0155A		-			
Drywall-Like Material.					



Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-Asbe	estos	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1206-63-2-Insulation	Roof Core	Brown/Gray/Yellow Fibrous Heterogeneous	30% Cellulose 1% Glass	69% Non-fibrous (Other)	None Detected
	Poof Floohing		<1% Cellulose	959/ Non fibroup (Other)	None Detected
1206-64-1-Flashing	Roof Flashing	White/Blue Fibrous Homogeneous	15% Synthetic	85% Non-fibrous (Other)	None Detected
1206-64-1-Mastic	Roof Flashing	Tan	<1% Cellulose	100% Non-fibrous (Other)	None Detected
021801945-0156A	recorridoring	Non-Fibrous Homogeneous	170 Condicoo	roove from instruction (canon)	None Beleeted
1206-64-2-Flashing	Roof Flashing	White/Blue Fibrous	15% Synthetic	85% Non-fibrous (Other)	None Detected
021801945-0157		Homogeneous			
1206-64-2-Mastic	Roof Flashing	Tan/Yellow Non-Fibrous	3% Cellulose	97% Non-fibrous (Other)	None Detected
021801945-0157A		Homogeneous			
1206-65-1	White Roofing Caulk	Gray/White Non-Fibrous	<1% Cellulose	10% Ca Carbonate 90% Non-fibrous (Other)	None Detected
021801945-0158	M/hita Da - fire - O	Homogeneous		FOV Co. Contracts	Mana Detected
1206-65-2 021801945-0159	White Roofing Caulk	White/Beige Non-Fibrous Homogeneous		5% Ca Carbonate 95% Non-fibrous (Other)	None Detected
	Gray Roof Surface	Gray/White	<1% Cellulose	2% Quartz	None Detected
1206-66-1 021801945-0160	Coating	Non-Fibrous Homogeneous	<1% Cellulose	2% Quartz 10% Ca Carbonate 88% Non-fibrous (Other)	None Detected
1206-66-2	Gray Roof Surface	White/Beige/Rust Non-Fibrous	1% Cellulose	5% Quartz 10% Ca Carbonate	None Detected
021801945-0161	Coating	Homogeneous		84% Non-fibrous (Other)	
1206-67-1	Gray Flashing Mastic	Brown/Gray/White Non-Fibrous	<1% Cellulose	2% Quartz 10% Ca Carbonate	5% Chrysotile
021801945-0162		Homogeneous		83% Non-fibrous (Other)	
1206-67-2	Gray Flashing Mastic				Positive Stop (Not Analyzed
021801945-0163					
1206-68-1	Black Roof Patch Mastic	Gray/Black Fibrous	10% Cellulose	90% Non-fibrous (Other)	None Detected
021801945-0164		Homogeneous			
1206-68-2	Black Roof Patch Mastic	Gray/Black/Rust Non-Fibrous	1% Cellulose	99% Non-fibrous (Other)	None Detected
021801945-0165	Dad Doof Datab	Heterogeneous	410/ Octivises	900/ Non Share (Others)	None Datastad
1206-69-1 021801945-0166	Red Roof Patch Mastic	Gray/White/Pink Fibrous Homogeneous	<1% Cellulose 20% Synthetic	80% Non-fibrous (Other)	None Detected
1206-69-2	Red Roof Patch Mastic	Gray/White/Pink Fibrous	<1% Cellulose 20% Synthetic	80% Non-fibrous (Other)	None Detected
021801945-0167	Madio	Homogeneous	2070 Cynthicuo		
1206-69-3	Red Roof Patch Mastic	Gray/White/Pink Fibrous	1% Cellulose 15% Synthetic	84% Non-fibrous (Other)	None Detected
021801945-0168		Heterogeneous	<u> </u>		
1206-70-1	Black Flashing Mastic	Gray/White/Black Fibrous	5% Cellulose	85% Non-fibrous (Other)	10% Chrysotile
021801945-0169		Heterogeneous			
1206-70-2	Black Flashing Mastic				Positive Stop (Not Analyzed
021801945-0170					
1206-71-1	White Flashing Mastic	White Non-Fibrous	<1% Cellulose	10% Ca Carbonate 90% Non-fibrous (Other)	None Detected
021801945-0171		Homogeneous			



Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-A	asbestos	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Туре
1206-71-2	White Flashing Mastic	White		10% Ca Carbonate	None Detected
		Non-Fibrous		90% Non-fibrous (Other)	
021801945-0172		Homogeneous			

Analyst(s)

Nicole Shutts (145) Scott Combs (97) Stephen Bennett, Laboratory Manager or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%

Samples analyzed by EMSL Analytical, Inc. Kernersville, NC NVLAP Lab Code 102104-0, CA ELAP 2689, Virginia 3333-000228, West Virginia LT000321



1825 Blanding Street

Columbia, SC 29201

Attention: Glynn M. Ellen

EMSL Order: 021801945 Customer ID: FMEC62 Customer PO: E5700.19

Project ID:

Phone: (803) 254-4540

Fax: (803) 254-4542
Received Date: 03/19/2018 9:00 AM

Analysis Date: 03/23/2018 **Collected Date:** 03/16/2018

Project: ACM Investigation - Former SCE&G Building

Test Report: Asbestos Analysis of Non-Friable Organically Bound Materials by TEM via EPA/600/R-93/116 Section 2.5.5.1

Sample ID	Description	Appearance	% Matrix Material	% Non-Asbestos Fibers	Asbestos Types
1206-4-3		Beige	100	None	No Asbestos Detected
021801945-0173		Fibrous			
		Heterogeneous			
1206-5-3		Brown	100	None	No Asbestos Detected
021801945-0174		Non-Fibrous			
		Homogeneous			
1206-6-3		Tan	100	None	No Asbestos Detected
021801945-0175		Non-Fibrous			
		Homogeneous			
1206-7-3-Floor Tile		Blue	100	None	No Asbestos Detected
021801945-0176		Non-Fibrous			
		Heterogeneous			
1206-7-3-Mastic		Tan	100	None	No Asbestos Detected
021801945-0177		Non-Fibrous			
		Homogeneous			
1206-8-3-Floor Tile		Blue	100	None	No Asbestos Detected
021801945-0178		Non-Fibrous			
		Heterogeneous			
1206-8-3-Mastic		Tan	100	None	No Asbestos Detected
021801945-0179		Non-Fibrous			
		Homogeneous			
1206-9-3-Floor Tile		Red	100	None	No Asbestos Detected
021801945-0180		Non-Fibrous			
		Heterogeneous			
1206-9-3-Mastic		Tan	100	None	No Asbestos Detected
021801945-0181		Non-Fibrous			
		Homogeneous			
1206-10-3-Floor Tile		Beige	100	None	No Asbestos Detected
021801945-0182		Non-Fibrous			
		Heterogeneous			
1206-10-3-Mastic		 Tan	100	None	No Asbestos Detected
021801945-0183		Non-Fibrous			
		Homogeneous			
1206-11-3-Tan		 Tan	100	None	No Asbestos Detected
Mastic		Non-Fibrous			
021801945-0184		Homogeneous			

This laboratory is not responsible for % asbestos in total sample when the residue only is submitted for analysis. The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. Samples received in good condition unless otherwise noted. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample.

Samples analyzed by EMSL Analytical, Inc. Kernersville, NC



1825 Blanding Street

Columbia, SC 29201

Attention: Glynn M. Ellen

 EMSL Order:
 021801945

 Customer ID:
 FMEC62

 Customer PO:
 E5700.19

Project ID:

Phone: (803) 254-4540

Fax: (803) 254-4542

Received Date: 03/19/2018 9:00 AM
Analysis Date: 03/23/2018

Analysis Date: 03/23/2018 **Collected Date**: 03/16/2018

Project: ACM Investigation - Former SCE&G Building

Test Report: Asbestos Analysis of Non-Friable Organically Bound Materials by TEM via EPA/600/R-93/116 Section 2.5.5.1

Sample ID	Description	Appearance	% Matrix Material	% Non-Asbestos Fibers	Asbestos Types
1206-12-3-Floor Tile		Green/Beige	100	None	No Asbestos Detected
021801945-0185		Non-Fibrous			
		Heterogeneous			
1206-13-3		Purple	99.3	None	0.74% Chrysotile
021801945-0186		Non-Fibrous			
		Heterogeneous			
1206-14-3-Floor Tile		Beige	100	None	No Asbestos Detected
021801945-0187		Non-Fibrous			
		Heterogeneous			
1206-14-3-Mastic		Tan	100	None	No Asbestos Detected
021801945-0188		Non-Fibrous			
		Homogeneous			
1206-15-3-Floor Tile	!	Gray	100	None	No Asbestos Detected
021801945-0189		Non-Fibrous			
		Heterogeneous			
1206-15-3-Mastic		Tan	100	None	No Asbestos Detected
021801945-0190		Non-Fibrous			
		Homogeneous			
1206-16-3		Beige	100	None	No Asbestos Detected
021801945-0191		Non-Fibrous			
		Homogeneous			
1206-17-3		Gray	100	None	No Asbestos Detected
021801945-0192		Fibrous			
		Heterogeneous			
1206-18-3		Gray	100	None	No Asbestos Detected
021801945-0193		Fibrous			
		Heterogeneous			
1206-21-3		Brown	100	None	No Asbestos Detected
021801945-0194		Non-Fibrous			
		Homogeneous			
1206-25-3-Floor Tile		Beige	100	None	No Asbestos Detected
021801945-0195		Non-Fibrous	.00		
		Heterogeneous			
1206-25-3-Mastic		Yellow	100	None	No Asbestos Detected
021801945-0196		Non-Fibrous	100	NOILE	ואט עסטבפוטפ הבוברובת
021001940-0190					
		Homogeneous			

This laboratory is not responsible for % asbestos in total sample when the residue only is submitted for analysis. The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. Samples received in good condition unless otherwise noted. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample.

Samples analyzed by EMSL Analytical, Inc. Kernersville, NC



1825 Blanding Street

Columbia, SC 29201

Attention: Glynn M. Ellen

EMSL Order: 021801945 Customer ID: FMEC62 Customer PO: E5700.19

Project ID:

Phone: (803) 254-4540 Fax: (803) 254-4542

Received Date: 03/19/2018 9:00 AM

Analysis Date: 03/23/2018 **Collected Date**: 03/16/2018

Project: ACM Investigation - Former SCE&G Building

Test Report: Asbestos Analysis of Non-Friable Organically Bound Materials by TEM via EPA/600/R-93/116 Section 2.5.5.1

Sample ID	Description	Appearance	% Matrix Material	% Non-Asbestos Fibers	Asbestos Types
1206-26-3-Floor Tile 021801945-0197		Blue Non-Fibrous Heterogeneous	100	None	No Asbestos Detected
1206-27-3 021801945-0198		Tan Non-Fibrous Homogeneous	100	None	No Asbestos Detected
1206-29-3-Floor Tile 021801945-0199		Gray Non-Fibrous Heterogeneous	100	None	No Asbestos Detected
1206-29-3-Mastic 021801945-0199A		Tan Non-Fibrous Homogeneous	100	None	No Asbestos Detected
1206-30-3 021801945-0200		Gray Non-Fibrous Homogeneous	100	None	No Asbestos Detected
1206-32-3 021801945-0201		Gray Fibrous Heterogeneous	100	None	No Asbestos Detected
1206-34-3 021801945-0202		Tan Non-Fibrous Homogeneous	100	None	No Asbestos Detected
1206-35-3 021801945-0203		Tan Non-Fibrous Homogeneous	100	None	No Asbestos Detected
1206-40-3-Floor Tile 021801945-0204		Gray Non-Fibrous Heterogeneous	100	None	No Asbestos Detected
1206-40-3-Mastic 021801945-0205		Tan Non-Fibrous Homogeneous	100	None	No Asbestos Detected
1206-41-3-Floor Tile 021801945-0206		Gray Non-Fibrous Heterogeneous	100	None	No Asbestos Detected
1206-41-3-Mastic 021801945-0207		Tan Non-Fibrous Homogeneous	100	None	No Asbestos Detected

This laboratory is not responsible for % asbestos in total sample when the residue only is submitted for analysis. The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. Samples received in good condition unless otherwise noted. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample.

Samples analyzed by EMSL Analytical, Inc. Kernersville, NC



1825 Blanding Street

Columbia, SC 29201

Attention: Glynn M. Ellen

 EMSL Order:
 021801945

 Customer ID:
 FMEC62

 Customer PO:
 E5700.19

Project ID:

Phone: (803) 254-4540

Fax: (803) 254-4542

Received Date: 03/19/2018 9:00 AM

Analysis Date: 03/23/2018 **Collected Date**: 03/16/2018

Project: ACM Investigation - Former SCE&G Building

Test Report: Asbestos Analysis of Non-Friable Organically Bound Materials by TEM via EPA/600/R-93/116 Section 2.5.5.1

Sample ID	Description	Appearance	% Matrix Material	% Non-Asbestos Fibers	Asbestos Types
1206-42-3-Floor Tile		Tan	100	None	No Asbestos Detected
021801945-0208		Non-Fibrous			
		Heterogeneous			
1206-43-3-Top		Tan	100	None	No Asbestos Detected
Mastic		Non-Fibrous			
021801945-0209		Homogeneous			
1206-43-3-Floor Tile		Beige	100	None	No Asbestos Detected
021801945-0210		Non-Fibrous			
		Heterogeneous			
1206-43-3-Bottom		Black	99.3	None	0.68% Chrysotile
Mastic		Non-Fibrous			
021801945-0211		Homogeneous			
1206-45-3		Red	100	None	No Asbestos Detected
021801945-0212		Fibrous			
		Heterogeneous			
1206-47-3		Black	100	None	No Asbestos Detected
021801945-0213		Fibrous			
		Heterogeneous			
1206-48-3		Black	100	None	No Asbestos Detected
021801945-0214		Fibrous			
		Heterogeneous			
1206-49-3		Tan/White	100	None	No Asbestos Detected
021801945-0215		Fibrous			
		Heterogeneous			
1206-51-3		Black	100	None	No Asbestos Detected
021801945-0216		Non-Fibrous			
		Heterogeneous			
1206-55-3		Tan	100	None	No Asbestos Detected
021801945-0217		Fibrous			
		Heterogeneous			
1206-57-3		Beige	100	None	No Asbestos Detected
021801945-0218		Non-Fibrous			
		Homogeneous			
1206-58-3		Gray	100	None	No Asbestos Detected
021801945-0219		Non-Fibrous			
		Heterogeneous			

This laboratory is not responsible for % asbestos in total sample when the residue only is submitted for analysis. The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. Samples received in good condition unless otherwise noted. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample.

Samples analyzed by EMSL Analytical, Inc. Kernersville, NC



1825 Blanding Street

Columbia, SC 29201

Attention: Glynn M. Ellen

EMSL Order: 021801945 Customer ID: FMEC62 Customer PO: E5700.19

Project ID:

Phone: (803) 254-4540

Fax: (803) 254-4542
Received Date: 03/19/2018 9:00 AM

Analysis Date: 03/23/2018 **Collected Date:** 03/16/2018

Project: ACM Investigation - Former SCE&G Building

Test Report: Asbestos Analysis of Non-Friable Organically Bound Materials by TEM via EPA/600/R-93/116 Section 2.5.5.1

Sample ID	Description	Appearance	% Matrix Material	% Non-Asbestos Fibers	Asbestos Types
1206-58-3		Tan	100	None	No Asbestos Detected
021801945-0220		Non-Fibrous			
		Homogeneous			
1206-59-3		Black/Beige	100	None	No Asbestos Detected
021801945-0221		Non-Fibrous			
		Heterogeneous			
1206-60-3		Black	100	None	No Asbestos Detected
021801945-0222		Non-Fibrous			
		Homogeneous			
1206-61-3		Gray	100	None	No Asbestos Detected
021801945-0223		Non-Fibrous			
		Homogeneous			
1206-63-3-Roofing		Black	100	None	No Asbestos Detected
021801945-0224		Fibrous			
		Heterogeneous			
1206-63-3-Backing		Gray	100	None	No Asbestos Detected
Board		Fibrous			
021801945-0225		Heterogeneous			
1206-63-3-Insulation		Yellow	100	None	No Asbestos Detected
021801945-0226		Non-Fibrous			
		Heterogeneous			
1206-64-3-Flashing		Brown	100	None	No Asbestos Detected
021801945-0227		Fibrous			
		Heterogeneous			
1206-64-3-Mastic		Tan	100	None	No Asbestos Detected
021801945-0228		Non-Fibrous			
		Homogeneous			
1206-65-3		White	100	None	No Asbestos Detected
021801945-0229		Fibrous			
		Heterogeneous			
1206-66-3		Gray	100	None	No Asbestos Detected
021801945-0230		Non-Fibrous			
		Homogeneous			
1206-68-3		Black	99.3	None	0.70% Chrysotile
021801945-0231		Non-Fibrous			
		Homogeneous			

This laboratory is not responsible for % asbestos in total sample when the residue only is submitted for analysis. The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. Samples received in good condition unless otherwise noted. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample.

Samples analyzed by EMSL Analytical, Inc. Kernersville, NC



1825 Blanding Street

Columbia, SC 29201

Attention: Glynn M. Ellen

EMSL Order: 021801945 **Customer ID:** FMEC62 **Customer PO:** E5700.19

Project ID:

Phone: (803) 254-4540

Fax: (803) 254-4542

Received Date: 03/19/2018 9:00 AM

Analysis Date: 03/23/2018 **Collected Date**: 03/16/2018

Project: ACM Investigation - Former SCE&G Building

Test Report: Asbestos Analysis of Non-Friable Organically Bound Materials by TEM via EPA/600/R-93/116 Section 2.5.5.1

Sample ID	Description	Appearance	% Matrix Material	% Non-Asbestos Fibers	Asbestos Types
1206-71-3		Gray/White	100	None	No Asbestos Detected
021801945-0232		Non-Fibrous			
		Heterogeneous			

Analyst(s)
Stephen Bennett (61)

Stephen Bennett, Laboratory Manager or other approved signatory

This laboratory is not responsible for % asbestos in total sample when the residue only is submitted for analysis. The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. Samples received in good condition unless otherwise noted. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample.

Samples analyzed by EMSL Analytical, Inc. Kernersville, NC

Appendix J

Chain of Custody Forms



OrderID: 021801945

Asbestos Chain of Custody EMSL Order Number (Lab Use Only):

ISL Order Number (Lab Use Only):

EMSL ANALYTICAL, INC.

□ 3 Hour □ 6 Hour *For TEM Air 3 hr through 6 hr, please consultation form for this sense from NY □ NIOSH 7400 □ w/ OSHA 8hr. TWA PLM - Bulk (reporting limit) □ PLM EPA 600/R-93/116 (<1%) □ PLM EPA NOB (<1%) Point Count □ 400 (<0.25%) □ 1000 (<0.1%) Point Count w/Gravimetric	SL-Bill to: Same Different Third Party Billing requires we Turnaround Time (TAT 24 Hour 48 Hour all ahead to schedule. *There is a premio vice. Analysis completed in accordance TEM - Air 4-4.5hr TAT AHERA 40 CFR, Part 7 NIOSH 7402 EPA Level II ISO 10312	Please Prove Purchase O EMSL Projet CT Samples - If Bill to is Differentiation) Options* - P 72 Ho 72 Ho	#: 803-254-49 vide Results: Prder: E5700.19 ect ID (Internal s: O Comment note instructions on from third part Please Check Our O Sour TEM AHERA ms and Condition TEM- Dust Microval	Fax Email 19 I Use Only): rcial/Taxable Residual is in Comments** by 6 Hour 1 Week or EPA Level II TAT. You in ns located in the Analytical in	dential/Tax Exempt	
Report To (Name): Glynn Ellen Email Address: gellen@fmecol.cc Project Name/Number: ACM Intellege Building U.S. State Samples Taken: SC EMS 3 Hour 6 Hour For TEM Air 3 hr through 6 hr, please consultarization form for this sense of authorization form for this sense from NY NIOSH 7400 W/ OSHA 8hr. TWA PLM - Bulk (reporting limit) PLM EPA 600/R-93/116 (<1%) PLM EPA NOB (<1%) Point Count 400 (<0.25%) 1000 (<0.1%) Point Count w/Gravimetric	om, mmincey@fmecol.com vestigation - Former SCE&G SL-Bill to: Same Different Third Party Billing requires wi Turnaround Time (TAT 24 Hour 48 Hour 48 Hour Analysis completed in accordance TEM - Air 4-4.5hr TAT AHERA 40 CFR, Part 7 NIOSH 7402 EPA Level II ISO 10312	Please Prove Purchase O EMSL Projet CT Samples - If Bill to is Differentiation) Options* - P 72 Ho 72 Ho	order: E5700. Sect ID (Internal Sect ID (Intern	Fax Email 19 I Use Only): rcial/Taxable Residual is in Comments** by 6 Hour 1 Week or EPA Level II TAT. You in a located in the Analytical in	dential/Tax Exempt	
Email Address: gellen@fmecol.co Project Name/Number: ACM Integration Building U.S. State Samples Taken: SC EMS 3 Hour 6 Hour For TEM Air 3 hr through 6 hr, please or authorization form for this sense from NY NIOSH 7400 NIOSH 7400 NIOSH 8hr. TWA PLM - Bulk (reporting limit) PLM EPA 600/R-93/116 (<1%) PLM EPA NOB (<1%) Point Count 400 (<0.25%) 1000 (<0.1%) Point Count w/Gravimetric	SL-Bill to: Same Different Third Party Billing requires we Turnaround Time (TAT 24 Hour 48 Hour all ahead to schedule. *There is a premio vice. Analysis completed in accordance TEM - Air 4-4.5hr TAT AHERA 40 CFR, Part 7 NIOSH 7402 EPA Level II ISO 10312	Purchase O EMSL Proje CT Samples - If Bill to is Differer itten authorization) Options* - P	ect ID (Internalis: Comment note instructions on from third particles Check our 9 our TEM AHERA ms and Condition TEM- Dust	I Use Only): rcial/Taxable Residual Res	2 Week	
Project Name/Number: ACM Integrity Building U.S. State Samples Taken: SC EMS 3 Hour	SL-Bill to: Same Different Third Party Billing requires we Turnaround Time (TAT 24 Hour 48 Hour all ahead to schedule. *There is a premio vice. Analysis completed in accordance TEM - Air 4-4.5hr TAT AHERA 40 CFR, Part 7 NIOSH 7402 EPA Level II ISO 10312	EMSL Proje CT Samples - If Bill to is Differentiation authorization) Options* - P 72 Ho um charge for 3 Ho e with EMSL's Tential (AHERA only)	sct ID (Internal s: Comme in note instructions in from third part lease Check our Sour Sour Sour ms and Condition TEM- Dust Microvae	I Use Only): rcial/Taxable Residual Re	2 Week	
BMS 3 Hour	Third Party Billing requires we Turnaround Time (TAT 24 Hour 48 Hour all ahead to schedule. *There is a premie vice. Analysis completed in accordance TEM - Air	- if Bill to is Differer itten authorization Options* - P \(\sum 72 \text{ Ho} \) In charge for 3 Ho owith EMSL's Ten (AHERA only)	nt note instructions In from third par Please Check Our S 9 Our TEM AHERA ms and Condition TEM- Dust	s in Comments** fy 6 Hour 1 Week or EPA Level II TAT. You in slocated in the Analytical in the Anal	2 Week	
For TEM Air 3 hr through 6 hr, please or authorization form for this send PCM - Air	Turnaround Time (TAT 24 Hour	Options – P 72 Ho m charge for 3 Ho e with EMSL's Ten (AHERA only)	Dur EM AHERA ms and Condition TEM- Dust	6 Hour 1 1 Week or EPA Level II TAT. You in ns located in the Analytical i	will be asked to sign an	
*For TEM Air 3 hr through 6 hr, please or authorization form for this sense from NY Check if samples are from NY NIOSH 7400 w/ OSHA 8hr. TWA PLM - Bulk (reporting limit) PLM EPA 600/R-93/116 (<1%) PLM EPA NOB (<1%) Point Count 400 (<0.25%) 1000 (<0.1%) Point Count w/Gravimetric	all ahead to schedule. There is a premiovice. Analysis completed in accordance TEM - Air	om charge for 3 Ho e with EMSL's Ten (AHERA only)	ms and Condition TEM- Dust	or EPA Level II TAT. You on the state of the Analytical in	will be asked to sign an	
PCM - Air	TEM - Air	(AHERA only)	TEM- Dust			
□ NIOSH 7400 □ w/ OSHA 8hr. TWA PLM - Bulk (reporting limit) □ PLM EPA 600/R-93/116 (<1%) □ PLM EPA NOB (<1%) Point Count □ 400 (<0.25%) □ 1000 (<0.1%) Point Count w/Gravimetric	☐ AHERA 40 CFR, Part 7 ☐ NIOSH 7402 ☐ EPA Level II ☐ ISO 10312		☐ Microva			
□ w/ OSHA 8hr. TWA PLM - Bulk (reporting limit) □ PLM EPA 600/R-93/116 (<1%) □ PLM EPA NOB (<1%) Point Count □ 400 (<0.25%) □ 1000 (<0.1%) Point Count w/Gravimetric	□ NIOSH 7402 □ EPA Level II □ ISO 10312					
PLM - Bulk (reporting limit)	☐ EPA Level II ☐ ISO 10312		I I VVIDE - A	- ASTM D6480		
☐ PLM EPA 600/R-93/116 (<1%) ☐ PLM EPA NOB (<1%) Point Count ☐ 400 (<0.25%) ☐ 1000 (<0.1%) Point Count w/Gravimetric	☐ ISO 10312			et Sonication (EPA 600/J-93/167)		
☐ PLM EPA NOB (<1%) Point Count ☐ 400 (<0.25%) ☐ 1000 (<0.1%) Point Count w/Gravimetric	TEM D. II			ock/Vermiculite		
☐ 400 (<0.25%) ☐ 1000 (<0.1%) Point Count w/Gravimetric	TEM - Bulk			EPA 600/R-93/116 with milling prep (<1%)		
400 (<0.25%) 1000 (<0.1%)	☐ Chatfield SOP	NYS NOB 198.4 (non-friable-NY)		□ PLM EPA 600/R-93/116 with milling prep (<0.25% □ TEM EPA 600/R-93/116 with milling prep (<0.1%) □ TEM Qualitative via Filtration Prep □ TEM Qualitative via Drop Mount Prep		
☐ NYS 198.1 (friable in NY)	TEM - Water: EPA 100.2		The second secon	ti Method EPA 600/R-0)4/004 - PLM/TEM	
☐ NYS 198.6 NOB (non-friable-NY☐ NYS 198.8 SOF-V☐ NIOSH 9002 (<1%)		☐ Drinking ☐ Drinking	(BC only) Other:			
☐ Check For Positive Stop - Cle	arly Identify Homogenous Grou			ir Samples): 🔲 0.8µ		
Samplers Name: Mike Mincey		Samplers	s Signature:	With Mu	ay	
Sample #	Sample Descrip			Volume/Area (Air) HA # (Bulk)	Date/Time Sampled	
1206-1-1 to 1206-1-7 Drywal	II/Joint Compound		7/			
1206-2-1 to 1206-2-3 2' x 2' h	Heavy Textured Ceiling Tiles					
1206-3-1 to 1206-3-3 2' x 4' 5	Small Pinhole Ceiling Tiles					
*1206-4-1 to 1206-4-3 Cream	Baseboard Adhesive					
*1206-5-1 to 1206-5-3 Brown	Baseboard Adhesive					
	6-1-1 . Www.cry Date	1206-71-3 e: 3	3/16/2018	Total # of Samples: Time:	223 - 57 NOTE	
Received (Lab): Comments/Special Instructions	Date	o: 3/19	9/18	Time:	_	

Page 1 of 4 pages

OrderID: 021801945

Asbestos Chain of Custody EMSL Order Number (Lab Use Only):

EMBL ANALYTICAL, INC.

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Sample #	Sample Description	Volume/Area (Air) HA # (Bulk)	Date/Time Sampled
*1206-6-1 to 1206-6-3	Carpet Adhesive		
*1206-7-1 to 1206-7-3	12" x 12" Gray Floor Tile/Mastic		
*1206-8-1 to 1206-8-3	12" x 12" Blue Floor Tile/Mastic		
*1206-9-1 to 1206-9-3	12" x 12" Red Floor Tile/Mastic		CIT
*1206-10-1 to 1206-10-3	12" x 12" Peach Floor Tile/Mastic		
1206-11-1 to 1206-11-3	White Leveling Compound	-	
*1206-12-1 to 1206-12-3	12" x 12" Tan Floor Tile/Mastic	100000000000000000000000000000000000000	
*1206-13-1 to 1206-13-3	Tan Sink Undercoating		
*1206-14-1 to 1206-14-3	12" x 12" Light Brown Floor Tile/Mastic		
*1206-15-1 to 1206-15-3	12" x 12" Tan Streaked Floor Tile/Mastic		
*1206-16-1 to 1206-16-3	Tan Mastic on HVAC Duct Wrap		
*1206-17-1 to 1206-17-3	Gray Mastic on HVAC Duct Wrap		
*1206-18-1 to 1206-18-3	White Mastic on HVAC Duct Wrap		
*1206-19-1 to 1206-19-3	Black Mastic on HVAC Duct Wrap		
1206-20-1 to 1206-20-7	Plaster (Both Coates)		
*1206-21-1 to 1206-21-3	Brown Interior Window Caulk	2000	
1206-22-1	TSI Pipe Insulation		1
1206-23-1 to 23-5	Drywall/Joint Compound		
1206-24-1 to 1206-24-3	2' x 2' Textured Ceiling Tiles		
*1206-25-1 to 1206-25-3	12" x 12"Gray/Off White Floor Tile/Mastic & Carpet Adhesive	1 301	
*1206-26-1 to 1206-26-3	12" x 12" Blue Floor Tile/Mastic		
*1206-27-1 to 1206-27-3	Baseboard Adhesive		
1206-28-1 to 1206-28-3 *Comments/Special Ins	Gypsum Ceiling Tiles		

Page 2 of 4 pages

OrderID: 021801945

Asbestos Chain of Custody EMSL Order Number (Lab Use Only):

EMSL ANALYTICAL, INC.

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Sample #	Sample Description	Volume/Area (Air) HA # (Bulk)	Date/Time Sampled
*1206-29-1 to 1206-29-3	12" X 12" Off-White Floor Tile/Mastic		
*1206-30-1 to 1206-30-3	Gray Duct Mastic		
1206-31-1 to 1206-31-3	Textured Wall Surfacing Material		
*1206-32-1 to 1206-32-3	Light Gray Duct Mastic		
1206-33-1 to 1206-33-7	Drywall/Joint Compound		
*1206-34-1 to 1206-34-3	Carpet Adhesive		
*1206-35-1 to 1206-35-3	Baseboard Adhesive		
1206-36-1 to 1206-36-3	2' x 4' Textured Ceiling Tiles		
1206-37-1 to 1206-37-3	2' x 2' Textured Ceiling Tiles		
1206-38-1 to 1206-38-3	2' x 2' Rough Textured Ceiling Tiles		
*1206-39-1 to 1206-39-3	Black Mastic on HVAC Duct Wrap	100 (SVI)	
*1206-40-1 to 1206-40-3	12" x 12" Gray on Brown Floor Tile/Mastic		
*1206-41-1 to 1206-41-3	12" x 12" Gray w/White Floor Tile/Mastic		12:10
*1206-42-1 to 1206-42-3	12" x 12" Beige w/Tan Floor Tile/Mastic		
*1206-43-1 to 1206-43-3	12" x 12" White w/Black Floor Tile/Mastic		
*1206-44-1 to 1206-44-3	Residual Black Floor Tile Mastic		
*1206-45-1 to 1206-45-3	Red Fire Stop		
1206-46-1 to 46-2	Mudded Elbow		
*1206-47-1 to 1206-47-3	Floor Underfelt (Old)	The state of	
*1206-48-1 to 1206-48-3	Floor Underfelt (Newer)		
*1206-49-1 to 1206-49-3	Floor Underfelt (Red)		
1206-50-1	Residual Floor Penetration TSI		, link
*1206-51-1 to 1206-51-3 *Comments/Special Ins	Expansion Joint Material		

Page 3 of 4 pages

Asbestos Chain of Custody EMSL Order Number (Lab Use Qnly):

EMSL ANALYTICAL, INC.

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Sample #	Sample Description	Volume/Area (Air) HA # (Bulk)	Date/Time Sampled
1206-52-1 to 1206-52-3	Timber Column Felt		
1206-53-1 to 1206-53-3	Expansion Joint Felt (Black)		
1206-54-1 to 1206-54-3	Expansion Joint Felt (Red)	4	
*1206-55-1 to 1206-55-3	Fire Door Material		
1206-56-1 to 1206-56-3	Stucco Window Fill	4 1 1 1 1 1	- (-)
*1206-57-1 to 1206-57-3	Stair Tread Adhesive		
*1206-58-1 to 1206-58-3	12" x 12" Gray Floor Tile		
*1206-59-1 to 1206-59-3	Interior Door Caulk		
*1206-60-1 to 1206-60-3	Exterior Door/Window Caulk		
*1206-61-1 to 1206-61-3	Exterior White Window Caulk		
1206-62-1 to 1206-62-5	Textured Exterior Stucco	CONTRACTOR OF THE PARTY OF THE	in a series
*1206-63-1 to 1206-63-3	Roof Core		
*1206-64-1 to 1206-64-3	Roof Flashing		
*1206-65-1 to 1206-65-3	White Roofing Caulk		
*1206-66-1 to 1206-66-3	Gray Roof Surface Coating		
*1206-67-1 to 1206-67-3	Gray Flashing Mastic		
*1206-68-1 to 1206-68-3	Black Roof Patch Mastic		
1206-69-1 to 1206-69-3	Red Roof Patch Mastic		
*1206-70-1 to 1206-70-3	Black Flashing Mastic		
*1206-71-1 to 1206-71-3	White Flashing Mastic		2 1/4
		2014	
			au l

Page #of 4 pages

Appendix K

Personnel Certifications



SCDHEC ISSUED

Asbestos ID Card

Michael Mincey



SUPERAHERA SA-01424 CONSULTMP AIRSAMPLER

MP-00161 AS-00272

Expiration Date: 01/30/19 01/29/19 01/30/19

This card is nontransferable and account invalid if loaned or given to another person for identification. This card will also be invalid if altered or defaced. This card is property of SCDHEC. It must be returned to the department if the holder's accreditation is revoked or if this card is invalidated. Any person performing regulated asbestos activities without current accreditation shall be subject to legal sanction. This card must be returned upon expiration and/or issuance of a new card.

YOU MUST HAVE THIS IDENTIFICATION CARD WITH YOU ON THE JOB.

For information of corrections contact:

SCDHEC - Asbestos Section 2600 Bull Street

Columbia, SC 29201 (803) 898-4289

SCDHEC ISSUED

Asbestos ID Card

Glynn M Ellen



SUPERAHERA SA-00455 01/30/19 CONSULTPD PD-00098 06/09/18 CONSULTMP ASB-22641 01/29/19 AIRSAMPLER AS-00079 01/30/19

This card is nontransferable and _____ invalid if loaned or given to another person for identification. This card will also be invalid if altered or defaced. This card is property of SCDHEC. It must be returned to the department if the holder's accreditation is revoked or if this card is invalidated. Any person performing regulated asbestos activities without current accreditation shall be subject to legal sanction. This card must be returned upon expiration and/or issuance of a new card.

YOU MUST HAVE THIS IDENTIFICATION CARD WITH YOU ON THE JOB.

For information of corrections contact:

SCDHEC – Asbestos Section 2600 Bull Street

Columbia, SC 29201 (803) 898-4289

Appendix L

Regulatory Summary



Asbestos Regulatory Information

Renovations & Demolitions

Definitions

Renovation means altering a facility or one or more facility components in any way, including the stripping or removal of regulated asbestos-containing materials (RACM) from a facility component. "Remodeling" is considered renovation.

Demolition is wrecking or taking out any load-supporting structural member of a facility together and any related handling operations. Structural burns are prohibited by State Open Burning Regulations.

Applicability

Renovation and demolition of most facilities (including buildings, structures, and other installations), are subject to State and Federal asbestos regulations. Certain residential buildings may be exempt. Contact the SCDHEC Asbestos Section for additional information.

All asbestos-containing materials must be removed from a facility prior to demolition. Only the following asbestos-containing materials (ACM) may be left in place during demolition:

- ACM on a facility component that is encased in concrete or other similarly hard material and is adequately wet whenever exposed during demolition
- RACM that was not accessible for testing and was, therefore, not discovered until after demolition began and, as a result of the demolition, cannot be safely removed. If not removed for safety reasons, all exposed RACM and any asbestos-contaminated debris must be treated as regulated asbestos-containing waste material. Category I and Category II non-friable mastic, glue, and adhesive ACM that is not friable or in poor condition, and where the probability is low that the materials will become crumbled, pulverized, or reduced to powder during demolition operations.
- Category I and Category II non-friable mastic, glue, and adhesive ACM that is not friable
 or in poor condition, and where the probability is low that the materials will become
 crumbled, pulverized, or reduced to powder during demolition operations.

The facility owner and the renovation or demolition contractor are both responsible for ensuring compliance with these regulations.

Building Inspections

Before a facility or a portion of a facility is renovated or demolished, the owner/operator of the facility or renovation or demolition activity must ensure that the facility or portion of the facility being renovated or demolished has been thoroughly inspected for the presence of asbestos. The inspection must be performed by a person who has been trained and licensed as an Asbestos Building Inspector or management planner in accordance with State training and licensing requirements.

The inspector must identify, quantify, and assess the condition of all suspect asbestos-containing material, either friable or non-friable, on interior and exterior portions of the facility. The inspector must also comply with the procedures specified in Regulation 61-86.1 VI D. In addition, the inspector is required to prepare a written report detailing the findings of the inspection. At a minimum, the report must include information required in Regulation 61-86.1 VI C. A legible copy of the building inspection report must be provided to the Department prior to each demolition, and upon request for renovations. (Note: "BUILDING INSPECTIONS "can be consulted for a detailed explanation of the aforementioned sampling and reporting protocols.)

A building inspection will only be acceptable if performed **within three years** prior to the demolition or renovation. If an inspection report is more than three years old, then it must be confirmed and verified by a licensed Asbestos Building Inspector or Management Planner.

Friable Asbestos Containing Materials

If friable asbestos-containing materials (e.g., pipe insulation) are present, they must be removed prior to being disturbed during renovation or demolition activities. Removal (abatement) must be performed by trained, licensed persons using procedures detailed in State and Federal regulations.

A project design must be prepared for each asbestos abatement project involving the abatement of greater than 3,000 square feet, 1,500 linear feet and/or 656 cubic feet of RACM in a facility to be reoccupied. Such designs must be prepared by a person licensed by DHEC as an Asbestos Project Designer.

Non-Friable Asbestos Containing Materials

Please note that when it can reasonably be expected that non-friable materials will become friable during removal, that these materials must be considered friable from the beginning. If non-friable Asbestos Containing Materials (ACM) becomes friable during an abatement project, the removal becomes subject to the same requirements as friable materials, including training, licensing, notification, and work practices.

- Material should always be lowered to the ground carefully. Throwing or dropping non-friable ACM to the ground or into a truck will cause the material to become friable.
- Materials should be kept wet or misted with water during removal to minimize potential fiber release. **NOTE: The use of water is only a control measure and by no means prevents a material from becoming friable.**
- Once removed, materials may be placed in 6-mil polyethylene bags or drums or wrapped with 6-mil polyethylene sheeting. Additional water may be added to ensure thorough wetting, but do not add so much that the bag or wrapping breaks when lifted.
- Debris already on the ground should be wet and either collected manually or gathered with a shovel and bagged for disposal. These materials can be potential sources of airborne asbestos fiber releases.
- South Carolina Regulation 61-86.1 requires that containers (bags, drums, wrapped components) holding asbestos waste must be labeled with the following: **DANGER** -

CONTAINS ASBESTOS FIBERS - AVOID CREATING DUST - CANCER AND LUNG DISEASE HAZARD.

- Materials should be taken to a landfill as soon as possible but may be stored temporarily
 in a <u>secure</u> area subject to Departmental approval. Transport the materials so as to
 prevent them from leaking, spilling, or blowing off the vehicle.
- You should contact the landfill directly to make sure it will accept the material. You must obtain written approval from DHEC in advance for the disposal. You can get this approval by writing to the following address:

South Carolina Department of Health and Environmental Control Attn: Bureau of Air Quality/Asbestos Section 2600 Bull Street Columbia, SC 29201

Be sure to include the following:

- 1. the address where the material is to be removed;
- 2. a brief description of the content (cement-like tiles, asphaltic shingles, etc.);
- 3. the volume of waste in cubic yards or the area in square feet of material removed, and;
- 4. the name and location of the landfill which has agreed to accept the waste.

Please remember to include your name, return address, and phone number.

 DO NOT BURN OR RECYCLE any asbestos-containing or asbestos-contaminated materials.

The Occupational Safety and Health Administration (OSHA) has rules for workers affected by asbestos-containing materials. These rules must be complied with by all contractors and facility owners and include specific work practices, respiratory protection, and asbestos training requirements, **even for activities involving only non-friable asbestos-containing materials.** Contact the Department of Labor at (803) 896-7665 for details.

Notification of Renovations & Demolitions

Prior to removing regulated asbestos-containing materials, <u>written notification</u> must be submitted to DHEC (up to 10 working days in advance, depending on the amount of asbestos to be removed). The notification must include certain required items of information about the owner, the contractor, the facility, and the asbestos removal project. Required fees must be submitted along with the notification. You must obtain a permit from the Department prior to the renovation activity.

Prior to the demolition of any regulated facility, <u>written notification</u> must be submitted to DHEC at least 10 working days in advance **even if a building inspector determines that asbestos is not present at the facility.** The notification must include certain required items of information about the owner, the contractor, the facility, and the demolition project. Required fees and a copy of the building inspector's report must be submitted along with the notification of demolition. You must obtain a permit from the Department prior to the demolition activity.

Disposal

Never burn any asbestos-containing waste material.

Non-asbestos-containing demolition debris and debris which contains only non-regulated roofing or flooring may be disposed of at a DHEC-approved disposal site for cellulosic or inert waste. Waste consolidation activities involving grinding, cutting, or compacting of non-friable asbestos-containing materials will subject these materials to more stringent State and Federal asbestos disposal regulations.

Regulated asbestos waste must be handled by properly licensed asbestos abatement personnel and disposed of at a landfill permitted to accept regulated asbestos waste. A list of approved landfills may be obtained from the Asbestos Section.

Building Inspection Report Directions

As required by the National Emission Standard for Hazardous Air Pollutants (NESHAP) and Regulation 61-86.1, an owner/operator shall ensure that a building inspection, to detect the presence of asbestos-containing material (ACM), has been performed prior to any renovation or demolition activity at a regulated facility.

Under Regulation 61-86.1, Section VI.A.6., an inspection cannot have been performed more than three years prior to a renovation or demolition activity. If more than three years have elapsed since the most recent inspection, the previous inspection shall be confirmed and verified by a licensed building inspector and/or management planner.

Regulation 61-86.1 requires that all inspections be performed by persons trained and licensed as either a building inspector and/or management planner. In order to be licensed in these disciplines, persons must have successfully completed a DHEC approved initial training course specific to inspecting for ACM in a building and/or a course specific to management planning for ACM in a building. Persons must also have taken and passed an examination at the end of the course with a score of 70 percent or above.

In performing inspections, Regulation 61-86.1 requires that a building inspector and/or management planner comply with the requirements of Section VI, Asbestos Building Inspection Requirements. An inspection shall include samples from suspect friable and non-friable ACM on interior and exterior portions of a facility or its facility components.

In performing inspections, Regulation 61-86.1 requires that a building inspector and/or management planner follow specific sampling procedures. According to Section IV.B.3.a of the regulation, a building inspector and/or management planner shall comply with the procedures specified in **40 CFR 763.86** in determining sampling locations and the number of representative samples to be collected. An inspection shall include samples from suspect friable and non-friable ACM on interior and exterior portions of a facility or its facility components.

Under 40 CFR Part 763.86, suspect ACM are divided into three categories: surfacing materials, thermal system insulation (commonly referred to as TSI), and miscellaneous materials.

Regulation 61-86.1, Section VI contains sampling procedures specific to each category of material.

<u>Surfacing material</u> includes, but is not limited to, joint compound, plaster, and painted, troweled on, or spray-applied textured material. To remain in compliance with Regulation 61-86.1, surfacing materials on exterior and interior portions of a facility shall be sampled according to procedures outlined in Regulation 61-86.1, Section VI.D.1. (a)-(c):

- A licensed asbestos inspector shall collect, in a statistically random manner, a minimum of three bulk samples from each homogeneous area of any surfacing that is not assumed to be ACM, and shall collect the samples as follows:
 - At least three bulk samples shall be collected from each homogeneous area that is 1,000 or fewer square feet (sf) or linear feet (Lf) in size.
 - o At least five bulk samples shall be collected from each homogeneous area that is greater than 1,000 but fewer than or equal to 5,000 sf or Lf.
 - o At least seven bulk samples shall be collected from each homogeneous area that is greater than 5,000 sf or Lf.

Thermal System Insulation (TSI) is any material that is applied to pipes, fittings, boilers, breeching, tanks, ducts, or other facility components for the purpose of preventing heat loss or gain, water condensation, or for other purposes. **Miscellaneous Material** is any material that is not considered a surfacing material or thermal system insulation and includes, but is not limited to, flooring, roofing, mastics, gaskets, cementitious materials, caulkings, ceiling tiles, fire doors, wall boards, and flexible duct connections. To remain in compliance with Regulation 61-86.1, TSI and miscellaneous materials on exterior and interior portions of a facility shall be sampled in accordance with procedures outlined in Regulation 61-86.1, Section VI.D.2:

- A licensed asbestos inspector shall collect, in a statistically random manner, at least three bulk samples from each homogeneous area of TSI and any miscellaneous material that is not assumed to be ACM.
- In accordance with ASTM E2356, and any subsequent amendments and editions, negative results for non-friable organically bound material (NOB) shall be verified with at least one TEM analysis.
- NOBs include flooring, roofing, mastics, adhesives, caulks, and glazing.
- If an accredited inspector has determined the thermal system insulation to be fiberglass, foam glass, rubber, or other non-suspect material, then bulk samples are not required.

Regulation 61-86.1, Section VI.C requires that a building inspector and/or management planner prepare a written asbestos building inspection report to include the following:

- A title page denoting:
 - 1. The client's name, company, address, and telephone number, and the name and exact location of the facility inspected;
 - 2. the date the inspection was performed;
 - 3. the date the inspection report was written; and
 - 4. the printed name and telephone number of the inspector(s), and his or her affiliated company name, address, and telephone number.

- A cover letter to the building owner or owner's representative that describes the purpose of the inspection; a general synopsis of the inspection and results; and the name, title, and signature of the inspector(s) and report writer, if different.
- A detailed narrative of the physical description of the building or part of the building affected by the renovation or demolition operation that includes:
 - 1. The square footage of the building or part of the building affected by the renovation or demolition operation;
 - 2. The building materials used in the construction of the exterior, roof, interior, and basement or crawlspace of the building affected by the demolition or affected by the renovation materials operation;
 - 3. An estimated or exact quantity (square or linear feet) for all suspect materials whether sampled for or assumed to be asbestos that may be affected by the renovation or demolition operation;
 - 4. Also include a description of non-suspect materials excluding: glass, metals, kiln brick, cement, fiberglass, concrete, pressed wood, cinder block, and rubber.
- An executive summary that details:
 - 1. The type of suspect ACM (e.g., TSI, floor tile, mastic), total square or linear footage, and the total number of samples collected for each separate homogenous area affected by the renovation or demolition operation;
 - 2. The date of the inspection, type, condition, quantity, sample results, and exact location of ACM positively identified or assumed to be ACM in the part of the building affected by the renovation or demolition operation;
 - 3. A list of the homogeneous areas identified;
 - 4. Whether the material is accessible for the building or part of the building affected by the renovation or demolition operation; and (5) The material's potential for disturbance for the building or part of the building affected by the renovation or demolition operation.
- For renovation and demolition operations, the inspector's determination that ACM is friable or non-friable.
- Except when suspect ACM materials are assumed to be asbestos, include a complete, clear, legible copy of all laboratory bulk sample results.
- Clear, legible drawings and/or photographs to clarify the scope of the renovation or demolition operation. Illustrate the exact location of each sample collected. For facilities that involve a trade secret or confidential component or an affected area process, a request for a variance may be submitted.
- The printed name and signature of each accredited inspector who collected the samples, and a clear legible copy of his or her DHEC issued asbestos building inspector or management planner license.

Things to Note:

- At no time will negative assumptions about a suspect material's content be acceptable. There are only two acceptable options:
 - 1. Positive assumptions of suspect materials or
 - 2. Sampling of suspect materials per the procedures specified in 40 CFR 763.86
- A homogenous area is considered not to contain ACM only if the results of all samples required to be collected from the area are one percent or less.
- Bulk samples shall not be composited for analysis.

- In a multi-unit building, each separate room in each part of the building or areas affected by the renovation or demolition operation shall be inspected to confirm and quantify ACM homogeneous areas for sampling purposes.
- DHEC will not accept an asbestos building inspection or written report for any structure from an employee of an abatement company also involved in the removal of asbestoscontaining materials from that structure, unless the licensed inspector is an employee of an entity regulated under Regulation 61-86.1, Section XX, Industrial Manufacturing and Electrical Generation Facilities.
- An asbestos building inspector shall not participate in the analysis of the bulk samples he
 or she has collected.
- Destructive sampling techniques shall be utilized.
- Material Safety Data Sheets (MSDS), statements from the manufacturer, and architecture signoff will not be accepted as proof that a building product contains no asbestos, except in cases where the owner can verify the direct correlation of the building product to the MSDS, statements from the manufacturer, and/or architecture signoff documents. DHEC reserves the right to reject documentation that it deems unacceptable.

Appendix M

Abatement Project Forms





ASBESTOS ABATEMENT PROJECT LICENSE APPLICATION

BUREAU OF AIR QUALITY • ASBESTOS SECTION • 2600 BULL STREET • COLUMBIA • SC • 29201

TYPE OF OPERATION: ☐ Standard Removal ☐ Emergency Removal ☐ Enclosure ☐ Encapsulation ☐ Cleanup ☐ Disposal

FOR OFFICE USE Postmark/Received:	Original □ / Revised □ / Cancellation □ (check one	Project License I.D. (For Rev	visions/Cancellations):
I. FACILITY OWNER:			
MAILING ADDRESS:			
CITY:	STATE:	ZIP:	
CONTACT PERSON:			
II. REMOVAL CONTRACTOR:			
MAILING ADDRESS:			
CITY:	STATE:	ZIP:	
CONTACT PERSON:		PHONE: ()
E-MAIL ADDRESS:		E-MAIL PERMIT 🗆	OR MAIL PERMIT
FEDERAL I.D. NUMBER:			
DHEC CONTRACTOR LICENSE NO. (If applicable			
III. FACILITY NAME:			
STREET ADDRESS:			
CITY:	STATE:	COUNTY:	
SITE (ROOM, FLOOR, WING, UNIT, MACHINE, ET	C.):		
BUILDING SIZE:	NO. OF FLOORS:	AGE IN YEARS: ———	
PRESENT USE:F	PRIOR USE:	FUTURE USE:	
IV. PROCEDURES, INCLUDING ANALYTICAL ME	THOD IF APPROPRIATE, USED TO DETECT THE	PRESENCE OF ASBESTOS	MATERIAL:
FACILITY OR FACILITY COMPONENT SURVEYED	BY (INSPECTOR NAME):		
COMPANY:		PHONE: ()	
DHEC LICENSE NUMBER:		EXPIRATION DATE:	
V. PROJECT DESIGN PERFORMED BY (IF APPLI	CABLE):		
COMPANY:		PHONE: ()	
DHEC LICENSE NUMBER:		EXPIRATION DATE:	
VI. ASBESTOS-CONTAINING MATERIALS (ACM)	TO BE REMOVED ONLY:		
TYPE (TSI, SURFACING, FLOORING, ROOFING, ETC.)	AMOUNT (SQUARE FEET, LINEAR FEET,	CUBIC FEET) CONI	DITION (CIRCLE ONE)
		□ FRIA	ABLE NON-FRIABLE
		□ FRIA	ABLE NON-FRIABLE
		□ FRI	ABLE NON-FRIABLE
		□ FRI/	ABLE NON-FRIABLE
VIII COUEDINED DATES OF DEMOVAL. STADT	DATE: COMPLETI	ON DATE:	
VII. SCHEDULED DATES OF REMOVAL: START I			
WORK DAYS:	WORK HOU	JRS:	
APPLICATIONS MUST BE SUBMITTED WITH		FOR FRIABLE ASBESTO	S-CONTAINING
PRIOR TO THE SCHEDULED START DATE A		MIADE EOOT OD I INEAD	FOOT
NESHAP PROJECTS: 10 WORKING DAYS SMALL PROJECTS: 4 WORKING DAYS	MINIMUM FEE O	QUARE FOOT OR LINEAR F \$25.00	TOOT
MINOR PROJECTS: 2 WORKING DAYS	MAXIMUM FEE O		

For additional information concerning regulatory requirements call or visit our Web site at http://www.scdhec.gov/environment/baq/asbestos.aspx

Non-Friable (NESAP-sized) Projects: 4 working days. No fee for non-friable ACM.

VIII. DESCRIPTION OF PLANN	NED ABATEMENT WORK & METHOD(S) TO BE USE	D:	
IX. DESCRIPTION OF WORK PR	RACTICES & ENGINEERING CONTROLS TO BE USED	O PREVENT EMISSIONS OF ASBESTOS	AT THE RENOVATION SITE:
Y WASTE TRANSPORTER #1	1:		
	1.		
	STATE:		
	STATE:		
	OTATE.		
CONTACT FERSON.		FIIONE. (
XI. WASTE DISPOSAL SITE: _			
MAILING ADDRESS:			
CITY:	STATE:	ZIP:	
CONTACT PERSON:		PHONE: ()
TEMPORARY ASBESTOS STO	DRAGE CONTAINMENT AREA LICENSE NUMBER (IF	APPLICAB <u>LE):</u>	
XII. DESCRIPTION OF EMERO	GENCY REMOVAL (PLEASE ATTACH A LETTER FROM TH	E FACILITY OWNER EXPLAINING THE NATUR	E OF THE EMERGENCY)
DATE & HOUR OF EMERGEN	CY (MM/DD/YY):		
DESCRIPTION OF SUDDEN, U	JNEXPECTED EVENT:		
EXPLANATION OF HOW THE EVEN	NT CAUSED UNSAFE CONDITIONS AND/OR WOULD CAUS	EQUIPMENT DAMAGE AND/OR AN UNREAS	ONABLE FINANCIAL BURDEN:
	EDURES TO BE FOLLOWED IN THE EVENT THAT U ECOMES CRUMBLED, PULVERIZED OR REDUCED '		PREVIOUSLY NON-FRIA-
	,		
VIV. 1050T/FV/T/14T 141/1/DIV/ID			
	UAL TRAINED IN THE PROVISIONS OF REGULATION (40 C		
	IRED TRAINING HAS BEEN ACCOMPLISHED BY THIS PER		JURING NORMAL BUSINESS
	IRED TRAINING HAS BEEN ACCOMPLISHED BY THIS PER	1	JURING NORMAL BUSINESS
(SIGNATURI	E OF OWNER/OPERATOR)	//	JURING NURMAL BUSINESS
(SIGNATURE XIV. I CERTIFY THAT THE ABOVE	E OF OWNER/OPERATOR)		JURING NORMAL BUSINESS
•	E OF OWNER/OPERATOR)		URING NORMAL BUSINESS



DEMOLITION LICENSE APPLICATION

BUREAU OF AIR QUALITY • ASBESTOS SECTION • 2600 BULL STREET • COLUMBIA • SC • 29201

TYPE OF OPERATION: ☐ Total Demolition ☐ Partial Demolition ☐ Ordered Demolition

FOR OFFICE USE Postmark/Received:	Original/Revis	ed/Cancellation (circle one)	Project License I.D. (For Revisions/Cancellations):	
I. FACILITY OWNER:				_
				_
CITY:		STATE:	ZIP:	_
CONTACT PERSON:			PHONE: ()	_
II. IS ASBESTOS PRESENT IN THE FACILITY?:				
III. DEMOLITION CONTRACTOR:			FEDERAL ID NO.:	_
MAILING ADDRESS:				_
CITY:		STATE:	ZIP:	
CONTACT PERSON:			PHONE: ()	_
E-MAIL ADDRESS:			E-MAIL PERMIT OR MAIL PERMIT	l
FEDERAL I.D. NUMBER:				
ASBESTOS REMOVAL CONTRACTOR (If applicab	le):			_
MAILING ADDRESS:				_
CITY:		STATE:	ZIP:	
CONTACT PERSON:			PHONE: ()	-
IV. FACILITY NAME:				_
STREET ADDRESS:				_
CITY:		STATE:	COUNTY:	_
SITE (ROOM, FLOOR, WING, UNIT, MACHINE, ET	C.):			_
BUILDING SIZE:N	NO. OF FLOORS: _		AGE IN YEARS:	_
PRESENT USE:F	PRIOR USE:		FUTURE USE:	-
V. PROCEDURES, INCLUDING ANALYTICAL MET	HOD IF APPROPR	IATE, USED TO DETECT TH	HE PRESENCE OF ASBESTOS MATERIAL:	
FACILITY OR FACILITY COMPONENT SURVEYED	BY (INSPECTOR	NAME):		_
COMPANY:			PHONE: ()	-
DHEC LICENSE NUMBER:			EXPIRATION DATE:	-
VI. NON-FRIABLE MASTIC, GLUE, AND ADHESIV	E ASBESTOS-CON	ITAINING MATERIALS REM	AINING IN PLACE DURING DEMOLITION (IF APPLICABLE)	:
TYPE (MASTIC, GLUE, AND ADI	HESIVE)		AMOUNT (SQUARE FEET)	_
				_
VII. SCHEDULED DATES OF DEMOLITION (YOU	MUST SPECIFY DA	TES):		_
START DATE:		COMPL	ETION DATE:	_
WORK DAYS:		WORK I	HOURS:	_
Applications must be mailed along with	o ¢50 00 foo (no	rable to SCDUEC) at lea	ot 10 working days prior to the schoduled	_

- Applications must be mailed along with a \$50.00 fee (payable to SCDHEC) at least 10 working days prior to the scheduled start date. Faxes will not be accepted.
- · A copy of an asbestos survey report (no older than 3 years) must accompany the application.

For additional information concerning regulatory requirements call or visit our Web site at http://www.scdhec.gov/environment/baq/asbestos.aspx

VIII. DESCRIPTION OF □ BULLDOZER	PLANNED DEMOLITION N	METHOD(S) TO BE USED:	□ MANUAL	□ BURNING	☐ IMPLOSION/EXPLOSION
IF OTHER PLEASE DES	-	LI WRECKING BALL	LI MANUAL	LI BURINING	LI INIPLOSION/EXPLOSION
IV DECODIDITION OF W		EEDING CONTROL S TO BE	LICED TO DDEVENT	TAILOCIONIC OF ACRE	CTOC AT THE DEMONITION CITE.
IX. DESCRIPTION OF WO	JRK PRACTICES & ENGINE	EERING CONTROLS TO BE	USED TO PREVENTE	EMISSIONS OF ASBES	STOS AT THE DEMOLITION SITE:
V MARTE TRANSPORT					
		CTATE			ZIP:
CONTACT PERSON:					()
WASTE TRANSPORTER					
MAILING ADDRESS:					
				Z	ZIP:
					()
					·
					ZIP:
CONTACT PERSON:				_ PHONE:	()
XII. IF DEMOLITION OR	DERED BY GOVERNMENT	TAGENCY, PLEASE IDENT	TIFY THE AGENCY BE	ELOW: (PLEASE ATT	ACH A COPY OF THE ORDER)
NAME:			TITLE:		
AUTHORITY:					
DATE OF ORDER (MM/D)D/YY):	DATE O	RDERED TO BEGIN((MM/DD/YY):	
		LLOWED IN THE EVENT TH .ED, PULVERIZED, OR RED			OR PREVIOUSLY NONFRI-
ABLE ASBESTOS MATE	RIAL BECOIVES CROIVIBL	.ED, POLVERIZED, OR REL	DOCED TO FOWDER	-	
NO. () 0 = 0 = 1 = 1					
THE DEMOLITION INVO	LVING RACM AND EVIDE	NCE THAT THE REQUIRE			I) WILL BE ON-SITE DURING BY THIS PERSON WILL BE
AVAILABLE FOR INSPE	CTION DURING NORMAL	BUSINESS HOURS.			
(CICA	NATURE OF OWNER/OREDAT	TOD)		/ _(DATE)	
	NATURE OF OWNER/OPERAT E ABOVE INFORMATION I			(DATE)	
		-			
(SIGN	NATURE OF OWNER/OPERAT	ŌR)		/	
			SCDHEC) at least	,	prior to the scheduled

- Applications must be mailed along with a \$50.00 fee (payable to SCDHEC) at least 10 working days prior to the scheduled start date. Faxes will not be accepted.
- A copy of an asbestos survey report (no older than 3 years) must accompany the application.

For additional information concerning regulatory requirements call or visit our Web site at http://www.scdhec.gov/environment/baq/asbestos.aspx



Asbestos Waste Shipment Record

1.	SCDHEC ASBESTOS ABATEMENT PROJECT	LICE	NSE:		
Ge	nerator Information				
2.	Waste Generator/Owner Name & Address:	Work	Site Name & Physical Address:	Waste G Number ()	Generator/Owner Telephone
3.	Abatement Contractor Name & Address:	l		Abateme Number	ent Contractor Telephone
4.	Name of waste disposal site (WDS), mailing addr physical site location:	ess, ar	nd	WDS Te	elephone Number:)
5.	Description of Waste Materials (please circle): Friable (Regulated) / Nonfriable (Nonregulated)		6. Bags of Containers: No. Type Drums Bags Bulk Load	7. Total m3	Quantity: (yd3)
8.	Special handling instructions & additional informat	tion:			
9.	Generator's/Contractor's Certification: I hereby de by proper shipping name and are classified, pack transport by highway according to applicable inter-	ed, ma	rked and labeled. The contents are in all		
	Print Name:		Signature:		Date:
Tra	nsporter Information (Acknowledgment of Receip	ot of Ma	aterials):		
10.	Name, title, address, telephone number:		Signature:		Date:
11.	Name, title, address, telephone number:		Signature:		Date:
Dis	posal Site Operator				
12.	Discrepancy:		Bags or Containers	Total Qu	uantity
13.	Waste Disposal Site Owner or Operator certification as noted in item 11.	ion of r	eceipt of asbestos materials covered by	this mani	ifest except
	Print Name:		Signature:		Date:
	Please forward a completed copy of this record to: SO	CDHEC	s, Bureau of Air Quality, Asbestos Section, 26	00 Bull Str	eet, Columbia, SC 29201

(803) 898-4389 office. (803) 898-4281 fax.



LEAD-BASED PAINT INVESTIGATION REPORT

UNIVERSITY OF SOUTH CAROLINA FORMER SCE&G COMPOUND MAIN 2-STORY BUILDING (BUILDING 1) 1206 FLORA STREET COLUMBIA, SOUTH CAROLINA

PREPARED FOR:



Mr. Christopher Geary University of South Carolina 1300 Pickens Street Columbia, South Carolina 29201

PREPARED BY:

F&ME Consultants 1825 Blanding Street Columbia, South Carolina 29201

April 4, 2018

F&ME Project No.: E5700.190

TABLE OF CONTENTS

1.	Executive Summary	1
2.	Lead-Based Paint Background Information	3
3.	Introduction	3
4.	Investigation Results	4
5.	Recommendations	5
Арр	oendices	7
	Appendix A – Site Vicinity Map	
	Appendix B – General Building Plans	
	Appendix C – XRF Data	
	Appendix D – Site Photographs of Lead Positive Items	
	Appendix E – Personnel Certifications	

1. EXECUTIVE SUMMARY

This executive summary is intended as an overview for the convenience of the reader. This report should be reviewed in its entirety prior to making any decisions regarding this project.

F&ME Consultants has completed a Lead-Based Paint (LBP) Investigation of multiple structures associated with the former SCE&G Compound (Site) located at 1206 Flora Street in Columbia, SC for the University of South Carolina (USC). This report is for the investigation of the main 2-story former mill structure (Building 1) found on the compound that fronts Flora Street. This LBP Investigation was performed on March 13th through March 15, 2018 in anticipation of planned renovation activities to both the interior and exterior of the building. Appendix A – Site Vicinity Map is provided to show the location of Building 1. Appendix B – General Building Plans, are provided to show the building lay-out and locations of XRF scans taken throughout the building.

Per an agreed upon scope of work, this LBP Investigation was conducted to identify, analyze, and assess the condition of any LBP or coated interior and exterior building components along with the roof which may be affected by renovation activities. Additionally, F&ME agreed to make recommendations regarding proper handling and/or disposal methods if any LBP or coatings were identified. This investigation includes both a visual evaluation of the physical condition of painted materials as well as quantitative testing of random surfaces using a Thermo Scientific Niton X-Ray Fluorescence (XRF) Portable Analyzer. The XRF documents the concentration of lead, if any, in the overall paint or coating. Building components were scanned with a Niton XRF analyzer (Model #XLp 300A, Serial #18185) with a limit of detection (LOD) of 0.01 mg/cm².

LBP is regulated by multiple government agencies, and each requires different response actions when the concentration of lead exceeds specified thresholds. The Occupational Safety and Health Administration (OSHA) regulates worker exposure to lead dust, and as a result considers materials with any lead content to be a potential hazard. Additionally, South Carolina Department of Health and Environmental Control (SCDHEC) requires some waste materials to be disposed of at specific disposal facilities which are able to manage this waste. Appendix C – XRF Data, is provided to present the data in a user-friendly format. Items in red text contain lead in concentrations regulated by SCDHEC and these materials must be addressed upon disposal. Items in blue and red text contain lead in concentrations that must be considered a potential for worker exposure by OSHA.

The results from the XRF quantitative testing indicate that lead is present in paint and/or coatings on building components associated with the subject structure. The components found to equal or exceed the threshold for lead (0.7 mg/cm²) include the following:

- Paint on interior brick and plaster walls
- Paint on interior wood columns throughout the first and second floors
- Metal cap plate supports for wood columns throughout the first and second floors
- Yellow painted metal shelving first-floor main warehouse area (Room 100)
- Yellow striping paint on concrete floor first-floor main warehouse area (Room 100)



- Tan ceramic baseboard tiles bathrooms and janitor closet
- Tan ceramic wall tile in shower Room 238A
- Grey painted exterior metal staircase west side of the building
- Yellow painted metal dock edge protector rear loading dock
- Yellow painted metal security bars on exterior window Room 102B
- Yellow painted hoist/crane laydown yard on west side of the building

We appreciate the opportunity to assist you in this project. If you have any questions or require additional information, please feel free to contact our office at (803) 254-4540.

Sincerely,

F&ME CONSULTANTS

Jeffrey S. Leary

S.C. Lead-Based Paint Inspector

Jeffrey S. Leary

EPA Certification No. SC-I-18721-3 (Exp. 07/29/18)

Glynn M. Ellen

Environmental Department Manager

2. LEAD-BASED PAINT BACKGROUND INFORMATION

Housing and Urban Development (HUD) defines "LBP" as any coating that has a lead concentration of 1.0 milligrams of lead per square centimeter (1.0 mg/cm²) or greater, or if the lead concentration is greater than one half of a percent (> 0.5%) by weight. The Consumer Product Safety Commission (CPSC) currently considers paint to be lead-containing if the concentration of lead exceeds 90 ppm (0.009% by weight). In 1978, the CPSC banned the sale of LBP to consumers, and banned its application in areas where consumers have direct access to painted surfaces. Both the CPSC and HUD definitions of lead-containing paint are aimed at protecting the general population from exposure to lead in the residential setting.

In contrast, the mission of OSHA with respect to lead-containing paint is to protect workers during construction activities that may generate elevated airborne lead concentrations. OSHA states that construction work (including renovation, maintenance, and demolition) carried-out on structures coated with paint having lead concentrations lower than the HUD or CPSC can still result in airborne lead concentrations in excess of regulatory limits. For this reason, OSHA has not defined lead-containing paint, but states that paint having any measurable level of lead (≥ 0.01 mg/cm²) may pose a substantial exposure hazard during construction work, depending upon the work performed. Therefore, in these situations, OSHA guidelines and safety procedures should be followed. By OSHA standards and regulations, the employer shall ensure that no employee is exposed to lead at concentrations greater than fifty micrograms per cubic meter of air (50 ug/m³) averaged over an 8-hour period.

Additionally, SCDHEC requires the use of specific waste disposal sites if materials contain lead concentrations greater than or equal to (\ge) 0.7 mg/cm². It is imperative that these regulations be considered if any present or future renovations and/or demolition activities will impact LBP-containing building materials or equipment. Due to the anticipated impact on the building's components from the planned renovation activities, SCDHEC lead disposal requirements were used as the threshold for this Investigation.

3. INTRODUCTION

It is F&ME's understanding that renovations are in the planning stages for Building 1, and currently the scope of the renovations is undefined. It is also our understanding that the renovations will likely impact the entire structure, will impact both the interior and exterior of the building, and will potentially include the replacement of the existing roof system. This LBP Investigation was conducted to identify, analyze, and assess the condition of any LBP or coated interior and exterior building components, including the roof, that may be affected by renovation activities. Where LBP or coatings have been identified, recommendations regarding proper handling and/or disposal methods are provided.

The existing building structure, Building 1, is an approximate 65,000 square foot, 2-story structure located at 1206 Flora Street, in Columbia SC. The structure was originally the location for the Capital City Mills and in recent years was owned and operated by SCE&G. USC took possession of the property in March of 2018. The original building construction is believed to have occurred near the turn of the century. A historic document found online indicated Capital City Mills being incorporated in 1900.

Building 1 is a 2-story structure originally constructed with masonry brick and concrete,



Photo 1. University of South Carolina, former SCE&G Compound, Main Building (Building 1) located at 1206 Flora Street, Columbia SC.

with wood columns and beams throughout. There have been alterations or renovations made to the structure over its history that include more current construction. Two (2) all metal additions were noted during the investigation on the northwest and southwest corners of the building. It appeared that an earlier renovation included the addition of the stairwells at the front entrance and northwest corner of the building. The stairwells were added before the metal addition on the northwest corner of the building. It also appears that the entire second floor was renovated, and all new finishes were installed at some point in time. Based on the condition of the building materials, the two (2) areas with offices found on the first-floor level were likely renovated earlier than the renovations on the second floor of the building. The roof system for the main structure consists of a commercial TPO membrane roof and flashing. The additions at the northwest and southwest corners have metal roof systems.

The interior spaces of the building consisted of drywall, plaster, wood, masonry block and brick walls, carpet and various 12" x 12" floor tiles over concrete and/or wood flooring, and suspended drop ceiling system. The main warehouse area (Room 100) on the first floor is opened to the underside of the floor of the second-floor level. See Appendix A – Site Vicinity Map, for the location of the structure. See Appendix B –General Building Plans, for a layout of the building.

4. INVESTIGATION RESULTS

F&ME's LBP Investigation sampling protocol consisted of randomly selecting interior and exterior building components and scanning these components with a Thermo Scientific Niton X-Ray Fluorescence (XRF) Portable Analyzer (Model XLp300A, Serial #18185, Isotope 1: Cd109, 40mCi, source date 09/01/2015). The components scanned with the XRF include the following: walls, ceilings, columns, beams, doors and door components, windows and window components, flooring,



baseboards, porcelain sinks, toilets, and urinals, piping, staircasing and components, floor striping, roof components, etc.

The XRF results indicate that LBP is present within the subject building structure. The components found to contain LBP include the following:

- Paint on interior brick and plaster walls
- Paint on interior wood columns throughout the first and second floors
- Metal cap plate supports for wood columns throughout the first and second floors
- Yellow painted metal shelving first-floor main warehouse area (Room 100)
- Yellow striping paint on concrete floor first-floor main warehouse area (Room 100)
- Tan ceramic baseboard tiles bathrooms and janitor closet
- Tan ceramic wall tile in shower Room 238A
- Grey painted exterior metal staircase west side of the building
- Yellow painted metal dock edge protector rear loading dock
- Yellow painted metal security bars on exterior window Room 102B
- Yellow painted hoist/crane laydown yard on west side of the building

For more information regarding the specific descriptions and locations of the items that were scanned, refer to the Appendix C – XRF Data. Also, Appendix D – Site Photographs, shows the materials that were found to be coated or painted with LBP greater than or equal to (\ge) 0.7 mg/cm². Appendix E - Personnel Certification, is included to show F&ME qualifications with regards to LBP Investigations.

5. RECOMMENDATIONS

The results, conclusions and recommendations from this investigation are representative of the conditions observed at the site on the dates of the field inspection. F&ME does not assume responsibility for any changes in conditions or circumstances that occur after the inspection. This report has been prepared exclusively for USC and shall not be disseminated in whole or part to other parties without prior consent from USC or F&ME Consultants, Inc. No other environmental issues were addressed as part of this report.

LBP was identified in concentrations above both SCDHEC and OSHA limits on building materials listed in *Section 4. Investigation Results*. It is important to ensure that the debris generated from the renovation activities is handled and disposed of appropriately. The proper handling and disposal procedures depend on the type of substrate (e.g., metal, wood, masonry block, etc.). In order to reduce and/or eliminate the generation of lead-containing dust, and residue, it is recommended that cutting, sanding and grinding be kept to a minimum, and to the extent practicable, the substrate materials should be removed intact. Metal components painted with and/or containing lead, such as the grey painted exterior staircase or the yellow painted loading dock edge protectors may be recycled, if they are taken to a recycling facility that accepts lead painted and/or lead-containing material.



During this investigation, paint chips from the brick and plaster interior walls that tested positive for lead were noted on the concrete floor along the perimeter walls of the first-floor main warehouse area (Room 100). During renovation activities, these paint chips need to be collected following OSHA regulations and procedures along with USC protocol for handling lead-based paint items and debris/paint chips. Once the paints chips are collected and containerized, lab analysis should be performed to determine the proper disposal method.

Components found to contain lead should be handled appropriately. It is recommended that work tasks which require grinding, sanding, cutting torch, or other disturbance of the LBP surfaces identified herein be performed in accordance with federal regulations pertaining to worker protection from exposure to LBP. When lead containing items are disturbed or begin to decay they become a concern with regard to human health and the environmental. The typical routes of exposure to lead are through the inhalation or ingestion of lead-contaminated materials. Minimal risk of exposure exists where the lead-containing paint and coating are intact (e.g., has not been aerosolized, free of chipping or flaking, etc.).

As stated previously, OSHA regulates any measurable level of lead ($\geq 0.01 \text{ mg/cm}^2$), as it may pose a substantial exposure hazard to workers. Therefore, in these situations, OSHA regulations and safety procedures should be followed. These regulations also list the proper personal protective equipment to be used by the workers disturbing the LBP items and the requirements for personal air monitoring. OSHA's exposure action level (AL) for lead, regardless of respirator use, is an airborne concentration of $30\mu\text{g/cm}^3$, averaged over an eight-hour period. The action level (AL) is the level at which an employer must begin specific compliance activities as outlined in OSHA's lead standards. By OSHA standards and regulations, the employer shall ensure that no employee is exposed to lead at concentrations greater than fifty micrograms per cubic meter of air ($50 \mu\text{g/m}^3$) averaged over an 8-hour period which is the permissible exposure level (PEL).

SCDHEC regulates the proper disposal of LBP and associated debris. SCDHEC defines two types of LBP debris. The first is LBP *waste*, which is defined as material such as wood, brick and metal that is painted with LBP. The other is LBP *residue* which is defined as residue that is generated from the removal (e.g., scraped, chipped, sandblasted, or chemical) of LBP from a structure. LBP *waste* that comes from a commercial or residential facility may be disposed of in either a class 2 or 3 landfill, while LBP *residue* from a commercial facility must have a toxicity characteristic leaching procedure (TCLP) analysis to determine the lead content. TCLP analysis is used to determine whether or not a waste is a characteristic hazardous waste due to leachability under the South Carolina Hazardous Waste Management Regulations. LBP *residue* with a TCLP analysis result greater than or equal to five milligrams per liter (≥ 5 mg/l) lead must be disposed of in a Subtitle C landfill (Hazardous Waste). However, LBP *residue* from a commercial facility with a TCLP analysis result less than five milligrams per liter (≤ 5 mg/l) lead is required to be disposed of in a Class 3 landfill.

Should any hidden and/or inaccessible components suspected to have LBP be encountered during renovation activities, the contractor performing the work is advised to stop work, follow proper procedures and precautions relating to LBP, and contact F&ME Consultants at (803) 254-4540 for an immediate response action.



APPENDICES

Appendix A – Site Vicinity Map

Appendix B – General Building Plans

Appendix C – XRF Data

Appendix D – Site Photographs of Lead Positive Items

Appendix E – Personnel Certification

Appendix A

Site Vicinity Map






FIGURE NUMBER:

1

F&ME CONSULTANTS PROJECT NUMBER:

E5700.190

Lead-Based Paint Investigation Former SCE&G Complex 1206 Flora Street, Columbia, SC 29201 Appendix A - Site Location Plan

> Prepared for: Facilities Planning and Construction 743 Greene Street Columbia, SC 29208




ORIGINAL:	DRWN. BY: CTC
March 23, 2018	CHKD. BY: JSL
REVISIONS:	APPR. BY: GME
1	
2	NOTES:
3	
SCALE	
As Shown	

Appendix B

General Building Plans






F&ME CONSULTANTS GEOTECHNICAL - ENVIRONMENTAL - IN 3112 Devine Street COLUMBIA, SC 29205

Lead-Based Paint Investigation
Former SCE&G Complex - Main 2-Story Structure
1206 Flora Street, Columbia, SC 29201
Appendix B - General Building Plan
Prepared for:

E5700.190

FIGURE NUMBER:

2



F&ME
CONSULTANTS
GEOTECHNICAL - ENVIRONMENTAL - IN
3112 Devine Street
COLUMBIA, SC 29205

Lead-Based Paint Investigation
Former SCE&G Complex - Main 2-Story Structure
1206 Flora Street, Columbia, SC 29201
Appendix B - General Building Plan
Prepared for:

F&ME CONSULTANTS PROJECT NUMBER: E5700.190

FIGURE NUMBER:

3

Appendix C

XRF Data



Scan No.	Component	Substrate	Side	Condition	Color	Sample Location	PbC mg/cm ²
1		Shu	ıtter Calibra	te			NA
2			Calibrate				0.9
3			Calibrate				0.7
4			Calibrate				1.2
5			Calibrate				0.7
6	Ceiling	Wood	A	Peeling	Cream	200	< LOD
7	Ceiling	Wood	A	Peeling	Cream	200	< LOD
8	Ceiling	Wood	A	Peeling	Cream	200	< LOD
9	Beam	Wood	A	Peeling	Cream	200	< LOD
10	Beam	Wood	A	Peeling	Cream	200	0.14
11	Column	Wood	A	Poor	Cream	200	2.9
12	Wall	Drywall	A	Intact	Blue	200	< LOD
13	Wall	Drywall	С	Intact	Blue	200	< LOD
14	Wall	Drywall	С	Intact	Blue	200	< LOD
15	Wall	Drywall	C	Intact	Wallpaper	221	< LOD
16	Sink	Porcelain	В	Intact	White	221	< LOD
17	Toilet	Porcelain	D	Intact	White	221	< LOD
18	Floor	Ceramic Tile	D	Intact	Grey	221	< LOD
19	Baseboard	Ceramic Tile	В	Intact	Grey	221	< LOD
20	Partition wall	Wood	D	Intact	Grey	221	< LOD
21	Door	Wood	A	Intact	Grey	221	< LOD
22	Door Casing	Metal	A	Intact	Grey	221	< LOD
23	Ceiling Track Urinal	Metal	A	Intact	White	221	< LOD
24 25		Porcelain Wood	C	Intact Intact	White Blue	220 220	< LOD
26	Sink counter Wall	_	A C		Blue	218	< LOD < LOD
27	Win. Sill	Drywall Drywall	C	Intact Intact	Blue	218	< LOD < LOD
28	Win. Casing	Metal	C	Intact	Brown	218	< LOD < LOD
29	Column	Wood	Center	Fair	Tan	218	< LOD
30	Column	Wood	Center	Fair	Tan	218	5.7
31	Column	Wood	Center	Fair	Tan	218	< LOD
32	Column	Wood	Center	Fair	Tan	218	< LOD
33	Column	Wood	Center	Fair	Tan	218	3.7
34	Column	Wood	Center	Fair	Tan	218	3.4
35	Beam	Wood	Center	Fair	Tan	218	< LOD
36	Beam	Wood	Center	Fair	Tan	218	< LOD
37	Column Top Plate	Metal	Center	Poor	Tan	218	11.7
38	Beam	Metal	Center	Peeling	Tan	218	< LOD
39	Shelf	Wood	В	Intact	Cream	212	< LOD
40	Shelf	Wood	В	Intact	Cream	212	< LOD
41	Wall	Drywall	A	Intact	Cream	212	< LOD
42	Door	Wood	A	Intact	Blue	212	< LOD
43	Door Casing	Metal	A	Intact	Blue	212	< LOD
44	Fan Coil	Metal	D	Intact	Cream	213	< LOD



Scan No.	Component	Substrate	Side	Condition	Color	Sample Location	PbC mg/cm ²
45	Wall	Drywall	D	Intact	Cream	213	< LOD
46	Wall	Drywall	В	Intact	White	211	< LOD
47	Door	Metal	В	Intact	Blue	211	< LOD
48	Door Casing	Metal	В	Intact	Blue	211	< LOD
49	Door	Metal	D	Intact	Blue	211	< LOD
50	Wall	Drywall	A	Intact	White	208	< LOD
51	Floor Heat Unit	Metal	В	Intact	Tan	208	< LOD
52	Door	Wood	D	Intact	Blue	208	< LOD
53	Door Casing	Metal	D	Intact	Blue	208	< LOD
54	Wall	Drywall	С	Intact	Blue	204	< LOD
55	Wall	Wood	Center	Intact	Blue	202	< LOD
56	Computer Wire Rack	Metal	Center	Intact	Grey	202	< LOD
57	Wall	Drywall	С	Intact	Cream	226	< LOD
58	Wall	Drywall	A	Intact	Cream	226	< LOD
59	Door	Wood	Α	Intact	Cream	226	< LOD
60	Door Casing	Metal	A	Intact	Cream	226	< LOD
61	Wall	Drywall	A	Intact	Cream	223C	< LOD
62	Shelf	Wood	В	Intact	Cream	223C	< LOD
63	Door	Wood	D	Intact	Cream	223C	< LOD
64	Door Casing	Metal	D	Intact	Cream	223C	< LOD
65	Wall	Cinder Block	D	Intact	Cream	236	< LOD
66	Wall	Drywall	В	Intact	Cream	236	< LOD
67	Door Casing	Metal	В	Intact	Cream	236	< LOD
68	Door	Wood	В	Intact	Varnish	236	< LOD
69	Floor	Ceramic Tile	В	Intact	Yellow	236	< LOD
70	Baseboard	Ceramic Tile	В	Intact	Tan	236	1
71	Janitor Sink Splash	Ceramic Tile	С	Intact	White	236	0.3
72	Shelf	Wood	D	Intact	Tan	236	< LOD
73 74	Sink Urinal	Porcelain Porcelain	C C	Intact	White White	238	< LOD < LOD
75	Toilet	Porcelain	C	Intact Intact	White	238	< LOD < LOD
76	Wall	Drywall	C	Intact	Cream	238	< LOD < LOD
77	Partition	Metal	C	Intact	Cream	238	0.07
78	Floor	Ceramic Tile	C	Intact	Yellow	238	< LOD
79	Floor	Ceramic Tile	C	Intact	Yellow	238	< LOD
80	Baseboard	Ceramic Tile	C	Intact	Tan	238	0.9
81	Shower wall	Ceramic Tile	C	Intact	Tan	238A	1
82	Shower floor	Ceramic Tile	C	Intact	Yellow	238A	< LOD
83	Wall	Cinder Block	D	Intact	Cream	ST02	< LOD
84	Wall	Brick	D	Intact	Cream	ST02	< LOD
85	Stair Stringer	Metal	Center	Intact	Cream	ST02	0.09
86	Stair Riser	Metal	Center	Intact	Cream	ST02	0.03
87	Newel Post	Metal	Center	Intact	Cream	ST02	0.4
88	Door	Metal	C	Intact	Brown	ST02	< LOD



Scan No.	Component	Substrate	Side	Condition	Color	Sample Location	PbC mg/cm ²
89	Door Casing	Metal	С	Intact	Brown	ST02	< LOD
90	Wall Patch	Brick	В	Intact	Cream	ST02	2.2
91	Wall	Brick	В	Intact	Cream	ST02	< LOD
92	Wall	Brick	В	Peeling	Cream	ST02	< LOD
93	Wall Patch	Brick	В	Peeling	Cream	ST02	2.5
94	Wall	Brick	A	Intact	Cream	ST02	< LOD
95	Wall	Brick	A	Intact	Cream	ST02	< LOD
96	Wall	Brick	D	Intact	Cream	ST02	< LOD
97	Wall	Brick	D	Intact	Cream	ST02	< LOD
98	Wall	Brick	D	Intact	Cream	ST02	< LOD
99	Wall	Brick	D	Intact	Cream	ST02	< LOD
100	Wall	Brick	В	Intact	Cream	ST02	< LOD
101	Wall	Brick	В	Intact	Cream	ST02	< LOD
102	Wall	Brick	С	Intact	Cream	ST02	< LOD
103	Ceiling	Drywall	С	Intact	Cream	ST02	< LOD
104	Brick Wall - Lentel	Metal	С	Intact	Cream	ST02	< LOD
105	Roof Door	Metal	С	Intact	Brown	ST02	< LOD
106	Roof Door Casing	Metal	С	Intact	Brown	ST02	< LOD
107	Ceiling	Wood	С	Peeling	Cream	200	< LOD
108	Ceiling	Wood	С	Peeling	Cream	200	< LOD
109	Beam	Wood	C	Peeling	Cream	200	< LOD
110	Beam	Wood	C	Peeling	Cream	200	< LOD
111	Beam	Wood	C	Peeling	Cream	200	< LOD
112	Beam	Wood	С	Peeling	Cream	200	< LOD
113	Wall	Brick	D	Intact	Cream	V101	< LOD
114	Wall	Drywall	C	Intact	wallpaper	V101	< LOD
115	Wall	Drywall	С	Intact	wallpaper	V101	< LOD
116	Chair Rail	Wood	С	Intact	Varnish	V101	< LOD
117	Baseboard	Wood	C	Intact	Varnish	V101	< LOD
118	Win. Casing	Metal	A	Intact	Brown	V101	< LOD
119	Wall Wall	Brick	B B	Intact	Cream	V101	< LOD
120		Brick		Intact	Cream	V101	< LOD
121 122	Wall Elevator Door	Brick Metal	B B	Intact Intact	Cream Brown	V101 V101	< LOD < LOD
123	Elevator Door Casing	Metal	В	Intact	Brown	V101 V101	< LOD
123	Wall	Cinder Block	В			ST01	< LOD
124	Wall	Brick	В	Intact Intact	Cream Cream	ST01	< LOD < LOD
125	Wall	Brick	В	Intact	Cream	ST01	< LOD < LOD
127	Wall	Brick	В	Intact	Cream	ST01	< LOD < LOD
127	Newel Post	Metal	В	Intact	Cream	ST01	< LOD < LOD
129	Stair Riser	Metal	Center	Intact	Cream	ST01	< LOD
130	Wall	Concrete	A	Intact	Cream	V101	< LOD
131	Wall	Brick	B	Intact	Cream	V101 V101	< LOD
131	Wall	Drywall	С	Intact	Blue	V101 V101	< LOD



Scan No.	Component	Substrate	Side	Condition	Color	Sample Location	PbC mg/cm ²
133	Wall	Drywall	С	Intact	Green	V101	< LOD
134	Door	Metal	D	Intact	Brown	V101	< LOD
135	Door Casing	Metal	D	Intact	Brown	V101	< LOD
136	Wall	Brick	A	Peeling	Cream	100	< LOD
137	Wall	Brick	A	Peeling	Cream	100	< LOD
138	Wall	Plaster	A	Peeling	Cream	100	0.6
139		Shi	ıtter Calibra	ite			NA
140			Calibrate				1.3
141			Calibrate				0.8
142			Calibrate				0.9
143			Calibrate		~	100	0.6
144	Wall	Plaster	A	Peeling	Cream	100	< LOD
145	Wall	Brick	A	Peeling	Cream	100	< LOD
146	Wall	Brick	A	Peeling	Cream	100	< LOD
147	Wall	Plaster	A	Peeling	Cream	100	0.6
148 149	Wall	Plaster	C C	Peeling	Cream	100	< LOD
150	Wall Wall	Plaster Plaster	C	Peeling Peeling	Cream Cream	100	< LOD 0.7
151	Wall	Plaster	C	Peeling	Cream	100	0.7
152	Wall	Plaster	C	Peeling	Cream	100	0.7
153	Wall	Plaster	C	Peeling	Cream	100	1.4
154	Wall	Brick	C	Peeling	Cream	100	1.4
155	Wall	Brick	D	Peeling	Cream	100	< LOD
156	Wall	Plaster	D	Peeling	Cream	100	1
157	Column	Wood	D	Peeling	Cream	100	1.6
158	Column	Wood	Center	Peeling	Cream	100	0.8
159	Shelf	Metal	Center	Intact	Yellow	100	1.6
160	Shelf	Metal	Center	Intact	Yellow	100	2.9
161	Floor Striping	Concrete	Center	Poor	Yellow	100	0.29
162	Floor Striping	Concrete	Center	Poor	Yellow	100	0.8
163	Floor Striping	Concrete	Center	Poor	Yellow	100	0.5
164	Shelf	Metal	D	Intact	Red	100	< LOD
165	Shelf	Metal	D	Intact	Red	100	< LOD
166	Shelf	Metal	D	Intact	Red	100	< LOD
167	Metal Bollard	Metal	D	Intact	Yellow	100	< LOD
168	Shelf	Metal	D	Intact	Yellow	100	2.4
169	Ceiling	Wood	A	Peeling	Cream	100	< LOD
170	Ceiling	Wood	A	Peeling	Cream	100	< LOD
171	Beam	Wood	A	Peeling	Cream	100	< LOD
172	Beam	Wood	A	Peeling	Cream	100	< LOD
173	Pipe	Metal	A	Peeling	Cream	100	< LOD
174	Pipe	Metal	A	Peeling	Cream	100	< LOD
175	Wall	Wood	A	Intact	White	110	< LOD
176	Column	Metal	A	Intact	White	110	< LOD



Scan No.	Component	Substrate	Side	Condition	Color	Sample Location	PbC mg/cm ²
177	Beam	Metal	A	Intact	White	110	< LOD
178	Garage Door	Metal	A	Intact	White	110	< LOD
179	Wall	Brick	C	Intact	Cream	110	0.21
180	Wall	Brick	C	Intact	Cream	110	< LOD
181	Wall	Brick	С	Intact	Cream	110	< LOD
182	Wall	Brick	С	Intact	White	110	0.25
183	Wall	Brick	В	Intact	White	110	0.15
184	Beam	Metal	Center	Intact	Cream	110	< LOD
185	Angle Iron	Metal	Center	Intact	Cream	110	< LOD
186	Z-channel	Metal	Center	Intact	Cream	110	< LOD
187	Win. Casing	Wood	D	Intact	Cream	110	< LOD
188	Wall	Brick	D	Peeling	Cream	111	< LOD
189	Wall	Brick	D	Peeling	Cream	111	< LOD
190	Wall	Brick	D	Peeling	Cream	111	1
191	Wall	Brick	D	Peeling	Cream	111	< LOD
192	Wall	Brick	D	Peeling	Cream	111	0.5
193	Wall	Brick	A	Peeling	Cream	111	0.7
194	Wall	Brick	A	Peeling	Cream	111	< LOD
195	Wall	Brick	D	Peeling	Cream	111	< LOD
196	Wall	Brick	В	Peeling	Cream	111	1.5
197	Column	Wood	Center	Peeling	Cream	111	1.4
198 199	Floor Striping	Concrete	Center	Poor	White	111	< LOD
200	Floor Striping	Concrete	ıtter Calibra	Poor	White	111	0.21 NA
200		SIIC	Calibrate	ile			0.7
202			Calibrate				1
203			Calibrate				0.6
204			Calibrate				1.1
205		Shi	itter Calibra	te.			NA
206		Since	Calibrate				0.6
207			Calibrate				1
208			Calibrate				0.6
209			Calibrate				0.9
210	Floor	Ceramic Tile	Center	Intact	Grey	219	< LOD
211	Baseboard	Ceramic Tile	С	Intact	Grey	219	< LOD
212	Wall	Ceramic Tile	С	Intact	Grey	219	< LOD
213	Wall	Drywall	С	Intact	White	219	< LOD
214	Pipe	Metal	С	Peeling	White	219	< LOD
215	Wall	Brick	A	Peeling	Cream	100	0.8
216	Wall	Plaster	A	Peeling	Cream	100	0.8
217	Wall	Plaster	A	Peeling	Cream	100	0.8
218	Wall	Plaster	D	Peeling	Cream	100	< LOD
219	Wall	Plaster	D	Peeling	Cream	100	1.4
220	Wall	Brick	D	Peeling	Cream	100	1.1



Scan No.	Component	Substrate	Side	Condition	Color	Sample Location	PbC mg/cm ²
221	Wall	Plaster	D	Peeling	Cream	100	1.5
222	Ceiling-2nd layer	Wood	С	Peeling	Cream	100	< LOD
223	Ceiling-2nd layer	Wood	С	Peeling	Cream	100	0.06
224	Fire Sprinkler Pipe	Metal	В	Intact	Cream	100	<lod< td=""></lod<>
225	Ceiling Pipe	Metal	В	Intact	Cream	100	<lod< td=""></lod<>
226	Wall	Brick	С	Peeling	Cream	H102	< LOD
227	Wall	Brick	C	Peeling	Cream	H102	< LOD
228	Wall	Brick	C	Intact	White	H102	1.9
229	Window fill-in	Plaster	С	Intact	Cream	H102	< LOD
230	Wall	Drywall	A	Intact	Cream	H102	< LOD
231	Door	Metal	Center	Intact	Brown	H102	< LOD
232	Door Casing	Metal	Center	Intact	Brown	H102	0.05
233	Garage Door	Metal	С	Intact	Grey	100	< LOD
234	Shelf	Metal	В	Intact	Blue	100	< LOD
235	Shelf	Metal	В	Intact	Blue	100	< LOD
236	Wall	Drywall	A	Intact	White	102C	< LOD
237	Sink	Porcelain	С	Intact	White	102C	< LOD
238	Toilet	Porcelain	С	Intact	White	102C	< LOD
239	Floor	Ceramic Tile	С	Intact	Yellow	102C	< LOD
240	Baseboard	Ceramic Tile	C	Intact	Tan	102C	0.8
241	Baseboard	Ceramic Tile	D	Intact	Tan	102C	0.9
242	Baseboard	Ceramic Tile	Α	Intact	Tan	104	1.1
243	Floor	Ceramic Tile	A	Intact	Yellow	104	< LOD
244	Wall	Drywall	A	Peeling	Cream	104	< LOD
245	Door Casing	Wood	В	Fair	Cream	104	< LOD
246	Baseboard	Ceramic Tile	В	Intact	Tan	105	0.8
247	Urinal	Porcelain	D	Intact	White	105	< LOD
248	Wall	Drywall	В	Intact	Cream	105	< LOD
249	Wall	Drywall	В	Intact	Cream	108	< LOD
250	Ceiling track	Metal	В	Intact	Cream	108	< LOD
251	Door Casing	Wood	D	Intact	Cream	108	< LOD
252	Door	Wood	D	Intact	Varnish	108	< LOD
253	Wall	Brick	A	Peeling	Yellow	Exterior	< LOD
254	Wall	Brick	A	Peeling	Yellow	Exterior	< LOD
255	Wall	Plaster	A	Poor	Yellow	Exterior	< LOD
256	Wall	Brick	A	Peeling	Yellow	Exterior	< LOD
257	Wall	Brick	A	Peeling	Yellow	Exterior	< LOD
258	Ext. Downspout	Metal	A	Intact	White	Exterior	< LOD
259	Wall	Concrete	A	Intact	Yellow	Exterior	< LOD
260	Wall	Brick	D	Peeling	Yellow	Exterior	0.18
261	Wall	Brick	D	Peeling	Yellow	Exterior	0.2
262	Wall	Metal	D	Peeling	Yellow	Exterior	< LOD
263	Staircase	Metal	D	Poor	Grey	Exterior	< LOD
264	Staircase	Metal	D	Poor	Grey	Exterior	1.2



Scan No.	Component	Substrate	Side	Condition	Color	Sample Location	PbC mg/cm ²
265	Staircase Column	Metal	D	Peeling	Grey	Exterior	0.7
266	Staircase Column	Metal	D	Peeling	Grey	Exterior	< LOD
267	Staircase Beam	Metal	D	Peeling	Grey	Exterior	< LOD
268	Staircase Beam	Metal	D	Peeling	Grey	Exterior	< LOD
269	Staircase Column	Metal	D	Peeling	Grey	Exterior	0.6
270	Staircase handrail	Metal	D	Poor	Grey	Exterior	< LOD
271	Column	Metal	C	Intact	Tan	114	< LOD
272	Column	Metal	D	Intact	Tan	114	< LOD
273	Wall	Brick	A	Peeling	Cream	114	< LOD
274	Wall	Wood	A	Intact	Cream	114	< LOD
275	Wall	Cinder Block	С	Intact	Yellow	Exterior	< LOD
276	Column	Concrete	C	Intact	Yellow	Exterior	< LOD
277	Staircase	Metal	C	Poor	Grey	Exterior	< LOD
278	Staircase	Metal	C	Poor	Grey	Exterior	< LOD
279	Wall	Brick	A	Poor	White	114A	< LOD
280 281	Wall Wall	Brick Brick	A	Poor Poor	White White	114A 114A	< LOD < LOD
281	Column	Metal	A C	Intact	White	114A 114A	< LOD < LOD
283	Column	Metal	В	Intact	White	114A 114A	0.06
284	Column	Metal	A	Intact	Yellow	X101	< LOD
285	Column	Metal	C	Intact	Brown	X101 X101	< LOD
286	Wall	Brick	A	Peeling	Yellow	X101	< LOD
287	Wall	Brick	A	Peeling	Yellow	X101	< LOD
288	Wall	Brick	A	Peeling	Yellow	X101	< LOD
289	Garage Door	Metal	A	Intact	Grey	X101	< LOD
290	Brick Corner Protector	Metal	A	Intact	Yellow	X101	< LOD
291	Door	Metal	В	Intact	Brown	X101	< LOD
292	Column	Metal	A	Peeling	Yellow	X101	< LOD
293	Ramp	Concrete	С	Peeling	Yellow	X101	< LOD
294	Ramp	Concrete	С	Peeling	Yellow	X101	< LOD
295	Loading Dock Corner Protector	Metal	С	Peeling	Yellow	X101	2.8
296	Loading Dock Corner Protector	Metal	С	Peeling	Yellow	X101	< LOD
297	Loading Dock Corner Protector	Metal	С	Peeling	Yellow	X101	0.6
298	Loading Dock Corner Protector	Metal	C	Peeling	Yellow	X101	3.3
299	Loading Dock Corner Protector	Metal	C	Peeling	Yellow	X101	0.8
300	Loading Dock Corner Protector	Metal	С	Peeling	Yellow	X101	1.1
301	Loading Ramp Height Adjuster	Metal	С	Peeling	Yellow-grey	X101	< LOD



Scan No.	Component	Substrate	Side	Condition	Color	Sample Location	PbC mg/cm ²
302	Loading Ramp Height Adjuster	Metal	С	Peeling	Yellow-grey	X101	0.4
303	Wall	Brick	С	Peeling	Yellow	Exterior	< LOD
304	Wall	Brick	C	Intact	Yellow	Exterior	< LOD
305	Wall	Brick	В	Intact	Yellow	Exterior	< LOD
306	Wall	Brick	В	Peeling	Yellow	Exterior	< LOD
307	Wall	Brick	В	Intact	Yellow	Exterior	< LOD
308	Staircase Column	Metal	В	Intact	Brown	Exterior	< LOD
309	Stair Stringer	Metal	В	Intact	Brown	Exterior	< LOD
310	Stair Handrail	Metal	В	Poor	Brown	Exterior	< LOD
311	Stair Step	Metal	В	Poor	Brown	Exterior	< LOD
312	Stair Canopy	Metal	В	Intact	Brown	Exterior	< LOD
313	Stair Canopy	Metal	В	Intact	Brown	Exterior	< LOD
314	Door	Metal	В	Intact	Brown	Exterior	< LOD
315	Hoist-Crane	Metal		Poor	Yellow	Exterior	0.4
316	Hoist-Crane	Metal		Poor	Yellow	Exterior	1.5
317	Hoist-Crane	Metal		Poor	Yellow	Exterior	1.1
318	Hoist-Crane	Metal		Poor	Yellow	Exterior	1.1
319	Hoist-Crane	Metal		Poor	Yellow	Exterior	1.9
320	Hoist-Crane	Metal		Poor	Yellow	Exterior	0.5
321	Hoist-Crane	Metal		Poor	Yellow	Exterior	< LOD
322	Hoist-Crane	Metal		Poor	Yellow	Exterior	0.7
323	Bollard	Metal	D	Intact	Yellow	Exterior	< LOD
324	Bollard	Metal	D	Intact	Yellow	Exterior	< LOD
325	Parking strip	Asphalt	D	Poor	Yellow	Exterior	< LOD
326	Parking strip	Asphalt	D	Poor	Yellow	Exterior	< LOD
327		Shi	utter Calibra	te			NA
328			Calibrate				0.6
329			Calibrate				1.1
330			Calibrate				0.7
331			Calibrate				1.1
332	Window Casing	Wood	C	Peeling	Grey	Exterior	< LOD
333	Window Sill	Wood	C	Peeling	Grey	Exterior	< LOD
334	Window Security Bars	Metal	C	Fair	Yellow	Exterior	1.2
335	Window Security Bars	Metal	C	Fair	Yellow	Exterior	< LOD
336	Window Security Bars	Metal	C	Fair	Yellow	Exterior	1.5
337	Window Security Bars	Metal	C	Fair	Yellow	Exterior	0.7
338	Window Security Bars	Metal	C	Fair	Yellow	Exterior	1.2
339 340	Window Security Bars	Metal Matal	C	Fair	Yellow	Exterior	1.3
-	Garage Door Bar	Metal	A	Poor	Yellow	X101	< LOD
341	Garage Door Bar Wall	Metal Brick	В	Poor	Yellow	X101 2nd floor Hallway by ST02	< LOD 9.5



Scan No.	Component	Substrate	Side	Condition	Color	Sample Location	PbC mg/cm ²
343	Wall	Brick	В	Intact	Yellow	2nd floor Hallway by ST02	8.2
344	Wall	Brick	В	Peeling	Yellow	2nd floor Hallway by ST02	9.8
345	Skylight	Fiberglass	Center	Intact	Green	Roof	< LOD
346	Knee Wall cap	Metal	Center	Intact	White	Roof	< LOD
347	Wall	Brick	В	Intact	White	Roof-ST02	< LOD
348	Ext. Facia	Wood	В	Peeling	Yellow	Roof-ST02	< LOD
349	Roof	TPO	Center	Intact	White	Roof-ST02	< LOD
350	Roof	TPO	Center	Intact	White	Roof-ST02	< LOD
351	Door	Metal	D	Poor	Brown	Roof-ST02	< LOD
352	Roof	Metal	В	Intact	Yellow	X101	< LOD
353	Ext. Gutter	Metal	C	Intact	Brown	X101	< LOD
354	Beam	Metal	В	Intact	Red	X101	< LOD
355	Beam	Metal	В	Intact	Red	X101	< LOD
356	S-channel	Metal	В	Intact	Red	X101	< LOD
357		Shutter Calibrate					NA
358			Calibrate				0.6
359			Calibrate				1
360			Calibrate				0.6
361			Calibrate				1



Appendix D

Site Photographs of Lead Positive Items



Photographs 1 & 2





Photo taken from above drop ceiling in room 200 showing wood columns and column top plate that contain lead-based paint. Close-up view of column and column top plate.

Photographs 3 & 4





Photo in main warehouse area (Room 100) of the wood columns and metal yellow shelving that contain lead based paint.

Photographs 5 & 6





Photo in main warehouse area (Room 100) of the lead containing yellow paint striping on concrete floor.

Photographs 7 & 8





Photo in main warehouse area (Room 100) of the lead-based painted plaster walls with photo of paint chips on the floor.

Photographs 9 & 10





Photo in main warehouse area (Room 100) of the lead-based painted brick walls with photo of paint chips on the floor.

Photographs 11 & 12





Photo of yellow painted brick walls painted with lead-based paint above drop ceiling on second floor in hallway by stairway STO2.

Photo of creampainted brick wall patched section in ST02 containing lead-based paint.

Photograph 13



Photo of white painted brick walls painted with lead-based paint located in room 111.

Photographs 14 & 15





Photo of leadcontaining tan ceramic baseboard tile, located in janitor closet and bathrooms.

Photographs 16 & 17



Photo of lead containing tan ceramic baseboard tile, located in bathrooms.



Photo of leadcontaining tan ceramic wall tile located in shower. (Room 238A)

Photographs 18 & 19






Photo of leadcontaining yellow painted metal loading dock edge protector on back loading dock.

Photo of leadcontaining yellow painted metal window security bars on room 102B.

Photographs 20 & 21





Photo of leadcontaining gray painted exterior staircase located on west side of the building.

Photo of leadcontaining yellow painted hoist located on west side of the building.

Appendix E

Personnel Certification



United States Environmental Protection Agency This is to certify that



Jeffrey Steve Leary

has fulfilled the requirements of the Toxic Substances Control Act (TSCA) Section 402, and has received certification to conduct lead-based paint activities pursuant to 40 CFR Part 745.226 as:

Inspector

In the Jurisdiction of:

South Carolina		
	July 20, 2018	

SC-I-18721-3
Certification #
April 24, 2015
Issued On



Adrienne Priselac, Manager, Toxics Office

Land Division

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to all Sections in the Project Manual.
 - 1. The Contractor shall issue a copy of all Division 01 Sections, including copy of Table of Contents, when issuing a partial set of specifications to other contractors. Issuing partial sets of construction documents is discouraged by the Architect and the Owner. Issuing partial sets will be at the Contractor's risk.

1.2 SUMMARY

A. Section Includes:

- 1. Project information.
- 2. Work covered by Contract Documents.
- 3. Access to site.
- 4. Coordination with occupants.
- 5. Work restrictions.
- 6. Specification and drawing conventions.

1.3 PROJECT INFORMATION

- A. Project Identification: 1206 Flora Street Mill Renovation Fire Alarm Bid Package
 - 1. Project Location: Columbia, South Carolina.
- B. Owner: University of South Carolina.
- C. Architect: GMC, Inc., 1219 Wayne Street, South Carolina 29201.

1.4 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work of the Project is defined by the Contract Documents and consists of the following.
 - 1. The project work consists of the Installation of a new and complete Fire Alarm System throughout the existing building as noted in the associated set of documents.

B. Construction Description:

1. The Work includes selective demolition, installation of the new fire alarm system.

SUMMARY 011000 - 1 of 3

C. Type of Contract:

1. Project will be constructed under a single prime contract. The contractor shall coordinate with other contractors performing other work not described in this project.

1.5 ACCESS TO SITE

- A. General: Contractor shall have limited use of Project site for construction operations as indicated on Drawings by the Contract limits and as indicated by requirements of this Section.
- B. Use of Site: Limit use of Project site to Work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.
 - 1. Limits: Confine construction operations to areas shown on the drawings.
 - 2. Driveways, Walkways and Entrances: Keep driveways, loading areas, and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or for storage of materials.
 - a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
 - b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.

1.6 COORDINATION WITH OCCUPANTS

- A. Full Owner Occupancy: Owner will occupy site and existing building during entire construction period. Cooperate with Owner during construction operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with Owner's day-to-day operations. Maintain existing exits unless otherwise indicated.
 - Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Owner and approval of authorities having jurisdiction.
 - 2. Notify Owner not less than 7 days in advance of activities that will affect Owner's operations.
- B. Owner Limited Occupancy of Completed Areas of Construction: Owner reserves the right to occupy and to place and install equipment in completed portions of the Work, prior to Substantial Completion of the Work, provided such occupancy does not interfere with completion of the Work. Such placement of equipment and limited occupancy shall not constitute acceptance of the total Work.

1.7 WORK RESTRICTIONS

- A. Work Restrictions, General: Comply with restrictions on construction operations.
 - 1. Comply with limitations on use of public streets and with other requirements of authorities having jurisdiction.

SUMMARY 011000 - 2 of 3

PROJECT # H27-I851 50001658-25 GMC PROJECT # ACOL180003 03/20/2020

B. On-Site Work Hours: Work shall be generally performed during normal business working hours of 7:00 a.m. to 6:00 p.m., Monday through Friday.

1.8 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
 - 1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
 - 2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.
- B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.
- C. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:
 - 1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
 - 2. Abbreviations: Materials and products are identified by abbreviations published as part of the U.S. National CAD Standard and scheduled on Drawings.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

SUMMARY 011000 - 3 of 3

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

B. Related Requirements:

1. Section 012500 "Substitution Procedures" for administrative procedures for handling requests for substitutions made after the Contract award.

1.3 MINOR CHANGES IN THE WORK

A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time.

1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include revised Documents.
 - 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
 - 2. Within time specified in Proposal Request or 10 days, when not otherwise specified, after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and supervision directly attributable to the change.
 - d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 - e. Quotation Form: Use forms acceptable to Architect.

- B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.
 - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 - 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - 4. Include costs of labor and supervision directly attributable to the change.
 - 5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 - 6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
 - 7. Proposal Request Form: Use form acceptable to Architect.

1.5 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Work Changes Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on SE-480 (latest edition).

1.6 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 - 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
 - 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Requirements:
 - 1. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.

1.3 DEFINITIONS

A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.
 - 1. Coordinate line items in the schedule of values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with continuation sheets.
 - b. Submittal schedule.
 - c. Items required to be indicated as separate activities in Contractor's construction schedule.
 - 2. Submit the schedule of values to Architect at earliest possible date, but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
 - 1. Identification: Include the following Project identification on the schedule of values:
 - a. Project name and location.
 - b. Name of Architect.
 - c. Architect's project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
 - 2. Arrange schedule of values consistent with format of AIA Document G703.

- 3. Arrange the schedule of values in tabular form with separate columns to indicate the following for each item listed:
 - a. Related Specification Section or Division.
 - b. Description of the Work.
 - c. Name of subcontractor.
 - d. Name of manufacturer or fabricator.
 - e. Name of supplier.
 - f. Change Orders (numbers) that affect value.
 - g. Dollar value of the following, as a percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.
 - 1) Labor.
 - 2) Materials.
 - 3) Equipment.
- 4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with Project Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
- 5. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
- 6. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - a. Differentiate between items stored on-site and items stored off-site. If required, include evidence of insurance.
- 7. Provide separate line items in the schedule of values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
- 8. Schedule Updating: Update and resubmit the schedule of values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
 - 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
- C. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.

- 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
- 2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
- 3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
- 4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.
- E. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored onsite and items stored off-site.
 - 1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment, for stored materials.
 - 2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
 - 3. Provide summary documentation for stored materials indicating the following:
 - a. Value of materials previously stored and remaining stored as of date of previous Applications for Payment.
 - b. Value of previously stored materials put in place after date of previous Application for Payment and on or before date of current Application for Payment.
 - c. Value of materials stored since date of previous Application for Payment and remaining stored as of date of current Application for Payment.
- F. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
 - 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from entities lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
 - 1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
 - 2. When an application shows completion of an item, submit conditional final or full waivers.
 - 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
 - 4. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.
- H. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:

- 1. List of subcontractors.
- 2. Schedule of values.
- 3. Contractor's construction schedule (preliminary if not final).
- 4. List of Contractor's staff assignments.
- 5. List of Contractor's principal consultants.
- I. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
 - 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 - 2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
 - 1. Evidence of completion of Project closeout requirements.
 - 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 - 3. Updated final statement, accounting for final changes to the Contract Sum.
 - 4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
 - 5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
 - 6. AIA Document G707, "Consent of Surety to Final Payment."
 - 7. Evidence that claims have been settled.
 - 8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
 - 9. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
 - 1. General coordination procedures.
 - 2. Requests for Information (RFIs).
 - 3. Project meetings.
- B. Each contractor shall participate in coordination requirements. Certain areas of responsibility are assigned to a specific contractor.

C. Related Requirements:

- 1. Section 013200 "Construction Progress Documentation" for preparing and submitting Contractor's construction schedule.
- 2. Section 017300 "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
- 3. Section 017700 "Closeout Procedures" for coordinating closeout of the Contract.

1.3 DEFINITIONS

A. RFI: Request from Owner, Architect, or Contractor seeking information required by or clarifications of the Contract Documents.

1.4 INFORMATIONAL SUBMITTALS

- A. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
 - 1. Name, address, and telephone number of entity performing subcontract or supplying products.
 - 2. Number and title of related Specification Section(s) covered by subcontract.
 - 3. Drawing number and detail references, as appropriate, covered by subcontract.

B. Key Personnel Names: Within 5 days of starting construction operations, submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers, including home, office, and cellular telephone numbers and e-mail addresses. Provide names, addresses, and telephone numbers of individuals assigned as alternates in the absence of individuals assigned to Project.

1.5 GENERAL COORDINATION PROCEDURES

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
 - 3. Make adequate provisions to accommodate items scheduled for later installation.
 - 4. Coordinate with other Contractors hired by the owner to perform other work outside the scope of this project.
- B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
 - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.
- C. Conservation: Coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials. Coordinate use of temporary utilities to minimize waste.

1.6 REQUESTS FOR INFORMATION (RFIs)

- A. General: Immediately on discovery of the need for additional information or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.
 - 1. Architect will return RFIs submitted to Architect by other entities controlled by Contractor with no response.
 - 2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:
 - 1. Project name.
 - 2. Project number.

- 3. Date.
- 4. Name of Contractor.
- 5. Name of Architect.
- 6. RFI number, numbered sequentially.
- 7. RFI subject.
- 8. Specification Section number and title and related paragraphs, as appropriate.
- 9. Drawing number and detail references, as appropriate.
- 10. Field dimensions and conditions, as appropriate.
- 11. Contractor's suggested resolution. If Contractor's suggested resolution impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
- 12. Contractor's signature.
- 13. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
 - a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.
- C. RFI Forms: Software-generated form with substantially the same content as indicated above, acceptable to Architect.
 - 1. Attachments shall be electronic files in Adobe Acrobat PDF format.
- D. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow seven working days for Architect's response for each RFI. RFIs received by Architect after 1:00 p.m. will be considered as received the following working day.
 - 1. The following Contractor-generated RFIs will be returned without action:
 - a. Requests for approval of submittals.
 - b. Requests for approval of substitutions.
 - c. Requests for approval of Contractor's means and methods.
 - d. Requests for coordination information already indicated in the Contract Documents.
 - e. Requests for adjustments in the Contract Time or the Contract Sum.
 - f. Requests for interpretation of Architect's actions on submittals.
 - g. Incomplete RFIs or inaccurately prepared RFIs.
 - 2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt of additional information.
 - 3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."
 - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.
- E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly. Include the following:

- 1. Project name.
- 2. Name and address of Contractor.
- 3. Name and address of Architect.
- 4. RFI number including RFIs that were returned without action or withdrawn.
- 5. RFI description.
- 6. Date the RFI was submitted.
- 7. Date Architect's response was received.
- F. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within seven days if Contractor disagrees with response.
 - 1. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
 - 2. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.

1.7 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site unless otherwise indicated.
 - 1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
 - 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
 - 3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within three days of the meeting.
- B. Preconstruction Conference: Schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 5 days after execution of the Agreement.
 - 1. Conduct the conference to review responsibilities and personnel assignments.
 - 2. Attendees: Authorized representatives of Owner Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 3. Agenda: Discuss items of significance that could affect progress, including the following:
 - a. Tentative construction schedule.
 - b. Critical work sequencing and long-lead items.
 - c. Designation of key personnel and their duties.
 - d. Lines of communications.
 - e. Procedures for processing field decisions and Change Orders.

- f. Procedures for RFIs.
- g. Procedures for testing and inspecting.
- h. Procedures for processing Applications for Payment.
- i. Distribution of the Contract Documents.
- j. Submittal procedures.
- k. Preparation of record documents.
- 1. Use of the premises and existing building.
- m. Work restrictions.
- n. Working hours.
- o. Owner's occupancy requirements.
- p. Responsibility for temporary facilities and controls.
- q. Procedures for moisture and mold control.
- r. Procedures for disruptions and shutdowns.
- s. Construction waste management and recycling.
- t. Parking availability.
- u. Office, work, and storage areas.
- v. Equipment deliveries and priorities.
- w. First aid.
- x. Security.
- y. Progress cleaning.
- 4. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.
 - 1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
 - 2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
 - a. Contract Documents.
 - b. Options.
 - c. Related RFIs.
 - d. Related Change Orders.
 - e. Purchases.
 - f. Deliveries.
 - g. Submittals.
 - h. Review of mockups.
 - i. Possible conflicts.
 - j. Compatibility requirements.
 - k. Time schedules.
 - 1. Weather limitations.
 - m. Manufacturer's written instructions.
 - n. Warranty requirements.
 - o. Compatibility of materials.
 - p. Acceptability of substrates.
 - q. Temporary facilities and controls.

- r. Space and access limitations.
- s. Regulations of authorities having jurisdiction.
- t. Testing and inspecting requirements.
- u. Installation procedures.
- v. Coordination with other work.
- w. Required performance results.
- x. Protection of adjacent work.
- y. Protection of construction and personnel.
- 3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
- 4. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
- 5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Progress Meetings: Conduct progress meetings at weekly intervals.
 - 1. Coordinate dates of meetings with preparation of payment requests.
 - 2. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 3. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - 1) Review schedule for next period.
 - b. Review present and future needs of each entity present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Deliveries.
 - 5) Off-site fabrication.
 - 6) Access.
 - 7) Site utilization.
 - 8) Temporary facilities and controls.
 - 9) Progress cleaning.
 - 10) Quality and work standards.
 - 11) Status of correction of deficient items.
 - 12) Field observations.
 - 13) Status of RFIs.

- 14) Status of proposal requests.
- 15) Pending changes.
- 16) Status of Change Orders.
- 17) Pending claims and disputes.
- 18) Documentation of information for payment requests.
- 4. Minutes: Entity responsible for conducting the meeting will record and distribute the meeting minutes to each party present and to parties requiring information.
 - a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.
- E. Coordination Meetings: Conduct Project coordination meetings at weekly intervals. Project coordination meetings are in addition to specific meetings held for other purposes, such as progress meetings and preinstallation conferences.
 - 1. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meetings shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 2. Agenda: Review and correct or approve minutes of the previous coordination meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Combined Contractor's Construction Schedule: Review progress since the last coordination meeting. Determine whether each contract is on time, ahead of schedule, or behind schedule, in relation to combined Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - b. Schedule Updating: Revise combined Contractor's construction schedule after each coordination meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with report of each meeting.
 - c. Review present and future needs of each contractor present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Deliveries.
 - 5) Off-site fabrication.
 - 6) Access.
 - 7) Site utilization.
 - 8) Temporary facilities and controls.
 - 9) Work hours.
 - 10) Hazards and risks.
 - 11) Progress cleaning.
 - 12) Quality and work standards.
 - 13) Change Orders.

USC 1206 FLORA STREET MILL RENOVATION FIRE ALARM BID PACKAGE

PROJECT # H27-I851 50001658-25 GMC PROJECT # ACOL180003 03/20/2020

3. Reporting: Record meeting results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013100

SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
 - 1. Contractor's construction schedule.
 - 2. Construction schedule updating reports.
 - 3. Material location reports.
 - 4. Site condition reports.
 - 5. Special reports.

B. Related Requirements:

- 1. Section 013300 "Submittal Procedures" for submitting schedules and reports.
- 2. Section 014000 "Quality Requirements" for submitting a schedule of tests and inspections.

1.3 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.
 - 1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
 - 2. Predecessor Activity: An activity that precedes another activity in the network.
 - 3. Successor Activity: An activity that follows another activity in the network.
- B. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.
- C. Float: The measure of leeway in starting and completing an activity.
 - 1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.

- 2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
- 3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.

1.4 INFORMATIONAL SUBMITTALS

- A. Format for Submittals: Submit required submittals in the following format:
 - 1. Working electronic copy of schedule file, where indicated.
 - 2. PDF electronic file.
- B. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.
- C. Construction Schedule Updating Reports: Submit with Applications for Payment.
- D. Site Condition Reports: Submit at time of discovery of differing conditions.
- E. Special Reports: Submit at time of unusual event.
- F. Qualification Data: For scheduling consultant.

1.5 COORDINATION

- A. Coordinate Contractor's construction schedule with the schedule of values, submittal schedule, progress reports, payment requests, and other required schedules and reports.
 - 1. Secure time commitments for performing critical elements of the Work from entities involved.
 - 2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

PART 2 - PRODUCTS

2.1 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Time Frame: Extend schedule from date established for the Notice to Proceed to date of Substantial Completion.
 - 1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- B. Activities: Treat each story or separate area as a separate numbered activity for each main element of the Work. Comply with the following:
 - 1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.

- 2. Procurement Activities: Include procurement process activities for the following long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
- 3. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's construction schedule with submittal schedule.
- 4. Startup and Testing Time: Include no fewer than 15 days for startup and testing.
- 5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
- 6. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and final completion.
- C. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.
 - 1. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
 - 2. Owner-Furnished Products: Include a separate activity for each product. Include delivery date indicated in Section 011000 "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
 - 3. Work Restrictions: Show the effect of the following items on the schedule:
 - a. Coordination with existing construction.
 - b. Environmental control.
 - 4. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:
 - a. Submittals.
 - b. Fabrication.
 - c. Installation.
 - d. Curing.
- D. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and final completion.
- E. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:
 - 1. Unresolved issues.
 - 2. Unanswered Requests for Information.
 - 3. Rejected or unreturned submittals.
 - 4. Notations on returned submittals.
 - 5. Pending modifications affecting the Work and Contract Time.
- F. Recovery Schedule: When periodic update indicates the Work is **14** or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which

Contractor intends to regain compliance with the schedule. Indicate changes to working hours, working days, crew sizes, and equipment required to achieve compliance, and date by which recovery will be accomplished.

G. Computer Scheduling Software: Prepare schedules using current version of a program that has been developed specifically to manage construction schedules.

2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Submit a comprehensive, fully developed, horizontal, Contractor's construction schedule within 10 days of date established for the Notice to Proceed. Base schedule on the startup construction schedule and additional information received since the start of Project.
- B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line.

2.3 REPORTS

A. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

2.4 SPECIAL REPORTS

- A. General: Submit special reports directly to Owner within one day(s) of an occurrence. Distribute copies of report to parties affected by the occurrence.
- B. Reporting Unusual Events: When an event of an unusual and significant nature occurs at Project site, whether or not related directly to the Work, prepare and submit a special report. List chain of events, persons participating, response by Contractor's personnel, evaluation of results or effects, and similar pertinent information. Advise Owner in advance when these events are known or predictable.

PART 3 - EXECUTION

3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.
 - 1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.

USC 1206 FLORA STREET MILL RENOVATION FIRE ALARM BID PACKAGE

PROJECT # H27-I851 50001658-25 GMC PROJECT # ACOL180003 03/20/2020

- 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
- 3. As the Work progresses, indicate final completion percentage for each activity.
- B. Distribution: Distribute copies of approved schedule to Architect Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
 - 1. Post copies in Project meeting rooms and temporary field offices.
 - 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION 013200

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.

B. Related Requirements:

- 1. Section 012900 "Payment Procedures" for submitting Applications for Payment and the schedule of values.
- 2. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
- 3. Section 017823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
- 4. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.3 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."
- C. Portable Document Format (PDF): An open standard file format licensed by Adobe Systems used for representing documents in a device-independent and display resolution-independent fixed-layout document format.

1.4 ACTION SUBMITTALS

A. Submittal Schedule: Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making

corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.

- 1. Coordinate submittal schedule with list of subcontracts, the schedule of values, and Contractor's construction schedule.
- 2. Initial Submittal: Submit concurrently with startup construction schedule. Include submittals required during the first 30 days of construction. List those submittals required to maintain orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
- 3. Final Submittal: Submit concurrently with the first complete submittal of Contractor's construction schedule.
 - a. Submit revised submittal schedule to reflect changes in current status and timing for submittals.
- 4. Format: Arrange the following information in a tabular format:
 - a. Scheduled date for first submittal.
 - b. Specification Section number and title.
 - c. Submittal category: Action; informational.
 - d. Name of subcontractor.
 - e. Description of the Work covered.
 - f. Scheduled date for Architect's final release or approval.
 - g. Scheduled date of fabrication.
 - h. Scheduled dates for installation.

1.5 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. Architect's Digital Data Files: Electronic digital data files of the Contract Drawings will be provided by Architect for Contractor's use in preparing submittals.
 - 1. Architect will furnish Contractor one set of digital data drawing files of the Contract Drawings for use in preparing Shop Drawings.
 - a. Architect makes no representations as to the accuracy or completeness of digital data drawing files as they relate to the Contract Drawings.
 - b. Digital Drawing Software Program: The Contract Drawings are available in AutoCAD.
 - c. Contractor shall execute a data licensing agreement in the form of Agreement included at the end of this specification section.
 - d. The following digital data files will by furnished for each appropriate discipline:
 - 1) Floor plans.
 - 2) Reflected ceiling plans.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
 - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 - 2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.

- 3. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
 - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 - 1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
 - 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 - 3. Resubmittal Review: Allow 15 days for review of each resubmittal.
 - 4. Sequential Review: Where sequential review of submittals by Architect's consultants, Owner, or other parties is indicated, allow 21 days for initial review of each submittal.
 - 5. Concurrent Consultant Review: Where the Contract Documents indicate that submittals may be transmitted simultaneously to Architect and to Architect's consultants, allow 15 days for review of each submittal. Submittal will be returned to Architect before being returned to Contractor.
- D. Electronic Submittals: Identify and incorporate information in each electronic submittal file as follows:
 - 1. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
 - 2. Name file with submittal number or other unique identifier, including revision identifier.
 - a. File name shall use project identifier and Specification Section number followed by a decimal point and then a sequential number (e.g., USCT-061000.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., USCT-061000.01.A).
 - 3. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by Architect.
 - 4. Transmittal Form for Electronic Submittals: Use electronic form acceptable to Architect, containing the following information:
 - a. Project name.
 - b. Date.
 - c. Name and address of Architect.
 - d. Name of Contractor.
 - e. Name of firm or entity that prepared submittal.
 - f. Names of subcontractor, manufacturer, and supplier.
 - g. Submittal purpose and description.
 - h. Specification Section number and title.
 - i. Drawing number and detail references, as appropriate.

- j. Location(s) where product is to be installed, as appropriate.
- k. Related physical samples submitted directly.
- 1. Indication of full or partial submittal.
- m. Transmittal number, numbered consecutively.
- n. Submittal and transmittal distribution record.
- o. Other necessary identification.
- p. Remarks.
- E. Options: Identify options requiring selection by Architect.
- F. Deviations and Additional Information: On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Architect on previous submittals, and deviations from requirements in the Contract Documents, including minor variations and limitations. Include same identification information as related submittal.
- G. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
 - 1. Note date and content of previous submittal.
 - 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
 - 3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.
- H. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- I. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.
- J. Paper Submittals: Paper submittals shall be used for samples and material/color selection charts only. Place a permanent label or title block on each submittal item for identification.
 - 1. Indicate name of firm or entity that prepared each submittal on label or title block.
 - 2. Provide a space approximately 6 by 8 inches (150 by 200 mm) on label or beside title block to record Contractor's review and approval markings and action taken by Architect.
 - 3. Include the following information for processing and recording action taken:
 - a. Project name.
 - b. Date.
 - c. Name of Architect.
 - d. Name of Construction Manager.
 - e. Name of Contractor.
 - f. Name of subcontractor.
 - g. Name of supplier.
 - h. Name of manufacturer.
 - i. Submittal number or other unique identifier, including revision identifier.
 - 1) Submittal number shall use Specification Section number followed by a decimal point and then a sequential number (e.g., USC-TC -061000.01).

Resubmittals shall include an alphabetic suffix after another decimal point (e.g., USC-TC -061000.01.A).

- j. Number and title of appropriate Specification Section.
- k. Drawing number and detail references, as appropriate.
- 1. Location(s) where product is to be installed, as appropriate.
- m. Other necessary identification.
- 4. Additional Paper Copies: Unless additional copies are required for final submittal, and unless Architect observes noncompliance with provisions in the Contract Documents, initial submittal may serve as final submittal.
 - a. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Architect.
- 5. Transmittal for Paper Submittals: Assemble each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Architect will return without review submittals received from sources other than Contractor.
 - a. Transmittal Form for Paper Submittals: Provide locations on form for the following information:
 - 1) Project name.
 - 2) Date.
 - 3) Destination (To:).
 - 4) Source (From:).
 - 5) Name and address of Architect.
 - 6) Name of Construction Manager.
 - 7) Name of Contractor.
 - 8) Name of firm or entity that prepared submittal.
 - 9) Names of subcontractor, manufacturer, and supplier.
 - 10) Category and type of submittal.
 - 11) Submittal purpose and description.
 - 12) Specification Section number and title.
 - 13) Specification paragraph number or drawing designation and generic name for each of multiple items.
 - 14) Drawing number and detail references, as appropriate.
 - 15) Indication of full or partial submittal.
 - 16) Transmittal number, numbered consecutively.
 - 17) Submittal and transmittal distribution record.
 - 18) Remarks.
 - 19) Signature of transmitter.

PART 2 - PRODUCTS

2.1 SUBMITTAL PROCEDURES

- A. General Submittal Procedure Requirements: Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.
 - 1. Submit electronic submittals via email as PDF electronic files.
 - a. Architect will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.

- 2. Action Submittals: For paper submittals, submit seven paper copies of each submittal unless otherwise indicated. Architect will return two copies.
- 3. Informational Submittals: Submit one digital copy of each submittal unless otherwise indicated. Architect will not return copies.
- 4. Certificates and Certifications Submittals: Provide a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.
 - a. Provide a digital signature with digital certificate on electronically submitted certificates and certifications where indicated.
 - b. Provide a notarized statement on original paper copy certificates and certifications where indicated.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data, unless submittal based on Architect's digital data drawing files is otherwise permitted.
- D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.
 - 1. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
- E. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
 - 1. Submit product schedule in the following format:
 - a. PDF electronic file.
- F. Coordination Drawing Submittals: Comply with requirements specified in Section 013100 "Project Management and Coordination."
- G. Contractor's Construction Schedule: Comply with requirements specified in Section 013200 "Construction Progress Documentation."
- H. Application for Payment and Schedule of Values: Comply with requirements specified in Section 012900 "Payment Procedures."
- I. Test and Inspection Reports and Schedule of Tests and Inspections Submittals: Comply with requirements specified in Section 014000 "Quality Requirements."

- J. Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Section 017700 "Closeout Procedures."
- K. Maintenance Data: Comply with requirements specified in Section 017823 "Operation and Maintenance Data."
- L. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- M. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
- N. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.

2.2 DELEGATED-DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
 - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF electronic file and three paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.
 - 1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

- A. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Project Closeout and Maintenance Material Submittals: See requirements in Section 017700 "Closeout Procedures."
- C. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date

PROJECT # H27-I851 50001658-25 GMC PROJECT # ACOL180003 03/20/2020

of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ARCHITECT'S ACTION

- A. Action Submittals: Architect will review each submittal, make marks to indicate corrections or revisions required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.
- B. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- C. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.
- D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.
- E. Submittals not required by the Contract Documents may be returned by the Architect without action

END OF SECTION 013300

SECTION 014000 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specific quality-assurance and -control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
 - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
 - 3. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.
 - 4. Specific test and inspection requirements are not specified in this Section.
- C. Special Inspections: No Special Inspections are required for this project.

1.3 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.
- C. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.

- D. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- E. Source Quality-Control Testing: Tests and inspections that are performed at the source, e.g., plant, mill, factory, or shop.
- F. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- G. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- H. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
 - 1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).
- I. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

1.4 CONFLICTING REQUIREMENTS

- A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.5 INFORMATIONAL SUBMITTALS

- A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.
- B. Qualification Data: For Contractor's quality-control personnel.

- C. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility sent to authorities having jurisdiction before starting work on the following systems:
 - 1. Seismic-force-resisting system, designated seismic system, or component listed in the designated seismic system quality-assurance plan prepared by Architect.
- D. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- E. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
 - 1. Specification Section number and title.
 - 2. Entity responsible for performing tests and inspections.
 - 3. Description of test and inspection.
 - 4. Identification of applicable standards.
 - 5. Identification of test and inspection methods.
 - 6. Number of tests and inspections required.
 - 7. Time schedule or time span for tests and inspections.
 - 8. Requirements for obtaining samples.
 - 9. Unique characteristics of each quality-control service.

1.6 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
 - 1. Date of issue.
 - 2. Project title and number.
 - 3. Name, address, and telephone number of testing agency.
 - 4. Dates and locations of samples and tests or inspections.
 - 5. Names of individuals making tests and inspections.
 - 6. Description of the Work and test and inspection method.
 - 7. Identification of product and Specification Section.
 - 8. Complete test or inspection data.
 - 9. Test and inspection results and an interpretation of test results.
 - 10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
 - 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.

- 12. Name and signature of laboratory inspector.
- 13. Recommendations on retesting and reinspecting.
- B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:
 - 1. Name, address, and telephone number of technical representative making report.
 - 2. Statement on condition of substrates and their acceptability for installation of product.
 - 3. Statement that products at Project site comply with requirements.
 - 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
 - 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 - 6. Statement whether conditions, products, and installation will affect warranty.
 - 7. Other required items indicated in individual Specification Sections.
- C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:
 - 1. Name, address, and telephone number of factory-authorized service representative making report.
 - 2. Statement that equipment complies with requirements.
 - 3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 - 4. Statement whether conditions, products, and installation will affect warranty.
 - 5. Other required items indicated in individual Specification Sections.
- D. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

1.7 QUALITY ASSURANCE

- A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

- C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- D. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar in material, design, and extent to those indicated for this Project.
- F. Specialists: Certain Specification Sections require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.
 - 1. Requirements of authorities having jurisdiction shall supersede requirements for specialists.
- G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according to ASTM E 329; and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.
 - 1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
 - 2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.

1.8 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
 - 1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
 - 2. Payment for these services will be made from testing and inspecting allowances, as authorized by Change Orders.
 - 3. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.
- B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.

- 1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
- 2. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.
 - a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
- 3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
- 4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
- 5. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
- 6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Section 013300 "Submittal Procedures."
- D. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.
- E. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.
- F. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
 - 1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
 - 2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
 - 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
 - 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
 - 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
 - 6. Do not perform any duties of Contractor.

- G. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
 - 1. Access to the Work.
 - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 - 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
 - 4. Facilities for storage and field curing of test samples.
 - 5. Preliminary design mix proposed for use for material mixes that require control by testing agency.
 - 6. Security and protection for samples and for testing and inspecting equipment at Project site.
- H. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
 - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.

1.9 SPECIAL TESTS AND INSPECTIONS

- A. Special Tests and Inspections: Owner will engage a qualified testing agency and special inspector to conduct special tests and inspections required by authorities having jurisdiction as the responsibility of Owner, as indicated in Statement of Special Inspections attached to this Section, and as follows:
 - 1. No special Inspections are required for this project.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

- A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:
 - 1. Date test or inspection was conducted.
 - 2. Description of the Work tested or inspected.
 - 3. Date test or inspection results were transmitted to Architect.
 - 4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
 - 1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 014000

SECTION 01 41 50 - SPECIAL INSPECTIONS AND TESTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for quality assurance and quality control.
 - 1. The Owner will hire inspectors, testing companies and special inspections.
 - 2. It is intended to inform the Contractor of the Owner's Quality Assurance Program and the extent of the Contractor's responsibilities.
 - 3. This specification section is also intended to notify the Special Inspector, Testing Laboratory, and other Agents of the Special Inspector of their requirements and responsibilities.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specific quality-assurance and -control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
 - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
 - 3. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section
 - 4. It shall be the Owner's responsibility to contract for special inspections and testing, however, the Contractor shall be responsible for proper notification when inspection is required in the progress of the work, providing access to facilitate the inspection and making corrections necessary when work is not in compliance with the Contract Documents.

C. Scope:

1. This section includes a listing of special inspections to be performed during the progress of this project. A Certificate of Occupancy cannot be issued without documentation of that these inspections have been performed and the work is in conformance with the Contract Documents.

D. Related Sections include the following:

- 1. Division 1 Section "Quality Requirements" shall apply to this section.
- 2. Division 1 Section "Project Management and Coordination" for conducting Preconstruction conference.
- 3. Division 1 Section "Construction Progress Documentation" for developing a schedule of required tests and inspections.
- 4. Division 1 Section "Cutting and Patching" for repair and restoration of construction disturbed by testing and inspecting activities.
- 5. Divisions 2 through 33 Sections for specific test and inspection requirements.

1.3 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.
- C. Source Quality-Control Testing: Tests and inspections that are performed at the source, i.e., plant, mill, factory, or shop.
- D. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- E. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- F. Aiken County Building Official: Governing entity that will issue Certificate of Occupancy.

1.4 GENERAL REQUIREMENTS

- A. Special Inspections and Structural Testing shall be in accordance with Chapter 17 of the 2015 International Building Code.
- B. Inspections shall be in accordance with Chapter 1 of the 2015 International Building Code.
- C. Required Inspections and Tests are described in the "Statement of Special Inspections" attached at the end of this section, and in the individual specification Sections for the items to be inspected or tested.
- D. Prior to the commencement of any work, a pre-construction conference shall be held to review the special inspection requirements for the project. Attendees shall include: the Owner's representative, all Contractors / sub-contractors, Architect, Engineers, Special Inspectors and Special Inspection Agency.

1.5 QUALIFICATIONS:

- A. The Testing Laboratory and individual technicians shall be approved by the Building Official.
- B. The Testing Laboratory shall maintain a full time licensed Professional Engineer (P.E.) on staff who shall certify the test reports. The Engineer shall be responsible for the training of the testing technicians and shall be in responsible charge of the field and laboratory testing operations.
- C. Special Inspections shall be performed by Qualified Inspectors:
 - 1. It is the Special Inspector's responsibility to thoroughly review the approved plans in advance of construction to establish that adequate information is available to conduct the required inspections and tests. All errors and/or omissions in the reviewed plans that create any form of uncertainty or ambiguity shall be resolved through the Architect / Engineer of Record. It is the duty of the Architect / Engineer of Record to coordinate any code interpretation by the building official.

1.6 CONFLICTING REQUIREMENTS

- A. General: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer uncertainties and requirements that are different, but apparently equal, to Architect for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.7 SUBMITTALS (CONTRACTOR RESPONSIBILITY)

- A. Certification from facilities / plants: When work is performed on the premises of facility or plant that is approved by a nationally certified organization (e.g. Steel Joist Institute or American Institute of Steel Construction), shop inspections are not required. The Contractor shall submit to the Architect and the City of Columbia approved Inspector:
 - 1. A copy of fabricator's current certification.
 - 2. A letter stating the name, address, control number of the project and the fabricator's file number. Letter shall state that they are a fabricator for the project, and that upon completion, a Certificate of Compliance will be submitted stating that the fabrication work was performed in accordance with the approved plans, shop drawings, and specifications.
 - 3. NO CERTIFICATE OF OCCUPANCY WILL BE ISSUED BY THE OFFICE OF SCHOOL FACILITIES Building Official until this information has been submitted.

1.8 SUBMITTALS (OWNER HIRED INSPECTORS AND TESTING COMPANIES)

- A. The Special Inspector and Testing Laboratory shall disclose any past or present business relationship or potential conflict of interest with the Contractor or any of the Subcontractors whose work will be inspected or tested.
- B. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
 - 1. Specification Section number and title.
 - 2. Description of test and inspection.
 - 3. Identification of applicable standards.
 - 4. Identification of test and inspection methods.
 - 5. Number of tests and inspections required.
 - 6. Time schedule or time span for tests and inspections.
 - 7. Entity responsible for performing tests and inspections.
 - 8. Requirements for obtaining samples.
 - 9. Unique characteristics of each quality-control service.
- C. Reports: Prepare and submit certified written reports that include the following:
 - 1. Detailed daily and weekly reports shall be prepared of each inspection and test by the Special Inspector and Testing Laboratory. *Inspections and Testing shall occur as needed throughout the project and reports shall be submitted with in a few days of completion of the testing.*
 - 2. Reports shall include:
 - a. Date of issue.
 - b. Project title and number.
 - c. Name, address, and telephone number of testing agency.
 - d. Dates and locations of samples and tests or inspections.
 - e. Names of individuals making tests and inspections.
 - f. Description of the Work and test and inspection method.
 - g. Identification of product and Specification Section.
 - h. Complete test or inspection data.
 - i. Test and inspection results and an interpretation of test results.
 - j. Applicable ASTM Standard.
 - k. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
 - 1. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
 - m. Name and signature of laboratory inspector.
 - n. Engineer's seal and signature on FINAL REPORT only.
 - o. Recommendations on retesting and reinspecting.
 - 3. The Special Inspector shall submit DAILY inspection and test reports to the Architect and Contractor upon their completion.
 - 4. The Special Inspector shall submit all other inspection and test reports to the Architect upon their completion. The Architect will distribute copies of the Weekly Reports and other testing information to the Engineers, Contractors, Owners, and Office of State Engineer as needed.

- 5. Any discrepancies from the Contract Documents found during a Special Inspection shall be immediately reported to the Contractor and the Architect. If the discrepancies are not corrected, the Special Inspector shall notify the Architect. Reports shall document all discrepancies identified and the corrective action taken.
- 6. The Testing Laboratory shall immediately notify the Architect by telephone, fax, or email of any test results which fail to comply with the requirements in the Contract Documents.
- 7. At the completion of the work requiring Special Inspections, each inspection agency and testing laboratory shall provide a statement to the Architect and Building Official that all work was completed in substantial conformance with the Contract Documents and that all appropriate inspections and tests were performed.

D. Final Report of Special Inspections

- 1. The "Final Report of Special Inspections" shall be completed by the Special Inspector and submitted to the Architect and Building Official prior to issuance of a Certificate of Use and Occupancy.
- 2. The "Final Report of the Special Inspections" will certify that all required inspections have been performed and will itemize any discrepancies that were not corrected or resolved.

1.9 QUALITY ASSURANCE

- A. General: Qualifications paragraphs in this Article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or products that are similar to those indicated for this Project in material, design, and extent.

1.10 QUALITY CONTROL

- A. Owner Responsibilities: The Owner will engage and pay for the services of a qualified testing agency or special inspector to conduct special tests and inspections required, and as follows:
 - 1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing / inspections they are to perform.
 - 2. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.
- B. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.

1.11 SPECIAL TESTS AND INSPECTIONS

- A. Special Tests and Inspections: Owner will engage and pay for the services of a qualified testing agency or special inspector to conduct special tests and inspections required by authorities having jurisdiction, and as follows:
 - 1. Verifying that all work requiring special inspections is inspected and/or tested prior to concealment.
 - 2. Verifying that manufacturer maintains detailed fabrication and quality-control procedures and reviewing the completeness and adequacy of those procedures to perform the Work.
 - 3. When work is performed on the premises of facility or plant that is approved by a nationally certified organization (e.g. Steel Joist Institute or American Institute of Steel Construction), shop inspections are not required. The Contractor shall submit to the Architect and the City of Columbia approved Inspector information required under Contractor Submittals.
 - 4. Notifying Architect and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
 - 5. Submitting a certified written report of each test, inspection, and similar quality-control service to Architect, with copy to Contractor and to authorities having jurisdiction.
 - 6. Submitting a final report of special tests and inspections at Substantial Completion, which includes a list of unresolved deficiencies.
 - 7. Interpreting tests and inspections and stating in each report whether tested and inspected work complies with or deviates from the Contract Documents.
 - 8. The Contractor shall be responsible for the cost of any Retesting and reinspecting corrected work which fails to comply with the requirements of the Contract Documents.

1.12 CONTRACTOR RESPONSIBILITIES

- 1. Contractor's Statement of Responsibility: Each Contractor responsible for the construction of a seismic-force-resisting system, designated seismic system.
- B. The Contractor shall cooperate with the Special Inspector and his agents so that the Special Inspections and testing may be performed without hindrance.
- C. The Contractor shall review the "Statement of Special Inspections" and shall be responsible for coordinating and scheduling inspections and tests. The Contractor shall notify the Special Inspector or Testing Laboratory and Architect at least 48 hours in advance of a required inspection or test. Un-inspected work that required inspection may be rejected solely on that basis. Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
 - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.
- D. The Contractor shall keep at the project site the latest set of construction drawings, field sketches, approved and field use shop and erection drawings, and specifications for use by the inspectors and testing technicians.

- E. The Contractor shall provide incidental labor and facilities to provide access to the work to be inspected or tested, to obtain and handle samples at the site or at the source of products to be tested, and to facilitate tests and inspection, storage and curing of test samples. Provide the following:
 - 1. Access to the Work.
 - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 - 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
 - 4. Facilities for storage and field curing of test samples.
 - 5. Preliminary design mix proposed for use for material mixes that require control by testing agency.
 - 6. Security and protection for samples and for testing and inspecting equipment at Project site.
- F. The Special Inspection program shall in no way relieve the Contractor of his obligation to perform the work in accordance with the requirements of the Contract Documents or from implementing an effective Quality Control program. All work that is to be subjected to Special Inspections shall first be reviewed by the Contractor's quality control personnel.
- G. The Contractor shall be solely responsibly for construction site safety.

1.13 LIMITS ON AUTHORITY

- A. The Special Inspector or Testing Laboratory may not release, revoke, alter, or enlarge the requirements on the Contract Documents.
- B. The Special Inspector or Testing Laboratory will not have control over the Contractor's means and methods of construction.
- C. The Special Inspector or Testing Laboratory shall not be responsible for construction site safety.
- D. The Special Inspector or Testing Laboratory has no authority to stop work.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

A. The Contractor shall maintain log at Project site. Post changes and modifications as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
 - 1. Comply with the Contract Document requirements for Division 1 Section "Cutting and Patching."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

PROJECT # H27-I851 50001658-25 GMC PROJECT # ACOL180003 03/20/2020

SCHEDULE OF SPECIAL INSPECTIONS

Project Name: USC 1206 FLORA STREET MILL RENOVATION – FIRE ALARM PACKAGE

Architect's Project No: ACOL180003

Owner: University of South Carolina

Seismic Design Category: "C"

Inspection requirements based on Section 110 of Chapter 1 of the 2015 International Building Code.

MATERIALS	TYPE OF INSPECTION	SPECIFICATION OR CODE REFERENCE	INSPECTION BY		
			ARCH	ENG	Third Party Testing Company
Special Inspections and Testing	See table below				
Mechanical Inspections	Underground inspection after trenches or ditches are excavated and piping installed, prior to backfill in place.	International Mechanical Code 2015 - M107.1 Not Applicable			
	Rough-in inspection prior to	International			Not Applicable
	wall or ceiling membranes	Mechanical Code 2015 - M107.1			To Be Determined
Plumbing Inspections	Underground inspection after trenches or ditches are	International Plumbing Code 2015 - P107.1			
	excavated and piping installed, prior to backfill in place.	2013 - P107.1			To Be Determined
	Rough-in inspection prior to wall or ceiling membranes	International Plumbing Code 2015 - P107.1			To Be Determined
Electrical Inspections	Underground inspection after trenches or ditches are excavated and conduit installed, prior to backfill in place.	National Electric Code 2014 - E702			To Be Determined
	Rough-in inspection prior to wall or ceiling membranes	National Electric Code 2014 - E702			To Be Determined
National Fire Alarm Inspections	Installing Contractor's written Statement of installation and testing	NFPA Section 4.5			To Be Determined

USC 1206 FLORA STREET MILL RENOVATION FIRE ALARM BID PACKAGE

PROJECT # H27-I851 50001658-25 GMC PROJECT # ACOL180003 03/20/2020

Record of Completion Form	NFPA Section 4.5		
			To Be Determined

Special Inspection requirements based on Section 1705 of Chapter 17 of the 2015 International Building Code.

MATERIALS	TYPE OF INSPECTION	SPECIFICATION OR CODE REFERENCE	INSPECTION BY		
			ARCH	ENG	Third Party Testing Company
Fire Protection Components	Seismic attachments to structure and anchorage of seismic braces and anchorage for fire protection piping and equipment.	IBC 1705.12.6			To Be Determined

SEISMIC RESISTANCE

IBC states, in Chapter 17, specific contractor responsibilities, as follows:

- A. Each contractor responsible for the construction of a main seismic-force resisting system, designated seismic system or a seismic-resisting component listed in the statement of special inspections shall submit a written statement of responsibility to the building official and the owner prior to the commencement of work on the system or component. The contractor's statement of responsibility shall contain acknowledgment of awareness of the special requirements contained in the statement of special inspections.
- B. It is the inspectors' responsibility to verify that the contractor conforms to this section of the code. Furthermore, it is vital to understand that mechanical, electrical and plumbing seismic and vibration analysis and inspections are required and must include the seismic protection for electrical raceways, and equipment; plumbing, piping and relate equipment; and, seismic protection for mechanical systems.

END OF SECTION 014150

SECTION 014200 - REFERENCES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.3 INDUSTRY STANDARDS

A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.

- B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.
- C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.
 - 1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

1.4 ABBREVIATIONS AND ACRONYMS

- A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States."
- B. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.
 - 1. AABC Associated Air Balance Council; www.aabc.com.
 - 2. AAMA American Architectural Manufacturers Association; www.aamanet.org.
 - 3. AAPFCO Association of American Plant Food Control Officials; www.aapfco.org.
 - 4. AASHTO American Association of State Highway and Transportation Officials; www.transportation.org.
 - 5. AATCC American Association of Textile Chemists and Colorists; www.aatcc.org.
 - 6. ABMA American Bearing Manufacturers Association; www.americanbearings.org.
 - 7. ACI American Concrete Institute; (Formerly: ACI International); www.concrete.org.
 - 8. ACPA American Concrete Pipe Association; www.concrete-pipe.org.
 - 9. AEIC Association of Edison Illuminating Companies, Inc. (The); www.aeic.org.
 - 10. AF&PA American Forest & Paper Association; www.afandpa.org.
 - 11. AGA American Gas Association; www.aga.org.
 - 12. AHAM Association of Home Appliance Manufacturers; www.aham.org.
 - 13. AHRI Air-Conditioning, Heating, and Refrigeration Institute (The); www.ahrinet.org.
 - 14. AI Asphalt Institute; www.asphaltinstitute.org.
 - 15. AIA American Institute of Architects (The); www.aia.org.
 - 16. AISC American Institute of Steel Construction; www.aisc.org.
 - 17. AISI American Iron and Steel Institute; www.steel.org.
 - 18. AITC American Institute of Timber Construction; www.aitc-glulam.org.
 - 19. AMCA Air Movement and Control Association International, Inc.; www.amca.org.
 - 20. ANSI American National Standards Institute; www.ansi.org.
 - 21. AOSA Association of Official Seed Analysts, Inc.; www.aosaseed.com.
 - 22. APA APA The Engineered Wood Association; www.apawood.org.
 - 23. APA Architectural Precast Association; www.archprecast.org.
 - 24. API American Petroleum Institute; www.api.org.
 - 25. ARI Air-Conditioning & Refrigeration Institute; (See AHRI).
 - 26. ARI American Refrigeration Institute; (See AHRI).
 - 27. ARMA Asphalt Roofing Manufacturers Association; www.asphaltroofing.org.

- 28. ASCE American Society of Civil Engineers; www.asce.org.
- ASCE/SEI American Society of Civil Engineers/Structural Engineering Institute; (See ASCE).
- 30. ASHRAE American Society of Heating, Refrigerating and Air-Conditioning Engineers; www.ashrae.org.
- 31. ASME ASME International; (American Society of Mechanical Engineers); www.asme.org.
- 32. ASSE American Society of Safety Engineers (The); www.asse.org.
- 33. ASSE American Society of Sanitary Engineering; www.asse-plumbing.org.
- 34. ASTM ASTM International; (American Society for Testing and Materials International); www.astm.org.
- 35. ATIS Alliance for Telecommunications Industry Solutions; www.atis.org.
- 36. AWEA American Wind Energy Association; www.awea.org.
- 37. AWI Architectural Woodwork Institute; www.awinet.org.
- 38. AWMAC Architectural Woodwork Manufacturers Association of Canada; www.awmac.com.
- 39. AWPA American Wood Protection Association; (Formerly: American Wood-Preservers' Association); www.awpa.com.
- 40. AWS American Welding Society; www.aws.org.
- 41. AWWA American Water Works Association; www.awwa.org.
- 42. BHMA Builders Hardware Manufacturers Association; www.buildershardware.com.
- 43. BIA Brick Industry Association (The); www.gobrick.com.
- 44. BICSI BICSI, Inc.; www.bicsi.org.
- 45. BIFMA BIFMA International; (Business and Institutional Furniture Manufacturer's Association); www.bifma.com.
- 46. BISSC Baking Industry Sanitation Standards Committee; www.bissc.org.
- 47. BOCA BOCA; (Building Officials and Code Administrators International Inc.); (See ICC).
- 48. BWF Badminton World Federation; (Formerly: International Badminton Federation); www.bwfbadminton.org.
- 49. CDA Copper Development Association; www.copper.org.
- 50. CEA Canadian Electricity Association; www.electricity.ca.
- 51. CEA Consumer Electronics Association; www.ce.org.
- 52. CFFA Chemical Fabrics & Film Association, Inc.; www.chemicalfabricsandfilm.com.
- 53. CFSEI Cold-Formed Steel Engineers Institute; www.cfsei.org.
- 54. CGA Compressed Gas Association; www.cganet.com.
- 55. CIMA Cellulose Insulation Manufacturers Association; www.cellulose.org.
- 56. CISCA Ceilings & Interior Systems Construction Association; www.cisca.org.
- 57. CISPI Cast Iron Soil Pipe Institute; www.cispi.org.
- 58. CLFMI Chain Link Fence Manufacturers Institute; www.chainlinkinfo.org.
- 59. CPA Composite Panel Association; www.pbmdf.com.
- 60. CRI Carpet and Rug Institute (The); www.carpet-rug.org.
- 61. CRRC Cool Roof Rating Council; www.coolroofs.org.
- 62. CRSI Concrete Reinforcing Steel Institute; www.crsi.org.
- 63. CSA Canadian Standards Association; www.csa.ca.
- 64. CSA CSA International; (Formerly: IAS International Approval Services); www.csa-international.org.
- 65. CSI Construction Specifications Institute (The); www.csinet.org.
- 66. CSSB Cedar Shake & Shingle Bureau; www.cedarbureau.org.
- 67. CTI Cooling Technology Institute; (Formerly: Cooling Tower Institute); www.cti.org.

- 68. CWC Composite Wood Council; (See CPA).
- 69. DASMA Door and Access Systems Manufacturers Association; www.dasma.com.
- 70. DHI Door and Hardware Institute; www.dhi.org.
- 71. ECA Electronic Components Association; www.ec-central.org.
- 72. ECAMA Electronic Components Assemblies & Materials Association; (See ECA).
- 73. EIA Electronic Industries Alliance; (See TIA).
- 74. EIMA EIFS Industry Members Association; www.eima.com.
- 75. EJMA Expansion Joint Manufacturers Association, Inc.; www.ejma.org.
- 76. ESD ESD Association; (Electrostatic Discharge Association); www.esda.org.
- 77. ESTA Entertainment Services and Technology Association; (See PLASA).
- 78. EVO Efficiency Valuation Organization; www.evo-world.org.
- 79. FIBA Federation Internationale de Basketball; (The International Basketball Federation); www.fiba.com.
- 80. FIVB Federation Internationale de Volleyball; (The International Volleyball Federation); www.fivb.org.
- 81. FM Approvals FM Approvals LLC; www.fmglobal.com.
- 82. FM Global FM Global; (Formerly: FMG FM Global); www.fmglobal.com.
- 83. FRSA Florida Roofing, Sheet Metal & Air Conditioning Contractors Association, Inc.; www.floridaroof.com.
- 84. FSA Fluid Sealing Association; www.fluidsealing.com.
- 85. FSC Forest Stewardship Council U.S.; www.fscus.org.
- 86. GA Gypsum Association; www.gypsum.org.
- 87. GANA Glass Association of North America; www.glasswebsite.com.
- 88. GS Green Seal; www.greenseal.org.
- 89. HI Hydraulic Institute; www.pumps.org.
- 90. HI/GAMA Hydronics Institute/Gas Appliance Manufacturers Association; (See AHRI).
- 91. HMMA Hollow Metal Manufacturers Association; (See NAAMM).
- 92. HPVA Hardwood Plywood & Veneer Association; www.hpva.org.
- 93. HPW H. P. White Laboratory, Inc.; www.hpwhite.com.
- 94. IAPSC International Association of Professional Security Consultants; www.iapsc.org.
- 95. IAS International Approval Services; (See CSA).
- 96. ICBO International Conference of Building Officials; (See ICC).
- 97. ICC International Code Council; www.iccsafe.org.
- 98. ICEA Insulated Cable Engineers Association, Inc.; www.icea.net.
- 99. ICPA International Cast Polymer Alliance; www.icpa-hq.org.
- 100. ICRI International Concrete Repair Institute, Inc.; www.icri.org.
- 101. IEC International Electrotechnical Commission; www.iec.ch.
- 102. IEEE Institute of Electrical and Electronics Engineers, Inc. (The); www.ieee.org.
- 103. IES Illuminating Engineering Society; (Formerly: Illuminating Engineering Society of North America); www.ies.org.
- 104. IESNA Illuminating Engineering Society of North America; (See IES).
- 105. IEST Institute of Environmental Sciences and Technology; www.iest.org.
- 106. IGMA Insulating Glass Manufacturers Alliance; www.igmaonline.org.
- 107. IGSHPA International Ground Source Heat Pump Association; www.igshpa.okstate.edu.
- 108. ILI Indiana Limestone Institute of America, Inc.; www.iliai.com.
- 109. Intertek Intertek Group; (Formerly: ETL SEMCO; Intertek Testing Service NA); www.intertek.com.
- 110. ISA International Society of Automation (The); (Formerly: Instrumentation, Systems, and Automation Society); www.isa.org.
- 111. ISAS Instrumentation, Systems, and Automation Society (The); (See ISA).

- 112. ISFA International Surface Fabricators Association; (Formerly: International Solid Surface Fabricators Association); www.isfanow.org.
- 113. ISO International Organization for Standardization; www.iso.org.
- 114. ISSFA International Solid Surface Fabricators Association; (See ISFA).
- 115. ITU International Telecommunication Union; www.itu.int/home.
- 116. KCMA Kitchen Cabinet Manufacturers Association; www.kcma.org.
- 117. LMA Laminating Materials Association; (See CPA).
- 118. LPI Lightning Protection Institute; www.lightning.org.
- 119. MBMA Metal Building Manufacturers Association; www.mbma.com.
- 120. MCA Metal Construction Association; www.metalconstruction.org.
- 121. MFMA Maple Flooring Manufacturers Association, Inc.; www.maplefloor.org.
- 122. MFMA Metal Framing Manufacturers Association, Inc.; www.metalframingmfg.org.
- 123. MHIA Material Handling Industry of America; www.mhia.org.
- 124. MIA Marble Institute of America; www.marble-institute.com.
- 125. MMPA Moulding & Millwork Producers Association; (Formerly: Wood Moulding & Millwork Producers Association); www.wmmpa.com.
- 126. MPI Master Painters Institute; www.paintinfo.com.
- 127. MSS Manufacturers Standardization Society of The Valve and Fittings Industry Inc.; www.mss-hq.org.
- 128. NAAMM National Association of Architectural Metal Manufacturers; www.naamm.org.
- 129. NACE NACE International; (National Association of Corrosion Engineers International); www.nace.org.
- 130. NADCA National Air Duct Cleaners Association; www.nadca.com.
- 131. NAIMA North American Insulation Manufacturers Association; www.naima.org.
- 132. NBGQA National Building Granite Quarries Association, Inc.; www.nbgqa.com.
- 133. NCAA National Collegiate Athletic Association (The); www.ncaa.org.
- 134. NCMA National Concrete Masonry Association; www.ncma.org.
- 135. NEBB National Environmental Balancing Bureau; www.nebb.org.
- 136. NECA National Electrical Contractors Association; www.necanet.org.
- 137. NeLMA Northeastern Lumber Manufacturers Association; www.nelma.org.
- 138. NEMA National Electrical Manufacturers Association; www.nema.org.
- 139. NETA InterNational Electrical Testing Association; www.netaworld.org.
- 140. NFHS National Federation of State High School Associations; www.nfhs.org.
- 141. NFPA NFPA; (National Fire Protection Association); www.nfpa.org.
- 142. NFPA NFPA International; (See NFPA).
- 143. NFRC National Fenestration Rating Council; www.nfrc.org.
- 144. NHLA National Hardwood Lumber Association; www.nhla.com.
- 145. NLGA National Lumber Grades Authority; www.nlga.org.
- 146. NOFMA National Oak Flooring Manufacturers Association; (See NWFA).
- 147. NOMMA National Ornamental & Miscellaneous Metals Association; www.nomma.org.
- 148. NRCA National Roofing Contractors Association; www.nrca.net.
- 149. NRMCA National Ready Mixed Concrete Association; www.nrmca.org.
- 150. NSF NSF International; (National Sanitation Foundation International); www.nsf.org.
- 151. NSPE National Society of Professional Engineers; www.nspe.org.
- 152. NSSGA National Stone, Sand & Gravel Association; www.nssga.org.
- 153. NTMA National Terrazzo & Mosaic Association, Inc. (The); www.ntma.com.
- 154. NWFA National Wood Flooring Association; www.nwfa.org.
- 155. PCI Precast/Prestressed Concrete Institute; www.pci.org.
- 156. PDI Plumbing & Drainage Institute; www.pdionline.org.

- 157. PLASA PLASA; (Formerly: ESTA Entertainment Services and Technology Association); www.plasa.org.
- 158. RCSC Research Council on Structural Connections; www.boltcouncil.org.
- 159. RFCI Resilient Floor Covering Institute; www.rfci.com.
- 160. RIS Redwood Inspection Service; www.redwoodinspection.com.
- 161. SAE SAE International; (Society of Automotive Engineers); www.sae.org.
- 162. SCTE Society of Cable Telecommunications Engineers; www.scte.org.
- 163. SDI Steel Deck Institute; www.sdi.org.
- 164. SDI Steel Door Institute; www.steeldoor.org.
- 165. SEFA Scientific Equipment and Furniture Association; www.sefalabs.com.
- 166. SEI/ASCE Structural Engineering Institute/American Society of Civil Engineers; (See ASCE).
- 167. SIA Security Industry Association; www.siaonline.org.
- 168. SJI Steel Joist Institute; www.steeljoist.org.
- 169. SMA Screen Manufacturers Association; www.smainfo.org.
- 170. SMACNA Sheet Metal and Air Conditioning Contractors' National Association; www.smacna.org.
- 171. SMPTE Society of Motion Picture and Television Engineers; www.smpte.org.
- 172. SPFA Spray Polyurethane Foam Alliance; www.sprayfoam.org.
- 173. SPIB Southern Pine Inspection Bureau; www.spib.org.
- 174. SPRI Single Ply Roofing Industry; www.spri.org.
- 175. SRCC Solar Rating and Certification Corporation; www.solar-rating.org.
- 176. SSINA Specialty Steel Industry of North America; www.ssina.com.
- 177. SSPC SSPC: The Society for Protective Coatings; www.sspc.org.
- 178. STI Steel Tank Institute; www.steeltank.com.
- 179. SWI Steel Window Institute; www.steelwindows.com.
- 180. SWPA Submersible Wastewater Pump Association; www.swpa.org.
- 181. TCA Tilt-Up Concrete Association; www.tilt-up.org.
- 182. TCNA Tile Council of North America, Inc.; (Formerly: Tile Council of America); www.tileusa.com.
- 183. TEMA Tubular Exchanger Manufacturers Association, Inc.; www.tema.org.
- 184. TIA Telecommunications Industry Association; (Formerly: TIA/EIA Telecommunications Industry Association/Electronic Industries Alliance); www.tiaonline.org.
- 185. TIA/EIA Telecommunications Industry Association/Electronic Industries Alliance; (See TIA).
- 186. TMS The Masonry Society; www.masonrysociety.org.
- 187. TPI Truss Plate Institute; www.tpinst.org.
- 188. TPI Turfgrass Producers International; www.turfgrasssod.org.
- 189. TRI Tile Roofing Institute; www.tileroofing.org.
- 190. UBC Uniform Building Code; (See ICC).
- 191. UL Underwriters Laboratories Inc.; www.ul.com.
- 192. UNI Uni-Bell PVC Pipe Association; www.uni-bell.org.
- 193. USAV USA Volleyball; www.usavolleyball.org.
- 194. USGBC U.S. Green Building Council; www.usgbc.org.
- 195. USITT United States Institute for Theatre Technology, Inc.; www.usitt.org.
- 196. WASTEC Waste Equipment Technology Association; www.wastec.org.
- 197. WCLIB West Coast Lumber Inspection Bureau; www.wclib.org.
- 198. WCMA Window Covering Manufacturers Association; www.wcmanet.org.
- 199. WDMA Window & Door Manufacturers Association; www.wdma.com.

- 200. WI Woodwork Institute; (Formerly: WIC Woodwork Institute of California); www.wicnet.org.
- 201. WMMPA Wood Moulding & Millwork Producers Association; (See MMPA).
- 202. WSRCA Western States Roofing Contractors Association; www.wsrca.com.
- 203. WPA Western Wood Products Association; www.wwpa.org.
- C. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. This information is believed to be accurate as of the date of the Contract Documents.
 - 1. DIN Deutsches Institut für Normung e.V.; www.din.de.
 - 2. IAPMO International Association of Plumbing and Mechanical Officials; www.iapmo.org.
 - 3. ICC International Code Council; www.iccsafe.org.
 - 4. ICC-ES ICC Evaluation Service, LLC; www.icc-es.org.
- D. Federal Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. Information is subject to change and is up-to-date as of the date of the Contract Documents.
 - 1. COE Army Corps of Engineers; www.usace.army.mil.
 - 2. CPSC Consumer Product Safety Commission; www.cpsc.gov.
 - 3. DOC Department of Commerce; National Institute of Standards and Technology; www.nist.gov.
 - 4. DOD Department of Defense; http://dodssp.daps.dla.mil.
 - 5. DOE Department of Energy; www.energy.gov.
 - 6. EPA Environmental Protection Agency; www.epa.gov.
 - 7. FAA Federal Aviation Administration; www.faa.gov.
 - 8. FG Federal Government Publications; www.gpo.gov.
 - 9. GSA General Services Administration; www.gsa.gov.
 - 10. HUD Department of Housing and Urban Development; www.hud.gov.
 - 11. LBL Lawrence Berkeley National Laboratory; Environmental Energy Technologies Division; http://eetd.lbl.gov.
 - 12. OSHA Occupational Safety & Health Administration; www.osha.gov.
 - 13. SD Department of State; www.state.gov.
 - 14. TRB Transportation Research Board; National Cooperative Highway Research Program; www.trb.org.
 - 15. USDA Department of Agriculture; Agriculture Research Service; U.S. Salinity Laboratory; www.ars.usda.gov.
 - 16. USDA Department of Agriculture; Rural Utilities Service; www.usda.gov.
 - 17. USDJ Department of Justice; Office of Justice Programs; National Institute of Justice; www.ojp.usdoj.gov.
 - 18. USP U.S. Pharmacopeia; www.usp.org.
 - 19. USPS United States Postal Service; www.usps.com.
- E. Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the standards and regulations in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.

- 1. CFR Code of Federal Regulations; Available from Government Printing Office; www.gpo.gov/fdsys.
- 2. DOD Department of Defense; Military Specifications and Standards; Available from Department of Defense Single Stock Point; http://dodssp.daps.dla.mil.
- 3. DSCC Defense Supply Center Columbus; (See FS).
- 4. FED-STD Federal Standard; (See FS).
- 5. FS Federal Specification; Available from Department of Defense Single Stock Point; http://dodssp.daps.dla.mil.
 - a. Available from Defense Standardization Program; www.dsp.dla.mil.
 - b. Available from General Services Administration; www.gsa.gov.
 - c. Available from National Institute of Building Sciences/Whole Building Design Guide; www.wbdg.org/ccb.
- 6. MILSPEC Military Specification and Standards; (See DOD).
- 7. USAB United States Access Board; www.access-board.gov.
- 8. USATBCB U.S. Architectural & Transportation Barriers Compliance Board; (See USAB).
- F. State Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.
 - 1. CBHF State of California; Department of Consumer Affairs; Bureau of Electronic Appliance and Repair, Home Furnishings and Thermal Insulation; www.bearhfti.ca.gov.
 - 2. CCR California Code of Regulations; Office of Administrative Law; California Title 24 Energy Code; www.calregs.com.
 - 3. CDHS California Department of Health Services; (See CDPH).
 - 4. CDPH California Department of Public Health; Indoor Air Quality Program; www.caliaq.org.
 - 5. CPUC California Public Utilities Commission; www.cpuc.ca.gov.
 - 6. SCAQMD South Coast Air Quality Management District; www.aqmd.gov.
 - 7. TFS Texas Forest Service; Forest Resource Development and Sustainable Forestry; http://txforestservice.tamu.edu.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 014200

SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.

B. Related Requirements:

1. Section 01 10 00 "Summary" for work restrictions and limitations on utility interruptions.

1.3 USE CHARGES

- A. General: Installation and removal of and use charges for temporary facilities shall be included in the Contract Sum unless otherwise indicated.
- B. Water and Sewer Service from Existing System: Water from Owner's existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.
- C. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

1.4 QUALITY ASSURANCE

- A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.
- C. Accessible Temporary Egress: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines and ICC/ANSI A117.1.

1.5 PROJECT CONDITIONS

A. Temporary Use of Permanent Facilities: Engage Installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Temporary Partitions: Provide temporary partitions of wood stud construction or fencing with windscreen separating the existing stadium areas from the construction area.

2.2 TEMPORARY FACILITIES

- A. Field Offices, General: Field Office Trailer is **NOT** required. Utilize an existing room at the Existing Building as the construction field office, if authorized by the Owner.
 - 1. Protect and preserve all existing equipment that is to remain in like-new or current condition. Repair or replace any damage to the existing space. Vacate space at least 2 weeks prior to substantial completion or as directed by the owner.
- B. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment for construction operations.
 - 1. Store combustible materials apart from building.
 - 2. Locate material storage in locations acceptable to the owner.

2.3 EQUIPMENT

A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.
- B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Install temporary service or connect to existing service.
 - 1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.
 - 2. Use of the Existing utilities on site is permitted by the Owner. Notify the Owner of connection locations and types of services being used. Notify the owner of any changes to the existing utilities/
- B. Water Service: Connect to Owner's existing water service facilities. Clean and maintain water service facilities in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.
- C. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.
- D. Isolation of Work Areas in Occupied Facilities: Prevent dust, fumes, and odors from entering occupied areas.
- E. Electric Power Service: Connect to Owner's existing electric power service. Maintain equipment in a condition acceptable to Owner.
- F. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.
 - 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.

3.3 SUPPORT FACILITIES INSTALLATION

- A. Parking: Use designated areas of Owner's existing parking areas for construction personnel.
- B. Project Signs: Unauthorized signs are not permitted.
 - 1. Temporary Signs: Provide other signs as indicated and as required to inform public and individuals seeking entrance to Project.
 - a. Provide temporary, directional signs for construction personnel and visitors.
 - 2. Maintain and touchup signs so they are legible at all times.
- C. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of authorities having jurisdiction. Comply with progress cleaning requirements in Section 017300 "Execution."
- D. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.
 - 1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.

2. Protect existing flooring in the facility. Repair and replace and damage caused by Lifts and Hoists.

3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.
 - 1. Provide temporary partitions that separate the work area from other portions of the building, including dust protection.
- B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.
 - 1. Comply with work restrictions specified in Section 011000 "Summary."
- C. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals so Project will be free of pests and their residues at Substantial Completion. Perform control operations lawfully, using environmentally safe materials.
- D. Security Enclosure and Lockup: Install temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each work day.
- E. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire-prevention program.
 - 1. Prohibit smoking in construction areas.
 - 2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition according to requirements of authorities having jurisdiction.
 - 3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.

END OF SECTION 015000

SECTION 016000 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.

B. Related Requirements:

- 1. Section 012500 "Substitution Procedures" for requests for substitutions.
- 2. Section 014200 "References" for applicable industry standards for products specified.

1.3 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
 - 3. Comparable Product: Product that is demonstrated and approved through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a specific manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of additional manufacturers named in the specification.

1.4 ACTION SUBMITTALS

- A. Comparable Product Requests: Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Include data to indicate compliance with the requirements specified in "Comparable Products" Article.
 - 2. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
 - a. Form of Approval: As specified in Section 013300 "Submittal Procedures."
- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Section 013300 "Submittal Procedures." Show compliance with requirements.

1.5 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.
 - 1. Each contractor is responsible for providing products and construction methods compatible with products and construction methods of other contractors.
 - 2. If a dispute arises between contractors over concurrently selectable but incompatible products, Architect will determine which products shall be used.

1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

B. Delivery and Handling:

- 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
- 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
- 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
- 4. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.

C. Storage:

- 1. Store products to allow for inspection and measurement of quantity or counting of units.
- 2. Store materials in a manner that will not endanger Project structure.
- 3. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
- 4. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
- 5. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
- 6. Protect stored products from damage and liquids from freezing.
- 7. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

1.7 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
 - 1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
 - 2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.
 - 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
 - 2. Specified Form: When specified forms are included with the Specifications, prepare a written document using indicated form properly executed.
 - 3. See other Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Section 017700 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.

- 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
- 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
- 3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
- 4. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
- 5. Or Equal: For products specified by name and accompanied by the term "or equal," or "or approved equal," or "or approved," comply with requirements in "Comparable Products" Article to obtain approval for use of an unnamed product.

B. Product Selection Procedures:

- 1. Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
- 2. Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.

3. Products:

- a. Nonrestricted List: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed, or an unnamed product, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product.
- 4. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.
- C. Visual Matching Specification: Where Specifications require "match Architect's sample", provide a product that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches.
 - 1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Section 012500 "Substitution Procedures" for proposal of product.
- D. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, select a product that complies with

requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

- A. Conditions for Consideration: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:
 - 1. Evidence that the proposed product does not require revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
 - 2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
 - 3. Evidence that proposed product provides specified warranty.
 - 4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
 - 5. Samples, if requested.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

SECTION 017300 - EXECUTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work including, but not limited to, the following:
 - 1. Construction layout.
 - 2. Field engineering and surveying.
 - 3. Installation of the Work.
 - 4. Cutting and patching.
 - 5. Progress cleaning.
 - 6. Starting and adjusting.
 - 7. Protection of installed construction.
 - 8. Correction of Work.

1.3 DEFINITIONS

- A. Cutting: Removal of in-place construction necessary to permit installation or performance of other work.
- B. Patching: Fitting and repair work required to restore construction to original conditions after installation of other work.

1.4 QUALITY ASSURANCE

- A. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.
 - 1. Structural Elements: When cutting and patching structural elements, notify Architect of locations and details of cutting and await directions from Architect before proceeding. Shore, brace, and support structural elements during cutting and patching. Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection
 - 2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in

increased maintenance or decreased operational life or safety. Operational elements include the following:

- a. Primary operational systems and equipment.
- b. Mechanical systems piping and ducts.
- c. Fire-detection and -alarm systems.
- d. Electrical wiring systems.
- e. Operating systems of special construction.
- 3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety.
 - a. Water, moisture, or vapor barriers.
 - b. Membranes and flashings.
 - c. Equipment supports.
 - d. Piping, ductwork, vessels, and equipment.
- 4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- B. Cutting and Patching Conference: Before proceeding, meet at Project site with parties involved in cutting and patching, including mechanical and electrical trades. Review areas of potential interference and conflict. Coordinate procedures and resolve potential conflicts before proceeding.
- C. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of products and equipment.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.
- B. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
 - 1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place materials.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Existing Conditions: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and

verify the existence and location of underground utilities, mechanical and electrical systems, and other construction affecting the Work.

- 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; underground electrical services, and other utilities.
- 2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
 - 1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
 - 2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
 - 3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Written Report: Where a written report listing conditions detrimental to performance of the Work is required by other Sections, include the following:
 - 1. Description of the Work.
 - 2. List of detrimental conditions, including substrates.
 - 3. List of unacceptable installation tolerances.
 - 4. Recommended corrections.
- D. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- B. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- C. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents caused by differing field conditions outside the control of Contractor, submit a request for information to Architect according to requirements in Section 013100 "Project Management and Coordination."

3.3 CONSTRUCTION LAYOUT

- A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks. If discrepancies are discovered, notify Architect promptly.
- B. General: Lay out the Work using accepted surveying practices.
 - 1. Establish benchmarks and control points to set lines and levels at each story of construction and elsewhere as needed to locate each element of Project.
 - 2. Establish limits on use of Project site.
 - 3. Establish dimensions within tolerances indicated. Do not scale Drawings to obtain required dimensions.
 - 4. Inform installers of lines and levels to which they must comply.
 - 5. Check the location, level and plumb, of every major element as the Work progresses.
 - 6. Notify Architect when deviations from required lines and levels exceed allowable tolerances.
- C. Building Lines and Levels: Locate and lay out control lines and levels for structures, building foundations, column grids, and floor levels, including those required for mechanical and electrical work. Transfer survey markings and elevations for use with control lines and levels. Level foundations and piers from two or more locations.

3.4 FIELD ENGINEERING

- A. Identification: Owner will identify existing benchmarks, control points, and property corners.
- B. Reference Points: Locate existing permanent benchmarks, control points, and similar reference points before beginning the Work. Preserve and protect permanent benchmarks and control points during construction operations.
 - 1. Do not change or relocate existing benchmarks or control points without prior written approval of Architect. Report lost or destroyed permanent benchmarks or control points promptly. Report the need to relocate permanent benchmarks or control points to Architect before proceeding.
 - 2. Replace lost or destroyed permanent benchmarks and control points promptly. Base replacements on the original survey control points.

3.5 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
 - 1. Make vertical work plumb and make horizontal work level.
 - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
 - 3. Conceal pipes, ducts, and wiring in finished areas unless otherwise indicated.

- 4. Maintain minimum headroom clearance and ceiling heights specified. Notify the Architect if ceiling heights cannot be reasonably achieved through coordination between trades and if any obstruction less than 96" is encountered.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on site and placement in permanent locations.
- F. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- G. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions.
 - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
 - 2. Allow for building movement, including thermal expansion and contraction.
 - 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.
- I. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
- J. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

3.6 CUTTING AND PATCHING

- A. Cutting and Patching, General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 - 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.

- B. Temporary Support: Provide temporary support of work to be cut.
- C. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- D. Adjacent Occupied Areas: Where interference with use of adjoining areas or interruption of free passage to adjoining areas is unavoidable, coordinate cutting and patching according to requirements in Section 011000 "Summary."
- E. Existing Utility Services and Mechanical/Electrical Systems: Where existing services/systems are required to be removed, relocated, or abandoned, bypass such services/systems before cutting to minimize interruption to occupied areas.
- F. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
 - 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 - 2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
 - 3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
 - 4. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
 - 5. Proceed with patching after construction operations requiring cutting are complete.
- G. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other work. Patch with durable seams that are as invisible as practicable. Provide materials and comply with installation requirements specified in other Sections, where applicable.
 - 1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
 - 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will minimize evidence of patching and refinishing.
 - a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
 - b. Restore damaged pipe covering to its original condition.
 - 3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.

- a. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch. Provide additional coats until patch blends with adjacent surfaces.
- 4. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition and ensures thermal and moisture integrity of building enclosure.
- H. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

3.7 OWNER-INSTALLED PRODUCTS

- A. Site Access: Provide access to Project site for Owner's construction personnel.
- B. Coordination: Coordinate construction and operations of the Work with work performed by Owner's construction personnel.
 - Construction Schedule: Inform Owner of Contractor's preferred construction schedule for Owner's portion of the Work. Adjust construction schedule based on a mutually agreeable timetable. Notify Owner if changes to schedule are required due to differences in actual construction progress.
 - 2. Preinstallation Conferences: Include Owner's construction personnel at preinstallation conferences covering portions of the Work that are to receive Owner's work. Attend preinstallation conferences conducted by Owner's construction personnel if portions of the Work depend on Owner's construction.

3.8 PROGRESS CLEANING

- A. General: Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.
 - 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
 - 2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F (27 deg C).
 - 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
 - a. Use containers intended for holding waste materials of type to be stored.
 - 4. Coordinate progress cleaning for joint-use areas where Contractor and other contractors are working concurrently.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
 - 1. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.

- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.
- F. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways. Comply with waste disposal requirements in Section 015000 "Temporary Facilities and Controls."
- H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- J. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.9 STARTING AND ADJUSTING

- A. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- B. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.
- C. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Manufacturer's Field Service: Comply with qualification requirements in Section 014000 "Quality Requirements."

3.10 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.

END OF SECTION 017300

SECTION 01 73 10 - CUTTING AND PATCHING

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes procedural requirements for cutting and patching.
- B. See Divisions 2 through 16 Sections for specific requirements and limitations applicable to cutting and patching individual parts of the Work.

1.2 SUBMITTALS

- A. Cutting and Patching Proposal: Submit a proposal describing procedures at least 10 days before the time cutting and patching will be performed, requesting approval to proceed. Include the following information:
 - 1. Extent: Describe cutting and patching, show how they will be performed, and indicate why they cannot be avoided.
 - 2. Changes to In-Place Construction: Describe anticipated results. Include changes to structural elements and operating components as well as changes in building's appearance and other significant visual elements.
 - 3. Products: List products to be used and firms or entities that will perform the Work.
 - 4. Dates: Indicate when cutting and patching will be performed.
 - 5. Structural Elements: Where cutting and patching involve adding reinforcement to structural elements, submit details and engineering calculations showing integration of reinforcement with original structure.

1.3 **OUALITY ASSURANCE**

- A. Structural Elements: Do not cut and patch structural elements in a manner that could change their load-carrying capacity or load-deflection ratio.
- B. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.
- C. Visual Requirements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch construction exposed on the exterior or in occupied spaces in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.

1.4 WARRANTY

A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during cutting and patching operations, by methods and with materials so as not to void existing warranties.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.
- B. In-Place Materials: Use materials identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
 - 1. If identical materials are unavailable or cannot be used, use materials that, when installed, will match the visual and functional performance of in-place materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine surfaces to be cut and patched and conditions under which cutting and patching are to be performed.
 - 1. Compatibility: Before patching, verify compatibility with and suitability of substrates, including compatibility with in-place finishes or primers.
 - 2. Proceed with installation only after unsafe or unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Temporary Support: Provide temporary support of Work to be cut.
- B. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- C. Adjoining Areas: Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.

3.3 PERFORMANCE

A. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.

- 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
 - 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots as small as possible, neatly to size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 - 2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
 - 3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
 - 4. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
 - 5. Proceed with patching after construction operations requiring cutting are complete.
- C. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other Work. Patch with durable seams that are as invisible as possible. Provide materials and comply with installation requirements specified in other Sections.
 - 1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate integrity of installation.
 - 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will eliminate evidence of patching and refinishing.
- D. Cleaning: Clean areas and spaces where cutting and patching are performed. Completely remove paint, mortar, oils, putty, and similar materials.

END OF SECTION

SECTION 01 73 20 - SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 **SUMMARY**

- A. This Section includes the following:
 - 1. Demolition and removal of selected portions of existing building or structure.
 - 2. Demolition and removal of selected site elements.
 - 3. Salvage of existing items to be reused or recycled.
- B. See Division 23 Sections for demolishing, cutting, patching, or relocating mechanical items.
- C. See Division 26 Sections for demolishing, cutting, patching, or relocating electrical items.

1.2 **DEFINITIONS**

- A. Remove: Detach items from existing construction and legally dispose of them off-site, unless indicated to be removed and salvaged or removed and reinstalled.
- B. Remove and Salvage: Detach items from existing construction and deliver them to Owner.
- C. Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated.
- D. Existing to Remain: Existing items of construction that are not to be removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.3 MATERIALS OWNERSHIP

A. Except for items or materials indicted to be reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, demolished materials shall become Contractor's property and shall be removed from Project site.

1.4 SUBMITTALS

- A. Schedule of Selective Demolition Activities: Indicate detailed sequence of selective demolition and removal work, with starting and ending dates for each activity, interruption of utility services, use of stairs, and locations of temporary partitions and means of egress.
- B. Inventory: After selective demolition is complete, submit a list of items that have been removed and salvaged.

1.5 QUALITY ASSURANCE

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ANSI A10.6 and NFPA 241.
- C. Predemolition Conference: Conduct conference at Project site.

1.6 PROJECT CONDITIONS

- A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted. Provide not less than 7 days notice to Owner of activities that will affect Owner's operations. Owner permission is also necessary prior to performing any utility disruptions.
- B. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities.
 - 1. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from authorities having jurisdiction.
- C. Owner assumes no responsibility for condition of areas to be selectively demolished.
 - 1. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
- D. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- E. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.
 - 1. If materials suspected of containing hazardous materials are encountered, do not disturb; immediately notify Architect and Owner. Owner will remove hazardous materials under a separate contract.
- F. Storage or sale of removed items or materials on-site is not permitted.
- G. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.

1.7 WARRANTY

A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties.

PART 2 - PRODUCTS

2.1 REPAIR MATERIALS

- A. Use repair materials identical to existing materials.
 - 1. If identical materials are unavailable or cannot be used for exposed surfaces, use materials that visually match existing adjacent surfaces to the fullest extent possible.
 - 2. Use materials whose installed performance equals or surpasses that of existing materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped.
- B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- C. Inventory and record the condition of items to be removed and reinstalled and items to be removed and salvaged.
- D. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Architect.
- E. Engage a professional engineer to survey condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective demolition operations.

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems: Maintain services/systems indicated to remain and protect them against damage during selective demolition operations.
- B. Do not interrupt existing utilities serving occupied or operating facilities unless authorized in writing by Owner and authorities having jurisdiction. Provide temporary services during interruptions to existing utilities, as acceptable to Owner and to authorities having jurisdiction.
 - 1. Provide at least 7 days prior notice to Owner if shutdown of service is required for any utility interruption.
- C. Service/System Requirements: Locate, identify, disconnect, and seal or cap off indicated utility services and mechanical/electrical systems serving areas to be selectively demolished.
 - 1. Arrange to shut off indicated utilities with utility companies.

- 2. If services/systems are required to be removed, relocated, or abandoned, before proceeding with selective demolition provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
- 3. Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit after bypassing.
- D. Utility Requirements: Refer to Division 15 and 16 Sections for shutting off, disconnecting, removing, and sealing or capping utilities. Do not start selective demolition work until utility disconnecting and sealing have been completed and verified in writing.

3.3 PREPARATION

- A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 - 1. Comply with requirements for access and protection specified in Division 1 Section "Temporary Facilities and Controls."
- B. Temporary Facilities: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
- C. Temporary Shoring: Provide and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.
- D. Temporary Partitions: Erect and maintain dustproof partitions and temporary enclosures to limit dust and dirt migration and to separate areas from fumes and noise.

3.4 SELECTIVE DEMOLITION

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations.
 - 1. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction.
 - 2. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 - 3. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain fire watch and portable fire-suppression devices during flame-cutting operations.
 - 4. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.

- 5. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
- 6. Dispose of demolished items and materials promptly.
- B. Existing Facilities: Comply with building manager's requirements for using and protecting stairs, walkways, loading docks, building entries, and other building facilities during selective demolition operations.
- C. Removed and Salvaged Items:
 - 1. Clean salvaged items.
 - 2. Pack or crate items after cleaning. Identify contents of containers.
 - 3. Store items in a secure area until delivery to Owner.
 - 4. Transport items to Owner's storage area on-site.
 - 5. Protect items from damage during transport and storage.
- D. Removed and Reinstalled Items:
 - 1. Clean and repair items to functional condition adequate for intended reuse. Paint equipment to match new equipment.
 - 2. Pack or crate items after cleaning and repairing. Identify contents of containers.
 - 3. Protect items from damage during transport and storage.
 - 4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.
- E. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and cleaned and reinstalled in their original locations after selective demolition operations are complete.

3.5 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Promptly dispose of demolished materials. Do not allow demolished materials to accumulate on-site.
- B. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

END OF SECTION

SECTION 017700 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Substantial Completion procedures.
 - 2. Final completion procedures.
 - 3. Warranties.
 - 4. Final cleaning.
 - 5. Repair of the Work.

B. Related Requirements:

- 1. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.
- 2. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.3 ACTION SUBMITTALS

- A. Product Data: For cleaning agents.
- B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- C. Certified List of Incomplete Items: Final submittal at Final Completion.

1.4 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.

1.5 SUBSTANTIAL COMPLETION PROCEDURES

A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.

- B. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
 - 1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
 - 2. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Architect. Label with manufacturer's name and model number where applicable.
 - a. Schedule of Maintenance Material Items: Prepare and submit schedule of maintenance material submittal items, including name and quantity of each item and name and number of related Specification Section. Obtain Architect's signature for receipt of submittals.

1.6 FINAL COMPLETION PROCEDURES

- A. Submittals Prior to Final Completion: Before requesting final inspection for determining final completion, complete the following:
 - 1. Submit a final Application for Payment according to Section 012900 "Payment Procedures."
 - 2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
 - 3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
- B. Inspection: Submit a written request for final inspection.

1.7 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
 - 1. Organize list of spaces in sequential order.
 - 2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
 - 3. Include the following information at the top of each page:
 - a. Project name.
 - b. Date.
 - c. Name of Architect.
 - d. Name of Contractor.
 - 4. Submit list of incomplete items in the following format:
 - a. MS Excel electronic file. Architect will return annotated file.
 - b. PDF electronic file. Architect will return annotated file.

1.8 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated, or when delay in submittal of warranties might limit Owner's rights under warranty.
- B. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.
 - 1. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch (215-by-280-mm) paper.
 - 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
 - 3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
 - 4. Warranty Electronic File: Scan warranties and bonds and assemble complete warranty and bond submittal package into a single indexed electronic PDF file with links enabling navigation to each item. Provide bookmarked table of contents at beginning of document.
- C. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities of rubbish, waste material, litter, and other foreign substances.
 - b. Remove tools, construction equipment, machinery, and surplus material from Project site.

- c. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
- d. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
- e. Sweep concrete floors broom clean in unoccupied spaces.
- f. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.
- g. Remove labels that are not permanent.
- h. Wipe surfaces of mechanical and electrical equipment and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
- i. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
- j. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
- k. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency.
- l. Leave Project clean and ready for occupancy.
- C. Construction Waste Disposal: Comply with waste disposal requirements in Section 015000 "Temporary Facilities and Controls."

3.2 REPAIR OF THE WORK

- A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Repair or remove and replace defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.
 - 1. Remove and replace chipped, scratched, and broken glass, reflective surfaces, and other damaged transparent materials.
 - 2. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that that already show evidence of repair or restoration.
 - a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.
 - 3. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.
 - 4. Replace burned-out bulbs, bulbs noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.

SECTION 01 78 20 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
 - 1. Emergency manuals.
 - 2. Operation manuals for systems, subsystems, and equipment.
 - 3. Maintenance manuals for the care and maintenance of products, materials, finishes, and systems and equipment.
- B. See Divisions 2 through 16 Sections for specific operation and maintenance manual requirements for the Work in those Sections.

1.2 SUBMITTALS

- A. Submission of Operating and Maintenance Manuals: When the HVAC systems are approximately 75 percent complete, submit four sets of manuals for Architect's review.
 - 1. Architect will submit one copy with review comments to the Owner for approval.
- B. Initial Submittal: Include a complete operation and maintenance directory. Architect will return one copy of draft and mark whether general scope and content of manual are acceptable.

C. Final Submittal:

1. Correct or modify each manual to comply with Architect's comments. Provide one electronic copy of the final manual on CDROM or Flash Drive in Adobe PDF format. Provide PDF bookmarks for each section and subsection of the manual. Submit corrected manual within 15 days of receipt of Architect's comments.

1.3 COORDINATION

- A. Where operation and maintenance documentation includes information on installations by more than one factory-authorized service representative, assemble and coordinate information furnished by representatives and prepare manuals.
- B. Purge manuals prior to submitting to Architect to include only technical data related to in-place construction.

PART 2 - PRODUCTS

2.1 OPERATION AND MAINTENANCE DOCUMENTATION DIRECTORY

- A. Organization: Include a section in the directory for each of the following:
 - 1. List of documents.
 - 2. List of systems.
 - 3. List of equipment.
 - 4. Table of contents.
- B. List of Systems and Subsystems: List systems alphabetically. Include references to operation and maintenance manuals that contain information about each system.
- C. List of Equipment: List equipment for each system, organized alphabetically by system. For pieces of equipment not part of system, list alphabetically in separate list.
- D. Tables of Contents: Include a table of contents for each emergency, operation, and maintenance manual.
- E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation according to ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

2.2 MANUALS, GENERAL

- A. Organization: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain a title page, table of contents, and manual contents.
- B. Title Page: Enclose title page in transparent plastic sleeve. Include the following information:
 - 1. Subject matter included in manual.
 - 2. Name and address of Project.
 - 3. Name and address of Owner.
 - 4. Date of submittal.
 - 5. Name, address, and telephone number of Contractor.
 - 6. Name and address of Architect.
 - 7. Cross-reference to related systems in other operation and maintenance manuals.
- C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.

- D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.
 - 1. Binders: Heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, sized to hold 8-1/2-by-11-inch (215-by-280-mm) paper; with clear plastic sleeve on spine to hold label describing contents and with pockets inside covers to hold folded oversize sheets.
 - a. Identify each binder on front and spine, with printed title "OPERATION AND MAINTENANCE MANUAL," Project title or name, and subject matter of contents. Indicate volume number for multiple-volume sets.
 - 2. Dividers: Heavy-paper dividers with plastic-covered tabs for each section. Mark each tab to indicate contents. Include typed list of products and major components of equipment included in the section on each divider, cross-referenced to Specification Section number and title of Project Manual.
 - 3. Protective Plastic Sleeves: Transparent plastic sleeves designed to enclose diagnostic software diskettes for computerized electronic equipment.
 - 4. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.
 - a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
 - b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

2.3 EMERGENCY MANUALS

- A. Content: Organize manual into a separate section for type of emergency, emergency instructions, and emergency procedures.
- B. Type of Emergency: Where applicable for each type of emergency indicated below, include instructions and procedures for each system, subsystem, piece of equipment, and component for fire, flood, gas leak, water leak, power failure, water outage, equipment failure, and chemical release or spill.
- C. Emergency Instructions: Describe and explain warnings, trouble indications, error messages, and similar codes and signals. Include responsibilities of Owner's operating personnel for notification of Installer, supplier, and manufacturer to maintain warranties.
- D. Emergency Procedures: Include instructions on stopping, shutdown instructions for each type of emergency, operating instructions for conditions outside normal operating limits, and required sequences for electric or electronic systems.

2.4 OPERATION MANUALS

- A. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and equipment descriptions, operating standards, operating procedures, operating logs, wiring and control diagrams, and license requirements.
- B. Descriptions: Include the following:
 - 1. Product name and model number.
 - 2. Manufacturer's name.
 - 3. Equipment identification with serial number of each component.
 - 4. Equipment function.
 - 5. Operating characteristics.
 - 6. Limiting conditions.
 - 7. Performance curves.
 - 8. Engineering data and tests.
 - 9. Complete nomenclature and number of replacement parts.
- C. Operating Procedures: Include start-up, break-in, and control procedures; stopping and normal shutdown instructions; routine, normal, seasonal, and weekend operating instructions; and required sequences for electric or electronic systems.
- D. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.
- E. Piped Systems: Diagram piping as installed, and identify color-coding where required for identification.

2.5 PRODUCT MAINTENANCE MANUAL

- A. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
- B. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual.
- C. Product Information: Include the following, as applicable:
 - 1. Product name and model number.
 - 2. Manufacturer's name.
 - 3. Color, pattern, and texture.
 - 4. Material and chemical composition.
 - 5. Reordering information for specially manufactured products.

- D. Maintenance Procedures: Include manufacturer's written recommendations and inspection procedures, types of cleaning agents, methods of cleaning, schedule for cleaning and maintenance, and repair instructions.
- E. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.
- F. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

2.6 SYSTEMS AND EQUIPMENT MAINTENANCE MANUAL

- A. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranty and bond information, as described below.
- B. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual.
- C. Manufacturers' Maintenance Documentation: Manufacturers' maintenance documentation including maintenance instructions, drawings and diagrams for maintenance, nomenclature of parts and components, and recommended spare parts for each component part or piece of equipment.
- D. Maintenance Procedures: Include test and inspection instructions, troubleshooting guide, disassembly instructions, and adjusting instructions, and demonstration and training videotape if available, that detail essential maintenance procedures.
- E. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.
- F. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.
- G. Maintenance Service Contracts: Include copies of maintenance agreements with name and telephone number of service agent.
- H. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

PART 3 - EXECUTION

3.1 MANUAL PREPARATION

- A. Operation and Maintenance Documentation Directory: Prepare a separate manual that provides an organized reference to emergency, operation, and maintenance manuals.
- B. Emergency Manual: Assemble a complete set of emergency information indicating procedures for use by emergency personnel and by Owner's operating personnel for types of emergencies indicated.
- C. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.
- D. Operation and Maintenance Manuals: Assemble a complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.
- E. Manufacturers' Data: Where manuals contain manufacturers' standard printed data, include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
- F. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in Record Drawings to ensure correct illustration of completed installation.
 - 1. Do not use original Project Record Documents as part of operation and maintenance manuals.
- G. Comply with Division 1 Section "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

END OF SECTION

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for project record documents, including the following:
 - 1. Record Drawings.
 - 2. Record Product Data.
 - 3. Miscellaneous record submittals.
- B. Related Requirements:
 - 1. Section 017700 "Closeout Procedures" for general closeout procedures.

1.3 CLOSEOUT SUBMITTALS

- A. Record Drawings: Comply with the following:
 - 1. Number of Copies: Submit copies of record Drawings as follows:
 - a. Initial Submittal:
 - 1) Submit PDF electronic files of scanned record prints.
 - 2) Architect will indicate whether general scope of changes, additional information recorded, and quality of drafting are acceptable.
 - b. Final Submittal:
 - 1) Submit PDF electronic files of scanned record prints and 1 set(s) of prints.
 - 2) Print each drawing, whether or not changes and additional information were recorded.
- B. Record Product Data: Submit annotated PDF electronic files and directories of each submittal.
 - 1. Where record Product Data are required as part of operation and maintenance manuals, submit duplicate marked-up Product Data as a component of manual.
- C. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Submit annotated PDF electronic files and directories of each submittal.

PART 2 - PRODUCTS

2.1 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.
 - 1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
 - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
 - b. Record and check the markup before enclosing concealed installations.
 - 2. Content: Types of items requiring marking include, but are not limited to, the following:
 - a. Dimensional changes to Drawings.
 - b. Revisions to details shown on Drawings.
 - c. Revisions to routing of piping and conduits.
 - d. Actual equipment locations.
 - e. Locations of concealed internal utilities.
 - f. Changes made by Change Order or Construction Change Directive.
 - g. Changes made following Architect's written orders.
 - h. Field records for variable and concealed conditions.
 - 3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
 - 4. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
 - 5. Mark important additional information that was either shown schematically or omitted from original Drawings.
- B. Format: Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.
 - 1. Record Prints: Organize record prints into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
 - 2. Format: Annotated PDF electronic file with comment function enabled.
 - 3. Identification: As follows:
 - a. Project name.
 - b. Date.
 - c. Designation "PROJECT RECORD DRAWINGS."
 - d. Name of Architect.
 - e. Name of Contractor.

2.2 RECORD PRODUCT DATA

- A. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.
 - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 - 2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
- B. Format: Submit record Product Data as annotated PDF electronic file.
 - 1. Include record Product Data directory organized by Specification Section number and title, electronically linked to each item of record Product Data.

2.3 MISCELLANEOUS RECORD SUBMITTALS

- A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.
- B. Format: Submit miscellaneous record submittals as PDF electronic file or scanned PDF electronic file(s) of marked-up miscellaneous record submittals.
 - 1. Include miscellaneous record submittals directory organized by Specification Section number and title, electronically linked to each item of miscellaneous record submittals.

PART 3 - EXECUTION

3.1 RECORDING AND MAINTENANCE

- A. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.
- B. Maintenance of Record Documents and Samples: Store record documents and Samples in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Architect's reference during normal working hours.

END OF SECTION 017839

SECTION 078413 - PENETRATION FIRESTOPPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Penetrations in fire-resistance-rated walls.
- 2. Penetrations in horizontal assemblies.
- 3. Joints in or between fire-resistance-rated constructions.
- 4. Joints at exterior curtain-wall/floor intersections.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Product Schedule: For each penetration firestopping system. Include location and design designation of qualified testing and inspecting agency.
 - 1. Where Project conditions require modification to a qualified testing and inspecting agency's illustration for a particular penetration firestopping condition, submit illustration, with modifications marked, approved by penetration firestopping manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer.
- B. Installer Certificates: From Installer indicating penetration firestopping has been installed in compliance with requirements and manufacturer's written recommendations.
- C. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for penetration firestopping.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: A firm experienced in installing penetration firestopping similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful performance. Qualifications include having the necessary

experience, staff, and training to install manufacturer's products per specified requirements. Manufacturer's willingness to sell its penetration firestopping products to Contractor or to Installer engaged by Contractor does not in itself confer qualification on buyer.

- B. Fire-Test-Response Characteristics: Penetration firestopping shall comply with the following requirements:
 - 1. Penetration firestopping tests are performed by a qualified testing agency acceptable to authorities having jurisdiction.
 - 2. Penetration firestopping is identical to those tested per testing standard referenced in "Penetration Firestopping" Article. Provide rated systems complying with the following requirements:
 - a. Penetration firestopping products bear classification marking of qualified testing and inspecting agency.
 - b. Classification markings on penetration firestopping correspond to designations listed by the following:
 - 1) UL in its "Fire Resistance Directory."
- C. Preinstallation Conference: Conduct conference at Project site.

1.6 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install penetration firestopping when ambient or substrate temperatures are outside limits permitted by penetration firestopping manufacturers or when substrates are wet because of rain, frost, condensation, or other causes.
- B. Install and cure penetration firestopping per manufacturer's written instructions using natural means of ventilations or, where this is inadequate, forced-air circulation.

1.7 COORDINATION

- A. One installer entity shall perform all penetration firestopping and joint firestopping system installations required for the project.
- B. Coordinate construction of openings and penetrating items to ensure that penetration and joint firestopping is installed according to specified requirements.
- C. Coordinate sizing of sleeves, openings, core-drilled holes, or cut openings to accommodate penetration firestopping.
- D. Notify Owner's testing agency at least seven days in advance of penetration firestopping installations; confirm dates and times on day preceding each series of installations.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. <u>Manufacturers:</u> Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. 3M Fire Protection Products.
 - 2. Grace Construction Products; W.R. Grace & Co. -- Conn.
 - 3. Hilti, Inc.
 - 4. <u>Tremco, Inc</u>.

2.2 PENETRATION FIRESTOPPING

- A. Provide penetration firestopping that is produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of construction penetrated. Penetration firestopping systems shall be compatible with one another, with the substrates forming openings, and with penetrating items if any.
- B. Penetrations in Vertical Assemblies including Fire-Resistance-Rated Walls: Provide penetration firestopping with ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa).
 - 1. Fire-resistance-rated walls include fire walls fire-barrier walls and fire partitions.
 - 2. F-Rating: Not less than the fire-resistance rating of constructions penetrated.
- C. Penetrations in Horizontal Assemblies: Provide penetration firestopping with ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa).
 - 1. Horizontal assemblies include floors floor/ceiling assemblies and ceiling membranes of roof/ceiling assemblies.
 - a. Provide penetration firestopping at rated and not rated floor assemblies between floors and slab edge systems such as curtain wall assemblies as well as fire rated locations such as other horizontal floor/ceiling assemblies, roof assemblies, etc.
 - 2. F-Rating: At least 1 hour, but not less than the fire-resistance rating of constructions penetrated.
 - 3. T-Rating: At least 1 hour, but not less than the fire-resistance rating of constructions penetrated except for floor penetrations within the cavity of a wall.
- D. Exposed Penetration Firestopping: Provide products with flame-spread and smoke-developed indexes of less than 25 and 450, respectively, as determined per ASTM E 84.
- E. Accessories: Provide components for each penetration firestopping system that are needed to install fill materials and to maintain ratings required. Use only those components specified by penetration firestopping manufacturer and approved by qualified testing and inspecting agency for firestopping indicated.

- 1. Permanent forming/damming/backing materials, including the following:
 - a. Slag-wool-fiber or rock-wool-fiber insulation.
 - b. Sealants used in combination with other forming/damming/backing materials to prevent leakage of fill materials in liquid state.
 - c. Fire-rated form board.
 - d. Fillers for sealants.
- 2. Temporary forming materials.
- 3. Substrate primers.
- 4. Collars.
- 5. Steel sleeves.

2.3 FILL MATERIALS

- A. Cast-in-Place Firestop Devices: Factory-assembled devices for use in cast-in-place concrete floors and consisting of an outer metallic sleeve lined with an intumescent strip, a radial extended flange attached to one end of the sleeve for fastening to concrete formwork, and a neoprene gasket.
- B. Latex Sealants: Single-component latex formulations that do not re-emulsify after cure during exposure to moisture.
- C. Firestop Devices: Factory-assembled collars formed from galvanized steel and lined with intumescent material sized to fit specific diameter of penetrant.
- D. Intumescent Composite Sheets: Rigid panels consisting of aluminum-foil-faced elastomeric sheet bonded to galvanized-steel sheet.
- E. Intumescent Putties: Nonhardening dielectric, water-resistant putties containing no solvents, inorganic fibers, or silicone compounds.
- F. Intumescent Wrap Strips: Single-component intumescent elastomeric sheets with aluminum foil on one side.
- G. Mortars: Prepackaged dry mixes consisting of a blend of inorganic binders, hydraulic cement, fillers, and lightweight aggregate formulated for mixing with water at Project site to form a nonshrinking, homogeneous mortar.
- H. Pillows/Bags: Reusable heat-expanding pillows/bags consisting of glass-fiber cloth cases filled with a combination of mineral-fiber, water-insoluble expansion agents, and fire-retardant additives. Where exposed, cover openings with steel-reinforcing wire mesh to protect pillows/bags from being easily removed.
- I. Silicone Foams: Multicomponent, silicone-based liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.
- J. Silicone Sealants: Single-component, silicone-based, neutral-curing elastomeric sealants of grade indicated below:

1. Grade: Pourable (self-leveling) formulation for openings in floors and other horizontal surfaces, and nonsag formulation for openings in vertical and sloped surfaces, unless indicated firestopping limits use of nonsag grade for both opening conditions.

2.4 MIXING

A. For those products requiring mixing before application, comply with penetration firestopping manufacturer's written instructions for accurate proportioning of materials, water (if required), type of mixing equipment, selection of mixer speeds, mixing containers, mixing time, and other items or procedures needed to produce products of uniform quality with optimum performance characteristics for application indicated.

2.5 JOINT FIRESTOPPING SYSTEMS

- A. Joint Firestopping Systems: Systems that resist spread of fire, passage of smoke and other gases, and maintain original fire-resistance rating of assemblies in or between which joint firestopping systems are installed. Joint firestopping systems shall accommodate building movements without impairing their ability to resist the passage of fire and hot gases.
- B. Joints in or between Fire-Resistance-Rated Construction: Provide joint firestopping systems with ratings determined per ASTM E 1966 or UL 2079.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. 3M Fire Protection Products.
 - b. Hilti, Inc.
 - c. Specified Technologies, Inc.
 - 2. Fire-Resistance Rating: Equal to or exceeding the fire-resistance rating of the wall, floor, or roof in or between which it is installed.
- C. Joints at Exterior Curtain-Wall/Floor Intersections: Provide joint firestopping systems with rating determined per ASTM E 2307.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. 3M Fire Protection Products.
 - b. Hilti, Inc.
 - c. Specified Technologies, Inc.
 - 2. F-Rating: Equal to or exceeding the fire-resistance rating of the floor assembly.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for opening configurations, penetrating items, substrates, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Cleaning: Clean out openings immediately before installing penetration firestopping to comply with manufacturer's written instructions and with the following requirements:
 - 1. Remove from surfaces of opening substrates and from penetrating items foreign materials that could interfere with adhesion of penetration firestopping.
 - 2. Clean opening substrates and penetrating items to produce clean, sound surfaces capable of developing optimum bond with penetration firestopping. Remove loose particles remaining from cleaning operation.
 - 3. Remove laitance and form-release agents from concrete.
- B. Priming: Prime substrates where recommended in writing by manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.
- C. Masking Tape: Use masking tape to prevent penetration firestopping from contacting adjoining surfaces that will remain exposed on completion of the Work and that would otherwise be permanently stained or damaged by such contact or by cleaning methods used to remove stains. Remove tape as soon as possible without disturbing firestopping's seal with substrates.

3.3 INSTALLATION

- A. General: Install penetration firestopping and fire-resistive joint systems to comply with manufacturer's written installation instructions and published drawings for products and applications indicated.
- B. Install forming materials and other accessories of types required to support fill materials during their application and in the position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.
 - 1. After installing fill materials and allowing them to fully cure, remove combustible forming materials and other accessories not indicated as permanent components of firestopping.
- C. Install fill materials for firestopping by proven techniques to produce the following results:
 - 1. Fill voids and cavities formed by openings, forming materials, accessories, and penetrating items as required to achieve fire-resistance ratings indicated.
 - 2. Apply materials so they contact and adhere to substrates formed by openings and penetrating items.
 - 3. For fill materials that will remain exposed after completing the Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.
- D. Install elastomeric fill materials for fire-resistive joint systems by proven techniques to produce the following results:
 - 1. Elastomeric fill voids and cavities formed by joints and forming materials as required to achieve fire-resistance ratings indicated.

- 2. Apply elastomeric fill materials so they contact and adhere to substrates formed by joints.
- 3. For elastomeric fill materials that will remain exposed after completing the Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

3.4 IDENTIFICATION

- A. Wall Identification: Permanently label walls containing penetration firestopping systems with the words "FIRE AND/OR SMOKE BARRIER PROTECT ALL OPENINGS," using lettering not less than 3 inches (76 mm) high and with minimum 0.375-inch (9.5-mm) strokes.
 - 1. Locate in accessible concealed floor, floor-ceiling, or attic space at 15 feet (4.57 m) from end of wall and at intervals not exceeding 30 feet (9.14 m).
- B. Identify penetration firestopping with preprinted metal or plastic labels. Attach labels permanently to surfaces adjacent to and within 6 inches (150 mm) of firestopping edge so labels will be visible to anyone seeking to remove penetrating items or firestopping. Use mechanical fasteners or self-adhering-type labels with adhesives capable of permanently bonding labels to surfaces on which labels are placed. Include the following information on labels:
 - 1. The words "Warning Penetration Firestopping Do Not Disturb. Notify Building Management of Any Damage."
 - 2. Contractor's name, address, and phone number.
 - 3. Designation of applicable testing and inspecting agency.
 - 4. Date of installation.
 - 5. Manufacturer's name.
 - 6. Installer's name.
- C. Joint Identification: Identify joint firestopping systems with legible metal or plastic labels. Attach labels permanently to surfaces adjacent to and within 6 inches (150 mm) of joint edge so labels are visible to anyone seeking to remove or joint firestopping system. Use mechanical fasteners or self-adhering-type labels with adhesives capable of permanently bonding labels to surfaces on which labels are placed. Include the following information on labels:
 - 1. The words "Warning Joint Firestopping Do Not Disturb. Notify Building Management of Any Damage."
 - 2. Contractor's name, address, and phone number.
 - 3. Designation of applicable testing agency.
 - 4. Date of installation.
 - 5. Manufacturer's name.
 - 6. Installer's name.

3.5 FIELD QUALITY CONTROL

- A. Owner will engage a qualified testing agency to perform tests and inspections according to ASTM E 2393.
- B. Where deficiencies are found or penetration firestopping is damaged or removed because of testing, repair or replace penetration firestopping to comply with requirements.
- C. Do not proceed with enclosing penetration firestopping with other construction until all inspection reports are issued and the above ceiling areas have been inspected by OSF. At double wall

construction (where one wall is rated and the parallel wall is non-rated), provide minimum 8" x 8" access openings in the non-rated walls for installation and subsequent inspection of the firestopping.

D. Proceed with enclosing joint firestopping systems with other construction only after inspection reports are issued and installations comply with requirements.

3.6 CLEANING AND PROTECTION

- A. Clean off excess fill materials adjacent to openings as the Work progresses by methods and with cleaning materials that are approved in writing by penetration firestopping manufacturers and that do not damage materials in which openings occur.
- B. Provide final protection and maintain conditions during and after installation that ensure that penetration firestopping is without damage or deterioration at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, immediately cut out and remove damaged or deteriorated penetration firestopping and install new materials to produce systems complying with specified requirements.

3.7 PENETRATION FIRESTOPPING SCHEDULE

- A. The Firestopping Subcontractor shall submit a Firestopping Schedule illustrating each proposed assembly and location for use to the Architect for review prior to installation.
- B. Where UL-classified systems are indicated, they refer to system numbers in UL's "Fire Resistance Directory" under product Category XHEZ.
 - 1. Provide a schedule for the following:
 - a. Firestopping with No Penetrating Items
 - b. Firestopping for Metallic Pipes, Conduit, or Tubing
 - c. Firestopping for Nonmetallic Pipe, Conduit, or Tubing
 - d. Firestopping for Electrical Cables
 - e. Firestopping for Cable Trays with Electric Cables
 - f. Firestopping for Insulated Pipes
 - g. Firestopping for Miscellaneous Electrical Penetrants
 - h. Firestopping for Miscellaneous Mechanical Penetrants
 - i. Firestopping for Groupings of Penetrants
- C. Where UL-classified systems are indicated, they refer to system numbers in UL's "Fire Resistance Directory" under product Category XHBN or Category XHDG.
 - 1. Provide a schedule for the following:
 - a. Floor-to-Floor, Joint Firestopping Systems
 - b. Wall-to-Wall, Joint Firestopping Systems
 - c. Floor-to-Wall, Joint Firestopping Systems
 - d. Head-of-Wall, Fire-Resistive Joint Firestopping Systems
 - e. Bottom-of-Wall, Joint Firestopping Systems
 - f. Wall-to-Wall, Joint Firestopping Systems Intended for Use as Corner Guards
 - g. Perimeter Joint Firestopping Systems

END OF SECTION 078413

SECTION 260500 - COMMON WORK RESULTS FOR ELECTRICAL

PART 1 - GENERAL

1.1 SCOPE OF WORK

- A. Provide all labor, materials, equipment and supervision to construct complete and operable electrical systems as indicated on the drawings and specified herein.
- B. All materials and equipment used shall be new, undamaged and free from any defects.

1.2 RELATED DOCUMENTS AND OTHER INFORMATION

A. The general provisions of the Contract, including General and Supplementary Conditions and General Requirements, apply to the portions of work specified in each and every Section, individually and collectively.

1.3 PRODUCT WARRANTIES

- A. Provide manufacturer's standard printed commitment in reference to a specific product and normal application, stating that certain acts of restitution will be performed for the Purchaser or Owner by the manufacturer, when and if the product fails within certain operational conditions and time limits. Where the warranty requirements of a specific specification section exceed the manufacturer's standard warranty, the more stringent requirements will apply and modified manufacturer's warranty shall be provided. In no case shall the manufacturer's warranty be less than one (1) year from the date of substantial completion.
 - 1. Where manufacturer's warranty lists a start date of PO or date of ship, contractor shall purchase extended warranty to ensure warranty period extends to a minimum of 1 year after date of substantial completion.

1.4 PRODUCT SUBSTITUTIONS

A. General: Materials specified by manufacturer's name shall be used unless prior approval of an alternate is given by addenda. Requests for substitutions must be received in the office of the Architect at least 10 days prior to opening of bids.

1.5 SUBMITTAL REQUIREMENTS

- A. Submit for review by the Engineer Architect a schedule with engineering data of materials and equipment to be incorporated in the work. Submittals shall be supported by descriptive materials, i.e., catalog sheets, product data sheets, diagrams, performance curves and charts published by the manufacturer, warranties, etc., to show conformance to Specifications and Plan requirements; model numbers alone shall not be acceptable. Data submitted for review shall contain all information to indicate compliance with Contract Documents. Complete electrical characteristics shall be provided for all equipment. Submittals for lighting fixtures shall include Photometric Data. The Engineer reserves the right to require samples of any equipment to be submitted for review.
- B. The purpose of shop drawing review is to demonstrate to the Architect that the Contractor

- understands the design concept. The Architect's review of such drawings, schedules, or cuts shall not relieve the Contractor from responsibility for deviations from the drawings or specifications unless he has, in writing, called the Architect's attention to such deviation at the time of submission, and received written permission from the Architect for such deviations.
- C. Where cut sheets include an entire product family, mark all specific items to be utilized for this project on equipment cut sheets. Generic cut sheets with no indication of which items on the cut sheet shall be used will be rejected.
- D. Response to Submittals: Shop drawings shall be noted with the following classifications:
 - 1. "Reviewed": No corrections, no marks. Contractor shall submit copies for distribution.
 - 2. "Provide as Corrected": A few minor corrections. Items may be ordered as marked up without further resubmission. Submit shall submit copies for distribution. Formally correct prior to submitting O&M manuals.
 - 3. "Revise and Resubmit": Minor corrections. Items may be ordered at the Contractor's option. Contractor shall resubmit documents with corrections noted.
 - 4. "Rejected": Major corrections required or not in accordance with the contract documents. Contractor shall correct and resubmit documents.

1.6 ELECTRICAL DRAWINGS

- A. Electrical contract drawings are diagrammatic and indicate the general arrangement of electrical equipment. Do not scale electrical plans. Obtain all dimensions from the Architect's dimensioned drawings and field measurements. The Contractor shall review Architectural plans for door swings and built-in equipment; conditions indicated on those plans shall govern for this work.
- B. Coordinate installation of electrical equipment with the structural and mechanical equipment and access thereto. Coordinate exterior electrical work with civil and landscaping work.
- C. Discrepancies shown on different drawings, between drawings and specifications or between documents and field conditions shall be installed to provide the better quality or greater quantity of work; or, comply with the more stringent requirement; either or both in accordance with the A/E's interpretation.

1.7 ELECTRICAL WORK SCHEDULE

- A. After the award of contract, the Contractor shall prepare a detailed schedule (aka milestone chart, or Gantt chart) for review by the Architect/Engineer and Owner at least 10-days prior to beginning work. The Contractor Project Schedule (CPS) shall indicate detailed activities for the projected life of the project. The CPS shall consist of detailed activities and their restraining relationships. It will also detail manpower usage throughout the project. Specific items shall include (but not limited to) the following:
 - 1. Date of on-site arrival of electrical equipment and accessories required for system installation.
 - 2. Estimated dates and duration of all service outages.
 - 3. Estimated start date and completion date for the demolition of each existing panelboard.

- 4. Estimated start date and completion date for the installation of each panelboard.
- 5. Estimated dates and duration of required work access to areas that are not in the current phase, or scope of work.

1.8 SUBMITTALS – GENERAL ELECTRICAL

- A. Electrical coordination drawings shall be provided as described below:
 - 1. Electrical Rooms: Provide layouts of all electrical rooms using the dimensions of equipment and accessories furnished. Locate all ducts and piping entering or crossing these spaces.
 - 2. Feeders over 100 Amps: The routing of main feeders is not shown on the drawings. Actual routing shall be determined by the contractor in accordance with the specifications and shall be coordinated with work by other trades. For underground lines, show all utility crossings.
 - 3. Drawings Format: Drawings shall be prepared at a scale of no less than 1/16" = 1'-0" for feeder routes and 1/4" = 1'-0" for electrical rooms / equipment yards.

 Drawing shall be titled to define Project Name, Drawing subject and date prepared.

 Drawings are to be prepared in AutoCAD or compatible software.
- B. Firestopping Submittals shall be provided for each proposed system type prior to installation. Submittal shall include the following:
 - 1. Firestopping Materials
 - 2. Firestopping Installation Drawings for each conduit penetration, cable in metal sleeve penetration, and blank metal sleeve penetration for each type of wall / floor construction encountered.

1.9 SYSTEMS REQUIRING ROUGH-IN

- A. Rough-in shall consist of all outlet boxes/raceway systems/supports and sleeves required for the installation of cables/devices by other Divisions and by the Owner. It shall be the responsibility of this Contractor to determine the requirements by reviewing the contract documents and meeting with the Superintendent of the trade involved and Owner's representative to review submittal data, shop drawings, etc.
- B. Sealing of all sleeves, to meet the fire rating of the assembly, whether active or not, is work of this Division.

1.10 EXISTING SERVICES AND FACILITIES

- A. Damage to Existing Services: Existing services and facilities damaged by the Contractor through negligence or through use of faulty materials or workmanship shall be promptly repaired, replaced, or otherwise restored to previous conditions by the Contractor without additional cost to the Owner.
- B. Interruption of Services: Interruptions of services necessary for connection to or modification of existing systems or facilities shall occur only at prearranged times approved by the Owner. Interruptions shall only occur after the provision of all temporary work and the availability of adequate labor and materials will assure that the duration of the interruption will not exceed the time agreed upon.

- C. Removed Materials: Existing materials made unnecessary by the new installation shall be stored on site. They shall remain the property of the Owner and shall be stored at a location and in a manner as directed by the Owner. If classified by the Owner's authorized representative as unsuitable for further use, the material shall become the property of the Contractor and shall be removed from the site at no additional cost to the owner.
- D. Contractor shall review drawings for all trades for coordination with existing conditions. Contractor shall be responsible for routing of underground raceways and coordinate with GC and other trades for cutting and repair of existing slabs, parking areas, sidewalks, sheetrock and/or plaster walls, etc.
- E. Contractor shall be responsible for coordinating with contract documents and other trades for routing of ducts, pipes, cable-tray and other components with existing conditions. Contractor shall be responsible for field verifying source of raceways and cabling that are in conflict regardless of whether they serve devices in the area of work or not. The relocation of these raceways to assist in avoiding these conflicts shall also be included at no additional cost to the owner.
- F. Contractor shall protect all existing low-voltage cabling from damage. If conflicts arise, contact architect immediately to determine status of cabling. Existing cabling that is damaged during construction shall be replaced by the contractor.

PART 2 - PRODUCTS

2.1 FIRESTOPPING:

- A. Refer to section 078413 for additional requirements.
- B. A firestop system shall be used to seal penetrations of electrical conduits and cables through fire-rated partitions per NEC 300.21, and NEC 800.26. The firestop system shall be qualified by formal performance testing in accordance with ASTM E-814, or UL 1479.
- C. The firestop system shall consist of a fire-rated caulk type substance and a high temperature fiber insulation. It shall be permanently flexible, waterproof, non-toxic, smoke and gas tight and have a high adhesion to all solids so damming is not required. Only metal conduit shall be used in conjunction with this system to penetrate fire rated partitions. Install in strict compliance with manufacturer's recommendations. 3M or approved equal.
- D. Comply with TIA/EIA-569-A, Annex A, "Firestopping."
- E. Comply with BICSI TDMM, "Firestopping Systems" Article.

PART 3 - EXECUTION

3.1 PRODUCT INSTALLATION, GENERAL

A. Except where more stringent requirements are indicated, comply with the product

manufacturer's installation instructions and recommendations, including handling, anchorage, assembly, connections, cleaning and testing, charging, lubrication, startup, test operation and shutdown of operating equipment. Consult with manufacturer's technical experts, for specific instructions on unique product conditions and unforeseen problems.

- B. Protection and Identification: Deliver products to project properly identified with names, models numbers, types, grades, compliance labels and similar information needed for distinct identifications; adequately packaged or protected to prevent deterioration during shipment, storage and handling. Store in a dry, well ventilated, indoor space, except where prepared and protected by the manufacturer specifically for exterior storage.
- C. Permits and Tests: Provide labor, material and equipment to perform all tests required by the governing agencies and submit a record of all tests to the Owner or his representative. Notify the Architect five days in advance of any testing.
- D. Install temporary protective covers over equipment enclosures, outlet boxes and similar items after interiors, conductors, devices, etc. are installed, to prevent the entry of construction debris and to protect the installation during finish work performed by others. Do not install device plates, equipment covers or trims until finish work is complete.
- E. Clean all equipment, inside and out, upon completion of the work. Scratched or marred surfaces shall be touched-up with touch-up paint furnished by the equipment manufacturer.
- F. Replace all equipment and materials that become damaged.
- G. No more than three phase conductors, each of opposite phases for a three phase WYE system, shall be combined in a single raceway unless written approval is granted by the engineer or noted otherwise on the construction documents. 120-volt and 277-volt receptacle and lighting circuits are except from this requirement, but must meet the requirements of the NEC.
- H. Shared neutrals shall not be utilized (including, but not limited to homeruns) unless written permission is obtained from the Engineer for a specific application.

3.2 EQUIPMENT PROTECTION

- A. Equipment and materials shall be protected during shipment and storage against physical damage, vermin, dirt, corrosive substances, fumes, moisture, cold and rain.
- B. Store equipment indoors in clean dry space with uniform temperature to prevent condensation. Equipment shall include but not be limited to switchgear, switchboards, panelboards, transformers, motor control centers, motor controllers, uninterruptible power systems, enclosures, controllers, circuit protective devices, cables, wire, light fixtures, electronic equipment, and accessories.
- C. During installation, equipment shall be protected against entry of foreign matter; and be vacuum cleaned both inside and outside before testing and operating. Compressed air shall not be used to clean equipment. Remove loose packing and flammable materials from inside equipment.

- D. Damaged equipment shall be, as determined by the Engineer, placed in first class operating condition or be returned to the source of supply for repair or replacement.
- E. Painted surfaces shall be protected with factory installed removable heavy kraft paper, sheet vinyl or equal.
- F. Damaged paint on equipment and materials shall be refinished with the same quality of paint and workmanship as used by the manufacturer so repaired areas are not obvious.

3.3 ELECTRICAL WORK:

- A. Electrical work shall be accomplished with all affected circuits or equipment de-energized. When an electrical outage cannot be accomplished in this manner for the required work, the following requirements are mandatory:
 - Electricians must use full protective equipment (i.e., certified and tested insulating material to cover exposed energized electrical components, certified and tested insulated tools, etc.) while working on energized systems in accordance with NFPA 70E.
 - 2. Electricians must wear personal protective equipment while working on energized systems in accordance with NFPA 70E.
 - 3. Before initiating any work, a job specific work plan must be developed by the contractor with a peer review conducted and documented by the Contractor. The work plan must include procedures to be used on and near the live electrical equipment, barriers to be installed, safety equipment to be used and exit pathways.
 - 4. Work on energized circuits or equipment cannot begin until prior written approval is obtained from the Owner/ Architect.

END OF SECTION 260500

SECTION 260519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 GENERAL

1.1 SUMMARY

- A. Division 27 and 28 requirements shall be a sub-contract to Division 26. Division 26 shall be responsible for all requirements listed on electrical drawings, and Division 26, 27, and 28 specifications.
- B. Section includes building wire and cable and wiring connectors and connections.

1.2 REFERENCES

- A. International Electrical Testing Association:
 - 1. NETA ATS Acceptance Testing Specifications for Electrical Power Distribution Equipment and Systems.
- B. National Fire Protection Association:
 - 1. NFPA 70 National Electrical Code.
 - 2. NFPA 262 Standard Method of Test for Flame Travel and Smoke of Wires and Cables for Use in Air-Handling Spaces.
- C. Underwriters Laboratories, Inc.:
 - 1. UL Standard 83 for Thermoplastic-Insulated Wires and Cables.
 - 2. UL Standard 44 for Thermoset-Insulated Wires and Cables.
 - 3. UL 514B Standard for Conduit, Tubing, and Cable Fittings.
 - 4. UL 1277 Standard for Safety for Electrical Power and Control Tray Cables with Optional Optical-Fiber Members.
 - 5. UL 1569 Standard for Metal-Clad Cables

1.3 SYSTEM DESCRIPTION

- A. Product Requirements: Provide products as follows:
 - 1. Solid conductor for branch circuits 10 AWG and smaller.
 - 2. Stranded conductors for control circuits.
 - 3. Conductor not smaller than 12 AWG for power and lighting circuits.
 - 4. Conductor not smaller than 14 AWG for control circuits.
 - 5. Increase wire size in branch circuits to limit voltage drop to a maximum of 3 percent.
- B. Wiring Methods: Provide the following wiring methods:
 - 1. Use only building wire, Type THHN/THWN-2 insulation, in raceway unless specifically noted otherwise.

1.4 SUBMITTALS

- A. Division 01 Specifications Submittal Procedures: Requirements for submittals.
- B. Product Data for the following:
 - 1. Wire and Cable
 - 2. Splice Kits
 - 3. Waterproof Wire Connectors
- C. Test Reports: Indicate procedures and values obtained.

1.5 CLOSEOUT SUBMITTALS

- A. Division 01 Specifications Execution and Closeout Requirements: Requirements for submittals.
- B. Project Record Documents: Record actual locations of components and circuits.

1.6 QUALITY ASSURANCE

- A. Provide wiring materials located in plenums with peak optical density not greater than 0.5, average optical density not greater than 0.15, and flame spread not greater than 5 feet (1.5 m) when tested in accordance with NFPA 262.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Conform to requirements of NFPA 70.

1.7 QUALIFICATIONS

A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum three years experience.

1.8 FIELD MEASUREMENTS

A. Verify field measurements prior to work. Coordinate dimensions with architectural, structural, and civil drawings. Electrical Drawings are diagrammatic only and shall not be scaled.

1.9 COORDINATION

- A. Division 01 Specifications Administrative Requirements: Requirements for coordination.
- B. Where wire and cable destination is indicated and routing is not shown, determine routing and lengths required.

C. Wire and cable routing indicated is approximate unless dimensioned. Include wire and cable lengths within 10 ft of length shown.

PART 2 PRODUCTS

2.1 BUILDING WIRE

- A. Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Southwire
 - 2. AETNA.
 - 3. American Insulated Wire Corp.
 - 4. Colonial Wire
 - 5. General Cable Co.
 - 6. Substitutions: Section 01 60 00 Product Requirements.
- B. Product Description: Single conductor insulated wire.
- C. Conductor: Copper
- D. Insulation Voltage Rating: 600 volts.

2.2 TERMINATIONS

- A. Terminal Lugs for Wires 6 AWG and Smaller: Solderless, compression type copper.
- B. Lugs for Wires 4 AWG and Larger: Color keyed, compression type copper, with insulating sealing collars.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Division 01 Specification Administrative Requirements: Coordination and project conditions.
- B. Verify interior of building has been protected from weather.
- C. Verify mechanical work likely to damage wire and cable has been completed.
- D. Verify raceway installation is complete and supported.

3.2 PREPARATION

A. Completely and thoroughly swab raceway before installing wire.

3.3 INSTALLATION

- A. Route wire and cable to meet Project conditions.
- B. Neatly train and lace wiring inside boxes, equipment, and panelboards.
- C. Identify wire and cable under provisions of Section 26 05 53. Identify each conductor with its circuit number or other designation indicated.
- D. Special Techniques--Building Wire in Raceway:
 - 1. Pull conductors into raceway at same time.
 - 2. Install building wire 4 AWG and larger with pulling equipment.
- E. Special Techniques Wiring Connections:
 - 1. Clean conductor surfaces before installing lugs and connectors.
 - 2. Make splices, taps, and terminations to carry full ampacity of conductors with no perceptible temperature rise.
 - 3. Tape uninsulated conductors and connectors with electrical tape to 150 percent of insulation rating of conductor.
 - 4. Install split bolt connectors for copper conductor splices and taps, 6 AWG and larger.
 - 5. Install solderless pressure connectors with insulating covers for copper conductor splices and taps, 8 AWG and smaller.
 - 6. Install insulated spring wire connectors with plastic caps for copper conductor splices and taps, 10 AWG and smaller.
 - 7. Polaris type splice kits will not be accepted.
- F. Install stranded conductors for branch circuits 10 AWG and smaller. Install crimp on fork terminals for device terminations. Do not place bare stranded conductors directly under screws.
- G. Install terminal lugs on ends of 600 volt wires unless lugs are furnished on connected device, such as circuit breakers.
- H. Size lugs in accordance with manufacturer's recommendations terminating wire sizes. Install 2-hole type lugs to connect wires 4 AWG and larger to copper bus bars.
- I. For terminal lugs fastened together such as on motors, transformers, and other apparatus, or when space between studs is small enough that lugs can turn and touch each other, insulate for dielectric strength of 2-1/2 times normal potential of circuit.

3.4 WIRE COLOR

A. General:

- 1. For wire sizes 6 AWG and smaller, install wire with insulation colors as designated below.
- 2. For wire sizes 4 AWG and larger, identify wire with colored tape at terminals, splices and boxes. Colors are as follows:

120/208-volt systems: Phase A - Black

Phase B - Red Phase C - Blue Neutral - White Ground - Green

277/480-volt systems: Phase A - Orange

Phase B - Brown Phase C - Yellow Neutral - Gray Ground - Green

3.5 FIELD QUALITY CONTROL

- A. Division 01 Specification Execution and Closeout Requirements: Field inspecting, testing, adjusting, and balancing.
- B. Inspect and test in accordance with NETA ATS, except Section 4.
- C. Perform inspections and tests listed in NETA ATS, Section 7.3.1.

END OF SECTION 260519

SECTION 260526 - GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.1 SUMMARY

- A. Division 27 and 28 requirements shall be a sub-contract to Division 26. Division 26 shall be responsible for all requirements listed on electrical drawings, and Division 26, 27, and 28 specifications.
- B. Section Includes:
 - 1. Rod electrodes.
 - 2. Wire.
 - 3. Mechanical connectors.
 - 4. Exothermic connections.

1.2 REFERENCES

- A. Institute of Electrical and Electronics Engineers:
 - 1. IEEE 142 Recommended Practice for Grounding of Industrial and Commercial Power Systems.
 - 2. IEEE 1100 Recommended Practice for Powering and Grounding Electronic Equipment.
- B. International Electrical Testing Association:
 - 1. NETA ATS Acceptance Testing Specifications for Electrical Power Distribution Equipment and Systems.
- C. National Fire Protection Association:
 - 1. NFPA 70 National Electrical Code.
 - 2. NFPA 99 Standard for Health Care Facilities.

1.3 DESIGN REQUIREMENTS

A. Construct and test grounding systems for access flooring systems on conductive floors accordance with IEEE 1100. Refer to Section 09 69 00.

1.4 PERFORMANCE REQUIREMENTS

A. Grounding System Resistance: 5 ohms maximum.

1.5 SUBMITTALS

- A. Division 01 Specifications Submittal Procedures: Requirements for submittals.
- B. Product Data: Submit data on grounding electrodes and connections.

- C. Test Reports: Indicate overall resistance to ground.
- D. Manufacturer's Installation Instructions: Submit for active electrodes.
- E. Manufacturer's Certificate: Certify Products meet or exceed specified requirements.

1.6 CLOSEOUT SUBMITTALS

- A. Division 01 Specifications Execution and Closeout: Requirements for submittals.
- B. Project Record Documents: Record actual locations of components and grounding electrodes.

1.7 QUALITY ASSURANCE

A. Provide grounding materials conforming to requirements of NEC, IEEE 142, and UL labeled.

1.8 QUALIFICATIONS

- A. Manufacturer: Company specializing in manufacturing Products specified in this section with minimum three years experience.
- B. Installer: Company specializing in performing work of this section with minimum three years experience.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Division 01 Specifications Product Requirements: Requirements for transporting, handling, storing, and protecting products.
- B. Accept materials on site in original factory packaging, labeled with manufacturer's identification.
- C. Protect from weather and construction traffic, dirt, water, chemical, and mechanical damage, by storing in original packaging.
- D. Do not deliver items to project before time of installation. Limit shipment of bulk and multiple-use materials to quantities needed for immediate installation.

1.10 COORDINATION

- A. Division 01 Specifications Administrative Requirements: Requirements for coordination.
- B. Complete grounding and bonding of building reinforcing steel prior concrete placement.

PART 2 PRODUCTS

2.1 ROD ELECTRODES

- A. Product Description:
 - 1. Material: Copper-clad steel.
 - 2. Diameter: 3/4 inch (19 mm).
 - 3. Length: 10 feet (3.0 m).
- B. Connector: Connector for exothermic welded connection.

2.2 WIRE

- A. Material: Stranded copper.
- B. Foundation Electrodes: 4 AWG.
- C. Grounding Electrode Conductor: Copper conductor bare.
- D. Bonding Conductor: Copper conductor insulated.

2.3 MECHANICAL CONNECTORS

- A. Description: Bronze connectors, suitable for grounding and bonding applications, in configurations required for particular installation.
 - 1. Bonding Jumpers: Compression type connectors, using zinc-plated fasteners and external tooth lock washers.
 - 2. Ground Busbars: Two-hole compression type lugs using tin-plated copper or copper alloy bolts and nuts.
 - 3. Rack and cabinet ground bars: One-hole compression type lugs using zinc-plated or copper alloy fasteners.

2.4 EXOTHERMIC CONNECTIONS

A. Product Description: Exothermic materials, accessories, and tools for preparing and making permanent field connections between grounding system components.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Division 01 Specifications Administrative: Verification of existing conditions before starting work.
- B. Verify final backfill and compaction has been completed before driving rod electrodes.

3.2 PREPARATION

A. Remove paint, rust, mill oils, and other surface contaminants at connection points.

3.3 EXISTING WORK

- A. Modify existing grounding system to maintain continuity to accommodate renovations.
- B. Extend existing grounding system using materials and methods compatible with existing electrical installations, or as specified.

3.4 INSTALLATION

- A. Install in accordance with IEEE 142.
- B. Install rod electrodes at locations as indicated on Drawings. Install additional rod electrodes to achieve specified resistance to ground.
- C. Install grounding and bonding conductors concealed from view.
- D. Install grounding electrode conductor and connect to reinforcing steel in foundation footing. Electrically bond steel together. If it is determined that the reinforcing steel cannot be made electrically continuous, install a 4 AWG bare copper conductor in foundation footing around the perimeter of the building.
- E. Equipment Grounding Conductor: Install separate, insulated conductor within each feeder and branch circuit raceway. Terminate each end on suitable lug, bus, or bushing.
- F. Install continuous grounding using underground cold water system and building steel as grounding electrode. Where water piping is not available, install artificial station ground by means of driven rods or buried electrodes.
- G. Permanently ground entire light and power system in accordance with NEC, including service equipment, distribution panels, lighting panelboards, switch and starter enclosures, motor frames, grounding type receptacles, and other exposed non-current carrying metal parts of electrical equipment.
- H. Accomplish grounding of electrical system by using insulated grounding conductor installed with feeders and branch circuit conductors in conduits. Size grounding conductors in accordance with NEC. Install from grounding bus of serving panel to ground bus of served panel, grounding screw of receptacles, lighting fixture housing, light switch outlet boxes or metal enclosures of service equipment. Ground conduits by means of grounding bushings on terminations at panelboards with installed number 12 conductor to grounding bus.
- I. Grounding electrical system using continuous metal raceway system enclosing circuit conductors in accordance with NEC.

J. Permanently attach equipment and grounding conductors prior to energizing equipment.

3.5 FIELD QUALITY CONTROL

- A. Division 01 Specifications Quality Requirements: Field inspecting, testing, adjusting, and balancing.
- B. Inspect and test in accordance with NETA ATS, except Section 4.
- C. Grounding and Bonding: Perform inspections and tests listed in NETA ATS, Section 7.13.
- D. Perform ground resistance testing in accordance with IEEE 142.
- E. Perform continuity testing in accordance with IEEE 142.
- F. When improper grounding is found on receptacles, check receptacles in entire project and correct. Perform retest.

END OF SECTION 260526

SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.1 SUMMARY

- A. Division 27 and 28 requirements shall be a sub-contract to Division 26. Division 26 shall be responsible for all requirements listed on electrical drawings, and Division 26, 27, and 28 specifications.
- B. Section Includes:
 - 1. Conduit and equipment support.
 - 2. Anchors and fasteners.

1.2 DELIVERY, STORAGE, AND HANDLING

- A. Division 01 Specifications Product Requirements: Requirements for transporting, handling, storing, and protecting products.
- B. Accept materials on site in original factory packaging, labeled with manufacturer's identification.
- C. Protect from weather and construction traffic, dirt, water, chemical, and mechanical damage, by storing in original packaging.

PART 2 PRODUCTS

2.1 CONDUIT SUPPORTS

- A. Hanger Rods: Threaded high tensile strength galvanized carbon steel with free running threads.
- B. Beam Clamps: Malleable Iron, with tapered hole in base and back to accept either bolt or hanger rod. Set screw: hardened steel.
- C. Conduit clamps for trapeze hangers: Galvanized steel, notched to fit trapeze with single bolt to tighten.
- D. Conduit clamps general purpose: One hole malleable iron for surface mounted conduits.
- E. Cable Ties: High strength nylon temperature rated to 185 degrees F (85 degrees C). Self locking.

2.2 FORMED STEEL CHANNEL

A. Product Description: Galvanized 12 gage (2.8 mm) thick steel. With holes 1-1/2 inches (38 mm) on center.

2.3 SPRING STEEL CLIPS

A. Product Description: Mounting hole and screw closure.

PART 3 EXECUTION

3.1 EXAMINATION

A. Division 01 Specifications - Administrative Requirements: Verification of existing conditions before starting work.

3.2 PREPARATION

- A. The use of powder-actuated anchors is not allowed.
- B. Do not drill or cut structural members.

3.3 INSTALLATION - HANGERS AND SUPPORTS

- A. Anchors and Fasteners:
 - 1. Concrete Structural Elements: Provide precast inserts, expansion anchors and preset inserts.
 - 2. Steel Structural Elements: Provide beam clamps, spring steel clips, and steel ramset fasteners.
 - 3. Concrete Surfaces: Provide self-drilling anchors and expansion anchors.
 - 4. Hollow Masonry, Plaster, and Gypsum Board Partitions: Provide toggle bolts and hollow wall fasteners.
 - 5. Solid Masonry Walls: Provide expansion anchors and preset inserts.
 - 6. Sheet Metal: Provide sheet metal screws.
 - 7. Wood Elements: Provide wood screws.

B. Inserts:

- 1. Install inserts for placement in concrete forms.
- 2. Install inserts for suspending hangers from reinforced concrete slabs and sides of reinforced concrete beams.
- 3. Provide hooked rod to concrete reinforcement section for inserts carrying pipe over 4 inches (100 mm).
- 4. Where concrete slabs form finished ceiling, locate inserts flush with slab surface.
- 5. Where inserts are omitted, drill through concrete slab from below and provide through-bolt with recessed square steel plate and nut recessed into and grouted flush with slab.

- C. Install conduit and raceway support and spacing in accordance with NEC.
- D. Do not fasten supports to pipes, ducts, mechanical equipment, or conduit.
- E. Install multiple conduit runs on common hangers.

F. Supports:

- 1. Fabricate supports from structural steel or formed steel channel. Install hexagon head bolts to present neat appearance with adequate strength and rigidity. Install spring lock washers under nuts.
- 2. Install surface mounted cabinets and panelboards with minimum of four anchors.
- 3. In wet and damp locations install steel channel supports to stand cabinets and panelboards 1 inch (25 mm) off wall.
- 4. Support vertical conduit at every other floor.

3.4 INSTALLATION - EQUIPMENT BASES AND SUPPORTS

- A. Provide housekeeping pads of concrete, minimum 3-1/2 inches (87 mm) thick and extending 6 inches (150 mm) beyond supported equipment. Refer to Section 03 30 00.
- B. Using templates furnished with equipment, install anchor bolts, and accessories for mounting and anchoring equipment.
- C. Construct supports of steel members. Brace and fasten with flanges bolted to structure.

3.5 FIELD QUALITY CONTROL

A. Division 01 Specifications - Quality Requirements: Field inspecting, testing, adjusting, and balancing.

3.6 PROTECTION OF FINISHED WORK

- A. Division 01 Specifications Execution and Closeout Requirements: Requirements for protecting finished Work.
- B. Protect adjacent surfaces from damage by material installation.

END OF SECTION 260529

SECTION 260533 - RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.1 SUMMARY

A. Section includes conduit and tubing, surface raceways, wireways, outlet boxes, pull and junction boxes, and handholes.

1.2 REFERENCES

- A. American National Standards Institute:
 - 1. ANSI C80.1 Rigid Steel Conduit, Zinc Coated.
 - 2. ANSI C80.3 Specification for Electrical Metallic Tubing, Zinc Coated.
- B. National Electrical Manufacturers Association:
 - 1. NEMA 250 Enclosures for Electrical Equipment (1000 Volts Maximum).
 - 2. NEMA FB 1 Fittings, Cast Metal Boxes, and Conduit Bodies for Conduit and Cable Assemblies.
 - 3. NEMA OS 1 Sheet Steel Outlet Boxes, Device Boxes, Covers, and Box Supports.

1.3 SYSTEM DESCRIPTION

- A. Raceway and boxes located as indicated on Drawings, and at other locations required for splices, taps, wire pulling, equipment connections, and compliance with regulatory requirements. Raceway and boxes are shown in approximate locations unless dimensioned. Provide raceway to complete wiring system.
- B. Concealed Dry Locations: Provide electrical metallic tubing. Provide sheet-metal boxes. Provide flush mounting outlet box in finished areas. Provide hinged enclosure for large pull boxes.

1.4 DESIGN REQUIREMENTS

A. Minimum Raceway Size: 3/4 inch (19 mm) unless otherwise specified.

1.5 CLOSEOUT SUBMITTALS

- A. Division 01 Specifications Execution and Closeout Requirements: Closeout procedures.
- B. Project Record Documents:
 - 1. Record actual locations and mounting heights of outlet, pull, and junction boxes.

1.6 COORDINATION

- A. Division 01 Specifications Administrative Requirements: Coordination and project conditions.
- B. Coordinate installation of outlet boxes for equipment connected under Section 26 05 03.
- C. Coordinate mounting heights, orientation and locations of outlets mounted above counters, benches, and backsplashes.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers listed below are basis of design or can provide products equal to basis of design.
 - 1. Carlon Electrical Products.
 - 2. Hubbell Wiring Devices.
 - 3. Thomas & Betts Corp.
 - 4. The Wiremold Co.
 - 5. Substitutions: Division 01 Specifications Product Requirements.

2.2 FLEXIBLE METAL CONDUIT

- A. Product Description: Interlocked steel construction.
- B. Fittings: NEMA FB 1.

2.3 LIQUIDTIGHT FLEXIBLE METAL CONDUIT

- A. Product Description: Interlocked steel construction with PVC jacket.
- B. Fittings: NEMA FB 1.

2.4 ELECTRICAL METALLIC TUBING (EMT)

- A. Product Description: ANSI C80.3; galvanized tubing.
- B. Fittings and Conduit Bodies: NEMA FB 1; steel compression type.
- C. All EMT conduit shall be Anodized with the following color coating:
 - 1. Emergency Life Safety Power: Yellow
 - 2. Normal Power: Silver
 - 3. Fire Alarm System: Red
 - 4. Communications Systems: Black

2.5 WIREWAY

- A. Product Description: General purpose for interior locations, and Raintight type for exterior locations wireway.
- B. Cover: Hinged cover.
- C. Finish: Rust inhibiting primer coating with gray enamel finish.

2.6 OUTLET BOXES

- A. Sheet Metal Outlet Boxes: NEMA OS 1, galvanized steel.
 - 1. Equipment Supporting Boxes: Rated for weight of equipment supported; furnish 1/2 inch (13 mm) male fixture studs where required.
 - 2. Concrete Ceiling Boxes: Concrete type.
- B. Cast Boxes: NEMA FB 1, Type FD. Furnish gasketed cover by box manufacturer.

2.7 PULL AND JUNCTION BOXES

- A. Sheet Metal Boxes: NEMA OS 1, galvanized steel.
- B. Hinged Enclosures: As specified in Section 26 27 16.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Division 01 Specifications Administrative Requirements: Coordination and project conditions.
- B. Verify locations, routing and termination locations of raceway prior to rough-in.

3.2 EXISTING WORK

- A. Remove exposed abandoned raceway, including abandoned raceway above accessible ceiling finishes. Cut raceway flush with walls and floors, and patch surfaces.
- B. Remove concealed abandoned raceway to its source.
- C. Disconnect abandoned outlets and remove devices. Remove abandoned outlets when raceway is abandoned and removed. Install blank cover for abandoned outlets not removed.
- D. Maintain access to existing boxes and other installations remaining active and requiring access. Modify installation or provide access panel.

- E. Extend existing raceway and box installations using materials and methods compatible with existing electrical installations, or as specified.
- F. Clean and repair existing raceway and boxes to remain.

3.3 INSTALLATION

- A. Ground and bond raceway and boxes in accordance with Section 26 05 26.
- B. Fasten raceway and box supports to structure and finishes in accordance with Section 26 05 29.
- C. Identify raceway and boxes in accordance with Section 26 05 53.
- D. Arrange raceway and boxes to maintain headroom and present neat appearance.
- E. Do not install raceways or boxes within 1-1/2" of roof decking to prevent damage from roof installation or repair.

3.4 INSTALLATION - RACEWAY

- A. Raceway routing is shown in approximate locations unless dimensioned. Route to complete wiring system.
- B. Arrange raceway supports to prevent misalignment during wiring installation.
- C. Support raceway using coated steel or malleable iron straps, lay-in adjustable hangers, clevis hangers, and split hangers.
- D. Group related raceway; support using conduit rack. Construct rack using steel channel specified in Section 26 05 29; provide space on each for 25 percent additional raceways.
- E. Do not support raceway with wire or perforated pipe straps. Remove wire used for temporary supports
- F. Do not attach raceway to ceiling support wires or other piping systems.
- G. Construct wireway supports from steel channel specified in Section 26 05 29.
- H. Route exposed raceway parallel and perpendicular to walls.
- I. Route raceway installed above accessible ceilings parallel and perpendicular to walls.
- J. Maintain clearance between raceway and piping for maintenance purposes.
- K. Maintain 12 inch (300 mm) clearance between raceway and surfaces with temperatures exceeding 104 degrees F (40 degrees C).

- L. Cut conduit square using saw or pipe cutter; de-burr cut ends.
- M. Bring conduit to shoulder of fittings; fasten securely.
- N. Install conduit hubs or sealing locknuts to fasten conduit to cast boxes.
- O. Install no more than equivalent of two 90 degree bends between boxes for communications systems. Install conduit bodies to make sharp changes in direction, as around beams. Install factory elbows for bends in metal conduit larger than 2 inch (50 mm) size.
- P. Avoid moisture traps; install junction box with drain fitting at low points in conduit system.
- Q. Install fittings to accommodate expansion and deflection where raceway crosses seismic, control and expansion joints.
- R. Install suitable pull string or cord in each empty raceway except sleeves and nipples.
- S. Install suitable caps to protect installed conduit against entrance of dirt and moisture.
- T. Close ends and unused openings in wireways, junction boxes, and pull boxes.

3.5 INSTALLATION - BOXES

- A. Install wall mounted boxes at elevations to accommodate mounting heights as indicated on Drawings.
- B. Adjust box location up to 10 feet (3 m) prior to rough-in to accommodate intended purpose.
- C. Orient boxes to accommodate wiring devices oriented as specified in Section 26 27 26.
- D. Install pull boxes and junction boxes above accessible ceilings and in unfinished areas only.
- E. In Accessible Ceiling Areas: Install outlet and junction boxes no more than 6 inches (150 mm) from ceiling access panel or from removable recessed luminaire.
- F. Do not install flush mounting box back-to-back in walls; install with minimum 6 inches (150 mm) separation. Install with minimum 24 inches (600 mm) separation in acoustic rated walls.
- G. Secure flush mounting box to interior wall and partition studs. Accurately position to allow for surface finish thickness.
- H. Install stamped steel bridges to fasten flush mounting outlet box between studs.

- I. Install flush mounting box without damaging wall insulation or reducing its effectiveness.
- J. Install adjustable steel channel fasteners for hung ceiling outlet box.
- K. Do not fasten boxes to ceiling support wires or other piping systems.
- L. Support boxes independently of conduit.
- M. Install gang box where more than one device is mounted together. Do not use sectional box.
- N. Install gang box with plaster ring for single device outlets.
- O. Install junction boxes or pull boxes at locations that can be accessed through existing ceiling with a standard ladder. Maximum height of junction boxes above accessible ceiling or through an access panel in a non-accessible is 4' above top of ceiling frame.

3.6 INTERFACE WITH OTHER PRODUCTS

- A. Install conduit to preserve fire resistance rating of partitions and other elements, using materials and methods in accordance with Section 07 84 00.
- B. Route conduit through roof openings for piping and ductwork or through suitable roof jack with pitch pocket. Coordinate location with roofing installer.
- C. Locate outlet boxes to allow luminaires positioned as indicated on Drawings.
- D. Align adjacent wall mounted outlet boxes for switches, thermostats, and similar devices.

3.7 ADJUSTING

- A. Division 01 Specifications Execution and Closeout Requirements: Testing, adjusting, and balancing.
- B. Adjust flush-mounting outlets to make front flush with finished wall material.
- C. Install knockout closures in unused openings in boxes.

3.8 CLEANING

- A. Division 01 Specifications Execution and Closeout Requirements: Final cleaning.
- B. Clean interior of boxes to remove dust, debris, and other material.
- C. Clean exposed surfaces and restore finish.

END OF SECTION 260533

SECTION 260553 - IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.1 SUMMARY

- A. Division 27 and 28 requirements shall be a sub-contract to Division 26. Division 26 shall be responsible for all requirements listed on electrical drawings, and Division 26, 27, and 28 specifications.
- B. Section Includes:
 - 1. Nameplates.
 - 2. Labels.
 - 3. Wire markers.

1.2 DELIVERY, STORAGE, AND HANDLING

- A. Division 01 Specifications Product Requirements: Requirements for transporting, handling, storing, and protecting products.
- B. Accept identification products on site in original containers. Inspect for damage.
- C. Protect insulation from weather and construction traffic, dirt, water, chemical, and mechanical damage, by storing in original wrapping.

1.3 ENVIRONMENTAL REQUIREMENTS

- A. Division 01 Specifications Product Requirements: Environmental conditions affecting products on site.
- B. Install nameplates and labels only when ambient temperature and humidity conditions for adhesive are within range recommended by manufacturer.

PART 2 PRODUCTS

2.1 NAMEPLATES

- A. Product Description: Laminated three-layer plastic with engraved letters on contrasting background color. See specification sections for specific equipment for nameplate color schemes. If no color scheme is specified for specific equipment, provide black letters on a white background.
- B. Letter Size:
 - 1. 1/8 inch (3 mm) high letters for identifying individual equipment and loads.
- C. Minimum nameplate thickness: 1/8 inch (3 mm).

2.2 LABELS

A. Labels: Embossed adhesive tape, with 3/16 inch (5 mm) white letters on black background.

2.3 WIRE MARKERS

- A. Plenum-Rated Cable Ties: Self extinguishing, UV stabilized, one piece, self locking.
 - 1. Width: 3/16 inch (5 mm).
 - 2. Tensile Strength at 73 deg F (23 deg C), According to ASTM D 638: 7000 psi (48.2 MPa).
 - 3. UL 94 Flame Rating: 94V-0.
 - 4. Temperature Range: -50 deg F to +284 deg F (-46 deg C to +140 deg C).

B. Legend:

- 1. Power and Lighting Circuits: Branch circuit or feeder number.
- 2. Control Circuits: Control wire number as indicated on shop drawings.

PART 3 EXECUTION

3.1 PREPARATION

A. Degrease and clean surfaces to receive adhesive for identification materials.

3.2 INSTALLATION

- A. Install identifying devices after completion of painting.
- B. Nameplate Installation:
 - 1. Install nameplate parallel to equipment lines.
 - 2. Install nameplate for each electrical distribution and control equipment enclosure with corrosive-resistant mechanical fasteners, or adhesive.
 - 3. Install nameplates for each control panel and major control components located outside panel with corrosive-resistant mechanical fasteners, or adhesive.
 - 4. Secure nameplate to equipment front using screws, or adhesive.
 - 5. Install nameplates for the following:
 - a. Power panelboard with fire alarm power circuit
 - b. Fire Alarm Control Panels
 - c. Fire Alarm Extender Panels

C. Label Installation:

- 1. Install label parallel to equipment lines.
- 2. Install label for identification of individual control device stations.
- 3. Install labels for permanent adhesion and seal with clear lacquer.
- D. Wire Marker Installation:

USC 1206 FLORA STREET MILL RENOVATION FIRE ALARM BID PACKAGE

PROJECT # H27-I851 50001658-25 GMC PROJECT # ACOL180003 03/18/2020

- 1. Install wire marker for each conductor at panelboard gutters, pull boxes, outlet and junction boxes, and each load connection.
- 2. Mark data cabling at each end. Install additional marking at accessible locations along the cable run.
- 3. Install labels at data outlets identifying patch panel and port designation.

END OF SECTION 260553

SECTION 260583 - EQUIPMENT WIRING CONNECTIONS

PART 1 GENERAL

1.1 SUMMARY

- A. Division 27 and 28 requirements shall be a sub-contract to Division 26. Division 26 shall be responsible for all requirements listed on electrical drawings, and Division 26, 27, and 28 specifications.
- B. Section includes electrical connections to equipment.

1.2 REFERENCES

- A. National Electrical Manufacturers Association:
 - 1. NEMA WD 1 General Requirements for Wiring Devices.
 - 2. NEMA WD 6 Wiring Devices-Dimensional Requirements.

1.3 SUBMITTALS

- A. Division 01 Specification Submittal Procedures.
- B. Product Data: Submit wiring device manufacturer's catalog information showing dimensions, configurations, and construction.
- C. Signed Letter from Contractor indicating that shop drawings have been reviewed for all equipment requiring electrical connections that are furnished by other divisions prior to ordering equipment.
- D. Manufacturer's installation instructions.

1.4 CLOSEOUT SUBMITTALS

- A. Division 01 Specification Execution and Closeout Requirements.
- B. Project Record Documents: Record actual locations, sizes, and configurations of equipment connections.

1.5 COORDINATION

- A. Division 01 Specification Administrative Requirements: Coordination and project conditions.
- B. Obtain and review shop drawings, product data, manufacturer's wiring diagrams, and manufacturer's instructions for equipment furnished under other sections.

- C. Prior to ordering electrical gear, compare to electrical requirements listed on electrical drawings for each piece of equipment. Notify architect / engineer immediately of any changes.
- D. Determine connection locations and requirements.
- E. Sequence rough-in of electrical connections to coordinate with installation of equipment.
- F. Sequence electrical connections to coordinate with start-up of equipment.

PART 2 PRODUCTS

2.1 EQUIPMENT REQUIRING ELECTRICAL SERVICE

- A. Provide electrical connections for all electrically driven equipment. Final connections are electrical work, unless specifically noted otherwise. Obtain a copy of the shop drawings of equipment. Review shop drawings to verify electrical characteristics and to determine rough-in requirements, final connection requirements, location of disconnect switch, etc. Notify the General Contractor if the information received is ambiguous or incomplete. Keep a copy of these shop drawings at the project site throughout the course of construction.
- B. Equipment to be connected includes, but is not limited to the following:
 - 1. Fire Alarm System
 - 2. Elevators
 - 3. Control Systems
- C. The design of circuits for electrically driven equipment is based on the product of one manufacturer and may not be representative of all acceptable manufacturers. If equipment furnished has differing characteristics, make necessary adjustments to circuit components at no additional cost to the Owner, subject to the approval of the Architect.
- D. Provide motor starters and disconnects for all mechanical equipment unless provided by the mechanical contractor.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Division 01 Specification Administrative Requirements: Coordination and project conditions.
- B. Verify equipment is ready for electrical connection, for wiring, and to be energized.

3.2 EXISTING WORK

- A. Remove exposed abandoned equipment wiring connections, including abandoned connections above accessible ceiling finishes.
- B. Disconnect abandoned utilization equipment and remove wiring connections. Remove abandoned components when connected raceway is abandoned and removed. Install blank cover for abandoned boxes and enclosures not removed.
- C. Extend existing equipment connections using materials and methods as specified.

3.3 INSTALLATION

- A. Make electrical connections.
- B. Make conduit connections to equipment using flexible conduit. Use liquid-tight flexible conduit with watertight connectors in damp or wet locations.
- C. Connect heat producing equipment using wire and cable with insulation suitable for temperatures encountered.
- D. Install receptacle outlet to accommodate connection with attachment plug.
- E. Install cord and cap for field-supplied attachment plug.
- F. Install suitable strain-relief clamps and fittings for cord connections at outlet boxes and equipment connection boxes.
- G. Install disconnect switches, controllers, control stations, and control devices to complete equipment wiring requirements.
- H. Install terminal block jumpers to complete equipment wiring requirements.
- I. Install interconnecting conduit and wiring between devices and equipment to complete equipment wiring requirements.

3.4 ADJUSTING

- A. Division 01 Specification Execution and Closeout Requirements: Testing, adjusting, and balancing.
- B. Cooperate with utilization equipment installers and field service personnel during checkout and starting of equipment to allow testing and balancing and other startup operations. Provide personnel to operate electrical system and checkout wiring connection components and configurations.

END OF SECTION 260583

SECTION 264300 – SURGE PROTECTIVE DEVICES

PART 1 - GENERAL

1.1 SUMMARY

- A. Division 27 and 28 requirements shall be a sub-contract to Division 26. Division 26 shall be responsible for all requirements listed on electrical drawings, and Division 26, 27, and 28 specifications.
- B. Section Includes: Surge Protection Devices Type 1 and Type 2 Devices

1.2 REFERENCES

- A. Institute of Electrical and Electronics Engineers:
 - 1. IEEE 1100 Recommended Practice for Powering and Grounding Electronic Equipment.
 - 2. IEEE C62.41 Recommended Practice on Surge Voltages in Low-Voltage AC Power Circuits
 - 3. IEEE C62.45 Guide on Surge Testing for Equipment Connected to Low-Voltage AC Power Circuits.
- B. National Fire Protection Association:
 - 1. NFPA 70 National Electrical Code.
 - 2. NFPA 780 Standard for the Installation of Lightning Protection Systems.
- C. Underwriters Laboratories Inc.:
 - 1. UL 1283 Electromagnetic Interference Filters.
 - 2. UL 1449 Third Edition Surge Protective Devices.

1.3 SUBMITTALS

- A. Division 01 Specifications Submittal Procedures: Requirements for submittals.
- B. Product Data: Submit the following
 - 1. Unit Dimensions and Weights
 - 2. Wiring configuration.
 - 3. Warranty Statement
 - 4. Current Ratings
 - 5. Clamping Voltages
 - 6. Response Time
- C. Test Reports:
 - 1. Indicate Let-Through voltage test data.
 - 2. Submit spectrum analysis of each unit.
 - 3. Submit test reports from nationally recognized independent testing laboratory verifying suppressors can survive published surge current rating.
- D. Manufacturer's Installation Instructions: Submit installation instructions and connection requirements.

E. Manufacturer's Certificate: Certify transient voltage surge suppression device complies with UL 1449 Third Edition Surge Voltage Ratings.

1.4 QUALITY ASSURANCE

- A. Reference Standard: Comply with the latest edition of the applicable provisions and recommendations of the following, except as otherwise stated in this document:
 - 1. UL 1449 3rd Edition 2009 Revision
 - 2. UL 1283.
 - 3. ANSI/IEEE C62.41, Recommended Practice for Surge Voltages in Low-Voltage AC Power Circuits.
 - 4. ANSI/IEEE C62.45, Guide for Surge Testing for equipment connected to Low-Voltage AC Power Circuits.
 - 5. IEEE 1100 Emerald Book.
 - 6. National Fire Protective Association (NFPA 70: National Electrical Code).

1.5 WARRANTY

A. Provide a 5 year product warranty.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following manufacturers:
 - 1. Emerson / APT
 - 2. Current Technologies
 - 3. Thor
 - 4. GE Electric
 - 5. Square D
 - 6. Eaton
 - 7. Substitutions: Division 01 Specifications Product Requirements

2.2 ELECTRICAL REQUIREMENTS

- A. Declared Maximum Continuous Operating Voltage (MCOV) shall be greater than 115 percent of the nominal system operating voltage and in compliance with test and evaluation procedures outlined in the nominal discharge surge current test of UL1449 3rd Edition, section 37.7. MCOV values claimed based on the component's value or on the 30-minute 115% operational voltage test, section 38 in UL1449 will not be accepted.
- B. Unit shall have not more than 10% deterioration or degradation of the UL1449 3rd Edition Voltage Protective Rating VPR) due to repeated surges. Unit shall have a monitoring option available to be able to test and determine the percentage of protective available at all times.
- C. Protection Modes: SVR(6kV, 500A) and UL1449 3rd Edition VPR(6kV, 3kA) for grounded WYE/delta and High Leg Delta circuits with voltages of (480Y/277), (208Y/120),

(600Y/347) 3-Phase/4 wire and (120/240) Split phase/3 wire circuits shall be as follows and comply with test procedures outlined in UL1449 3rd Edition section 37.6

System Voltage	Mode	MCOV	B3 Ringwave	C3 Comb. Wave	UL 1449 Second Edition SVR Rating	UL 1449 Third Edition VPR Rating
120/240	L-N	150	325/375	650/775	400/400	700/700
120/208	L-G	150	400/450	650/825	500/500	700/700
	N-G	150	350/350	500/500	500/500	900/900
	L-L	300	400/500	950/1250	700/700	900/900
277/480	L-N	320	550/600	1125/1225	900/900	1000/1000
	L-G	320	850/875	1075/1225	1000/1000	1200/1200
	N-G	320	700/700	900/900	800/800	1200/1200
	L-L	550	650/750	1950/2200	1500/1500	1800/1800

- D. Electrical Noise Filter- each unit shall include a high performance EMI/RFI noise rejection filter. Noise attenuation for electric noise shall be as follows using the MIL-STD-220B insertion loss test method.
 - 1. 100 kHz at 44 db or better.
 - 2. All other frequencies should be 32 db or better.
- E. Each fuse shall be individually sealed in a manner that eliminates the potential for cross arcing.
- F. Each unit shall provide the following features:
 - 1. Phase Indicator lights, Form C dry contacts, surge counter and audible alarm.
 - 2. Field testable while installed.
 - 3. Measuring capability to indicate the percent protective available in SPD.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Each unit shall be installed per Manufacturer's recommended installation and wiring practices.
- B. The UL 1449 Voltage Protective Rating (VPR) shall be permanently affixed to the SPD unit.
- C. The UL 1449 Nominal Discharge Surge Current Rating shall be a minimum of 20kA.
- D. Surge Current Rating of device shall be as noted on drawings.
- E. The SCCR rating of the SPD shall be 200kAIC without requiring an upstream protective device for safe operation.

- F. Locate SPDs and associated circuit breaker in panelboard or switchboard so as to minimize conductor lengths and bends.
 - 1. Conductors between SPD and circuit breaker shall be no more than 24" in length.
 - 2. There shall be no sharp bends or kinks in conductors.
 - 3. Conductors shall be continuous from device to breaker.
 - 4. Do not bundle or tie-wrap conductors together.
 - 5. If conductors must exceed 24" in length or contain multiple bends due to location constraints, contractor shall provide manufacturer's specialty cable for excessive lengths at no additional cost.
- G. The SPD manufacturer's technician shall perform a system checkout and start-up in the field to assure proper installation, operation and to initiate the warranty of the system. The technician will be required to do the following:
 - 1. Verify voltage clamping levels using the DTS-2 test equipment.
 - 2. Verify N-G connection when applicable.
 - 3. Record information to product signature card for each product installed.

END OF SECTION 264300

SECTION 283100 - FIRE DETECTION AND ALARM

PART 1 GENERAL

1.1 SUMMARY

- A. Division 27 and 28 requirements shall be a sub-contract to Division 26. Division 26 shall be responsible for all requirements listed on electrical drawings, and Division 26, 27, and 28 specifications.
- B. Section includes fire alarm control panels, manual fire alarm stations, automatic smoke and heat detectors, fire alarm signaling appliances, and auxiliary fire alarm equipment and power and signal wire and cable.

1.2 REFERENCES

- A. National Fire Protection Association:
 - 1. NFPA 72 National Fire Alarm Code.
 - 2. NFPA 262 Standard Method of Test for Flame Travel and Smoke of Wires and Cables for Use in Air-Handling Spaces.

1.3 SYSTEM DESCRIPTION

- A. General: Provide a complete, non-coded, addressable microprocessor-based fire alarm system with initiating devices, audio (voice evac) and visual notification appliances, and monitoring and control devices as indicated on the drawings and as specified herein.
- B. History Logs: The system shall provide a means to recall alarms and trouble conditions in chronological order for the purpose of recreating an event history. A separate alarm and trouble log shall be provided.
- C. All fire alarm work in this scope shall be coordinated with the University of South Carolina Fire and Public Safety Division Contact person: Todd Griffin (803) 777-1640. Central monitoring system shall be connected to USC Police. Mass notification system shall be coordinated with USC Police.
- D. Wiring/Signal Transmission:
 - 1. Transmission shall be hard-wired, addressable signal transmission, dedicated to fire alarm service only.
 - 2. System connections for initiating, signaling line circuits and notification appliance circuits shall be Class A.
 - 3. Circuit Supervision: Circuit faults shall be indicated by a trouble signal at the FACP. Provide a distinctive indicating audible tone and alphanumeric annunciation.
- E. Required Functions: The following are required system functions and operating features:

- 1. Transmission to Remote Central Station: Automatically route alarm, supervisory, and trouble signals to a remote central station service as coordinated with USC Fire and Safety Division and USC Police Department.
- 2. Annunciation: Operation of alarm and supervisory initiating devices shall be annunciated at the FACP and the remote annunciator, indicating the location and type of device.
- 3. General Alarm: A system general alarm shall include:
 - a. Indication of alarm condition at the FACP and the annunciator(s).
 - b. Identification of the device that is the source of the alarm at the FACP and the annunciator(s).
 - c. Operation of audible (voice evac) and visible notification devices throughout the building until silenced at FACP.
 - d. Closing doors normally held open by magnetic door holders.
 - e. Unlocking designated doors.
 - f. Shutting down supply and return fans serving zone where alarm is initiated.
 - g. Closing smoke dampers on system serving zone where alarm is initiated.
 - h. Notifying the local fire department.
 - i. Initiation of elevator recall in accordance with ASME/ANSI A17.1, when specified detectors or sensors are activated.
- 4. Supervisory Operations: Upon activation of a supervisory device such as tamper switch, the system shall operate as follows:
 - a. Activate the system supervisory service audible signal and illuminate the LED at the control unit and the remote annunciator.
 - b. Pressing the Supervisory Acknowledge Key will silence the supervisory audible signal while maintaining the Supervisory LED "on" indicating off-normal condition.
 - c. Record the event in the FACP historical log.
 - d. Transmission of supervisory signal to remote central station.
 - e. Restoring the condition shall cause the Supervisory LED to clear and restore the system to normal.
- 5. Alarm Silencing: If the "Alarm Silence" button is pressed, all audible and visible alarm signals shall cease operation.
- 6. System Reset:
 - a. The "System Reset" button shall be used to return the system to its normal state. Display messages shall provide operator assurance of the sequential steps ("IN PROGRESS", "RESET COMPLETED") as they occur. The system shall verify all circuits or devices are restored prior to resetting the system to avoid the potential for re-alarming the system. The display message shall indicate "ALARM PRESENT, SYSTEM RESET ABORTED."
 - b. Should an alarm condition continue, the system will remain in an alarmed state.
- 7. A manual evacuation (drill) switch shall be provided to operate the notification appliances without causing other control circuits to be activated.
- 8. WALKTEST: The system shall have the capacity of 8 programmable passcode protected one person testing groups, such that only a portion of the system need

be disabled during testing. The actuation of the "enable one person test" program at the control unit shall activate the "One Person Testing" mode of the system as follows:

- a. The city circuit connection and any suppression release circuits shall be bypassed for the testing group.
- b. Control relay functions associated to one of the 8 testing groups shall be bypassed.
- c. The control unit shall indicate a trouble condition.
- d. The alarm activation of any initiation device in the testing group shall cause the audible notification appliances assigned only to that group to sound a code to identify the device or zone.
- e. The unit shall automatically reset itself after signaling is complete.
- f. Any opening of an initiating or notification appliance circuit wiring shall cause the audible signals to sound for 4 seconds indicating the trouble condition.

F. Analog Smoke Sensors:

- 1. Monitoring: FACP shall individually monitor sensors for calibration, sensitivity, and alarm condition, and shall individually adjust for sensitivity. The control unit shall determine the condition of each sensor by comparing the sensor value to the stored values.
- 2. Environmental Compensation: The FACP shall maintain a moving average of the sensor's smoke chamber value to automatically compensate for dust, dirt, and other conditions that could affect detection operations.
- 3. Programmable Sensitivity: Photoelectric Smoke Sensors shall have 7 selectable sensitivity levels ranging from 0.2% to 3.7%, programmed and monitored from the FACP.
- 4. Sensitivity Testing Reports: The FACP shall provide sensor reports that meet NFPA 72 calibrated test method requirements. The reports shall be viewed on a CRT Display or printed for annual recording and logging of the calibration maintenance schedule.
- The FACP shall automatically indicate when an individual sensor needs cleaning. 5. The system shall provide a means to automatically indicate when a sensor requires cleaning. When a sensor's average value reaches a predetermined value, (3) progressive levels of reporting are provided. The first level shall indicate if a sensor is close to a trouble reporting condition and will be indicated on the FACP as "ALMOST DIRTY." This condition provides a means to alert maintenance staff of a sensor approaching dirty without creating a trouble in the system. If this indicator is ignored and the second level is reached, a "DIRTY SENSOR" condition shall be indicated at the FACP and subsequently a system trouble is reported [to the Central Monitoring Station]. The sensor base LED shall glow steady giving a visible indication at the sensor location. The "DIRTY SENSOR" condition shall not affect the sensitivity level required to alarm the sensor. If a "DIRTY SENSOR" is left unattended, and its average value increases to a third predetermined value, an "EXCESSIVELY DIRTY SENSOR" trouble condition shall be indicated at the control unit.

- 6. The FACP shall continuously perform an automatic self-test on each sensor which will check sensor electronics and ensure the accuracy of the values being transmitted. Any sensor that fails this test shall indicate a "SELF TEST ABNORMAL" trouble condition.
- 7. Magnet test of smoke sensors shall be distinguished by its label and history log entry as being activated by a magnet.
- G. Alarm Notification: By Visual Strobes and Voice Evac Speakers in areas as indicated on drawings.
 - 1. Notification device locations are recommendations based on room type, sizes, finishes and other components.
 - 2. Contractor is responsible for device layout, strobe intensity, and speaker volume to provide a fully compliant system with required sound levels and intelligibility of message. Provide audibility and intelligibility calculations for voice notification system.

H. Fire Suppression Monitoring:

- 1. Water flow: Activation of water flow switch shall initiate general alarm operations.
- 2. Sprinkler valve tamper switch: The activation of any valve tamper switch shall activate system supervisory operations.
- 3. Pressure switch in dry pipe systems.
- 4. Provide 24-volt connection from fire alarm panel to sprinkler system alarm bell furnished under Division 21.

I. Power Requirements

- 1. The control unit shall receive AC power via a dedicated fused disconnect circuit.
- 2. The system shall be provided with sufficient battery capacity to operate the entire system upon loss of normal AC power in a normal supervisory mode for a period as defined under Emergency Power Supply in this Specification. The system shall automatically transfer to battery standby upon power failure. All battery charging and recharging operations shall be automatic.
- 3. All circuits requiring system-operating power shall be 24 VDC and shall be individually fused at the control unit.
- 4. The incoming power to the system shall be supervised so that any power failure will be indicated at the control unit. A green "power on" LED shall be displayed continuously at the user interface while incoming power is present.
- 5. The system batteries shall be supervised so that a low battery or a depleted battery condition, or disconnection of the battery shall be indicated at the control unit and displayed for the specific fault type.
- 6. The system shall support NAC Lockout feature to prevent subsequent activation of Notification Appliance Circuits after a Depleted Battery condition occurs in order to make use of battery reserve for front panel annunciation and control.
- 7. The system shall support 100% of addressable devices in alarm or operated at the same time, under both primary (AC) and secondary (battery) power conditions.
- 8. Loss of primary power shall sound a trouble signal at the FACP. FACP shall indicate when the system is operating on an alternate power supply.

1.4 SUBMITTALS

- A. Section 01 33 00 Submittal Procedures: Submittal procedures.
- B. Shop Drawings: Prepare on "E-Size" (30x42) sheets.
 - 1. Indicate system wiring diagrams
 - 2. Floor plans with each device location, conduit routing and wiring connections.
 - 3. Annunciator layout
 - 4. Battery calculations.
 - 5. Voltage Drop Calculations
 - 6. System riser diagram
 - 7. Audibility / Intelligibility Calculations
 - 8. List of all devices on each signaling line circuit, with spare capacity indicated.
 - 9. Clear and concise description of operation, with input/output matrix.
- C. Product Data: Submit catalog data showing electrical characteristics and connection requirements.
- D. Warranty
- E. Submission to Authority Having Jurisdiction: In addition to routine submission of the above material, make an identical submission to the authority having jurisdiction. Include copies of shop drawings as required to depict component locations to facilitate review. Upon receipt of comments from the Authority, make resubmissions if required to make clarifications or revisions to obtain approval.
- F. Inspection and Test Reports:
 - 1. Submit inspection and test plan prior to closeout demonstration
 - 2. Submit documentation of satisfactory inspections and tests.
 - 3. Submit NFPA 72 "Inspection and Test Form," filled out.
- G. Test Reports: Indicate procedures and results for specified field testing and inspection.
- H. Manufacturer's Field Reports: Indicate activities on site, adverse findings, and recommendations.

1.5 CLOSEOUT SUBMITTALS

- A. Section 01 70 00 Execution and Closeout Requirements: Closeout procedures.
- B. Project Record Documents: Record actual locations of fire alarm equipment.
- C. Operation and Maintenance Data: Submit manufacturer's standard operating and maintenance instructions.

1.6 OUALITY ASSURANCE

- A. Provide wiring materials located in plenums with peak optical density not greater than 0.5, average optical density not greater than 0.15, and flame spread not greater than 5 feet (1.5 m) when tested in accordance with NFPA 262.
- B. Installer Qualifications: NICET Level III certified fire alarm technician.
 - 1. Authorized representative of control unit manufacturer; submit manufacturer's certification that installer is authorized; include name and title of manufacturer's representative making certification.
- C. Each and all items of the Fire Alarm System shall be listed as a product of a single fire alarm system manufacturer under the appropriate category by Underwriters Laboratories, Inc. (UL), and shall bear the "UL" label.
- D. Maintain one copy of contract documents and shop drawings on site.

1.7 QUALIFICATIONS

- A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum five years of experience and with service facilities within 50 miles of project.
- B. Installer: Certified fire alarm installer with service facilities within 50 miles of Project.
- C. Design fire alarm under direct supervision of NICET Level III technician.

1.8 MAINTENANCE SERVICE

- A. Section 01 70 00 Execution and Closeout: Maintenance service.
- B. Furnish service and maintenance of fire alarm equipment for one year from Date of Substantial Completion.

1.9 MAINTENANCE MATERIALS

- A. Section 01 70 00 Execution and Closeout Requirements: Spare parts and maintenance products.
- B. Furnish six keys of each type.

1.10 EXTRA MATERIALS

- A. Section 01 70 00 Execution and Closeout Requirements: Spare parts and maintenance products.
- B. Furnish three of each type of automatic smoke detector.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: The equipment and service described in this specification are those supplied and supported by SimplexGrinnell and represent the base bid for the equipment.
 - 1. Subject to compliance with requirements, provide alternate products by one of the following:
 - a. SimplexGrinnell
 - b. Edwards Systems Technology
 - c. Notifier
 - d. Gamewell FCI

2.2 CONTROL PANEL

- A. General: Comply with UL 864, "Control Units for Fire-Protective Signaling Systems."
- B. Product Description: Modular fire alarm control panel with surface wall-mounted enclosure.
- C. The following hardware shall be provided:
 - 1. Power Limited base panel with red cabinet and door, 120 VAC input power.
 - 2. 2,000 point capacity minimum where (1) point equals (1) monitor (input) or (1) control (output).
 - 3. 2,000 points of Network Annunciation minimum at FACP Display when applied as a Network Node
 - 4. 2000 points of annunciation minimum where one (1) point of annunciation equals:
 - a. 1 LED driver output on a graphic driver or 1 switch input on a graphic switch input module.
 - b. 1 LED on panel or 1 switch on panel.
 - 5. From all battery charging circuits in the system provide battery voltage and ammeter readouts on the FCP LCD Display.
 - 6. Municipal City Circuit Connection with Disconnect switch, 24VDC Remote Station (reverse polarity), local energy, shunt master box, or a form "C" contact output.
 - 7. One Auxiliary electronically resetable fused 2A @24VDC Output, with programmable disconnect operation for 4-wire detector reset.
 - 8. One Auxiliary Relay, SPDT 2A @32VDC, programmable as a trouble relay, either as normally energized or de-energized, or as an auxiliary control.
 - 9. Three (3) Class B or A (Style Y/Z) Notification Appliance Circuits (NAC; rated 3A@24VDC, resistive).
 - 10. Four (4) form "C" Auxiliary Relay Circuits (Form C contacts rated 2A @ 24VDC, resistive), operation is programmable for trouble, alarm, supervisory of other fire response functions. Relays shall be capable of switching up to ½ A @ 120VAC, inductive.
 - 11. The FACP shall support (6) RS-232-C ports and one service port.

- 12. Remote Unit Interface: supervised serial communication channel for control and monitoring of remotely located annunciators and I/O panels.
- 13. Remote Station Signal Transmitter: Electrically supervised digital alarm communicator transmitter (DACT), capable of transmitting alarm and trouble signals over telephone lines to central station receiver. Programmable DACT for either Common Event Reporting or per Point Reporting.
- 14. Service Port Modem for dial in passcode access to all fire control panel information.
- 15. System Supervision: Component or power supply failure places system in trouble mode.
- D. Initiating Device Circuits: Supervised zone module with alarm and trouble indication; occurrence of single ground or open condition places circuit in trouble mode but does not disable circuit from initiating alarm.
- E. Indicating Appliance Circuits: Supervised march time signal module, sufficient for signal devices connected to system; occurrence of single ground or open condition places circuit in trouble mode but does not disable circuit from signaling alarm.
- F. Cabinet: Lockable steel enclosure. Arrange unit so all operations required for testing or for normal care and maintenance of the system are performed from the front of the enclosure. If more than a single unit is required to form a complete control unit, provide exactly matching modular unit enclosures.
- G. Alphanumeric Display and System Controls: Panel shall include an 80 character LCD display to indicate alarm, supervisory, and component status messages and shall include a keypad for use in entering and executing control commands.

2.3 EMERGENCY POWER SUPPLY

- A. General: Components include battery, charger, and an automatic transfer switch.
- B. Battery: Sealed lead-acid or nickel cadmium type. Provide sufficient capacity to operate the complete alarm system in normal or supervisory (non-alarm) mode for a period of 48 hours. Following this period of operation on battery power, the battery shall have sufficient capacity to operate all components of the system, including all alarm indicating devices in alarm or supervisory mode for a period of 10 minutes.

2.4 MANUAL FIRE ALARM STATIONS

- A. Product Description: Manual double-action station. Station will mechanically latch upon operation and remain so until manually reset by opening with a key common with the control units.
- B. Mounting: Semi-Flush.
- C. Backbox: Manufacturer's standard. Surface mount applications shall utilize manufacturer's surface mount box. Do not mount on a standard outlet box.

2.5 SPOT HEAT DETECTOR

- A. Thermal Sensor: Combination fixed-temperature and rate-of-rise unit with plug-in base and alarm indication lamp; 135-deg F fixed-temperature setting except as indicated.
- B. Thermal sensor shall be of the epoxy encapsulated electronic design. It shall be thermistor-based, rate-compensated, self-restoring and shall not be affected by thermal lag.
- C. Sensor fixed temperature sensing shall be independent of rate-of-rise sensing and programmable to operate at 135-deg F. Sensor rate-of-rise temperature detection shall be selectable at the FACP for either 15-deg F per minute.
- D. Sensor shall have the capability to be programmed as a utility monitoring device to monitor for temperature extremes in the range from 32-deg F to 155-deg F.

2.6 CEILING SMOKE DETECTOR

- A. General: Comply with UL 268, "Smoke Detectors for Fire Protective Signaling Systems." Include the following features:
 - 1. Factory Nameplate: Serial number and type identification.
 - 2. Operating Voltage: 24 VDC, nominal.
 - 3. Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore normal operation.
 - 4. Plug-In Arrangement: Sensor and associated electronic components are mounted in a module that connects to a fixed base with a twist-locking plug connection. Base shall provide break-off plastic tab that can be removed to engage the head/base locking mechanism. No special tools shall be required to remove head once it has been locked. Removal of the detector head shall interrupt the supervisory circuit of the fire alarm detection loop and cause a trouble signal at the control unit.
 - 5. Each sensor base shall contain an LED that will flash each time it is scanned by the Control Unit (once every 4 seconds). In alarm condition, the sensor base LED shall be on steady.
 - 6. Each sensor base shall contain a magnetically actuated test switch to provide for easy alarm testing at the sensor location.
 - 7. Each sensor shall be scanned by the Control Unit for its type identification to prevent inadvertent substitution of another sensor type. Upon detection of a "wrong device", the control unit shall operate with the installed device at the default alarm settings for that sensor; 2.5% obscuration for photoelectric sensor, 135-deg F and 15-deg F rate-of-rise for the heat sensor, but shall indicate a "Wrong Device" trouble condition.
 - 8. The sensor's electronics shall be immune from false alarms caused by EMI and RFI.
 - Sensors include a communication transmitter and receiver in the mounting base having a unique identification and capability for status reporting to the FACP. Sensor address shall be located in base to eliminate false addressing when replacing sensors.

- 10. Removal of the sensor head for cleaning shall not require the setting of addresses.
- B. Bases: Relay output, isolator bases shall be supported alternatives to the standard base.

2.7 DUCT-MOUNTED SMOKE DETECTOR

- A. Duct Smoke Sensor: Photoelectric type, with sampling tube of design and dimensions as recommended by the manufacturer for the specific duct size and installation conditions where applied. Sensor includes relay as required for fan shutdown.
 - 1. Environmental compensation, programmable sensitivity settings, status testing, and monitoring of sensor dirt accumulation for the duct sensor shall be provided by the FACP.
 - 2. The Duct Housing shall provide a supervised relay driver circuit for driving up to 15 relays with a single "Form C" contact rated at 7A@ 28VDC or 10A@ 120VAC. This auxiliary relay output shall be fully programmable. Relay shall be mounted within 3 feet of HVAC control circuit.
 - 3. Duct Housing shall provide a relay control trouble indicator Yellow LED.
 - 4. Compact Duct Housing shall have a transparent cover to monitor for the presence of smoke. Cover shall secure to housing by means of four (4) captive fastening screws.
 - 5. Duct Housing shall provide two (2) Test Ports for measuring airflow and for testing. These ports will allow aerosol injection in order to test the activation of the duct smoke sensor.
 - 6. Duct Housing shall provide a magnetic test area and Red sensor status LED.
 - 7. For maintenance purposes, it shall be possible to clean the duct housing sampling tubes by accessing them through the duct housing front cover.
 - 8. Each duct sensor shall have a Remote Test Station with an alarm LED and test switch.
 - 9. Where indicated provide a NEMA 4X weatherproof duct housing enclosure shall provide for the circulation of conditioned air around the internally mounted addressable duct sensor housing to maintain the sensor housing at its rated temperature range. The housing shall be UL Listed to Standard 268A.

2.8 ALARM NOTIFICATION APPLIANCES

- A. Horn: Listed to UL 464. Horn appliances shall have a High/Lo Setting, programmable by channel from the addressable controller or by appliance from the host FACP. The horn shall have a minimum sound pressure level of 83 or 89 dBA @ 24VDC. The horn shall mount directly to a standard single gang, double gang or 4" square electrical box, without the use of special adapter or trim rings. Appliances shall be wired with UTP conductors, having a minimum of 3 twists per foot.
- B. Visible/Only: Listed to UL 1971. The V/O shall consist of a xenon flash tube and associated lens/reflector system. The V/O enclosure shall mount directly to standard single gang, double gang or 4" square electrical box, without the use of special adapters or trim rings. Appliances shall be wired with UTP conductors, having a minimum of 3 twists per foot. V/O appliances shall be provided with different minimum flash intensities

- of 15cd, 75cd and 110cd. Provide a label inside the strobe lens to indicate the listed candela rating of the specific Visible/Only appliance.
- C. Audible/Visible: Addressable combination Audible/Visible (A/V) Notification Appliances shall be listed to UL 1971 and UL 464. The strobe light shall consist of a xenon flash tube and associated lens/reflector system. Provide a label inside the strobe lens to indicate the listed candela rating of the specific strobe. The horn shall have a minimum sound pressure level of 83 or 89 dBA @ 24VDC. The audible/visible enclosure shall mount directly to standard single gang, double gang or 4" square electrical box, without the use of special adapters or trim rings. Appliances shall be wired with UTP conductors, having a minimum of 3 twists per foot. The appliance shall be capable of two-wire synchronization with one of the following options:
 - 1. Synchronized Strobe with Horn on steady
 - 2. Synchronized Strobe with Temporal Code Pattern on Horn
 - 3. Synchronized Strobe with March Time cadence on Horn
 - 4. Synchronized Strobe firing to NAC sync signal with Horn silenced
- D. Speaker/Visible: Combination Speaker/Visible (S/V) units combine the speaker and visible functions into a common housing. The S/V shall be listed to UL 1971 and UL 1480. Addressable functionality controls visible operation, while the speaker operates on a 25VRMS or 70.7VRMS NAC.
 - 1. Twisted/shielded wire is required for speaker connections on a standard 25VRMS or 70.7VRMS NAC using and UTP conductors, having a minimum of 3 twists per foot is required for addressable strobe connections.
 - 2. The following taps are available: 0.25W, 0.50W, 1.0W and 2.0W. At the 1.0W tap, the speaker has minimum UL rated sound pressure level of 84dBA at 10 feet.
 - 3. The S/V shall have a frequency response of 400 to 4000 Hz for Fire Alarm and 125 to 12kHz for General Signaling.
 - 4. The S/V installs directly to a 4" square, 1 1/2 in. deep electrical box with 1 1/2" extension
 - 5. Test the lines and automatically restore the connection.

2.9 REMOTE ANNUNCIATOR

- A. Provide where required a remote LCD Annunciator with the same "look and feel" as the FACP operator interface. The Remote LCD Annunciator shall use the same Primary Acknowledge, Silence, and Reset Keys, Status LEDs and LCD Display as the FACP.
- B. Annunciator shall have two lines of 40 characters each. Annunciator shall be provided with four (4) programmable control switches and associated LEDs.
- C. Under normal conditions the LCD shall display a "SYSTEM IS NORMAL" message and the current time and date.
- D. Should an abnormal condition be detected the appropriate LED (Alarm, Supervisory or Trouble) shall flash. The unit audible signal shall pulse for alarm conditions and sound steady for trouble and supervisory conditions.

- E. The LCD shall display the following information relative to the abnormal condition of a point in the system:
 - 1. 40 character custom location label.
 - 2. Type of device (e.g., smoke, pull station, waterflow).
 - 3. Point status (e.g., alarm, trouble).
- F. Operator keys shall be key switch enabled to prevent unauthorized use. The key shall only be removable in the disabled position. Acknowledge, Silence and Reset operation shall be the same as the FACP.
- G. Mounting: Factory mounted in flush wall-mounted enclosure.

2.10 DOOR RELEASE

- A. Description: Units shall be listed to UL 228. Units are equipped for wall or floor mounting as indicated and are complete with matching door plate. Unit shall operate from a 120VAC, a 24VAC or a 24VDC source, and develops a minimum of 25 lbs. holding force.
- B. Material and Finish: Match door hardware.

2.11 WIRE AND CABLE

- A. Fire Alarm wire and cabling shall be installed in conduit. See Section 26 05 33 for more information.
- B. Contractor shall coordinate conduit requirements with Fire Alarm System installer prior to bid.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Section 01 30 00 Administrative Requirements: Coordination and project conditions.
- B. Verify products and systems receiving devices are ready for installation.

3.2 INSTALLATION

- A. Install system components and all associated devices in accordance with applicable NFPA Standards and manufacturer's recommendations.
- B. Install conductors for fire alarm detection and signal circuit conductors in conduit.
- C. System Wiring: Wire and cable shall be a type listed for its intended use by an approval agency acceptable to the Authority Having Jurisdiction and shall be installed in

accordance with the appropriate articles from the current approved edition of NFPA 70: National Electric Code (NEC).

- 1. Contractor shall obtain from the Fire Alarm System Manufacturer written instruction regarding the appropriate wire/cable to be used for this installation. No deviation from the written instruction shall be made by the Contractor without the prior written approval of the Fire Alarm System Manufacturer.
- 2. Color Coding: Color-code fire alarm conductors differently from the normal building power wiring. Use one color code for alarm initiating device circuits wiring and a different color code for supervisory circuits. Color-code notification appliance circuits differently from alarm-initiating circuits. Paint fire alarm system junction boxes and covers red.
- D. Furnish and install a complete Fire Alarm System as described herein and as shown on the plans. Include sufficient control unit(s), annunciator(s), manual stations, automatic fire detectors, smoke detectors, audible and visible notification appliances, wiring, terminations, electrical boxes, and all other necessary material for a complete operating system.
- E. Water-Flow and Valve Supervisory Switches: Connect to each sprinkler valve and Flow center assembly. Provide for quantity and locations shown on Fire Suppression shop drawings regardless of how many are shown on fire alarm system plans. Coordinate with fire suppression installer prior to bid.
- F. Mount outlet box for electric door holder to withstand 80 pounds (36.4 kg) pulling force.
- G. Connect conduit and wire to door release devices, sprinkler flow switches, sprinkler valve tamper switches, fire suppression system control panels, duct smoke detectors, elevator controllers and all other systems requiring fire alarm monitoring or interface. All fire alarm devices (i.e. audio notification appliance) in elevator cab shall require travel cables; coordinate with USC and elevator contractor. Provide all required cables.
- H. Automatic Detector Installation: Conform to NFPA 72.
- I. Install engraved plastic nameplates in accordance with Section 26 05 53.
- J. Ground and bond fire alarm equipment and circuits in accordance with Section 26 05 26.

3.3 FIELD QUALITY CONTROL

- A. See Division 01 Specification Quality Requirements: Field inspecting, testing, adjusting, and balancing.
- B. Provide fire alarm documentation box adjacent to fire alarm panel per NFPA 72-7.7.2. Provide all record documents as well as all documentation defined in submittal section and NFPA 72-7.2.

- C. Manufacturer's Field Services: Provide services of a factory-authorized service representative to supervise the field assembly and connection of components and the pretesting, testing, and adjustment of the system.
- D. Installation personnel shall be supervised by persons who are qualified and experienced in the installation, inspection, and testing of fire alarm systems. Examples of qualified personnel shall include, but not be limited to, the following:
 - 1. Factory trained and certified personnel.
 - 2. National Institute of Certification in Engineering Technologies (NICET) fire alarm level III certified personnel.
 - 3. International Municipal Signal Association (IMSA) fire alarm certified.
 - 4. Personnel licensed or certified by state or local authority.
 - 5. Trained and qualified personnel employed by an organization listed by a national testing laboratory for the servicing of fire alarm systems.
- E. Test entire fire alarm system in accordance with NFPA 72 and local fire department requirements.
- F. Pretesting: Determine, through pretesting, the conformance of the system to the requirements of the Drawings and Specifications. Correct deficiencies observed in pretesting. Replace malfunctioning or damaged items with new and retest until satisfactory performance and conditions are achieved.
- G. Final Test Notice: Provide a 10-day minimum notice in writing when the system is ready for final acceptance testing. Notify authorities having jurisdiction and comply with their requirements for scheduling inspections and tests and for observation by their personnel.
- H. Retesting: Correct deficiencies indicated by tests and completely retest work affected by such deficiencies. Verify by the system test that the total system meets the Specifications and complies with applicable standards.
- I. Report of Tests and Inspections: Provide a written record of inspections, tests, and detailed test results in the form of a test log.
- J. Final Test, Certificate of Completion, and Certificate of Occupancy:
 - 1. Test the system as required by the Authority Having Jurisdiction in order to obtain a certificate of occupancy.

3.4 CLEANING AND ADJUSTING

- A. Cleaning: Remove paint splatters and other spots, dirt, and debris. Clean unit internally using methods and materials recommended by manufacturer.
- B. Occupancy Adjustments: When requested within one year of date of Substantial Completion, provide on-site assistance in adjusting sound levels and adjusting controls and sensitivities to suit actual occupied conditions. Provide up to three visits to the site for this purpose.

3.5 DEMONSTRATION AND TRAINING

- A. Provide the services of a factory-authorized service representative to demonstrate the system and train Owner's maintenance personnel as specified below.
 - 1. Train Owner's maintenance personnel in the procedures and schedules involved in operating, troubleshooting, servicing, and preventive maintaining of the system. Provide a minimum of 8 hours' training.
 - 2. Schedule training with the Owner at least seven days in advance.

END OF SECTION 283100